

THE EXPERT'S VOICE® IN .NET

Pro C# 2010 and .NET 4 Platform

*Exploring the .NET universe using
curly brackets*

FIFTH EDITION

Andrew Troelsen

Apress®

Pro C# 2010 and the .NET 4 Platform

Fifth Edition



Andrew Troelsen

Apress®

Pro C# 2010 and the .NET 4 Platform, Fifth Edition

Copyright © 2010 by Andrew Troelsen

All rights reserved. No part of this work may be reproduced or transmitted in any form or by any means, electronic or mechanical, including photocopying, recording, or by any information storage or retrieval system, without the prior written permission of the copyright owner and the publisher.

ISBN-13 (pbk): 978-1-4302-2549-2

ISBN-13 (electronic): 978-1-4302-2550-8

Printed and bound in the United States of America 9 8 7 6 5 4 3 2 1

Trademarked names may appear in this book. Rather than use a trademark symbol with every occurrence of a trademarked name, we use the names only in an editorial fashion and to the benefit of the trademark owner, with no intention of infringement of the trademark.

President and Publisher: Paul Manning

Lead Editor: Ewan Buckingham

Technical Reviewer: Andy Olsen

Editorial Board: Clay Andres, Steve Anglin, Mark Beckner, Ewan Buckingham, Gary Cornell, Jonathan Gennick, Jonathan Hassell, Michelle Lowman, Matthew Moodie, Duncan Parkes, Jeffrey Pepper, Frank Pohlmann, Douglas Pundick, Ben Renow-Clarke, Dominic Shakeshaft, Matt Wade, Tom Welsh

Coordinating Editor: Debra Kelly

Copy Editors: Patrick Meader, Katie Stence, and Sharon Terdeman

Compositor: folio 2

Indexer: Potomac Indexers

Artist: April Milne

Cover Designer: Anna Ishchenko

Distributed to the book trade worldwide by Springer-Verlag New York, Inc., 233 Spring Street, 6th Floor, New York, NY 10013. Phone 1-800-SPRINGER, fax 201-348-4505, e-mail orders-ny@springer-sbm.com, or visit www.springeronline.com.

For information on translations, please e-mail rights@apress.com, or visit www.apress.com.

Apress and friends of ED books may be purchased in bulk for academic, corporate, or promotional use. eBook versions and licenses are also available for most titles. For more information, reference our Special Bulk Sales—eBook Licensing web page at www.apress.com/info/bulksales.

The information in this book is distributed on an “as is” basis, without warranty. Although every precaution has been taken in the preparation of this work, neither the author(s) nor Apress shall have any liability to any person or entity with respect to any loss or damage caused or alleged to be caused directly or indirectly by the information contained in this work.

The source code for this book is available to readers at www.apress.com.

To the memory of my wonderful grandmother, Maxine. I love you, Gerta. Rest peacefully.

Contents at a Glance

Contents.....	viii
About the Author.....	XXV
About the Technical Reviewer	xxvi
Acknowledgments	xxvii
Introduction	xxviii
■ ■ ■ Part 1: Introducing C# and the .NET Platform.....	1
■ Chapter 1: The Philosophy of .NET.....	3
■ Chapter 2: Building C# Applications	41
■ ■ ■ Part 2: Core C# Programming Constructs	71
■ Chapter 3: Core C# Programming Constructs, Part I	73
■ Chapter 4: Core C# Programming Constructs, Part II.....	125
■ Chapter 5: Defining Encapsulated Class Types.....	167
■ Chapter 6: Understanding Inheritance and Polymorphism.....	219
■ Chapter 7: Understanding Structured Exception Handling	259
■ Chapter 8: Understanding Object Lifetime	289
■ ■ ■ Part 3: Advanced C# Programming Constructs	319
■ Chapter 9: Working with Interfaces.....	321
■ Chapter 10: Understanding Generics	361

■ Chapter 11: Delegates, Events, and Lambdas.....	397
■ Chapter 12: Advanced C# Language Features	439
■ Chapter 13: LINQ to Objects.....	489
■ ■ ■ Part 4: Programming with .NET Assemblies.....	523
■ Chapter 14: Configuring .NET Assemblies	525
■ Chapter 15: Type Reflection, Late Binding, and Attribute-Based Programming.....	581
■ Chapter 16: Processes, AppDomains, and Object Contexts.....	625
■ Chapter 17: Understanding CIL and the Role of Dynamic Assemblies.....	653
■ Chapter 18: Dynamic Types and the Dynamic Language Runtime	701
■ ■ ■ Part 5: Introducing the .NET Base Class Libraries	725
■ Chapter 19: Multithreaded and Parallel Programming.....	727
■ Chapter 20: File I/O and Object Serialization.....	775
■ Chapter 21: ADO.NET Part I: The Connected Layer.....	825
■ Chapter 22: ADO.NET Part II: The Disconnected Layer.....	885
■ Chapter 23: ADO.NET Part III: The Entity Framework	951
■ Chapter 24: Introducing LINQ to XML	993
■ Chapter 25: Introducing Windows Communication Foundation	1013
■ Chapter 26: Introducing Windows Workflow Foundation 4.0	1077
■ ■ ■ Part 6: Building Desktop User Interfaces with WPF	1115
■ Chapter 27: Introducing Windows Presentation Foundation and XAML.....	1117
■ Chapter 28: Programming with WPF Controls	1179
■ Chapter 29: WPF Graphics Rendering Services	1245
■ Chapter 30: WPF Resources, Animations, and Styles.....	1285
■ Chapter 31: WPF Control Templates and UserControls.....	1325

Part 7: Building Web Applications with ASP.NET.....	1377
Chapter 32: Building ASP.NET Web Pages	1379
Chapter 33: ASP.NET Web Controls, Master Pages and Themes	1429
Chapter 34: ASP.NET State Management Techniques.....	1473
Appendix A: Programming with Windows Forms	1511
Appendix B: Platform-Independent .NET Development with Mono.....	1561
Index.....	1583

Contents

About the Author.....	xxv
About the Technical Reviewer	xxvi
Acknowledgments	xxvii
Introduction	xxviii
■ ■ ■ Part 1: Introducing C# and the .NET Platform.....	1
■ Chapter 1: The Philosophy of .NET.....	3
Understanding the Previous State of Affairs.....	3
The .NET Solution	6
Introducing the Building Blocks of the .NET Platform (the CLR, CTS, and CLS).....	7
Additional .NET-Aware Programming Languages.....	10
An Overview of .NET Assemblies	12
Understanding the Common Type System.....	19
Understanding the Common Language Specification.....	23
Understanding the Common Language Runtime	25
The Assembly/Namespace/Type Distinction	27
Exploring an Assembly Using ildasm.exe	33
Exploring an Assembly Using Reflector	35
Deploying the .NET Runtime	36

The Platform-Independent Nature of .NET	37
Summary	39
■ Chapter 2: Building C# Applications	41
The Role of the .NET Framework 4.0 SDK	41
Building C# Applications Using csc.exe	42
Building .NET Applications Using Notepad++	49
Building .NET Applications Using SharpDevelop.....	50
Building .NET Applications Using Visual C# 2010 Express	53
Building .NET Applications Using Visual Studio 2010	54
Summary	69
■ ■ ■ Part 2: Core C# Programming Constructs	71
■ Chapter 3: Core C# Programming Constructs, Part I	73
The Anatomy of a Simple C# Program	73
An Interesting Aside: Some Additional Members of the System.Environment Class.....	79
The System.Console Class.....	81
System Data Types and C# Shorthand Notation	86
Working with String Data.....	97
Narrowing and Widening Data Type Conversions.....	106
Understanding Implicitly Typed Local Variables	112
C# Iteration Constructs	117
Decision Constructs and the Relational/Equality Operators	119
Summary	122
■ Chapter 4: Core C# Programming Constructs, Part II	125
Methods and Parameter Modifiers	125
Understanding C# Arrays	137
Understanding the Enum Type.....	144

Understanding the Structure Type.....	151
Understanding Value Types and Reference Types.....	154
Understanding C# Nullable Types.....	162
Summary	165
Chapter 5: Defining Encapsulated Class Types.....	167
Introducing the C# Class Type	167
Understanding Constructors	170
The Role of the this Keyword.....	174
Understanding the static Keyword.....	181
Defining the Pillars of OOP.....	188
C# Access Modifiers	192
The First Pillar: C#'s Encapsulation Services.....	194
Understanding Automatic Properties.....	206
Understanding Object Initializer Syntax.....	210
Working with Constant Field Data	214
Understanding Partial Types.....	217
Summary	218
Chapter 6: Understanding Inheritance and Polymorphism.....	219
The Basic Mechanics of Inheritance.....	219
Revising Visual Studio Class Diagrams	224
The Second Pillar of OOP: The Details of Inheritance	226
Programming for Containment/Delegation	232
The Third Pillar of OOP: C#'s Polymorphic Support	235
Understanding Base Class/Derived Class Casting Rules	247
The Master Parent Class: System.Object.....	250
Summary	258

■ Chapter 7: Understanding Structured Exception Handling	259
Ode to Errors, Bugs, and Exceptions	259
The Role of .NET Exception Handling.....	260
The Simplest Possible Example	263
Configuring the State of an Exception	267
System-Level Exceptions (System.SystemException)	272
Application-Level Exceptions (System.ApplicationException)	273
Processing Multiple Exceptions	277
Who Is Throwing What?	282
The Result of Unhandled Exceptions	283
Debugging Unhandled Exceptions Using Visual Studio	284
A Brief Word Regarding Corrupted State Exceptions (CSE)	285
Summary	287
■ Chapter 8: Understanding Object Lifetime	289
Classes, Objects, and References.....	289
The Basics of Object Lifetime	291
The Role of Application Roots	294
Understanding Object Generations	296
Concurrent Garbage Collection under .NET 1.0 - 3.5	297
Background Garbage Collection under .NET 4.0	297
The System.GC Type	298
Building Finalizable Objects.....	302
Building Disposable Objects	305
Building Finalizable and Disposable Types.....	309
Understanding Lazy Object Instantiation	313
Summary	316

■ ■ ■ Part 3: Advanced C# Programming Constructs	319
■ Chapter 9: Working with Interfaces.....	321
Understanding Interface Types.....	321
Defining Custom Interfaces	325
Implementing an Interface.....	327
Invoking Interface Members at the Object Level	329
Interfaces As Parameters	331
Interfaces As Return Values.....	333
Arrays of Interface Types.....	334
Implementing Interfaces Using Visual Studio 2010	335
Resolving Name Clashes via Explicit Interface Implementation.....	336
Designing Interface Hierarchies	339
Building Enumerable Types (IEnumerable and IEnumerator)	343
Building Cloneable Objects (ICloneable)	349
Building Comparable Objects (IComparable)	354
Summary	359
■ Chapter 10: Understanding Generics	361
The Issues with Non-Generic Collections	361
The Role of Generic Type Parameters	371
The System.Collections.Generic Namespace	376
Creating Custom Generic Methods	385
Creating Custom Generic Structures and Classes	388
Constraining Type Parameters	392
Summary	395
■ Chapter 11: Delegates, Events, and Lambdas.....	397
Understanding the .NET Delegate Type	397

Defining a Delegate Type in C#.....	398
The System.MulticastDelegate and System.Delegate Base Classes	400
The Simplest Possible Delegate Example.....	402
Sending Object State Notifications using Delegates	405
Method Group Conversion Syntax.....	411
Understanding Delegate Covariance.....	413
Understanding Generic Delegates	415
Understanding C# Events.....	418
Understanding C# Anonymous Methods.....	427
Understanding Lambda Expressions	430
Summary	437
■ Chapter 12: Advanced C# Language Features	439
Understanding Indexer Methods.....	439
Understanding Operator Overloading	444
Understanding Custom Type Conversions	454
Understanding Extension Methods	460
Understanding Partial Methods	470
Understanding Anonymous Types	473
Working with Pointer Types.....	479
Summary	487
■ Chapter 13: LINQ to Objects	489
LINQ Specific Programming Constructs.....	489
Understanding the Role of LINQ.....	493
Applying LINQ Queries to Primitive Arrays.....	496
Returning the Result of a LINQ Query	503
Applying LINQ Queries to Collection Objects	505

Investigating the C# LINQ Query Operators	508
The Internal Representation of LINQ Query Statements	517
Summary	522
Part 4: Programming with .NET Assemblies.....	523
Chapter 14: Configuring .NET Assemblies	525
Defining Custom Namespaces.....	525
The Role of .NET Assemblies	532
Understanding the Format of a .NET Assembly	533
Building and Consuming a Single-File Assembly	538
Building and Consuming a Multifile Assembly.....	550
Understanding Private Assemblies	553
Understanding Shared Assemblies.....	558
Consuming a Shared Assembly	567
Configuring Shared Assemblies.....	569
Understanding Publisher Policy Assemblies.....	574
Understanding the <codeBase> Element.....	576
The System.Configuration Namespace.....	577
Summary	579
Chapter 15: Type Reflection, Late Binding, and Attribute-Based Programming ...	581
The Necessity of Type Metadata.....	581
Understanding Reflection	586
Building a Custom Metadata Viewer.....	590
Dynamically Loading Assemblies	596
Reflecting on Shared Assemblies	598
Understanding Late Binding	600
Understanding the Role of .NET Attributes	604

Building Custom Attributes	609
Assembly-Level (and Module-Level) Attributes	612
Reflecting on Attributes Using Early Binding	614
Reflecting on Attributes Using Late Binding	615
Putting Reflection, Late Binding, and Custom Attributes in Perspective	617
Building an Extendable Application	618
Summary	624
■ Chapter 16: Processes, AppDomains, and Object Contexts	625
The Role of a Windows Process.....	625
Interacting with Processes Under the .NET Platform.....	627
Understanding .NET Application Domains	637
Interacting with the Default Application Domain	640
Creating New Application Domains	643
Understanding Object Context Boundaries	648
Summarizing Processes, AppDomains, and Context	652
Summary	652
■ Chapter 17: Understanding CIL and the Role of Dynamic Assemblies	653
Reasons for Learning the Grammar of CIL.....	653
Examining CIL Directives, Attributes, and OpCodes	654
Pushing and Popping: The Stack-Based Nature of CIL	656
Understanding Round-Trip Engineering.....	658
Understanding CIL Directives and Attributes	666
.NET Base Class Library, C#, and CIL Data Type Mappings	673
Defining Type Members in CIL.....	674
Examining CIL OpCodes	677

Building a .NET Assembly with CIL	683
Understanding Dynamic Assemblies	688
Summary	698
Chapter 18: Dynamic Types and the Dynamic Language Runtime	701
The Role of the C# dynamic Keyword	701
The Role of the Dynamic Language Runtime (DLR)	707
Simplifying Late Bound Calls Using Dynamic Types.....	710
Simplifying COM Interoperability using Dynamic Data	714
COM Interop using C# 4.0 Language Features	718
Summary	723
Part 5: Introducing the .NET Base Class Libraries	725
Chapter 19: Multithreaded and Parallel Programming.....	727
The Process/AppDomain/Context/Thread Relationship	727
A Brief Review of the .NET Delegate.....	729
The Asynchronous Nature of Delegates.....	731
Invoking a Method Asynchronously	733
The System.Threading Namespace	739
The System.Threading.Thread Class	741
Programmatically Creating Secondary Threads	744
The Issue of Concurrency	750
Programming with Timer Callbacks	758
Understanding the CLR ThreadPool	760
Parallel Programming under the .NET Platform.....	761
Parallel LINQ Queries (PLINQ)	771
Summary	774

■ Chapter 20: File I/O and Object Serialization.....	775
Exploring the System.IO Namespace.....	775
The Directory(Info) and File(Info) Types	777
Working with the DirectoryInfo Type	778
Working with the Directory Type	782
Working with the DriveInfo Class Type	783
Working with the FileInfo Class	785
Working with the File Type	789
The Abstract Stream Class	792
Working with StreamWriters and StreamReaders	794
Working with StringWriters and StringReaders	798
Working with BinaryWriters and BinaryReaders.....	799
Watching Files Programmatically	801
Understanding Object Serialization	804
Configuring Objects for Serialization	806
Choosing a Serialization Formatter.....	808
Serializing Objects Using the BinaryFormatter	811
Serializing Objects Using the SoapFormatter	813
Serializing Objects Using the XmlSerializer	814
Serializing Collections of Objects	816
Customizing the Soap/Binary Serialization Process	818
Summary	824
■ Chapter 21: ADO.NET Part I: The Connected Layer.....	825
A High-Level Definition of ADO.NET	825
Understanding ADO.NET Data Providers	827
Additional ADO.NET Namespaces	831

The Types of the System.Data Namespace	832
Abstracting Data Providers Using Interfaces	837
Creating the AutoLot Database	840
The ADO.NET Data Provider Factory Model	847
Understanding the Connected Layer of ADO.NET	853
Working with Data Readers	859
Building a Reusable Data Access Library	861
Creating a Console UI-Based Front End	871
Understanding Database Transactions	877
Summary	883
Chapter 22: ADO.NET Part II: The Disconnected Layer.....	885
Understanding the Disconnected Layer of ADO.NET.....	885
Understanding the Role of the DataSet.....	886
Working with DataColumns	889
Working with DataRow.....	893
Working with DataTables.....	897
Binding DataTable Objects to Windows Forms GUIs.....	903
Working with Data Adapters	913
Adding Disconnection Functionality to AutoLotDAL.dll	917
Multitabled DataSet Objects and Data Relationships	921
The Windows Forms Database Designer Tools.....	927
Isolating Strongly Typed Database Code into a Class Library.....	938
Programming with LINQ to DataSet.....	943
Summary	949
Chapter 23: ADO.NET Part III: The Entity Framework	951
Understanding the Role of Entity Framework	951

Building and Analyzing your First EDM	961
Programming Against the Conceptual Model	973
AutoLotDAL Version 4.0, Now with Entities	979
Data Binding Entities to Windows Forms GUIs.....	986
Summary	991
■ Chapter 24: Introducing LINQ to XML	993
A Tale of Two XML APIs	993
Members of the System.Xml.Linq Namespace	997
Working with XElement and XDocument	1002
Manipulating an in Memory XML Document.....	1006
Summary	1011
■ Chapter 25: Introducing Windows Communication Foundation	1013
A Potpourri of Distributed Computing APIs	1013
The Role of WCF.....	1019
Investigating the Core WCF Assemblies	1022
The Visual Studio WCF Project Templates	1023
The Basic Composition of a WCF Application	1025
The ABCs of WCF	1027
Building a WCF Service.....	1032
Hosting the WCF Service	1036
Building the WCF Client Application.....	1046
Simplifying Configuration Settings with WCF 4.0	1050
Using the WCF Service Library Project Template	1057
Hosting the WCF Service within a Windows Service	1061
Invoking a Service Asynchronously from the Client.....	1067

Designing WCF Data Contracts	1070
Summary	1076
Chapter 26: Introducing Windows Workflow Foundation 4.0	1077
Defining a Business Process	1078
Building a (Painfully) Simple Workflow.....	1079
The WF 4.0 Runtime	1083
Examining the Workflow 4.0 Activities	1088
Building a Flowchart Workflow.....	1093
Isolating Workflows into Dedicated Libraries	1103
Consuming the Workflow Library	1112
Summary	1114
Part 6: Building Desktop User Interfaces with WPF	1115
Chapter 27: Introducing Windows Presentation Foundation and XAML.....	1117
The Motivation Behind WPF.....	1117
The Various Flavors of WPF	1121
Investigating the WPF Assemblies.....	1126
Building a WPF Application without XAML.....	1135
Building a WPF Application using Only XAML.....	1144
Transforming Markup into a .NET Assembly	1150
Understanding The Syntax of WPF XAML	1154
Building a WPF Application using Code-Behind Files	1165
Building WPF Applications Using Visual Studio 2010	1167
Summary	1178
Chapter 28: Programming with WPF Controls.....	1179
A Survey of the Core WPF Controls.....	1179
Controlling Content Layout Using Panels.....	1184

Building a Window's Frame Using Nested Panels	1195
Understanding WPF Control Commands	1200
Building a WPF User Interface with Expression Blend.....	1207
Building the Ink API Tab.....	1216
Introducing the Documents API	1227
Building the Documents Tab.....	1228
Introducing the WPF Data-Binding Model.....	1235
Summary	1244
■ Chapter 29: WPF Graphics Rendering Services	1245
Understanding WPF's Graphical Rendering Services	1245
Rendering Graphical Data Using Shapes	1247
WPF Brushes and Pens.....	1257
Applying Graphical Transformations.....	1262
Working with Shapes using Expression Blend	1266
Rendering Graphical Data Using Drawings and Geometries.....	1271
Generating Complex Vector Graphics using Expression Design	1275
Rendering Graphical Data Using the Visual Layer	1277
Summary	1284
■ Chapter 30: WPF Resources, Animations, and Styles.....	1285
Understanding the WPF Resource System	1285
Working with Object (Logical) Resources	1292
Understanding WPF's Animation Services.....	1303
Authoring Animations in XAML	1309
Understanding the Role of WPF Styles	1312
Generating Styles with Expression Blend	1320
Summary	1324

■ Chapter 31: WPF Control Templates and UserControls.....	1325
Understanding the Role of Dependency Properties	1325
Building a Custom Dependency Property	1331
Understanding Routed Events	1337
Logical Trees, Visual Trees and Default Templates.....	1341
Building a Custom Control Template with Visual Studio 2010.....	1348
Building Custom UserControls with Blend	1356
Creating the Jackpot Deluxe WPF Application.....	1364
Summary	1375
■ ■ ■ Part 7: Building Web Applications with ASP.NET.....	1377
■ Chapter 32: Building ASP.NET Web Pages	1379
The Role of HTTP	1379
Understanding Web Applications and Web Servers.....	1380
The Role of HTML.....	1382
The Role of Client-Side Scripting.....	1388
Posting Back to the Web Server	1390
The Feature Set of the ASP.NET API	1391
Building a Single File ASP.NET Web Page	1395
Building an ASP.NET Web Page using Code Files.....	1406
ASP.NET Web Sites and ASP.NET Web Applications.....	1412
The ASP.NET Web Site Directory Structure	1413
The Inheritance Chain of the Page Type	1416
Interacting with the Incoming HTTP Request	1417
Interacting with the Outgoing HTTP Response	1421
The Life Cycle of an ASP.NET Web Page.....	1423

The Role of the Web.config File	1427
Summary	1428
■ Chapter 33: ASP.NET Web Controls, Master Pages and Themes	1429
Understanding the Nature of Web Controls	1429
The Control and WebControl Base Classes	1432
Major Categories of ASP.NET Web Controls	1438
Building the ASP.NET Cars Web Site	1441
The Role of the Validation Controls.....	1457
Working with Themes	1465
Summary	1471
■ Chapter 34: ASP.NET State Management Techniques.....	1473
The Issue of State	1473
ASP.NET State Management Techniques	1476
Understanding the Role of ASP.NET View State	1476
The Role of the Global.asax File.....	1479
Understanding the Application/Session Distinction.....	1483
Working with the Application Cache.....	1488
Maintaining Session Data	1493
Understanding Cookies.....	1497
The Role of the <sessionState> Element	1500
Understanding the ASP.NET Profile API	1502
Summary	1509
■ Appendix A: Programming with Windows Forms	1511
The Windows Forms Namespaces.....	1512
Building a Simple Windows Forms Application	1513
The Visual Studio Windows Forms Project Template	1518

The Anatomy of a Form.....	1525
Responding to Mouse and Keyboard Activity	1534
Designing Dialog Boxes	1538
Rendering Graphical Data Using GDI+.....	1545
Building a Complete Windows Forms Application	1551
Summary	1560
■ Appendix B: Platform-Independent .NET Development with Mono.....	1561
The Platform-Independent Nature of .NET.....	1561
Obtaining and Installing Mono	1565
The Mono Development Languages.....	1569
Microsoft-Compatible Mono Development Tools.....	1570
Building .NET Applications with Mono	1572
Who is Using Mono?	1581
Suggestions for Further Study.....	1581
Summary	1582

About the Author



■ **Andrew Troelsen** fondly recalls his very first computer, an Atari 400 complete with a tape deck storage device and a black and white TV serving as a monitor (which his parents permitted him to have in his bedroom - thanks guys!). He also is grateful to the legacy *Compute!* magazine, a B.A. degree in mathematical linguistics, and three years of formal Sanskrit. All of these artifacts have greatly influenced his current career.

Andrew is currently employed with Intertech (www.intertech.com), a .NET and Java training and consulting center.

He has authored a number of books, including *Developer's Workshop to COM* and ATL 3.0 (Wordware Publishing, 2000), *COM and .NET Interoperability* (Apress, 2002) and *Visual Basic 2008 and the .NET 3.5 Platform: An Advanced Guide* (Apress, 2008).

About the Technical Reviewer



■ **Andy Olsen** is a freelance consultant and trainer based in the UK. Andy has been working with .NET since the days of the first beta and is actively involved with the latest features in the .NET 4.0 platform. Andy lives by the sea in Swansea with his wife, Jayne, and their children, Emily and Tom. Andy enjoys running along the sea front (with regular coffee stops along the way), skiing, and following the swans and ospreys. Andy can be reached at andyo@olsensoft.com.

Acknowledgments

For whatever crazy reason (or collection of reasons), the current edition of this text proved to be much harder to author than I anticipated. If it were not for the help and support from a good many people, I suspect that *Pro C# 2010 and the .NET 4.0 Platform* would not have been released until sometime after .NET 6.0 Beta 1.

Huge thanks are in order to my technical editor, Andy Olsen. Far beyond pointing out a misplaced semicolon, Andy had a number of great suggestions to clarify and refine my initial code samples. Thanks Andy!

More huge thanks are in order to the copyediting team. Mary Behr, Patrick Meader, Katie Stence, and Sharon Terdeman were not only very fun to work with, but they were able to identify and correct grammatical errors that I would certainly have never seen.

A special thanks to Debra Kelly of Apress. This is our first project together, and based on numerous late submissions, misplaced emails, and updates to updates, I truly hope she chooses to work with me again. Thanks Debra ;-)

Last, but certainly not least, thanks to my wife, Mandy. As always, you keep me sane during all of my writing projects. Thanks hon.

Introduction

This book has existed, in one form or another, since the first release of *C# and the .NET Platform* was published in step with Microsoft's release of .NET 1.0 Beta 2 (circa the summer of 2001). Since that point, I have been extremely happy to see that this text continues to be very well received by the press. Over the years, it was nominated as a 2002 Jolt Award finalist (I lost, but hey, life goes on); it was also awarded the 2003 Referenceware Excellence Award for programming book of the year.

More importantly, I have been very grateful to receive e-mails from readers all around the world. It is very cool to chat with so many people who have told me this book has helped their careers in some small way. On a related note, I have to say that this book is better than it has ever been, thanks to the readers who have send me various suggestions for improvements, pointed out typos in the text, and alerted me to other glitches on my part.

I have also been taken aback to learn that this very book has been, and is being used, in college and university settings, and is required reading for numerous undergraduate and graduate courses in the field of computer science.

To the press, readers, and professors, I have nothing to say but *thank you and happy programming!*

In any case, since the initial release of this book, I have worked hard to keep the material current with each release of the .NET platform. The fifth edition of this text, which you hold in your hands, has been fully updated to provide coverage on the new features of the C# 2010 programming language, as well as the new features of .NET 4.0 Platform. Here you will find information on the new Dynamic Language Runtime (DLR), the Task Parallel Library (TPL), Parallel LINQ (PLINQ), the ADO.NET Entity Framework (EF), and several "minor" (but very useful) updates, such as C# 2010 named arguments, C# 2010 optional parameters, the Lazy<T> class type, and so on.

In addition to covering all the new bits, this book continues to provide you with a rock-solid foundation of the C# language as a whole, the pillars of object oriented programming (OOP), assembly configuration, database access (through ADO.NET), as well as the process of building desktop GUI applications, web applications, and distributed systems (among other topics).

As with the earlier editions, this edition presents the C# programming language and .NET base class libraries using a friendly and approachable tone (or so I have been told!). As well, this new edition remains focused on providing you with the information you need to build software solutions today, rather than spending too much time examining esoteric details that few individuals will ever actually care about.

We're a Team, You and I

Technology authors write for a demanding group of people (I should know—I'm one of them). You know that building software solutions using any platform (e.g., .NET, Java, and COM) is extremely complicated and is highly specific to your department, company, client base, and subject matter. Perhaps you work in the electronic publishing industry, develop systems for the state or local government, or work at NASA or a branch of the military. Speaking for myself, I have developed children's educational software (Oregon Trail / Amazon Trail anyone?), various n-tier systems, and projects within the medical and financial industries. The chances are almost 100 percent that the code you write at your place of employment has little to do with the code I write at mine (unless we happened to work together previously!).

Therefore, in this book, I have deliberately chosen to avoid creating examples that tie the example code to a specific industry or vein of programming. Given this, I explain C#, OOP, the CLR, and the .NET 4.0 base class libraries using industry-agnostic examples. Rather than having every blessed example fill a grid with data, calculate payroll, or whatnot, I'll stick to subject matter everyone can relate to: automobiles (with some geometric structures and employee payroll systems thrown in for good measure). And that's where you come in.

My job is to explain the C# programming language and the core aspects of the .NET platform as well as I possibly can. I will also do everything I can to equip you with the tools and strategies you need to continue your studies at this book's conclusion.

Your job is to take this information and apply it to your specific programming assignments. I obviously appreciate that your projects most likely don't revolve around automobiles with friendly pet names (e.g., Zippy the BMW and a Yugo named Clunker), but that's what applied knowledge is all about!

Rest assured, once you understand the topics and concepts presented within this text, you will be in a perfect position to build .NET solutions that map to your own unique programming environment.

An Overview of This Book

Pro C# 2010 and the .NET 4.0 Platform, Fifth Edition is logically divided into seven distinct parts, each of which contains a number of related chapters. If you have read the earlier editions of this text, you will quickly notice a number of changes. For example, I am no longer isolating new C# language features to a dedicated chapter. Rather, they are included as part of a specific chapter where they can be introduced naturally. Furthermore, based on reader feedback, I have greatly expanded my coverage of Windows Presentation Foundation (WPF). Here is a part-by-part and chapter-by-chapter breakdown of the text.

Part 1: Introducing C# and the .NET Platform

The purpose of Part 1 is to acclimate you to the nature of the .NET platform and various development tools (many of which are open source) used during the construction of .NET applications. Along the way, you will also check out some fundamental details of the C# programming language and the .NET type system.

Chapter 1: The Philosophy of .NET

This first chapter functions as the backbone for the remainder of the text. You begin by examining the world of traditional Windows development and uncover the shortcomings with the previous state of affairs. The primary goal of this chapter, however, is to acquaint you with a number of .NET centric building blocks, such as the Common Language Runtime (CLR), Common Type System (CTS), Common Language Specification (CLS), and base class libraries. Here, you will take an initial look at the C# programming language and the .NET assembly format; you will also get an overview of the platform-independent nature of the .NET platform (Appendix B will examine this topic in greater detail).

Chapter 2: Building C# Applications

The goal of this chapter is to introduce you to the process of compiling C# source code files using various tools and techniques. You will begin by learning how to use the command-line compiler (`csc.exe`) and C# response files. Over the remainder of the chapter, you will examine numerous code editors and integrated development environments (IDEs), including Notepad++, SharpDevelop, Visual C# 2010 Express, and Visual Studio 2010. You will also learn how to configure your development machine with a local installation of the all important .NET Framework 4.0 SDK documentation.

Part 2: Core C# Programming Constructs

The topics presented in this part of the book are quite important because you will use them regardless of which type of .NET software you intend to develop (e.g., web applications, desktop GUI applications, code libraries, and Windows services). Here, you will come to understand the core constructs of the C# language, including the details of object-oriented programming (OOP). This part will also examine how to process runtime exceptions and dive into the details of .NET's garbage collection services.

Chapter 3: Core C# Programming Constructs, Part I

This chapter begins your formal investigation of the C# programming language. Here you will learn about the role of the `Main()` method and numerous details regarding the intrinsic data types of the .NET platform, including the manipulation of textual data using `System.String` and `System.Text.StringBuilder`. You will also examine iteration and decision constructs, narrowing and widening operations, and the `unchecked` keyword.

Chapter 4: Core C# Programming Constructs, Part II

This chapter completes your examination of the core aspects of C#, beginning with the construction of overloaded type methods and defining parameters using the `out`, `ref`, and `params` keywords. This chapter will examine two new C# 2010 features called arguments and optional parameters. You will also learn how to create and manipulate arrays of data, define nullable data types (with the `?` and `??` operators), and understand the distinction between *value types* (including enumerations and custom structures) and *reference types*.

Chapter 5: Defining Encapsulated Class Types

This chapter begins your examination of object-oriented programming (OOP) using the C# programming language. Once you master the pillars of OOP (encapsulation, inheritance, and polymorphism), the remainder of this chapter will show you how to build robust class types using constructors, properties, static members, constants, and read-only fields. You will wrap up with an examination of partial type definitions, object initialization syntax, and automatic properties.

Chapter 6: Understanding Inheritance and Polymorphism

Here, you will examine the remaining pillars of OOP (inheritance and polymorphism), which allow you to build families of related class types. As you do this, you will examine the role of virtual methods, abstract methods (and abstract base classes), and the nature of the *polymorphic interface*. Last but not least, this chapter will explain the role of the supreme base class of the .NET platform, `System.Object`.

Chapter 7: Understanding Structured Exception Handling

The point of this chapter is to discuss how to handle runtime anomalies in your code base through the use of structured exception handling. Not only will you learn about the C# keywords that allow you to handle such problems (`try`, `catch`, `throw`, and `finally`), but you will also come to understand the distinction between application-level and system-level exceptions. In addition, this chapter will examine various tools within Visual Studio 2010 that allow you to debug the exceptions that escape your notice.

Chapter 8: Understanding Object Lifetime

The final chapter of this part examines how the CLR manages memory using the .NET garbage collector. Here you will come to understand the role of application roots, object generations, and the `System.GC` type. Once you understand the basics, you will examine the topics of *disposable objects* (using the `IDisposable` interface) and the finalization process (using the `System.Object.Finalize()` method). This chapter will also investigate a new .NET 4.0 class, `Lazy<T>`, which allows you to define data that will not be allocated until requested by a caller. As you will see, this feature can be very helpful when you wish to ensure you do not clutter the heap with objects that are not actually required by your programs.

Part 3: Advanced C# Programming Constructs

This section of the book will deepen your understanding of the C# language by walking you through a number of more advanced (but very important) concepts. Here, you will complete your examination of the .NET type system by examining interfaces and delegates. You will also learn about the role of generics, take a first look at Language Integrated Query (LINQ), and examine a number of more advanced features of C# (e.g., extension methods, partial methods, and pointer manipulation).

Chapter 9: Working with Interfaces

The material in this chapter builds upon your understanding of object-based development by covering the topic of interface-based programming. Here, you will learn how to define classes and structures that support multiple behaviors, how to discover these behaviors at runtime, and how to selectively hide particular behaviors using *explicit interface implementation*. In addition to creating a number of custom interfaces, you will also learn how to implement standard interfaces found within the .NET platform. You will use these to build objects that can be sorted, copied, enumerated and compared.

Chapter 10: Understanding Generics

This chapter explores the topic of *generics*. As you will see, generic programming gives you a way to create types and type members, which contain various *placeholders* that can be specified by the caller. In a nutshell, generics greatly enhance application performance and type safety. Not only will you explore various generic types within the `System.Collections.Generic` namespace, but you will also learn how to build your own generic methods and types (with and without constraints).

Chapter 11: Delegates, Events, and Lambdas

The purpose of Chapter 11 is to demystify the *delegate* type. Simply put, a .NET delegate is an object that *points* to other methods in your application. Using this type, you can build systems that allow multiple objects to engage in a two-way conversation. After you have examined the use of .NET delegates, you will then be introduced to the C# event keyword, which you can use to simplify the manipulation of raw delegate programming. You will wrap up this chapter by investigating the role of the C# lambda operator (`=>`) and exploring the connection between delegates, anonymous methods, and lambda expressions.

Chapter 12: Advanced C# Language Features

This chapter deepens your understanding of the C# programming language by introducing you to a number of advanced programming techniques. Here, you will learn how to overload operators and create custom conversion routines (both implicit and explicit) for your types. You will also learn how to build and interact with *type indexers*, as well as work with *extension methods*, *anonymous types*, *partial methods*, and C# pointers using an *unsafe* code context.

Chapter 13: LINQ to Objects

This chapter will begin your examination of Language Integrated Query (LINQ). LINQ allows you to build strongly typed *query expressions* that can be applied to a number of LINQ targets to manipulate *data* in the broadest sense of the word. Here, you will learn about LINQ to Objects, which allows you to apply LINQ expressions to containers of data (e.g., arrays, collections, and custom types). This information will serve you well as you encounter a number of additional LINQ APIs throughout the remainder of this book (e.g., LINQ to XML, LINQ to DataSet, PLINQ, and LINQ to Entities).

Part 4: Programming with .NET Assemblies

Part 4 dives into the details of the .NET assembly format. Not only will you learn how to deploy and configure .NET code libraries, but you will also come to understand the internal composition of a .NET binary image. This part also explains the role of .NET attributes and the role of resolving type information at runtime. This section will also explain the role of the .NET 4.0 Dynamic Language Runtime (DLR) and the C# 2010 dynamic keyword. Later chapters will examine some fairly advanced topics, such as object context, CIL code, and the construction of in-memory assemblies.

Chapter 14: Introducing .NET Assemblies

At a very high level, *assembly* is the term used to describe a *.dll or *.exe binary file created with a .NET compiler. However, the true story of .NET assemblies is far richer than that. Here you will learn the distinction between single-file and multifile assemblies, as well as how to build and deploy each entity. You'll also examine how you can configure private and shared assemblies using XML-based *.config files and publisher policy assemblies. Along the way, you will investigate the internal structure of the global assembly cache (GAC), including some changes to the GAC as of .NET 4.0.

Chapter 15: Type Reflection, Late Binding, and Attribute-Based Programming

Chapter 15 continues your examination of .NET assemblies by checking out the process of runtime type discovery using the `System.Reflection` namespace. Using the types of this namespace, you can build applications that can read an assembly's metadata on the fly. You will also learn how to load and create types at runtime dynamically using *late binding*. The final topic of this chapter will explore the role of .NET attributes (both standard and custom). To illustrate the usefulness of each of these topics, the chapter shows you how to construct an extendable Windows Forms application.

Chapter 16: Processes, AppDomains, and Object Contexts

Now that you have a solid understanding of assemblies, this chapter dives deeper into the composition of a loaded .NET executable. The goal of this chapter is to illustrate the relationship between processes, application domains, and contextual boundaries. These topics provide the proper foundation for Chapter 19, where you will examine the construction of multithreaded applications.

Chapter 17: Understanding CIL and the Role of Dynamic Assemblies

The goal of this chapter is twofold. In the first half (more or less), you will examine the syntax and semantics of CIL in much greater detail than in previous chapters. The remainder of this chapter will cover the role of the `System.Reflection.Emit` namespace. You can use these types to build software that can generate .NET assemblies in memory at runtime. Formally speaking, assemblies defined and executed in memory are termed *dynamic assemblies*. You should not confuse this term with a *dynamic type*, which is the subject of Chapter 18.

Chapter 18: Dynamic Types and the Dynamic Language Runtime

.NET 4.0 introduces a new aspect of the .NET runtime environment called the *dynamic language runtime*. Using the DLR and the C# 2010 `dynamic` keyword, you can define data that is not truly resolved until runtime. Using these features simplifies some very complex .NET programming tasks dramatically. In this chapter, you will learn some practical uses of dynamic data, including how to leverage the .NET reflection APIs in a streamlined manner, as well as how to communicate with legacy COM libraries a minimum of fuss and bother.

Part 5: Introducing the .NET Base Class Libraries

By this point in the text, you have a solid handle on the C# language and the details of the .NET assembly format. Part 5 leverages your newfound knowledge by exploring a number of commonly used services found within the base class libraries, including the creation of multithreaded application, file I/O, and database access using ADO.NET. This part also covers the construction of distributed applications using Windows Communication Foundation (WCF), workflow-enabled applications that use the Windows Workflow Foundation (WF) API and the LINQ to XML API.

Chapter 19: Multithreaded and Parallel Programming

This chapter examines how to build multithreaded applications and illustrates a number of techniques you can use to author thread-safe code. The chapter opens by revisiting the .NET delegate type to ensure, explaining a delegate's intrinsic support for asynchronous method invocations. Next, you will investigate the types within the `System.Threading` namespace. The remainder of this chapter covers a brand new .NET 4.0 API called the *Task Parallel Library* (TPL). Using the TPL, .NET developers can build applications that distribute their workload across all available CPUs in a wickedly simple manner. At this point, you will also learn about the role of Parallel LINQ (PLINQ), which provides a way to create LINQ queries that scale across multiple machine cores.

Chapter 20: File I/O and Object Serialization

The `System.IO` namespace allows you to interact with a machine's file and directory structure. Over the course of this chapter, you will learn how to create (and destroy) a directory system programmatically. You will also learn how to move data into and out of various streams (e.g., file based, string based, and memory based). The latter part of this chapter will examine the object serialization services of the .NET platform. Simply put, *serialization* allows you to persist the state of an object (or a set of related objects) into a stream for later use. *Deserialization* (as you might expect) is the process of plucking an object from the stream into memory for consumption by your application. Once you understand the basics, you will learn how to customize the serialization process using the `ISerializable` interface and a set of .NET attributes.

Chapter 21: ADO.NET Part I: The Connected Layer

In this first of three database-centric chapters, you will take your first look at the database access API of the .NET platform, ADO.NET. Specifically, this chapter will introduce you to the role of .NET data providers and how to communicate with a relational database using the *connected layer* of ADO.NET, which is represented by connection objects, command objects, transaction objects, and data reader objects. Be aware that this chapter will also walk you through the creation of a custom database and the first iteration of a custom data access library (`AutoLotDAL.dll`); you will use this library throughout the remainder of this book.

Chapter 22: ADO.NET Part II: The Disconnected Layer

This chapter continues your study of database manipulation by examining the *disconnected layer* of ADO.NET. Here, you will learn the role of the `DataSet` type, data adapter objects. You will also learn about the many tools of Visual Studio 2010 that can greatly simplify the creation of data-driven applications. Along the way, you will learn how to bind `DataTable` objects to user interface elements, as well as how to apply LINQ queries to in-memory `DataSet` objects using LINQ to `DataSet`.

Chapter 23: ADO.NET Part III: The Entity Framework

This chapter wraps up your investigation of ADO.NET by examining the role of the Entity Framework (EF). Essentially, EF is a way for you to author data access code using strongly typed classes that directly map to your business model. Here, you will come to understand the role of EF Object Services, the Entity Client and Object Context, and the composition of an `*.edmx` file. While doing so, you will learn to interact with relational databases using LINQ to Entities. You will also build the final version of your custom data access library (`AutoLotDAL.dll`), which you will use in several of the remaining chapters of the book.

Chapter 24: LINQ to XML

Chapter 14 introduced you to the core LINQ programming model—specifically LINQ to Objects. Here, you will deepen your understanding of Language Integrated Query by examining how to apply LINQ queries to XML documents. You will begin by learning about the “warts” that were present in .NET’s initial foray into XML manipulation as you use the types of the `System.Xml.dll` assembly. With this brief history lesson behind you, you will explore how to create XML documents in memory, how to persist them to the hard drive, and how to navigate their contents using the LINQ programming model (LINQ to XML).

Chapter 25: Introducing Windows Communication Foundation

Until this point in the book, all of the sample applications have executed on a single computer. In this chapter, you will learn about the Windows Communication Foundation (WCF) API that allows you to build distributed applications in a symmetrical manner, regardless of their underlying plumbing. This chapter will expose you to the construction of WCF services, hosts, and clients. As you will see, WCF services are extremely flexible because they allow clients and hosts to leverage XML-based configuration files to specify addresses, bindings, and contracts declaratively. This chapter will also showcase a number of helpful shortcuts that introduced in .NET 4.0.

Chapter 26: Introducing Windows Workflow Foundation

Of all the .NET APIs, Windows Workflow Foundation (WF) can provide the biggest source of confusion for new developers. In fact, with the release of .NET 4.0, the initial incarnation of the WF API (introduced in .NET 3.0) has been given a complete, and total, reboot. In this chapter, you will begin by learning about the role of a workflow-enabled application, and you will come to understand the various ways to model business processes using the .NET 4.0 WF API. Next, you will examine the scope of the WF 4.0 activity library, as well as learn how to build custom activities that will use the custom database access library you created earlier in the book.

Part 6: Building Desktop User Interfaces using WPF

.NET 3.0 introduced programmers to an amazing API called Windows Presentation Foundation (WPF). This API has quickly become the *heir apparent* to the Windows Forms desktop programming model. In essence, WPF allows you to build desktop applications that incorporate vector graphics, interactive animations, and data-binding operations using a declarative markup grammar called XAML. Furthermore, the WPF control architecture provides a trivial way to restyle the look-and-feel of a typical control radically using little more than some well-formed XAML. I am happy to say that this edition of the text includes five chapters dedicated to the WPF programming model.

Chapter 27: Introducing Windows Presentation Foundation and XAML

Essentially, WPF allows you to build extremely interactive and media-rich front ends for desktop applications (and indirectly, web applications). Unlike Windows Forms, this supercharged UI framework integrates a number of key services (e.g., 2D and 3D graphics, animations, and rich documents) into a single, unified object model. In this chapter, you will begin your examination of WPF and the Extendable Application Markup Language (XAML). Here, you will learn how to build WPF programs without XAML, using nothing but XAML, and by using a combination of both approaches. You will wrap up the chapter by building a custom XAML editor that you will use for the remainder of the WPF-centric chapters.

Chapter 29: Programming with WPF Controls

This chapter will expose you to the process of using intrinsic WPF controls and layout managers. For example, you will learn to build menu systems, splitter windows, toolbars, and status bars. This chapter will also introduce you to a number of WPF APIs (and their related controls), including the WPF Documents API, the WPF Ink API, and the data-binding model. Just as importantly, this chapter will begin your investigation of Expression Blend IDE, which simplifies the task of creating rich UIs for a WPF application.

Chapter 30: WPF Graphical Rendering Services

WPF is a graphically intensive API; given this fact, WPF provides three ways to render graphics: *shapes*, *drawings and geometries*, and *visuals*. In this chapter, you will evaluate each option and learn about a number of important graphics primitives (e.g., brushes, pens, and transformations) along the way. This chapter will also examine a number of ways in which Expression Blend can help you simplify the process of creating WPF graphics, as well as how to perform hit-testing operations against graphical data.

Chapter 30: WPF Resources, Animations and Styles

This chapter will introduce you to three important (and interrelated) topics that will deepen your understanding of the Windows Presentation Foundation API. The first order of business is to learn the role of *logical resources*. As you will see, the logical resource (also termed an *object resource*) system provides a way for you to name and refer to commonly used objects within a WPF application. Next, you will learn how to define, execute, and control an animation sequence. Despite what you might be thinking, however, WPF animations are not limited to the confines of video game or multimedia applications. You will wrap up the chapter by learning about the role of WPF styles. Similar to a web page that uses CSS or the ASP.NET theme engine, a WPF application can define a common look-and-feel for a set of controls.

Chapter 31: WPF Control Templates and UserControls

This chapter concludes your investigation of the WPF programming model by introducing you to the process of building customized controls. This chapter begins by examining two topics that are important when creating a custom control: *dependency properties* and *routed events*. Once you understand these topics, you will learn about the role of a *default template*, as well as how to view them programmatically at runtime. Once this foundation has been laid, the remainder of this chapter will examine how to build custom UserControl classes using Visual Studio 2010 and Expression Blend, including the .NET 4.0 Visual State Manager (VSM).

Part 7: Building Web Applications with ASP.NET

Part 7 is devoted to an examination of constructing web applications using the ASP.NET programming API. Microsoft designed ASP.NET to model the creation of desktop user interfaces by layering an event-driven, object-oriented framework on top of a standard HTTP request/response.

Chapter 32: Building ASP.NET Web Pages

This chapter begins your study of web application development using ASP.NET. As you will see, server-side scripting code has now been replaced with real object-oriented languages (e.g., C# and VB .NET). This chapter will examine the construction of an ASP.NET web page, the underlying programming model, and other key aspects of ASP.NET, such as your choice of web server and the use of *Web.config* files.

Chapter 33: ASP.NET Web Controls, Themes, and Master Pages

Whereas the previous chapter showed you how to construct ASP.NET Page objects, this chapter will examine the controls that populate the internal control tree. Here, you will examine the core ASP.NET web controls, including validation controls, the intrinsic site navigation controls, and various data-binding operations. This chapter will also illustrate the role of *master pages* and the ASP.NET theme engine, which is a server-side alternative to traditional style sheets.

Chapter 34: ASP.NET State Management Techniques

This chapter extends your understanding of ASP.NET by examining various ways to handle state management under .NET. Like classic ASP, ASP.NET allows you to create cookies and application-level and session-level variables quite easily. However, ASP.NET also introduces a new state management technique: the application cache. Once you look at the numerous ways to handle state with ASP.NET, you will examine the role of the `HttpApplication` base class and learn how to alter the runtime behavior of your web application dynamically using the `Web.config` file.

Part 8: Appendixes

This final part of this book examines two important topics that did not seem to fit naturally within the bulk of the text, so I have placed them in appendices. Here you will complete your examination of C# and the .NET platform by gaining an overview of the initial GUI framework of the .NET platform (Windows Forms). You will also learn how to use the Mono Platform to build .NET applications on operating systems beyond Microsoft Windows.

Appendix A: Programming with Windows Forms

The original desktop GUI toolkit that shipped with the .NET platform is called *Windows Forms*. This appendix will walk you through the role of this UI framework and illustrate how to build main windows, dialog boxes, and menu systems. You will also learn about the role of form inheritance and see how to render 2D graphical data using the `System.Drawing` namespace. You will wrap things up by building a (semi-capable) painting application that illustrates the various topics discussed throughout this appendix.

Appendix B: Platform-Independent .NET Development with Mono

Last but not least, Appendix B covers how to use an open source implementation of the .NET platform named *Mono*. You can use Mono to build feature-rich .NET applications that can be created, deployed, and executed upon a variety of operating systems, including Mac OS X, Solaris, AIX, and numerous other Linux distributions. Given that Mono is largely comparable with Microsoft's .NET platform, you already know most of what Mono has to offer. Therefore, this appendix will focus on the Mono installation process, Mono development tools, and Mono runtime engine.

Obtaining This Book's Source Code

You can find all of the code examples contained in this book available as a free download from the Source Code/Download area of the Apress website. Simply navigate to www.apress.com, select the Source Code/Download link, and look up this title by name. Once you are on the home page for *Pro C# 2010 and the .NET 4.0 Platform, Fifth Edition*, you can download a self-extracting *.zip file. After you unzip the contents, you will find that the code has been partitioned on a chapter-by-chapter basis.

On a related note, be aware that you will find Source Code notes such as the following in many of the book's chapters. These notes serve as your visual cue that you can load the example under discussion into Visual Studio 2010 for further examination and modification:

■ **Source Code** This is a source code note that refers you to a specific directory in the ZIP archive!

To open a solution into Visual Studio 2010, use the File Open Project/Solution menu option, and then navigate to the correct *.sln file within the correct subdirectory of the unzipped archive.

Obtaining Updates for This Book

As you read through this text, you might find an occasional grammatical or code error (although I sure hope not). If this is the case, please accept my apologies. Being human, I am sure that a glitch or two might be present, despite my best efforts. If this is the case, you can obtain the current errata list from the Apress website (again, this is located on the home page for this book), as well as information on how to notify me of any errors you might find.

Contacting Me

If you have any questions regarding this book's source code, are in need of clarification for a given example, or simply wish to offer your thoughts regarding the .NET platform, feel free to drop me a line at the following email address (to ensure your messages don't end up in my junk mail folder, please include "C# FifthEd" in the Subject line somewhere):

atroelsen@intertech.com

Please understand that I will do my best to get back to you in a timely fashion; however, like yourself, I get busy from time to time. If I don't respond within a week or two, please be aware that I am not trying to be a jerk, nor am I trying to avoid talking to you. I'm just busy (or, if I'm lucky, on vacation somewhere). So, then! Thanks for buying this text (or at least looking at it in the bookstore while you try to decide whether you will buy it). I hope you enjoy reading this book and putting your newfound knowledge to good use.

Take care,
Andrew Troelsen

PART 1

■ ■ ■

Introducing C# and the .NET Platform

CHAPTER 1



The Philosophy of .NET

Every few years or so, the modern-day programmer must be willing to perform a self-inflicted knowledge transplant to stay current with the new technologies of the day. The languages (C++, Visual Basic 6.0, Java), frameworks (MFC, ATL, STL), architectures (COM, CORBA, EJB) and APIs that were touted as the silver bullets of software development eventually become overshadowed by something better, or at the very least something new.

Regardless of the frustration you can feel when upgrading your internal knowledge base, it is frankly unavoidable. To this end, the goal of this book is to examine the details of Microsoft's current offering within the landscape of software engineering: the .NET 4.0 platform and the C# 2010 programming language.

The point of this chapter is to lay the conceptual groundwork for the remainder of the book. Here you will find a high-level discussion of a number of .NET-related topics such as assemblies, the Common Intermediate Language (CIL), and just-in-time (JIT) compilation. In addition to previewing some keywords of the C# programming language, you will also come to understand the relationship between various aspects of the .NET Framework, such as the Common Language Runtime (CLR), the Common Type System (CTS), and the Common Language Specification (CLS).

This chapter also provides you with a survey of the functionality supplied by the .NET 4.0 base class libraries, sometimes abbreviated as BCLs or alternatively as FCLs (Framework class libraries). Here, you will also overview the language-agnostic and platform-independent nature of the .NET platform (yes, it's true; .NET is not confined to the Windows operating system). As you would hope, many of these topics are explored in further detail throughout the remainder of this text.

Understanding the Previous State of Affairs

Before examining the specifics of the .NET universe, it's helpful to consider some of the issues that motivated the genesis of Microsoft's current platform. To get in the proper mind-set, let's begin this chapter with a brief and painless history lesson to remember our roots and understand the limitations of the previous state of affairs (after all, admitting you have a problem is the first step toward finding a solution). After completing this quick tour of life as we knew it, we turn our attention to the numerous benefits provided by C# 2010 and the .NET 4.0 platform.

Life As a C/Windows API Programmer

Traditionally speaking, developing software for the Windows family of operating systems involved using the C programming language in conjunction with the Windows application programming interface (API). While it is true that numerous applications have been successfully created using this time-honored approach, few of us would disagree that building applications using the raw API is a complex undertaking.

The first obvious problem is that C is a very terse language. C developers are forced to contend with manual memory management, ugly pointer arithmetic, and ugly syntactical constructs. Furthermore, given that C is a structured language, it lacks the benefits provided by the object-oriented approach (can anyone say *spaghetti code*?). When you combine the thousands of global functions and data types defined by the Windows API to an already formidable language, it is little wonder that there are so many buggy applications floating around today.

Life As a C++/MFC Programmer

One vast improvement over raw C/API development is the use of the C++ programming language. In many ways, C++ can be thought of as an object-oriented *layer* on top of C. Thus, even though C++ programmers benefit from the famed pillars of OOP (encapsulation, inheritance, and polymorphism), they are still at the mercy of the painful aspects of the C language (e.g., manual memory management, ugly pointer arithmetic, and ugly syntactical constructs).

Despite its complexity, many C++ frameworks exist today. For example, the Microsoft Foundation Classes (MFC) provides the developer with a set of C++ classes that facilitate the construction of Windows applications. The main role of MFC is to wrap a *sane subset* of the underlying Windows API behind a number of classes, magic macros, and numerous code-generation tools (aka *wizards*). Regardless of the helpful assistance offered by the MFC framework (as well as many other C++-based windowing toolkits), the fact of the matter is that C++ programming remains a difficult and error-prone experience, given its historical roots in C.

Life As a Visual Basic 6.0 Programmer

Due to a heartfelt desire to enjoy a simpler lifestyle, many programmers shifted away from the world of C(++)-based frameworks to kinder, gentler languages such as Visual Basic 6.0 (VB6). VB6 became popular due to its ability to build complex user interfaces, code libraries (e.g., COM servers), and database access logic with minimal fuss and bother. Much more than MFC, VB6 hid the complexities of the raw Windows API from view using a number of integrated code wizards, intrinsic VB data types, classes, and VB-specific functions.

The major downfall of VB6 (which has been rectified given the advent of the .NET platform) is that it is *not* a fully object-oriented language; rather, it is *object based*. For example, VB6 does not allow the programmer to establish *is-a* relationships between classes (i.e., no classical inheritance) and has no intrinsic support for parameterized object construction. Moreover, VB6 doesn't provide the ability to build multithreaded applications unless you are willing to drop down to low-level API calls (which is complex at best and dangerous at worst).

■ **Note** The Visual Basic language used within the .NET platform (which is often referred to as VB.NET), has very little relationship to VB6. For example, modern day VB supports operator overloading, classical inheritance, type constructors and generics.

Life As a Java Programmer

Enter Java. Java is an object-oriented programming (OOP) language with its syntactic roots in C++. As many of you are aware, Java's strengths are far greater than its support for platform independence. As a language, Java cleans up many unsavory syntactical aspects of C++. As a platform, Java provides programmers with a large number of predefined packages that contain various type definitions. Using these types, Java programmers are able to build "100% Pure Java" applications complete with database connectivity, messaging support, web-enabled front ends, and a rich desktop user interface (among other services).

Although Java is a very elegant language, one potential problem is that using Java typically means that you must use Java front to back during the development cycle. In effect, Java offers little hope of language integration, as this goes against the grain of Java's primary goal—a single programming language for every need. In reality, however, there are millions of lines of existing code out there in the world that would ideally like to commingle with newer Java code. Sadly, Java makes this task problematic. While Java does provide a limited ability to access non-Java APIs, there is little support for true cross-language integration.

Life As a COM Programmer

The Component Object Model (COM) was Microsoft's previous application development framework, which first appeared on the programming landscape circa 1991 (or 1993, if you regard COM's introduction with the birth of OLE 1.0). COM is an architecture that says, in effect, "If you build your types in accordance with the rules of COM, you end up with a block of *reusable binary code*." These binary blobs of COM code are often called "COM servers".

One benefit of a binary COM server is that it can be accessed in a language-independent manner. Thus, C++ programmers can build COM classes that can be used by VB6; Delphi programmers can use COM classes built using C, and so forth. However, as you may be aware, COM's language independence is somewhat limited. For example, there is no way to derive a new COM class using an existing COM class (as COM has no support for classical inheritance). Rather, are limited to reuse via the *has-a* relationship.

Another benefit of COM is its location-transparent nature. Using constructs such as the system registry, application identifiers (AppIDs), stubs, proxies, and the COM runtime environment, programmers can avoid the need to work with raw sockets, RPC calls, and other low-level details when building a distributed application. For example, consider the following VB6 COM client code:

```
' The MyCOMClass class could have be written in
' any COM-aware language, and may be located anywhere
' on the network (including your local machine).
Dim obj as MyCOMClass
Set obj = New MyCOMClass  ' Location resolved using AppID.
obj.DoSomeWork
```

Although COM can be considered a very successful object model, it is extremely complex under the hood (at least until you have spent many months exploring its plumbing—especially if you happen to be a C++ programmer). To help simplify the development of COM binaries, programmers can make use of numerous COM-aware frameworks. For example, the Active Template Library (ATL) provides a set of C++ classes, templates, and macros to ease the creation of COM servers.

Many other languages also hide a good part of the COM infrastructure from view. However, language support alone is not enough to hide the complexity of COM. Even when you choose a relatively simple COM-aware language such as VB6, you are still forced to contend with fragile registration entries and numerous deployment-related issues (collectively, and somewhat comically, termed *DLL hell*).

The Complexity of COM Data Type Representation

Although COM certainly facilitates the construction of software applications using a variety of different programming languages, the language-independent nature of COM was not as straightforward as one would hope.

Some of the complexity is due to the simple fact that applications that are woven together using diverse languages are completely unrelated from a syntactic point of view. For example, JScript has a syntax much like C, while VBScript is a subset of VB6. The COM servers that are created to run under the COM+ runtime (a Windows OS feature which provides common services to custom code libraries [transactions, object lifetime, security, etc]) have an entirely different look and feel from the web-centric ASP pages that invoke them. The result was a rather confused mishmash of technologies.

Furthermore, and perhaps more important, each language and/or technology has its own *type system* (that may look nothing like another's type system). Beyond the fact that each API ships with its own collection of prefabricated code, even basic data types cannot always be treated identically. A `CComBSTR` in ATL is not quite the same as a `String` in VB6, both of which have nothing to do with a `char*` in C.

Given that each language has its own unique type system, COM programmers typically needed to be very careful with building public methods on public COM classes. For example, if a C++ developer needed to create a method that returned an array of integers to a VB6 application, they would be up to their eyeballs in complex COM API calls to construct a `SAFEARRAY` structure, which could easily require dozens of lines of code. In the COM world, the `SAFEARRAY` data type is the only way to build an array that all COM frameworks understand. If the C++ developer simply returned a native C++ array, VB6 would have no clue what to do with it.

Similar complexities could be found when building methods that manipulate simple string data, references to other COM objects, or even a trivial `BOOLEAN` value! To put it politely, COM programming is a very *asymmetrical* discipline.

The .NET Solution

So much for the brief history lesson. The bottom line is that life as a Windows programmer has historically been tough. The .NET Framework is a rather radical and brute-force approach to making our lives easier. As you will see during the remainder of this book, the .NET Framework is a software platform for building systems on the Windows family of operating systems, as well as on numerous non-Microsoft operating systems such as Mac OS X and various Unix/Linux distributions. To set the stage, here is a quick rundown of some core features provided courtesy of .NET.

- *Interoperability with existing code:* This is (of course) a good thing. Existing COM binaries can commingle (i.e., interop) with newer .NET binaries and vice versa. As of .NET 4.0, interoperability has been further simplified with the addition of the dynamic keyword (covered in Chapter 18).
- *Support for numerous programming languages:* .NET applications can be created using any number of programming languages (C#, Visual Basic, F#, S#, and so on).
- *A common runtime engine shared by all .NET-aware languages:* One aspect of this engine is a well-defined set of types that each .NET-aware language understands.
- *Complete and total language integration:* .NET supports cross-language inheritance, cross-language exception handling, and cross-language debugging of code.
- *A comprehensive base class library:* This library provides shelter from the complexities of raw API calls and offers a consistent object model used by all .NET-aware languages.
- *No more COM plumbing:* IClassFactory, IUnknown, IDispatch, IDL code, and the variant-compliant data types (e.g., BSTR, SAFEARRAY) have no place in a .NET binary.
- *A simplified deployment model:* Under .NET, there is no need to register a binary unit into the system registry. Furthermore, .NET allows multiple versions of the same *.dll to exist in harmony on a single machine.

As you can most likely gather from the previous bullet points, the .NET platform has nothing to do with COM (beyond the fact that both frameworks originated from Microsoft). In fact, the only way .NET and COM types can interact with each other is using the interoperability layer.

Introducing the Building Blocks of the .NET Platform (the CLR, CTS, and CLS)

Now that you know some of the benefits provided by .NET, let's preview three key (and interrelated) entities that make it all possible: the CLR, CTS, and CLS. From a programmer's point of view, .NET can be understood as a runtime environment and a comprehensive base class library. The runtime layer is properly referred to as the *Common Language Runtime*, or *CLR*. The primary role of the CLR is to locate, load, and manage .NET types on your behalf. The CLR also takes care of a number of low-level details such as memory management, application hosting, handling threads, and performing various security checks.

Another building block of the .NET platform is the *Common Type System*, or *CTS*. The CTS specification fully describes all possible data types and programming constructs supported by the runtime, specifies how these entities can interact with each other, and details how they are represented in the .NET metadata format (more information on metadata later in this chapter; see Chapter 15 for complete details).

Understand that a given .NET-aware language might not support each and every feature defined by the CTS. The *Common Language Specification*, or *CLS*, is a related specification that defines a subset of common types and programming constructs that all .NET programming languages can agree on. Thus, if you build .NET types that only expose CLS-compliant features, you can rest assured that all .NET-aware

languages can consume them. Conversely, if you make use of a data type or programming construct that is outside of the bounds of the CLS, you cannot guarantee that every .NET programming language can interact with your .NET code library. Thankfully, as you will see later in this chapter, it is very simple to tell your C# compiler to check all of your code for CLS compliance.

The Role of the Base Class Libraries

In addition to the CLR and CTS/CLS specifications, the .NET platform provides a base class library that is available to all .NET programming languages. Not only does this base class library encapsulate various primitives such as threads, file input/output (I/O), graphical rendering systems, and interaction with various external hardware devices, but it also provides support for a number of services required by most real-world applications.

For example, the base class libraries define types that facilitate database access, manipulation of XML documents, programmatic security, and the construction of web-enabled as well as traditional desktop and console-based front ends. From a high level, you can visualize the relationship between the CLR, CTS, CLS, and the base class library, as shown in Figure 1-1.




Figure 1-1. The CLR, CTS, CLS, and base class library relationship

What C# Brings to the Table

Given that .NET is such a radical departure from previous technologies, Microsoft crafted a new programming language, C#, specifically for this platform. C# is a programming language whose core syntax looks *very* similar to the syntax of Java. However, to call C# a Java rip-off is inaccurate. Both C# and Java are members of the C family of programming languages (e.g., C, Objective C, C++) and therefore share a similar syntax.

The truth of the matter is that many of C#'s syntactic constructs are modeled after various aspects of Visual Basic 6.0 and C++. For example, like VB6, C# supports the notion of formal type properties (as opposed to traditional getter and setter methods) and the ability to declare methods taking a varying

number of arguments (via parameter arrays). Like C++, C# allows you to overload operators, as well as create structures, enumerations, and callback functions (via delegates).

Moreover, as you work through this text, you will quickly see that C# supports a number of features traditionally found in various functional languages (e.g., LISP or Haskell) such as lambda expressions and anonymous types. Furthermore, with the advent of LINQ (*Language Integrated Query*), C# supports a number of constructs that make it quite unique in the programming landscape. Nevertheless, the bulk of C# is indeed influenced by C-based languages.

Due to the fact that C# is a hybrid of numerous languages, the result is a product that is as syntactically clean—if not cleaner—as Java, is about as simple as VB6, and provides just about as much power and flexibility as C++ (without the associated ugly bits). Here is a partial list of core C# features that are found in all versions of the language.

- No pointers required! C# programs typically have no need for direct pointer manipulation (although you are free to drop down to that level if absolutely necessary, as shown in Chapter 12).
- Automatic memory management through garbage collection. Given this, C# does not support a `delete` keyword.
- Formal syntactic constructs for classes, interfaces, structures, enumerations, and delegates.
- The C++-like ability to overload operators for a custom type, without the complexity (e.g., making sure to “return `*this` to allow chaining” is not your problem).
- Support for attribute-based programming. This brand of development allows you to annotate types and their members to further qualify their behavior.

With the release of .NET 2.0 (circa 2005), the C# programming language was updated to support numerous new bells and whistles, most notably the following:

- The ability to build generic types and generic members. Using generics, you are able to build very efficient and type-safe code that defines numerous *placeholders* specified at the time you interact with the generic item.
- Support for anonymous methods, which allow you to supply an inline function anywhere a delegate type is required.
- Numerous simplifications to the delegate/event model, including covariance, contravariance, and method group conversion. (If some of these terms are unfamiliar, fear not. You’ll learn about such details over the course of the book.)
- The ability to define a single type across multiple code files (or if necessary, as an in-memory representation) using the `partial` keyword.

.NET 3.5 (released circa 2008) added even more functionality to the C# programming language, including the following features:

- Support for strongly typed queries (e.g., LINQ) used to interact with various forms of data.
- Support for anonymous types that allow you to model the *shape* of a type rather than its behavior.

- The ability to extend the functionality of an existing type (without sub-classing) using extension methods.
- Inclusion of a lambda operator (`=>`), which even further simplifies working with .NET delegate types.
- A new object initialization syntax, which allows you to set property values at the time of object creation.

The current release of the .NET platform version 4.0 updates C# yet again with a handful of features. While the following list of new constructs may seem rather limited, you see just how useful they can be as you work through this text.

- Support for optional method parameters, as well as named method arguments.
- Support for dynamic lookup of members at runtime via the `dynamic` keyword. As you will see in Chapter 18 this provides a unified approach to invoking members on the fly, regardless of which framework the member implemented (COM, IronRuby, IronPython, HTML DOM, or via .NET reflection services).
- Related to the previous point, .NET 4.0 greatly simplifies how C# applications can interact with legacy COM servers by removing the dependency on interop assemblies and support for optional `ref` arguments.
- Working with generic types is much more intuitive, given that you can easily map generic data to and from general `System.Object` collections via covariance and contravariance.

Perhaps the most important point to understand about the C# language is that it can only produce code that can execute within the .NET runtime (you could never use C# to build a native COM server or an unmanaged C/C++ API application). Officially speaking, the term used to describe the code targeting the .NET runtime is *managed code*. The binary unit that contains the managed code is termed an *assembly* (more details on assemblies in just a bit). Conversely, code that cannot be directly hosted by the .NET runtime is termed *unmanaged code*.

Additional .NET-Aware Programming Languages

Understand that C# is not the only language that can be used to build .NET applications. When you install the freely downloadable Microsoft .NET 4.0 Framework Software Development Kit (SDK), as well as when you install Visual Studio 2010, you will be given five managed languages out of the box: C#, Visual Basic, C++/CLI, JScript .NET, and F#.

Note F# is a new .NET language based on the ML family of functional languages, especially OCaml. While F# can be used as a purely functional language, it also has support for OOP constructs and the .NET base class libraries. If you are interested in learning more about this managed language, navigate online to the official F# homepage, <http://msdn.microsoft.com/fsharp>.

In addition to the managed languages provided by Microsoft, there are .NET compilers for Smalltalk, COBOL, and Pascal (to name a few). Although this book focuses almost exclusively on C#, you may be interested in the following web site:

<http://www.dotnetauthor.com>

If you click the Resources link at the top of the homepage, you will find a list of .NET programming languages and related links where you are able to download various compilers (see Figure 1-2).




Figure 1-2. DotNetLanguages.net is one of many sites documenting known .NET programming languages

While I assume you are primarily interested in building .NET programs using the syntax of C#, I encourage you to visit this site, as you are sure to find many .NET languages worth investigating at your leisure (LISP .NET, anyone?).

Life in a Multi-Language World

As developers first come to understand the language-agnostic nature of .NET, numerous questions arise. The most prevalent of these questions would have to be, If all .NET languages compile down to managed code, why do we need more than one compiler? There are a number of ways to answer this question. First, we programmers are a *very* particular lot when it comes to our choice of programming language. Some of us prefer languages full of semicolons and curly brackets with as few language keywords as possible. Others enjoy a language that offers more *human-readable* syntactic tokens (such as Visual Basic). Still others may want to leverage their mainframe skills while moving to the .NET platform (via COBOL .NET).

Now, be honest. If Microsoft were to build a single “official” .NET language derived from the BASIC family of languages, can you really say all programmers would be happy with this choice? Or, if the only “official” .NET language were based on Fortran syntax, imagine all the folks out there who would ignore .NET altogether. Because the .NET runtime couldn’t care less which language was used to build a block of managed code, .NET programmers can stay true to their syntactic preferences and share the compiled code among teammates, departments, and external organizations (regardless of which .NET language others choose to use).

Another excellent byproduct of integrating various .NET languages into a single unified software solution is the simple fact that all programming languages have their own sets of strengths and weaknesses. For example, some programming languages offer excellent intrinsic support for advanced mathematical processing. Others offer superior support for financial calculations, logical calculations, interaction with mainframe computers, and so forth. When you take the strengths of a particular programming language and then incorporate the benefits provided by the .NET platform, everybody wins.

Of course, in reality the chances are quite good that you will spend much of your time building software using your .NET language of choice. However, once you master the syntax of one .NET language, it is very easy to learn another. This is also quite beneficial, especially to the software consultants of the world. If your language of choice happens to be C# but you are placed at a client site that has committed to Visual Basic, you are still able to leverage the functionality of the .NET Framework, and you should be able to understand the overall structure of the code base with minimal fuss and bother. Enough said.

An Overview of .NET Assemblies

Regardless of which .NET language you choose to program with, understand that despite the fact that .NET binaries take the same file extension as COM servers and unmanaged Windows binaries (*.dll or *.exe), they have absolutely no internal similarities. For example, *.dll .NET binaries do not export methods to facilitate communications with the COM runtime (given that .NET is *not* COM).

Furthermore, .NET binaries are not described using COM type libraries and are not registered into the system registry. Perhaps most important, .NET binaries do not contain platform-specific instructions, but rather platform-agnostic *Intermediate Language (IL)* and type metadata. Figure 1-3 shows the big picture of the story thus far.




Figure 1-3. All .NET-aware compilers emit IL instructions and metadata

Note There is one point to be made regarding the abbreviation “IL.” During the development of .NET, the official term for IL was Microsoft Intermediate Language (MSIL). However, with the final release of .NET, the term was changed to Common Intermediate Language (CIL). Thus, as you read the .NET literature, understand that IL, MSIL, and CIL are all describing the same entity. In keeping with the current terminology, I will use the abbreviation CIL throughout this text.

When a *.dll or *.exe has been created using a .NET-aware compiler, the binary blob is termed an *assembly*. You will examine numerous details of .NET assemblies in Chapter 14. However, to facilitate the discussion of the .NET runtime environment, you do need to understand some basic properties of this new file format.

As mentioned, an assembly contains CIL code, which is conceptually similar to Java bytecode in that it is not compiled to platform-specific instructions until absolutely necessary. Typically, “absolutely necessary” is the point at which a block of CIL instructions (such as a method implementation) is referenced for use by the .NET runtime.

In addition to CIL instructions, assemblies also contain *metadata* that describes in vivid detail the characteristics of every “type” living within the binary. For example, if you have a class named SportsCar, the type metadata describes details such as SportsCar’s base class, which interfaces are implemented by SportsCar (if any), as well as a full description of each member supported by the SportsCar type. .NET metadata is always present within an assembly, and is automatically generated by a .NET-aware language compiler.

Finally, in addition to CIL and type metadata, assemblies themselves are also described using metadata, which is officially termed a *manifest*. The manifest contains information about the current version of the assembly, culture information (used for localizing string and image resources), and a list of all externally referenced assemblies that are required for proper execution. You’ll examine various

tools that can be used to examine an assembly's types, metadata, and manifest information over the course of the next few chapters.

Single-File and Multi-File Assemblies

In a great number of cases, there is a simple one-to-one correspondence between a .NET assembly and the binary file (*.dll or *.exe). Thus, if you are building a .NET *.dll, it is safe to consider that the binary and the assembly are one and the same. Likewise, if you are building an executable desktop application, the *.exe can simply be referred to as the assembly itself. As you'll see in Chapter 14, however, this is not completely accurate. Technically speaking, if an assembly is composed of a single *.dll or *.exe module, you have a *single-file assembly*. Single-file assemblies contain all the necessary CIL, metadata, and associated manifest in an autonomous, single, well-defined package.

Multi-file assemblies, on the other hand, are composed of numerous .NET binaries, each of which is termed a *module*. When building a multi-file assembly, one of these modules (termed the *primary module*) must contain the assembly manifest (and possibly CIL instructions and metadata for various types). The other related modules contain a module-level manifest, CIL, and type metadata. As you might suspect, the primary module documents the set of required secondary modules within the assembly manifest.

Note Chapter 14 will examine the distinction between single-file and multi-file assemblies in detail. Be aware, however, that Visual Studio 2010 can only be used to build single file assemblies. In the rare case that you need to build a multi-file assembly, you must make use of command-line tools.

The Role of the Common Intermediate Language

Let's examine CIL code, type metadata, and the assembly manifest in a bit more detail. CIL is a language that sits above any particular platform-specific instruction set. For example, the following C# code models a trivial calculator. Don't concern yourself with the exact syntax for now, but do notice the format of the Add() method in the Calc class.

```
// Calc.cs
using System;

namespace CalculatorExample
{
    // This class contains the app's entry point.
    class Program
    {
        static void Main()
        {
            Calc c = new Calc();
            int ans = c.Add(10, 84);
            Console.WriteLine("10 + 84 is {0}.", ans);

        // Wait for user to press the Enter key before shutting down.
    }
}
```

```

        Console.ReadLine();
    }

// The C# calculator.
class Calc
{
    public int Add(int x, int y)
    { return x + y; }
}
}

```

Once you compile this code file using the C# compiler (`csc.exe`), you end up with a single-file `*.exe` assembly that contains a manifest, CIL instructions, and metadata describing each aspect of the `Calc` and `Program` classes.

Note Chapter 2 examines the details of compiling code using the C# compiler, as well as the use of graphical IDEs such as Microsoft Visual Studio 2010, Microsoft Visual C# 2010 Express, and SharpDevelop.

For example, if you were to open this assembly using `ildasm.exe` (examined a little later in this chapter), you would find that the `Add()` method is represented using CIL such as the following:

```

.method public hidebysig instance int32 Add(int32 x,
    int32 y) cil managed
{
    // Code size 9 (0x9)
    .maxstack 2
    .locals init (int32 V_0)
    IL_0000:  nop
    IL_0001:  ldarg.1
    IL_0002:  ldarg.2
    IL_0003:  add
    IL_0004:  stloc.0
    IL_0005:  br.s IL_0007
    IL_0007:  ldloc.0
    IL_0008:  ret
} // end of method Calc::Add

```

Don't worry if you are unable to make heads or tails of the resulting CIL for this method—Chapter 17 will describe the basics of the CIL programming language. The point to concentrate on is that the C# compiler emits CIL, not platform-specific instructions.

Now, recall that this is true of all .NET-aware compilers. To illustrate, assume you created this same application using Visual Basic, rather than C#.

```

' Calc.vb
Imports System

```

```

Namespace CalculatorExample

' A VB "Module" is a class that contains only
' static members.
Module Program
    Sub Main()
        Dim c As New Calc
        Dim ans As Integer = c.Add(10, 84)
        Console.WriteLine("10 + 84 is {0}.", ans)
        Console.ReadLine()
    End Sub
End Module

Class Calc
    Public Function Add(ByVal x As Integer, ByVal y As Integer) As Integer
        Return x + y
    End Function
End Class

End Namespace

```

If you examine the CIL for the Add() method, you find similar instructions (slightly tweaked by the Visual Basic compiler, vbc.exe).

```

.method public instance int32 Add(int32 x,
    int32 y) cil managed
{
    // Code size 8 (0x8)
    .maxstack 2
    .locals init (int32 V_0)
    IL_0000: ldarg.1
    IL_0001: ldarg.2
    IL_0002: add.ovf
    IL_0003: stloc.0
    IL_0004: br.s IL_0006
    IL_0006: ldloc.0
    IL_0007: ret
} // end of method Calc::Add

```

Source Code The Calc.cs and Calc.vb code files are included under the Chapter 1 subdirectory.

Benefits of CIL

At this point, you might be wondering exactly what is gained by compiling source code into CIL rather than directly to a specific instruction set. One benefit is language integration. As you have already seen, each .NET-aware compiler produces nearly identical CIL instructions. Therefore, all languages are able to interact within a well-defined binary arena.

Furthermore, given that CIL is platform-agnostic, the .NET Framework itself is platform-agnostic, providing the same benefits Java developers have grown accustomed to (e.g., a single code base running on numerous operating systems). In fact, there is an international standard for the C# language, and a large subset of the .NET platform and implementations already exist for many non-Windows operating systems (more details at the conclusion of this chapter). In contrast to Java, however, .NET allows you to build applications using your language of choice.

Compiling CIL to Platform-Specific Instructions

Due to the fact that assemblies contain CIL instructions rather than platform-specific instructions, CIL code must be compiled on the fly before use. The entity that compiles CIL code into meaningful CPU instructions is a JIT compiler, which sometimes goes by the friendly name of *Jitter*. The .NET runtime environment leverages a JIT compiler for each CPU targeting the runtime, each optimized for the underlying platform.

For example, if you are building a .NET application to be deployed to a handheld device (such as a Windows mobile device), the corresponding Jitter is well equipped to run within a low-memory environment. On the other hand, if you are deploying your assembly to a back-end server (where memory is seldom an issue), the Jitter will be optimized to function in a high-memory environment. In this way, developers can write a single body of code that can be efficiently JIT compiled and executed on machines with different architectures.

Furthermore, as a given Jitter compiles CIL instructions into corresponding machine code, it will cache the results in memory in a manner suited to the target operating system. In this way, if a call is made to a method named `PrintDocument()`, the CIL instructions are compiled into platform-specific instructions on the first invocation and retained in memory for later use. Therefore, the next time `PrintDocument()` is called, there is no need to recompile the CIL.

Note It is also possible to perform a “pre-JIT” of an assembly when installing your application using the `ngen.exe` command-line tool that ships with the .NET 4.0 Framework SDK. Doing so may improve startup time for graphically intensive applications.

The Role of .NET Type Metadata

In addition to CIL instructions, a .NET assembly contains full, complete, and accurate metadata, which describes each and every type (e.g., class, structure, enumeration) defined in the binary, as well as the members of each type (e.g., properties, methods, events). Thankfully, it is always the job of the compiler (not the programmer) to emit the latest and greatest type metadata. Because .NET metadata is so wickedly meticulous, assemblies are completely self-describing entities.

To illustrate the format of .NET type metadata, let’s take a look at the metadata that has been generated for the `Add()` method of the C# `Calc` class you examined previously (the metadata generated for the Visual Basic version of the `Add()` method is similar).

```
TypeDef #2 (02000003)
-----
  TypDefName: CalculatorExample.Calc (02000003)
  Flags      : [NotPublic] [AutoLayout] [Class]
  [AnsiClass] [BeforeFieldInit] (00100001)
  Extends   : 01000001 [TypeRef] System.Object
  Method #1 (06000003)

-----
  MethodName: Add (06000003)
  Flags      : [Public] [HideBySig] [ReuseSlot] (00000086)
  RVA       : 0x00002090
  ImplFlags : [IL] [Managed] (00000000)
  CallCnvntn: [DEFAULT]
  hasThis
  ReturnType: I4
  2 Arguments
  Argument #1: I4
  Argument #2: I4
  2 Parameters
  (1) ParamToken : (08000001) Name : x flags: [none] (00000000)
  (2) ParamToken : (08000002) Name : y flags: [none] (00000000)
```

Metadata is used by numerous aspects of the .NET runtime environment, as well as by various development tools. For example, the IntelliSense feature provided by tools such as Visual Studio 2010 is made possible by reading an assembly's metadata at design time. Metadata is also used by various object-browsing utilities, debugging tools, and the C# compiler itself. To be sure, metadata is the backbone of numerous .NET technologies including Windows Communication Foundation (WCF), reflection, late binding, and object serialization. Chapter 15 will formalize the role of .NET metadata.

The Role of the Assembly Manifest

Last but not least, remember that a .NET assembly also contains metadata that describes the assembly itself (technically termed a *manifest*). Among other details, the manifest documents all external assemblies required by the current assembly to function correctly, the assembly's version number, copyright information, and so forth. Like type metadata, it is always the job of the compiler to generate the assembly's manifest. Here are some relevant details of the manifest generated when compiling the Calc.cs code file shown earlier in this chapter (assume we instructed the compiler to name our assembly Calc.exe).

```
.assembly extern mscorel
{
  .publickeytoken = (B7 7A 5C 56 19 34 E0 89 )
  .ver 4:0:0:0
}
.assembly Calc
{
  .hash algorithm 0x00008004
  .ver 1:0:0:0
```

```

}
.module Calc.exe
.imagebase 0x00400000
.subsystem 0x00000003
.file alignment 512
.corflags 0x00000001

```

In a nutshell, this manifest documents the set of external assemblies required by `Calc.exe` (via the `.assembly extern` directive) as well as various characteristics of the assembly itself (e.g., version number, module name). Chapter 14 will examine the usefulness of manifest data in much more detail.

Understanding the Common Type System

A given assembly may contain any number of distinct types. In the world of .NET, *type* is simply a general term used to refer to a member from the set {class, interface, structure, enumeration, delegate}. When you build solutions using a .NET-aware language, you will most likely interact with many of these types. For example, your assembly may define a single class that implements some number of interfaces. Perhaps one of the interface methods takes an enumeration type as an input parameter and returns a structure to the caller.

Recall that the CTS is a formal specification that documents how types must be defined in order to be hosted by the CLR. Typically, the only individuals who are deeply concerned with the inner workings of the CTS are those building tools and/or compilers that target the .NET platform. It is important, however, for all .NET programmers to learn about how to work with the five types defined by the CTS in their language of choice. Here is a brief overview.

CTS Class Types

Every .NET-aware language supports, at the very least, the notion of a *class type*, which is the cornerstone of OOP. A class may be composed of any number of members (such as constructors, properties, methods, and events) and data points (fields). In C#, classes are declared using the `class` keyword.

```
// A C# class type with 1 method.
class Calc
{
    public int Add(int x, int y)
    { return x + y; }
}
```

Chapter 5 will begin your examination of building CTS class types with C#; however, Table 1-1 documents a number of characteristics pertaining to class types.

Table 1-1. CTS Class Characteristics

Class Characteristic	Meaning in Life
Is the class sealed or not?	Sealed classes cannot function as a base class to other classes.
Does the class implement any interfaces?	An interface is a collection of abstract members that provide a contract between the object and object user. The CTS allows a class to implement any number of interfaces.
Is the class abstract or concrete?	Abstract classes cannot be directly instantiated, but are intended to define common behaviors for derived types. Concrete classes can be instantiated directly.
What is the visibility of this class?	Each class must be configured with a visibility keyword such as public or internal. Basically, this controls if the class may be used by external assemblies or only from within the defining assembly.

CTS Interface Types

Interfaces are nothing more than a named collection of abstract member definitions, which may be supported (i.e., implemented) by a given class or structure. In C#, interface types are defined using the `interface` keyword. By convention, all .NET interfaces begin with a capital letter I, as in the following example:

```
// A C# interface type is usually
// declared as public, to allow types in other
// assemblies to implement their behavior.
public interface IDraw
{
    void Draw();
}
```

On their own, interfaces are of little use. However, when a class or structure implements a given interface in its unique way, you are able to request access to the supplied functionality using an interface reference in a polymorphic manner. Interface-based programming will be fully explored in Chapter 9.

CTS Structure Types

The concept of a structure is also formalized under the CTS. If you have a C background, you should be pleased to know that these user-defined types (UDTs) have survived in the world of .NET (although they behave a bit differently under the hood). Simply put, a *structure* can be thought of as a lightweight class type having value-based semantics. For more details on the subtleties of structures, see Chapter 4. Typically, structures are best suited for modeling geometric and mathematical data and are created in C# using the `struct` keyword.

```
// A C# structure type.
struct Point
{
    // Structures can contain fields.
    public int xPos, yPos;

    // Structures can contain parameterized constructors.
    public Point(int x, int y)
    { xPos = x; yPos = y; }

    // Structures may define methods.
    public void PrintPosition()
    {
        Console.WriteLine("{0}, {1}", xPos, yPos);
    }
}
```

CTS Enumeration Types

Enumerations are a handy programming construct that allow you to group name/value pairs. For example, assume you are creating a video game application that allows the player to select one of three character categories (Wizard, Fighter, or Thief). Rather than keeping track of simple numerical values to represent each possibility, you could build a custom enumeration using the `enum` keyword.

```
// A C# enumeration type.
enum CharacterType
{
    Wizard = 100,
    Fighter = 200,
    Thief = 300
}
```

By default, the storage used to hold each item is a 32-bit integer; however, it is possible to alter this storage slot if need be (e.g., when programming for a low-memory device such as a Windows mobile device). Also, the CTS demands that enumerated types derive from a common base class, `System.Enum`. As you will see in Chapter 4, this base class defines a number of interesting members that allow you to extract, manipulate, and transform the underlying name/value pairs programmatically.

CTS Delegate Types

Delegates are the .NET equivalent of a type-safe, C-style function pointer. The key difference is that a .NET delegate is a *class* that derives from `System.MulticastDelegate`, rather than a simple pointer to a raw memory address. In C#, delegates are declared using the `delegate` keyword.

```
// This C# delegate type can "point to" any method
// returning an int and taking two ints as input.
delegate int BinaryOp(int x, int y);
```

Delegates are useful when you wish to provide a way for one entity to forward a call to another entity and provide the foundation for the .NET event architecture. As you will see in Chapters 11 and 19, delegates have intrinsic support for multicasting (i.e., forwarding a request to multiple recipients) and asynchronous method invocations (i.e., invoking the method on a secondary thread).

CTS Type Members

Now that you have previewed each of the types formalized by the CTS, realize that most types take any number of *members*. Formally speaking, a type member is constrained by the set {constructor, finalizer, static constructor, nested type, operator, method, property, indexer, field, read-only field, constant, event}.

The CTS defines various *adornments* that may be associated with a given member. For example, each member has a given visibility trait (e.g., public, private, protected). Some members may be declared as abstract (to enforce a polymorphic behavior on derived types) as well as virtual (to define a canned, but overridable, implementation). Also, most members may be configured as static (bound at the class level) or instance (bound at the object level). The creation of type members is examined over the course of the next several chapters.

Note As described in Chapter 10, the C# language also supports the creation of generic types and generic members.

Intrinsic CTS Data Types

The final aspect of the CTS to be aware of for the time being is that it establishes a well-defined set of fundamental data types. Although a given language typically has a unique keyword used to declare an intrinsic CTS data type, all language keywords ultimately resolve to the same type defined in an assembly named `mscorlib.dll`. Consider Table 1-2, which documents how key CTS data types are expressed in various .NET languages.

Table 1-2. The Intrinsic CTS Data Types

CTS Data Type	VB .NET Keyword	C# Keyword	C++/CLI Keyword
<code>System.Byte</code>	<code>Byte</code>	<code>byte</code>	<code>unsigned char</code>
<code>System.SByte</code>	<code>SByte</code>	<code>sbyte</code>	<code>signed char</code>
<code>System.Int16</code>	<code>Short</code>	<code>short</code>	<code>short</code>
<code>System.Int32</code>	<code>Integer</code>	<code>int</code>	<code>int</code> or <code>long</code>
<code>System.Int64</code>	<code>Long</code>	<code>long</code>	<code>_int64</code>

Table 1-2. The Intrinsic CTS Data Types (continued)

CTS Data Type	VB .NET Keyword	C# Keyword	C++/CLI Keyword
System.UInt16	UShort	ushort	unsigned short
System.UInt32	UInteger	uint	unsigned int or unsigned long
System.UInt64	ULong	ulong	unsigned __int64
System.Single	Single	float	float
System.Double	Double	double	double
System.Object	Object	object	object^
System.Char	Char	char	wchar_t
System.String	String	string	String^
System.Decimal	Decimal	decimal	Decimal
System.Boolean	Boolean	bool	bool

Given the fact that the unique keywords of a managed language are simply shorthand notations for a real type in the `System` namespace, we no longer have to worry about overflow/underflow conditions for numerical data, or how strings and Booleans are internally represented across different languages. Consider the following code snippets, which define 32-bit numerical variables in C# and Visual Basic, using language keywords as well as the formal CTS data type:

```
// Define some "ints" in C#.
int i = 0;
System.Int32 j = 0;

' Define some "ints" in VB.
Dim i As Integer = 0
Dim j As System.Int32 = 0
```

Understanding the Common Language Specification

As you are aware, different languages express the same programming constructs in unique, language-specific terms. For example, in C# you denote string concatenation using the plus operator (+), while in VB you typically make use of the ampersand (&). Even when two distinct languages express the same programmatic idiom (e.g., a function with no return value), the chances are very good that the syntax will appear quite different on the surface.

```
// C# method returning nothing.
public void MyMethod()
{
    // Some interesting code...
}

' VB method returning nothing.
Public Sub MyMethod()
    ' Some interesting code...
End Sub
```

As you have already seen, these minor syntactic variations are inconsequential in the eyes of the .NET runtime, given that the respective compilers (`csc.exe` or `vbc.exe`, in this case) emit a similar set of CIL instructions. However, languages can also differ with regard to their overall level of functionality. For example, a .NET language may or may not have a keyword to represent unsigned data, and may or may not support pointer types. Given these possible variations, it would be ideal to have a baseline to which all .NET-aware languages are expected to conform.

The CLS is a set of rules that describe in vivid detail the minimal and complete set of features a given .NET-aware compiler must support to produce code that can be hosted by the CLR, while at the same time be accessed in a uniform manner by all languages that target the .NET platform. In many ways, the CLS can be viewed as a *subset* of the full functionality defined by the CTS.

The CLS is ultimately a set of rules that compiler builders must conform to if they intend their products to function seamlessly within the .NET universe. Each rule is assigned a simple name (e.g., CLS Rule 6) and describes how this rule affects those who build the compilers as well as those who (in some way) interact with them. The crème de la crème of the CLS is the mighty Rule 1.

- *Rule 1:* CLS rules apply only to those parts of a type that are exposed outside the defining assembly.

Given this rule, you can (correctly) infer that the remaining rules of the CLS do not apply to the logic used to build the inner workings of a .NET type. The only aspects of a type that must conform to the CLS are the member definitions themselves (i.e., naming conventions, parameters, and return types). The implementation logic for a member may use any number of non-CLS techniques, as the outside world won't know the difference.

To illustrate, the following C# `Add()` method is not CLS compliant, as the parameters and return values make use of unsigned data (which is not a requirement of the CLS):

```
class Calc
{
    // Exposed unsigned data is not CLS compliant!
    public ulong Add(ulong x, ulong y)
    { return x + y; }
}
```

However, if you were to only make use of unsigned data internally in a method as follows,

```
class Calc
{
    public int Add(int x, int y)
    {
        // As this ulong variable is only used internally,
```

```
// we are still CLS compliant.
ulong temp = 0;
...
return x + y;
}
}
```

you have still conformed to the rules of the CLS and can rest assured that all .NET languages are able to invoke the `Add()` method.

Of course, in addition to Rule 1, the CLS defines numerous other rules. For example, the CLS describes how a given language must represent text strings, how enumerations should be represented internally (the base type used for storage), how to define static members, and so forth. Luckily, you don't have to commit these rules to memory to be a proficient .NET developer. Again, by and large, an intimate understanding of the CTS and CLS specifications is only of interest to tool/compiler builders.

Ensuring CLS Compliance

As you will see over the course of this book, C# does define a number of programming constructs that are not CLS compliant. The good news, however, is that you can instruct the C# compiler to check your code for CLS compliance using a single .NET attribute.

```
// Tell the C# compiler to check for CLS compliance.
[assembly: System.CLSCompliant(true)]
```

Chapter 15 dives into the details of attribute-based programming. Until then, simply understand that the `[CLSCompliant]` attribute will instruct the C# compiler to check each and every line of code against the rules of the CLS. If any CLS violations are discovered, you receive a compiler error and a description of the offending code.

Understanding the Common Language Runtime

In addition to the CTS and CLS specifications, the final TLA (three-letter abbreviation) to contend with at the moment is the CLR. Programmatically speaking, the term *runtime* can be understood as a collection of services that are required to execute a given compiled unit of code. For example, when developers make use of the MFC to create a new application, they are aware that their program requires the MFC runtime library (i.e., `mfc42.dll`). Other popular languages also have a corresponding runtime: VB6 programmers are tied to a runtime module or two (e.g., `msvbm60.dll`), and Java developers are tied to the Java Virtual Machine (JVM), for example.

The .NET platform offers yet another runtime system. The key difference between the .NET runtime and the various other runtimes I just mentioned is the fact that the .NET runtime provides a single well-defined runtime layer that is shared by *all* languages and platforms that are .NET-aware.

The crux of the CLR is physically represented by a library named `mscoree.dll` (aka the Common Object Runtime Execution Engine). When an assembly is referenced for use, `mscoree.dll` is loaded automatically, which in turn loads the required assembly into memory. The runtime engine is responsible for a number of tasks. First and foremost, it is the entity in charge of resolving the location of an assembly and finding the requested type within the binary by reading the contained metadata. The CLR then lays out the type in memory, compiles the associated CIL into platform-specific instructions, performs any necessary security checks, and then executes the code in question.

In addition to loading your custom assemblies and creating your custom types, the CLR will also interact with the types contained within the .NET base class libraries when required. Although the entire base class library has been broken into a number of discrete assemblies, the key assembly is `mscorlib.dll`, which contains a large number of core types that encapsulate a wide variety of common programming tasks as well as the core data types used by all .NET languages. When you build .NET solutions, you automatically have access to this particular assembly.

Figure 1-4 illustrates the workflow that takes place between your source code (which is making use of base class library types), a given .NET compiler, and the .NET execution engine.




Figure 1-4. mscoree.dll in action

The Assembly/Namespace/Type Distinction

Each of us understands the importance of code libraries. The point of libraries such as MFC, Java Enterprise Edition, and ATL is to give developers a well-defined set of existing code to leverage in their applications. However, the C# language does not come with a language-specific code library. Rather, C# developers leverage the language-neutral .NET libraries. To keep all the types within the base class libraries well organized, the .NET platform makes extensive use of the *namespace* concept.

A namespace is a grouping of semantically related types contained in an assembly. For example, the `System.IO` namespace contains file I/O-related types, the `System.Data` namespace defines basic database types, and so on. It is very important to point out that a single assembly (such as `mscorlib.dll`) can contain any number of namespaces, each of which can contain any number of types.

To clarify, Figure 1-5 shows a screenshot of the Visual Studio 2010 Object Browser utility. This tool allows you to examine the assemblies referenced by your current project, the namespaces within a particular assembly, the types within a given namespace, and the members of a specific type. Note that the `mscorlib.dll` assembly contains many different namespaces (such as `System.IO`), each with its own semantically related types (e.g., `BinaryReader`).




Figure 1-5. A single assembly can have any number of namespaces

The key difference between this approach and a language-specific library such as MFC is that any language targeting the .NET runtime makes use of the *same* namespaces and *same* types. For example, the following three programs all illustrate the ubiquitous “Hello World” application, written in C#, VB, and C++/CLI:

```

// Hello world in C#
using System;

public class MyApp
{
    static void Main()
    {
        Console.WriteLine("Hi from C#");
    }
}

' Hello world in VB
Imports System

Public Module MyApp
    Sub Main()
        Console.WriteLine("Hi from VB")
    End Sub
End Module

// Hello world in C++/CLI
#include "stdafx.h"
using namespace System;

int main(array<System::String ^> ^args)
{
    Console::WriteLine(L"Hi from C++/CLI");
    return 0;
}

```

Notice that each language is making use of the `Console` class defined in the `System` namespace. Beyond minor syntactic variations, these three applications look and feel very much alike, both physically and logically.

Clearly, your primary goal as a .NET developer is to get to know the wealth of types defined in the (numerous) .NET namespaces. The most fundamental namespace to get your hands around initially is named `System`. This namespace provides a core body of types that you will need to leverage time and again as a .NET developer. In fact, you cannot build any sort of functional C# application without at least making a reference to the `System` namespace, as the core data types (e.g., `System.Int32`, `System.String`) are defined here. Table 1-3 offers a rundown of some (but certainly not all) of the .NET namespaces grouped by related functionality.

Table 1-3. A Sampling of .NET Namespaces

.NET Namespace	Meaning in Life
System	Within System, you find numerous useful types dealing with intrinsic data, mathematical computations, random number generation, environment variables, and garbage collection, as well as a number of commonly used exceptions and attributes.
System.Collections System.Collections.Generic	These namespaces define a number of stock container types, as well as base types and interfaces that allow you to build customized collections.
System.Data System.Data.Common System.Data.EntityClient System.Data.SqlClient	These namespaces are used for interacting with relational databases using ADO.NET.
System.IO System.IO.Compression System.IO.Ports	These namespaces define numerous types used to work with file I/O, compression of data, and port manipulation.
System.Reflection System.Reflection.Emit	These namespaces define types that support runtime type discovery as well as dynamic creation of types.
System.Runtime.InteropServices	This namespace provides facilities to allow .NET types to interact with unmanaged code (e.g., C-based DLLs and COM servers) and vice versa.
System.Drawing System.Windows.Forms	These namespaces define types used to build desktop applications using .NET's original UI toolkit (Windows Forms).
System.Windows System.Windows.Controls System.Windows.Shapes	The System.Windows namespace is the root for several namespaces that represent the Windows Presentation Foundation (WPF) UI toolkit.
System.Linq System.Xml.Linq System.Data.DataSetExtensions	These namespaces define types used when programming against the LINQ API.
System.Web	This is one of many namespaces that allow you to build ASP.NET web applications.
System.ServiceModel	This is one of many namespaces used to build distributed applications using the Windows Communication Foundation API.

Table 1-3. A Sampling of .NET Namespaces (continued)

.NET Namespace	Meaning in Life
System.Workflow.Runtime System.Workflow.Activities	These are two of many namespaces that define types used to build “workflow-enabled” applications using the Windows Workflow Foundation API.
System.Threading System.Threading.Tasks	This namespace defines numerous types to build multithreaded applications which can distribute workloads across multiple CPUs.
System.Security	Security is an integrated aspect of the .NET universe. In the security-centric namespaces, you find numerous types dealing with permissions, cryptography, and so on.
System.Xml	The XML-centric namespaces contain numerous types used to interact with XML data.

The Role of the Microsoft Root Namespace

I'm sure you noticed while reading over the listings in Table 1-3, that `System` is the root namespace for a good number of nested namespaces (e.g., `System.IO`, `System.Data`). As it turns out, however, the .NET base class library defines a number of topmost root namespaces beyond `System`, the most useful of which is named `Microsoft`.

Any namespace nested within `Microsoft` (e.g., `Microsoft.CSharp`, `Microsoft.ManagementConsole`, `Microsoft.Win32`) contains types that are used to interact with services unique to the Windows operating system. Given this point, you should not assume that these types could be used successfully on other .NET-enabled operating systems such as Mac OS X. For the most part, this text will not dig into the details of the `Microsoft` rooted namespaces, so be sure to consult the .NET Framework 4.0 SDK documentation if you are so interested.

Note Chapter 2 will illustrate the use of the .NET Framework 4.0 SDK documentation, which provides details regarding every namespace, type, and member found within the base class libraries.

Accessing a Namespace Programmatically

It is worth reiterating that a namespace is nothing more than a convenient way for us mere humans to logically understand and organize related types. Consider again the `System` namespace. From your perspective, you can assume that `System.Console` represents a class named `Console` that is contained within a namespace called `System`. However, in the eyes of the .NET runtime, this is not so. The runtime engine only sees a single entity named `System.Console`.

In C#, the `using` keyword simplifies the process of referencing types defined in a particular namespace. Here is how it works. Let's say you are interested in building a graphical desktop application

using the Windows Forms API. The main window renders a bar chart based on some information obtained from a back-end database and displays your company logo. While learning the types each namespace contains takes study and experimentation, here are some possible candidates to reference in your program.

```
// Here are all the namespaces used to build this application.
using System; // General base class library types.
using System.Drawing; // Graphical rendering types.
using System.Windows.Forms; // Windows Forms GUI widget types.
using System.Data; // General data-centric types.
using System.Data.SqlClient; // MS SQL Server data access types.
```

Once you have specified some number of namespaces (and set a reference to the assemblies that define them), you are free to create instances of the types they contain. For example, if you are interested in creating an instance of the `Bitmap` class (defined in the `System.Drawing` namespace), you can write

```
// Explicitly list the namespaces used by this file.
using System;
using System.Drawing;

class Program
{
    public void DisplayLogo()
    {
        // Create a 20 * 20 pixel bitmap.
        Bitmap companyLogo = new Bitmap(20, 20);
        ...
    }
}
```

Because your code file is importing `System.Drawing`, the compiler is able to resolve the `Bitmap` class as a member of this namespace. If you did not specify the `System.Drawing` namespace, you would be issued a compiler error. However, you are free to declare variables using a *fully qualified name* as well.

```
// Not listing System.Drawing namespace!
using System;

class Program
{
    public void DisplayLogo()
    {
        // Using fully qualified name.
        System.Drawing.Bitmap companyLogo =
            new System.Drawing.Bitmap(20, 20);
        ...
    }
}
```

While defining a type using the fully qualified name provides greater readability, I think you'd agree that the C# `using` keyword reduces keystrokes. In this text, I will avoid the use of fully qualified names

(unless there is a definite ambiguity to be resolved) and opt for the simplified approach of the C# `using` keyword.

However, always remember that the `using` keyword is simply a shorthand notation for specifying a type's fully qualified name, and either approach results in the *exact* same underlying CIL (given the fact that CIL code always makes use of fully qualified names) and has no effect on performance or the size of the assembly.

Referencing External Assemblies

In addition to specifying a namespace via the C# `using` keyword, you also need to tell the C# compiler the name of the assembly containing the actual CIL definition for the referenced type. As mentioned, many core .NET namespaces are defined within `mscorlib.dll`. However, the `System.Drawing.Bitmap` class is contained within a separate assembly named `System.Drawing.dll`. A vast majority of the .NET Framework assemblies are located under a specific directory termed the *global assembly cache* (GAC). On a Windows machine, this can be located by default under `C:\Windows\Assembly`, as shown in Figure 1-6.




Figure 1-6. Many .NET libraries reside in the GAC

Depending on the development tool you are using to build your .NET applications, you will have various ways to inform the compiler which assemblies you wish to include during the compilation cycle. You'll examine how to do so in the next chapter, so I'll hold off on the details for now.

Note With the release of .NET 4.0, Microsoft has opted to isolate .NET 4.0 assemblies in a unique location, which is independent from C:\Windows\Assembly. Chapter 14 will address this point in detail.

Exploring an Assembly Using ildasm.exe

If you are beginning to feel a tad overwhelmed at the thought of gaining mastery over every namespace in the .NET platform, just remember that what makes a namespace unique is that it contains types that are somehow *semantically related*. Therefore, if you have no need for a user interface beyond a simple Console Application, you can forget all about the System.Windows.Forms, System.Windows, and System.Web namespaces (among others). If you are building a painting application, the database namespaces are most likely of little concern. Like any new set of prefabricated code, you learn as you go.

The Intermediate Language Disassembler utility (ildasm.exe), which ships with the .NET Framework 4.0 SDK, allows you to load up any .NET assembly and investigate its contents, including the associated manifest, CIL code, and type metadata. By default, ildasm.exe should be installed under C:\Program Files\Microsoft SDKs\Windows\v7.0A\bin (if you cannot find ildasm.exe in this location, simply search your machine for a file named ildasm.exe).

Note You can easily run ildasm.exe by opening a Visual Studio 2010 Command Prompt, and type “ildasm” (without the quotes) followed by the Enter key.

Once you run this tool, proceed to the File | Open menu command and navigate to an assembly you wish to explore. By way of illustration, here is the Calc.exe assembly generated based on the Calc.cs file shown earlier in this chapter (see Figure 1-7). ildasm.exe presents the structure of an assembly using a familiar tree-view format.





Figure 1-7. ildasm.exe allows you to see the CIL code, manifest, and metadata within a .NET assembly

Viewing CIL Code

In addition to showing the namespaces, types, and members contained in a given assembly, ildasm.exe also allows you to view the CIL instructions for a given member. For example, if you were to double-click the `Main()` method of the `Program` class, a separate window would display the underlying CIL (see Figure 1-8).



```


CalculatorExample.CalcApp::Main : void()
Find Find Next
.method private hidebysig static void Main() cil managed
{
    .entrypoint
    // Code size      42 (0x2a)
    .maxstack 3
    .locals init (class CalculatorExample.Calc V_0,
                 int32 V_1)
    IL_0000: nop
    IL_0001: newobj     instance void CalculatorExample.Calc::.ctor()
    IL_0006: stloc.0
    IL_0007: ldloc.0
    IL_0008: ldc.i4.s 10
    IL_0009: ldc.i4.s 84
    IL_000c: callvirt   instance int32 CalculatorExample.Calc::Add(int32,
                                                               int32)
    IL_0011: stloc.1
    IL_0012: ldloc.1
}

```

Figure 1-8. Viewing the underlying CIL

Viewing Type Metadata

If you wish to view the type metadata for the currently loaded assembly, press Ctrl+M. Figure 1-9 shows the metadata for the `Calc.Add()` method.



```

MetaInfo
Find Find Next
Method #1 (06000003)
-----
MethodName: Add (06000003)
Flags : [Public] [HideBySig] [ReuseSlot] (00000006)
RVA : 0x00002090
ImplFlags : [IL] [Managed] (00000000)
CallConvtn: [DEFAULT]
hasThis
ReturnType: I4
2 Arguments
    Argument #1: I4
    Argument #2: I4
2 Parameters
    (1) ParamToken : (08000001) Name : x Flags: [none] (00000000)
    (2) ParamToken : (08000002) Name : y Flags: [none] (00000000)

Method #2 (06000004)
-----
MethodName: .ctor (06000004)

```

Figure 1-9. Viewing type metadata via ildasm.exe

Viewing Assembly Metadata (aka the Manifest)

Finally, if you are interested in viewing the contents of the assembly's manifest, simply double-click the MANIFEST icon (see Figure 1-10).




Figure 1-10. Viewing manifest data via ildasm.exe

To be sure, ildasm.exe has more options than shown here, and I will illustrate additional features of the tool where appropriate in the text.

Exploring an Assembly Using Reflector

While using ildasm.exe is a very common task when you wish to dig into the guts of a .NET assembly, the one gotcha is that you are only able to view the underlying CIL code, rather than looking at an assembly's implementation using your managed language of choice. Thankfully, many .NET object browsers and decompilers are available for download, including the very popular Reflector.

This free tool can be downloaded from <http://www.red-gate.com/products/reflector>. Once you have unzipped the archive, you are able to run the tool and plug in any assembly you wish using the File | Open menu option. Figure 1-11 shows our Calc.exe application once again.




Figure 1-11. Reflector is a very popular object browsing tool

Notice that reflector.exe supports a Disassembler window (opened by pressing the space bar) as well as a drop-down list box that allows you to view the underlying code base in your language of choice (including, of course, CIL code). I'll leave it up to you to check out the number of intriguing features found within this tool.

Note Be aware that over the course of the remainder of the book, I'll make use of both ildasm.exe as well as reflector.exe to illustrate various concepts. So take a moment to download Reflector if you have not already done so.

Deploying the .NET Runtime

It should come as no surprise that .NET assemblies can be executed only on a machine that has the .NET Framework installed. For an individual who builds .NET software, this should never be an issue, as your development machine will be properly configured at the time you install the freely available .NET Framework 4.0 SDK (as well as commercial .NET development environments such as Visual Studio 2010).

However, if you deploy your application to a computer that does not have .NET installed, it will fail to run. For this reason, Microsoft provides a setup package named `dotNetFx40_Full_x86.exe` that can be freely shipped and installed along with your custom software. This installation program can be downloaded from Microsoft's general download area (<http://www.microsoft.com/downloads>).

Once `dotNetFx40_Full_x86.exe` is installed, the target machine will now contain the .NET base class libraries, .NET runtime (`mscoree.dll`), and additional .NET infrastructure (such as the GAC).

Note The Vista and Windows 7 operating systems are preconfigured with the necessary .NET runtime infrastructure. However, if you are deploying your application to a different Microsoft OS, such as Windows XP, you will want to ensure the target machine has the .NET runtime environment installed and configured.

The .NET Client Profile Runtime

The `dotNetFx40_Full_x86.exe` setup program weighs in at approximately 77 MB in size. If you were deploying your application to the end user via a CD, this would not be an issue, as your setup program could simply run the executable if the machine were not configured correctly.

However, if the end user were required to download `dotNetFx40_Full_x86.exe` using a low-speed Internet connection, this could be a bit of a burden. To address this situation, Microsoft introduced an alternative setup program termed the *client profile* (`dotNetFx40_Client_x86.exe`), which can also be downloaded for free from the Microsoft download site.

As the name implies, this setup program installs a subset of the .NET base class libraries, in addition to the necessary runtime infrastructure. While the client profile is more lightweight than its big brother (approximately 34 MB in size), the target machine will not have the same libraries as a “Full” .NET installation. The omitted assemblies of the client profile can be optionally installed on the target machine when the end user performs a Windows Update.

Note Both the full and client runtime profiles do have 64-bit counterparts, `dotNetFx40_Full_x86_x64.exe` and `dotNetFx40_Client_x86_x64.exe` respectively.

The Platform-Independent Nature of .NET

To close this chapter, allow me to briefly comment on the platform-independent nature of the .NET platform. To the surprise of most developers, .NET assemblies can be developed and executed on non-Microsoft operating systems—Mac OS X, various Linux distributions, Solaris, as well as the Apple iPhone device (via the MonoTouch API). To understand how this is possible, you need to come to terms with yet another abbreviation in the .NET universe: CLI (Common Language Infrastructure).

When Microsoft released the C# programming language and the .NET platform, they also crafted a set of formal documents that described the syntax and semantics of the C# and CIL languages, the .NET assembly format, core .NET namespaces, and the mechanics of a hypothetical .NET runtime engine (known as the Virtual Execution System, or VES).

Better yet, these documents have been submitted to (and ratified by) Ecma International as official international standards (<http://www.ecma-international.org>). The specifications of interest are

- ECMA-334: The C# Language Specification
- ECMA-335: The Common Language Infrastructure (CLI)

The importance of these documents becomes clear when you understand that they enable third parties to build distributions of the .NET platform for any number of operating systems and/or processors. ECMA-335 is the more “meaty” of the two specifications, so much so that it has been broken into six partitions, as shown in Table 1-4.

Table 1-4. Partitions of the CLI

Partitions of ECMA-335	Meaning in Life
Partition I: Concepts and Architecture	Describes the overall architecture of the CLI, including the rules of the CTS and CLS, and the mechanics of the .NET runtime engine.
Partition II: Metadata Definition and Semantics	Describes the details of .NET metadata and the assembly format.
Partition III: CIL Instruction Set	Describes the syntax and semantics of CIL code.
Partition IV: Profiles and Libraries	Gives a high-level overview of the minimal and complete class libraries that must be supported by a .NET distribution.
Partition V	Debug Interchange Format
Partition VI: Annexes	Provides a collection of odds-and-ends details such as class library design guidelines and the implementation details of a CIL compiler.

Be aware that Partition IV (Profiles and Libraries) defines only a *minimal* set of namespaces that represent the core services expected by a CLI distribution (e.g., collections, console I/O, file I/O, threading, reflection, network access, core security needs, XML data manipulation). The CLI does *not* define namespaces that facilitate web development (ASP.NET), database access (ADO.NET), or desktop graphical user interface (GUI) application development (Windows Forms/Windows Presentation Foundation).

The good news, however, is that the mainstream .NET distributions extend the CLI libraries with Microsoft-compatible equivalents of ASP.NET, ADO.NET, and Windows Forms in order to provide full-featured, production-level development platforms. To date, there are two major implementations of the CLI (beyond Microsoft’s Windows-specific offering). Although this text focuses on the creation of .NET applications using Microsoft’s .NET distribution, Table 1-5 provides information regarding the Mono and Portable .NET projects.

Table 1-5. Open Source .NET Distributions

Distribution	Meaning in Life
http://www.mono-project.com	The Mono project is an open source distribution of the CLI that targets various Linux distributions (e.g., openSUSE, Fedora) as well as Windows and Mac OS X / iPhone devices.
http://www.dotgnu.org	Portable.NET is another open source distribution of the CLI that runs on numerous operating systems. Portable.NET aims to target as many operating systems as possible (e.g., Windows, AIX, BeOS, Mac OS X, Solaris, all major Linux distributions).

Both Mono and Portable.NET provide an ECMA-compliant C# compiler, .NET runtime engine, code samples, documentation, as well as numerous development tools that are functionally equivalent to the tools that ship with Microsoft's .NET Framework 4.0 SDK. Furthermore, Mono and Portable.NET collectively ship with a VB .NET, Java, and C complier.

■ **Note** Coverage of creating cross-platform .NET applications using Mono can be found in Appendix B.

Summary

The point of this chapter was to lay out the conceptual framework necessary for the remainder of this book. I began by examining a number of limitations and complexities found within the technologies prior to .NET, and followed up with an overview of how .NET and C# attempt to simplify the current state of affairs.

.NET basically boils down to a runtime execution engine (`mscoree.dll`) and base class library (`mscorlib.dll` and associates). The Common Language Runtime (CLR) is able to host any .NET binary (aka assembly) that abides by the rules of managed code. As you have seen, assemblies contain CIL instructions (in addition to type metadata and the assembly manifest) that are compiled to platform-specific instructions using a just-in-time (JIT) compiler. In addition, you explored the role of the Common Language Specification (CLS) and Common Type System (CTS).

This was followed by an examination of the `ildasm.exe` and `reflector.exe` object browsing utilities, as well as coverage of how to configure a machine to host .NET applications using the full and client profiles. I wrapped up by briefly addressing the platform-independent nature of C# and the .NET platform, a topic further examined in Appendix B.

CHAPTER 2



Building C# Applications

As a C# programmer, you may choose among numerous tools to build .NET applications. The point of this chapter is to provide a tour of various .NET development options, including, of course, Visual Studio 2010. The chapter opens, however, with an examination of working with the C# command-line compiler, `csc.exe`, and the simplest of all text editors, the Notepad application that ships with the Microsoft Windows OS as well as the freely downloadable Notepad++.

While you could work through this entire text using nothing other than `csc.exe` and a basic text editor, I'd bet you are also interested in working with feature-rich integrated development environments (IDEs). To address this need, you will be introduced to a free, open source .NET IDE named SharpDevelop. As you will see, this IDE rivals the functionality of many commercial .NET development environments. After briefly examining the Visual C# 2010 Express IDE (which is also free), you will be given a guided tour of the key features of Visual Studio 2010.

Note Over the course of this chapter, you will encounter some C# syntax we have not formally examined. If you are unfamiliar with the syntax, don't fret. Chapter 3 will formally begin your examination of the C# language.

The Role of the .NET Framework 4.0 SDK

One common misconception regarding .NET development is the belief that programmers must purchase a copy of Visual Studio in order to build their C# applications. The truth of the matter is that you are able to build any sort of .NET program using the freely downloadable .NET Framework 4.0 Software Development Kit (SDK). This SDK provides you with numerous managed compilers, command-line utilities, sample code, the .NET class libraries, and a complete documentation system.

Note The .NET Framework 4.0 SDK setup program (`dotnetfx40_full_setup.exe`) can be obtained from the .NET download web site (<http://msdn.microsoft.com/netframework>).

Now, be aware that if you are going to be using Visual Studio 2010 or Visual C# 2010 Express, you have no need to manually install the .NET Framework 4.0 SDK. When you install either of these products, the SDK is installed automatically, thereby giving you everything you need out of the box.

However, if you are *not* going to be using a Microsoft IDE as you work through this text, be sure to install the SDK before proceeding.

The Visual Studio 2010 Command Prompt

When you install the .NET Framework 4.0 SDK, Visual Studio 2010, or Visual C# 2010 Express, you will end up with a number of new directories on your local hard drive, each of which contains various .NET development tools. Many of these tools are driven from the command prompt, so if you wish to use these utilities from any Windows command window, you will need to register these paths with the operating system.

While you could update your PATH variable manually to do so, you can save yourself some time by simply making use of the Visual Studio 2010 Command Prompt that is accessible from the Start ➤ All Programs ➤ Microsoft Visual Studio 2010 ➤ Visual Studio Tools folder (see Figure 2-1).




Figure 2-1. The Visual Studio 2010 command prompt

The benefit of using this particular command prompt is that it has been preconfigured to provide access to each of the .NET development tools. Assuming you have a .NET development environment installed, type the following command and press the Enter key:

```
csc -?
```

If all is well, you should see a list of command-line arguments of the C# command-line compiler (where csc stands for the *C-sharp compiler*).

Building C# Applications Using csc.exe

While it is true that you may never decide to build a large-scale application using nothing but the C# command-line compiler, it is important to understand the basics of how to compile your code files by hand. I can think of a few reasons you should get a grip on the process.

- The most obvious reason is the simple fact that you might not have a copy of Visual Studio 2010 or another graphical IDE.

- You may be in a university setting where you are prohibited from using code generation tools/IDEs in the classroom.
- You plan to make use of automated build tools, such as `msbuild.exe` which require you to know the command-line options of the tools you are utilizing.
- You want to deepen your understanding of C#. When you use graphical IDEs to build applications, you are ultimately instructing `csc.exe` how to manipulate your C# input files. In this light, it's edifying to see what takes place behind the scenes.

Another nice by-product of working with `csc.exe` in the raw is that you become that much more comfortable manipulating other command-line tools included with the .NET Framework 4.0 SDK. As you will see throughout this book, a number of important utilities are accessible only from the command line.

To illustrate how to build a .NET application IDE-free, we will build a simple executable assembly named `TestApp.exe` using the C# command-line compiler and Notepad. First, you need some source code. Open Notepad (using the Start ▶ All Programs ▶ Accessories menu option) and enter the following trivial C# class definition:

```
// A simple C# application.
using System;

class TestApp
{
    static void Main()
    {
        Console.WriteLine("Testing! 1, 2, 3");
    }
}
```

Once you have finished, save the file in a convenient location (e.g., C:\CscExample) as `TestApp.cs`. Now let's get to know the core options of the C# compiler.

Note As a convention, all C# code files take a `*.cs` file extension. The name of the file does not need to have any mapping to the name of the type (or types) it is defining.

Specifying Input and Output Targets

The first point of interest is to understand how to specify the name and type of assembly to create (e.g., a console application named `MyShell.exe`, a code library named `MathLib.dll`, a Windows Presentation Foundation application named `Halo8.exe`). Each possibility is represented by a specific flag passed into `csc.exe` as a command-line parameter (see Table 2-1).

Table 2-1. Output Options of the C# Compiler

Option	Meaning in Life
/out	This option is used to specify the name of the assembly to be created. By default, the assembly name is the same as the name of the initial input *.cs file.
/target:exe	This option builds an executable console application. This is the default assembly output type, and thus may be omitted when building this type of application.
/target:library	This option builds a single-file *.dll assembly.
/target:module	This option builds a <i>module</i> . Modules are elements of multi-file assemblies (fully described in Chapter 14).
/target:winexe	Although you are free to build graphical user interface-based applications using the /target:exe option, /target:winexe prevents a console window from appearing in the background.

Note The options sent to the command-line compiler (as well as most other command-line tools) can be prefixed with either a dash (-) or a slash (/).

To compile TestApp.cs into a console application named TestApp.exe, change to the directory containing your source code file

```
cd C:\CscExample
```

and enter the following command set (note that command-line flags must come before the name of the input files, not after):

```
csc /target:exe TestApp.cs
```

Here I did not explicitly specify an /out flag; therefore, the executable will be named TestApp.exe given that TestApp is the name of the input file. Also be aware that most of the C# compiler flags support an abbreviated version, such as /t rather than /target (you can view all abbreviations by entering csc -? at the command prompt).

```
csc /t:exe TestApp.cs
```

Furthermore, given that the /t:exe flag is the default output used by the C# compiler, you could also compile TestApp.cs simply by typing the following:

```
csc TestApp.cs
```

TestApp.exe can now be run from the command line by typing the name of the executable, as shown in Figure 2-2.




Figure 2-2. TestApp.exe in action

Referencing External Assemblies

Next, let's examine how to compile an application that makes use of types defined in a separate .NET assembly. And just in case you are wondering how the C# compiler understood your reference to the `System.Console` type, recall from Chapter 1 that `mscorlib.dll` is *automatically referenced* during the compilation process (if for some strange reason you wish to disable this feature, you may specify the `/nostdlib` option of `csc.exe`).

Let's update the TestApp application to display a Windows Forms message box. Open your `TestApp.cs` file and modify it as follows:

```
using System;

// Add this!
using System.Windows.Forms;

class TestApp
{
    static void Main()
    {
        Console.WriteLine("Testing! 1, 2, 3");

        // Add this!
        MessageBox.Show("Hello...");
    }
}
```

Notice you are importing the `System.Windows.Forms` namespace via the C# `using` keyword (introduced in Chapter 1). Recall that when you explicitly list the namespaces used within a given `*.cs` file, you avoid the need to make use of fully qualified names of a type (which can lead to hand cramps).

At the command line, you must inform `csc.exe` which assembly contains the namespaces you are using. Given that you have made use of the `System.Windows.Forms.MessageBox` class, you must specify the `System.Windows.Forms.dll` assembly using the `/reference` flag (which can be abbreviated to `/r`).

```
csc /r:System.Windows.Forms.dll TestApp.cs
```

If you now rerun your application, you should see a message box appear (see Figure 2-3) in addition to the console output.



Figure 2-3. Your first Windows Forms application

Referencing Multiple External Assemblies

On a related note, what if you need to reference numerous external assemblies using `csc.exe`? Simply list each assembly using a semicolon-delimited list. You don't need to specify multiple external assemblies for the current example, but some sample usage follows:

```
csc /r:System.Windows.Forms.dll;System.Drawing.dll *.cs
```

Note As explained a bit later in this chapter, the C# compiler will automatically reference a set of core .NET assemblies (such as `System.Windows.Forms.dll`) even if they are not specified using the `/r` flag.

Compiling Multiple Source Files

The current incarnation of the `TestApp.exe` application was created using a single `*.cs` source code file. While it is perfectly permissible to have all of your .NET types defined in a single `*.cs` file, most projects are composed of multiple `*.cs` files to keep your code base a bit more flexible. Assume you have authored a new class contained in a new file named `HelloMsg.cs`.

```
// The HelloMessage class
using System;
using System.Windows.Forms;

class HelloMessage
{
    public void Speak()
    {
        MessageBox.Show("Hello...");
    }
}
```

Now, update your initial `TestApp` class to make use of this new class type and comment out the previous Windows Forms logic.

```
using System;

// Don't need this anymore.
// using System.Windows.Forms;

class TestApp
{
    static void Main()
    {
        Console.WriteLine("Testing! 1, 2, 3");

        // Don't need this anymore either.
        // MessageBox.Show("Hello...");

        // Use the HelloMessage class!
        HelloMessage h = new HelloMessage();
        h.Speak();
    }
}
```

You can compile your C# files by listing each input file explicitly.

```
csc /r:System.Windows.Forms.dll TestApp.cs HelloMsg.cs
```

As an alternative, the C# compiler allows you to make use of the wildcard character (*) to inform `csc.exe` to include all `*.cs` files contained in the project directory as part of the current build.

```
csc /r:System.Windows.Forms.dll *.cs
```

When you run the program again, the output is identical to the previous compiled code. The only difference between the two applications is the fact that the current logic has been split among multiple files.

Working with C# Response Files

As you might guess, if you were to build a complex C# application at the command prompt, you would have to specify a tedious number of input options to inform the compiler how to process your source code. To help lessen your typing burden, the C# compiler honors the use of *response files*.

C# response files contain all the instructions to be used during the compilation of your current build. By convention, these files end in a `*.rsp` (response) extension. Assume that you have created a response file named `TestApp.rsp` that contains the following options (as you can see, comments are denoted with the # character):

```
# This is the response file
# for the TestApp.exe example
# of Chapter 2.
```

```
# External assembly references.
/r:System.Windows.Forms.dll

# output and files to compile (using wildcard syntax).
/target:exe /out:TestApp.exe *.cs
```

Now, assuming this file is saved in the same directory as the C# source code files to be compiled, you are able to build your entire application as follows (note the use of the @ symbol):

```
csc @TestApp.rsp
```

If the need should arise, you can also specify multiple *.rsp files as input (e.g., csc @FirstFile.rsp @SecondFile.rsp @ThirdFile.rsp). If you take this approach, be aware that the compiler processes the command options as they are encountered. Therefore, command-line arguments in a later *.rsp file can override options in a previous response file.

Also note that flags listed explicitly on the command line before a response file will be overridden by the specified *.rsp file. Thus, if you were to enter the following:

```
csc /out:MyCoolApp.exe @TestApp.rsp
```

the name of the assembly would still be TestApp.exe (rather than MyCoolApp.exe), given the /out:TestApp.exe flag listed in the TestApp.rsp response file. However, if you list flags after a response file, the flag will override settings in the response file.

Note The effect of the /reference flag is cumulative. Regardless of where you specify external assemblies (before, after, or within a response file), the end result is a summation of each reference assembly.

The Default Response File (csc.rsp)

The final point to be made regarding response files is that the C# compiler has an associated default response file (csc.rsp), which is located in the same directory as csc.exe itself (which is by default installed under C:\Windows\Microsoft.NET\Framework\<version>, where <version> is a given version of the platform). If you were to open this file using Notepad, you will find that numerous .NET assemblies have already been specified using the /r: flag, including various libraries for web development, LINQ programming, data access, and other core libraries (beyond mscorelib.dll).

When you are building your C# programs using csc.exe, this response file will be automatically referenced, even when you supply a custom *.rsp file. Given the presence of the default response file, the current TestApp.exe application could be successfully compiled using the following command set (as System.Windows.Forms.dll is referenced within csc.rsp):

```
csc /out:TestApp.exe *.cs
```

In the event that you wish to disable the automatic reading of csc.rsp, you can specify the /noconfig option.

```
csc @TestApp.rsp /noconfig
```

Note If you reference assemblies (via the /r option) that you do not actually make use of, they are ignored by the compiler. Therefore, you have no need to worry about “code bloat.”

Obviously, the C# command-line compiler has many other options that can be used to control how the resulting .NET assembly is to be generated. You’ll see other important features where necessary over the course of this text, however full details of these options can be found within the .NET Framework 4.0 SDK documentation.

Source Code The CscExample application can be found under the Chapter 2 subdirectory.

Building .NET Applications Using Notepad++

Another text editor I’d like to quickly point out is the open source (and freely downloadable) Notepad++ application. This tool can be obtained from <http://notepad-plus.sourceforge.net>. Unlike the simple Windows Notepad application, Notepad++ allows you to author code in a variety of languages and supports various plug-in utilities. In addition, Notepad++ provides a few other niceties, including the following:

- Out-of-the-box support for C# keywords (including keyword color coding)
- Support for *syntax folding*, which allows you to collapse and expand groups of code statements within the editor (similar to Visual Studio 2010/C# 2010 Express)
- The ability to zoom in/zoom out text via Ctrl-mouse wheel
- Configurable autocomplete for a variety of C# keywords and .NET namespaces

Regarding this last point, the Ctrl+space keyboard combination will activate C# autocomplete support (see Figure 2-4).




Figure 2-4. Autocompletion using Notepad++

Note The options displayed by the autocomplete window can be modified and extended. Simply open up the C:\Program Files\Notepad++\plugins\APIs\cs.xml file for editing and add any additional entries.

I won't go into too many details of Notepad++ beyond what we have examined here. If you require more assistance, select the ?► Help content menu option.

Building .NET Applications Using SharpDevelop

As you may agree, authoring C# code with Notepad++ is a step in the right direction, compared to Notepad and the command prompt. However, these tools do not provide rich IntelliSense capabilities for C# code, designers for building graphical user interfaces, project templates, or database manipulation tools. To address such needs, allow me to introduce the next .NET development option: SharpDevelop (also known as #Develop).

SharpDevelop is an open source and feature-rich IDE that you can utilize to build .NET assemblies using C#, VB, CIL, or a Python-inspired .NET language named Boo. Beyond the fact that this IDE is completely free, it is interesting to note that it was written entirely in C#. In fact, you have the choice to download and compile the *.cs files manually or run a setup.exe program to install SharpDevelop on your development machine. Both distributions can be obtained from <http://www.sharpdevelop.com>.

SharpDevelop provides numerous productivity enhancements. Here is a hit list of some of the major benefits.

- Support for multiple .NET languages and project types
- IntelliSense, code completion, and code snippet capabilities

- An Add Reference dialog box to reference external assemblies, including assemblies deployed to the global assembly cache (GAC)
- A visual Windows Forms designer
- Integrated object browsing and code definition utilities
- Visual database designer utilities
- A C#-to-VB (and vice versa) code-conversion utility

Impressive for a free IDE, is it not? Although this chapter doesn't cover each of these points in detail, let's walk through a few items of interest.

Note At the time of this writing, the current version of SharpDevelop does not support C# 2010 / .NET 4.0 features. Be sure to check the SharpDevelop web site for future releases.

Building a Simple Test Project

Once you have installed SharpDevelop, the File > New > Solution menu option allows you to pick which type of project you wish to generate (and in which .NET language). For example, assume you have created a C# Windows Application solution named MySDWinApp (see Figure 2-5).




Figure 2-5. The SharpDevelop New Project dialog box

Like Visual Studio, you have a Windows Forms GUI designer toolbox (to drag and drop controls onto the designer), and a Properties window to set up the look and feel of each UI item. Figure 2-6 illustrates configuring a button control using the IDE (note that I clicked on the Design tab mounted on the bottom of the opened code file).




Figure 2-6. Graphically designing a Windows Forms Application with SharpDevelop

If you were to click the Source button mounted to the bottom of the form's designer, you would find the expected IntelliSense, code completion, and integrated help features (see Figure 2-7).




Figure 2-7. SharpDevelop supports numerous code-generation utilities

SharpDevelop was designed to mimic much of the same functionality found within Microsoft's .NET IDEs (which we will examine next). Given this point, I won't dive into all of the features of this open source .NET IDE. If you require more information, simply use the provided Help menu.

Building .NET Applications Using Visual C# 2010 Express

During the summer of 2004, Microsoft introduced a new line of IDEs that fall under the designation of *Express* products (<http://msdn.microsoft.com/express>). To date, there are various members of the Express family (all of which are *completely free* and supported and maintained by Microsoft Corporation), including the following:

- *Visual Web Developer 2010 Express*: A lightweight tool for building dynamic ASP.NET web sites and WCF services
- *Visual Basic 2010 Express*: A streamlined programming tool ideal for novice programmers who want to learn how to build applications using the user-friendly syntax of Visual Basic
- *Visual C# 2010 Express and Visual C++ 2010 Express*: Targeted IDEs for students and enthusiasts who wish to learn the fundamentals of computer science in their syntax of choice
- *SQL Server Express*: An entry-level, database management system geared toward hobbyists, enthusiasts, and student developers

Some Unique Features of Visual C# 2010 Express

By and large, the Express products are slimmed-down versions of their Visual Studio 2010 counterparts and are primarily targeted at .NET hobbyists and students. Like SharpDevelop, Visual C# 2010 Express provides various object browsing tools, a Windows Forms designer, the Add References dialog box, IntelliSense capabilities, and code expansion templates.

However, Visual C# 2010 Express offers a few (important) features currently not available in SharpDevelop, including the following:

- Rich support for Windows Presentation Foundation (WPF) XAML applications
- IntelliSense for new C# 2010 syntactical constructs including named arguments and optional parameters
- The ability to download additional free templates that support Xbox 360 development, WPF applications with Twitter integration, and much more

Consider Figure 2-8, which illustrates using Visual C# Express to author the XAML markup for a WPF project.




Figure 2-8. Visual C# 2010 Express has integrated support for .NET 4.0 APIs

Because the look and feel of Visual C# 2010 Express is so similar to that of Visual Studio 2010 (and, to some degree, SharpDevelop), I do not provide a walk-through of this particular IDE here. You are free to use this IDE as you work through the book, but do be aware that Visual C# 2010 Express does not support project templates for building ASP.NET web sites. If you wish to also build web applications, be sure to download Visual Web Developer 2010, also available from <http://msdn.microsoft.com/express>.

Building .NET Applications Using Visual Studio 2010

If you are a professional .NET software engineer, the chances are extremely good that your employer has purchased Microsoft's premier IDE, Visual Studio 2010, for your development endeavors (<http://msdn.microsoft.com/vstudio>). This tool is far and away the most feature-rich, enterprise-ready IDE examined in this chapter. Of course, this power comes at a price, which will vary based on the version of Visual Studio 2010 you purchase. As you might suspect, each version supplies a unique set of features.

Note There is a staggering number of members within the Visual Studio 2010 family. My assumption during the remainder of this text is that you have chosen to make use of Visual Studio 2010 Professional as your IDE of choice.

Although I will assume you have a copy of Visual Studio 2010 Professional, understand that owning a copy of this IDE is *not required* to use this edition of the text. In the worst case, I may examine an option that is not provided by your IDE. However, rest assured that all of this book's sample code will compile just fine when processed by your tool of choice.

Note Once you download the source code for this book from the Source Code/Downloads area of the Apress web site (<http://www.apress.com>), you may load the current example into Visual Studio 2010 (or C# 2010 Express) by double-clicking the example's *.sln file. If you are not using Visual Studio 2010/C# 2010 Express, you will need to manually insert the provided *.cs files into your IDE's project work space.

Some Unique Features of Visual Studio 2010

Visual Studio 2010 ships with the expected GUI designers, code snippet support, database manipulation tools, object and project browsing utilities, and an integrated help system. Unlike many of the IDEs we have already examined, Visual Studio 2010 provides numerous additions. Here is a partial list.

- Visual XML editors/designers
- Support for Windows mobile device development
- Support for Microsoft Office development
- Designer support for Windows Workflow Foundation projects
- Integrated support for code refactoring
- Visual class designer tools

To be completely honest, Visual Studio 2010 provides so many features that it would take an entire book (a rather large book at that) to fully describe every aspect of the IDE. *This is not that book*. However, I do want to point out some of the major features in the pages that follow. As you progress through the text, you'll learn more about the Visual Studio 2010 IDE where appropriate.

Targeting the .NET Framework Using the New Project Dialog Box

If you are following along, create a new C# Console Application (named Vs2010Example) using the File ► New ► Project menu item. As you can see in Figure 2-9, Visual Studio 2010 supports the ability to select which version of the .NET Framework you wish to build against (2.0, 3.x, or 4.0) using the drop-down list box on the top center of the New Project dialog box. For each project in this text, you can simply leave the default selection of .NET Framework 4.0.




Figure 2-9. Visual Studio 2010 allows you to target a particular version of the .NET Framework

Using the Solution Explorer Utility

The Solution Explorer utility (accessible from the View menu) allows you to view the set of all content files and referenced assemblies that comprise the current project (see Figure 2-10).




Figure 2-10. The Solution Explorer utility

Notice that the References folder of Solution Explorer displays a list of each assembly you have currently referenced, which will differ based on the type of project you select and the version of the Framework you are compiling against.

Referencing External Assemblies

When you need to reference additional assemblies, right-click the References folder and select Add Reference. At this point, you can select your assembly from the resulting dialog box (this is essentially the way Visual Studio allows you to specify the /reference option of the command-line compiler). The .NET tab (see Figure 2-11) displays a number of commonly used .NET assemblies; however, the Browse tab allows you to navigate to any .NET assembly on your hard drive. Also, the very useful Recent tab keeps a running tally of frequently referenced assemblies you have used in other projects.




Figure 2-11. The Add Reference dialog box

Viewing Project Properties

Finally, notice an icon named Properties within Solution Explorer. When you double-click this item, you are presented with a sophisticated project configuration editor (see Figure 2-12).




Figure 2-12. The Project Properties window

You will see various aspects of the Project Properties window as you progress through this book. However, if you take some time to poke around, you will see that you can establish various security settings, strongly name your assembly, deploy your application, insert application resources, and configure pre- and post-build events.

The Class View Utility

The next tool to examine is the Class View utility, which you can load from the View menu. The purpose of this utility is to show all of the types in your current project from an object-oriented perspective (rather than a file-based view of Solution Explorer). The top pane displays the set of namespaces and their types, while the bottom pane displays the currently selected type's members (see Figure 2-13).




Figure 2-13. The Class View utility

When you double click on a type or type member using the Class View tool, Visual Studio will automatically open the correct C# code file, and place your mouse cursor at the correct location. Another nice feature of the Visual Studio 2010 Class View tool is that you are able to open up any referenced assembly and drill into the contained namespaces, types, and members (Figure 2-14).




Figure 2-14. The Class View utility can also be used to view referenced assemblies

The Object Browser Utility

Visual Studio 2010 also provides a second utility to investigate the set of referenced assemblies within your current project. Activate the Object Browser using the View menu, and then select the assembly you wish to investigate (see Figure 2-15).




Figure 2-15. The Object Browser utility

Integrated Support for Code Refactoring

One major feature that ships with Visual Studio 2010 is support to *refactor* existing code. Simply put, refactoring is a formal and mechanical process whereby you improve an existing code base. In the bad old days, refactoring typically involved a ton of manual labor. Luckily, Visual Studio 2010 does a great deal to automate the refactoring process.

Using the Refactor menu (which will only be available when a code file is active), related keyboard shortcuts, smart tags, and/or context-sensitive mouse clicks, you can dramatically reshape your code with minimal fuss and bother. Table 2-2 defines some common refactorings recognized by Visual Studio 2010.

Table 2-2. Visual Studio 2010 Refactorings

Refactoring Technique	Meaning in Life
Extract Method	Allows you to define a new method based on a selection of code statements
Encapsulate Field	Turns a public field into a private field encapsulated by a C# property
Extract Interface	Defines a new interface type based on a set of existing type members
Reorder Parameters	Provide a way to reorder member arguments
Remove Parameters	Remove a given argument from the current list of parameters (as you would expect)
Rename	Allows you to rename a code token (method name, field, local variable, and so on) throughout a project

To illustrate refactoring in action, update your `Main()` method with the following simple code:

```
static void Main(string[] args)
{
    // Set up Console UI (CUI)
    Console.Title = "My Rocking App";
    Console.ForegroundColor = ConsoleColor.Yellow;
    Console.BackgroundColor = ConsoleColor.Blue;
    Console.WriteLine("*****");
    Console.WriteLine("***** Welcome to My Rocking App *****");
    Console.WriteLine("*****");
    Console.BackgroundColor = ConsoleColor.Black;

    // Wait for Enter key to be pressed.
    Console.ReadLine();
}
```

While there is nothing wrong with the preceding code as it now stands, imagine that you want to display this welcome message at various places throughout your program. Rather than retyping the same exact console user interface logic, it would be ideal to have a helper function that could be called to do so. Given this, you will apply the Extract Method refactoring to your existing code.

First, select each code statement within `Main()` (except the final call to `Console.ReadLine()`) using the editor. Then right-click the selected text and select the Extract Method option within the Refactor context menu (see Figure 2-16).




Figure 2-16. Activating a code refactoring

Name your new method `ConfigureCUI` using the resulting dialog box. When you have finished, you will find that your `Main()` method calls the newly generated `ConfigureCUI()` method, which now contains the previously selected code.

```
class Program
{
    static void Main(string[] args)
    {
        ConfigureCUI();

        // Wait for key press to close.
        Console.ReadLine();
    }

    private static void ConfigureCUI()
    {
        // Set up Console UI (CUI)
        Console.Title = "My Rocking App";
        Console.ForegroundColor = ConsoleColor.Yellow;
        Console.BackgroundColor = ConsoleColor.Blue;
        Console.WriteLine("*****");
        Console.WriteLine("***** Welcome to My Rocking App *****");
        Console.WriteLine("*****");
        Console.BackgroundColor = ConsoleColor.Black;
    }
}
```

This is a simple example of using the built-in refactorings of Visual Studio 2010, and you'll see additional examples here and there over the course of this text.

Code Expansions and Surround With Technology

Visual Studio 2010 (as well as Visual C# 2010 Express) is capable of inserting prefabricated blocks of C# code using menu selections, context-sensitive mouse clicks, and/or keyboard shortcuts. The number of available code expansions is impressive and can be broken down into two main groups.

- *Snippets*: These templates insert common code blocks at the location of the mouse cursor.
- *Surround With*: These templates wrap a block of selected statements within a relevant scope.

To see this functionality firsthand, assume that you wish to iterate over the incoming parameters of the `Main()` method using a `foreach` construct. Rather than typing the code in by hand, you can activate the `foreach` code snippet. When you have done so, the IDE will dump out a `foreach` code template at the current location of the mouse cursor.

To illustrate, place the mouse cursor after the initial opening curly bracket of `Main()`. One way to activate a code snippet is to right-click the mouse and activate the Insert Snippet (or Surround With) menu option. Here, you will find a list of all code snippets of this category (press the Esc key to dismiss the pop-up menu). As a shortcut, however, you can simply type in the name of the code snippet, `foreach` in this case. In Figure 2-17, notice how the icon for a code snippet looks a bit like a torn piece of paper.




Figure 2-17. Activating a code snippet

Once you find the snippet you want to activate, press the Tab key twice. This will autocomplete the entire snippet and leave a set of placeholders that you can fill in to complete the snippet. If you press the Tab key, you can cycle between each placeholder and fill in the gaps (press the Esc key to exit the code snippet edit mode).

If you were to right-click and select the Surround With menu, you would likewise be presented with a list of options. Recall that when using Surround With snippets, typically you first select a block of code statements to represent what should be used to wrap them (e.g., try/catch block). Be sure to take time to explore these predefined code expansion templates, as they can radically speed up the development process.

Note All code expansion templates are XML-based descriptions of the code to generate within the IDE. Using Visual Studio 2010 (as well as Visual C# 2010 Express), you can create your own custom code templates. Details of how to do so can be found in my article “Investigating Code Snippet Technology” at <http://msdn.microsoft.com>.

The Visual Class Designer

Visual Studio 2010 gives us the ability to design classes visually (this capability is not included in Visual C# 2010 Express). The Class Designer utility allows you to view and modify the relationships of the types (classes, interfaces, structures, enumerations, and delegates) in your project. Using this tool, you are able to visually add (or remove) members to (or from) a type and have your modifications reflected in the corresponding C# file. Also, as you modify a given C# file, changes are reflected in the class diagram.

To work with this aspect of Visual Studio 2010, the first step is to insert a new class diagram file. There are many ways to do so, one of which is to click the View Class Diagram button located on Solution Explorer’s right side (see Figure 2-18; be sure your project - not the solution - is the selected item in the window).




Figure 2-18. Inserting a class diagram file

Once you do, you will find class icons that represent the classes in your current project. If you click the arrow icon for a given type, you can show or hide the type’s members (see Figure 2-19).

Note Using the Class Designer toolbar, you can fine-tune the display options of the designer surface.




Figure 2-19. The Class Diagram viewer

This utility works in conjunction with two other aspects of Visual Studio 2010: the Class Details window (activated using the View ➤ Other Windows menu) and the Class Designer Toolbox (activated using the View ➤ Toolbox menu item). The Class Details window not only shows you the details of the currently selected item in the diagram, but also allows you to modify existing members and insert new members on the fly (see Figure 2-20).




Figure 2-20. The Class Details window

The Class Designer Toolbox, which can be activated using the View menu, allows you to insert new types into your project (and create relationships between these types) visually (see Figure 2-21). (Be aware you must have a class diagram as the active window to view this toolbox.) As you do so, the IDE automatically creates new C# type definitions in the background.




Figure 2-21. The Class Designer Toolbox

By way of example, drag a new Class from the Class Designer Toolbox onto your Class Designer. Name this class Car in the resulting dialog box. Now, using the Class Details window, add a public string field named petName (see Figure 2-22).



Figure 2-22. Adding a field with the Class Details window

If you now look at the C# definition of the Car class, you will see it has been updated accordingly (minus the additional code comments).

```
public class Car
{
    // Public data is typically a bad idea; however,
    // it keeps this example simple.
    public string petName;
}
```

Now, activate the designer file once again and drag another new Class onto the designer named SportsCar. Now, select the Inheritance icon from the Class Designer Toolbox and click the top of the SportsCar icon. Next, click the mouse on top of the Car class icon. If you performed these steps correctly, you have just derived the SportsCar class from Car (see Figure 2-23).




Figure 2-23. Visually deriving from an existing class

To complete this example, update the generated `SportsCar` class with a public method named `GetPetName()` authored as follows:

```

public class SportsCar : Car
{
    public string GetPetName()
    {
        petName = "Fred";
        return petName;
    }
}

```

You will make use of these (and other) visual tools of Visual Studio 2010 over the course of this book. However, you should now feel a bit more comfortable regarding the basics of the IDE.

Note The concept of inheritance will be fully examined in Chapter 6.

The Integrated .NET Framework 4.0 SDK Documentation System

The final aspect of Visual Studio 2010 you *must* be comfortable with from the outset is the fully integrated help system. The .NET Framework 4.0 SDK documentation is extremely good, very readable, and full of useful information. Given the huge number of predefined .NET types (which number well into the thousands), you must be willing to roll up your sleeves and dig into the provided documentation. If you resist, you are doomed to a long, frustrating, and painful existence as a .NET developer.

If you have an internet connection, you can view the .NET Framework 4.0 SDK documentation online at the following web address:

<http://msdn.microsoft.com/library>

Of course, if you do not have a live internet connection, this is not very useful. Thankfully, you can install the same help system locally to your computer. Assuming you have already installed Visual Studio 2010, navigate to the All Programs | Microsoft Visual Studio 2010 | Visual Studio Tools folder using your Windows Start button, and select the Manage Help Settings tool. Once you have done so, you can then elect to add the help documentation you are interested in, as seen in Figure 2-24 (if hard drive space allows, I'd recommend adding all possible documentation).



Figure 2-24. The Help Library Manager allows you to download a local copy of the .NET Framework 4.0 SDK Documentation

Note Beginning with .NET 4.0, the help system is viewed via your current web browser, even if you do a local installation of the .NET Framework 4.0 SDK documentation.

Once the local help system is installed, the simplest way to interact with the documentation is to select a C# keyword, type name or member name within the Visual Studio 2010 code window, and press the F1 key. This will automatically open a documentation window for the selected item. For example, select the `string` keyword within your `Car` class definition. Once you press F1, you will see the Help page appear.

Another useful aspect of the documentation is the Search edit box located on the upper left area of the display. Here you can enter in the name of any namespace, type, or member and navigate to the correct location. If you were to try to search for the `System.Reflection` namespace, you would be able to learn about the details of this namespace, examine the contained types, view code examples, and so forth (Figure 2-25)




Figure 2-25. The Search edit box allows you to look up items of interest

Each node in the tree defines the set of types in a given namespace, the members of a given type, and the parameters of a given member. Furthermore, when you view the help page for a given type, you will be told the name of the assembly and namespace that contains the type in question (located at the top of said page). As you read through the remainder of this book, I assume that you will dive into this very, very critical node to read up on additional details of the entity under examination.

Note At the risk of sounding like a broken record, I really can't emphasize enough how important it is that you learn to use the .NET Framework 4.0 SDK documentation. No book, no matter how lengthy, can cover every aspect of the .NET platform. Make sure you take some time to get comfortable using the help system—you'll thank yourself later.

Summary

So as you can see, you have many new toys at your disposal! The point of this chapter was to provide you with a tour of the major programming tools a C# programmer may leverage during the development process. You began the journey by learning how to generate .NET assemblies using nothing other than the free C# compiler and Notepad. Next, you were introduced to the TextPad and Notepad++ applications and walked through the process of using these tools to edit and compile *.cs code files. You also examined three feature-rich IDEs, starting with the open source SharpDevelop, followed by Microsoft's Visual C# 2010 Express and Visual Studio 2010 Professional. While this chapter only scratched the surface of each tool's functionality, you should be in a good position to explore your chosen IDE at your leisure (and remember that you'll see additional features of Visual Studio 2010 as you progress through the book).

PART 2

■ ■ ■

Core C# Programming Constructs



Core C# Programming Constructs, Part I

This chapter begins your formal investigation of the C# programming language by presenting a number of bite-sized, stand-alone topics you must be comfortable with as you explore the .NET Framework. The first order of business is to understand how to build your program's *application object* and the composition of an executable program's entry point: the `Main()` method. Next, you will investigate the fundamental C# data types (and their equivalent types in the `System` namespace) including an examination of the `System.String` and `System.Text.StringBuilder` class types.

Once you know the details of the fundamental .NET data types, you will then examine a number of data type conversion techniques, including narrowing operations, widening operations, and the use of the `checked` and `unchecked` keywords.

This chapter will also examine the role of the C# `var` keyword, which allows you to *implicitly* define a local variable. As you will see later in this book, implicit typing is extremely helpful, if not occasionally mandatory, when working with the LINQ technology set. We wrap up this chapter by quickly examining the core operators, iteration constructs, and decision constructs used to build valid C# code statements.

The Anatomy of a Simple C# Program

C# demands that all program logic be contained within a type definition (recall from Chapter 1 that type is a general term referring to a member of the set {class, interface, structure, enumeration, delegate}). Unlike many other languages, in C# it is not possible to create global functions or global points of data. Rather, all data members and methods must be contained within a type definition. To get the ball rolling, create a new Console Application project named `SimpleCSharpApp`. You might agree that the code within the initial `Program.cs` file is rather uneventful.

```
using System;
using System.Collections.Generic;
using System.Linq;
using System.Text;

namespace SimpleCSharpApp
{
```

```
class Program
{
    static void Main(string[] args)
    {
    }
}
```

Given this, update the `Main()` method of your `Program` class with the following code statements:

```
class Program
{
    static void Main(string[] args)
    {
        // Display a simple message to the user.
        Console.WriteLine("***** My First C# App *****");
        Console.WriteLine("Hello World!");
        Console.WriteLine();

        // Wait for Enter key to be pressed before shutting down.
        Console.ReadLine();
    }
}
```

Here we have a definition for a class type that supports a single method named `Main()`. By default, Visual Studio 2010 names the class defining `Main()` *Program*; however, you are free to change this if you so choose. Every executable C# application (console program, Windows desktop program, or Windows service) must contain a class defining a `Main()` method, which is used to signify the entry point of the application.

Formally speaking, the class that defines the `Main()` method is termed the *application object*. While it is possible for a single executable application to have more than one application object (which can be useful when performing unit tests), you must inform the compiler which `Main()` method should be used as the entry point via the `/main` option of the command-line compiler, or via the Startup Object dropdown list box, located under the Application tab of the Visual Studio 2010 project properties editor (see Chapter 2).

Note that the signature of `Main()` is adorned with the `static` keyword, which will be examined in detail in Chapter 5. For the time being, simply understand that static members are scoped to the class level (rather than the object level) and can thus be invoked without the need to first create a new class instance.

Note C# is a case-sensitive programming language. Therefore, `Main` is not the same as `main`, and `Readline` is not the same as `ReadLine`. Be aware that all C# keywords are lowercase (e.g., `public`, `lock`, `class`, `dynamic`), while namespaces, types, and member names begin (by convention) with an initial capital letter and have capitalized the first letter of any embedded words (e.g., `Console.WriteLine`, `System.Windows.Forms.MessageBox`, `System.Data.SqlClient`). As a rule of thumb, whenever you receive a compiler error regarding “undefined symbols”, be sure to check your spelling!

In addition to the `static` keyword, this `Main()` method has a single parameter, which happens to be an array of strings (`string[] args`). Although you are not currently bothering to process this array, this parameter may contain any number of incoming command-line arguments (you'll see how to access them momentarily). Finally, this `Main()` method has been set up with a `void` return value, meaning we do not explicitly define a return value using the `return` keyword before exiting the method scope.

The logic of `Program` is within `Main()` itself. Here, you make use of the `Console` class, which is defined within the `System` namespace. Among its set of members is the static `WriteLine()` which, as you might assume, sends a text string and carriage return to the standard output. You also make a call to `Console.ReadLine()` to ensure the command prompt launched by the Visual Studio 2010 IDE remains visible during a debugging session until you press the Enter key.

Variations on the Main() Method

By default, Visual Studio 2010 will generate a `Main()` method that has a `void` return value and an array of `string` types as the single input parameter. This is not the only possible form of `Main()`, however. It is permissible to construct your application's entry point using any of the following signatures (assuming it is contained within a C# class or structure definition):

```
// int return type, array of strings as the parameter.
static int Main(string[] args)
{
    // Must return a value before exiting!
    return 0;
}

// No return type, no parameters.
static void Main()
{
}

// int return type, no parameters.
static int Main()
{
    // Must return a value before exiting!
    return 0;
}
```

Note The `Main()` method may also be defined as `public` as opposed to `private`, which is assumed if you do not supply a specific access modifier. Visual Studio 2010 automatically defines a program's `Main()` method as implicitly `private`. Doing so ensures other applications cannot directly invoke the entry point of another.

Obviously, your choice of how to construct `Main()` will be based on two questions. First, do you want to return a value to the system when `Main()` has completed and your program terminates? If so, you need to return an `int` data type rather than `void`. Second, do you need to process any user-supplied,

command-line parameters? If so, they will be stored in the array of strings. Let's examine all of our options in more detail.

Specifying an Application Error Code

While a vast majority of your `Main()` methods will return `void` as the return value, the ability to return an `int` from `Main()` keeps C# consistent with other C-based languages. By convention, returning the value `0` indicates the program has terminated successfully, while another value (such as `-1`) represents an error condition (be aware that the value `0` is automatically returned, even if you construct a `Main()` method prototyped to return `void`).

On the Windows operating system, an application's return value is stored within a system environment variable named `%ERRORLEVEL%`. If you were to create an application that programmatically launches another executable (a topic examined in Chapter 16), you can obtain the value of `%ERRORLEVEL%` using the static `System.Diagnostics.Process.ExitCode` property.

Given that an application's return value is passed to the system at the time the application terminates, it is obviously not possible for an application to obtain and display its final error code while running. However, to illustrate how to view this error level upon program termination, begin by updating the `Main()` method as follows:

```
// Note we are now returning an int, rather than void.
static int Main(string[] args)
{
    // Display a message and wait for Enter key to be pressed.
    Console.WriteLine("***** My First C# App *****");
    Console.WriteLine("Hello World!");
    Console.WriteLine();
    Console.ReadLine();

    // Return an arbitrary error code.
    return -1;
}
```

Now let's capture the return value of `Main()` with the help of a batch file. Using Windows Explorer, navigate to the folder containing your compiled application (for example, `C:\SimpleCSharpApp\bin\Debug`). Add a new text file (named `SimpleCSharpApp.bat`) to the Debug folder that contains the following instructions (if you have not authored *.bat files before, don't concern yourself with the details; this is a test . . . this is only a test):

```
@echo off


rem A batch file for SimpleCSharpApp.exe
rem which captures the app's return value.

SimpleCSharpApp
@if "%ERRORLEVEL%" == "0" goto success

:fail
echo This application has failed!
echo return value = %ERRORLEVEL%
goto end
```

```
:success
echo This application has succeeded!
echo return value = %ERRORLEVEL%
goto end
:end
echo All Done.
```

At this point, open a Visual Studio 2010 command prompt and navigate to the folder containing your executable and new *.bat file. Execute the batch logic by typing its name and pressing the Enter key. You should find the output shown in Figure 3-1, given that your Main() method is returning -1. Had the Main() method returned 0, you would see the message "This application has succeeded!" print to the console.



The screenshot shows a Windows command prompt window titled "Visual Studio 2010 Command Prompt". The command line shows the path "C:\SimpleCSharpApp\bin\Debug>SimpleCSharpApp.bat". The output from the batch file is displayed:
 ***** My First C# App *****
 Hello World!

 This application has failed!
 return value = -1
 All Done.

 C:\SimpleCSharpApp\bin\Debug>

Figure 3-1. Capturing an application's return value via a batch file

Again, a vast majority (if not all) of your C# applications will use void as the return value from Main(), which, as you recall, implicitly returns the error code of zero. To this end, the Main() methods used in this text (beyond the current example) will indeed return void (and the remaining projects will certainly not need to make use of batch files to capture return codes).

Processing Command-Line Arguments

Now that you better understand the return value of the Main() method, let's examine the incoming array of string data. Assume that you now wish to update your application to process any possible command-line parameters. One way to do so is using a C# for loop. (Note that C#'s iteration constructs will be examined in some detail near the end of this chapter.)

```
static int Main(string[] args)
{
...
// Process any incoming args.
for(int i = 0; i < args.Length; i++)
    Console.WriteLine("Arg: {0}", args[i]);

    Console.ReadLine();
    return -1;
}
```

Here you are checking to see whether the array of strings contains some number of items using the `Length` property of `System.Array`. As you'll see in Chapter 4, all C# arrays actually alias the `System.Array` class and therefore share a common set of members. As you loop over each item in the array, its value is printed to the console window. Supplying the arguments at the command line is equally simple, as shown in Figure 3-2.



Figure 3-2. Supplying arguments at the command line

As an alternative to the standard `for` loop, you may iterate over an incoming string array using the C# `foreach` keyword. Here is some sample usage.

```
// Notice you have no need to check the size of the array when using "foreach".
static int Main(string[] args)
{
    ...
    // Process any incoming args using foreach.
    foreach(string arg in args)
        Console.WriteLine("Arg: {0}", arg);

    Console.ReadLine();
    return -1;
}
```

Finally, you are also able to access command-line arguments using the static `GetCommandLineArgs()` method of the `System.Environment` type. The return value of this method is an array of strings. The first index identifies the name of the application itself, while the remaining elements in the array contain the individual command-line arguments. Note that when using this approach, it is no longer necessary to define `Main()` as taking a string array as the input parameter, although there is no harm in doing so.

```
static int Main(string[] args)
{
    ...
    // Get arguments using System.Environment.
    string[] theArgs = Environment.GetCommandLineArgs();
    foreach(string arg in theArgs)
        Console.WriteLine("Arg: {0}", arg);

    Console.ReadLine();
    return -1;
}
```

Of course, it is up to you to determine which command-line arguments your program will respond to (if any) and how they must be formatted (such as with a - or / prefix). Here we simply passed in a series of options that were printed directly to the command prompt. Assume, however, you were creating a new video game and programmed your application to process an option named -godmode. If the user starts your application with the flag, you know he is, in fact, *a cheater* and you can take an appropriate course of action.

Specifying Command-Line Arguments with Visual Studio 2010

In the real world, an end user has the option of supplying command-line arguments when starting a program. However, during the development cycle, you may wish to specify possible command-line flags for testing purposes. To do so with Visual Studio 2010, double-click the Properties icon from Solution Explorer and select the Debug tab on the left side. From there, specify values using the command-line arguments text box (see Figure 3-3).




Figure 3-3. Setting command arguments via Visual Studio 2010

Once you have established such command-line arguments, they will automatically be passed to the Main() method when debugging or running your application within the Visual Studio IDE.

An Interesting Aside: Some Additional Members of the System.Environment Class

The Environment class exposes a number of extremely helpful methods beyond GetCommandLineArgs(). Specifically, this class allows you to obtain a number of details regarding the operating system currently

hosting your .NET application using various static members. To illustrate the usefulness of `System.Environment`, update your `Main()` method to call a helper method named `ShowEnvironmentDetails()`.

```
static int Main(string[] args)
{
    ...
    // Helper method within the Program class.
    ShowEnvironmentDetails();

    Console.ReadLine();
    return -1;
}
```

Implement this method within your `Program` class to call various members of the `Environment` type.

```
static void ShowEnvironmentDetails()
{
    // Print out the drives on this machine,
    // and other interesting details.
    foreach (string drive in Environment.GetLogicalDrives())
        Console.WriteLine("Drive: {0}", drive);

    Console.WriteLine("OS: {0}", Environment.OSVersion);
    Console.WriteLine("Number of processors: {0}",
        Environment.ProcessorCount);
    Console.WriteLine(".NET Version: {0}",
        Environment.Version);
}
```

Figure 3-4 shows a possible test run of invoking this method. If you did not specify command-line arguments via the Visual Studio 2010 Debug tab, you will not find them printed to the console.




Figure 3-4. Displaying system environment variables

The `Environment` type defines members other than those shown in the previous example. Table 3-1 documents some additional properties of interest; however, be sure to check out the .NET Framework 4.0 SDK documentation for full details.

Table 3-1. Select Properties of `System.Environment`

Property	Meaning in Life
<code>ExitCode</code>	Gets or sets the exit code for the application.
<code>MachineName</code>	Gets the name of the current machine.
<code>NewLine</code>	Gets the newline symbol for the current environment.
<code>StackTrace</code>	Gets the current stack trace information for the application.
<code>SystemDirectory</code>	Returns the full path to the system directory.
<code>UserName</code>	Returns the name of the user that started this application.

■ **Source Code** The SimpleCSharpApp project is located under the Chapter 3 subdirectory.

The `System.Console` Class

Almost all of the example applications created over the course of the initial chapters of this book make extensive use of the `System.Console` class. While it is true that a console user interface (CUI) is not as enticing as a graphical user interface (GUI) or web-application, restricting the early examples to console programs will allow us to keep focused on the syntax of C# and the core aspects of the .NET platform, rather than dealing with the complexities of building GUIs or web sites.

As its name implies, the `Console` class encapsulates input, output, and error-stream manipulations for console-based applications. Table 3-2 lists some (but definitely not all) members of interest.

Table 3-2. Select Members of `System.Console`

Member	Meaning in Life
<code>Beep()</code>	This method forces the console to emit a beep of a specified frequency and duration.
<code>BackgroundColor</code> <code>ForegroundColor</code>	These properties set the background/foreground colors for the current output. They may be assigned any member of the <code>ConsoleColor</code> enumeration.

Table 3-2. Select Members of *System.Console* (continued)

Member	Meaning in Life
BufferHeight BufferWidth	These properties control the height/width of the console's buffer area.
Title	This property sets the title of the current console.
WindowHeight WindowWidth WindowTop WindowLeft	These properties control the dimensions of the console in relation to the established buffer.
Clear()	This method clears the established buffer and console display area.

Basic Input and Output with the Console Class

In addition to the members in Table 3-2, the `Console` type defines a set of methods to capture input and output, all of which are static and are therefore called by prefixing the name of the class (`Console`) to the method name. As you have seen, `WriteLine()` pumps a text string (including a carriage return) to the output stream. The `Write()` method pumps text to the output stream without a carriage return. `ReadLine()` allows you to receive information from the input stream up until the Enter key is pressed, while `Read()` is used to capture a single character from the input stream.

To illustrate basic I/O using the `Console` class, create a new `Console Application` project named `BasicConsoleIO` and update your `Main()` method to call a helper method named `GetUserData()`:

```
class Program
{
    static void Main(string[] args)
    {
        Console.WriteLine("***** Basic Console I/O *****");
        GetUserData();
        Console.ReadLine();
    }
}
```

Implement this method within the `Program` class with logic that prompts the user for some bits of information and echoes each item to the standard output stream. For example, we could ask the user for his or her name and age (which we will treat as a text value for simplicity, rather than the expected numerical value) as follows:

```
static void GetUserData()
{
    // Get name and age.
    Console.Write("Please enter your name: ");
    string userName = Console.ReadLine();
    Console.Write("Please enter your age: ");
```

```

string userAge = Console.ReadLine();

// Change echo color, just for fun.
ConsoleColor prevColor = Console.ForegroundColor;
Console.ForegroundColor = ConsoleColor.Yellow;

// Echo to the console.
Console.WriteLine("Hello {0}! You are {1} years old.",
    userName, userAge);

// Restore previous color.
Console.ForegroundColor = prevColor;
}

```

Not surprisingly, when you run this application, the input data is printed to the console (using a custom color to boot!).

Formatting Console Output

During these first few chapters, you may have noticed numerous occurrences of tokens such as {0} and {1} embedded within various string literals. The .NET platform support a style of string formatting slightly akin to the printf() statement of C. Simply put, when you are defining a string literal that contains segments of data whose value is not known until runtime, you are able to specify a placeholder within the literal using this curly-bracket syntax. At runtime, the value(s) passed into `Console.WriteLine()` are substituted for each placeholder.

The first parameter to `WriteLine()` represents a string literal that contains optional place-holders designated by {0}, {1}, {2}, and so forth. Be very aware that the first ordinal number of a curly-bracket placeholder always begins with 0. The remaining parameters to `WriteLine()` are simply the values to be inserted into the respective placeholders.

Note If you have more uniquely numbered curly-bracket placeholders than fill arguments, you will receive a format exception at runtime.

It is also permissible for a given placeholder to repeat within a given string. For example, if you are a Beatles fan and want to build the string "9, Number 9, Number 9", you would write:

```
// John says...
Console.WriteLine("{0}, Number {0}, Number {0}", 9);
```

Also know that it is possible to position each placeholder in any location within a string literal, and it need not follow an increasing sequence. For example, consider the following code snippet:

```
// Prints: 20, 10, 30
Console.WriteLine("{1}, {0}, {2}", 10, 20, 30);
```

Formatting Numerical Data

If you require more elaborate formatting for numerical data, each placeholder can optionally contain various format characters. Table 3-3 shows the most common formatting options.

Table 3-3. .NET Numerical Format Characters

String Format Character	Meaning in Life
C or c	Used to format currency. By default, the flag will prefix the local cultural symbol (a dollar sign [\$] for U.S. English).
D or d	Used to format decimal numbers. This flag may also specify the minimum number of digits used to pad the value.
E or e	Used for exponential notation. Casing controls whether the exponential constant is uppercase (E) or lowercase (e).
F or f	Used for fixed-point formatting. This flag may also specify the minimum number of digits used to pad the value.
G or g	Stands for <i>general</i> . This character can be used to format a number to fixed or exponential format.
N or n	Used for basic numerical formatting (with commas).
X or x	Used for hexadecimal formatting. If you use an uppercase X, your hex format will also contain uppercase characters.

These format characters are suffixed to a given placeholder value using the colon token (e.g., {0:C}, {1:d}, {2:X}). To illustrate, update the Main() method to call a new helper function named FormatNumericalData(). Implement this method in your Program class to format a fixed numerical value in a variety of ways.

```
// Now make use of some format tags.
static void FormatNumericalData()
{
    Console.WriteLine("The value 99999 in various formats:");
    Console.WriteLine("c format: {0:c}", 99999);
    Console.WriteLine("d9 format: {0:d9}", 99999);
    Console.WriteLine("f3 format: {0:f3}", 99999);
    Console.WriteLine("n format: {0:n}", 99999);

    // Notice that upper- or lowercasing for hex
    // determines if letters are upper- or lowercase.
    Console.WriteLine("E format: {0:E}", 99999);
    Console.WriteLine("e format: {0:e}", 99999);
    Console.WriteLine("X format: {0:X}", 99999);
```

```

    Console.WriteLine("x format: {0:x}", 99999);
}

```

Figure 3-5 shows the output for our current application.




Figure 3-5. Basic console I/O (with .NET string formatting)

Beyond controlling how numerical data is formatted, the .NET platform provides additional tokens that may appear in a string literal that controls spacing and positioning of content. Furthermore, the tokens applied to numerical data can be applied to other data types (such as enumerations or the `DateTime` type) to control data formatting. Also, be aware that it is possible to build a custom class (or structure) that defines a custom formatting scheme through the implementation of the `ICustomFormatter` interface.

You'll see additional formatting examples where required throughout this text; however, if you are interested in digging into .NET string formatting further, look up *formatting types* within the .NET Framework 4.0 SDK documentation.

■ **Source Code** The `BasicConsoleIO` project is located under the Chapter 3 subdirectory.

Formatting Numerical Data Beyond Console Applications

On a final note, be aware that the use of the .NET string formatting characters is not limited to console programs. This same formatting syntax can be used when calling the static `string.Format()` method. This can be helpful when you need to compose textual data at runtime for use in any application type (e.g., desktop GUI app, ASP.NET web app, XML web services).

For example, assume you are building a graphical Windows Forms desktop application and need to format a string for display in a message box.

```

static void DisplayMessage()
{

```

```

// Using string.Format() to format a string literal.
string userMessage = string.Format("100000 in hex is {0:x}",
                                    100000);

// You would need to reference System.Windows.Forms.dll
// in order to compile this line of code!
System.Windows.Forms.MessageBox.Show(userMessage);
}

```

Notice how `string.Format()` returns a new `string` object, which is formatted according to the provided flags. After this point, you are free to use the textual data as you see fit.

System Data Types and C# Shorthand Notation

Like any programming language, C# defines an intrinsic set of fundamental data types, which are used to represent local variables, member variables, return values, and parameters. Unlike other programming languages, however, these keywords are much more than simple compiler-recognized tokens. Rather, the C# data type keywords are actually shorthand notations for full-blown types in the `System` namespace. Table 3-4 lists each system data type, its range, the corresponding C# keyword, and the type's compliance with the common language specification (CLS).

Note Recall from Chapter 1 that CLS-compliant .NET code can be used by any managed programming language. If you expose non-CLS-compliant data from your programs, other languages may not be able to make use of it.

Table 3-4. The Intrinsic Data Types of C#

C# Shorthand	CLS Compliant?	System Type	Range	Meaning in Life
<code>bool</code>	Yes	<code>System.Boolean</code>	true or false	Represents truth or falsity
<code>sbyte</code>	No	<code>System.SByte</code>	-128 to 127	Signed 8-bit number
<code>byte</code>	Yes	<code>System.Byte</code>	0 to 255	Unsigned 8-bit number
<code>short</code>	Yes	<code>System.Int16</code>	-32,768 to 32,767	Signed 16-bit number
<code>ushort</code>	No	<code>System.UInt16</code>	0 to 65,535	Unsigned 16-bit number
<code>int</code>	Yes	<code>System.Int32</code>	-2,147,483,648 to 2,147,483,647	Signed 32-bit number
<code>uint</code>	No	<code>System.UInt32</code>	0 to 4,294,967,295	Unsigned 32-bit number

Table 3-4. The Intrinsic Data Types of C# (continued)

C# Shorthand	CLS Compliant?	System Type	Range	Meaning in Life
long	Yes	System.Int64	-9,223,372,036,854,775,808 to 9,223,372,036,854,775,807	Signed 64-bit number
ulong	No	System.UInt64	0 to 18,446,744,073,709,551,615	Unsigned 64-bit number
char	Yes	System.Char	U+0000 to U+ffff	Single 16-bit Unicode character
float	Yes	System.Single	$\pm 1.5 \times 10^{-45}$ to $\pm 3.4 \times 10^{38}$	32-bit floating-point number
double	Yes	System.Double	$\pm 5.0 \times 10^{-324}$ to $\pm 1.7 \times 10^{308}$	64-bit floating-point number
decimal	Yes	System.Decimal	$\pm 1.0 \times 10^{-28}$ to $\pm 7.9 \times 10^{28}$	96-bit signed number
string	Yes	System.String	Limited by system memory	Represents a set of Unicode characters
Object	Yes	System.Object	Can store any data type in an object variable	The base class of all types in the .NET universe

■ **Note** By default, a floating point number is treated as a double. To declare a float variable, use the suffix f or F to the raw numerical value (for example, 5.3F). As well, raw whole numbers default to an int data type. To set the underlying data type to a long, suffix l or L (4L).

Each of the numerical types, such as short or int, map to a corresponding *structure* in the System namespace. Simply put, structures are *value types* allocated on the stack. On the other hand, string and object are *reference types*, meaning the data stored in the variable is allocated on the managed heap. You will examine full details of value and reference types in Chapter 4. For the time being, however, simply understand that value types can be allocated into memory very quickly and have a fixed and predictable lifetime.

Variable Declaration and Initialization

When you are declaring a local variable (e.g., a variable within a member scope), you do so by specifying the data type followed by the variable's name. To begin, create a new Console Application project named `BasicDataTypes`. Update the `Program` class with the following helper method that is called from within `Main()`:

```
static void LocalVarDeclarations()
{
    Console.WriteLine("=> Data Declarations:");
    // Local variables are declared as so:
    // dataType varName;
    int myInt;
    string myString;

    Console.WriteLine();
}
```

Be aware that it is a *compiler error* to make use of a local variable before assigning an initial value. Given this, it is good practice to assign an initial value to your local data points at the time of declaration. You may do so on a single line, or by separating the declaration and assignment into two code statements.

```
static void LocalVarDeclarations()
{
    Console.WriteLine("=> Data Declarations:");
    // Local variables are declared and initialized as follows:
    // dataType varName = initialValue;
    int myInt = 0;

    // You can also declare and assign on two lines.
    string myString;
    myString = "This is my character data";

    Console.WriteLine();
}
```

It is also permissible to declare multiple variables of the same underlying type on a single line of code, as in the following three `bool` variables:

```
static void LocalVarDeclarations()
{
    Console.WriteLine("=> Data Declarations:");
    int myInt = 0;
    string myString;
    myString = "This is my character data";
```

```
// Declare 3 bools on a single line.
bool b1 = true, b2 = false, b3 = b1;
Console.WriteLine();
}
```

Since the C# `bool` keyword is simply a shorthand notation for the `System.Boolean` structure, it is also possible to allocate any data type using its full name (of course, the same point holds true for any C# data type keyword). Here is the final implementation of `LocalVarDeclarations()`.

```
static void LocalVarDeclarations()
{
    Console.WriteLine("=> Data Declarations:");
    // Local variables are declared and initialized as follows:
    // dataType varName = initialValue;
    int myInt = 0;

    string myString;
    myString = "This is my character data";

    // Declare 3 bools on a single line.
    bool b1 = true, b2 = false, b3 = b1;

    // Use System data type to declare a bool.
    System.Boolean b4 = false;

    Console.WriteLine("Your data: {0}, {1}, {2}, {3}, {4}, {5}",
        myInt, myString, b1, b2, b3, b4);

    Console.WriteLine();
}
```

Intrinsic Data Types and the new Operator

All intrinsic data types support what is known as a *default constructor* (see Chapter 5). This feature allows you to create a variable using the `new` keyword, which automatically sets the variable to its default value.

- `bool` variables are set to `false`.
- Numeric data is set to 0 (or 0.0 in the case of floating-point data types).
- `char` variables are set to a single empty character.
- `BigInteger` variables are set to 0.
- `DateTime` variables are set to 1/1/0001 12:00:00 AM.
- Object references (including `strings`) are set to `null`.

■ **Note** The BigInteger data type seen in the previous list is a new .NET 4.0 programming feature, which will be explained in just a bit.

Although it is more cumbersome to use the new keyword when creating a basic data type variable, the following is syntactically well-formed C# code:

```
static void NewingDataTypes()
{
    Console.WriteLine("=> Using new to create variables:");
    bool b = new bool();           // Set to false.
    int i = new int();            // Set to 0.
    double d = new double();      // Set to 0.
    DateTime dt = new DateTime(); // Set to 1/1/0001 12:00:00 AM
    Console.WriteLine("{0}, {1}, {2}, {3}", b, i, d, dt);
    Console.WriteLine();
}
```

The Data Type Class Hierarchy

It is very interesting to note that even the primitive .NET data types are arranged in a *class hierarchy*. If you are new to the world of inheritance, you will discover the full details in Chapter 6. Until then, just understand that types at the top of a class hierarchy provide some default behaviors that are granted to the derived types. The relationship between these core system types can be understood as shown in Figure 3-6.




Figure 3-6. The class hierarchy of system types

Notice that each of these types ultimately derive from `System.Object`, which defines a set of methods (e.g., `ToString()`, `Equals()`, `GetHashCode()`) common to all types in the .NET base class libraries (these methods are fully detailed in Chapter 6).

Also note that many numerical data types derive from a class named `System.ValueType`. Descendents of `ValueType` are automatically allocated on the stack and therefore have a very predictable lifetime and are quite efficient. On the other hand, types that do not have `System.ValueType` in their inheritance chain (such as `System.Type`, `System.String`, `System.Array`, `System.Exception`, and `System.Delegate`) are not allocated on the stack, but on the garbage-collected heap.

Without getting too hung up on the details of `System.Object` and `System.ValueType`, just understand that because a C# keyword (such as `int`) is simply shorthand notation for the corresponding system type (in this case, `System.Int32`), the following is perfectly legal syntax, given that `System.Int32` (the C# `int`) eventually derives from `System.Object` and therefore can invoke any of its public members, as illustrated by this additional helper function:

```
static void ObjectFunctionality()
{
    Console.WriteLine("=> System.Object Functionality:");

    // A C# int is really a shorthand for System.Int32.
    // which inherits the following members from System.Object.
    Console.WriteLine("12.GetHashCode() = {0}", 12.GetHashCode());
    Console.WriteLine("12.Equals(23) = {0}", 12.Equals(23));
    Console.WriteLine("12.ToString() = {0}", 12.ToString());
    Console.WriteLine("12.GetType() = {0}", 12.GetType());
    Console.WriteLine();
}
```

If you were to call this method from within `Main()`, you would find the output shown in Figure 3-7.




Figure 3-7. All types (even numerical data) extend `System.Object`

Members of Numerical Data Types

To continue experimenting with the intrinsic C# data types, understand that the numerical types of .NET support `MaxValue` and `MinValue` properties that provide information regarding the range a given type can store. In addition to the `MinValue/MaxValue` properties, a given numerical system type may define further useful members. For example, the `System.Double` type allows you to obtain the values for epsilon and infinity (which may be of interest to those of you with a mathematical flare). To illustrate, consider the following helper function:

```
static void DataTypeFunctionality()
{
    Console.WriteLine("=> Data type Functionality:");

    Console.WriteLine("Max of int: {0}", int.MaxValue);
    Console.WriteLine("Min of int: {0}", int.MinValue);
```

```

        Console.WriteLine("Max of double: {0}", double.MaxValue);
        Console.WriteLine("Min of double: {0}", double.MinValue);
        Console.WriteLine("double.Epsilon: {0}", double.Epsilon);
        Console.WriteLine("double.PositiveInfinity: {0}",
            double.PositiveInfinity);
        Console.WriteLine("double.NegativeInfinity: {0}",
            double.NegativeInfinity);
        Console.WriteLine();
    }
}

```

Members of System.Boolean

Next, consider the `System.Boolean` data type. The only valid assignment a C# `bool` can take is from the set `{true | false}`. Given this point, it should be clear that `System.Boolean` does not support a `MinValue/MaxValue` property set, but rather `TrueString/FalseString` (which yields the string "True" or "False", respectively). Add the following code statements to the `DataTypeFunctionality()` helper method:

```

Console.WriteLine("bool.FalseString: {0}", bool.FalseString);
Console.WriteLine("bool.TrueString: {0}", bool.TrueString);

```

Figure 3-8 shows the output of invoking `DataTypeFunctionality()` from within `Main()`.




Figure 3-8. Select functionality of various data types

Members of System.Char

C# textual data is represented by the `string` and `char` keywords, which are simple shorthand notations for `System.String` and `System.Char`, both of which are Unicode under the hood. As you may already know, a `string` represents a contiguous set of characters (e.g., "Hello"), while the `char` can represent a single slot in a `string` (e.g., 'H').

The `System.Char` type provides you with a great deal of functionality beyond the ability to hold a single point of character data. Using the static methods of `System.Char`, you are able to determine

whether a given character is numerical, alphabetical, a point of punctuation, or whatnot. Consider the following method:

```
static void CharFunctionality()
{
    Console.WriteLine("=> char type Functionality:");

    char myChar = 'a';
    Console.WriteLine("char.IsDigit('a'): {0}", char.IsDigit(myChar));
    Console.WriteLine("char.IsLetter('a'): {0}", char.IsLetter(myChar));
    Console.WriteLine("char.IsWhiteSpace('Hello There', 5): {0}",
        char.IsWhiteSpace("Hello There", 5));
    Console.WriteLine("char.IsWhiteSpace('Hello There', 6): {0}",
        char.IsWhiteSpace("Hello There", 6));
    Console.WriteLine("char.IsPunctuation('?'): {0}",
        char.IsPunctuation('?'));
    Console.WriteLine();
}
```

As illustrated in the previous code snippet, many members of `System.Char` have two calling conventions: a single character or a string with a numerical index that specifies the position of the character to test.

Parsing Values from String Data

The .NET data types provide the ability to generate a variable of their underlying type given a textual equivalent (e.g., parsing). This technique can be extremely helpful when you wish to convert a bit of user input data (such as a selection from a GUI-based, drop-down list box) into a numerical value. Consider the following parsing logic within a method named `ParseFromStrings()`:

```
static void ParseFromStrings()
{
    Console.WriteLine("=> Data type parsing:");

    bool b = bool.Parse("True");
    Console.WriteLine("Value of b: {0}", b);
    double d = double.Parse("99.884");
    Console.WriteLine("Value of d: {0}", d);
    int i = int.Parse("8");
    Console.WriteLine("Value of i: {0}", i);
    char c = Char.Parse("w");
    Console.WriteLine("Value of c: {0}", c);
    Console.WriteLine();
}
```

System.DateTime and System.TimeSpan

The `System` namespace defines a few useful data types for which there is no C# keyword, such as the `DateTime` and `TimeSpan` structures (I'll leave the investigation of `System.Guid` and `System.Void`, as shown in Figure 3-6, to interested readers).

The `DateTime` type contains data that represents a specific date (month, day, year) and time value, both of which may be formatted in a variety of ways using the supplied members. The `TimeSpan` structure allows you to easily define and transform units of time using various members.

```
static void UseDatesAndTimes()
{
    Console.WriteLine("=> Dates and Times:");

    // This constructor takes (year, month, day)
    DateTime dt = new DateTime(2010, 10, 17);

    // What day of the month is this?
    Console.WriteLine("The day of {0} is {1}", dt.Date, dt.DayOfWeek);

    // Month is now December.
    dt = dt.AddMonths(2);
    Console.WriteLine("Daylight savings: {0}", dt.IsDaylightSavingTime());

    // This constructor takes (hours, minutes, seconds)
    TimeSpan ts = new TimeSpan(4, 30, 0);
    Console.WriteLine(ts);

    // Subtract 15 minutes from the current TimeSpan and
    // print the result.
    Console.WriteLine(ts.Subtract(new TimeSpan(0, 15, 0)));
}
```

The .NET 4.0 System.Numerics Namespace

.NET 4.0 introduces a new namespace named `System.Numerics`, which defines a structure named `BigInteger`. As its name implies, the `BigInteger` data type can be used when you need to represent humongous numerical values (sadly, such as the national debt of the United States), which are not constrained by a fixed upper or lower limit.

Note The `System.Numerics` namespace defines a second structure named `Complex`, which allows you to model mathematically complex numerical data (e.g., imaginary data, real data, hyperbolic tangents). Consult the .NET Framework 4.0 SDK documentation if you are interested.

While many of your .NET applications may never need to make use of the `BigInteger` structure, if you do find the need to define a massive numerical value, your first step is to reference the

System.Numerics.dll assembly into your project. If you wish to follow along with the current example, perform the following tasks:

1. Select the Project | Add Reference... menu option of Visual Studio.
 2. Select the .NET tab from the resulting dialog box.
 3. Locate and select the System.Numerics assembly within the list of presented libraries.
 4. Press the OK button.

Once you have done so, add the following using directive to the file, which will be using the BigInteger data type:

```
// BigInteger lives here!
using System.Numerics;
```

At this point, you can create a `BigInteger` variable using the new operator. Within the constructor you can specify a numerical value, including floating point data. However, recall that when you define a literal whole number (such as 500), the runtime will default the data type to an `int`. Likewise, literal floating point data (such as 55.333) will default to a `double`. How, then, can you set `BigInteger` to a massive value while not overflowing the default data types used for raw numerical values?

The simplest approach is to establish the massive numerical value as a text literal, which can be converted into a `BigInteger` variable via the static `Parse()` method. If required, you can also pass in a byte array directly to the constructor of the `BigInteger` class.

Note Once you assign a value to a BigInteger variable, you cannot change it, as the data is immutable. However, the BigInteger class defines a number of members that will return new BigInteger objects based on your data modifications (such as the static Multiply() method used in the proceeding code sample).

In any case, once you have defined a `BigInteger` variable, you will find this class defines very similar members as other intrinsic C# data types (e.g., `float`, `int`). In addition, the `BigInteger` class defines several static members that allow you to apply basic mathematical expressions (such as adding and multiplying) to `BigInteger` variables. Here is an example of working with the `BigInteger` class.

It is also important to note that the `BigInteger` data type responds to C#'s intrinsic mathematical operators, such as `+`, `-`, and `*`. Therefore, rather than calling `BigInteger.Multiply()` to multiply two huge numbers, you could author the following code:

```
BigInteger reallyBig2 = biggy * reallyBig;
```

At this point, I hope you understand that the C# keywords representing basic data types have a corresponding type in the .NET base class libraries, each of which exposes a fixed functionality. While I have not detailed each member of these data types, you are in a great position to dig into the details as you see fit. Be sure to consult the .NET Framework 4.0 SDK documentation for full details regarding the various .NET data types.

Source Code The BasicDataTypes project is located under the Chapter 3 subdirectory.

Working with String Data

`System.String` provides a number of methods you would expect from such a utility class, including methods that return the length of the character data, find substrings within the current string, and convert to and from uppercase/lowercase. Table 3-5 lists some (but by no means all) of the interesting members.

Table 3-5. Select Members of `System.String`

String Member	Meaning in Life
<code>Length</code>	This property returns the length of the current string.
<code>Compare()</code>	This static method compares two strings.
<code>Contains()</code>	This method determines whether a string contains a specific substring.
<code>Equals()</code>	This method tests whether two string objects contain identical character data.
<code>Format()</code>	This static method formats a string using other primitives (e.g., numerical data, other strings) and the <code>{0}</code> notation examined earlier in this chapter.
<code>Insert()</code>	This method inserts a string within a given string.
<code>PadLeft()</code> <code>PadRight()</code>	These methods are used to pad a string with some characters.

Table 3-5. Select Members of System.String (continued)

String Member	Meaning in Life
Remove() Replace()	Use these methods to receive a copy of a string with modifications (characters removed or replaced).
Split()	This method returns a String array containing the substrings in this instance that are delimited by elements of a specified char array or string array.
Trim()	This method removes all occurrences of a set of specified characters from the beginning and end of the current string.
ToUpper() ToLower()	These methods create a copy of the current string in uppercase or lowercase format, respectively.

Basic String Manipulation

Working with the members of System.String is as you would expect. Simply declare a `string` variable and make use of the provided functionality via the dot operator. Be aware that a few of the members of System.String are static members and are, therefore, called at the class (rather than the object) level. Assume you have created a new Console Application project named FunWithStrings. Author the following method, which should be called from within `Main()`:

```
static void BasicStringFunctionality()
{
    Console.WriteLine("=> Basic String functionality:");
    string firstName = "Freddy";
    Console.WriteLine("Value of firstName: {0}", firstName);
    Console.WriteLine("firstName has {0} characters.", firstName.Length);
    Console.WriteLine("firstName in uppercase: {0}", firstName.ToUpper());
    Console.WriteLine("firstName in lowercase: {0}", firstName.ToLower());
    Console.WriteLine("firstName contains the letter y?: {0}",
        firstName.Contains("y"));
    Console.WriteLine("firstName after replace: {0}", firstName.Replace("dy", ""));
    Console.WriteLine();
}
```

Not too much to say here, as this method simply invokes various members, such as `ToUpper()` and `Contains()`, on a local `string` variable to yield various formats and transformations. Figure 3-9 shows the initial output.




Figure 3-9. Basic string manipulation

While this output may not seem too surprising, the output seen via calling the `Replace()` method is a tad bit misleading. In reality, the `firstName` variable has not changed at all; rather, we receive back a new string in a modified format. We will revisit the immutable nature of strings in just a few moments.

String Concatenation

string variables can be connected together to build larger strings via the C# + operator. As you may know, this technique is formally termed *string concatenation*. Consider the following new helper function:

```
static void StringConcatenation()
{
    Console.WriteLine("=> String concatenation:");
    string s1 = "Programming the ";
    string s2 = "PsychoDrill (PTP)";
    string s3 = s1 + s2;
    Console.WriteLine(s3);
    Console.WriteLine();
}
```

You may be interested to know that the C# + symbol is processed by the compiler to emit a call to the static `String.Concat()` method. In fact, if you were to compile the previous code and open the assembly within `ildasm.exe` (see Chapter 1), you would find the common intermediate language (CIL) code shown in Figure 3-10.




Figure 3-10. The C# + operator results in a call to String.Concat()

Given this, it is possible to perform string concatenation by calling `String.Concat()` directly (although you really have not gained anything by doing so—in fact, you have incurred additional keystrokes!).

```
static void StringConcatenation()
{
    Console.WriteLine("=> String concatenation:");
    string s1 = "Programming the ";
    string s2 = "PsychoDrill (PTP)";
    string s3 = String.Concat(s1, s2);
    Console.WriteLine(s3);
    Console.WriteLine();
}
```

Escape Characters

As in other C-based languages, C# string literals may contain various *escape characters*, which qualify how the character data should be printed to the output stream. Each escape character begins with a backslash, followed by a specific token. In case you are a bit rusty on the meanings behind these escape characters, Table 3-6 lists the more common options.

Table 3-6. String Literal Escape Characters

Character	Meaning in Life
\'	Inserts a single quote into a string literal.
\"	Inserts a double quote into a string literal.
\\\	Inserts a backslash into a string literal. This can be quite helpful when defining file or network paths.
\a	Triggers a system alert (beep). For console programs, this can be an audio clue to the user.

Table 3-6. String Literal Escape Characters (continued)

Character	Meaning in Life
\n	Inserts a new line (on Windows platforms).
\r	Inserts a carriage return.
\t	Inserts a horizontal tab into the string literal.

For example, to print a string that contains a tab between each word, you can make use of the \t escape character. Or assume you wish to create a string literal that contains quotation marks, another that defines a directory path, and a final string literal that inserts three blank lines after printing the character data. To do so without compiler errors, you would need to make use of the \"", \\, and \\n escape characters. Also, to annoy any person within a 10-foot radius from you, notice that I have embedded an alarm within each string literal (to trigger a beep). Consider the following:

```
static void EscapeChars()
{
    Console.WriteLine("=> Escape characters:\a");
    string strWithTabs = "Model\tColor\tSpeed\tPet Name\a ";
    Console.WriteLine(strWithTabs);

    Console.WriteLine("Everyone loves \"Hello World\"\a ");
    Console.WriteLine("C:\\MyApp\\bin\\Debug\a ");

    // Adds a total of 4 blank lines (then beep again!).
    Console.WriteLine("All finished.\n\n\n\a ");
    Console.WriteLine();
}
```

Defining Verbatim Strings

When you prefix a string literal with the @ symbol, you have created what is termed a *verbatim string*. Using verbatim strings, you disable the processing of a literal's escape characters and print out a string as is. This can be most useful when working with strings representing directory and network paths. Therefore, rather than making use of \\ escape characters, you can simply write the following:

```
// The following string is printed verbatim
// thus, all escape characters are displayed.
Console.WriteLine(@"C:\\MyApp\\bin\\Debug");
```

Also note that verbatim strings can be used to preserve white space for strings that flow over multiple lines.

```
// White space is preserved with verbatim strings.
string myLongString = @"This is a very
very
```

```
    very
        long string";
Console.WriteLine(myLongString);
```

Using verbatim strings, you can also directly insert a double quote into a literal string by doubling the " token.

```
Console.WriteLine(@"Cerebus said ""Darrr! Pret-ty sun-sets""");
```

Strings and Equality

As fully explained in Chapter 4, a *reference type* is an object allocated on the garbage-collected managed heap. By default, when you perform a test for equality on reference types (via the C# == and != operators), you will be returned true if the references are pointing to the same object in memory. However, even though the `string` data type is indeed a reference type, the equality operators have been redefined to compare the *values* of `string` objects, not the object in memory to which they refer.

```
static void StringEquality()
{
    Console.WriteLine("=> String equality:");
    string s1 = "Hello!";
    string s2 = "Yo!";
    Console.WriteLine("s1 = {0}", s1);
    Console.WriteLine("s2 = {0}", s2);
    Console.WriteLine();

    // Test these strings for equality.
    Console.WriteLine("s1 == s2: {0}", s1 == s2);
    Console.WriteLine("s1 == Hello!: {0}", s1 == "Hello!");
    Console.WriteLine("s1 == HELLO!: {0}", s1 == "HELLO!");
    Console.WriteLine("s1 == hello!: {0}", s1 == "hello!");
    Console.WriteLine("s1.Equals(s2): {0}", s1.Equals(s2));
    Console.WriteLine("Yo.Equals(s2): {0}", "Yo!".Equals(s2));
    Console.WriteLine();
}
```

The C# equality operators perform a case-sensitive, character-by-character equality test on `string` objects. Therefore, "Hello!" is not equal to "HELLO!", which is different from "hello!". Also, keeping the connection between `string` and `System.String` in mind, notice that we are able to test for equality using the `Equals()` method of `String` as well as the baked-in equality operators. Finally, given that every `string` literal (such as "Yo") is a valid `System.String` instance, we are able to access `string`-centric functionality from a fixed sequence of characters.

Strings Are Immutable

One of the interesting aspects of `System.String` is that once you assign a `string` object with its initial value, the character data *cannot be changed*. At first glance, this might seem like a flat-out lie, given that we are always reassigning strings to new values and because the `System.String` type defines a number of methods that appear to modify the character data in one way or another (such as uppercasing and

lowercasing). However, if you look more closely at what is happening behind the scenes, you will notice the methods of the `string` type are, in fact, returning you a brand-new `string` object in a modified format.

```
static void StringsAreImmutable()
{
    // Set initial string value.
    string s1 = "This is my string.";
    Console.WriteLine("s1 = {0}", s1);

    // Uppercase s1?
    string upperString = s1.ToUpper();
    Console.WriteLine("upperString = {0}", upperString);

    // Nope! s1 is in the same format!
    Console.WriteLine("s1 = {0}", s1);
}
```

If you examine the relevant output in Figure 3-11, you can verify that the original `string` object (`s1`) is not uppercased when calling `ToUpper()`, rather you are returned a *copy* of the `string` in a modified format.




Figure 3-11. Strings are immutable

The same law of immutability holds true when you use the C# assignment operator. To illustrate, comment out (or delete) any existing code within `StringsAreImmutable()` (to decrease the amount of generated CIL code) and add the following code statements:

```
static void StringAreImmutable()
{
    string s2 = "My other string";
    s2 = "New string value";
}
```

Now, compile your application and load the assembly into `ildasm.exe` (again, see Chapter 1). Figure 3-12 shows what you would find if you were to generate CIL code for the `StringAreImmutable()` method.




Figure 3-12. Assigning a value to a string object results in a new string object

Although we have yet to examine the low-level details of the CIL, note the numerous calls to the `ldstr` (load string) opcode. Simply put, the `ldstr` opcode of the CIL loads a new string object on the managed heap. The previous `string` object that contained the value `"My other string."` will eventually be garbage collected.

So, what exactly are we to gather from this insight? In a nutshell, the `string` class can be inefficient and result in bloated code if misused, especially when performing string concatenation. If you need to represent basic character data such as a U.S. Social Security number, first or last names, or simple bits of text used within your application, the `string` class is the perfect choice.

However, if you are building an application that makes heavy use of textual data (such as a word processing program), it would be a very bad idea to represent the word processing data using `string` objects, as you will most certainly (and often indirectly) end up making unnecessary copies of string data. So what is a programmer to do? Glad you asked.

The `System.Text.StringBuilder` Type

Given that the `string` type can be inefficient when used with reckless abandon, the .NET base class libraries provide the `System.Text` namespace. Within this (relatively small) namespace lives a class named `StringBuilder`. Like the `System.String` class, the `StringBuilder` defines methods that allow you to replace or format segments, for example. When you wish to use this type in your C# code files, your first step is to make sure the following namespace is imported into your code file:

```
// StringBuilder lives here!
using System.Text;
```

What is unique about the `StringBuilder` is that when you call members of this type, you are directly modifying the object's internal character data (making it more efficient), not obtaining a copy of the data in a modified format. When you create an instance of the `StringBuilder`, you can supply the object's initial startup values via one of many *constructors*. If you are new to the topic of constructors, simply understand that constructors allow you to create an object with an initial state when you apply the `new` keyword. Consider the following usage of `StringBuilder`:

```

static void FunWithStringBuilder()
{
    Console.WriteLine("=> Using the StringBuilder:");
    StringBuilder sb = new StringBuilder("**** Fantastic Games ****");
    sb.Append("\n");
    sb.AppendLine("Half Life");
    sb.AppendLine("Beyond Good and Evil");
    sb.AppendLine("Deus Ex 2");
    sb.AppendLine("System Shock");
    Console.WriteLine(sb.ToString());

    sb.Replace("2", "Invisible War");
    Console.WriteLine(sb.ToString());
    Console.WriteLine("sb has {0} chars.", sb.Length);
    Console.WriteLine();
}

```

Here we have constructed a `StringBuilder` set to the initial value "**** Fantastic Games ****". As you can see, we are appending to the internal buffer and are able to replace or remove characters at will. By default, a `StringBuilder` is only able to initially hold a string of 16 characters or fewer (but will expand automatically if necessary); however, this default starting value can be changed via an additional constructor argument.

```

// Make a StringBuilder with an initial size of 256.
StringBuilder sb = new StringBuilder("**** Fantastic Games ****", 256);

```

If you append more characters than the specified limit, the `StringBuilder` object will copy its data into a new instance and grow the buffer by the specified limit. Figure 3-13 shows the output of the current helper function.

```

***** Fun with Strings *****
=> Using the StringBuilder:
**** Fantastic Games ****
Half Life
Beyond Good and Evil
Deus Ex 2
System Shock

**** Fantastic Games ****
Half Life
Beyond Good and Evil
Deus Ex Invisible War
System Shock

sb as 96 chars.

```

Figure 3-13. The `StringBuilder` is more efficient than `string`

■ **Source Code** The FunWithStrings project is located under the Chapter 3 subdirectory.

Narrowing and Widening Data Type Conversions

Now that you understand how to interact with intrinsic C# data types, let's examine the related topic of *data type conversion*. Assume you have a new Console Application project named TypeConversions that defines the following class:

```
class Program
{
    static void Main(string[] args)
    {
        Console.WriteLine("***** Fun with type conversions *****");

        // Add two shorts and print the result.
        short numb1 = 9, numb2 = 10;
        Console.WriteLine("{0} + {1} = {2}",
            numb1, numb2, Add(numb1, numb2));
        Console.ReadLine();
    }

    static int Add(int x, int y)
    {
        return x + y;
    }
}
```

Notice that the `Add()` method expects to be sent two `int` parameters. However, the `Main()` method is, in fact, sending in two `short` variables. While this might seem like a complete and total mismatch of data types, the program compiles and executes without error, returning the expected result of 19.

The reason the compiler treats this code as syntactically sound is due to the fact that there is no possibility for loss of data. Given that the maximum value of a `short` (32,767) is well within the range of an `int` (2,147,483,647), the compiler implicitly *widens* each `short` to an `int`. Formally speaking, *widening* is the term used to define an implicit *upward cast* that does not result in a loss of data.

■ **Note** Look up *Type Conversion Tables* in the .NET Framework 4.0 SDK documentation if you wish to see permissible widening (and narrowing, see below) conversions for each C# data type.

Although this implicit widening worked in our favor for the previous example, other times this “feature” can be the source of compile-time errors. For example, assume that you have set values to `numb1` and `numb2` that (when added together) overflow the maximum value of a `short`. Also, assume you are storing the return value of the `Add()` method within a new local `short` variable, rather than directly printing the result to the console.

```
static void Main(string[] args)
```

```
{
    Console.WriteLine("***** Fun with type conversions *****");

    // Compiler error below!
    short numb1 = 30000, numb2 = 30000;
    short answer = Add(numb1, numb2);

    Console.WriteLine("{0} + {1} = {2}",
        numb1, numb2, answer);
    Console.ReadLine();
}
```

In this case, the compiler reports the following error:

```
Cannot implicitly convert type 'int' to 'short'. An explicit conversion exists (are you
missing a cast?)
```

The problem is that although the `Add()` method is capable of returning an `int` with the value 60,000 (as this fits within the range of a `System.Int32`), the value cannot be stored in a `short`, as it overflows the bounds of this data type. Formally speaking, the CLR was unable to apply a *narrowing operation*. As you can guess, narrowing is the logical opposite of widening, in that a larger value is stored within a smaller data type variable.

It is important to point out that all narrowing conversions result in a compiler error, even when you can reason that the narrowing conversion should indeed succeed. For example, the following code also results in a compiler error:

```
// Another compiler error!
static void NarrowingAttempt()
{
    byte myByte = 0;
    int myInt = 200;
    myByte = myInt;

    Console.WriteLine("Value of myByte: {0}", myByte);
}
```

Here, the value contained within the `int` variable (`myInt`) is safely within the range of a `byte`; therefore, you would expect the narrowing operation to not result in a runtime error. However, given that C# is a language built with type safety in mind, we do indeed receive a compiler error.

When you wish to inform the compiler that you are willing to deal with a possible loss of data due to a narrowing operation, you must apply an *explicit cast* using the C# casting operator `()`. Consider the following update to the `Program` type and resulting output in Figure 3-14.

```
class Program
{
    static void Main(string[] args)
    {
        Console.WriteLine("***** Fun with type conversions *****");
        short numb1 = 30000, numb2 = 30000;
```

```

// Explicitly cast the int into a short (and allow loss of data).
short answer = (short)Add(numb1, numb2);

Console.WriteLine("{0} + {1} = {2}",
    numb1, numb2, answer);
NarrowingAttempt();
Console.ReadLine();
}

static int Add(int x, int y)
{ return x + y; }

static void NarrowingAttempt()
{
    byte myByte = 0;
    int myInt = 200;

    // Explicitly cast the int into a byte (no loss of data).
    myByte = (byte)myInt;
    Console.WriteLine("Value of myByte: {0}", myByte);
}
}

```




Figure 3-14. OOPS! We lost some data when adding our numbers!

Trapping Narrowing Data Conversions

As you have just witnessed, an explicit cast allows you to force the compiler to apply a narrowing conversion, even when doing so may result in a loss of data. In the case of the `NarrowingAttempt()` method, this was not a problem, as the value 200 can fit snuggly within the range of a byte. However, in the case of adding the two shorts within `Main()`, the end result is completely unacceptable ($30,000 + 30,000 = -5536$?). If you are building an application where loss of data is always unacceptable, C# provides the `checked` and `unchecked` keywords to ensure data loss does not escape undetected.

To illustrate the use of these keywords, assume you have a new method within `Program` that attempts to add two bytes, each of which has been assigned a value that is safely below the maximum (255). If you were to add the values of these types (casting the returned `int` to a `byte`), you would assume that the result would be the exact sum of each member.

```

static void ProcessBytes()
{
    byte b1 = 100;

```

```

byte b2 = 250;
byte sum = (byte)Add(b1, b2);

// sum should hold the value 350. However, we find the value 94!
Console.WriteLine("sum = {0}", sum);
}

```

If you were to view the output of this application, you might be surprised to find that `sum` contains the value 94 (rather than the expected 350). The reason is simple. Given that a `System.Byte` can hold a value only between 0 and 255 (inclusive, for a grand total of 256 slots), `sum` now contains the overflow value ($350 - 256 = 94$). By default, if you take no corrective course of action, overflow/under-flow conditions occur without error.

To handle overflow or underflow conditions in your application, you have two options. Your first choice is to leverage your wits and programming skills to handle all overflow/underflow conditions manually. Of course, the problem with this technique is the simple fact that you are human, and even your best attempts may result in errors that have escaped your eyes.

Thankfully, C# provides the `checked` keyword. When you wrap a statement (or a block of statements) within the scope of the `checked` keyword, the C# compiler emits additional CIL instructions that test for overflow conditions that may result when adding, multiplying, subtracting, or dividing two numerical data types.

If an overflow has occurred, you will receive a runtime exception: `System.OverflowException`. Chapter 7 will examine all the details of structured exception handling and the use of the `try` and `catch` keywords. Without getting too hung up on the specifics at this point, observe the following update:

```

static void ProcessBytes()
{
    byte b1 = 100;
    byte b2 = 250;

    // This time, tell the compiler to add CIL code
    // to throw an exception if overflow/underflow
    // takes place.
    try
    {
        byte sum = checked((byte)Add(b1, b2));
        Console.WriteLine("sum = {0}", sum);
    }
    catch (OverflowException ex)
    {
        Console.WriteLine(ex.Message);
    }
}

```

Notice that the return value of `Add()` has been wrapped within the scope of the `checked` keyword. Since the sum is greater than a `byte`, we trigger a runtime exception. Notice the error message printed out via the `Message` property in Figure 3-15.




Figure 3-15. The checked keyword forces runtime exceptions to be thrown when data loss occurs

If you wish to force overflow checking to occur over a block of code statements, you can do so by defining a checked scope as follows:

```
try
{
    checked
    {
        byte sum = (byte)Add(b1, b2);
        Console.WriteLine("sum = {0}", sum);
    }
}
catch (OverflowException ex)
{
    Console.WriteLine(ex.Message);
}
```

In either case, the code in question will be evaluated for possible overflow conditions automatically, which will trigger an overflow exception if encountered.

Setting Project-wide Overflow Checking

If you are creating an application that should never allow silent overflow to occur, you may find yourself in the annoying position of wrapping numerous lines of code within the scope of the checked keyword. As an alternative, the C# compiler supports the /checked flag. When enabled, all of your arithmetic will be evaluated for overflow without the need to make use of the C# checked keyword. If overflow has been discovered, you will still receive a runtime exception.

To enable this flag using Visual Studio 2010, open your project's property page and click the Advanced button on the Build tab. From the resulting dialog box, select the Check for arithmetic overflow/underflow check box (see Figure 3-16).




Figure 3-16. Enabling project-wide overflow/underflow data checking

Enabling this setting can be very helpful when you’re creating a debug build. Once all of the overflow exceptions have been squashed out of the code base, you’re free to disable the /checked flag for subsequent builds (which will increase the runtime performance of your application).

The unchecked Keyword

Now, assuming you have enabled this project-wide setting, what are you to do if you have a block of code where data loss *is* acceptable? Given that the /checked flag will evaluate all arithmetic logic, C# provides the unchecked keyword to disable the throwing of an overflow exception on a case-by-case basis. This keyword’s use is identical to that of the checked keyword in that you can specify a single statement or a block of statements.

```
// Assuming /checked is enabled,
// this block will not trigger
// a runtime exception.
unchecked
{
    byte sum = (byte)(b1 + b2);
    Console.WriteLine("sum = {0} ", sum);
}
```

So, to summarize the C# checked and unchecked keywords, remember that the default behavior of the .NET runtime is to ignore arithmetic overflow/underflow. When you want to selectively handle discrete statements, make use of the checked keyword. If you wish to trap overflow errors throughout your application, enable the /checked flag. Finally, the unchecked keyword may be used if you have a block of code where overflow is acceptable (and thus should not trigger a runtime exception).

The Role of System.Convert

To wrap up the topic of data type conversions, I'd like to point out the fact that the `System` namespace defines a class named `Convert` that can also be used to widen or narrow data.

```
static void NarrowWithConvert()
{
    byte myByte = 0;
    int myInt = 200;
    myByte = Convert.ToByte(myInt);
    Console.WriteLine("Value of myByte: {0}", myByte);
}
```

One benefit of using `System.Convert` is that it provides a language-neutral manner to convert between data types (for example, the Visual Basic language syntax for casting is completely different from the C# language syntax). However, given that C# provides an explicit conversion operator, using the `Convert` type to do your data type conversions is usually nothing more than a matter of personal preference.

Source Code The `TypeConversions` project is located under the Chapter 3 subdirectory.

Understanding Implicitly Typed Local Variables

Up until this point in the chapter, when we have been defining local variables, we've *explicitly* specified the underlying data type of said variable.

```
static void DeclareExplicitVars()
{
    // Explicitly typed local variables
    // are declared as follows:
    // dataType variableName = initialValue;
    int myInt = 0;
    bool myBool = true;
    string myString = "Time, marches on...";
}
```

While it is always good practice to explicitly specify the data type of each variable, the C# language does provide for *implicitly typing* of local variables using the `var` keyword. The `var` keyword can be used in place of specifying a specific data type (such as `int`, `bool`, or `string`). When you do so, the compiler will automatically infer the underlying data type based on the initial value used to initialize the local data point.

To illustrate the role of implicit typing, create a new Console Application project named `ImplicitlyTypedLocalVars`. Notice how the local variables within the previous method can now be declared as follows:

```
static void DeclareImplicitVars()
```

```
{
    // Implicitly typed local variables
    // are declared as follows:
    // var variableName = initialValue;
    var myInt = 0;
    var myBool = true;
    var myString = "Time, marches on...";
}
```

Note Strictly speaking, `var` is not a C# keyword. It is permissible to declare variables, parameters, and fields named “`var`” without compile-time errors. However, when the `var` token is used as a data type, it is contextually treated as a keyword by the compiler. For simplicity, I will use the term “`var` keyword,” rather than the more cumbersome “contextual `var` token.”

In this case, the compiler is able to infer, given the initially assigned value, that `myInt` is, in fact, a `System.Int32`, `myBool` is a `System.Boolean`, and `myString` is indeed of type `System.String`. You can verify this by printing out the type name via *reflection*. As you will see in much more detail in Chapter 15, reflection is the act of determining the composition of a type at runtime. For example, using reflection, you can determine the data type of an implicitly typed local variable. Update your method with the following code statements:

```
static void DeclareImplicitVars()
{
    // Implicitly typed local variables.
    var myInt = 0;
    var myBool = true;
    var myString = "Time, marches on...";

    // Print out the underlying type.
    Console.WriteLine("myInt is a: {0}", myInt.GetType().Name);
    Console.WriteLine("myBool is a: {0}", myBool.GetType().Name);
    Console.WriteLine("myString is a: {0}", myString.GetType().Name);
}
```

Note Be aware that you can use this implicit typing for any type including arrays, generic types (see Chapter 10), and your own custom types. You’ll see other examples of implicit typing over the course of this book.

If you were to call the `DeclareImplicitVars()` method from within `Main()`, you’d find the output shown in Figure 3-17.




Figure 3-17. Reflecting over implicitly defined local variables

Restrictions on Implicitly Typed Variables

There are, of course, various restrictions regarding the use of the `var` keyword. First and foremost, implicit typing applies *only* to local variables in a method or property scope. It is illegal to use the `var` keyword to define return values, parameters, or field data of a custom type. For example, the following class definition will result in various compile-time errors:

```
class ThisWillNeverCompile
{
    // Error! var cannot be used as field data!
    private var myInt = 10;

    // Error! var cannot be used as a return value
    // or parameter type!
    public var MyMethod(var x, var y){}
}
```

Also, local variables declared with the `var` keyword *must* be assigned an initial value at the exact time of declaration and *cannot* be assigned the initial value of `null`. This last restriction should make sense, given that the compiler cannot infer what sort of type in memory the variable would be pointing to based only on `null`.

```
// Error! Must assign a value!
var myData;

// Error! Must assign value at exact time of declaration!
var myInt;
myInt = 0;

// Error! Can't assign null as initial value!
var myObj = null;
```

It is permissible, however, to assign an inferred local variable to `null` after its initial assignment (provided it is a reference type).

```
// OK, is SportsCar is a reference type!
var myCar = new SportsCar();
myCar = null;
```

Furthermore, it is permissible to assign the value of an implicitly typed local variable to the value of other variables, implicitly typed or not.

```
// Also OK!
var myInt = 0;
var anotherInt = myInt;

string myString = "Wake up!";
var myData = myString;
```

Also, it is permissible to return an implicitly typed local variable to the caller, provided the method return type is the same underlying type as the var-defined data point.

```
static int GetAnInt()
{
    var retVal = 9;
    return retVal;
}
```

Last but not least, be aware that it is illegal to define a nullable implicitly typed local variable using the C# ? token (see Chapter 4 for details on nullable data types).

```
// Nope, can't define nullable implicit variables,
// as implicit variables can never be initially assigned
// null to begin with!
var? nope = new SportsCar();
var? stillNo = 12;
var? noWay = null;
```

Implicit Typed Data Is Strongly Typed Data

Be very aware that implicit typing of local variables results in *strongly typed data*. Therefore, use of the var keyword is *not* the same technique used with scripting languages (such as JavaScript or Perl) or the COM Variant data type, where a variable can hold values of different types over its lifetime in a program (often termed *dynamic typing*).

Note .NET 4.0 does allow for dynamic typing in C# using a new keyword called—surprise, surprise—dynamic. You will learn about this aspect of the language in Chapter 18.

Rather, type inference keeps the strongly typed aspect of the C# language and affects only the declaration of variables at compile time. After that, the data point is treated as if it were declared with that type; assigning a value of a different type into that variable will result in a compile-time error.

```
static void ImplicitTypingIsStrongTyping()
{
```

```

// The compiler knows "s" is a System.String.
var s = "This variable can only hold string data!";
s = "This is fine...";

// Can invoke any member of the underlying type.
string upper = s.ToUpper();

// Error! Can't assign numerical data to a string!
s = 44;
}

```

Usefulness of Implicitly Typed Local Variables

Now that you have seen the syntax used to declare implicitly typed local variables, I am sure you are wondering when to make use of this construct? First and foremost, using var to declare local variables simply for the sake of doing so really brings little to the table. Doing so can be confusing to others reading your code, as it becomes harder to quickly determine the underlying data type and therefore more difficult to understand the overall functionality of the variable. So if you know you need an int, declare an int!

However, as you will see beginning in Chapter 13, the LINQ technology set makes use of *query expressions* that can yield dynamically created result sets based on the format of the query itself. In these cases, implicit typing is extremely helpful, as we do not need to explicitly define the type that a query may return, which in some cases would be literally impossible to do. Without getting hung up on the following LINQ example code, see if you can figure out the underlying data type of subset:

```

static void QueryOverInts()
{
    int[] numbers = { 10, 20, 30, 40, 1, 2, 3, 8 };

    // LINQ query!
    var subset = from i in numbers where i < 10 select i;

    Console.WriteLine("Values in subset: ");
    foreach (var i in subset)
    {
        Console.Write("{0} ", i);
    }
    Console.WriteLine();

    // Hmm...what type is subset?
    Console.WriteLine("subset is a: {0}", subset.GetType().Name);
    Console.WriteLine("subset is defined in: {0}", subset.GetType().Namespace);
}

```

I'll let the interested reader verify the underlying data type of subset by executing the preceding code (and it is not an array of integers!). In any case, it should be clear that implicit typing does have its place within the LINQ technology set. In fact, it could be argued that the *only time* one would make use of the var keyword is when defining data returned from a LINQ query. Remember, if you know you need an int, just declare an int! Overuse of implicit typing (via the var keyword) is considered bad style in production code.

■ **Source Code** The `ImplicitlyTypedLocalVars` project can be found under the Chapter 3 subdirectory.

C# Iteration Constructs

All programming languages provide ways to repeat blocks of code until a terminating condition has been met. Regardless of which language you have used in the past, the C# iteration statements should not raise too many eyebrows and should require little explanation. C# provides the following four iteration constructs:

- `for` loop
- `foreach/in` loop
- `while` loop
- `do/while` loop

Let's quickly examine each looping construct in turn, using a new Console Application project named `IterationsAndDecisions`.

The `for` Loop

When you need to iterate over a block of code a fixed number of times, the `for` statement provides a good deal of flexibility. In essence, you are able to specify how many times a block of code repeats itself, as well as the terminating condition. Without belaboring the point, here is a sample of the syntax.

```
// A basic for loop.
static void ForAndForEachLoop()
{
    // Note! "i" is only visible within the scope of the for loop.
    for(int i = 0; i < 4; i++)
    {
        Console.WriteLine("Number is: {0} ", i);
    }
    // "i" is not visible here.
}
```

All of your old C, C++, and Java tricks still hold when building a C# `for` statement. You can create complex terminating conditions, build endless loops, and make use of the `goto`, `continue`, and `break` keywords. I'll assume that you will bend this iteration construct as you see fit. Consult the .NET Framework 4.0 SDK documentation if you require further details on the C# `for` keyword.

The foreach Loop

The C# `foreach` keyword allows you to iterate over all items within an array (or a collection object; see Chapter 10) without the need to test for an upper limit. Here are two examples using `foreach`—one to traverse an array of strings and the other to traverse an array of integers.

```
// Iterate array items using foreach.
static void ForAndForEachLoop()
{
...
    string[] carTypes = {"Ford", "BMW", "Yugo", "Honda" };
    foreach (string c in carTypes)
        Console.WriteLine(c);

    int[] myInts = { 10, 20, 30, 40 };
    foreach (int i in myInts)
        Console.WriteLine(i);
}
```

In addition to iterating over simple arrays, `foreach` is also able to iterate over system-supplied or user-defined collections. I'll hold off on the details until Chapter 9, as this aspect of the `foreach` keyword entails an understanding of interface-based programming and the role of the `IEnumerator` and `IEnumerable` interfaces.

Use of var Within foreach Constructs

It is also possible to make use of implicit typing within a `foreach` looping construct. As you would expect, the compiler will correctly infer the correct “type of type.” Consider the following method, which iterates over a local array of integers:

```
static void VarInForEachLoop()
{
    int[] myInts = { 10, 20, 30, 40 };

    // Use "var" in a standard foreach loop.
    foreach (var item in myInts)
    {
        Console.WriteLine("Item value: {0}", item);
    }
}
```

Understand that in this example there is no compelling reason to use the `var` keyword in our `foreach` loop, as we can clearly see that we are indeed iterating over an array of integers. But once again, when using the LINQ programming model, using `var` within a `foreach` loop will be very useful, and in some cases, absolutely mandatory.

The while and do/while Looping Constructs

The `while` looping construct is useful should you wish to execute a block of statements until some terminating condition has been reached. Within the scope of a `while` loop, you will need to ensure this terminating event is indeed established; otherwise, you will be stuck in an endless loop. In the following example, the message “In `while` loop” will be continuously printed until the user terminates the loop by entering `yes` at the command prompt:

```
static void ExecuteWhileLoop()
{
    string userIsDone = "";

    // Test on a lower-class copy of the string.
    while(userIsDone.ToLower() != "yes")
    {
        Console.WriteLine("Are you done? [yes] [no]: ");
        userIsDone = Console.ReadLine();
        Console.WriteLine("In while loop");
    }
}
```

Closely related to the `while` loop is the `do/while` statement. Like a simple `while` loop, `do/while` is used when you need to perform some action an undetermined number of times. The difference is that `do/while` loops are guaranteed to execute the corresponding block of code at least once. In contrast, it is possible that a simple `while` loop may never execute if the terminating condition is false from the onset.

```
static void ExecuteDoWhileLoop()
{
    string userIsDone = "";

    do
    {
        Console.WriteLine("In do/while loop");
        Console.WriteLine("Are you done? [yes] [no]: ");
        userIsDone = Console.ReadLine();
    }while(userIsDone.ToLower() != "yes"); // Note the semicolon!
}
```

Decision Constructs and the Relational/Equality Operators

Now that you can iterate over a block of statements, the next related concept is how to control the flow of program execution. C# defines two simple constructs to alter the flow of your program, based on various contingencies:

- The `if/else` statement
- The `switch` statement

The if/else Statement

First up is our good friend the if/else statement. Unlike in C and C++, however, the if/else statement in C# operates only on Boolean expressions, not ad hoc values such as -1 or 0. Given this, if/else statements typically involve the use of the C# operators shown in Table 3-7 in order to obtain a literal Boolean value.

Table 3-7. C# Relational and Equality Operators

C# Equality/Relational Operator	Example Usage	Meaning in Life
==	if(age == 30)	Returns true only if each expression is the same.
!=	if("Foo" != myStr)	Returns true only if each expression is different.
<	if(bonus < 2000)	>Returns true if expression A (bonus) is less than,
>	if(bonus > 2000)	greater than, less than or equal to, or greater than
<=	if(bonus <= 2000)	or equal to expression B (2000).
>=	if(bonus >= 2000)	

Again, C and C++ programmers need to be aware that the old tricks of testing a condition for a value not equal to zero will not work in C#. Let's say you want to see whether the string you are working with is longer than zero characters. You may be tempted to write

```
static void ExecuteIfElse()
{
    // This is illegal, given that Length returns an int, not a bool.
    string stringData = "My textual data";
    if(stringData.Length)
    {
        Console.WriteLine("string is greater than 0 characters");
    }
}
```

If you wish to make use of the `String.Length` property to determine truth or falsity, you need to modify your conditional expression to resolve to a Boolean.

```
// Legal, as this resolves to either true or false.
if(stringData.Length > 0)
{
    Console.WriteLine("string is greater than 0 characters");
}
```

An if statement may be composed of complex expressions as well and can contain else statements to perform more complex testing. The syntax is identical to C(++) and Java. To build complex expressions, C# offers an expected set of logical operators, as shown in Table 3-8.

Table 3-8. C# Logical Operators

Logical Operator	Example	Meaning in Life
&&	if(age == 30 && name == "Fred")	AND operator. Returns true if all expressions are true.
	if(age == 30 name == "Fred")	OR operator. Returns true if at least one expression is true.
!	if(!myBool)	NOT operator. Returns true if false, or false if true.

■ **Note** The `&&` and `||` operators both “short circuit” when necessary. This means once a complex expression has been determined to be false, the remaining expressions will not be checked.

The switch Statement

The other simple selection construct offered by C# is the `switch` statement. As in other C-based languages, the `switch` statement allows you to handle program flow based on a predefined set of choices. For example, the following `Main()` logic prints a specific string message based on one of two possible selections (the default case handles an invalid selection).

```
// Switch on a numerical value.
static void ExecuteSwitch()
{
    Console.WriteLine("1 [C#], 2 [VB]");
    Console.Write("Please pick your language preference: ");

    string langChoice = Console.ReadLine();
    int n = int.Parse(langChoice);

    switch (n)
    {
        case 1:
            Console.WriteLine("Good choice, C# is a fine language.");
            break;
        case 2:
            Console.WriteLine("VB: OOP, multithreading, and more!");
            break;
        default:
            Console.WriteLine("Well...good luck with that!");
            break;
    }
}
```

■ **Note** C# demands that each case (including default) that contains executable statements have a terminating break or goto to avoid fall-through.

One nice feature of the C# switch statement is that you can evaluate string data in addition to numeric data. Here is an updated switch statement that does this very thing (notice we have no need to parse the user data into a numeric value with this approach).

```
static void ExecuteSwitchOnString()
{
    Console.WriteLine("C# or VB");
    Console.Write("Please pick your language preference: ");

    string langChoice = Console.ReadLine();
    switch (langChoice)
    {
        case "C#":
            Console.WriteLine("Good choice, C# is a fine language.");
            break;
        case "VB":
            Console.WriteLine("VB: OOP, multithreading and more!");
            break;
        default:
            Console.WriteLine("Well...good luck with that!");
            break;
    }
}
```

■ **Source Code** The IterationsAndDecisions project is located under the Chapter 3 subdirectory.

That wraps up your look at the looping and decision keywords of C#, and the common operators that are used to build complex statements. I've tried to keep this part of the chapter short and to the point, as I am assuming you have experience using similar keywords (if, for, switch, etc.) in your current programming language. If you require more information, look up the topic of interest within the .NET Framework 4.0 SDK Documentation.

Summary

The goal of this chapter was to expose you to numerous core aspects of the C# programming language. Here, we examined the commonplace constructs in any application you may be interested in building. After examining the role of an application object, you learned that every C# executable program must have a type defining a `Main()` method, which serves as the program's entry point. Within the scope of

`Main()`, you typically create any number of objects that work together to breathe life into your application.

Next, we dove into the details of the built-in data types of C# and came to understand that each data type keyword (e.g., `int`) is really a shorthand notation for a full-blown type in the `System` namespace (`System.Int32` in this case). Given this, each C# data type has a number of built-in members. Along the same vein, you also learned about the role of *widening* and *narrowing* as well as the role of the `checked` and `unchecked` keywords.

We wrapped up by checking out the role of implicit typing using the `var` keyword. As we discussed, the most useful place for implicit typing is when working with the LINQ programming model. Finally, we quickly examined the various iteration and decision constructs supported by C#. Now that you have an understanding of some of the basic nuts and bolts, the next chapter completes our examination of core language features. After that you will be well prepared to examine the object-oriented features of C#.



Core C# Programming Constructs, Part II

This chapter picks up where the previous chapter left off, and completes your investigation of the core aspects of the C# programming language. We begin by examining various details regarding the construction of C# methods, exploring the `out`, `ref`, and `params` keywords. Along the way, you will also examine two new C# language features introduced with .NET 4.0, specifically optional and named parameters.

After you examine the topic of *method overloading*, the next task is to investigate the details behind manipulating arrays using the syntax of C# and get to know the functionality contained within the related `System.Array` class type.

In addition, this chapter provides a discussion regarding the construction of enumeration and structure types, including a fairly detailed examination of the distinction between a *value type* and a *reference type*. We wrap this up by examining the role of nullable data types and the `?` and `??` operators. Once you have completed this chapter, you will be in a perfect position to learn the object oriented capabilities of C#, beginning in Chapter 5.

Methods and Parameter Modifiers

To begin this chapter, let's examine the details of defining methods. Just like the `Main()` method (see Chapter 3), your custom methods may or may not take parameters and may or may not return values to the caller. As you will see over the next several chapters, methods can be implemented within the scope of classes or structures (as well as prototyped within interface types) and may be decorated with various keywords (e.g., `internal`, `virtual`, `public`, `new`) to qualify their behavior. At this point in the text, each of our methods has followed this basic format:

```
// Recall that static methods can be called directly
// without creating a class instance.
class Program
{
    // static returnType MethodName(params) {...}
    static int Add(int x, int y){ return x + y; }
}
```

While the definition of a method in C# is quite straightforward, there are a handful of keywords that you can use to control how arguments are passed to the method in question. These are listed in Table 4-1.

Table 4-1. C# Parameter Modifiers

Parameter Modifier	Meaning in Life
(None)	If a parameter is not marked with a parameter modifier, it is assumed to be passed by value, meaning the called method receives a copy of the original data.
out	Output parameters must be assigned by the method being called, and therefore are passed by reference. If the called method fails to assign output parameters, you are issued a compiler error.
ref	The value is initially assigned by the caller and may be optionally reassigned by the called method (as the data is also passed by reference). No compiler error is generated if the called method fails to assign a ref parameter.
params	This parameter modifier allows you to send in a variable number of arguments as a single logical parameter. A method can have only a single params modifier, and it must be the final parameter of the method. In reality, you may not need to use the params modifier all too often, however be aware that numerous methods within the base class libraries do make use of this C# language feature.

To illustrate the use of these keywords, create a new Console Application project named `FunWithMethods`. Now, let's walk through the role of each keyword.

The Default Parameter-Passing Behavior

The default manner in which a parameter is sent into a function is *by value*. Simply put, if you do not mark an argument with a parameter modifier, a copy of the data is passed into the function. As explained at the end of this chapter, exactly *what* is copied will depend on whether the parameter is a value type or a reference type. For the time being, assume the following method within the `Program` class that operates on two numerical data types passed by value:

```
// Arguments are passed by value by default.
static int Add(int x, int y)
{
    int ans = x + y;

    // Caller will not see these changes
    // as you are modifying a copy of the
    // original data.
    x = 10000;
    y = 88888;
    return ans;
}
```

Numerical data falls under the category of *value types*. Therefore, if you change the values of the parameters within the scope of the member, the caller is blissfully unaware, given that you are changing the values on a *copy* of the caller's original data:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Methods *****\n");

    // Pass two variables in by value.
    int x = 9, y = 10;
    Console.WriteLine("Before call: X: {0}, Y: {1}", x, y);
    Console.WriteLine("Answer is: {0}", Add(x, y));
    Console.WriteLine("After call: X: {0}, Y: {1}", x, y);
    Console.ReadLine();
}
```

As you would hope, the values of x and y remain identical before and after the call to Add(), as shown in the following:

```
***** Fun with Methods *****
```

```
Before call: X: 9, Y: 10
Answer is: 19
After call: X: 9, Y: 10
```

The out Modifier

Next, you have the use of *output parameters*. Methods that have been defined to take output parameters (via the `out` keyword) are under obligation to assign them to an appropriate value before exiting the method scope (if you fail to do so, you will receive compiler errors).

To illustrate, here is an alternative version of the `Add()` method that returns the sum of two integers using the C# `out` modifier (note the physical return value of this method is now `void`):

```
// Output parameters must be assigned by the called method.
static void Add(int x, int y, out int ans)
{
    ans = x + y;
}
```

Calling a method with output parameters also requires the use of the `out` modifier. However, the local variables which are passed as output variables are not required to be assigned before passing them in as output arguments (if you do so, the original value is lost after the call). The reason the compiler allows you to send in seemingly unassigned data is due to the fact that the method being called *must* make an assignment. The following code is an example:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Methods *****");
    ...
    // No need to assign initial value to local variables
```

```
// used as output parameters, provided the first time
// you use them is as output arguments.
int ans;
Add(90, 90, out ans);
Console.WriteLine("90 + 90 = {0}", ans);
Console.ReadLine();
}
```

The previous example is intended to be illustrative in nature; you really have no reason to return the value of your summation using an output parameter. However, the C# `out` modifier does serve a very useful purpose: it allows the caller to obtain multiple return values from a single method invocation.

```
// Returning multiple output parameters.
static void FillTheseValues(out int a, out string b, out bool c)
{
    a = 9;
    b = "Enjoy your string.";
    c = true;
}
```

The caller would be able to invoke the `FillTheseValues()` method. Do notice that you must use the `out` modifier when you invoke the method, as well as when you implement the method:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Methods *****");
    ...
    int i; string str; bool b;
    FillTheseValues(out i, out str, out b);

    Console.WriteLine("Int is: {0}", i);
    Console.WriteLine("String is: {0}", str);
    Console.WriteLine("Boolean is: {0}", b);
    Console.ReadLine();
}
```

Finally, always remember that a method that defines output parameters *must* assign the parameter to a valid value before exiting the method scope. Therefore, the following code will result in a compiler error, as the output parameter has not been assigned within the method scope:

```
static void ThisWontCompile(out int a)
{
    Console.WriteLine("Error! Forgot to assign output arg!");
}
```

The `ref` Modifier

Now consider the use of the C# `ref` parameter modifier. Reference parameters are necessary when you wish to allow a method to operate on (and usually change the values of) various data points declared in

the caller's scope (such as a sorting or swapping routine). Note the distinction between output and reference parameters:

- Output parameters do not need to be initialized before they passed to the method. The reason for this? The method must assign output parameters before exiting.
- Reference parameters must be initialized before they are passed to the method. The reason for this is that you are passing a reference to an existing variable. If you don't assign it to an initial value, that would be the equivalent of operating on an unassigned local variable.

Let's check out the use of the `ref` keyword by way of a method that swaps two `string` variables:

```
// Reference parameters.
public static void SwapStrings(ref string s1, ref string s2)
{
    string tempStr = s1;
    s1 = s2;
    s2 = tempStr;
}
```

This method can be called as follows:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Methods *****");
    ...
    string s1 = "Flip";
    string s2 = "Flop";
    Console.WriteLine("Before: {0}, {1} ", s1, s2);
    SwapStrings(ref s1, ref s2);
    Console.WriteLine("After: {0}, {1} ", s1, s2);
    Console.ReadLine();
}
```

Here, the caller has assigned an initial value to local string data (`s1` and `s2`). Once the call to `SwapStrings()` returns, `s1` now contains the value "Flop", while `s2` reports the value "Flip":

Before: Flip, Flop
After: Flop, Flip

Note The C# `ref` keyword will be revisited later in this chapter in the section "Understanding Value Types and Reference Types." As you will see, the behavior of this keyword changes just a bit depending on whether the argument is a value type (structure) or reference type (class).

The params Modifier

C# supports the use of *parameter arrays* using the `params` keyword. To understand this language feature you must (as the name implies) understand how to manipulate C# arrays. If this is not the case, you may wish to return to this section once you read the section “Array Manipulation in C#” found a bit later in this chapter.

The `params` keyword allows you to pass into a method a variable number of identically typed parameters as a *single logical parameter*. As well, arguments marked with the `params` keyword can be processed if the caller sends in a strongly typed array or a comma-delimited list of items. Yes, this can be confusing! To clear things up, assume you wish to create a function that allows the caller to pass in any number of arguments and return the calculated average.

If you were to prototype this method to take an array of doubles, this would force the caller to first define the array, then fill the array, and finally pass it into the method. However, if you define `CalculateAverage()` to take a `params` of double data types, the caller can simply pass a comma-delimited list of doubles. The .NET runtime will automatically package the set of doubles into an array of type `double` behind the scenes:

```
// Return average of "some number" of doubles.
static double CalculateAverage(params double[] values)
{
    Console.WriteLine("You sent me {0} doubles.", values.Length);

    double sum = 0;
    if(values.Length == 0)
        return sum;

    for (int i = 0; i < values.Length; i++)
        sum += values[i];
    return (sum / values.Length);
}
```

This method has been defined to take a parameter array of doubles. What this method is in fact saying is, “Send me any number of doubles (including zero) and I’ll compute the average.” Given this, you can call `CalculateAverage()` in any of the following ways:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Methods *****");
    ...

    // Pass in a comma-delimited list of doubles...
    double average;
    average = CalculateAverage(4.0, 3.2, 5.7, 64.22, 87.2);
    Console.WriteLine("Average of data is: {0}", average);

    // ...or pass an array of doubles.
    double[] data = { 4.0, 3.2, 5.7 };
    average = CalculateAverage(data);
    Console.WriteLine("Average of data is: {0}", average);

    // Average of 0 is 0!
    Console.WriteLine("Average of data is: {0}", CalculateAverage());
```

```
    Console.ReadLine();
}
```

If you did not make use of the `params` modifier in the definition of `CalculateAverage()`, the first invocation of this method would result in a compiler error, as the compiler would be looking for a version of `CalculateAverage()` which took five `double` arguments.

Note To avoid any ambiguity, C# demands a method only support `single params argument`, which must be the final argument in the parameter list.

As you might guess, this technique is nothing more than a convenience for the caller, given that the array is created by the CLR as necessary. By the time the array is within the scope of the method being called, you are able to treat it as a full-blown .NET array that contains all the functionality of the `System.Array` base class library type. Consider the following output:

```
You sent me 5 doubles.  
Average of data is: 32.864  
You sent me 3 doubles.  
Average of data is: 4.3  
You sent me 0 doubles.  
Average of data is: 0
```

Defining Optional Parameters

With the release of .NET 4.0, C# programmers are now able to create methods which can take *optional arguments*. This technique allows the caller to invoke a single method while omitting arguments deemed unnecessary, provided the caller is happy with the specified defaults.

Note As you will see in Chapter 18, a key motivation for adding optional arguments to C# is to simplify interacting with COM objects. Several Microsoft object models (e.g., Microsoft Office) expose their functionality via COM objects, many of which were written long ago to make use of optional parameters.

To illustrate working with optional arguments, assume you have a method named `EnterLogData()`, which defines a single optional parameter:

```
static void EnterLogData(string message, string owner = "Programmer")
{
    Console.Beep();
```

```

    Console.WriteLine("Error: {0}", message);
    Console.WriteLine("Owner of Error: {0}", owner);
}

```

Here, the final string argument has been assigned the default value of "Programmer", via an assignment within the parameter definition. Given this, we can call `EnterLogData()` from within `Main()` in two manners:

```

static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Methods *****");
    ...
    EnterLogData("Oh no! Grid can't find data");
    EnterLogData("Oh no! I can't find the payroll data", "CFO");

    Console.ReadLine();
}

```

Because the first invocation of `EnterLogData()` did not specify a second string argument, we would find that the programmer is the one responsible for losing data for the grid, while the CFO misplaced the payroll data (as specified by the second argument in the second method call).

One very important thing to be aware of, is that the value assigned to an optional parameter must be known at compile time, and cannot be resolved at runtime (if you attempt to do so, you'll receive compile time errors!). To illustrate, assume you wish to update `EnterLogData()` with the following extra optional parameter:

```

// Error! The default value for an optional arg must be known
// at compile time!
static void EnterLogData(string message,
                         string owner = "Programmer", DateTime timeStamp = DateTime.Now)
{
    Console.Beep();
    Console.WriteLine("Error: {0}", message);
    Console.WriteLine("Owner of Error: {0}", owner);
    Console.WriteLine("Time of Error: {0}", timeStamp);
}

```

This will not compile, as the value of the `Now` property of the `DateTime` class is resolved at runtime, not compile time.

Note To avoid ambiguity, optional parameters must always be packed onto the *end* of a method signature. It is a compiler error to have optional parameters listed before non-optional parameters.

Invoking Methods using Named Parameters

Another new language feature added to C# with the release of .NET 4.0 is support for *named arguments*. To be honest, at first glance, this language construct may appear to do little more than result in confusing code. And to continue being completely honest, this could be the case! Much like optional arguments, including support for named parameters are largely motivated by the desire to simplify the process of working with the COM interoperability layer (again, see Chapter 18).

Named arguments allow you to invoke a method by specifying parameter values in any order you choose. Thus, rather than passing parameters solely by position (as you will do in most cases), you can choose to specify each argument by name using a colon operator. To illustrate the use of named arguments, assume we have added the following method to the `Program` class:

```
static void DisplayFancyMessage(ConsoleColor textColor,
    ConsoleColor backgroundColor, string message)
{
    // Store old colors to restore once message is printed.
    ConsoleColor oldTextColor = Console.ForegroundColor;
    ConsoleColor oldBackgroundColor = Console.BackgroundColor;

    // Set new colors and print message.
    Console.ForegroundColor = textColor;
    Console.BackgroundColor = backgroundColor;

    Console.WriteLine(message);

    // Restore previous colors.
    Console.ForegroundColor = oldTextColor;
    Console.BackgroundColor = oldBackgroundColor;
}
```

Now, the way `DisplayFancyMessage()` was written, you would expect the caller to invoke this method by passing two `ConsoleColor` variables followed by a `string` type. However, using named arguments, the following calls are completely fine:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Methods *****");
    ...
    DisplayFancyMessage(message: "Wow! Very Fancy indeed!",
        textColor: ConsoleColor.DarkRed,
        backgroundColor: ConsoleColor.White);

    DisplayFancyMessage(backgroundColor: ConsoleColor.Green,
        message: "Testing...",
        textColor: ConsoleColor.DarkBlue);
    Console.ReadLine();
}
```

One minor gotcha regarding named arguments is that if you begin to invoke a method using positional parameters, they must be listed before any named parameters. In other words, named arguments must always be packed onto the end of a method call. The following code is an example:

```
// This is OK, as positional args are listed before named args.
DisplayFancyMessage(ConsoleColor.Blue,
    message: "Testing...",
    backgroundColor: ConsoleColor.White);

// This is an ERROR, as positional args are listed after named args.
DisplayFancyMessage(message: "Testing...",
    backgroundColor: ConsoleColor.White,
    ConsoleColor.Blue);
```

This restriction aside, you might still be wondering when you would ever want to use this language feature. After all, if you need to specify three arguments to a method, why bother flipping around their position?

Well, as it turns out, if you have a method that defines optional arguments, this feature can actually be really helpful. Assume `DisplayFancyMessage()` has been rewritten to now support optional arguments, as you have assigned fitting defaults:

```
static void DisplayFancyMessage(ConsoleColor textColor = ConsoleColor.Blue,
    ConsoleColor backgroundColor = ConsoleColor.White,
    string message = "Test Message")
{
    ...
}
```

Given that each argument has a default value, named arguments allows the caller to only specify the parameter(s) for which they do not wish to receive the defaults. Therefore, if the caller wants the value "Hello!" to appear in blue text surrounded by a white background, they can simply say:

```
DisplayFancyMessage(message: "Hello!");
```

Or, if the caller wants to see "Test Message" print out with a green background containing blue text, they can invoke `DisplayFancyMessage()`:

```
DisplayFancyMessage(backgroundColor: ConsoleColor.Green);
```

As you can see, optional arguments and named parameters do tend to work hand in hand. To wrap up our examination of building C# methods, I need to address the topic of *method overloading*.

Source Code The `FunWithMethods` application is located under the Chapter 4 subdirectory.

Understanding Method Overloading

Like other modern object-oriented languages, C# allows a method to be *overloaded*. Simply put, when you define a set of identically named methods that differ by the number (or type) of parameters, the method in question is said to be overloaded.

To understand why overloading is so useful, consider life as a Visual Basic 6.0 developer. Assume you are using VB6 to build a set of methods that return the sum of various incoming data types (Integers, Doubles, and so on). Given that VB6 does not support method overloading, you would be required to define a unique set of methods that essentially do the same thing (return the sum of the arguments):

```
' VB6 code examples.
Public Function AddInts(ByVal x As Integer, ByVal y As Integer) As Integer
    AddInts = x + y
End Function

Public Function AddDoubles(ByVal x As Double, ByVal y As Double) As Double
    AddDoubles = x + y
End Function

Public Function AddLongs(ByVal x As Long, ByVal y As Long) As Long
    AddLongs = x + y
End Function
```

Not only can code such as this become tough to maintain, but the caller must now be painfully aware of the name of each method. Using overloading, you are able to allow the caller to call a single method named `Add()`. Again, the key is to ensure that each version of the method has a distinct set of arguments (methods differing only by return type are not unique enough).

Note As explained in Chapter 10, it is possible to build generic methods that take the concept of overloading to the next level. Using generics, you can define “placeholders” for a method implementation that are specified at the time you invoke the member.

To check this out firsthand, create a new Console Application project named `MethodOverloading`. Now, consider the following class definition:

```
// C# code.
class Program
{
    static void Main(string[] args) { }

    // Overloaded Add() method.
    static int Add(int x, int y)
    { return x + y; }
    static double Add(double x, double y)
    { return x + y; }
    static long Add(long x, long y)
```

```
{ return x + y; }
```

The caller can now simply invoke `Add()` with the required arguments and the compiler is happy to comply, given the fact that the compiler is able to resolve the correct implementation to invoke given the provided arguments:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Method Overloading *****\n");

    // Calls int version of Add()
    Console.WriteLine(Add(10, 10));

    // Calls long version of Add()
    Console.WriteLine(Add(900000000000, 900000000000));

    // Calls double version of Add()
    Console.WriteLine(Add(4.3, 4.4));

    Console.ReadLine();
}
```

The Visual Studio 2010 IDE provides assistance when calling overloaded methods to boot. When you type in the name of an overloaded method (such as our good friend `Console.WriteLine()`), IntelliSense will list each version of the method in question. Note that you are able to cycle through each version of an overloaded method using the up and down arrow keys shown in Figure 4-1.




Figure 4-1. Visual Studio IntelliSense for overloaded methods

Source Code The MethodOverloading application is located under the Chapter 4 subdirectory.

That wraps up our initial examination of building methods using the syntax of C#. Next, let's check out how to build and manipulate arrays, enumerations, and structures. After this point, we will wrap up the chapter with an examination of 'nullable data types' and the C# ? and ?? operators.

Understanding C# Arrays

As I would guess you are already aware, an *array* is a set of data items, accessed using a numerical index. More specifically, an array is a set of contiguous data points of the same type (an array of ints, an array of strings, an array of SportsCars, and so on). Declaring an array with C# is quite straightforward. To illustrate, create a new Console Application project (named FunWithArrays) that contains a helper method named SimpleArrays(), invoked from within Main():

```
class Program
{
    static void Main(string[] args)
    {
        Console.WriteLine("***** Fun with Arrays *****");
        SimpleArrays();
        Console.ReadLine();
    }

    static void SimpleArrays()
    {
        Console.WriteLine("=> Simple Array Creation.");
        // Assign an array of ints containing 3 elements {0, 1, 2}
        int[] myInts = new int[3];

        // Initialize a 100 item string array, indexed {0 - 99}
        string[] booksOnDotNet = new string[100];
        Console.WriteLine();
    }
}
```

Look closely at the previous code comments. When declaring a C# array using this syntax, the number used in the array declaration represents the total number of items, not the upper bound. Also note that the lower bound of an array always begins at 0. Thus, when you write `int[] myInts = new int[3]`, you end up with an array holding three elements, indexed at positions 0, 1, 2.

Once you have defined an array variable, you are then able to fill the elements index by index as shown in the updated SimpleArrays() method:

```
static void SimpleArrays()
{
    Console.WriteLine("=> Simple Array Creation.");
    // Create and fill an array of 3 Integers
    int[] myInts = new int[3];
```

```

myInts[0] = 100;
myInts[1] = 200;
myInts[2] = 300;

// Now print each value.
foreach(int i in myInts)
    Console.WriteLine(i);
    Console.WriteLine();
}

```

Note Do be aware that if you declare an array, but do not explicitly fill each index, each item will be set to the default value of the data type (e.g., an array of bools will be set to false or an array of ints will be set to 0).

C# Array Initialization Syntax

In addition to filling an array element by element, you are also able to fill the items of an array using C# *array initialization syntax*. To do so, specify each array item within the scope of curly brackets ({}). This syntax can be helpful when you are creating an array of a known size and wish to quickly specify the initial values. For example, consider the following alternative array declarations:

```

static void ArrayInitialization()
{
    Console.WriteLine("=> Array Initialization.");

    // Array initialization syntax using the new keyword.
    string[] stringArray = new string[]
        { "one", "two", "three" };
    Console.WriteLine("stringArray has {0} elements", stringArray.Length);

    // Array initialization syntax without using the new keyword.
    bool[] boolArray = { false, false, true };
    Console.WriteLine("boolArray has {0} elements", boolArray.Length);

    // Array initialization with new keyword and size.
    int[] intArray = new int[4] { 20, 22, 23, 0 };
    Console.WriteLine("intArray has {0} elements", intArray.Length);
    Console.WriteLine();
}

```

Notice that when you make use of this “curly bracket” syntax, you do not need to specify the size of the array (seen when constructing the stringArray variable), given that this will be inferred by the number of items within the scope of the curly brackets. Also notice that use of the new keyword is optional (shown when constructing the boolArray type).

In the case of the intArray declaration, again recall the numeric value specified represents the number of elements in the array, not the value of the upper bound. If there is a mismatch between the declared size and the number of initializers, you are issued a compile-time error. The following is an example:

```
// OOPS! Mismatch of size and elements!
int[] intArray = new int[2] { 20, 22, 23, 0 };
```

Implicitly Typed Local Arrays

In the previous chapter, you learned about the topic of implicitly typed local variables. Recall that the `var` keyword allows you to define a variable, whose underlying type is determined by the compiler. In a similar vein, the `var` keyword can be used to define *implicitly typed local arrays*. Using this technique, you can allocate a new array variable without specifying the type contained within the array itself:

```
static void DeclareImplicitArrays()
{
    Console.WriteLine("=> Implicit Array Initialization.");

    // a is really int[].
    var a = new[] { 1, 10, 100, 1000 };
    Console.WriteLine("a is a: {0}", a.ToString());

    // b is really double[].
    var b = new[] { 1, 1.5, 2, 2.5 };
    Console.WriteLine("b is a: {0}", b.ToString());

    // c is really string[].
    var c = new[] { "hello", null, "world" };
    Console.WriteLine("c is a: {0}", c.ToString());
    Console.WriteLine();
}
```

Of course, just as when you allocate an array using explicit C# syntax, the items in the array's initialization list must be of the same underlying type (e.g., all ints, all strings, or all `SportsCars`). Unlike what you might be expecting, an implicitly typed local array does not default to `System.Object`; thus the following generates a compile-time error:

```
// Error! Mixed types!
var d = new[] { 1, "one", 2, "two", false };
```

Defining an Array of Objects

In most cases, when you define an array, you do so by specifying the explicitly type of item that can be within the array variable. While this seems quite straightforward, there is one notable twist. As you will come to understand in Chapter 6, `System.Object` is the ultimate base class to each and every type (including fundamental data types) in the .NET type system. Given this fact, if you were to define an array of objects, the subitems could be anything at all. Consider the following `ArrayOfObjects()` method (which again can be invoked from `Main()` for testing):

```
static void ArrayOfObjects()
{
    Console.WriteLine("=> Array of Objects.");

    // An array of objects can be anything at all.
```

```

object[] myObjects = new object[4];
myObjects[0] = 10;
myObjects[1] = false;
myObjects[2] = new DateTime(1969, 3, 24);
myObjects[3] = "Form & Void";

foreach (object obj in myObjects)
{
    // Print the type and value for each item in array.
    Console.WriteLine("Type: {0}, Value: {1}", obj.GetType(), obj);
}
Console.WriteLine();
}

```

Here, as you are iterating over the contents of `myObjects`, you print out the underlying type of each item using the `GetType()` method of `System.Object` as well as the value of the current item. Without going into too much detail regarding `System.Object.GetType()` at this point in the text, simply understand that this method can be used to obtain the fully qualified name of the item (Chapter 15 examines the topic of type information and reflection services in detail). The following output shows the result of calling `ArrayOfObjects()`.

```

=> Array of Objects.
Type: System.Int32, Value: 10
Type: System.Boolean, Value: False
Type: System.DateTime, Value: 3/24/1969 12:00:00 AM
Type: System.String, Value: Form & Void

```

Working with Multidimensional Arrays

In addition to the single-dimension arrays you have seen thus far, C# also supports two varieties of multidimensional arrays. The first of these is termed a *rectangular array*, which is simply an array of multiple dimensions, where each row is of the same length. To declare and fill a multidimensional rectangular array, proceed as follows:

```

static void RectMultidimensionalArray()
{
    Console.WriteLine("=> Rectangular multidimensional array.");
    // A rectangular MD array.
    int[,] myMatrix;
    myMatrix = new int[6,6];

    // Populate (6 * 6) array.
    for(int i = 0; i < 6; i++)
        for(int j = 0; j < 6; j++)
            myMatrix[i, j] = i * j;

    // Print (6 * 6) array.
    for(int i = 0; i < 6; i++)
    {

```

```

    for(int j = 0; j < 6; j++)
        Console.Write(myMatrix[i, j] + "\t");
    Console.WriteLine();
}
Console.WriteLine();
}

```

The second type of multidimensional array is termed a *jagged array*. As the name implies, jagged arrays contain some number of inner arrays, each of which may have a unique upper limit, for example:

```

static void JaggedMultidimensionalArray()
{
    Console.WriteLine("=> Jagged multidimensional array.");
    // A jagged MD array (i.e., an array of arrays).
    // Here we have an array of 5 different arrays.
    int[][] myJagArray = new int[5][];

    // Create the jagged array.
    for (int i = 0; i < myJagArray.Length; i++)
        myJagArray[i] = new int[i + 7];

    // Print each row (remember, each element is defaulted to zero!)
    for(int i = 0; i < 5; i++)
    {
        for(int j = 0; j < myJagArray[i].Length; j++)
            Console.Write(myJagArray[i][j] + " ");
        Console.WriteLine();
    }
    Console.WriteLine();
}

```

Figure 4-2 shows the output of calling each of the `RectMultidimensionalArray()` and `JaggedMultidimensionalArray()` methods within `Main()`.

```

C:\> C:\Windows\system32\cmd.exe
***** Fun with Arrays *****
=> Rectangular multidimensional array.
0   0   0   0   0   0
0   1   2   3   4   5
0   2   4   6   8   10
0   3   6   9   12  15
0   4   8   12  16  20
0   5   10  15  20  25

=> Jagged multidimensional array.
0 0 0 0 0 0
0 0 0 0 0 0
0 0 0 0 0 0
0 0 0 0 0 0
0 0 0 0 0 0
Press any key to continue . . .

```

Figure 4-2. Rectangular and jagged multidimensional arrays

Arrays As Arguments or Return Values

Once you have created an array, you are free to pass it as an argument or receive it as a member return value. For example, the following `PrintArray()` method takes an incoming array of ints and prints each member to the console, while the `GetStringArray()` method populates an array of strings and returns it to the caller:

```
static void PrintArray(int[] myInts)
{
    for(int i = 0; i < myInts.Length; i++)
        Console.WriteLine("Item {0} is {1}", i, myInts[i]);
}

static string[] GetStringArray()
{
    string[] theStrings = {"Hello", "from", "GetStringArray"};
    return theStrings;
}
```

These methods may be invoked as you would expect:

```
static void PassAndReceiveArrays()
{
    Console.WriteLine("> Arrays as params and return values.");
    // Pass array as parameter.
    int[] ages = {20, 22, 23, 0} ;
    PrintArray(ages);

    // Get array as return value.
    string[] strs = GetStringArray();
    foreach(string s in strs)
        Console.WriteLine(s);

    Console.WriteLine();
}
```

At this point, hopefully you feel comfortable with the process of defining, filling, and examining the contents of a C# array variable. To complete the picture, let's now examine the role of the `System.Array` class.

The `System.Array` Base Class

Every array you create gathers much of its functionality from the `System.Array` class. Using these common members, you are able to operate on an array using a consistent object model. Table 4-2 gives a rundown of some of the more interesting members (be sure to check the .NET Framework 4.0 SDK documentation for full details).

Table 4-2. Select Members of System.Array

Member of Array Class	Meaning in Life
Clear()	This static method sets a range of elements in the array to empty values (0 for numbers, null for object references, false for booleans).
CopyTo()	This method is used to copy elements from the source array into the destination array.
Length	This property returns the number of items within the array.
Rank	This property returns the number of dimensions of the current array.
Reverse()	This static method reverses the contents of an one-dimensional array.
Sort()	This static method sorts a one-dimensional array of intrinsic types. If the elements in the array implement the IComparer interface, you can also sort your custom types (see Chapter 9).

Let's see some of these members in action. The following helper method makes use of the static Reverse() and Clear() methods to pump out information about an array of string types to the console:

```
static void SystemArrayFunctionality()
{
    Console.WriteLine("=> Working with System.Array.");
    // Initialize items at startup.
    string[] gothicBands = {"Tones on Tail", "Bauhaus", "Sisters of Mercy"};

    // Print out names in declared order.
    Console.WriteLine("-> Here is the array:");
    for (int i = 0; i < gothicBands.Length; i++)
    {
        // Print a name
        Console.Write(gothicBands[i] + ", ");
    }
    Console.WriteLine("\n");

    // Reverse them...
    Array.Reverse(gothicBands);
    Console.WriteLine("-> The reversed array");
    // ... and print them.
    for (int i = 0; i < gothicBands.Length; i++)
    {
        // Print a name
        Console.Write(gothicBands[i] + ", ");
    }
    Console.WriteLine("\n");
```

```
// Clear out all but the final member.
Console.WriteLine("-> Cleared out all but one...");
Array.Clear(gothicBands, 1, 2);
for (int i = 0; i < gothicBands.Length; i++)
{
    // Print a name
    Console.Write(gothicBands[i] + ", ");
}
Console.WriteLine();
}
```

If you invoke this method from within `Main()`, you will get the output shown here.

```
=> Working with System.Array.
-> Here is the array:
Tones on Tail, Bauhaus, Sisters of Mercy,
-> The reversed array
Sisters of Mercy, Bauhaus, Tones on Tail,
-> Cleared out all but one...
Sisters of Mercy, , ,
```

Notice that many members of `System.Array` are defined as static members and are therefore called at the class level (for example, the `Array.Sort()` or `Array.Reverse()` methods). Methods such as these are passed in the array you wish to process. Other methods of `System.Array` (such as the `Length` property) are bound at the object level, thus you are able to invoke the member directly on the array.

■ Source Code The `FunWithArrays` application is located under the Chapter 4 subdirectory.

Understanding the Enum Type

Recall from Chapter 1 that the .NET type system is composed of classes, structures, enumerations, interfaces, and delegates. To begin exploration of these types, let's check out the role of the *enumeration* (or simply, *enum*) using a new Console Application project named `FunWithEnums`.

When building a system, it is often convenient to create a set of symbolic names that map to known numerical values. For example, if you are creating a payroll system, you may want to refer to the type of employees using constants such as vice president, manager, contractor, and grunt. C# supports the notion of custom enumerations for this very reason. For example, here is an enumeration named `EmpType`:

```
// A custom enumeration.
enum EmpType
{
    Manager,           // = 0
```

```

Grunt,      // = 1
Contractor, // = 2
VicePresident // = 3
}

```

The `EmpType` enumeration defines four named constants, corresponding to discrete numerical values. By default, the first element is set to the value zero (0), followed by an $n + 1$ progression. You are free to change the initial value as you see fit. For example, if it made sense to number the members of `EmpType` as 102 through 105, you could do so as follows:

```

// Begin with 102.
enum EmpType
{
    Manager = 102,
    Grunt,      // = 103
    Contractor, // = 104
    VicePresident // = 105
}

```

Enumerations do not necessarily need to follow a sequential ordering, and need not have unique values. If (for some reason or another) it makes sense to establish your `EmpType` as shown here, the compiler continues to be happy:

```

// Elements of an enumeration need not be sequential!
enum EmpType
{
    Manager = 10,
    Grunt = 1,
    Contractor = 100,
    VicePresident = 9
}

```

Controlling the Underlying Storage for an Enum

By default, the storage type used to hold the values of an enumeration is a `System.Int32` (the C# `int`); however, you are free to change this to your liking. C# enumerations can be defined in a similar manner for any of the core system types (`byte`, `short`, `int`, or `long`). For example, if you want to set the underlying storage value of `EmpType` to be a `byte` rather than an `int`, you can write the following:

```

// This time, EmpType maps to an underlying byte.
enum EmpType : byte
{
    Manager = 10,
    Grunt = 1,
    Contractor = 100,
    VicePresident = 9
}

```

Changing the underlying type of an enumeration can be helpful if you are building a .NET application that will be deployed to a low-memory device (such as a .NET-enabled cell phone or PDA) and need to conserve memory wherever possible. Of course, if you do establish your enumeration to use

a byte as storage, each value must be within its range! For example, the following version of `EmpType` will result in a compiler error, as the value 999 cannot fit within the range of a byte:

```
// Compile time error! 999 is too big for a byte!
enum EmpType : byte
{
    Manager = 10,
    Grunt = 1,
    Contractor = 100,
    VicePresident = 999
}
```

Declaring Enum Variables

Once you have established the range and storage type of your enumeration, you can use it in place of so-called “magic numbers.” Because enumerations are nothing more than a user-defined data type, you are able to use them as function return values, method parameters, local variables, and so forth. Assume you have a method named `AskForBonus()`, taking an `EmpType` variable as the sole parameter. Based on the value of the incoming parameter, you will print out a fitting response to the pay bonus request:

```
class Program
{
    static void Main(string[] args)
    {
        Console.WriteLine("**** Fun with Enums *****");
        // Make a contractor type.
        EmpType emp = EmpType.Contractor;
        AskForBonus(emp);
        Console.ReadLine();
    }

    // Enums as parameters.
    static void AskForBonus(EmpType e)
    {
        switch (e)
        {
            case EmpType.Manager:
                Console.WriteLine("How about stock options instead?");
                break;
            case EmpType.Grant:
                Console.WriteLine("You have got to be kidding...");
                break;
            case EmpType.Contractor:
                Console.WriteLine("You already get enough cash...");
                break;
            case EmpType.VicePresident:
                Console.WriteLine("VERY GOOD, Sir!");
                break;
        }
    }
}
```

Notice that when you are assigning a value to an enum variable, you must scope the enum name (`EmpType`) to the value (`Grunt`). Because enumerations are a fixed set of name/value pairs, it is illegal to set an enum variable to a value that is not defined directly by the enumerated type:

```
static void ThisMethodWillNotCompile()
{
    // Error! SalesManager is not in the EmpType enum!
    EmpType emp = EmpType.SalesManager;

    // Error! Forgot to scope Grunt value to EmpType enum!
    emp = Grunt;
}
```

The System.Enum Type

The interesting thing about .NET enumerations is that they gain functionality from the `System.Enum` class type. This class defines a number of methods that allow you to interrogate and transform a given enumeration. One helpful method is the static `Enum.GetUnderlyingType()`, which as the name implies returns the data type used to store the values of the enumerated type (`System.Byte` in the case of the current `EmpType` declaration).

```
static void Main(string[] args)
{
    Console.WriteLine("**** Fun with Enums *****");
    // Make a contractor type.
    EmpType emp = EmpType.Contractor;
    AskForBonus(emp);

    // Print storage for the enum.
    Console.WriteLine("EmpType uses a {0} for storage",
        Enum.GetUnderlyingType(emp.GetType()));
    Console.ReadLine();
}
```

If you were to consult the Visual Studio 2010 object browser, you would be able to verify that the `Enum.GetUnderlyingType()` method requires you to pass in a `System.Type` as the first parameter. As fully examined in Chapter 16, `Type` represents the metadata description of a given .NET entity.

One possible way to obtain metadata (as shown previously) is to use the `GetType()` method, which is common to all types in the .NET base class libraries. Another approach is to make use of the C# `typeof` operator. One benefit of doing so is that you do not need to have a variable of the entity you wish to obtain a metadata description of:

```
// This time use typeof to extract a Type.
Console.WriteLine("EmpType uses a {0} for storage",
    Enum.GetUnderlyingType(typeof(EmpType)));
```

Dynamically Discovering an Enum's Name/Value Pairs

Beyond the `Enum.GetUnderlyingType()` method, all C# enumerations support a method named `Tostring()`, which returns the string name of the current enumeration's value. The following code is an example:

```
static void Main(string[] args)
{
    Console.WriteLine("**** Fun with Enums ****");
    EmpType emp = EmpType.Contractor;

    // Prints out "emp is a Contractor".
    Console.WriteLine("emp is a {0}.", emp.ToString());
    Console.ReadLine();
}
```

If you are interested in discovering the value of a given enumeration variable, rather than its name, you can simply cast the enum variable against the underlying storage type. The following is an example:

```
static void Main(string[] args)
{
    Console.WriteLine("**** Fun with Enums ****");
    EmpType emp = EmpType.Contractor;

    // Prints out "Contractor = 100".
    Console.WriteLine("{0} = {1}", emp.ToString(), (byte)emp);
    Console.ReadLine();
}
```

Note The static `Enum.Format()` method provides a finer level of formatting options by specifying a desired format flag. Consult the .NET Framework 4.0 SDK documentation for full details of the `System.Enum.Format()` method.

`System.Enum` also defines another static method named `GetValues()`. This method returns an instance of `System.Array`. Each item in the array corresponds to a member of the specified enumeration. Consider the following method, which will print out each name/value pair within any enumeration you pass in as a parameter:

```
// This method will print out the details of any enum.
static void EvaluateEnum(System.Enum e)
{
    Console.WriteLine("=> Information about {0}", e.GetType().Name);


    Console.WriteLine("Underlying storage type: {0}",
        Enum.GetUnderlyingType(e.GetType()));
```

```
// Get all name/value pairs for incoming parameter.  
Array enumData = Enum.GetValues(e.GetType());  
Console.WriteLine("This enum has {0} members.", enumData.Length);  
  
// Now show the string name and associated value, using the D format  
// flag (see Chapter 3).  
for(int i = 0; i < enumData.Length; i++)  
{  
    Console.WriteLine("Name: {0}, Value: {0:D}",  
        enumData.GetValue(i));  
}  
Console.WriteLine();  
}
```

To test this new method, update your `Main()` method to create variables of several enumeration types declared in the `System` namespace (as well as an `EmpType` enumeration for good measure). The following code is an example:

```
static void Main(string[] args)  
{  
    Console.WriteLine("**** Fun with Enums *****");  
    EmpType e2 = EmpType.Contractor;  
  
    // These types are enums in the System namespace.  
    DayOfWeek day = DayOfWeek.Monday;  
    ConsoleColor cc = ConsoleColor.Gray;  
  
    EvaluateEnum(e2);  
    EvaluateEnum(day);  
    EvaluateEnum(cc);  
    Console.ReadLine();  
}
```

The output is shown in Figure 4-3.



```
***** Fun with Enums *****
=> Information about EmpType
Underlying storage type: System.Byte
This enum has 4 members.
Name: Grunt, Value: 1
Name: VicePresident, Value: 9
Name: Manager, Value: 10
Name: Contractor, Value: 100

=> Information about DayOfWeek
Underlying storage type: System.Int32
This enum has 7 members.
Name: Sunday, Value: 0
Name: Monday, Value: 1
Name: Tuesday, Value: 2
Name: Wednesday, Value: 3
Name: Thursday, Value: 4
Name: Friday, Value: 5
Name: Saturday, Value: 6

=> Information about ConsoleColor
Underlying storage type: System.Int32
This enum has 16 members.
Name: Black, Value: 0
Name: DarkBlue, Value: 1
Name: DarkGreen, Value: 2
Name: DarkCyan, Value: 3
Name: DarkRed, Value: 4
Name: DarkMagenta, Value: 5
Name: DarkYellow, Value: 6
Name: Gray, Value: 7
Name: DarkGray, Value: 8
Name: Blue, Value: 9
Name: Green, Value: 10
Name: Cyan, Value: 11
Name: Red, Value: 12
Name: Magenta, Value: 13
Name: Yellow, Value: 14
Name: White, Value: 15
```

Figure 4-3. Dynamically discovering name/value pairs of enumeration types

As you will see over the course of this text, enumerations are used extensively throughout the .NET base class libraries. For example, ADO.NET makes use of numerous enumerations to represent the state of a database connection (e.g., opened or closed), the state of a row in a DataTable (e.g., changed, new, or detached). Therefore, when you make use of any enumeration, always remember that you are able to interact with the name/value pairs using the members of `System.Enum`.

■ **Source Code** The `FunWithEnums` project is located under the Chapter 4 subdirectory.

Understanding the Structure Type

Now that you understand the role of enumeration types, let's examine the use of .NET *structures* (or simply *structs*). Structure types are well suited for modeling mathematical, geometrical, and other “atomic” entities in your application. A structure (like an enumeration) is a user-defined type; however, structures are not simply a collection of name/value pairs. Rather, structures are types that can contain any number of data fields and members that operate on these fields.

■ **Note** If you have a background in OOP, you can think of a structure as a “lightweight class type,” given that structures provide a way to define a type that supports encapsulation, but cannot be used to build a family of related types. When you need to build a family of related types through inheritance, you will need to make use of class types.

On the surface, the process of defining and using structures is very simple, but as they say, the devil is in the details. To begin understanding the basics of structure types, create a new project named `FunWithStructures`. In C#, structures are created using the `struct` keyword. Define a new structure named `Point`, which defines two member variables of type `int` and a set of methods to interact with said data:

```
struct Point
{
    // Fields of the structure.
    public int X;
    public int Y;

    // Add 1 to the (X, Y) position.
    public void Increment()
    {
        X++; Y++;
    }

    // Subtract 1 from the (X, Y) position.
    public void Decrement()
    {
        X--; Y--;
    }

    // Display the current position.
    public void Display()
    {
        Console.WriteLine("X = {0}, Y = {1}", X, Y);
    }
}
```

Here, you have defined your two integer fields (`X` and `Y`) using the `public` keyword, which is an access control modifier (Chapter 5 furthers this discussion). Declaring data with the `public` keyword ensures the caller has direct access to the data from a given `Point` variable (via the dot operator).

■ **Note** It is typically considered bad style to define public data within a class or structure. Rather, you will want to define *private* data, which can be accessed and changed using *public* properties. These details will be examined in Chapter 5.

Here is a `Main()` method that takes our `Point` type out for a test drive:

```
static void Main(string[] args)
{
    Console.WriteLine("***** A First Look at Structures *****\n");
    // Create an initial Point.
    Point myPoint;
    myPoint.X = 349;
    myPoint.Y = 76;
    myPoint.Display();

    // Adjust the X and Y values.
    myPoint.Increment();
    myPoint.Display();
    Console.ReadLine();
}
```

The output is as you would expect:

```
***** A First Look at Structures *****

X = 349, Y = 76
X = 350, Y = 77
```

Creating Structure Variables

When you wish to create a structure variable, you have a variety of options. Here, you simply create a `Point` variable and assign each piece of public field data before invoking its members. If you do *not* assign each piece of public field data (`X` and `Y` in our case) before making use of the structure, you will receive a compiler error:

```
// Error! Did not assign Y value.
Point p1;
p1.X = 10;
p1.Display();
```

```
// OK! Both fields assigned before use.
Point p2;
p2.X = 10;
p2.Y = 10;
p2.Display();
```

As an alternative, we can create structure variables using the C# new keyword, which will invoke the structure's *default constructor*. By definition, a default constructor does not take any arguments. The benefit of invoking the default constructor of a structure is that each piece of field data is automatically set to its default value:

```
// Set all fields to default values
// using the default constructor.
Point p1 = new Point();

// Prints X=0,Y=0
p1.Display();
```

It is also possible to design a structure with a *custom constructor*. This allows you to specify the values of field data upon variable creation, rather than having to set each data member field by field. Chapter 5 will provide a detailed examination of constructors; however, to illustrate, update the Point structure with the following code:

```
struct Point
{
    // Fields of the structure.
    public int X;
    public int Y;

    // A custom constructor.
    public Point(int XPos, int YPos)
    {
        X = XPos;
        Y = YPos;
    }
    ...
}
```

With this, we could now create Point variables as follows:

```
// Call custom constructor.
Point p2 = new Point(50, 60);

// Prints X=50,Y=60
p2.Display();
```

As mentioned, working with structures on the surface is quite simple. However, to deepen your understanding of this type, you need to explore the distinction between a .NET value type and a .NET reference type.

■ **Source Code** The FunWithStructures project is located under the Chapter 4 subdirectory.

Understanding Value Types and Reference Types

■ **Note** The following discussion of value types and reference types assumes that you have a background in object-oriented programming. If this is not the case, you may wish to skip to the final section in this chapter (Understanding C# Nullable Types) and return to this section once you have read Chapters 5 and 6.

Unlike arrays, strings, or enumerations, C# structures do not have an identically named representation in the .NET library (that is, there is no `System.Structure` class), but are implicitly derived from `System.ValueType`. Simply put, the role of `System.ValueType` is to ensure that the derived type (e.g., any structure) is allocated on the *stack* rather than the garbage collected *heap*. Simply put, data allocated on the stack can be created and destroyed very quickly, as its lifetime is determined by the defining scope. Heap allocated data, on the other hand, is monitored by the .NET garbage collector, and has a lifetime that is determined by a large number of factors, which will be examined in Chapter 8.

Functionally, the only purpose of `System.ValueType` is to override the virtual methods defined by `System.Object` to use value-based, versus reference-based, semantics. As you may know, overriding is the process of changing the implementation of a virtual (or possibly abstract) method defined within a base class. The base class of `ValueType` is `System.Object`. In fact, the instance methods defined by `System.ValueType` are identical to those of `System.Object`:

```
// Structures and enumerations implicitly extend System.ValueType.  
public abstract class ValueType : object  
{  
    public virtual bool Equals(object obj);  
    public virtual int GetHashCode();  
    public Type GetType();  
    public virtual string ToString();  
}
```

Given the fact that value types are using value-based semantics, the lifetime of a structure (which includes all numerical data types [`int`, `float`], as well as any enum or custom structure) is very predictable. When a structure variable falls out of the defining scope, it is removed from memory immediately:

```
// Local structures are popped off  
// the stack when a method returns.  
static void LocalValueTypes()  
{  
    // Recall! "int" is really a System.Int32 structure.  
    int i = 0;  
  
    // Recall! Point is a structure type.  
    Point p = new Point();  
} // "i" and "p" popped off the stack here!
```

Value Types, References Types, and the Assignment Operator

When you assign one value type to another, a member-by-member copy of the field data is achieved. In the case of a simple data type such as `System.Int32`, the only member to copy is the numerical value. However, in the case of your `Point`, the `X` and `Y` values are copied into the new structure variable. To illustrate, create a new Console Application project named `ValueAndReferenceTypes`, then copy your previous `Point` definition into your new namespace. Next, add the following method to your `Program` type:

```
// Assigning two intrinsic value types results in
// two independent variables on the stack.
static void ValueTypeAssignment()
{
    Console.WriteLine("Assigning value types\n");

    Point p1 = new Point(10, 10);
    Point p2 = p1;

    // Print both points.
    p1.Display();
    p2.Display();

    // Change p1.X and print again. p2.X is not changed.
    p1.X = 100;
    Console.WriteLine("\n=> Changed p1.X\n");
    p1.Display();
    p2.Display();
}
```

Here you have created a variable of type `Point` (named `p1`) that is then assigned to another `Point` (`p2`). Because `Point` is a value type, you have two copies of the `MyPoint` type on the stack, each of which can be independently manipulated. Therefore, when you change the value of `p1.X`, the value of `p2.X` is unaffected:

Assigning value types

```
X = 10, Y = 10
X = 10, Y = 10

=> Changed p1.X

X = 100, Y = 10
X = 10, Y = 10
```

In stark contrast to value types, when you apply the assignment operator to reference types (meaning all class instances), you are redirecting what the reference variable points to in memory. To illustrate, create a new class type named `PointRef` that has the exact same members as the `Point` structures, beyond renaming the constructor to match the class name:

```
// Classes are always reference types.
```

```

class PointRef
{
    // Same members as the Point structure...

    // Be sure to change your constructor name to PointRef!
    public PointRef(int XPos, int YPos)
    {
        X = XPos;
        Y = YPos;
    }
}

```

Now, make use of your `PointRef` type within the following new method. Note that beyond using the `PointRef` class, rather than the `Point` structure, the code is identical to the `ValueTypeAssignment()` method.

```

static void ReferenceTypeAssignment()
{
    Console.WriteLine("Assigning reference types\n");
    PointRef p1 = new PointRef(10, 10);
    PointRef p2 = p1;

    // Print both point refs.
    p1.Display();
    p2.Display();

    // Change p1.X and print again.
    p1.X = 100;
    Console.WriteLine("\n=> Changed p1.X\n");
    p1.Display();
    p2.Display();
}

```

In this case, you have two references pointing to the same object on the managed heap. Therefore, when you change the value of `X` using the `p2` reference, `p1.X` reports the same value. Assuming you have called this new method within `Main()`, your output should look like the following:

Assigning reference types

```

X = 10, Y = 10
X = 10, Y = 10

```

```
=> Changed p1.X
```

```

X = 100, Y = 10
X = 100, Y = 10

```

Value Types Containing Reference Types

Now that you have a better feeling for the basic differences between value types and reference types, let's examine a more complex example. Assume you have the following reference (class) type that maintains an informational string that can be set using a custom constructor:

```
class ShapeInfo
{
    public string infoString;
    public ShapeInfo(string info)
    { infoString = info; }
}
```

Now assume that you want to contain a variable of this class type within a value type named Rectangle. To allow the caller to set the value of the inner ShapeInfo member variable, you also provide a custom constructor. Here is the complete definition of the Rectangle type:

```
struct Rectangle
{
    // The Rectangle structure contains a reference type member.
    public ShapeInfo rectInfo;

    public int rectTop, rectLeft, rectBottom, rectRight;

    public Rectangle(string info, int top, int left, int bottom, int right)
    {
        rectInfo = new ShapeInfo(info);
        rectTop = top; rectBottom = bottom;
        rectLeft = left; rectRight = right;
    }

    public void Display()
    {
        Console.WriteLine("String = {0}, Top = {1}, Bottom = {2}, " +
            "Left = {3}, Right = {4}",
            rectInfo.infoString, rectTop, rectBottom, rectLeft, rectRight);
    }
}
```

At this point, you have contained a reference type within a value type. The million dollar question now becomes, what happens if you assign one Rectangle variable to another? Given what you already know about value types, you would be correct in assuming that the integer data (which is indeed a structure) should be an independent entity for each Rectangle variable. But what about the internal reference type? Will the object's state be fully copied, or will the reference to that object be copied? To answer this question, define the following method and invoke it from Main().

```
static void ValueTypeContainingRefType()
{
    // Create the first Rectangle.
    Console.WriteLine("-> Creating r1");
    Rectangle r1 = new Rectangle("First Rect", 10, 10, 50, 50);
```

```
// Now assign a new Rectangle to r1.
Console.WriteLine("-> Assigning r2 to r1");
Rectangle r2 = r1;

// Change some values of r2.
Console.WriteLine("-> Changing values of r2");
r2.rectInfo.infoString = "This is new info!";
r2.rectBottom = 4444;

// Print values of both rectangles.
r1.Display();
r2.Display();
}
```

The output can be seen in the following:

```
-> Creating r1
-> Assigning r2 to r1
-> Changing values of r2
String = This is new info!, Top = 10, Bottom = 50, Left = 10, Right = 50
String = This is new info!, Top = 10, Bottom = 4444, Left = 10, Right = 50
```

As you can see, when you change the value of the informational string using the `r2` reference, the `r1` reference displays the same value. By default, when a value type contains other reference types, assignment results in a copy of the references. In this way, you have two independent structures, each of which contains a reference pointing to the same object in memory (i.e., a shallow copy). When you want to perform a deep copy, where the state of internal references is fully copied into a new object, one approach is to implement the `ICloneable` interface (as you will do in Chapter 9).

Source Code The `ValueAndReferenceTypes` project is located under the Chapter 4 subdirectory.

Passing Reference Types by Value

Reference types or value types can obviously be passed as parameters to methods. However, passing a reference type (e.g., a class) by reference is quite different from passing it by value. To understand the distinction, assume you have a simple `Person` class defined in a new Console Application project named `RefTypeValTypeParams`, defined as follows:

```
class Person
{
    public string personName;
    public int personAge;

    // Constructors.
    public Person(string name, int age)
    {
```

```

    personName = name;
    personAge = age;
}
public Person(){}
public void Display()
{
    Console.WriteLine("Name: {0}, Age: {1}", personName, personAge);
}
}

```

Now, what if you create a method that allows the caller to send in the Person object by value (note the lack of parameter modifiers, such as `out` or `ref`):

```

static void SendAPersonByValue(Person p)
{
    // Change the age of "p"?
    p.personAge = 99;

    // Will the caller see this reassignment?
    p = new Person("Nikki", 99);
}

```

Notice how the `SendAPersonByValue()` method attempts to reassign the incoming `Person` reference to a new `Person` object as well as change some state data. Now let's test this method using the following `Main()` method:

```

static void Main(string[] args)
{
    // Passing ref-types by value.
    Console.WriteLine("***** Passing Person object by value *****");
    Person fred = new Person("Fred", 12);
    Console.WriteLine("\nBefore by value call, Person is:");
    fred.Display();

    SendAPersonByValue(fred);
    Console.WriteLine("\nAfter by value call, Person is:");
    fred.Display();
    Console.ReadLine();
}

```

The following is the output of this call.

```
***** Passing Person object by value *****
```

```
Before by value call, Person is:
Name: Fred, Age: 12
```

```
After by value call, Person is:
Name: Fred, Age: 99
```

As you can see, the value of `personAge` has been modified. This behavior seems to fly in the face of what it means to pass a parameter “by value.” Given that you were able to change the state of the incoming `Person`, what was copied? The answer: a copy of the reference to the caller’s object. Therefore, as the `SendAPersonByValue()` method is pointing to the same object as the caller, it is possible to alter the object’s state data. What is not possible is to reassign what the reference *is pointing to*.

Passing Reference Types by Reference

Now assume you have a `SendAPersonByReference()` method, which passes a reference type by reference (note the `ref` parameter modifier):

```
static void SendAPersonByReference(ref Person p)
{
    // Change some data of "p".
    p.personAge = 555;

    // "p" is now pointing to a new object on the heap!
    p = new Person("Nikki", 999);
}
```

As you might expect, this allows complete flexibility of how the callee is able to manipulate the incoming parameter. Not only can the callee change the state of the object, but if it so chooses, it may also reassign the reference to a new `Person` type. Now ponder the following updated `Main()` method:

```
static void Main(string[] args)
{
    // Passing ref-types by ref.
    Console.WriteLine("***** Passing Person object by reference *****");
    Person mel = new Person("Mel", 23);
    Console.WriteLine("Before by ref call, Person is:");
    mel.Display();

    SendAPersonByReference(ref mel);
    Console.WriteLine("After by ref call, Person is:");
    mel.Display();
    Console.ReadLine();
}
```

Notice the following output:

```
***** Passing Person object by reference *****
Before by ref call, Person is:
Name: Mel, Age: 23
After by ref call, Person is:
Name: Nikki, Age: 999
```

As you can see, an object named `Mel` returns after the call as an object named `Nikki`, as the method was able to change what the incoming reference pointed to in memory. The golden rule to keep in mind when passing reference types is the following:

- If a reference type is passed by reference, the callee may change the values of the object's state data as well as the object it is referencing.
 - If a reference type is passed by value, the callee may change the values of the object's state data but *not* the object it is referencing.
-

■ Source Code The RefTypeValTypeParams project is located under the Chapter 4 subdirectory.

Final Details Regarding Value Types and Reference Types

To wrap up this topic, consider the information in Table 4-3, which summarizes the core distinctions between value types and reference types.

Table 4-3. Value Types and Reference Types Side by Side

Intriguing Question	Value Type	Reference Type
Where is this type allocated?	Allocated on the stack.	Allocated on the managed heap.
How is a variable represented?	Value type variables are local copies.	Reference type variables are pointing to the memory occupied by the allocated instance.
What is the base type?	Must derive from <code>System.ValueType</code> .	Can derive from any other type (except <code>System.ValueType</code>), as long as that type is not “sealed” (more details on this in Chapter 6).
Can this type function as a base to other types?	No. Value types are always sealed and cannot be inherited from.	Yes. If the type is not sealed, it may function as a base to other types.
What is the default parameter passing behavior?	Variables are passed by value (i.e., a copy of the variable is passed into the called function).	For value types, the object is copied-by-value. For reference types, the reference is copied-by-value.
Can this type override <code>System.Object.Finalize()</code> ?	No. Value types are never placed onto the heap and therefore do not need to be finalized.	Yes, indirectly (more details on this in Chapter 8).

Table 4-3. Value Types and Reference Types Side by Side (continued)

Intriguing Question	Value Type	Reference Type
Can I define constructors for this type?	Yes, but the default constructor is reserved (i.e., your custom constructors must all have arguments).	But of course!
When do variables of this type die?	When they fall out of the defining scope	When the object is garbage collected.

Despite their differences, value types and reference types both have the ability to implement interfaces and may support any number of fields, methods, overloaded operators, constants, properties, and events.

Understanding C# Nullable Types

To wrap up this chapter, let's examine the role of *nullable data type* using a final Console Application named `NullableTypes`. As you know, CLR data types have a fixed range and are represented as a type in the `System` namespace. For example, the `System.Boolean` data type can be assigned a value from the set `{true, false}`. Now, recall that all of the numerical data types (as well as the Boolean data type) are *value types*. Value types can never be assigned the value of `null`, as that is used to establish an empty object reference:

```
static void Main(string[] args)
{
    // Compiler errors!
    // Value types cannot be set to null!
    bool myBool = null;
    int myInt = null;

    // OK! Strings are reference types.
    string myString = null;
}
```

Since the release of .NET 2.0, it has been possible to create nullable data types. Simply put, a nullable type can represent all the values of its underlying type, plus the value `null`. Thus, if we declare a nullable `bool`, it could be assigned a value from the set `{true, false, null}`. This can be extremely helpful when working with relational databases, given that it is quite common to encounter undefined columns in database tables. Without the concept of a nullable data type, there is no convenient manner in C# to represent a numerical data point with no value.

To define a nullable variable type, the question mark symbol (?) is suffixed to the underlying data type. Do note that this syntax is only legal when applied to value types. If you attempt to create a nullable reference type (including `strings`), you are issued a compile-time error. Like a nonnullable variable, local nullable variables must be assigned an initial value before you can use them:

```
static void LocalNullableVariables()
{
```

```

// Define some local nullable types.
int? nullableInt = 10;
double? nullableDouble = 3.14;
bool? nullableBool = null;
char? nullableChar = 'a';
int?[] arrayOfNullableInts = new int?[10];

// Error! Strings are reference types!
// string? s = "oops";
}

```

In C#, the ? suffix notation is a shorthand for creating an instance of the generic System.Nullable<T> structure type. Although we will not examine generics until Chapter 10, it is important to understand that the System.Nullable<T> type provides a set of members that all nullable types can make use of.

For example, you are able to programmatically discover whether the nullable variable indeed has been assigned a null value using the HasValue property or the != operator. The assigned value of a nullable type may be obtained directly or via the Value property. In fact, given that the ? suffix is just a shorthand for using Nullable<T>, you could implement your LocalNullableVariables() method as follows:

```

static void LocalNullableVariablesUsingNullable()
{
    // Define some local nullable types using Nullable<T>.
    Nullable<int> nullableInt = 10;
    Nullable<double> nullableDouble = 3.14;
    Nullable<bool> nullableBool = null;
    Nullable<char> nullableChar = 'a';
    Nullable<int>[] arrayOfNullableInts = new int?[10];
}

```

Working with Nullable Types

As stated, nullable data types can be particularly useful when you are interacting with databases, given that columns in a data table may be intentionally empty (e.g., undefined). To illustrate, assume the following class, which simulates the process of accessing a database that has a table containing two columns that may be null. Note that the GetIntFromDatabase() method is not assigning a value to the nullable integer member variable, while GetBoolFromDatabase() is assigning a valid value to the bool? member:

```

class DatabaseReader
{
    // Nullable data field.
    public int? numericValue = null;
    public bool? boolValue = true;

    // Note the nullable return type.
    public int? GetIntFromDatabase()
    { return numericValue; }
}

```

```
// Note the nullable return type.
public bool? GetBoolFromDatabase()
{ return boolValue; }
}
```

Now, assume the following Main() method, which invokes each member of the DatabaseReader class, and discovers the assigned values using the HasValue and Value members as well as using the C# equality operator (not equal, to be exact):

```
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Nullable Data *****\n");
    DatabaseReader dr = new DatabaseReader();

    // Get int from "database".
    int? i = dr.GetIntFromDatabase();
    if (i.HasValue)
        Console.WriteLine("Value of 'i' is: {0}", i.Value);
    else
        Console.WriteLine("Value of 'i' is undefined.");

    // Get bool from "database".
    bool? b = dr.GetBoolFromDatabase();
    if (b != null)
        Console.WriteLine("Value of 'b' is: {0}", b.Value);
    else
        Console.WriteLine("Value of 'b' is undefined.");
    Console.ReadLine();
}
```

The ?? Operator

The final aspect of nullable types to be aware of is that they can make use of the C# ?? operator. This operator allows you to assign a value to a nullable type if the retrieved value is in fact null. For this example, assume you wish to assign a local nullable integer to 100 if the value returned from GetIntFromDatabase() is null (of course, this method is programmed to *always* return null, but I am sure you get the general idea):

```
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Nullable Data *****\n");
    DatabaseReader dr = new DatabaseReader();

    ...
    // If the value from GetIntFromDatabase() is null,
    // assign local variable to 100.
    int myData = dr.GetIntFromDatabase() ?? 100;
    Console.WriteLine("Value of myData: {0}", myData);
    Console.ReadLine();
}
```

The benefit of using the ?? operator is that it provides a more compact version of a traditional if/else condition. However, if you wish, you could have authored the following, functionally equivalent code to ensure that if a value comes back as null, it will indeed be set to the value 100:

```
// Long hand version of using ? : ?? syntax.  
int? moreData = dr.GetIntFromDatabase();  
if (!moreData.HasValue)  
    moreData = 100;  
Console.WriteLine("Value of moreData: {0}", moreData);
```

■ **Source Code** The NullableTypes application is located under the Chapter 4 subdirectory.

Summary

This chapter began with an examination of several C# keywords that allow you to build custom methods. Recall that by default, parameters are passed by value; however, you may pass a parameter by reference if you mark it with `ref` or `out`. You also learned about the role of optional or named parameters and how to define and invoke methods taking parameter arrays.

Once we investigated the topic of method overloading, the bulk of this chapter examined several details regarding how arrays, enumerations, and structures are defined in C# and represented within the .NET base class libraries. Along the way, you examined several details regarding value types and reference types, including how they respond when passing them as parameters to methods, and how to interact with nullable data types using the `?` and `??` operators.

With this, our initial investigation of the C# programming language is complete! In the next chapter, you will begin to dig into the details of object-oriented development.



Defining Encapsulated Class Types

In the previous two chapters, you investigated a number of core syntactical constructs that are commonplace to any .NET application you may be developing. Here, you will begin your examination of the object-oriented capabilities of C#. The first order of business is to examine the process of building well-defined class types that support any number of *constructors*. Once you understand the basics of defining classes and allocating objects, the remainder of this chapter will examine the role of *encapsulation*. Along the way you will understand how to define class properties as well as the role of static members, object initialization syntax, read-only fields, constant data, and partial classes.

Introducing the C# Class Type

As far as the .NET platform is concerned, the most fundamental programming construct is the *class type*. Formally, a class is a user-defined type that is composed of field data (often called *member variables*) and members that operate on this data (such as constructors, properties, methods, events, and so forth). Collectively, the set of field data represents the “state” of a class instance (otherwise known as an *object*). The power of object-based languages such as C# is that by grouping data and related functionality in a unified class definition, you are able to model your software after entities in the real world.

To get the ball rolling, create a new C# Console Application named SimpleClassExample. Next, insert a new class file (named `Car.cs`) into your project using the Project ➤ Add Class... menu selection, choose the Class icon from the resulting dialog box as shown in Figure 5-1, and click the Add button.

A class is defined in C# using the `class` keyword. Here is the simplest possible declaration:

```
class Car  
{  
}
```

Once you have defined a class type, you will need to consider the set of member variables that will be used to represent its state. For example, you may decide that cars maintain an `int` data type to represent the current speed and a `string` data type to represent the car’s friendly pet name. Given these initial design notes, update your `Car` class as follows:

```
class Car  
{  
    // The 'state' of the Car.  
    public string petName;  
    public int currSpeed;  
}
```




Figure 5-1. Inserting a new C# class type

Notice that these member variables are declared using the `public` access modifier. Public members of a class are directly accessible once an object of this type has been created. Recall the term “object” is used to represent an instance of a given class type created using the `new` keyword.

Note Field data of a class should seldom (if ever) be defined as public. To preserve the integrity of your state data, it is a far better design to define data as private (or possibly protected) and allow controlled access to the data via type properties (as shown later in this chapter). However, to keep this first example as simple as possible, public data fits the bill.

After you have defined the set of member variables that represent the state of the class, the next design step is to establish the members that model its behavior. For this example, the `Car` class will define one method named `SpeedUp()` and another named `PrintState()`. Update your class as so:

```
class Car
{
    // The 'state' of the Car.
    public string petName;
    public int currSpeed;

    // The functionality of the Car.
    public void PrintState()
```

```

{
    Console.WriteLine("{0} is going {1} MPH.", petName, currSpeed);
}

public void SpeedUp(int delta)
{
    currSpeed += delta;
}
}

```

`PrintState()` is more or less a diagnostic function that will simply dump the current state of a given `Car` object to the command window. `SpeedUp()` will increase the speed of the `Car` by the amount specified by the incoming `int` parameter. Now, update your `Main()` method in the `Program` class with the following code:

```

static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Class Types *****\n");

    // Allocate and configure a Car object.
    Car myCar = new Car();
    myCar.petName = "Henry";
    myCar.currSpeed = 10;

    // Speed up the car a few times and print out the
    // new state.
    for (int i = 0; i <= 10; i++)
    {
        myCar.SpeedUp(5);
        myCar.PrintState();
    }
    Console.ReadLine();
}

```

Once you run your program, you will see that the `Car` variable (`myCar`) maintains its current state throughout the life of the application, as shown in the following code:

***** Fun with Class Types *****

```

Henry is going 15 MPH.
Henry is going 20 MPH.
Henry is going 25 MPH.
Henry is going 30 MPH.
Henry is going 35 MPH.
Henry is going 40 MPH.
Henry is going 45 MPH.
Henry is going 50 MPH.
Henry is going 55 MPH.
Henry is going 60 MPH.
Henry is going 65 MPH.

```

Allocating Objects with the new Keyword

As shown in the previous code example, objects must be allocated into memory using the `new` keyword. If you do not make use of the `new` keyword and attempt to make use of your class variable in a subsequent code statement, you will receive a compiler error. For example, the following `Main()` method will not compile:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Class Types *****\n");

    // Error! Forgot to use 'new' to create object!
    Car myCar;
    myCar.petName = "Fred";
}
```

To correctly create an object using the `new` keyword, you may define and allocate a `Car` object on a single line of code:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Class Types *****\n");
    Car myCar = new Car();
    myCar.petName = "Fred";
}
```

As an alternative, if you wish to define and allocate a class instance on separate lines of code, you may do so as follows:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Class Types *****\n");
    Car myCar;
    myCar = new Car();
    myCar.petName = "Fred";
}
```

Here, the first code statement simply declares a reference to a yet-to-be-determined `Car` object. It is not until you assign a reference to an object that this reference points to a valid object in memory.

In any case, at this point we have a trivial class that defines a few points of data and some basic methods. To enhance the functionality of the current `Car` class, we need to understand the role of *constructors*.

Understanding Constructors

Given that objects have state (represented by the values of an object's member variables), a programmer will typically want to assign relevant values to the object's field data before use. Currently, the `Car` class demands that the `petName` and `currSpeed` fields be assigned on a field-by-field basis. For the current example, this is not too problematic, given that we have only two public data points. However, it is not

uncommon for a class to have dozens of fields to contend with. Clearly, it would be undesirable to author 20 initialization statements to set 20 points of data!

Thankfully, C# supports the use of *constructors*, which allow the state of an object to be established at the time of creation. A constructor is a special method of a class that is called indirectly when creating an object using the new keyword. However, unlike a “normal” method, constructors never have a return value (not even void) and are always named identically to the class they are constructing.

The Role of the Default Constructor

Every C# class is provided with a freebee *default constructor* that you may redefine if need be. By definition, a default constructor never takes arguments. After allocating the new object into memory, the default constructor ensures that all field data of the class is set to an appropriate default value (see Chapter 3 for information regarding the default values of C# data types).

If you are not satisfied with these default assignments, you may redefine the default constructor to suit your needs. To illustrate, update your C# Car class as follows:

```
class Car
{
    // The 'state' of the Car.
    public string petName;
    public int currSpeed;

    // A custom default constructor.
    public Car()
    {
        petName = "Chuck";
        currSpeed = 10;
    }
    ...
}
```

In this case, we are forcing all Car objects to begin life named Chuck at a rate of 10 mph. With this, you are able to create a Car object set to these default values as follows:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Class Types *****\n");

    // Invoking the default constructor.
    Car chuck = new Car();

    // Prints "Chuck is going 10 MPH."
    chuck.PrintState();

    ...
}
```

Defining Custom Constructors

Typically, classes define additional constructors beyond the default. In doing so, you provide the object user with a simple and consistent way to initialize the state of an object directly at the time of creation. Ponder the following update to the `Car` class, which now supports a total of three constructors:

```
class Car
{
    // The 'state' of the Car.
    public string petName;
    public int currSpeed;

    // A custom default constructor.
    public Car()
    {
        petName = "Chuck";
        currSpeed = 10;
    }

    // Here, currSpeed will receive the
    // default value of an int (zero).
    public Car(string pn)
    {
        petName = pn;
    }

    // Let caller set the full state of the Car.
    public Car(string pn, int cs)
    {
        petName = pn;
        currSpeed = cs;
    }
}

...
```

Keep in mind that what makes one constructor different from another (in the eyes of the C# compiler) is the number of and type of constructor arguments. Recall from Chapter 4, when you define a method of the same name that differs by the number or type of arguments, you have overloaded the method. Thus, the `Car` class has overloaded the constructor to provide a number of ways to create an object at the time of declaration. In any case, you are now able to create `Car` objects using any of the public constructors. For example:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Class Types *****\n");

    // Make a Car called Chuck going 10 MPH.
    Car chuck = new Car();
    chuck.PrintState();

    // Make a Car called Mary going 0 MPH.
    Car mary = new Car("Mary");
    mary.PrintState();
```

```
// Make a Car called Daisy going 75 MPH.
Car daisy = new Car("Daisy", 75);
daisy.PrintState();
...
}
```

The Default Constructor Revisited

As you have just learned, all classes are provided with a free default constructor. Thus, if you insert a new class into your current project named `Motorcycle`, defined like so:

```
class Motorcycle
{
    public void PopAWheely()
    {
        Console.WriteLine("Yeeeeeee Haaaaaeeewww!");
    }
}
```

you are able to create an instance of the `Motorcycle` type via the default constructor out of the box:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Class Types *****\n");
    Motorcycle mc = new Motorcycle();
    mc.PopAWheely();
    ...
}
```

However, as soon as you define a custom constructor, the default constructor is silently removed from the class and is no longer available! Think of it this way: if you do not define a custom constructor, the C# compiler grants you a default in order to allow the object user to allocate an instance of your type with field data set to the correct default values. However, when you define a unique constructor, the compiler assumes you have taken matters into your own hands.

Therefore, if you wish to allow the object user to create an instance of your type with the default constructor, as well as your custom constructor, you must *explicitly* redefine the default. To this end, understand that in a vast majority of cases, the implementation of the default constructor of a class is intentionally empty, as all you require is the ability to create an object with default values. Consider the following update to the `Motorcycle` class:

```
class Motorcycle
{
    public int driverIntensity;

    public void PopAWheely()
    {
        for (int i = 0; i <= driverIntensity; i++)
        {
            Console.WriteLine("Yeeeeeee Haaaaaeeewww!");
        }
    }
}
```

```

// Put back the default constructor, which will
// set all data members to default values.
public Motorcycle() {}

// Our custom constructor.
public Motorcycle(int intensity)
{ driverIntensity = intensity; }
}

```

The Role of the this Keyword

C# supplies a `this` keyword that provides access to the current class instance. One possible use of the `this` keyword is to resolve scope ambiguity, which can arise when an incoming parameter is named identically to a data field of the type. Of course, ideally you would simply adopt a naming convention that does not result in such ambiguity; however, to illustrate this use of the `this` keyword, update your `Motorcycle` class with a new `string` field (named `name`) to represent the driver's name. Next, add a method named `SetDriverName()` implemented as follows:

```

class Motorcycle
{
    public int driverIntensity;

    // New members to represent the name of the driver.
    public string name;
    public void SetDriverName(string name)
    { name = name; }

...
}

```

Although this code will compile just fine, Visual Studio 2010 will display a warning message informing you that you have assigned a variable back to itself! To illustrate, update `Main()` to call `SetDriverName()` and then print out the value of the `name` field, you may be surprised to find that the value of the `name` field is an empty string!

```

// Make a Motorcycle with a rider named Tiny?
Motorcycle c = new Motorcycle(5);
c.SetDriverName("Tiny");
c.PopAWheely();
Console.WriteLine("Rider name is {0}", c.name); // Prints an empty name value!

```

The problem is that the implementation of `SetDriverName()` is assigning the incoming parameter *back to itself* given that the compiler assumes `name` is referring to the variable currently in the method scope rather than the `name` field at the class scope. To inform the compiler that you wish to set the current object's `name` data field to the incoming `name` parameter, simply use `this` to resolve the ambiguity:

```

public void SetDriverName(string name)
{ this.name = name; }

```

Do understand that if there is no ambiguity, you are not required to make use of the `this` keyword when a class wishes to access its own data fields or members, as `this` is implied. For example, if we

rename the string data member from name to driverName (which will also require you to update your Main() method) the use of this is optional as there is no longer a scope ambiguity:

```
class Motorcycle
{
    public int driverIntensity;
    public string driverName;

    public void SetDriverName(string name)
    {
        // These two statements are functionally the same.
        driverName = name;
        this.driverName = name;
    }
...
}
```

Even though there is little to be gained when using this in unambiguous situations, you may still find this keyword useful when implementing class members, as IDEs such as SharpDevelop and Visual Studio 2010 will enable IntelliSense when this is specified. This can be very helpful when you have forgotten the name of a class member and want to quickly recall the definition. Consider Figure 5-2.




Figure 5-2. The IntelliSense of this

■ **Note** It is a compiler error to use the `this` keyword within the implementation of a static member. As you will see, static members operate on the class (not object) level, and therefore at the class level, there is no current object (thus no `this`)!

Chaining Constructor Calls Using `this`

Another use of the `this` keyword is to design a class using a technique termed *constructor chaining*. This design pattern is helpful when you have a class that defines multiple constructors. Given the fact that constructors often validate the incoming arguments to enforce various business rules, it can be quite common to find redundant validation logic within a class's constructor set. Consider the following updated `Motorcycle`:

```
class Motorcycle
{
    public int driverIntensity;
    public string driverName;

    public Motorcycle() { }

    // Redundant constructor logic!
    public Motorcycle(int intensity)
    {
        if (intensity > 10)
        {
            intensity = 10;
        }
        driverIntensity = intensity;
    }

    public Motorcycle(int intensity, string name)
    {
        if (intensity > 10)
        {
            intensity = 10;
        }
        driverIntensity = intensity;
        driverName = name;
    }
    ...
}
```

Here, perhaps in an attempt to ensure the safety of the rider, each constructor is ensuring that the intensity level is never greater than 10. While this is all well and good, you do have redundant code statements in two constructors. This is less than ideal, as you are now required to update code in multiple locations if your rules change (for example, if the intensity should not be greater than 5).

One way to improve the current situation is to define a method in the `Motorcycle` class that will validate the incoming argument(s). If you were to do so, each constructor could make a call to this

method before making the field assignment(s). While this approach does allow you to isolate the code you need to update when the business rules change, you are now dealing with the following redundancy:

```
class Motorcycle
{
    public int driverIntensity;
    public string driverName;

    // Constructors.
    public Motorcycle() { }

    public Motorcycle(int intensity)
    {
        SetIntensity(intensity);
    }

    public Motorcycle(int intensity, string name)
    {
        SetIntensity(intensity);
        driverName = name;
    }

    public void SetIntensity(int intensity)
    {
        if (intensity > 10)
        {
            intensity = 10;
        }
        driverIntensity = intensity;
    }

    ...
}
```

A cleaner approach is to designate the constructor that takes the *greatest number of arguments* as the “master constructor” and have its implementation perform the required validation logic. The remaining constructors can make use of the `this` keyword to forward the incoming arguments to the master constructor and provide any additional parameters as necessary. In this way, you only need to worry about maintaining a single constructor for the entire class, while the remaining constructors are basically empty.

Here is the final iteration of the `Motorcycle` class (with one additional constructor for the sake of illustration). When chaining constructors, note how the `this` keyword is “dangling” off the constructor’s declaration (via a colon operator) outside the scope of the constructor itself:

```
class Motorcycle
{
    public int driverIntensity;
    public string driverName;

    // Constructor chaining.
    public Motorcycle() {}
    public Motorcycle(int intensity)
        : this(intensity, "") {}
```

```

public Motorcycle(string name)
    : this(0, name) {}

// This is the 'master' constructor that does all the real work.
public Motorcycle(int intensity, string name)
{
    if (intensity > 10)
    {
        intensity = 10;
    }
    driverIntensity = intensity;
    driverName = name;
}
...
}

```

Understand that using the `this` keyword to chain constructor calls is never mandatory. However, when you make use of this technique, you do tend to end up with a more maintainable and concise class definition. Again, using this technique you can simplify your programming tasks, as the real work is delegated to a single constructor (typically the constructor that has the most parameters), while the other constructors simply “pass the buck.”

Observing Constructor Flow

On a final note, do know that once a constructor passes arguments to the designated master constructor (and that constructor has processed the data), the constructor invoked originally by the caller will finish executing any remaining code statements. To clarify, update each of the constructors of the `Motorcycle` class with a fitting call to `Console.WriteLine()`:

```

class Motorcycle
{
    public int driverIntensity;
    public string driverName;

    // Constructor chaining.
    public Motorcycle()
    {
        Console.WriteLine("In default ctor");
    }

    public Motorcycle(int intensity)
        : this(intensity, "") 
    {
        Console.WriteLine("In ctor taking an int");
    }

    public Motorcycle(string name)
        : this(0, name)
    {
        Console.WriteLine("In ctor taking a string");
    }
}

```

```
// This is the 'master' constructor that does all the real work.
public Motorcycle(int intensity, string name)
{
    Console.WriteLine("In master ctor ");
    if (intensity > 10)
    {
        intensity = 10;
    }
    driverIntensity = intensity;
    driverName = name;
}
...
}
```

Now, ensure your `Main()` method exercises a `Motorcycle` object as follows:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with class Types *****\n");

    // Make a Motorcycle.
    Motorcycle c = new Motorcycle(5);
    c.SetDriverName("Tiny");
    c.PopAWheely();
    Console.WriteLine("Rider name is {0}", c.driverName);
    Console.ReadLine();
}
```

With this, ponder the output from the previous `Main()` method:

```
***** Fun with class Types *****
```

```
In master ctor
In ctor taking an int
Yeeeeeee Haaaaaeeewww!
Yeeeeeee Haaaaaeeewww!
Yeeeeeee Haaaaaeeewww!
Yeeeeeee Haaaaaeeewww!
Yeeeeeee Haaaaaeeewww!
Rider name is Tiny
```

As you can see, the flow of constructor logic is as follows:

- You create your object by invoking the constructor requiring a single `int`.
- This constructor forwards the supplied data to the master constructor and provides any additional startup arguments not specified by the caller.
- The master constructor assigns the incoming data to the object's field data.

- Control is returned to the constructor originally called, and executes any remaining code statements.

The nice thing about using constructor chaining, is that this programming pattern will work with any version of the C# language and .NET platform. However, if you are targeting .NET 4.0 and higher, you can further simplify your programming tasks by making use of optional arguments as an alternative to traditional constructor chaining.

Revisiting Optional Arguments

In Chapter 4, you learned about optional and named arguments. Recall that optional arguments allow you to define supplied default values to incoming arguments. If the caller is happy with these defaults, they are not required to specify a unique value, however they may do so to provide the object with custom data. Consider the following version of *Motorcycle* which now provides a number of ways to construct objects using a *single* constructor definition:

```
class Motorcycle
{
    // Single constructor using optional args.
    public Motorcycle(int intensity = 0, string name = "")
    {
        if (intensity > 10)
        {
            intensity = 10;
        }
        driverIntensity = intensity;
        driverName = name;
    }
    ...
}
```

With this one constructor, you are now able to create a new *Motorcycle* object using zero, one, or two arguments. Recall that named argument syntax allows you to essentially skip over acceptable default settings (see Chapter 3).

```
static void MakeSomeBikes()
{
    // driverName = "", driverIntensity = 0
    Motorcycle m1 = new Motorcycle();
    Console.WriteLine("Name= {0}, Intensity= {1}",
        m1.driverName, m1.driverIntensity);

    // driverName = "Tiny", driverIntensity = 0
    Motorcycle m2 = new Motorcycle(name:"Tiny");
    Console.WriteLine("Name= {0}, Intensity= {1}",
        m2.driverName, m2.driverIntensity);

    // driverName = "", driverIntensity = 7
    Motorcycle m3 = new Motorcycle(7);
    Console.WriteLine("Name= {0}, Intensity= {1}",
```

```
m3.driverName, m3.driverIntensity);
}
```

While the use of optional/named arguments is a very slick way to streamline how you define the set of constructors used by a given class, do always remember that this syntax will lock you into compiling your software under C# 2010 and running your code under .NET 4.0. If you need to build classes which can run under any version of the .NET platform, it is best to stick to classical constructor chaining techniques.

In any case, at this point you are able to define a class with field data (aka member variables) and various members such as methods and constructors. Next up, let's formalize the role of the `static` keyword.

Source Code The SimpleClassExample project is included under the Chapter 5 subdirectory.

Understanding the `static` Keyword

A C# class may define any number of *static members* using the `static` keyword. When you do so, the member in question must be invoked directly from the class level, rather than from an object reference. To illustrate the distinction, consider your good friend `System.Console`. As you have seen, you do not invoke the `WriteLine()` method from the object level:

```
// Error! WriteLine() is not an object level method!
Console c = new Console();
c.WriteLine("I can't be printed...");
```

but instead simply prefix the class name to the static `WriteLine()` member:

```
// Correct! WriteLine() is a static method.
Console.WriteLine("Thanks...");
```

Simply put, static members are items that are deemed (by the class designer) to be so commonplace that there is no need to create an instance of the type when invoking the member. While any class can define static members, they are most commonly found within “utility classes.” For example, if you were to use the Visual Studio 2010 object browser (via the `View > Object Browser` menu item) to view the `System` namespace of `mscorlib.dll`, you will see that all of the members of the `Console`, `Math`, `Environment`, and `GC` classes (among others) expose all of their functionality via static members.

Defining Static Methods

Assume you have a new Console Application project named `StaticMethods` and have inserted a class named `Teenager` that defines a static method named `Complain()`. This method returns a random string, obtained in part by calling a static helper function named `GetRandomNumber()`:

```
class Teenager
{
    public static Random r = new Random();
```

```

public static int GetRandomNumber(short upperLimit)
{
    return r.Next(upperLimit);
}

public static string Complain()
{
    string[] messages = {"Do I have to?", "He started it!",
        "I'm too tired...", "I hate school!",
        "You are sooooooo wrong!"};
    return messages[GetRandomNumber(5)];
}

```

Notice that the `System.Random` member variable and the `GetRandomNumber()` helper function method have also been declared as static members of the `Teenager` class, given the rule that static members such as the `Complain()` method can operate only on other static members.

Note Allow me to repeat myself: static members can operate only on static data and call static methods of the defining class. If you attempt to make use of nonstatic class data or call a nonstatic method of the class within a static member's implementation, you'll receive compile-time errors.

Like any static member, to call `Complain()`, prefix the name of the defining class:

```

static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Static Methods *****\n");
    for(int i =0; i < 5; i++)
        Console.WriteLine(Teenager.Complain());
    Console.ReadLine();
}

```

Source Code The `StaticMethods` application is located under the Chapter 5 subdirectory.

Defining Static Field Data

In addition to static methods, a class (or structure) may also define static field data such as the `Random` member variable seen in the previous `Teenager` class. Understand that when a class defines nonstatic data (properly referred to as *instance data*), each object of this type maintains an independent copy of the field. For example, assume a class that models a savings account is defined in a new `Console Application` project named `StaticData`:

```
// A simple savings account class.
class SavingsAccount
{
    public double currBalance;
    public SavingsAccount(double balance)
    {
        currBalance = balance;
    }
}
```

When you create `SavingsAccount` objects, memory for the `currBalance` field is allocated for each object. Static data, on the other hand, is allocated once and shared among all objects of the same class category. To illustrate the usefulness of static data, add a static point of data named `currInterestRate` to the `SavingsAccount` class, which is set to a default value of 0.04:

```
// A simple savings account class.
class SavingsAccount
{
    public double currBalance;

    // A static point of data.
    public static double currInterestRate = 0.04;

    public SavingsAccount(double balance)
    {
        currBalance = balance;
    }
}
```

If you were to create three instances of `SavingsAccount` in `Main()` as follows:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Static Data *****\n");
    SavingsAccount s1 = new SavingsAccount(50);
    SavingsAccount s2 = new SavingsAccount(100);
    SavingsAccount s3 = new SavingsAccount(10000.75);
    Console.ReadLine();
}
```

the in-memory data allocation would look something like Figure 5-3.




Figure 5-3. Static data is allocated once and shared among all instances of the class

Let's update the `SavingsAccount` class to define two static methods to get and set the interest rate value:

```
// A simple savings account class.
class SavingsAccount
{
    public double currBalance;

    // A static point of data.
    public static double currInterestRate = 0.04;

    public SavingsAccount(double balance)
    {
        currBalance = balance;
    }

    // Static members to get/set interest rate.
    public static void SetInterestRate(double newRate )
    { currInterestRate = newRate; }

    public static double GetInterestRate()
    { return currInterestRate; }
}
```

Now, observe the following usage:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Static Data *****\n");
    SavingsAccount s1 = new SavingsAccount(50);
    SavingsAccount s2 = new SavingsAccount(100);

    // Print the current interest rate.
    Console.WriteLine("Interest Rate is: {0}", SavingsAccount.GetInterestRate());
```

```

// Make new object, this does NOT 'reset' the interest rate.
SavingsAccount s3 = new SavingsAccount(10000.75);
Console.WriteLine("Interest Rate is: {0}", SavingsAccount.GetInterestRate());
Console.ReadLine();
}

```

The output of the previous Main() is seen here:

```
***** Fun with Static Data *****
```

```
In static ctor!
Interest Rate is: 0.04
Interest Rate is: 0.04
```

As you can see, when you create new instances of the `SavingsAccount` class, the value of the static data is not reset, as the CLR will allocate the data into memory exactly one time. After that point, all objects of type `SavingsAccount` operate on the same value.

When designing any C# class, one of your design challenges is to determine which pieces of data should be defined as static members, and which should not. While there are no hard and fast rules, remember that a static data field is shared by all objects. Therefore, if you are defining a point of data that *all* objects should share between them, static is the way to go.

Consider what would happen if the interest rate variable were *not* defined using the `static` keyword. This would mean every `SavingsAccount` object would have its own copy of the `currInterestRate` field. Now, assume you created 100 `SavingsAccount` objects, and need to change the interest rate. That would require you to call the `SetInterestRateObj()` method 100 times! Clearly, this would not be a very useful way to model shared data. Again, static data is perfect when you have a value that should be common to all objects of that category.

Defining Static Constructors

Recall that constructors are used to set the value of an object's data at the time of creation. Thus, if you were to assign a value to a static data member within an instance-level constructor, you may be surprised to find that the value is reset each time you create a new object! For example, assume you have updated the `SavingsAccount` class as follows:

```

class SavingsAccount
{
    public double currBalance;
    public static double currInterestRate;

    // Notice that our constructor is setting
    // the static currInterestRate value.
    public SavingsAccount(double balance)
    {
        currInterestRate = 0.04;
        currBalance = balance;
    }
    ...
}
```

If you execute the previous `Main()` method, you would see that that the `currInterestRate` variable is reset each time you create a new `SavingsAccount` object, and it is always set to `0.04`. Clearly, setting the values of static data in a normal instance level constructor sort of defeats the whole purpose. Every time you make a new object, the class level data is reset! One approach to setting a static field is to use member initialization syntax, as you did originally:

```
class SavingsAccount
{
    public double currBalance;

    // A static point of data.
    public static double currInterestRate = 0.04;
    ...
}
```

This approach will ensure the static field is assigned only once, regardless of how many objects you create. However, what if the value for your static data needed to be obtained at runtime? For example, in a typical banking application, the value of an interest rate variable would be read from a database or external file. To perform such tasks requires a method scope such as a constructor to execute the code statements.

For this very reason, C# allows you to define a static constructor, which allows you to safely set the values of your static data. Consider the following update:

```
class SavingsAccount
{
    public double currBalance;
    public static double currInterestRate;

    public SavingsAccount(double balance)
    {
        currBalance = balance;
    }

    // A static constructor!
    static SavingsAccount()
    {
        Console.WriteLine("In static ctor!");
        currInterestRate = 0.04;
    }
    ...
}
```

Simply put, a static constructor is a special constructor that is an ideal place to initialize the values of static data when the value is not known at compile time (e.g., you need to read in the value from an external file or generate a random number). Here are a few points of interest regarding static constructors:

- A given class may define only a single static constructor. In other words, the static constructor cannot be overloaded.
- A static constructor does not take an access modifier and cannot take any parameters.

- A static constructor executes exactly one time, regardless of how many objects of the type are created.
- The runtime invokes the static constructor when it creates an instance of the class or before accessing the first static member invoked by the caller.
- The static constructor executes before any instance-level constructors.

Given this modification, when you create new `SavingsAccount` objects, the value of the static data is preserved, as the static member is set only one time within the static constructor, regardless of the number of objects created.

Defining Static Classes

It is also possible to apply the `static` keyword directly on the class level. When a class has been defined as static, it is not creatable using the `new` keyword, and it can contain only members or fields marked with the `static` keyword. If this is not the case, you receive compiler errors.

Note Class or structures that only expose static functionality are often termed utility classes. When designing a utility class, it is good practice to apply the `static` keyword to the class definition.

At first glance, this might seem like a fairly useless feature, given that a class that cannot be created does not appear all that helpful. However, if you create a class that contains nothing but static members and/or constant data, the class has no need to be allocated in the first place. Consider the following new static class type:

```
// Static classes can only
// contain static members!
static class TimeUtilClass
{
    public static void PrintTime()
    { Console.WriteLine(DateTime.Now.ToString()); }

    public static void PrintDate()
    { Console.WriteLine(DateTime.Today.ToString()); }
}
```

Given that this class has been defined with the `static` keyword, you cannot create an instance of `TimeUtilClass` using the `new` keyword. Rather, all functionality is exposed from the class level:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Static Data *****\n");

    // This is just fine.
    TimeUtilClass.PrintDate();
    TimeUtilClass.PrintTime();
```

```
// Compiler error! Can't create static classes!
TimeUtilClass u = new TimeUtilClass ();
...
}
```

Before the introduction of static class declaration (introduced in .NET 2.0), the only way to prevent the creation of a class that only exposed static functionality was to either redefine the default constructor using the `private` keyword or mark the class as an abstract type using the C# `abstract` keyword (full details regarding abstract types are in Chapter 6). Consider the following approaches:

```
class TimeUtilClass2
{
    // Redefine the default ctor as private
    // to prevent creation.
    private TimeUtilClass2 () {}

    public static void PrintTime()
    { Console.WriteLine(DateTime.Now.ToString()); }
    public static void PrintDate()
    { Console.WriteLine(DateTime.Today.ToString()); }
}

// Define type as abstract to prevent
// creation.
abstract class TimeUtilClass3
{
    public static void PrintTime()
    { Console.WriteLine(DateTime.Now.ToString()); }
    public static void PrintDate()
    { Console.WriteLine(DateTime.Today.ToString()); }
}
```

While these constructs are still permissible, the use of static classes is a cleaner solution and more type-safe, given that the previous two techniques allowed nonstatic members to appear within the class definition without error. This would be a big problem! If you had a class that was no longer creatable, you would have a chunk of functionality (e.g., all the non-static items) which could not be used!

At this point in the chapter you hopefully feel comfortable defining simple class types containing constructors, fields, and various static (and nonstatic) members. Now that you have the basics under your belt, you can formally investigate the three pillars of object-oriented programming.

Source Code The `StaticData` project is located under the Chapter 5 subdirectory.

Defining the Pillars of OOP

All object-based languages (C#, Java, C++, Smalltalk, Visual Basic, etc.) must contend with three core principals, often called the pillars of object-oriented programming (OOP):

- *Encapsulation*: How does this language hide an object's internal implementation details and preserve data integrity?
- *Inheritance*: How does this language promote code reuse?
- *Polymorphism*: How does this language let you treat related objects in a similar way?

Before digging into the syntactic details of each pillar, it is important that you understand the basic role of each. Here is an overview of each pillar, which will be examined in full detail over the remainder of this chapter and the next.

The Role of Encapsulation

The first pillar of OOP is called *encapsulation*. This trait boils down to the language's ability to hide unnecessary implementation details from the object user. For example, assume you are using a class named `DatabaseReader`, which has two primary methods named `Open()` and `Close()`:

```
// Assume this class encapsulates the details of opening and closing a database.
DatabaseReader dbReader = new DatabaseReader();
dbReader.Open(@"C:\AutoLot.mdf");

// Do something with data file and close the file.
dbReader.Close();
```

The fictitious `DatabaseReader` class encapsulates the inner details of locating, loading, manipulating, and closing the data file. Programmers love encapsulation, as this pillar of OOP keeps coding tasks simpler. There is no need to worry about the numerous lines of code that are working behind the scenes to carry out the work of the `DatabaseReader` class. All you do is create an instance and send the appropriate messages (e.g., “Open the file named `AutoLot.mdf` located on my C drive”).

Closely related to the notion of encapsulating programming logic is the idea of data protection. Ideally, an object's state data should be specified using the `private` (or possibly `protected`) keyword. In this way, the outside world must ask politely in order to change or obtain the underlying value. This is a good thing, as publicly declared data points can easily become corrupted (hopefully by accident rather than intent!). You will formally examine this aspect of encapsulation in just a bit.

The Role of Inheritance

The next pillar of OOP, *inheritance*, boils down to the language's ability to allow you to build new class definitions based on existing class definitions. In essence, inheritance allows you to extend the behavior of a base (or *parent*) class by inheriting core functionality into the derived subclass (also called a *child class*). Figure 5-4 shows a simple example.

You can read the diagram in Figure 5-4 as “A Hexagon is-a Shape that is-an Object.” When you have classes related by this form of inheritance, you establish “*is-a*” relationships between types. The “*is-a*” relationship is termed *inheritance*.

Here, you can assume that `Shape` defines some number of members that are common to all descendants (maybe a value to represent the color to draw the shape, and other values to represent the height and width). Given that the `Hexagon` class extends `Shape`, it inherits the core functionality defined by `Shape` and `Object`, as well as defines additional hexagon-related details of its own (whatever those may be).

Note Under the .NET platform, `System.Object` is always the topmost parent in any class hierarchy, which defines some general functionality for all types, fully described in Chapter 6.




Figure 5-4. The “is-a” relationship

There is another form of code reuse in the world of OOP: the containment/delegation model also known as the “has-a” relationship or aggregation. This form of reuse is not used to establish parent/child relationships. Rather, the “has-a” relationship allows one class to define a member variable of another class and expose its functionality (if required) to the object user indirectly.

For example, assume you are again modeling an automobile. You might want to express the idea that a car “has-a” radio. It would be illogical to attempt to derive the `Car` class from a `Radio`, or vice versa (a Car “is-a” Radio? I think not!). Rather, you have two independent classes working together, where the `Car` class creates and exposes the `Radio`’s functionality:

```

class Radio
{
    public void Power(bool turnOn)
    {
        Console.WriteLine("Radio on: {0}", turnOn);
    }
}

class Car
{
    // Car 'has-a' Radio.
    private Radio myRadio = new Radio();

    public void TurnOnRadio(bool onOff)
    {
        // Delegate call to inner object.
        myRadio.Power(onOff);
    }
}
  
```

Notice that the object user has no clue that the `Car` class is making use of an inner `Radio` object.

```
static void Main(string[] args)
{
    // Call is forwarded to Radio internally.
    Car viper = new Car();
    viper.TurnOnRadio(false);
}
```

The Role of Polymorphism

The final pillar of OOP is *polymorphism*. This trait captures a language's ability to treat related objects in a similar manner. Specifically, this tenant of an object-oriented language allows a base class to define a set of members (formally termed the *polymorphic interface*) that are available to all descendants. A class's polymorphic interface is constructed using any number of *virtual* or *abstract* members (see Chapter 6 for full details).

In a nutshell, a *virtual member* is a member in a base class that defines a default implementation that may be changed (or more formally speaking, *overridden*) by a derived class. In contrast, an *abstract method* is a member in a base class that does not provide a default implementation, but does provide a signature. When a class derives from a base class defining an abstract method, it *must* be overridden by a derived type. In either case, when derived types override the members defined by a base class, they are essentially redefining how they respond to the same request.

To preview polymorphism, let's provide some details behind the shapes hierarchy shown in Figure 5-5. Assume that the `Shape` class has defined a virtual method named `Draw()` that takes no parameters. Given the fact that every shape needs to render itself in a unique manner, subclasses such as `Hexagon` and `Circle` are free to override this method to their own liking (see Figure 5-5).




Figure 5-5. Classical polymorphism

Once a polymorphic interface has been designed, you can begin to make various assumptions in your code. For example, given that `Hexagon` and `Circle` derive from a common parent (`Shape`), an array of `Shape` types could contain anything deriving from this base class. Furthermore, given that `Shape` defines a polymorphic interface to all derived types (the `Draw()` method in this example), you can assume each member in the array has this functionality.

Consider the following `Main()` method, which instructs an array of `Shape`-derived types to render themselves using the `Draw()` method:

```
class Program
{
    static void Main(string[] args)
    {
        Shape[] myShapes = new Shape[3];
        myShapes[0] = new Hexagon();
        myShapes[1] = new Circle();
        myShapes[2] = new Hexagon();

        foreach (Shape s in myShapes)
        {
            // Use the polymorphic interface!
            s.Draw();
        }
        Console.ReadLine();
    }
}
```

This wraps up our brisk overview of the pillars of OOP. Now that you have the theory in your mind, the remainder of this chapter explores further details of how encapsulation is handled under C#. Chapter 6 will tackle the details of inheritance and polymorphism.

C# Access Modifiers

When working with encapsulation, you must always take into account which aspects of a type are visible to various parts of your application. Specifically, types (classes, interfaces, structures, enumerations, and delegates) as well as their members (properties, methods, constructors, and fields) are defined using a specific keyword to control how “visible” the item is to other parts of your application. Although C# defines numerous keywords to control access, they differ on where they can be successfully applied (type or member). Table 5-1 documents the role of each access modifier and where it may be applied.

Table 5-1. C# Access Modifiers

C# Access Modifier	May Be Applied To	Meaning in Life
<code>public</code>	Types or type members	Public items have no access restrictions. A public member can be accessed from an object as well as any derived class. A public type can be accessed from other external assemblies.
<code>private</code>	Type members or nested types	Private items can only be accessed by the class (or structure) that defines the item.

Table 5-1. C# Access Modifiers (continued)

C# Access Modifier	May Be Applied To	Meaning in Life
protected	Type members or nested types	Protected items can be used by the class which defines it, and any child class. However, protected items cannot be accessed from the outside world using the C# dot operator.
internal	Types or type members	Internal items are accessible only within the current assembly. Therefore, if you define a set of internal types within a .NET class library, other assemblies are not able to make use of them.
protected internal	Type members or nested types	When the protected and internal keywords are combined on an item, the item is accessible within the defining assembly, the defining class, and by derived classes.

In this chapter, you are only concerned with the public and private keywords. Later chapters will examine the role of the internal and protected internal modifiers (useful when you build .NET code libraries) and the protected modifier (useful when you are creating class hierarchies).

The Default Access Modifiers

By default, type members are *implicitly private* while types are *implicitly internal*. Thus, the following class definition is automatically set to internal, while the type's default constructor is automatically set to private:

```
// An internal class with a private default constructor.
class Radio
{
    Radio(){}
}
```

To allow other parts of a program to invoke members of an object, you must mark them as publicly accessible. As well, if you wish to expose the Radio to external assemblies (again, useful when building .NET code libraries; see Chapter 14) you will need to add the public modifier.

```
// A public class with a public default constructor.
public class Radio
{
    public Radio(){}
}
```

Access Modifiers and Nested Types

As mentioned in Table 5-1, the `private`, `protected`, and `internal` access modifiers can be applied to a *nested type*. Chapter 6 will examine nesting in detail. What you need to know at this point, however, is that a nested type is a type declared directly within the scope of class or structure. By way of example, here is a `private` enumeration (named `Color`) nested within a `public` class (named `SportsCar`):

```
public class SportsCar
{
    // OK! Nested types can be marked private.
    private enum CarColor
    {
        Red, Green, Blue
    }
}
```

Here, it is permissible to apply the `private` access modifier on the nested type. However, nonnested types (such as the `SportsCar`) can only be defined with the `public` or `internal` modifiers. Therefore, the following class definition is illegal:

```
// Error! Nonnested types cannot be marked private!
private class SportsCar
{}
```

Now that you have seen the access modifiers at work, you are ready to formally investigate the first pillar of OOP.

The First Pillar: C#'s Encapsulation Services

The concept of encapsulation revolves around the notion that an object's internal data should not be directly accessible from an object instance. Rather, if the caller wants to alter the state of an object, the user does so indirectly using accessor (i.e., "getter") and mutator (i.e., "setter") methods. In C#, encapsulation is enforced at the syntactic level using the `public`, `private`, `internal`, and `protected` keywords. To illustrate the need for encapsulation services, assume you have created the following class definition:

```
// A class with a single public field.
class Book
{
    public int numberOfPages;
}
```

The problem with public data is that the data itself has no ability to "understand" whether the current value to which they are assigned is valid with regard to the current business rules of the system. As you know, the upper range of a C# `int` is quite large (2,147,483,647). Therefore, the compiler allows the following assignment:

```
// Humm. That is one heck of a mini-novel!
static void Main(string[] args)
{
    Book miniNovel = new Book();
    miniNovel.numberOfPages = 30000000;
}
```

Although you have not overflowed the boundaries of an `int` data type, it should be clear that a mini-novel with a page count of 30,000,000 pages is a bit unreasonable. As you can see, public fields do not provide a way to trap logical upper (or lower) limits. If your current system has a business rule that states a book must be between 1 and 1,000 pages, you are at a loss to enforce this programmatically. Because of this, public fields typically have no place in a production-level class definition.

Note To be more specific, members of a class that represent an object's state should not be marked as public. As you will see later in this chapter, public constants and public read-only fields are a-okay.

Encapsulation provides a way to preserve the integrity of an object's state data. Rather than defining public fields (which can easily foster data corruption), you should get in the habit of defining *private data*, which is indirectly manipulated using one of two main techniques:

- Define a pair of accessor (get) and mutator (set) methods.
- Define a .NET property.

Whichever technique you choose, the point is that a well-encapsulated class should protect its data and hide the details of how it operates from the prying eyes of the outside world. This is often termed *black box programming*. The beauty of this approach is that an object is free to change how a given method is implemented under the hood. It does this without breaking any existing code making use of it, provided that the parameters and return values of the method remain constant.

Encapsulation Using Traditional Accessors and Mutators

Over the remaining pages in this chapter, you will be building a fairly complete class that models a general employee. To get the ball rolling, create a new Console Application named EmployeeApp and insert a new class file (named `Employee.cs`) using the Project ▶ Add class menu item. Update the `Employee` class with the following fields, methods, and constructors:

```
class Employee
{
    // Field data.
    private string empName;
    private int empID;
    private float currPay;

    // Constructors.
    public Employee() {}
    public Employee(string name, int id, float pay)
    {
        empName = name;
        empID = id;
        currPay = pay;
    }
}
```

```
// Methods.
public void GiveBonus(float amount)
{
    currPay += amount;
}
public void DisplayStats()
{
    Console.WriteLine("Name: {0}", empName);
    Console.WriteLine("ID: {0}", empID);
    Console.WriteLine("Pay: {0}", currPay);
}
```

Notice that the fields of the `Employee` class are currently defined using the `private` keyword. Given this, the `empName`, `empID`, and `currPay` fields are not directly accessible from an object variable:

```
static void Main(string[] args)
{
    // Error! Cannot directly access private members
    // from an object!
    Employee emp = new Employee();
    emp.empName = "Marv";
}
```

If you want the outside world to interact with a worker's full name, tradition dictates defining an accessor (get method) and a mutator (set method). The role of a 'get' method is to return to the caller the current value of the underlying state data. A 'set' method allows the caller to change the current value of the underlying state data, so long as the defined business rules are met.

To illustrate, let's encapsulate the `empName` field. To do so, add the following public methods to the `Employee` class. Notice that the `SetName()` method performs a test on the incoming data, to ensure the string is 15 characters or less. If it is not, an error prints to the console and returns without making a change to the `empName` field:

Note If this were a production level class, you would also make to check the character length for an employee's name within your constructor logic. Ignore this detail for the time being, you will clean up this code in just a bit when you examine .NET property syntax.

```
class Employee
{
    // Field data.
    private string empName;
    ...
    // Accessor (get method)
    public string GetName()
    {
        return empName;
    }
}
```

```
// Mutator (set method)
public void SetName(string name)
{
    // Do a check on incoming value
    // before making assignment.
    if (name.Length > 15)
        Console.WriteLine("Error! Name must be less than 16 characters!");
    else
        empName = name;
}
```

This technique requires two uniquely named methods to operate on a single data point. To test your new methods, update your `Main()` method as follows:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Encapsulation *****\n");
    Employee emp = new Employee("Marvin", 456, 30000);
    emp.GiveBonus(1000);
    emp.DisplayStats();

    // Use the get/set methods to interact with the object's name.
    emp.SetName("Marv");
    Console.WriteLine("Employee is named: {0}", emp.GetName());
    Console.ReadLine();
}
```

Because of the code in your `SetName()` method, if you attempted to specify more than 15 characters (see below), you would find the hard-coded error message print to the console:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Encapsulation *****\n");
    ...
    // Longer than 15 characters! Error will print to console.
    Employee emp2 = new Employee();
    emp2.SetName("Xena the warrior princess");

    Console.ReadLine();
}
```

So far so good. You have encapsulated the private `empName` field using two methods named `GetName()` and `SetName()`. If you were to further encapsulate the data in the `Employee` class, you would need to add various additional methods (`GetID()`, `SetID()`, `GetCurrentPay()`, `SetCurrentPay()` for example). Each of the mutator methods could have within it various lines of code to check for additional business rules. While this could certainly be done, the C# language has a useful alternative notation to encapsulate class data.

Encapsulation Using .NET Properties

Although you can encapsulate a piece of field data using traditional get and set methods, .NET languages prefer to enforce data encapsulation state data using *properties*. First of all, understand that properties are just a simplification for “real” accessor and mutator methods. Therefore, as a class designer, you are still able to perform any internal logic necessary before making the value assignment (e.g., uppercase the value, scrub the value for illegal characters, check the bounds of a numerical value, and so on).

Here is the updated Employee class, now enforcing encapsulation of each field using property syntax rather than traditional get and set methods:

```
class Employee
{
    // Field data.
    private string empName;
    private int empID;
    private float currPay;

    // Properties!
    public string Name
    {
        get { return empName; }
        set
        {
            if (value.Length > 15)
                Console.WriteLine("Error! Name must be less than 16 characters!");
            else
                empName = value;
        }
    }

    // We could add additional business rules to the sets of these properties,
    // however there is no need to do so for this example.
    public int ID
    {
        get { return empID; }
        set { empID = value; }
    }
    public float Pay
    {
        get { return currPay; }
        set { currPay = value; }
    }
    ...
}
```

A C# property is composed by defining a get scope (accessor) and set scope (mutator) directly within the property itself. Notice that the property specifies the type of data it is encapsulating by what appears to be a return value. Also take note that, unlike a method, properties do not make use of parentheses (not even empty parentheses) when being defined. Consider the commentary on your current ID property:

```
// The 'int' represents the type of data this property encapsulates.
// The data type must be identical to the related field (empID).
```

```
public int ID // Note lack of parentheses.
{
    get { return empID; }
    set { empID = value; }
}
```

Within a ‘set’ scope of a property, you use a token named `value`, which is used to represent the incoming value used to assign the property by the caller. This token is *not* a true C# keyword, but is what is known as a *contextual keyword*. When the token value is within the set scope of the property, it always represents the value being assigned by the caller, and it will always be the same underlying data type as the property itself. Thus, notice how the `Name` property can still test the range of the string as so:

```
public string Name
{
    get { return empName; }
    set
    {
        // Here, value is really a string.
        if (value.Length > 15)
            Console.WriteLine("Error! Name must be less than 16 characters!");
        else
            empName = value;
    }
}
```

Once you have these properties in place, it appears to the caller that it is getting and setting a *public point* of data; however, the correct get and set block is called behind the scenes to preserve encapsulation:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Encapsulation *****\n");
    Employee emp = new Employee("Marvin", 456, 30000);
    emp.GiveBonus(1000);
    emp.DisplayStats();

    // Set and get the Name property.
    emp.Name = "Marv";
    Console.WriteLine("Employee is named: {0}", emp.Name);
    Console.ReadLine();
}
```

Properties (as opposed to accessors and mutators) also make your types easier to manipulate, in that properties are able to respond to the intrinsic operators of C#. To illustrate, assume that the `Employee` class type has an internal private member variable representing the age of the employee. Here is the relevant update (notice the use of constructor chaining):

```
class Employee
{
    ...
    // New field and property.
    private int empAge;
    public int Age
    {
```

```

        get { return empAge; }
        set { empAge = value; }
    }

// Updated constructors
public Employee() {}
public Employee(string name, int id, float pay)
    :this(name, 0, id, pay){}

public Employee(string name, int age, int id, float pay)
{
    empName = name;
    empID = id;
    empAge = age;
    currPay = pay;
}

// Updated DisplayStats() method now accounts for age.
public void DisplayStats()
{
    Console.WriteLine("Name: {0}", empName);
    Console.WriteLine("ID: {0}", empID);
    Console.WriteLine("Age: {0}", empAge);
    Console.WriteLine("Pay: {0}", currPay);
}
}

```

Now assume you have created an `Employee` object named `joe`. On his birthday, you wish to increment the age by one. Using traditional accessor and mutator methods, you would need to write code such as the following:

```

Employee joe = new Employee();
joe.SetAge(joe.GetAge() + 1);

```

However, if you encapsulate `empAge` using a property named `Age`, you are able to simply write

```

Employee joe = new Employee();
joe.Age++;

```

Using Properties within a Class Definition

Properties, specifically the 'set' portion of a property, are common places to package up the business rules of your class. Currently, the `Employee` class has a `Name` property which ensures the name is no more than 15 characters. The remaining properties (ID, Pay and Age) could also be updated with any relevant logic.

While this is well and good, also consider what a class constructor typically does internally. It will take the incoming parameters, check for valid data, and then make assignments to the internal private fields. Currently your master constructor does *not* test the incoming string data for a valid range, so you could update this member as so:

```

public Employee(string name, int age, int id, float pay)
{

```

```

// Humm, this seems like a problem...
if (name.Length > 15)
    Console.WriteLine("Error! Name must be less than 16 characters!");
else
    empName = name;

empID = id;
empAge = age;
currPay = pay;
}

```

I am sure you can see the problem with this approach. The `Name` property and your master constructor are performing the same error checking! If you were also making checks on the other data points, you would have a good deal of duplicate code. To streamline your code, and isolate all of your error checking to a central location, you will do well if you *always* use properties within your class whenever you need to get or set the values. Consider the following updated constructor:

```

public Employee(string name, int age, int id, float pay)
{
    // Better! Use properties when setting class data.
    // This reduces the amount of duplicate error checks.
    Name = name;
    Age = age;
    ID = id;
    Pay = pay;
}

```

Beyond updating constructors to use properties when assigning values, it is good practice to use properties throughout a class implementation, to ensure your business rules are always enforced. In many cases, the only time when you directly make reference to the underlying private piece of data is within the property itself. With this in mind, here is your updated `Employee` class:

```

class Employee
{
    // Field data.
    private string empName;
    private int empID;
    private float currPay;
    private int empAge;

    // Constructors.
    public Employee() { }
    public Employee(string name, int id, float pay)
        :this(name, 0, id, pay){}
    public Employee(string name, int age, int id, float pay)
    {
        Name = name;
        Age = age;
        ID = id;
        Pay = pay;
    }

    // Methods.
    public void GiveBonus(float amount)

```

```

{ Pay += amount; }

public void DisplayStats()
{
    Console.WriteLine("Name: {0}", Name);
    Console.WriteLine("ID: {0}", ID);
    Console.WriteLine("Age: {0}", Age);
    Console.WriteLine("Pay: {0}", Pay);
}

// Properties as before...
...
}

```

Internal Representation of Properties

Many programmers who use traditional accessor and mutator methods, often name these methods using `get_` and `set_` prefixes (e.g., `get_Name()` and `set_Name()`). This naming convention itself is not problematic as far as C# is concerned. However, it is important to understand that under the hood, a property is represented in CIL code using this same naming convention.

For example, if you open up the `EmployeeApp.exe` assembly using `ildasm.exe`, you see that each property is mapped to hidden `get_XXX()`/`set_XXX()` methods called internally by the CLR (see Figure 5-6).




Figure 5-6. A property is represented by `get`/`set` methods internally

Assume the `Employee` type now has a private member variable named `empSSN` to represent an individual's Social Security number, which is manipulated by a property named `SocialSecurityNumber` (and also assume you have updated your type's custom constructor and `DisplayStats()` method to account for this new piece of field data).

```
// Add support for a new field representing the employee's SSN.
class Employee
{
...
    private string empSSN;
    public string SocialSecurityNumber
    {
        get { return empSSN; }
        set { empSSN = value; }
    }

    // Constructors
    public Employee() { }
    public Employee(string name, int id, float pay)
        :this(name, 0, id, pay, ""){}
    public Employee(string name, int age, int id, float pay, string ssn)
    {
        Name = name;
        Age = age;
        ID = id;
        Pay = pay;
        SocialSecurityNumber = ssn;
    }

    public void DisplayStats()
    {
        Console.WriteLine("Name: {0}", Name);
        Console.WriteLine("ID: {0}", ID);
        Console.WriteLine("Age: {0}", Age);
        Console.WriteLine("Pay: {0}", Pay);
        Console.WriteLine("SSN: {0}", SocialSecurityNumber);
    }
}
}
```

If you were to also define two methods named `get_SocialSecurityNumber()` and `set_SocialSecurityNumber()` in the same class, you would be issued compile-time errors:

```
// Remember, a property really maps to a get_/set_ pair!
class Employee
{
...
    public string get_SocialSecurityNumber()
    {
        return empSSN;
    }
    public void set_SocialSecurityNumber(string ssn)
```

```
{
    empSSN = ssn;
}
```

Note The .NET base class libraries always favor type properties over traditional accessor and mutator methods when encapsulating field data. Therefore, if you wish to build custom classes that integrate well with the .NET platform, avoid defining traditional get and set methods.

Controlling Visibility Levels of Property Get/Set Statements

Unless you say otherwise, the visibility of get and set logic is solely controlled by the access modifier of the property declaration:

```
// The get and set logic is both public,
// given the declaration of the property.
public string SocialSecurityNumber
{
    get { return empSSN; }
    set { empSSN = value; }
```

In some cases, it would be useful to specify unique accessibility levels for get and set logic. To do so, simply prefix an accessibility keyword to the appropriate get or set keyword (the unqualified scope takes the visibility of the property's declaration):

```
// Object users can only get the value, however
// the Employee class and derived types can set the value.
public string SocialSecurityNumber
{
    get { return empSSN; }
    protected set { empSSN = value; }
```

In this case, the set logic of SocialSecurityNumber can only be called by the current class and derived classes and therefore cannot be called from an object instance. Again, the protected keyword will be formally detailed in the next chapter when we examine inheritance and polymorphism.

Read-Only and Write-Only Properties

When encapsulating data, you may wish to configure a *read-only property*. To do so, simply omit the set block. Likewise, if you wish to have a *write-only property*, omit the get block. While there is no need to do so for the current example, here is how the SocialSecurityNumber property could be retrofitted as read-only:

```
public string SocialSecurityNumber
{
```

```
    get { return empSSN; }
}
```

Given this adjustment, the only manner in which an employee's US Social Security number can be set is through a constructor argument. Therefore, it would now be a compiler error to attempt to set an employee's SSN value within your master constructor:

```
public Employee(string name, int age, int id, float pay, string ssn)
{
    Name = name;
    Age = age;
    ID = id;
    Pay = pay;
    // OOPS! This is no longer possible if the property is read
    // only.
    SocialSecurityNumber = ssn;
}
```

If you did make this property read only, your only choice would be to use the underlying ssn member variable within your constructor logic.

Static Properties

C# also supports static properties. Recall from earlier in this chapter that static members are accessed at the class level, not from an instance (object) of that class. For example, assume that the Employee type defines a static point of data to represent the name of the organization employing these workers. You may encapsulate a static property as follows:

```
// Static properties must operate on static data!
class Employee
{
    ...
    private static string companyName;
    public static string Company
    {
        get { return companyName; }
        set { companyName = value; }
    }
    ...
}
```

Static properties are manipulated in the same manner as static methods, as shown here:

```
// Interact with the static property.
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Encapsulation *****\n");

    // Set company.
    Employee.Company = "My Company";
    Console.WriteLine("These folks work at {0}.", Employee.Company);

    Employee emp = new Employee("Marvin", 24, 456, 30000, "111-11-1111");
```

```

    emp.GiveBonus(1000);
    emp.DisplayStats();

    Console.ReadLine();
}

```

Finally, recall that classes can support static constructors. Thus, if you wanted to ensure that the name of the static `companyName` field was always assigned to “My Company,” you would write the following:

```

// Static constructors are used to initialize static data.
public class Employee
{
    private static companyName As string
    ...
    static Employee()
    {
        companyName = "My Company";
    }
}

```

Using this approach, there is no need to explicitly call the `Company` property to set the initial value:

```

// Automatically set to "My Company" via static constructor.
static void Main(string[] args)
{
    Console.WriteLine("These folks work at {0}", Employee.Company);
}

```

To wrap up the story thus far, recall that C# prefers properties to encapsulate data. These syntactic entities are used for the same purpose as traditional accessor (get)/mutator (set) methods. The benefit of properties is that the users of your objects are able to manipulate the internal data point using a single named item.

Source Code The `EmployeeApp` project can be found under the Chapter 5 subdirectory.

Understanding Automatic Properties

When .NET 3.5 was released, the C# language offered yet another way to define simple encapsulation services with minimal code, using *automatic property* syntax. To illustrate, create a new C# Console Application project named `AutoProps`. Now, insert a new C# class file (`Car.cs`) that defines the following class, which encapsulates a single point of data using classic property syntax.

```

// A Car type using standard property
// syntax.
class Car
{
    private string carName = string.Empty;
    public string PetName

```

```
{
    get { return carName; }
    set { carName = value; }
}
}
```

While it is very true that most C# properties contain business rules within their set scope, it is not too uncommon that some properties literally have nothing more to do than simply assign and return the value straightaway as you see here. In these cases, it can become rather verbose to define private backing fields and simple property definitions multiple times. By way of an example, if you are modeling a class that requires 15 private points of field data, you end up authoring 15 related properties that are little more than thin wrappers for encapsulation services.

To streamline the process of providing simple encapsulation of field data, you may use *automatic property syntax*. As the name implies, this feature will offload the work of defining a private backing field and the related C# property member to the compiler using a new bit of syntax. Consider the reworking of the Car class, which uses this syntax to quickly create three properties:

```
class Car
{
    // Automatic properties!
    public string PetName { get; set; }
    public int Speed { get; set; }
    public string Color { get; set; }
}
```

When defining automatic properties, you simply specify the access modifier, underlying data type, property name, and empty get/set scopes. At compile time, your type will be provided with an autogenerated private backing field and a fitting implementation of the get/set logic.

Note The name of the autogenerated private backing field is not visible within your C# code base. The only way to see it is to make use of a tool such as ildasm.exe.

Unlike traditional C# properties, however, it is *not* possible to build read-only or write-only automatic properties. While you might think you can just omit the get; or set; within your property declaration as follows:

```
// Read-only property? Error!
public int MyReadOnlyProp { get; }

// Write only property? Error!
public int MyWriteOnlyProp { set; }
```

this will result in a compiler error. When you are defining an automatic property, it must support both read and write functionality. However, it is possible to implement an automatic property which defines a more restrictive get or set:

```
// Public get, protected set!
// You could also set a get / set to private.
```

```
public int SomeOtherProperty { get; protected set; }
```

Interacting with Automatic Properties

Because the compiler will define the private backing field at compile time, the class defining automatic properties will always need to use property syntax to get and set the underlying value. This is important to note because many programmers make direct use of the private fields *within* a class definition, which is not possible in this case. For example, if the Car class were to provide a `DisplayStats()` method, it would need to implement this method using the property name:

```
class Car
{
    // Automatic properties!
    public string PetName { get; set; }
    public int Speed { get; set; }
    public string Color { get; set; }

    public void DisplayStats()
    {
        Console.WriteLine("Car Name: {0}", PetName);
        Console.WriteLine("Speed: {0}", Speed);
        Console.WriteLine("Color: {0}", Color);
    }
}
```

When you are using an object defined with automatic properties, you will be able to assign and obtain the values using the expected property syntax:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Automatic Properties *****\n");

    Car c = new Car();
    c.PetName = "Frank";
    c.Speed = 55;
    c.Color = "Red";

    Console.WriteLine("Your car is named {0}? That's odd...", 
        c.PetName);
    c.DisplayStats();

    Console.ReadLine();
}
```

Regarding Automatic Properties and Default Values

When you use automatic properties to encapsulate numerical or Boolean data, you are able to use the autogenerated type properties straightaway within your code base, as the hidden backing fields will be assigned a safe default value that can be used directly. However, be very aware that if you use automatic property syntax to wrap another class variable, the hidden private reference type will also be set to a default value of null.

Consider the following new class named Garage, which makes use of two automatic properties:

```
class Garage
{
    // The hidden int backing field is set to zero!
    public int NumberOfCars { get; set; }

    // The hidden Car backing field is set to null!
    public Car MyAuto { get; set; }
}
```

Given C#'s default values for field data, you would be able to print out the value of `NumberOfCars` as is (as it is automatically assigned the value of zero), but if you directly invoke `MyAuto`, you will receive a “null reference exception” at runtime, as the `Car` member variable used in the background has not been assigned to a new object:

```
static void Main(string[] args)
{
    ...
    Garage g = new Garage();

    // OK, prints default value of zero.
    Console.WriteLine("Number of Cars: {0}", g.NumberOfCars);

    // Runtime error! Backing field is currently null!
    Console.WriteLine(g.MyAuto.PetName);
    Console.ReadLine();
}
```

Given that the private backing fields are created at compile time, you will be unable to make use of C# field initialization syntax to allocate the reference type directly with the `new` keyword. Therefore, this work will need to be done with class constructors to ensure the object comes to life in a safe manner. For example:

```
class Garage
{
    // The hidden backing field is set to zero!
    public int NumberOfCars { get; set; }

    // The hidden backing field is set to null!
    public Car MyAuto { get; set; }

    // Must use constructors to override default
    // values assigned to hidden backing fields.
    public Garage()
    {
        MyAuto = new Car();
        NumberOfCars = 1;
    }
    public Garage(Car car, int number)
    {
        MyAuto = car;
        NumberOfCars = number;
    }
}
```

```
    }
}
```

With this update, you could now place a Car object into the Garage object as so:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Automatic Properties *****\n");

    // Make a car.
    Car c = new Car();
    c.PetName = "Frank";
    c.Speed = 55;
    c.Color = "Red";
    c.DisplayStats();

    // Put car in the garage.
    Garage g = new Garage();
    g.MyAuto = c;
    Console.WriteLine("Number of Cars in garage: {0}", g.NumberOfCars);
    Console.WriteLine("Your car is named: {0}", g.MyAuto.PetName);

    Console.ReadLine();
}
```

As you most likely agree, this is a very nice feature of the C# programming language, as you can define a number of properties for a class using a streamlined syntax. Be aware of course that if you are building a property that requires additional code beyond getting and setting the underlying private field (such as data validation logic, writing to an event log, communicating with a database, etc.), you will be required to define a “normal” .NET property type by hand. C# automatic properties never do more than provide simple encapsulation for an underlying piece of (compiler generated) private data.

■ Source Note The AutoProps project can be found under the Chapter 5 subdirectory.

Understanding Object Initializer Syntax

As seen throughout this chapter, a constructor allows you specify start up values when creating a new object. On a related note, properties allow you to get and set underlying data in a safe manner. When you are working with other people’s classes, including the classes found within the .NET base class library, it is not too uncommon to discover that there is not a single constructor which allows you to set every piece of underlying state data. Given this point, a programmer is typically forced to pick the best constructor possible, after which he or she makes assignments using a handful of provided properties.

To help streamline the process of getting an object up and running, C# offers *object initializer syntax*. Using this technique, it is possible to create a new object variable and assign a slew of properties and/or public fields in a few lines of code. Syntactically, an object initializer consists of a comma delimited list of specified values, enclosed by the { and } tokens. Each member in the initialization list maps to the name of a public field or public property of the object being initialized.

To see this syntax in action, create a new Console Application named ObjectInitializers. Now, consider a simple class named Point, created using automatic properties (which is not mandatory for this example, but helps us write some very concise code):

```
class Point
{
    public int X { get; set; }
    public int Y { get; set; }

    public Point(int xVal, int yVal)
    {
        X = xVal;
        Y = yVal;
    }
    public Point() { }

    public void DisplayStats()
    {
        Console.WriteLine("[{0}, {1}]", X, Y);
    }
}
```

Now consider how we can make Point objects using any of the following approaches:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Object Init Syntax *****\n");

    // Make a Point by setting each property manually.
    Point firstPoint = new Point();
    firstPoint.X = 10;
    firstPoint.Y = 10;
    firstPoint.DisplayStats();

    // Or make a Point via a custom constructor.
    Point anotherPoint = new Point(20, 20);
    anotherPoint.DisplayStats();

    // Or make a Point using object init syntax.
    Point finalPoint = new Point { X = 30, Y = 30 };
    finalPoint.DisplayStats();
    Console.ReadLine();
}
```

The final Point variable is not making use of a custom constructor (as one might do traditionally), but is rather setting values to the public X and Y properties. Behind the scenes, the type's default constructor is invoked, followed by setting the values to the specified properties. To this end, object initialization syntax is just shorthand notations for the syntax used to create a class variable using a default constructor, and setting the state data property by property.

Calling Custom Constructors with Initialization Syntax

The previous examples initialized Point types by implicitly calling the default constructor on the type:

```
// Here, the default constructor is called implicitly.
Point finalPoint = new Point { X = 30, Y = 30 };
```

If you wish to be very clear about this, it is permissible to explicitly call the default constructor as follows:

```
// Here, the default constructor is called explicitly.
Point finalPoint = new Point() { X = 30, Y = 30 };
```

Do be aware that when you are constructing a type using the new initialization syntax, you are able to invoke *any* constructor defined by the class. Our Point type currently defines a two-argument constructor to set the (x, y) position. Therefore, the following Point declaration results in an X value of 100 and a Y value of 100, regardless of the fact that our constructor arguments specified the values 10 and 16:

```
// Calling a custom constructor.
Point pt = new Point(10, 16) { X = 100, Y = 100 };
```

Given the current definition of your Point type, calling the custom constructor while using initialization syntax is not terribly useful (and more than a bit verbose). However, if your Point type provides a new constructor that allows the caller to establish a color (via a custom enum named PointColor), the combination of custom constructors and object initialization syntax becomes clear. Assume you have updated Point as follows:

```
public enum PointColor
{ LightBlue, BloodRed, Gold }

class Point
{
    public int X { get; set; }
    public int Y { get; set; }
    public PointColor Color { get; set; }

    public Point(int xVal, int yVal)
    {
        X = xVal;
        Y = yVal;
        Color = PointColor.Gold;
    }
    public Point(PointColor ptColor)
    {
        Color = ptColor;
    }
    public Point()
        : this(PointColor.BloodRed){ }

    public void DisplayStats()
    {
        Console.WriteLine("[{0}, {1}]", X, Y);
        Console.WriteLine("Point is {0}", Color);
    }
}
```

```
    }
}
```

With this new constructor, you can now create a golden point (positioned at 90, 20) as follows:

```
// Calling a more interesting custom constructor with init syntax.
Point goldPoint = new Point(PointColor.Gold){ X = 90, Y = 20 };
Console.WriteLine("Value of Point is: {0}", goldPoint.DisplayStats());
```

Initializing Inner Types

As briefly mentioned earlier in this chapter (and fully examined in Chapter 6), the “has-a” relationship allows us to compose new classes by defining member variables of existing classes. For example, assume you now have a `Rectangle` class, which makes use of the `Point` type to represent its upper-left/bottom-right coordinates. Since automatic properties set all internal class variables to `null`, you will implement this new class using ‘traditional’ property syntax:

```
class Rectangle
{
    private Point topLeft = new Point();
    private Point bottomRight = new Point();

    public Point TopLeft
    {
        get { return topLeft; }
        set { topLeft = value; }
    }
    public Point BottomRight
    {
        get { return bottomRight; }
        set { bottomRight = value; }
    }

    public void DisplayStats()
    {
        Console.WriteLine("[TopLeft: {0}, {1}, {2} BottomRight: {3}, {4}, {5}]",
            topLeft.X, topLeft.Y, topLeft.Color,
            bottomRight.X, bottomRight.Y, bottomRight.Color);
    }
}
```

Using object initialization syntax, you could create a new `Rectangle` variable and set the inner `Points` as follows:

```
// Create and initialize a Rectangle.
Rectangle myRect = new Rectangle
{
    TopLeft = new Point { X = 10, Y = 10 },
    BottomRight = new Point { X = 200, Y = 200}
};
```

Again, the benefit of object initialization syntax is that it basically decreases the number of keystrokes (assuming there is not a suitable constructor). Here is the traditional approach to establishing a similar Rectangle:

```
// Old-school approach.
Rectangle r = new Rectangle();
Point p1 = new Point();
p1.X = 10;
p1.Y = 10;
r.TopLeft = p1;
Point p2 = new Point();
p2.X = 200;
p2.Y = 200;
r.BottomRight = p2;
```

While you might feel object initialization syntax can take a bit of getting used to, once you get comfortable with the code, you'll be quite pleased at how quickly you can establish the state of a new object with minimal fuss and bother.

To wrap up this chapter, allow me to close with three bite-sized topics which will round out your understanding of building well encapsulated classes, specifically constant data, read only fields, and partial class definitions.

■ Source Note The ObjectInitializers project can be found under the Chapter 5 subdirectory.

Working with Constant Field Data

C# offers the `const` keyword to define constant data, which can never change after the initial assignment. As you might guess, this can be helpful when you are defining a set of known values for use in your applications that are logically connected to a given class or structure.

Assume you are building a utility class named `MyMathClass` that needs to define a value for the value `PI` (which you will assume to be 3.14). Begin by creating a new Console Application project named `ConstData`. Given that you would not want to allow other developers to change this value in code, `PI` could be modeled with the following constant:

```
namespace ConstData
{
    class MyMathClass
    {
        public const double PI = 3.14;
    }

    class Program
    {
        static void Main(string[] args)
        {
            Console.WriteLine("***** Fun with Const *****\n");
            Console.WriteLine("The value of PI is: {0}", MyMathClass.PI);
        }
    }
}
```

```

    // Error! Can't change a constant!
    // MyMathClass.PI = 3.1444;

    Console.ReadLine();
}
}
}

```

Notice that you are referencing the constant data defined by `MyMathClass` using a class name prefix (i.e., `MyMathClass.PI`). This is due to the fact that constant fields of a class are implicitly *static*. However, it is permissible to define and access a local constant variable within a type member. By way of example:

```

static void LocalConstStringVariable()
{
    // A local constant data point can be directly accessed.
    const string fixedStr = "Fixed string Data";
    Console.WriteLine(fixedStr);

    // Error!
    fixedStr = "This will not work!";
}

```

Regardless of where you define a constant piece of data, the one point to always remember is that the initial value assigned to the constant must be specified at the time you define the constant. Thus, if you were to modify your `MyMathClass` in such a way that the value of PI is assigned in a class constructor as follows:

```

class MyMathClass
{
    // Try to set PI in ctor?
    public const double PI;

    public MyMathClass()
    {
        // Error!
        PI = 3.14;
    }
}

```

you would receive a compile-time error. The reason for this restriction has to do with the fact the value of constant data must be known at compile time. Constructors, as you know, are invoked at runtime.

Understanding Read-Only Fields

Closely related to constant data is the notion of *read-only field data* (which should not be confused with a read-only property). Like a constant, a read-only field cannot be changed after the initial assignment. However, unlike a constant, the value assigned to a read-only field can be determined at runtime, and therefore can legally be assigned within the scope of a constructor, but nowhere else.

This can be very helpful when you don't know the value of a field until runtime, perhaps because you need to read an external file to obtain the value, but wish to ensure that the value will not change after that point. For the sake of illustration, assume the following update to `MyMathClass`:

```
class MyMathClass
{
    // Read-only fields can be assigned in ctors,
    // but nowhere else.
    public readonly double PI;

    public MyMathClass ()
    {
        PI = 3.14;
    }
}
```

Again, any attempt to make assignments to a field marked `readonly` outside the scope of a constructor results in a compiler error:

```
class MyMathClass
{
    public readonly double PI;
    public MyMathClass ()
    {
        PI = 3.14;
    }

    // Error!
    public void ChangePI()
    { PI = 3.14444; }
}
```

Static Read-Only Fields

Unlike a constant field, read-only fields are *not* implicitly static. Thus, if you wish to expose PI from the class level, you must explicitly make use of the `static` keyword. If you know the value of a static read-only field at compile time, the initial assignment looks very similar to that of a constant:

```
class MyMathClass
{
    public static readonly double PI = 3.14;

class Program
{
    static void Main(string[] args)
    {
        Console.WriteLine("***** Fun with Const *****");
        Console.WriteLine("The value of PI is: {0}", MyMathClass.PI);
        Console.ReadLine();
    }
}
```

However, if the value of a static read-only field is not known until runtime, you must make use of a static constructor as described earlier in this chapter:

```
class MyMathClass
{
    public static readonly double PI;

    static MyMathClass()
    { PI = 3.14; }
}
```

Source Code The ConstData project is included under the Chapter 5 subdirectory.

Understanding Partial Types

Last but not least, it is important to understand the role of the C# `partial` keyword. A production level class could very easily consist of hundreds and hundreds of lines of code. As well, given that a typical class is defined within a single *.cs file, you could end up with a very long file indeed. When you are creating your classes, it is often the case that much of the code can be basically ignored once accounted for. For example, field data, properties, and constructors tend to remain as-is during production, while methods tend to be modified quite often.

If you wish, you can partition a single class across multiple C# files, to isolate the boilerplate code from more readily useful members. To illustrate, open up the EmployeeApp project you created previously in this chapter into Visual Studio, and once you have done so, open the `Employee.cs` file for editing. Currently, this single file contains code of all aspects of the class:

```
class Employee
{
    // Field Data

    // Constructors

    // Methods

    // Properties
}
```

Using partial classes, you could choose to move the constructors and field data into a brand new file named `Employee.Internal.cs` (please note, the name of the file is irrelevant; here I just tacked on the work `internal` to represent the guts of the class). The first step is to add the `partial` keyword to the current class definition and cut the code to be placed into the new file:

```
// Employee.cs
partial class Employee
{
    // Methods

    // Properties
}
```

Next, assuming you have inserted a new class file into your project, you can move the data fields and constructors to the new file using a simple cut/paste operation. In addition, you *must* add the `partial` keyword to this aspect of the class definition. For example:

```
// Employee.Internal.cs
partial class Employee
{
    // Field data

    // Constructors
}
```

■ **Note** Remember! Every aspect of a partial class definition must be marked with the `partial` keyword.

Once you compile the modified project, you should see no difference whatsoever. The whole idea of a partial class is only realized during design time. Once the application has been compiled, there is just a single, unified class within the assembly. The only requirement when defining partial types is that the type's name (`Employee` in this case) is identical and defined within the same .NET namespace.

To be honest, you will most likely not need to make use of partial class definitions too often. However, Visual Studio uses them in the background all the time. Later in this book when you start to look into GUI application development in Windows Forms, Windows Presentation Foundation, or ASP.NET, you'll see that Visual Studio isolates designer generated code into a partial class, leaving you to focus on your application specific programming logic.

■ **Source Code** The `EmployeeApp` project can be found under the Chapter 5 subdirectory.

Summary

The point of this chapter was to introduce you to the role of the C# class type. As you have seen, classes can take any number of *constructors* that enable the object user to establish the state of the object upon creation. This chapter also illustrated several class design techniques (and related keywords). Recall that the `this` keyword can be used to obtain access to the current object, the `static` keyword allows you to define fields and members that are bound at the class (not object) level, and the `const` keyword (and `readonly` modifier) allows you to define a point of data that can never change after the initial assignment.

The bulk of this chapter dug into the details of the first pillar of OOP: encapsulation. Here you learned about the access modifiers of C# and the role of type properties, object initialization syntax, and partial classes. With this behind you, you are now able to turn to the next chapter where you will learn to build a family of related classes using inheritance and polymorphism.

CHAPTER 6



Understanding Inheritance and Polymorphism

The previous chapter examined the first pillar of OOP: encapsulation. At that time, you learned how to build a single well-defined class type with constructors and various members (fields, properties, constants, and read-only fields). This chapter will focus on the remaining two pillars of OOP: inheritance and polymorphism.

First, you will learn how to build families of related classes using *inheritance*. As you will see, this form of code reuse allows you to define common functionality in a parent class that can be leveraged, and possibly altered, by child classes. Along the way, you will learn how to establish a *polymorphic interface* into the class hierarchies using virtual and abstract members. I wrap up by examining the role of the ultimate parent class in the .NET base class libraries: `System.Object`.

The Basic Mechanics of Inheritance

Recall from the previous chapter that inheritance is the aspect of OOP that facilitates code reuse. Specifically speaking, code reuse comes in two flavors: inheritance (the “is-a” relationship) and the containment/delegation model (the “has-a” relationship). Let’s begin this chapter by examining the classical “is-a” inheritance model.

When you establish “is-a” relationships between classes, you are building a dependency between two or more class types. The basic idea behind classical inheritance is that new classes can be created using existing classes as a starting point. To begin with a very simple example, create a new Console Application project named `BasicInheritance`. Now assume you have designed a class named `Car` that models some basic details of an automobile:

```
// A simple base class.  
class Car  
{  
    public readonly int maxSpeed;  
    private int currSpeed;  
  
    public Car(int max)  
    {  
        maxSpeed = max;  
    }  
    public Car()  
    {
```

```

    maxSpeed = 55;
}

public int Speed
{
    get { return currSpeed; }
    set
    {
        currSpeed = value;
        if (currSpeed > maxSpeed)
        {
            currSpeed = maxSpeed;
        }
    }
}
}

```

Notice that the `Car` class is making use of encapsulation services to control access to the private `currSpeed` field using a public property named `Speed`. At this point, you can exercise your `Car` type as follows:

```

static void Main(string[] args)
{
    Console.WriteLine("***** Basic Inheritance *****\n");
    // Make a Car object and set max speed.
    Car myCar = new Car(80);

    // Set the current speed, and print it.
    myCar.Speed = 50;
    Console.WriteLine("My car is going {0} MPH", myCar.Speed);
    Console.ReadLine();
}

```

Specifying the Parent Class of an Existing Class

Now assume you wish to build a new class named `MiniVan`. Like a basic `Car`, you wish to define the `MiniVan` class to support a maximum speed, current speed, and a property named `Speed` to allow the object user to modify the object's state. Clearly, the `Car` and `MiniVan` classes are related; in fact, it can be said that a `MiniVan` “*is-a*” `Car`. The “*is-a*” relationship (formally termed *classical inheritance*) allows you to build new class definitions that extend the functionality of an existing class.

The existing class that will serve as the basis for the new class is termed a base or parent class. The role of a base class is to define all the common data and members for the classes that extend it. The extending classes are formally termed derived or child classes. In C#, you make use of the colon operator on the class definition to establish an “*is-a*” relationship between classes:

```

// MiniVan 'is-a' Car.
class MiniVan : Car
{
}

```

What have you gained by extending your `MiniVan` from the `Car` base class? Simply put, `MiniVan` objects now have access to each public member defined within the parent class.

■ **Note** Although constructors are typically defined as public, a derived class never inherits the constructors of a parent class.

Given the relation between these two class types, you could now make use of the `MiniVan` class like so:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Basic Inheritance *****\n");
    ...
    // Now make a MiniVan object.
    MiniVan myVan = new MiniVan();
    myVan.Speed = 10;
    Console.WriteLine("My van is going {0} MPH",
        myVan.Speed);
    Console.ReadLine();
}
```

Notice that although you have not added any members to the `MiniVan` class, you have direct access to the public `Speed` property of your parent class, and have thus reused code. This is a far better approach than creating a `MiniVan` class that has the exact same members as `Car` such as a `Speed` property. If you did duplicate code between these two classes, you would need to now maintain two bodies of code, which is certainly a poor use of your time.

Always remember, that inheritance preserves encapsulation; therefore, the following code results in a compiler error, as private members can never be accessed from an object reference.

```
static void Main(string[] args)
{
    Console.WriteLine("***** Basic Inheritance *****\n");
    ...
    // Make a MiniVan object.
    MiniVan myVan = new MiniVan();
    myVan.Speed = 10;
    Console.WriteLine("My van is going {0} MPH",
        myVan.Speed);

    // Error! Can't access private members!
    myVan.currSpeed = 55;
    Console.ReadLine();
}
```

On a related note, if the `MiniVan` defined its own set of members, it would not be able to access any private member of the `Car` base class. Again, private members can *only* be accessed by the class that defines it.

```
// MiniVan derives from Car.
class MiniVan : Car
{
    public void TestMethod()
```

```
{
    // OK! Can access public members
    // of a parent within a derived type.
    Speed = 10;

    // Error! Cannot access private
    // members of parent within a derived type.
    currSpeed = 10;
}
}
```

Regarding Multiple Base Classes

Speaking of base classes, it is important to keep in mind that C# demands that a given class have exactly *one* direct base class. It is not possible to create a class type that directly derives from two or more base classes (this technique [which is supported in unmanaged C++]) is known as *multiple inheritance*, or simply *MI*). If you attempted to create a class that specifies two direct parent classes as shown in the following code, you will receive compiler errors.

```
// Illegal! The .NET platform does not allow
// multiple inheritance for classes!
class WontWork
    : BaseClassOne, BaseClassTwo
{}
```

As examined in Chapter 9, the .NET platform does allow a given class, or structure, to implement any number of discrete interfaces. In this way, a C# type can exhibit a number of behaviors while avoiding the complexities associated with MI. On a related note, while a class can have only one direct base class, it is permissible for an interface to directly derive from multiple interfaces. Using this technique, you can build sophisticated interface hierarchies that model complex behaviors (again, see Chapter 9).

The sealed Keyword

C# supplies another keyword, *sealed*, that prevents inheritance from occurring. When you mark a class as *sealed*, the compiler will not allow you to derive from this type. For example, assume you have decided that it makes no sense to further extend the *MiniVan* class:

```
// The MiniVan class cannot be extended!
sealed class MiniVan : Car
{}
```

If you (or a teammate) were to attempt to derive from this class, you would receive a compile-time error:

```
// Error! Cannot extend
// a class marked with the sealed keyword!
class DeluxeMiniVan
    : MiniVan
{}
```

Most often, sealing a class makes the best sense when you are designing a utility class. For example, the `System` namespace defines numerous sealed classes. You can verify this for yourself by opening up the Visual Studio 2010 Object Browser (via the View menu) and selecting the `String` class within the `System` namespace of the `mscorlib.dll` assembly. Notice in Figure 6-1 the use of the `sealed` keyword seen within the Summary window.




Figure 6-1. The base class libraries define numerous sealed types

Thus, just like the `Minivan`, if you attempted to build a new class that extends `System.String`, you will receive a compile-time error:

```
// Another error! Cannot extend
// a class marked as sealed!
class MyString
    : String
{}
```

Note In Chapter 4 you learned that C# structures are always implicitly sealed (see Table 4-3). Therefore, you can never derive one structure from another structure, a class from a structure or a structure from a class. Structures can only be used to model standalone, atomic, user defined-data types. If you wish to leverage the Is-A relationship, you must use classes.

As you would guess, there are many more details to inheritance that you will come to know during the remainder of this chapter. For now, simply keep in mind that the colon operator allows you to establish base/derived class relationships, while the `sealed` keyword prevents subsequent inheritance from occurring.

Revising Visual Studio Class Diagrams

In Chapter 2, I briefly mentioned that Visual Studio 2010 allows you to establish base/derived class relationships visually at design time. To leverage this aspect of the IDE, your first step is to include a new class diagram file into your current project. To do so, access the Project ▶ Add New Item menu option and select the Class Diagram icon (in Figure 6-2, I renamed the file from *ClassDiagram1.cd* to *Cars.cd*).




Figure 6-2. Inserting a new class diagram

Once you click the Add button, you will be presented with a blank designer surface. To add types to a class designer, simply drag each file from the Solution Explorer window onto the surface. Also recall that if you delete an item from the visual designer (simply by selecting it and pressing the Delete key), this will not destroy the associated source code, but simply removes the item off the designer surface. The current class hierarchy is shown in Figure 6-3.




Figure 6-3. The visual designer of Visual Studio

■ **Note** As a shortcut, if you wish to automatically add all of your project's current types to a designer surface, select the Project node within the Solution Explorer and then click the View Class Diagram button in the upper right of the Solution Explorer window.

Beyond simply displaying the relationships of the types within your current application, recall from Chapter 2 that you can also create brand new types and populate their members using the Class Designer toolbox and Class Details window.

If you wish to make use of these visual tools during the remainder of the book, feel free. However, always make sure you analyze the generated code so you have a solid understanding of what these tools have done on your behalf.

■ **Source Code** The BasicInheritance project is located under the Chapter 6 subdirectory.

The Second Pillar of OOP: The Details of Inheritance

Now that you have seen the basic syntax of inheritance, let's create a more complex example and get to know the numerous details of building class hierarchies. To do so, you will be reusing the Employee class you designed in Chapter 5. To begin, create a brand new C# Console Application named Employees.

Next, activate the Project ► Add Existing Item menu option and navigate to the location of your Employee.cs and Employee.Internals.cs files you created in the EmployeeApp example of previous chapter. Select each of them (via a Ctrl-click) and click the Add button. Visual Studio 2010 responds by copying each file into the current project.

Before you start to build some derived classes, you have one detail to attend to. Because the original Employee class was created in a project named EmployeeApp, the class has been wrapped within an identically named .NET namespace. Chapter 14 will examine namespaces in detail; however, for simplicity, rename the current namespace (in both file locations) to Employees in order to match your new project name:

```
// Be sure to change the namespace name in both C# files!
namespace Employees
{
    partial class Employee
    {...}
}
```

■ **Note** As a sanity check, compile and run your new project by pressing Ctrl+F5. The program will not do anything at this point; however, this will ensure you do not have any compiler errors.

Your goal is to create a family of classes that model various types of employees in a company. Assume that you wish to leverage the functionality of the Employee class to create two new classes (SalesPerson and Manager). The class hierarchy you will be building initially over the next several pages looks something like what you see in Figure 6-4 (be aware that you will not see individual fields in your diagram if you make use of C# automatic property syntax).




Figure 6-4. The initial Employees hierarchy

As illustrated in Figure 6-4, you can see that a SalesPerson “is-a” Employee (as is a Manager). Remember that under the classical inheritance model, base classes (such as Employee) are used to define general characteristics that are common to all descendants. Subclasses (such as SalesPerson and Manager) extend this general functionality while adding more specific functionality.

For your example, you will assume that the Manager class extends Employee by recording the number of stock options, while the SalesPerson class maintains the number of sales made. Insert a new class file (Manager.cs) that defines the Manager class with the following automatic property:

```
// Managers need to know their number of stock options.
class Manager : Employee
{
    public int StockOptions { get; set; }
}
```

Next, add another new class file (SalesPerson.cs) that defines the SalesPerson class with a fitting automatic property:

```
// Salespeople need to know their number of sales.
class SalesPerson : Employee
{
```

```
    public int SalesNumber { get; set; }
}
```

Now that you have established an “is-a” relationship, `SalesPerson` and `Manager` have automatically inherited all public members of the `Employee` base class. To illustrate, update your `Main()` method as follows:

```
// Create a subclass object and access base class functionality.
static void Main(string[] args)
{
    Console.WriteLine("***** The Employee Class Hierarchy *****\n");
    SalesPerson danny = new SalesPerson();
    danny.Age = 31;
    danny.Name = "Danny";
    danny.SalesNumber = 50;
    Console.ReadLine();
}
```

Controlling Base Class Creation with the `base` Keyword

Currently, `SalesPerson` and `Manager` can only be created using the freebie default constructor (see Chapter 5). With this in mind, assume you have added a new six-argument constructor to the `Manager` type, which is invoked as follows:

```
static void Main(string[] args)
{
    ...
    // Assume Manager has a constructor matching this signature:
    // (string fullName, int age, int empID,
    // float currPay, string ssn, int numbOfOpts)
    Manager chucky = new Manager("Chucky", 50, 92, 100000, "333-23-2322", 9000);
    Console.ReadLine();
}
```

If you look at the parameter list, you can clearly see that most of these arguments should be stored in the member variables defined by the `Employee` base class. To do so, you might implement this custom constructor on the `Manager` class as follows:

```
public Manager(string fullName, int age, int empID,
               float currPay, string ssn, int numbOfOpts)
{
    // This property is defined by the Manager class.
    StockOptions = numbOfOpts;

    // Assign incoming parameters using the
    // inherited properties of the parent class.
    ID = empID;
    Age = age;
    Name = fullName;
    Pay = currPay;
```

```

// OOPS! This would be a compiler error,
// if the SSN property were read-only!
SocialSecurityNumber = ssn;
}

```

The first issue with this approach is that if you defined any property as read-only (for example, the `SocialSecurityNumber` property), you are unable to assign the incoming `string` parameter to this field, as seen in the final code statement of this custom constructor.

The second issue is that you have indirectly created a rather inefficient constructor, given the fact that under C#, unless you say otherwise, the default constructor of a base class is called automatically before the logic of the derived constructor is executed. After this point, the current implementation accesses numerous public properties of the `Employee` base class to establish its state. Thus, you have really made seven hits (five inherited properties and two constructor calls) during the creation of a `Manager` object!

To help optimize the creation of a derived class, you will do well to implement your subclass constructors to explicitly call an appropriate custom base class constructor, rather than the default. In this way, you are able to reduce the number of calls to inherited initialization members (which saves processing time). Let's retrofit the custom constructor of the `Manager` type to do this very thing using the `base` keyword:

```

public Manager(string fullName, int age, int empID,
               float currPay, string ssn, int numbOfOpts)
    : base(fullName, age, empID, currPay, ssn)
{
    // This property is defined by the Manager class.
    StockOptions = numbOfOpts;
}

```

Here, the `base` keyword is hanging off the constructor signature (much like the syntax used to chain constructors on a single class using the `this` keyword as was discussed in see Chapter 5), which always indicates a derived constructor is passing data to the immediate parent constructor. In this situation, you are explicitly calling the five-parameter constructor defined by `Employee` and saving yourself unnecessary calls during the creation of the child class. The custom `SalesPerson` constructor looks almost identical:

```

// As a general rule, all subclasses should explicitly call an appropriate
// base class constructor.
public SalesPerson(string fullName, int age, int empID,
                   float currPay, string ssn, int numbOfSales)
    : base(fullName, age, empID, currPay, ssn)
{
    // This belongs with us!
    SalesNumber = numbOfSales;
}

```

Note You may use the `base` keyword anytime a subclass wishes to access a public or protected member defined by a parent class. Use of this keyword is not limited to constructor logic. You will see examples using `base` in this manner during the examination of polymorphism later in this chapter.

Finally, recall that once you add a custom constructor to a class definition, the default constructor is silently removed. Therefore, be sure to redefine the default constructor for the SalesPerson and Manager types, for example:

```
// Add back the default ctor
// in the Manager class as well.
public SalesPerson() {}
```

Keeping Family Secrets: The protected Keyword

As you already know, public items are directly accessible from anywhere, while private items can only be accessed by the class that has defined it. Recall from Chapter 5 that C# takes the lead of many other modern object languages and provides an additional keyword to define member accessibility: `protected`.

When a base class defines protected data or protected members, it establishes a set of items that can be accessed directly by any descendent. If you wish to allow the SalesPerson and Manager child classes to directly access the data sector defined by Employee, you can update the original Employee class definition as follows:

```
// protected state data.
partial class Employee
{
    // Derived classes can now directly access this information.
    protected string empName;
    protected int empID;
    protected float currPay;
    protected int empAge;
    protected string empSSN;
    protected static string companyName;

    ...
}
```

The benefit of defining protected members in a base class is that derived types no longer have to access the data indirectly using public methods or properties. The possible downfall, of course, is that when a derived type has direct access to its parent's internal data, it is very possible to accidentally bypass existing business rules found within public properties. When you define protected members, you are creating a level of trust between the parent and child class, as the compiler will not catch any violation of your type's business rules.

Finally, understand that as far as the object user is concerned, protected data is regarded as private (as the user is "outside" of the family). Therefore, the following is illegal:

```
static void Main(string[] args)
{
    // Error! Can't access protected data from object instance.
    Employee emp = new Employee();
    emp.empName = "Fred";
}
```

Note Although protected field data can break encapsulation, it is quite safe (and useful) to define protected methods. When building class hierarchies, it is very common to define a set of methods that are only for use by derived types.

Adding a Sealed Class

Recall that a *sealed* class cannot be extended by other classes. As mentioned, this technique is most often used when you are designing a utility class. However, when building class hierarchies, you might find that a certain branch in the inheritance chain should be “capped off,” as it makes no sense to further extend the lineage. For example, assume you have added yet another class to your program (`PTSalesPerson`) that extends the existing `SalesPerson` type. Figure 6-5 shows the current update.




Figure 6-5. The `PTSalesPerson` class

`PTSalesPerson` is a class representing, of course, a part-time salesperson. For the sake of argument, let's say that you wish to ensure that no other developer is able to subclass from `PTSalesPerson`. (After all, how much more part-time can you get than “part-time”?) Again, to prevent others from extending a class, make use of the `sealed` keyword:

```

sealed class PTSalesPerson : SalesPerson
{
    public PTSalesPerson(string fullName, int age, int empID,
                         float currPay, string ssn, int numbfSales)
        :base (fullName, age, empID, currPay, ssn, numbfSales)
    {
    }
    // Assume other members here...
}
  
```

Given that sealed classes cannot be extended, you may wonder if it is possible to reuse the functionality found within a class marked sealed? Glad you asked! If you wish to build a new class that leverages the functionality of a sealed class, your one option is to make use of the containment/delegation model (aka the “has-a” relationship).

Programming for Containment/Delegation

Recall that code reuse comes in two flavors. You have just explored the classical “is-a” relationship. Before you examine the third pillar of OOP (polymorphism), let’s examine the “has-a” relationship (also known as the *containment/delegation model* or *aggregation*). Assume you have created a new class that models an employee benefits package:

```
// This new type will function as a contained class.
class BenefitPackage
{
    // Assume we have other members that represent
    // dental/health benefits, and so on.
    public double ComputePayDeduction()
    {
        return 125.0;
    }
}
```

Obviously, it would be rather odd to establish an “is-a” relationship between the BenefitPackage class and the employee types. (Employee “is-a” BenefitPackage? I don’t think so.) However, it should be clear that some sort of relationship between the two could be established. In short, you would like to express the idea that each employee “has-a” BenefitPackage. To do so, you can update the Employee class definition as follows:

```
// Employees now have benefits.
partial class Employee
{
    // Contain a BenefitPackage object.
    protected BenefitPackage empBenefits = new BenefitPackage();
...
}
```

At this point, you have successfully contained another object. However, to expose the functionality of the contained object to the outside world requires delegation. *Delegation* is simply the act of adding public members to the containing class that make use of the contained object’s functionality.

For example, you could update the Employee class to expose the contained empBenefits object using a custom property as well as make use of its functionality internally using a new method named GetBenefitCost():

```
public partial class Employee
{
    // Contain a BenefitPackage object.
    protected BenefitPackage empBenefits = new BenefitPackage();

    // Expose certain benefit behaviors of object.
    public double GetBenefitCost()
```

```

{ return empBenefits.ComputePayDeduction(); }

// Expose object through a custom property.
public BenefitPackage Benefits
{
    get { return empBenefits; }
    set { empBenefits = value; }
}
...
}

```

In the following updated `Main()` method, notice how you can interact with the internal `BenefitsPackage` type defined by the `Employee` type:

```

static void Main(string[] args)
{
    Console.WriteLine("***** The Employee Class Hierarchy *****\n");
    Manager chucky = new Manager("Chucky", 50, 92, 100000, "333-23-2322", 9000);
    double cost = chucky.GetBenefitCost();
    Console.ReadLine();
}

```

Understanding Nested Type Definitions

The previous chapter briefly mentioned the concept of nested types, which is a spin on the “has-a” relationship you have just examined. In C# (as well as other .NET languages), it is possible to define a type (enum, class, interface, struct, or delegate) directly within the scope of a class or structure. When you have done so, the nested (or “inner”) type is considered a member of the nesting (or “outer”) class, and in the eyes of the runtime can be manipulated like any other member (fields, properties, methods, and events). The syntax used to nest a type is quite straightforward:

```

public class OuterClass
{
    // A public nested type can be used by anybody.
    public class PublicInnerClass {}

    // A private nested type can only be used by members
    // of the containing class.
    private class PrivateInnerClass {}
}

```

Although the syntax is clean, understanding why you might want to do this may not readily apparent. To understand this technique, ponder the following traits of nesting a type:

- Nested types allow you to gain complete control over the access level of the inner type, as they may be declared privately (recall that non-nested classes cannot be declared using the `private` keyword).
- Because a nested type is a member of the containing class, it can access private members of the containing class.

- Oftentimes, a nested type is only useful as a helper for the outer class, and is not intended for use by the outside world.

When a type nests another class type, it can create member variables of the type, just as it would for any point of data. However, if you wish to make use of a nested type from outside of the containing type, you must qualify it by the scope of the nesting type. Consider the following code:

```
static void Main(string[] args)
{
    // Create and use the public inner class. OK!
    OuterClass.PublicInnerClass inner;
    inner = new OuterClass.PublicInnerClass();

    // Compiler Error! Cannot access the private class.
    OuterClass.PrivateInnerClass inner2;
    inner2 = new OuterClass.PrivateInnerClass();
}
```

To make use of this concept within the employees example, assume you have now nested the BenefitPackage directly within the Employee class type:

```
partial class Employee
{
    public class BenefitPackage
    {
        // Assume we have other members that represent
        // dental/health benefits, and so on.
        public double ComputePayDeduction()
        {
            return 125.0;
        }
    }
    ...
}
```

The nesting process can be as “deep” as you require. For example, assume you wish to create an enumeration named BenefitPackageLevel, which documents the various benefit levels an employee may choose. To programmatically enforce the tight connection between Employee, BenefitPackage, and BenefitPackageLevel, you could nest the enumeration as follows:

```
// Employee nests BenefitPackage.
public partial class Employee
{
    // BenefitPackage nests BenefitPackageLevel.
    public class BenefitPackage
    {
        public enum BenefitPackageLevel
        {
            Standard, Gold, Platinum
        }

        public double ComputePayDeduction()
        {

```

```

        return 125.0;
    }
}
...
}
```

Because of the nesting relationships, note how you are required to make use of this enumeration:

```

static void Main(string[] args)
{
...
// Define my benefit level.
Employee.BenefitPackage.BenefitPackageLevel myBenefitLevel =
    Employee.BenefitPackage.BenefitPackageLevel.Platinum;
Console.ReadLine();
}
```

Excellent! At this point you have been exposed to a number of keywords (and concepts) that allow you to build hierarchies of related types via classical inheritance, containment, and nested types. If the details aren't crystal clear right now, don't sweat it. You will be building a number of additional hierarchies over the remainder of this text. Next up, let's examine the final pillar of OOP: polymorphism.

The Third Pillar of OOP: C#'s Polymorphic Support

Recall that the `Employee` base class defined a method named `GiveBonus()`, which was originally implemented as follows:

```

public partial class Employee
{
    public void GiveBonus(float amount)
    {
        currPay += amount;
    }
...
}
```

Because this method has been defined with the `public` keyword, you can now give bonuses to salespeople and managers (as well as part-time salespeople):

```

static void Main(string[] args)
{
    Console.WriteLine("***** The Employee Class Hierarchy *****\n");

    // Give each employee a bonus?
    Manager chucky = new Manager("Chucky", 50, 92, 100000, "333-23-2322", 9000);
    chucky.GiveBonus(300);
    chucky.DisplayStats();
    Console.WriteLine();

    SalesPerson fran = new SalesPerson("Fran", 43, 93, 3000, "932-32-3232", 31);
    fran.GiveBonus(200);
```

```

fran.DisplayStats();
Console.ReadLine();
}

```

The problem with the current design is that the publicly inherited GiveBonus() method operates identically for all subclasses. Ideally, the bonus of a salesperson or part-time salesperson should take into account the number of sales. Perhaps managers should gain additional stock options in conjunction with a monetary bump in salary. Given this, you are suddenly faced with an interesting question: “How can related types respond differently to the same request?” Again, glad you asked!

The virtual and override Keywords

Polymorphism provides a way for a subclass to define its own version of a method defined by its base class, using the process termed *method overriding*. To retrofit your current design, you need to understand the meaning of the *virtual* and *override* keywords. If a base class wishes to define a method that *may be* (but does not have to be) overridden by a subclass, it must mark the method with the *virtual* keyword:

```

partial class Employee
{
    // This method can now be 'overridden' by a derived class.
    public virtual void GiveBonus(float amount)
    {
        currPay += amount;
    }
    ...
}

```

Note Methods that have been marked with the *virtual* keyword are (not surprisingly) termed *virtual methods*.

When a subclass wishes to change the implementation details of a virtual method, it does so using the *override* keyword. For example, the SalesPerson and Manager could override GiveBonus() as follows (assume that PTSalesPerson will not override GiveBonus() and therefore simply inherits the version defined by SalesPerson):

```

class SalesPerson : Employee
{
    ...
    // A salesperson's bonus is influenced by the number of sales.
    public override void GiveBonus(float amount)
    {
        int salesBonus = 0;
        if (numberOfSales >= 0 && numberOfSales <= 100)
            salesBonus = 10;
        else
        {
            if (numberOfSales >= 101 && numberOfSales <= 200)

```

```

        salesBonus = 15;
    else
        salesBonus = 20;
    }
    base.GiveBonus(amount * salesBonus);
}
}

class Manager : Employee
{
...
    public override void GiveBonus(float amount)
    {
        base.GiveBonus(amount);
        Random r = new Random();
        numberofOptions += r.Next(500);
    }
}

```

Notice how each overridden method is free to leverage the default behavior using the `base` keyword. In this way, you have no need to completely reimplement the logic behind `GiveBonus()`, but can reuse (and possibly extend) the default behavior of the parent class.

Also assume that the current `DisplayStats()` method of the `Employee` class has been declared virtually. By doing so, each subclass can override this method to account for displaying the number of sales (for salespeople) and current stock options (for managers). For example, consider the `Manager`'s version of the `DisplayStats()` method (the `SalesPerson` class would implement `DisplayStats()` in a similar manner to show the number of sales):

```

public override void DisplayStats()
{
    base.DisplayStats();
    Console.WriteLine("Number of Stock Options: {0}", StockOptions);
}

```

Now that each subclass can interpret what these virtual methods means to itself, each object instance behaves as a more independent entity:

```

static void Main(string[] args)
{
    Console.WriteLine("***** The Employee Class Hierarchy *****\n");

    // A better bonus system!
    Manager chucky = new Manager("Chucky", 50, 92, 100000, "333-23-2322", 9000);
    chucky.GiveBonus(300);
    chucky.DisplayStats();
    Console.ReadLine();

    SalesPerson fran = new SalesPerson("Fran", 43, 93, 3000, "932-32-3232", 31);
    fran.GiveBonus(200);
    fran.DisplayStats();
    Console.ReadLine();
}

```

The following output shows a possible test run of your application thus far:

***** The Employee Class Hierarchy *****

```
Name: Chucky
ID: 92
Age: 50
Pay: 100300
SSN: 333-23-2322
Number of Stock Options: 9337

Name: Fran
ID: 93
Age: 43
Pay: 5000
SSN: 932-32-3232
Number of Sales: 31
```

Overriding Virtual Members Using Visual Studio 2010

As you may have already noticed, when you are overriding a member, you must recall the type of each and every parameter—not to mention the method name and parameter passing conventions (ref, out and params). Visual Studio 2010 has a very helpful feature that you can make use of when overriding a virtual member. If you type the word “override” within the scope of a class type (then hit the spacebar), IntelliSense will automatically display a list of all the overridable members defined in your parent classes, as you see in Figure 6-6.



Figure 6-6. Quickly viewing overridable methods à la Visual Studio 2010

When you select a member and hit the Enter key, the IDE responds by automatically filling in the method stub on your behalf. Note that you also receive a code statement that calls your parent's version of the virtual member (you are free to delete this line if it is not required). For example, if you used this technique when overriding the `DisplayStats()` method, you might find the following autogenerated code:

```
public override void DisplayStats()
{
    base.DisplayStats();
}
```

Sealing Virtual Members

Recall that the `sealed` keyword can be applied to a class type to prevent other types from extending its behavior via inheritance. As you may remember, you sealed `PTSalesPerson` as you assumed it made no sense for other developers to extend this line of inheritance any further.

On a related note, sometimes you may not wish to seal an entire class, but simply want to prevent derived types from overriding particular virtual methods. For example, assume you do not want part-time salespeople to obtain customized bonuses. To prevent the `PTSalesPerson` class from overriding the virtual `GiveBonus()` method, you could effectively seal this method in the `SalesPerson` class as follows:

```
// SalesPerson has sealed the GiveBonus() method!
class SalesPerson : Employee
{
    ...
    public override sealed void GiveBonus(float amount)
    {
        ...
    }
}
```

Here, `SalesPerson` has indeed overridden the virtual `GiveBonus()` method defined in the `Employee` class; however, it has explicitly marked it as sealed. Thus, if you attempted to override this method in the `PTSalesPerson` class you receive compile-time errors, as shown in the following code:

```
sealed class PTSalesPerson : SalesPerson
{
    public PTSalesPerson(string fullName, int age, int empID,
                         float currPay, string ssn, int numbfSales)
        :base (fullName, age, empID, currPay, ssn, numbfSales)
    {
    }

    // Compiler error! Can't override this method
    // in the PTSalesPerson class, as it was sealed.
    public override void GiveBonus(float amount)
    {
    }
}
```

Understanding Abstract Classes

Currently, the `Employee` base class has been designed to supply various data members for its descendants, as well as supply two virtual methods (`GiveBonus()` and `DisplayStats()`) that may be overridden by a given descendent. While this is all well and good, there is a rather odd byproduct of the current design; you can directly create instances of the `Employee` base class:

```
// What exactly does this mean?
Employee X = new Employee();
```

In this example, the only real purpose of the `Employee` base class is to define common members for all subclasses. In all likelihood, you did not intend anyone to create a direct instance of this class, reason being that the `Employee` type itself is too general of a concept. For example, if I were to walk up to you and say, “I’m an employee!” I would bet your very first question to me would be, “What *kind* of employee are you?” Are you a consultant, trainer, admin assistant, copyeditor, or White House aide?

Given that many base classes tend to be rather nebulous entities, a far better design for this example is to prevent the ability to directly create a new `Employee` object in code. In C#, you can enforce this programmatically by using the `abstract` keyword in the class definition, thus creating an *abstract base class*:

```
// Update the Employee class as abstract
// to prevent direct instantiation.
abstract partial class Employee
{
    ...
}
```

With this, if you now attempt to create an instance of the `Employee` class, you are issued a compile-time error:

```
// Error! Cannot create an instance of an abstract class!
Employee X = new Employee();
```

At first glance it might seem very strange to define a class that you cannot directly create. Recall however that base classes (abstract or not) are very useful, in that they contain all of the common data and functionality of derived types. Using this form of abstraction, we are able to model that the “idea” of an employee is completely valid; it is just not a concrete entity. Also understand that although we cannot *directly* create an abstract class, it is still assembled in memory when derived classes are created. Thus, it is perfectly fine (and common) for abstract classes to define any number of constructors that are called *indirectly* when derived classes are allocated.

At this point, you have constructed a fairly interesting employee hierarchy. You will add a bit more functionality to this application later in this chapter when examining C# casting rules. Until then, Figure 6-7 illustrates the core design of your current types.




Figure 6-7. The Employee hierarchy

■ **Source Code** The Employees project is included under the Chapter 6 subdirectory.

Understanding the Polymorphic Interface

When a class has been defined as an abstract base class (via the `abstract` keyword), it may define any number of *abstract members*. Abstract members can be used whenever you wish to define a member that does *not* supply a default implementation, but *must* be accounted for by each derived class. By doing so, you enforce a *polymorphic interface* on each descendent, leaving them to contend with the task of providing the details behind your abstract methods.

Simply put, an abstract base class's polymorphic interface simply refers to its set of virtual and abstract methods. This is much more interesting than first meets the eye, as this trait of OOP allows you

to build easily extendable and flexible software applications. To illustrate, you will be implementing (and slightly modifying) the hierarchy of shapes briefly examined in Chapter 5 during the overview of the pillars of OOP. To begin, create a new C# Console Application project named Shapes.

In Figure 6-8, notice that the Hexagon and Circle types each extend the Shape base class. Like any base class, Shape defines a number of members (a PetName property and Draw() method in this case) that are common to all descendants.




Figure 6-8. The shapes hierarchy

Much like the employee hierarchy, you should be able to tell that you don't want to allow the object user to create an instance of Shape directly, as it is too abstract of a concept. Again, to prevent the direct creation of the Shape type, you could define it as an abstract class. As well, given that you wish the derived types to respond uniquely to the Draw() method, let's mark it as virtual and define a default implementation:

```

// The abstract base class of the hierarchy.
abstract class Shape
{
    public Shape(string name = "NoName")
    { PetName = name; }

    public string PetName { get; set; }

    // A single virtual method.
    public virtual void Draw()
    {
        Console.WriteLine("Inside Shape.Draw()");
    }
}
  
```

Notice that the virtual `Draw()` method provides a default implementation that simply prints out a message that informs you that you are calling the `Draw()` method within the `Shape` base class. Now recall that when a method is marked with the `virtual` keyword, the method provides a default implementation that all derived types automatically inherit. If a child class so chooses, it *may* override the method but does not *have to*. Given this, consider the following implementation of the `Circle` and `Hexagon` types:

```
// Circle DOES NOT override Draw().
class Circle : Shape
{
    public Circle() {}
    public Circle(string name) : base(name){}
}

// Hexagon DOES override Draw().
class Hexagon : Shape
{
    public Hexagon() {}
    public Hexagon(string name) : base(name){}
    public override void Draw()
    {
        Console.WriteLine("Drawing {0} the Hexagon", PetName);
    }
}
```

The usefulness of abstract methods becomes crystal clear when you once again remember that subclasses are *never required* to override virtual methods (as in the case of `Circle`). Therefore, if you create an instance of the `Hexagon` and `Circle` types, you'd find that the `Hexagon` understands how to "draw" itself correctly or at least print out an appropriate message to the console. The `Circle`, however, is more than a bit confused:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Polymorphism *****\n");

    Hexagon hex = new Hexagon("Beth");
    hex.Draw();

    Circle cir = new Circle("Cindy");
    // Calls base class implementation!
    cir.Draw();
    Console.ReadLine();
}
```

Now consider the following output of the previous `Main()` method:

```
***** Fun with Polymorphism *****
```

```
Drawing Beth the Hexagon
Inside Shape.Draw()
```

Clearly, this is not a very intelligent design for the current hierarchy. To force each child class to override the `Draw()` method, you can define `Draw()` as an abstract method of the `Shape` class, which by definition means you provide no default implementation whatsoever. To mark a method as abstract in C#, you use the `abstract` keyword. Notice that abstract members do not provide any implementation whatsoever:

```
abstract class Shape
{
    // Force all child classes to define how to be rendered.
    public abstract void Draw();
    ...
}
```

Note Abstract methods can only be defined in abstract classes. If you attempt to do otherwise, you will be issued a compiler error.

Methods marked with `abstract` are pure protocol. They simply define the name, return type (if any), and parameter set (if required). Here, the abstract `Shape` class informs the derived types “I have a method named `Draw()` that takes no arguments and returns nothing. If you derive from me, you figure out the details.”

Given this, you are now obligated to override the `Draw()` method in the `Circle` class. If you do not, `Circle` is also assumed to be a noncreatable abstract type that must be adorned with the `abstract` keyword (which is obviously not very useful in this example). Here is the code update:

```
// If we did not implement the abstract Draw() method, Circle would also be
// considered abstract, and would have to be marked abstract!
class Circle : Shape
{
    public Circle() {}
    public Circle(string name) : base(name) {}
    public override void Draw()
    {
        Console.WriteLine("Drawing {0} the Circle", PetName);
    }
}
```

The short answer is that you can now make the assumption that anything deriving from `Shape` does indeed have a unique version of the `Draw()` method. To illustrate the full story of polymorphism, consider the following code:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Polymorphism *****\n");

    // Make an array of Shape-compatible objects.
    Shape[] myShapes = {new Hexagon(), new Circle(), new Hexagon("Mick"),
        new Circle("Beth"), new Hexagon("Linda")};
```

```
// Loop over each item and interact with the
// polymorphic interface.
foreach (Shape s in myShapes)
{
    s.Draw();
}
Console.ReadLine();
}
```

Here is the output from the modified Main() method:

***** Fun with Polymorphism *****

```
Drawing NoName the Hexagon
Drawing NoName the Circle
Drawing Mick the Hexagon
Drawing Beth the Circle
Drawing Linda the Hexagon
```

This Main() method illustrates polymorphism at its finest. Although it is not possible to *directly* create an instance of an abstract base class (the Shape), you are able to freely store references to any subclass with an abstract base variable. Therefore, when you are creating an array of Shapes, the array can hold any object deriving from the Shape base class (if you attempt to place Shape-incompatible objects into the array, you receive a compiler error).

Given that all items in the myShapes array do indeed derive from Shape, you know they all support the same “polymorphic interface” (or said more plainly, they all have a Draw() method). As you iterate over the array of Shape references, it is at runtime that the underlying type is determined. At this point, the correct version of the Draw() method is invoked in memory.

This technique also makes it very simple to safely extend the current hierarchy. For example, assume you derived more classes from the abstract Shape base class (Triangle, Square, etc.). Due to the polymorphic interface, the code within your foreach loop would not have to change in the slightest as the compiler enforces that only Shape-compatible types are placed within the myShapes array.

Understanding Member Shadowing

C# provides a facility that is the logical opposite of method overriding termed *shadowing*. Formally speaking, if a derived class defines a member that is identical to a member defined in a base class, the derived class has *shadowed* the parent’s version. In the real world, the possibility of this occurring is the greatest when you are subclassing from a class you (or your team) did not create yourselves (for example, if you purchase a third-party .NET software package).

For the sake of illustration, assume you receive a class named ThreeDCircle from a coworker (or classmate) that defines a subroutine named Draw() taking no arguments:

```
class ThreeDCircle
{
    public void Draw()
    {
        Console.WriteLine("Drawing a 3D Circle");
    }
}
```

```
}
```

You figure that a ThreeDCircle “is-a” Circle, so you derive from your existing Circle type:

```
class ThreeDCircle : Circle
{
    public void Draw()
    {
        Console.WriteLine("Drawing a 3D Circle");
    }
}
```

Once you recompile, you find a warning in the Visual Studio 2010 error window (see Figure 6-9).




Figure 6-9. Oops! You just shadowed a member in your parent class

The problem is that you have a derived class (ThreeDCircle) which contains a method that is identical to an inherited method. Again, the exact warning reported by the compiler is:

'Shapes.ThreeDCircle.Draw()' hides inherited member 'Shapes.Circle.Draw()'. To make the current member override that implementation, add the override keyword. Otherwise add the new keyword.

To address this issue, you have two options. You could simply update the parent’s version of Draw() using the override keyword (as suggested by the compiler). With this approach, the ThreeDCircle type is able to extend the parent’s default behavior as required. However, if you don’t have access to the code defining the base class (again, as would be the case in many third-party libraries), you would be unable to modify the Draw() method as a virtual member, as you don’t have access to the code file!

As an alternative, you can include the new keyword to the offending Draw() member of the derived type (ThreeDCircle in this example). Doing so explicitly states that the derived type’s implementation is intentionally designed to effectively ignore the parent’s version (again, in the real world, this can be helpful if external .NET software somehow conflicts with your current software).

```
// This class extends Circle and hides the inherited Draw() method.
class ThreeDCircle : Circle
{
    // Hide any Draw() implementation above me.
    public new void Draw()
    {
```

```

        Console.WriteLine("Drawing a 3D Circle");
    }
}

```

You can also apply the new keyword to any member type inherited from a base class (field, constant, static member, or property). As a further example, assume that ThreeDCircle wishes to hide the inherited PetName property:

```

class ThreeDCircle : Circle
{
    // Hide the PetName property above me.
    public new string PetName { get; set; }

    // Hide any Draw() implementation above me.
    public new void Draw()
    {
        Console.WriteLine("Drawing a 3D Circle");
    }
}

```

Finally, be aware that it is still possible to trigger the base class implementation of a shadowed member using an explicit cast, as described in the next section. For example, the following code shows:

```

static void Main(string[] args)
{
    ...
    // This calls the Draw() method of the ThreeDCircle.
    ThreeDCircle o = new ThreeDCircle();
    o.Draw();

    // This calls the Draw() method of the parent!
    ((Circle)o).Draw();
    Console.ReadLine();
}

```

Source Code The Shapes project can be found under the Chapter 6 subdirectory.

Understanding Base Class/Derived Class Casting Rules

Now that you can build a family of related class types, you need to learn the rules of class *casting operations*. To do so, let's return to the Employees hierarchy created earlier in this chapter. Under the .NET platform, the ultimate base class in the system is `System.Object`. Therefore, everything "is-a" `Object` and can be treated as such. Given this fact, it is legal to store an instance of any type within an object variable:

```

void CastingExamples()
{
    // A Manager "is-a" System.Object, so we can
}

```

```
// store a Manager reference in an object variable just fine.
object frank = new Manager("Frank Zappa", 9, 3000, 40000, "111-11-1111", 5);
}
```

In the Employees example, Managers, SalesPerson, and PTSalesPerson types all extend Employee, so you can store any of these objects in a valid base class reference. Therefore, the following statements are also legal:

```
static void CastingExamples()
{
    // A Manager "is-a" System.Object, so we can
    // store a Manager reference in an object variable just fine.
    object frank = new Manager("Frank Zappa", 9, 3000, 40000, "111-11-1111", 5);

    // A Manager "is-an" Employee too.
    Employee moonUnit = new Manager("MoonUnit Zappa", 2, 3001, 20000, "101-11-1321", 1);

    // A PTSalesPerson "is-a" SalesPerson.
    SalesPerson jill = new PTSalesPerson("Jill", 834, 3002, 100000, "111-12-1119", 90);
}
```

The first law of casting between class types is that when two classes are related by an “is-a” relationship, it is always safe to store a derived object within a base class reference. Formally, this is called an *implicit cast*, as “it just works” given the laws of inheritance. This leads to some powerful programming constructs. For example, assume you have defined a new method within your current Program class:

```
static void GivePromotion(Employee emp)
{
    // Increase pay...
    // Give new parking space in company garage...

    Console.WriteLine("{0} was promoted!", emp.Name);
}
```

Because this method takes a single parameter of type Employee, you can effectively pass any descendent from the Employee class into this method directly, given the “is-a” relationship:

```
static void CastingExamples()
{
    // A Manager "is-a" System.Object, so we can
    // store a Manager reference in an object variable just fine.
    object frank = new Manager("Frank Zappa", 9, 3000, 40000, "111-11-1111", 5);

    // A Manager "is-an" Employee too.
    Employee moonUnit = new Manager("MoonUnit Zappa", 2, 3001, 20000, "101-11-1321", 1);
    GivePromotion(moonUnit);

    // A PTSalesPerson "is-a" SalesPerson.
    SalesPerson jill = new PTSalesPerson("Jill", 834, 3002, 100000, "111-12-1119", 90);
    GivePromotion(jill);
}
```

The previous code compiles given the implicit cast from the base class type (`Employee`) to the derived type. However, what if you also wanted to fire Frank Zappa (currently stored in a general `System.Object` reference)? If you pass the `frank` object directly into this method, you will find a compiler error as follows:

```
// Error!
object frank = new Manager("Frank Zappa", 9, 3000, 40000, "111-11-1111", 5);
GivePromotion(frank);
```

The problem is that you are attempting to pass in a variable which Is-NOT-A `Employee`, but a more general `System.Object`. Given the fact that `object` is higher up the inheritance chain than `Employee`, the compiler will not allow for an implicit cast, in an effort to keep your code as type safe as possible.

Even though you can figure out that the `object` reference is pointing to an `Employee` compatible class in memory, the compiler cannot, as that will not be known until runtime. You can satisfy the compiler by performing an *explicit cast*. This is the second law of casting: you can in such cases explicitly downcast using the C# casting operator. The basic template to follow when performing an explicit cast looks something like the following:

```
(ClassIWantToCastTo)referenceIHave
```

Thus, to pass the `object` variable into the `GivePromotion()` method, you must author the following code:

```
// OK!
GivePromotion((Manager)frank);
```

The C# as Keyword

Be very aware that explicit casting is evaluated at *runtime*, not compile time. Therefore, if you were to author the following C# code:

```
// Ack! You can't cast frank to a Hexagon, but this compiles fine!
Hexagon hex = (Hexagon)frank;
```

you would compile without error, but would receive a runtime error, or more formally a *runtime exception*. Chapter 7 will examine the full details of structured exception handling; however, it is worth pointing out for the time being when you are performing an explicit cast, you can trap the possibility of an invalid cast using the `try` and `catch` keywords (again, see Chapter 7 for full details):

```
// Catch a possible invalid cast.
try
{
    Hexagon hex = (Hexagon)frank;
}
catch (InvalidCastException ex)
{
    Console.WriteLine(ex.Message);
}
```

While this is a fine example of defensive programming, C# provides the `as` keyword to quickly determine at runtime whether a given type is compatible with another. When you use the `as` keyword, you are able to determine compatibility by checking against a null return value. Consider the following:

```
// Use 'as' to test compatibility.
Hexagon hex2 = frank as Hexagon;
if (hex2 == null)
    Console.WriteLine("Sorry, frank is not a Hexagon...");
```

The C# is Keyword

Given that the `GivePromotion()` method has been designed to take any possible type derived from `Employee`, one question on your mind may be how this method can determine which derived type was sent into the method. On a related note, given that the incoming parameter is of type `Employee`, how can you gain access to the specialized members of the `SalesPerson` and `Manager` types?

In addition to the `as` keyword, the C# language provides the `is` keyword to determine whether two items are compatible. Unlike the `as` keyword, however, the `is` keyword returns `false`, rather than a `null` reference, if the types are incompatible. Consider the following implementation of the `GivePromotion()` method:

```
static void GivePromotion(Employee emp)
{
    Console.WriteLine("{0} was promoted!", emp.Name);

    if (emp is SalesPerson)
    {
        Console.WriteLine("{0} made {1} sale(s)!", emp.Name,
            ((SalesPerson)emp).SalesNumber);
        Console.WriteLine();
    }
    if (emp is Manager)
    {
        Console.WriteLine("{0} had {1} stock options...", emp.Name,
            ((Manager)emp).StockOptions);
        Console.WriteLine();
    }
}
```

Here you are performing a runtime check to determine what the incoming base class reference is actually pointing to in memory. Once you determine whether you received a `SalesPerson` or `Manager` type, you are able to perform an explicit cast to gain access to the specialized members of the class. Also notice that you are not required to wrap your casting operations within a `try/catch` construct, as you know that the cast is safe if you enter either `if` scope, given your conditional check.

The Master Parent Class: `System.Object`

To wrap up this chapter, I'd like to examine the details of the master parent class in the .NET platform: `Object`. As you were reading the previous section, you may have noticed that the base classes in your hierarchies (`Car`, `Shape`, `Employee`) never explicitly specify their parent classes:

```
// Who is the parent of Car?
class Car
{...}
```

In the .NET universe, every type ultimately derives from a base class named `System.Object` (which can be represented by the C# `object` keyword [lowercase 'o']). The `Object` class defines a set of common members for every type in the framework. In fact, when you do build a class that does not explicitly define its parent, the compiler automatically derives your type from `Object`. If you want to be very clear in your intentions, you are free to define classes that derive from `Object` as follows:

```
// Here we are explicitly deriving from System.Object.
class Car : object
{...}
```

Like any class, `System.Object` defines a set of members. In the following formal C# definition, note that some of these items are declared `virtual`, which specifies that a given member may be overridden by a subclass, while others are marked with `static` (and are therefore called at the class level):

```
public class Object
{
    // Virtual members.
    public virtual bool Equals(object obj);
    protected virtual void Finalize();
    public virtual int GetHashCode();
    public virtual string ToString();

    // Instance level, non-virtual members.
    public Type GetType();
    protected object MemberwiseClone();

    // Static members.
    public static bool Equals(object objA, object objB);
    public static bool ReferenceEquals(object objA, object objB);
}
```

Table 6-1 offers a rundown of the functionality provided by some of the methods you're most likely to make use of.

Table 6-1. Core Members of `System.Object`

Instance Method of <code>Object</code> Class	Meaning in Life
<code>Equals()</code>	<p>By default, this method returns <code>true</code> only if the items being compared refer to the exact same item in memory. Thus, <code>Equals()</code> is used to compare object references, not the state of the object. Typically, this method is overridden to return <code>true</code> only if the objects being compared have the same internal state values (that is, value-based semantics).</p> <p>Be aware that if you override <code>Equals()</code>, you should also override <code>GetHashCode()</code>, as these methods are used internally by <code>Hashtable</code> types to retrieve subobjects from the container.</p> <p>Also recall from Chapter 4, that the <code>ValueType</code> class overrides this method for all structures, so they work with value-based comparisons.</p>

Table 6-1. Core Members of System.Object (continued)

Instance Method of Object Class	Meaning in Life
Finalize()	For the time being, you can understand this method (when overridden) is called to free any allocated resources before the object is destroyed. I talk more about the CLR garbage collection services in Chapter 8.
GetHashCode()	This method returns an int that identifies a specific object instance.
ToString()	This method returns a string representation of this object, using the <namespace>. <type name> format (termed the <i>fully qualified name</i>). This method will often be overridden by a subclass to return a tokenized string of name/value pairs that represent the object's internal state, rather than its fully qualified name.
GetType()	This method returns a Type object that fully describes the object you are currently referencing. In short, this is a Runtime Type Identification (RTTI) method available to all objects (discussed in greater detail in Chapter 15).
MemberwiseClone()	This method exists to return a member-by-member copy of the current object, which is often used when cloning an object (see Chapter 9).

To illustrate some of the default behavior provided by the Object base class, create a new C# Console Application named ObjectOverrides. Insert a new C# class type that contains the following empty class definition for a type named Person:

```
// Remember! Person extends Object.
class Person {}
```

Now, update your Main() method to interact with the inherited members of System.Object as follows:

```
class Program
{
    static void Main(string[] args)
    {
        Console.WriteLine("***** Fun with System.Object *****\n");
        Person p1 = new Person();

        // Use inherited members of System.Object.
        Console.WriteLine("ToString: {0}", p1.ToString());
        Console.WriteLine("Hash code: {0}", p1.GetHashCode());
        Console.WriteLine("Type: {0}", p1.GetType());
```

```

// Make some other references to p1.
Person p2 = p1;
object o = p2;

// Are the references pointing to the same object in memory?
if (o.Equals(p1) && p2.Equals(o))
{
    Console.WriteLine("Same instance!");
}
Console.ReadLine();
}
}

```

Here is the output of the current Main() method.

***** Fun with System.Object *****

```

ToString: ObjectOverrides.Person
Hash code: 46104728
Type: ObjectOverrides.Person
Same instance!

```

First, notice how the default implementation of ToString() returns the fully qualified name of the current type (ObjectOverrides.Person). As you will see later during the examination of building custom namespaces in Chapter 14, every C# project defines a “root namespace,” which has the same name of the project itself. Here, you created a project named ObjectOverrides; thus the Person type (as well as the Program class) have both been placed within the ObjectOverrides namespace.

The default behavior of Equals() is to test whether two variables are pointing to the same object in memory. Here, you create a new Person variable named p1. At this point, a new Person object is placed on the managed heap. p2 is also of type Person. However, you are not creating a *new* instance, but rather assigning this variable to reference p1. Therefore, p1 and p2 are both pointing to the same object in memory, as is the variable o (of type object, which was thrown in for good measure). Given that p1, p2, and o all point to the same memory location, the equality test succeeds.

Although the canned behavior of System.Object can fit the bill in a number of cases, it is quite common for your custom types to override some of these inherited methods. To illustrate, update the Person class to support some properties representing an individual’s first name, last name, and age, each of which can be set by a custom constructor:

```

// Remember! Person extends Object.
class Person
{
    public string FirstName { get; set; }
    public string LastName { get; set; }
    public int Age { get; set; }

    public Person(string fName, string lName, int personAge)
    {
        FirstName = fName;
        LastName = lName;
        Age = personAge;
    }
}

```

```

    }
    public Person(){}
}

```

Overriding System.Object.ToString()

Many classes (and structures) that you create can benefit from overriding `ToString()` in order to return a string textual representation of the type's current state. This can be quite helpful for purposes of debugging (among other reasons). How you choose to construct this string is a matter of personal choice; however, a recommended approach is to separate each name/value pair with semicolons and wrap the entire string within square brackets (many types in the .NET base class libraries follow this approach). Consider the following overridden `ToString()` for your `Person` class:

```

public override string ToString()
{
    string myState;
    myState = string.Format("[First Name: {0}; Last Name: {1}; Age: {2}]",
        FirstName, LastName, Age);
    return myState;
}

```

This implementation of `ToString()` is quite straightforward, given that the `Person` class only has three pieces of state data. However, always remember that a proper `ToString()` override should also account for any data defined *up the chain of inheritance*.

When you override `ToString()` for a class extending a custom base class, the first order of business is to obtain the `ToString()` value from your parent using the `base` keyword. Once you have obtained your parent's string data, you can append the derived class's custom information.

Overriding System.Object.Equals()

Let's also override the behavior of `Object.Equals()` to work with value-based semantics. Recall that by default, `Equals()` returns true only if the two objects being compared reference the same object instance in memory. For the `Person` class, it may be helpful to implement `Equals()` to return true if the two variables being compared contain the same state values (e.g., first name, last name, and age).

First of all, notice that the incoming argument of the `Equals()` method is a general `System.Object`. Given this, your first order of business is to ensure the caller has indeed passed in a `Person` object, and as an extra safeguard, to make sure the incoming parameter is not a null reference.

Once you have established the caller has passed you an allocated `Person`, one approach to implement `Equals()` is to perform a field-by-field comparison against the data of the incoming object to the data of the current object:

```

public override bool Equals(object obj)
{
    if (obj is Person && obj != null)
    {
        Person temp;
        temp = (Person)obj;
        if (temp.FirstName == this.FirstName
            && temp.LastName == this.LastName
            && temp.Age == this.Age)
    }
}

```

```

{
    return true;
}
else
{
    return false;
}
return false;
}

```

Here, you are examining the values of the incoming object against the values of your internal values (note the use of the `this` keyword). If the name and age of each are identical, you have two objects with the exact same state data and therefore return `true`. Any other possibility results in returning `false`.

While this approach does indeed work, you can certainly imagine how labor intensive it would be to implement a custom `Equals()` method for nontrivial types that may contain dozens of data fields. One common shortcut is to leverage your own implementation of `ToString()`. If a class has a prim-and-proper implementation of `ToString()` that accounts for all field data up the chain of inheritance, you can simply perform a comparison of the object's string data:

```

public override bool Equals(object obj)
{
    // No need to cast 'obj' to a Person anymore,
    // as everything has a ToString() method.
    return obj.ToString() == this.ToString();
}

```

Notice in this case that we no longer need to check if the incoming argument is of the correct type (a `Person` in our example), as everything in .NET supports a `ToString()` method. Even better, we no longer need to perform a property-by-property equality check, as we are not simply testing the value returned from `ToString()`.

Overriding System.Object.GetHashCode()

When a class overrides the `Equals()` method, you should also override the default implementation of `GetHashCode()`. Simply put, a *hash code* is a numerical value that represents an object as a particular state. For example, if you create two string variables that hold the value `Hello`, you would obtain the same hash code. However, if one of the string objects were in all lowercase (`hello`), you would obtain different hash codes.

By default, `System.Object.GetHashCode()` uses your object's current location in memory to yield the hash value. However, if you are building a custom type that you intend to store in a `Hashtable` type (within the `System.Collections` namespace), you should always override this member, as the `Hashtable` will be internally invoking `Equals()` and `GetHashCode()` to retrieve the correct object.

Note To be more specific, the `System.Collections.Hashtable` class calls `GetHashCode()` internally to gain a general idea where the object is located, but a subsequent (internal) call to `Equals()` determines the exact match.

Although you are not going to place your Person into a `System.Collections.Hashtable`, for completion, let's override `GetHashCode()`. There are many algorithms that can be used to create a hash code, some fancy, others not so fancy. Most of the time, you are able to generate a hash code value by leveraging the `System.String`'s `GetHashCode()` implementation.

Given that the `String` class already has a solid hash code algorithm that is using the character data of the `String` to compute a hash value, if you can identify a piece of field data on your class that should be unique for all instances (such as a Social Security number), simply call `GetHashCode()` on that point of field data. Thus, if the `Person` class defined a `SSN` property, we could author the following code:

```
// Return a hash code based on a point of unique string data.
public override int GetHashCode()
{
    return SSN.GetHashCode();
}
```

If you cannot find a single point of unique string data, but you have overridden `ToString()`, call `GetHashCode()` on your own string representation:

```
// Return a hash code based on the person's ToString() value.
public override int GetHashCode()
{
    return this.ToString().GetHashCode();
}
```

Testing Your Modified Person Class

Now that you have overridden the virtual members of `Object`, update `Main()` to test your updates.

```
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with System.Object *****\n");

    // NOTE: We want these to be identical to test
    // the Equals() and GetHashCode() methods.
    Person p1 = new Person("Homer", "Simpson", 50);
    Person p2 = new Person("Homer", "Simpson", 50);

    // Get stringified version of objects.
    Console.WriteLine("p1.ToString() = {0}", p1.ToString());
    Console.WriteLine("p2.ToString() = {0}", p2.ToString());

    // Test Overridden Equals()
    Console.WriteLine("p1 = p2?: {0}", p1.Equals(p2));

    // Test hash codes.
    Console.WriteLine("Same hash codes?: {0}", p1.GetHashCode() == p2.GetHashCode());
    Console.WriteLine();

    // Change age of p2 and test again.
    p2.Age = 45;
    Console.WriteLine("p1.ToString() = {0}", p1.ToString());
```

```

Console.WriteLine("p2.ToString() = {0}", p2.ToString());
Console.WriteLine("p1 = p2?: {0}", p1.Equals(p2));
Console.WriteLine("Same hash codes?: {0}", p1.GetHashCode() == p2.GetHashCode());
Console.ReadLine();
}

```

The output can be seen here:

***** Fun with System.Object *****

```

p1.ToString() = [First Name: Homer; Last Name: Simpson; Age: 50]
p2.ToString() = [First Name: Homer; Last Name: Simpson; Age: 50]
p1 = p2?: True
Same hash codes?: True

p1.ToString() = [First Name: Homer; Last Name: Simpson; Age: 50]
p2.ToString() = [First Name: Homer; Last Name: Simpson; Age: 45]
p1 = p2?: False
Same hash codes?: False

```

The Static Members of System.Object

In addition to the instance-level members you have just examined, `System.Object` does define two (very helpful) static members that also test for value-based or reference-based equality. Consider the following code:

```

static void StaticMembersOfObject()
{
    // Static members of System.Object.
    Person p3 = new Person("Sally", "Jones", 4);
    Person p4 = new Person("Sally", "Jones", 4);
    Console.WriteLine("P3 and P4 have same state: {0}", object.Equals(p3, p4));
    Console.WriteLine("P3 and P4 are pointing to same object: {0}",
        object.ReferenceEquals(p3, p4));
}

```

Here, you are able to simply send in two objects (of any type) and allow the `System.Object` class to determine the details automatically. These methods can be very helpful when you have redefined equality for a custom type, yet still need to quickly determine whether two reference variables point to the same location in memory (via the static `ReferenceEquals()` method).

Source Code The `ObjectOverrides` project is located under the Chapter 6 subdirectory.

Summary

This chapter explored the role and details of inheritance and polymorphism. Over these pages you were introduced to numerous new keywords and tokens to support each of these techniques. For example, recall that the colon token is used to establish the parent class of a given type. Parent types are able to define any number of virtual and/or abstract members to establish a polymorphic interface. Derived types override such members using the `override` keyword.

In addition to building numerous class hierarchies, this chapter also examined how to explicitly cast between base and derived types, and wrapped up by diving into the details of the cosmic parent class in the .NET base class libraries: `System.Object`.



Understanding Structured Exception Handling

In this chapter you will learn how to handle runtime anomalies in your C# code through the use of *structured exception handling* (often cryptically abbreviated as SEH). Not only will you examine the C# keywords that allow you to handle such matters (`try`, `catch`, `throw`, `finally`), you will also come to understand the distinction between application-level and system-level exceptions, as well as the role of the `System.Exception` base class. This discussion will lead into the topic of building custom exceptions, and, finally, to a quick look at the exception-centric debugging tools of Visual Studio 2010.

Ode to Errors, Bugs, and Exceptions

Despite what our (sometimes inflated) egos may tell us, no programmer is perfect. Writing software is a complex undertaking, and given this complexity, it is quite common for even the best software to ship with various...problems. Sometimes the problem is caused by “bad code” (such as overflowing the bounds of an array). Other times, a problem is caused by bogus user input that has not been accounted for in the application’s code base (e.g., a phone number input field assigned to the value “Chucky”).

Now, regardless of the cause of the problem, the end result is that the application does not work as expected. To help frame the upcoming discussion of structured exception handling, allow me to provide definitions for three commonly used anomaly-centric terms:

- *Bugs*: These are, simply put, errors made by the programmer. For example, suppose you are programming with unmanaged C++. If you fail to delete dynamically allocated memory, resulting in a memory leak, you have a bug.
- *User errors*: User errors, on the other hand, are typically caused by the individual running your application, rather than by those who created it. For example, an end user who enters a malformed string into a text box could very well generate an error if you fail to handle this faulty input in your code base.
- *Exceptions*: Exceptions are typically regarded as runtime anomalies that are difficult, if not impossible, to account for while programming your application. Possible exceptions include attempting to connect to a database that no longer exists, opening a corrupted XML file, or trying to contact a machine that is currently offline. In each of these cases, the programmer (or end user) has little control over these “exceptional” circumstances.

Given these definitions, it should be clear that .NET structured *exception handling* is a technique for dealing with runtime *exceptions*. However, even for the bugs and user errors that have escaped

your view, the CLR will often generate a corresponding exception that identifies the problem at hand. The .NET base class libraries define numerous exceptions, such as `FormatException`, `IndexOutOfRangeException`, `FileNotFoundException`, `ArgumentOutOfRangeException`, and so forth.

Within the .NET nomenclature, an “exception” accounts for bugs, bogus user input, and runtime errors, even though we programmers may view each of these as a distinct issue. However, before we get too far ahead of ourselves, let’s formalize the role of structured exception handling and check out how it differs from traditional error-handling techniques.

Note To make the code examples used in this book as clean as possible, I will not catch every possible exception that may be thrown by a given method in the base class libraries. In your production level projects, you should, of course, make liberal use of the techniques presented in this chapter.

The Role of .NET Exception Handling

Prior to .NET, error handling under the Windows operating system was a confused mishmash of techniques. Many programmers rolled their own error-handling logic within the context of a given application. For example, a development team could define a set of numerical constants that represented known error conditions, and make use of them as method return values. By way of an example, consider the following partial C code:

```
/* A very C-style error trapping mechanism. */
#define E_FILENOTFOUND 1000

int SomeFunction()
{
    // Assume something happens in this function
    // that causes the following return value.
    return E_FILENOTFOUND;
}

void main()
{
    int retVal = SomeFunction();
    if(retVal == E_FILENOTFOUND)
        printf("Cannot find file...");
}
```

This approach is less than ideal, given the fact that the constant `E_FILENOTFOUND` is little more than a numerical value, and is far from being a helpful agent regarding how to deal with the problem. Ideally, you would like to wrap the error’s name, a descriptive message, and other helpful information about this error condition into a single, well-defined package (which is exactly what happens under structured exception handling).

In addition to a developer’s ad hoc techniques, the Windows API defines hundreds of error codes that come by way of `#defines`, `HRESULTs`, and far too many variations on the simple Boolean (`bool`, `BOOL`, `VARIANT_BOOL`, and so on). Furthermore, many C++ COM developers (and indirectly, many VB6 COM

developers) made use of a small set of standard COM interfaces (e.g., `ISupportErrorInfo`, `IErrorInfo`, `ICreateErrorInfo`) to return meaningful error information to a COM client.

The obvious problem with these older techniques is the tremendous lack of symmetry. Each approach is more or less tailored to a given technology, a given language, and perhaps even a given project. To put an end to this madness, the .NET platform provides a standard technique to send and trap runtime errors: structured exception handling (SEH).

The beauty of this approach is that developers now have a unified approach to error handling, which is common to all languages targeting the .NET platform. Therefore, the way in which a C# programmer handles errors is syntactically similar to that of a VB programmer, or a C++ programmer using C++/CLI.

As an added bonus, the syntax used to throw and catch exceptions across assemblies and machine boundaries is identical. For example, if you use C# to build a Windows Communication Foundation (WCF) service, you can throw a SOAP fault to a remote caller, using the same keywords that allow you to throw an exception between methods in the same application.

Another bonus of .NET exceptions is that rather than receiving a cryptic numerical value that simply identifies the problem at hand, exceptions are objects that contain a human-readable description of the problem, as well as a detailed snapshot of the call stack that triggered the exception in the first place. Furthermore, you are able to give the end user help-link information that points the user to a URL that provides details about the error, as well as custom programmer-defined data.

The Atoms of .NET Exception Handling

Programming with structured exception handling involves the use of four interrelated entities:

- A class type that represents the details of the exception
- A member that *throws* an instance of the exception class to the caller under the correct circumstances
- A block of code on the caller's side that invokes the exception-prone member
- A block of code on the caller's side that will process (or *catch*) the exception should it occur

The C# programming language offers four keywords (`try`, `catch`, `throw`, and `finally`) that allow you to throw and handle exceptions. The object that represents the problem at hand is a class extending `System.Exception` (or a descendent thereof). Given this fact, let's check out the role of this exception-centric base class.

The `System.Exception` Base Class

All user- and system-defined exceptions ultimately derive from the `System.Exception` base class, which in turn derives from `System.Object`. Here is the crux of this class (note that some of these members are virtual and may thus be overridden by derived classes):

```
public class Exception : ISerializable, _Exception
{
    // Public constructors
    public Exception(string message, Exception innerException);
    public Exception(string message);
```

```

public Exception();
...
// Methods
public virtual Exception GetBaseException();
public virtual void GetObjectData(SerializationInfo info,
    StreamingContext context);

// Properties
public virtual IDictionary Data { get; }
public virtual string HelpLink { get; set; }
public Exception InnerException { get; }
public virtual string Message { get; }
public virtual string Source { get; set; }
public virtual string StackTrace { get; }
public MethodBase TargetSite { get; }
...
}

```

As you can see, many of the properties defined by `System.Exception` are read-only in nature. This is due to the fact that derived types will typically supply default values for each property. For example, the default message of the `IndexOutOfRangeException` type is “Index was outside the bounds of the array.”

Note The `Exception` class implements two .NET interfaces. Although we have yet to examine interfaces (see Chapter 9), just understand that the `_Exception` interface allows a .NET exception to be processed by an unmanaged code base (such as a COM application), while the `ISerializable` interface allows an exception object to be persisted across boundaries (such as a machine boundary).

Table 7-1 describes the most important members of `System.Exception`.

Table 7-1. Core Members of the `System.Exception` Type

System.Exception Property	Meaning in Life
Data	This read-only property retrieves a collection of key/value pairs (represented by an object implementing <code>IDictionary</code>) that provide additional, programmer-defined information about the exception. By default, this collection is empty.
HelpLink	This property gets or sets a URL to a help file or web site describing the error in full detail.

Table 7-1. Core Members of the System.Exception Type (continued)

System.Exception Property	Meaning in Life
InnerException	This read-only property can be used to obtain information about the previous exception(s) that caused the current exception to occur. The previous exception(s) are recorded by passing them into the constructor of the most current exception.
Message	This read-only property returns the textual description of a given error. The error message itself is set as a constructor parameter.
Source	This property gets or sets the name of the assembly, or the object, that threw the current exception.
StackTrace	This read-only property contains a string that identifies the sequence of calls that triggered the exception. As you might guess, this property is very useful during debugging or if you wish to dump the error to an external error log.
TargetSite	This read-only property returns a MethodBase object, which describes numerous details about the method that threw the exception (invoking ToString() will identify the method by name).

The Simplest Possible Example

To illustrate the usefulness of structured exception handling, we need to create a class that will throw an exception under the correct (or one might say *exceptional*) circumstances. Assume we have created a new C# Console Application project (named SimpleException) that defines two class types (Car and Radio) associated by the “has-a” relationship. The Radio class defines a single method that turns the radio’s power on or off:

```
class Radio
{
    public void TurnOn(bool on)
    {
        if(on)
            Console.WriteLine("Jamming...");
        else
            Console.WriteLine("Quiet time...");
    }
}
```

In addition to leveraging the Radio class via containment/delegation, the Car class (shown below) is defined in such a way that if the user accelerates a Car object beyond a predefined maximum speed (specified using a constant member variable named MaxSpeed), its engine explodes, rendering the Car unusable (captured by a private bool member variable named carIsDead).

Beyond these points, the `Car` type has a few properties to represent the current speed and a user supplied “pet name,” as well as various constructors to set the state of a new `Car` object. Here is the complete definition (with code annotations):

```
class Car
{
    // Constant for maximum speed.
    public const int MaxSpeed = 100;

    // Car properties.
    public int CurrentSpeed {get; set;}
    public string PetName {get; set;}

    // Is the car still operational?
    private bool carIsDead;

    // A car has-a radio.
    private Radio theMusicBox = new Radio();

    // Constructors.
    public Car() {}
    public Car(string name, int speed)
    {
        CurrentSpeed = speed;
        PetName = name;
    }

    public void CrankTunes(bool state)
    {
        // Delegate request to inner object.
        theMusicBox.TurnOn(state);
    }

    // See if Car has overheated.
    public void Accelerate(int delta)
    {
        if (carIsDead)
            Console.WriteLine("{0} is out of order...", PetName);
        else
        {
            CurrentSpeed += delta;
            if (CurrentSpeed > MaxSpeed)
            {
                Console.WriteLine("{0} has overheated!", PetName);
                CurrentSpeed = 0;
                carIsDead = true;
            }
            else
                Console.WriteLine("=> CurrentSpeed = {0}", CurrentSpeed);
        }
    }
}
```

Now, if we implement a `Main()` method that forces a `Car` object to exceed the predefined maximum speed (set to 100, in the `Car` class) as shown here:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Simple Exception Example *****");
    Console.WriteLine("=> Creating a car and stepping on it!");
    Car myCar = new Car("Zippy", 20);
    myCar.CrankTunes(true);

    for (int i = 0; i < 10; i++)
        myCar.Accelerate(10);
    Console.ReadLine();
}
```

we would see the following output:

```
***** Simple Exception Example *****
=> Creating a car and stepping on it!
Jamming...
=> CurrentSpeed = 30
=> CurrentSpeed = 40
=> CurrentSpeed = 50
=> CurrentSpeed = 60
=> CurrentSpeed = 70
=> CurrentSpeed = 80
=> CurrentSpeed = 90
=> CurrentSpeed = 100
Zippy has overheated!
Zippy is out of order...
```

Throwing a General Exception

Now that we have a functional `Car` class, I'll demonstrate the simplest way to throw an exception. The current implementation of `Accelerate()` simply displays an error message if the caller attempts to speed up the `Car` beyond its upper limit.

To retrofit this method to throw an exception if the user attempts to speed up the automobile after it has met its maker, you want to create and configure a new instance of the `System.Exception` class, setting the value of the read-only `Message` property via the class constructor. When you wish to send the exception object back to the caller, use the C# `throw` keyword. Here is the relevant code update to the `Accelerate()` method:

```
// This time, throw an exception if the user speeds up beyond MaxSpeed.
public void Accelerate(int delta)
{
    if (carIsDead)
        Console.WriteLine("{0} is out of order...", PetName);
    else
    {
        CurrentSpeed += delta;
```

```

if (CurrentSpeed >= MaxSpeed)
{
    carIsDead = true;
    CurrentSpeed = 0;

    // Use the "throw" keyword to raise an exception.
    throw new Exception(string.Format("{0} has overheated!", PetName));
}
else
    Console.WriteLine("=> CurrentSpeed = {0}", CurrentSpeed);
}
}

```

Before examining how a caller would catch this exception, a few points of interest. First of all, when you are throwing an exception, it is always up to you to decide exactly what constitutes the error in question, and when an exception should be thrown. Here, you are making the assumption that if the program attempts to increase the speed of a Car object that has expired, a System.Exception object should be thrown to indicate the Accelerate() method cannot continue (which may or may not be a valid assumption; this will be a judgment call on your part based on the application you are creating).

Alternatively, you could implement Accelerate() to recover automatically without needing to throw an exception in the first place. By and large, exceptions should be thrown only when a more terminal condition has been met (for example, not finding a necessary file, failing to connect to a database, and the like). Deciding exactly what justifies throwing an exception is a design issue you must always contend with. For our current purposes, assume that asking a doomed automobile to increase its speed is cause to throw an exception.

Catching Exceptions

Because the Accelerate() method now throws an exception, the caller needs to be ready to handle the exception should it occur. When you are invoking a method that may throw an exception, you make use of a try/catch block. Once you have caught the exception object, you are able to invoke the members of the exception object to extract the details of the problem.

What you do with this data is largely up to you. You may wish to log this information to a report file, write the data to the Windows event log, e-mail a system administrator, or display the problem to the end user. Here, you will simply dump the contents to the console window:

```

// Handle the thrown exception.
static void Main(string[] args)
{
    Console.WriteLine("***** Simple Exception Example *****");
    Console.WriteLine("=> Creating a car and stepping on it!");
    Car myCar = new Car("Zippy", 20);
    myCar.CrankTunes(true);

    // Speed up past the car's max speed to
    // trigger the exception.
    try
    {
        for(int i = 0; i < 10; i++)
            myCar.Accelerate(10);
    }
}

```

```

catch(Exception e)
{
    Console.WriteLine("\n*** Error! ***");
    Console.WriteLine("Method: {0}", e.TargetSite);
    Console.WriteLine("Message: {0}", e.Message);
    Console.WriteLine("Source: {0}", e.Source);
}

// The error has been handled, processing continues with the next statement.
Console.WriteLine("\n***** Out of exception logic *****");
Console.ReadLine();
}

```

In essence, a try block is a section of statements that may throw an exception during execution. If an exception is detected, the flow of program execution is sent to the appropriate catch block. On the other hand, if the code within a try block does not trigger an exception, the catch block is skipped entirely, and all is right with the world. The following output shows a test run of this program.

```

***** Simple Exception Example *****
=> Creating a car and stepping on it!
Jamming...
=> CurrentSpeed = 30
=> CurrentSpeed = 40
=> CurrentSpeed = 50
=> CurrentSpeed = 60
=> CurrentSpeed = 70
=> CurrentSpeed = 80
=> CurrentSpeed = 90

*** Error! ***
Method: Void Accelerate(Int32)
Message: Zippy has overheated!
Source: SimpleException

***** Out of exception logic *****

```

As you can see, once an exception has been handled, the application is free to continue on from the point after the catch block. In some circumstances, a given exception may be critical enough to warrant the termination of the application. However, in a good number of cases, the logic within the exception handler will ensure the application can continue on its merry way (although it may be slightly less functional, such as not being able to connect to a remote data source).

Configuring the State of an Exception

Currently, the `System.Exception` object configured within the `Accelerate()` method simply establishes a value exposed to the `Message` property (via a constructor parameter). As shown previously in Table 7-1, however, the `Exception` class also supplies a number of additional members (`TargetSite`, `StackTrace`,

`HelpLink`, and `Data`) that can be useful in further qualifying the nature of the problem. To spruce up our current example, let's examine further details of these members on a case-by-case basis.

The TargetSite Property

The `System.Exception.TargetSite` property allows you to determine various details about the method that threw a given exception. As shown in the previous `Main()` method, printing the value of `TargetSite` will display the return type, name, and parameter types of the method that threw the exception. However, `TargetSite` does not return just a vanilla-flavored string, but rather a strongly typed `System.Reflection.MethodBase` object. This type can be used to gather numerous details regarding the offending method, as well as the class that defines the offending method. To illustrate, assume the previous catch logic has been updated as follows:

```
static void Main(string[] args)
{
...
// TargetSite actually returns a MethodBase object.
catch(Exception e)
{
    Console.WriteLine("\n*** Error! ***");
    Console.WriteLine("Member name: {0}", e.TargetSite);
    Console.WriteLine("Class defining member: {0}", e.TargetSite.DeclaringType);
    Console.WriteLine("Member type: {0}", e.TargetSite.MemberType);
    Console.WriteLine("Message: {0}", e.Message);
    Console.WriteLine("Source: {0}", e.Source);
}
Console.WriteLine("\n***** Out of exception logic *****");
Console.ReadLine();
}
```

This time, you make use of the `MethodBase.DeclaringType` property to determine the fully qualified name of the class that threw the error (`SimpleException.Car` in this case) as well as the `MemberType` property of the `MethodBase` object to identify the type of member (such as a property vs. a method) where this exception originated. In this case, the catch logic would display the following:

```
*** Error! ***
Member name: Void Accelerate(Int32)
Class defining member: SimpleException.Car
Member type: Method
Message: Zippy has overheated!
Source: SimpleException
```

The StackTrace Property

The `System.Exception.StackTrace` property allows you to identify the series of calls that resulted in the exception. Be aware that you never set the value of `StackTrace` as it is established automatically at the time the exception is created. To illustrate, assume you have once again updated your catch logic:

```
catch(Exception e)
{
    ...
    Console.WriteLine("Stack: {0}", e.StackTrace);
}
```

If you were to run the program, you would find the following stack trace is printed to the console (your line numbers and file paths may differ, of course):

```
Stack: at SimpleException.Car.Accelerate(Int32 delta)
in c:\MyApps\SimpleException\car.cs:line 65 at SimpleException.Program.Main()
in c:\MyApps\SimpleException\Program.cs:line 21
```

The string returned from `StackTrace` documents the sequence of calls that resulted in the throwing of this exception. Notice how the bottommost line number of this string identifies the first call in the sequence, while the topmost line number identifies the exact location of the offending member. Clearly, this information can be quite helpful during the debugging or logging of a given application, as you are able to “follow the flow” of the error’s origin.

The HelpLink Property

While the `TargetSite` and `StackTrace` properties allow programmers to gain an understanding of a given exception, this information is of little use to the end user. As you have already seen, the `System.Exception.Message` property can be used to obtain human-readable information that can be displayed to the current user. In addition, the `HelpLink` property can be set to point the user to a specific URL or standard Windows help file that contains more detailed information.

By default, the value managed by the `HelpLink` property is an empty string. If you wish to fill this property with a more interesting value, you need to do so before throwing the `System.Exception` object. Here are the relevant updates to the `Car.Accelerate()` method:

```
public void Accelerate(int delta)
{
    if (carIsDead)
        Console.WriteLine("{0} is out of order...", PetName);
    else
    {
        CurrentSpeed += delta;
        if (CurrentSpeed >= MaxSpeed)
        {
            carIsDead = true;
            CurrentSpeed = 0;

            // We need to call the HelpLink property, thus we need to
            // create a local variable before throwing the Exception object.
            Exception ex =
                new Exception(string.Format("{0} has overheated!", PetName));
            ex.HelpLink = "http://www.CarsRUs.com";
            throw ex;
        }
    }
}
```

```

        }
    else
        Console.WriteLine("=> CurrentSpeed = {0}", CurrentSpeed);
    }
}

```

The catch logic could now be updated to print out this help link information as follows:

```

catch(Exception e)
{
    ...
    Console.WriteLine("Help Link: {0}", e.HelpLink);
}

```

The Data Property

The `Data` property of `System.Exception` allows you to fill an exception object with relevant auxiliary information (such as a time stamp). The `Data` property returns an object implementing an interface named `IDictionary`, defined in the `System.Collections` namespace. Chapter 9 examines the role of interface-based programming as well as the `System.Collections` namespace. For the time being, just understand that dictionary collections allow you to create a set of values that are retrieved using a specific key. Observe the next update to the `Car.Accelerate()` method:

```

public void Accelerate(int delta)
{
    if (carIsDead)
        Console.WriteLine("{0} is out of order...", PetName);
    else
    {
        CurrentSpeed += delta;
        if (CurrentSpeed >= MaxSpeed)
        {
            carIsDead = true;
            CurrentSpeed = 0;

            // We need to call the HelpLink property, thus we need
            // to create a local variable before throwing the Exception object.
            Exception ex =
                new Exception(string.Format("{0} has overheated!", PetName));
            ex.HelpLink = "http://www.CarsRUs.com";

            // Stuff in custom data regarding the error.
            ex.Data.Add("TimeStamp",
                string.Format("The car exploded at {0}", DateTime.Now));
            ex.Data.Add("Cause", "You have a lead foot.");
            throw ex;
        }
    }
}

```

```

        Console.WriteLine("=> CurrentSpeed = {0}", CurrentSpeed);
    }
}

```

To successfully enumerate over the key/value pairs, you must first make sure to specify a `using` directive for the `System.Collections` namespace, since you will use a `DictionaryEntry` type in the file containing the class implementing your `Main()` method:

```
using System.Collections;
```

Next, you need to update the catch logic to test that the value returned from the `Data` property is not `null` (the default value). After that, you make use of the `Key` and `Value` properties of the `DictionaryEntry` type to print the custom data to the console:

```

catch (Exception e)
{
...
// By default, the data field is empty, so check for null.
Console.WriteLine("\n-> Custom Data:");
if (e.Data != null)
{
    foreach (DictionaryEntry de in e.Data)
        Console.WriteLine("-> {0}: {1}", de.Key, de.Value);
}
}

```

With this, here's the final output you'd see:

```

***** Simple Exception Example *****
=> Creating a car and stepping on it!
Jamming...
=> CurrentSpeed = 30
=> CurrentSpeed = 40
=> CurrentSpeed = 50
=> CurrentSpeed = 60
=> CurrentSpeed = 70
=> CurrentSpeed = 80
=> CurrentSpeed = 90

*** Error! ***
Member name: Void Accelerate(Int32)
Class defining member: SimpleException.Car
Member type: Method
Message: Zippy has overheated!
Source: SimpleException
Stack: at SimpleException.Car.Accelerate(Int32 delta)
      at SimpleException.Program.Main(String[] args)
Help Link: http://www.CarsRUs.com

-> Custom Data:
-> TimeStamp: The car exploded at 1/12/2010 8:02:12 PM

```

-> Cause: You have a lead foot.

***** Out of exception logic *****

The `Data` property is very useful in that it allows us to pack in custom information regarding the error at hand, without requiring the building of a brand-new class type to extend the `Exception` base class (which, prior to .NET 2.0, was our only option!). As helpful as the `Data` property may be, however, it is still common for .NET developers to build strongly typed exception classes, which handle custom data using strongly typed properties.

This approach allows the caller to catch a specific exception-derived type, rather than having to dig into a data collection to obtain additional details. To understand how to do this, we need to examine the distinction between system-level and application-level exceptions.

Source Code The `SimpleException` project is included under the Chapter 7 subdirectory.

System-Level Exceptions (`System.SystemException`)

The .NET base class libraries define many classes that ultimately derive from `System.Exception`. For example, the `System` namespace defines core exception objects such as `ArgumentOutOfRangeException`, `IndexOutOfRangeException`, `StackOverflowException`, and so forth. Other namespaces define exceptions that reflect the behavior of that namespace. For example, `System.Drawing.Printing` defines printing exceptions, `System.IO` defines input/output-based exceptions, `System.Data` defines database-centric exceptions, and so forth.

Exceptions that are thrown by the .NET platform are (appropriately) called *system exceptions*. These exceptions are regarded as non-recoverable, fatal errors. System exceptions derive directly from a base class named `System.SystemException`, which in turn derives from `System.Exception` (which derives from `System.Object`):

```
public class SystemException : Exception
{
    // Various constructors.
}
```

Given that the `System.SystemException` type does not add any additional functionality beyond a set of custom constructors, you might wonder why `SystemException` exists in the first place. Simply put, when an exception type derives from `System.SystemException`, you are able to determine that the .NET runtime is the entity that has thrown the exception, rather than the code base of the executing application. You can verify this quite simply using the `is` keyword:

```
// True! NullReferenceException is-a SystemException.
NullReferenceException nullRefEx = new NullReferenceException();

Console.WriteLine("NullReferenceException is-a SystemException? : {0}",
    nullRefEx is SystemException);
```

Application-Level Exceptions (`System.ApplicationException`)

Given that all .NET exceptions are class types, you are free to create your own application-specific exceptions. However, due to the fact that the `System.SystemException` base class represents exceptions thrown from the CLR, you may naturally assume that you should derive your custom exceptions from the `System.Exception` type. You could do this, but you could instead derive from the `System.ApplicationException` class:

```
public class ApplicationException : Exception
{
    // Various constructors.
}
```

Like `SystemException`, `ApplicationException` does not define any additional members beyond a set of constructors. Functionally, the only purpose of `System.ApplicationException` is to identify the source of the error. When you handle an exception deriving from `System.ApplicationException`, you can assume the exception was raised by the code base of the executing application, rather than by the .NET base class libraries or .NET runtime engine.

Building Custom Exceptions, Take One

While you can always throw instances of `System.Exception` to signal a runtime error (as shown in the first example), it is sometimes advantageous to build a *strongly typed exception* that represents the unique details of your current problem. For example, assume you wish to build a custom exception (named `CarIsDeadException`) to represent the error of speeding up a doomed automobile. The first step is to derive a new class from `System.Exception/System.ApplicationException` (by convention, all exception classes end with the “Exception” suffix; in fact, this is a .NET best practice).

Note As a rule, all custom exception classes should be defined as public classes (recall, the default access modifier of a non-nested type is internal). The reason is that exceptions are often passed outside of assembly boundaries, and should therefore be accessible to the calling code base.

Create a new Console Application project named `CustomException`, and copy the previous `Car.cs` and `Radio.cs` files into your new project using the `Project > Add Existing Item` menu option (for clarity, be sure to change the namespace that defines the `Car` and `Radio` types from `SimpleException` to `CustomException`). Next, add the following class definition:

```
// This custom exception describes the details of the car-is-dead condition.
public class CarIsDeadException : ApplicationException
{}
```

As with any class, you are free to include any number of custom members that can be called within the catch block of the calling logic. You are also free to override any virtual members defined by your parent classes. For example, we could implement the `CarIsDeadException` by overriding the virtual `Message` property.

As well, rather than populating a data dictionary (via the `Data` property) when throwing our exception, our constructor allows the sender to pass in a time stamp and reason for the error. Finally, the time stamp data and cause of the error can be obtained using strongly typed properties:

```
public class CarIsDeadException : ApplicationException
{
    private string messageDetails = String.Empty;
    public DateTime ErrorTimeStamp {get; set;}
    public string CauseOfError {get; set;}

    public CarIsDeadException(){}
    public CarIsDeadException(string message,
        string cause, DateTime time)
    {
        messageDetails = message;
        CauseOfError = cause;
        ErrorTimeStamp = time;
    }

    // Override the Exception.Message property.
    public override string Message
    {
        get
        {
            return string.Format("Car Error Message: {0}", messageDetails);
        }
    }
}
```

Here, the `CarIsDeadException` class maintains a private field (`messageDetails`) that represents data regarding the current exception, which can be set using a custom constructor. Throwing this exception from the `Accelerate()` method is straightforward. Simply allocate, configure, and throw a `CarIsDeadException` type rather than a `System.Exception` (notice that in this case, we no longer need to fill the data collection manually):

```
// Throw the custom CarIsDeadException.
public void Accelerate(int delta)
{
    ...
    CarIsDeadException ex =
        new CarIsDeadException (string.Format("{0} has overheated!", PetName),
            "You have a lead foot", DateTime.Now);
    ex.HelpLink = "http://www.CarsRUs.com";
    throw ex;
}
```

To catch this incoming exception, your catch scope can now be updated to catch a specific `CarIsDeadException` type (however, given that `CarIsDeadException` “is-a” `System.Exception`, it is still permissible to catch a `System.Exception` as well):

```
static void Main(string[] args)
{
```

```

Console.WriteLine("***** Fun with Custom Exceptions *****\n");
Car myCar = new Car("Rusty", 90);

try
{
    // Trip exception.
    myCar.Accelerate(50);
}
catch (CarIsDeadException e)
{
    Console.WriteLine(e.Message);
    Console.WriteLine(e.ErrorTimeStamp);
    Console.WriteLine(e.CauseOfError);
}
Console.ReadLine();
}

```

So, now that you understand the basic process of building a custom exception, you may wonder when you are required to do so. Typically, you only need to create custom exceptions when the error is tightly bound to the class issuing the error (for example, a custom file-centric class that throws a number of file-related errors, a Car class that throws a number of car-related errors, a data access object that throws errors regarding a particular database table, and so forth). In doing so, you provide the caller with the ability to handle numerous exceptions on a descriptive error-by-error basis.

Building Custom Exceptions, Take Two

The current `CarIsDeadException` type has overridden the virtual `System.Exception.Message` property in order to configure a custom error message, and has supplied two custom properties to account for additional bits of data. In reality, however, you are not required to override the virtual `Message` property, as you could simply pass the incoming message to the parent's constructor as follows:

```

public class CarIsDeadException : ApplicationException
{
    public DateTime ErrorTimeStamp { get; set; }
    public string CauseOfError { get; set; }

    public CarIsDeadException() { }

    // Feed message to parent constructor.
    public CarIsDeadException(string message, string cause, DateTime time)
        :base(message)
    {
        CauseOfError = cause;
        ErrorTimeStamp = time;
    }
}

```

Notice that this time you have *not* defined a string variable to represent the message, and have *not* overridden the `Message` property. Rather, you are simply passing the parameter to your base class constructor. With this design, a custom exception class is little more than a uniquely named class

deriving from `System.ApplicationException`, (with additional properties if appropriate), devoid of any base class overrides.

Don't be surprised if most (if not all) of your custom exception classes follow this simple pattern. Many times, the role of a custom exception is not necessarily to provide additional functionality beyond what is inherited from the base classes, but to supply a *strongly named type* that clearly identifies the nature of the error, so the client can provide different handler-logic for different types of exceptions.

Building Custom Exceptions, Take Three

If you wish to build a truly prim-and-proper custom exception class, you would want to make sure your type adheres to .NET best practices. Specifically, this requires that your custom exception

- Derives from `ApplicationException`
- Is marked with the `[System.Serializable]` attribute
- Defines a default constructor
- Defines a constructor that sets the inherited `Message` property
- Defines a constructor to handle “inner exceptions”
- Defines a constructor to handle the serialization of your type

Now, based on your current background with .NET, you may have no idea regarding the role of attributes or object serialization, which is just fine. I'll address these topics later in the text (see Chapter 15 for information on attributes and Chapter 20 for details on serialization services). However, to complete our examination of building custom exceptions, here is the final iteration of `CarIsDeadException`, which accounts for each of these special constructors:

```
[Serializable]
public class CarIsDeadException : ApplicationException
{
    public CarIsDeadException() { }
    public CarIsDeadException(string message) : base( message ) { }
    public CarIsDeadException(string message,
                             System.Exception inner)
        : base( message, inner ) { }
    protected CarIsDeadException(
        System.Runtime.Serialization.SerializationInfo info,
        System.Runtime.Serialization.StreamingContext context)
        : base( info, context ) { }

    // Any additional custom properties, constructors and data members...
}
```

Given that building custom exceptions that adhere to .NET best practices really differ by only their name, you will be happy to know that Visual Studio 2010 provides a code snippet template named “Exception” (see Figure 7-1) that will autogenerate a new exception class that adheres to .NET best practices. (Recall from Chapter 2, a code snippet can be activated by typing its name [`exception` in this case] and pressing the Tab key twice.)




Figure 7-1. The Exception code snippet template

■ **Source Code** The CustomException project is included under the Chapter 7 subdirectory.

Processing Multiple Exceptions

In its simplest form, a try block has a single catch block. In reality, though, you often run into situations where the statements within a try block could trigger *numerous* possible exceptions. Create a new C# Console Application project named ProcessMultipleExceptions, add the Car.cs, Radio.cs, and CarIsDeadException.cs files from the previous CustomException example into the new project (via Project ► Add Existing Item), and update your namespace names accordingly.

Now, update the Car's Accelerate() method to also throw a predefined base class library ArgumentOutOfRangeException if you pass an invalid parameter (which we will assume is any value less than zero). Note the constructor of this exception class takes the name of the offending argument as the first string, followed by a message describing the error.

```
// Test for invalid argument before proceeding.
public void Accelerate(int delta)
{
    if(delta < 0)
        throw new
            ArgumentOutOfRangeException("delta", "Speed must be greater than zero!");
    ...
}
```

The catch logic could now specifically respond to each type of exception:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Handling Multiple Exceptions *****\n");
    Car myCar = new Car("Rusty", 90);
    try
    {
        // Trip Arg out of range exception.
        myCar.Accelerate(-10);
    }
```

```

catch (CarIsDeadException e)
{
    Console.WriteLine(e.Message);
}
catch (ArgumentOutOfRangeException e)
{
    Console.WriteLine(e.Message);
}
Console.ReadLine();
}

```

When you are authoring multiple catch blocks, you must be aware that when an exception is thrown, it will be processed by the “first available” catch. To illustrate exactly what the “first available” catch means, assume you retrofitted the previous logic with an additional catch scope that attempts to handle all exceptions beyond `CarIsDeadException` and `ArgumentOutOfRangeException` by catching a general `System.Exception` as follows:

```

// This code will not compile!
static void Main(string[] args)
{
    Console.WriteLine("***** Handling Multiple Exceptions *****\n");
    Car myCar = new Car("Rusty", 90);

    try
    {
        // Trigger an argument out of range exception.
        myCar.Accelerate(-10);
    }
    catch(Exception e)
    {
        // Process all other exceptions?
        Console.WriteLine(e.Message);
    }
    catch (CarIsDeadException e)
    {
        Console.WriteLine(e.Message);
    }
    catch (ArgumentOutOfRangeException e)
    {
        Console.WriteLine(e.Message);
    }
    Console.ReadLine();
}

```

This exception-handling logic generates compile-time errors. The problem is due to the fact that the first catch block can handle *anything* derived from `System.Exception` (given the “is-a” relationship), including the `CarIsDeadException` and `ArgumentOutOfRangeException` types. Therefore, the final two catch blocks are unreachable!

The rule of thumb to keep in mind is to make sure your catch blocks are structured such that the very first catch is the most specific exception (i.e., the most derived type in an exception-type inheritance chain), leaving the final catch for the most general (i.e., the base class of a given exception inheritance chain, in this case `System.Exception`).

Thus, if you wish to define a catch block that will handle any errors beyond `CarIsDeadException` and `ArgumentOutOfRangeException`, you could write the following:

```
// This code compiles just fine.
static void Main(string[] args)
{
    Console.WriteLine("***** Handling Multiple Exceptions *****\n");
    Car myCar = new Car("Rusty", 90);
    try
    {
        // Trigger an argument out of range exception.
        myCar.Accelerate(-10);
    }
    catch (CarIsDeadException e)
    {
        Console.WriteLine(e.Message);
    }
    catch (ArgumentOutOfRangeException e)
    {
        Console.WriteLine(e.Message);
    }
    // This will catch any other exception
    // beyond CarIsDeadException or
    // ArgumentOutOfRangeException.
    catch (Exception e)
    {
        Console.WriteLine(e.Message);
    }
    Console.ReadLine();
}
```

Note Where at all possible, always favor catching specific exception classes, rather than a general `System.Exception`. Though it might appear to make life simple in the short term (you may think, “Ah! This catches all the other things I don’t care about.”), in the long term you could end up with strange runtime crashes, as a more serious error was not directly dealt with in your code. Remember, a final catch block that deals with `System.Exception` tends to be very general indeed.

General catch Statements

C# also supports a “general” catch scope that does not explicitly receive the exception object thrown by a given member:

```
// A generic catch.
static void Main(string[] args)
{
    Console.WriteLine("***** Handling Multiple Exceptions *****\n");
```

```

Car myCar = new Car("Rusty", 90);
try
{
    myCar.Accelerate(90);
}
catch
{
    Console.WriteLine("Something bad happened...");
}
Console.ReadLine();
}

```

Obviously, this is not the most informative way to handle exceptions, since you have no way to obtain meaningful data about the error that occurred (such as the method name, call stack, or custom message). Nevertheless, C# does allow for such a construct, which can be helpful when you want to handle all errors in a very, very general fashion.

Rethrowing Exceptions

When you catch an exception, it is permissible for the logic in a try block to *rethrow* the exception up the call stack to the previous caller. To do so, simply use the throw keyword within a catch block. This passes the exception up the chain of calling logic, which can be helpful if your catch block is only able to partially handle the error at hand:

```

// Passing the buck.
static void Main(string[] args)
{
...
try
{
    // Speed up car logic...
}
catch(CarIsDeadException e)
{
    // Do any partial processing of this error and pass the buck.
    throw;
}
...
}

```

Be aware that in this example code, the ultimate receiver of CarIsDeadException is the CLR, since it is the Main() method rethrowing the exception. Because of this, your end user is presented with a system-supplied error dialog box. Typically, you would only rethrow a partially handled exception to a caller that has the ability to handle the incoming exception more gracefully.

Notice as well that we are not explicitly rethrowing the CarIsDeadException object, but rather making use of the throw keyword with no argument. We're not creating a new exception object; we're just rethrowing the original exception object (with all its original information). Doing so preserves the context of the original target.

Inner Exceptions

As you may suspect, it is entirely possible to trigger an exception at the time you are handling another exception. For example, assume you are handling a `CarIsDeadException` within a particular catch scope, and during the process you attempt to record the stack trace to a file on your C: drive named `carErrors.txt` (you must specify you are using the `System.IO` namespace to gain access to these I/O-centric types):

```
catch(CarIsDeadException e)
{
    // Attempt to open a file named carErrors.txt on the C drive.
    FileStream fs = File.Open(@"C:\carErrors.txt", FileMode.Open);
    ...
}
```

Now, if the specified file is not located on your C: drive, the call to `File.Open()` results in a `FileNotFoundException`! Later in this text, you will learn all about the `System.IO` namespace where you'll discover how to programmatically determine whether a file exists on the hard drive before attempting to open the file in the first place (thereby avoiding the exception altogether). However, to stay focused on the topic of exceptions, assume the exception has been raised.

When you encounter an exception while processing another exception, best practice states that you should record the new exception object as an “inner exception” within a new object of the same type as the initial exception. (That was a mouthful!) The reason you need to allocate a new object of the exception being handled is that the only way to document an inner exception is via a constructor parameter. Consider the following code:

```
catch (CarIsDeadException e)
{
    try
    {
        FileStream fs = File.Open(@"C:\carErrors.txt", FileMode.Open);
        ...
    }
    catch (Exception e2)
    {
        // Throw an exception that records the new exception,
        // as well as the message of the first exception.
        throw new CarIsDeadException(e.Message, e2);
    }
}
```

Notice in this case, we have passed in the `FileNotFoundException` object as the second parameter to the `CarIsDeadException` constructor. Once we have configured this new object, we throw it up the call stack to the next caller, which in this case would be the `Main()` method.

Given that there is no “next caller” after `Main()` to catch the exception, we would be again presented with an error dialog box. Much like the act of rethrowing an exception, recording inner exceptions is usually only useful when the caller has the ability to gracefully catch the exception in the first place. If this is the case, the caller's catch logic can make use of the `.InnerException` property to extract the details of the inner exception object.

The Finally Block

A try/catch scope may also define an optional finally block. The purpose of a finally block is to ensure that a set of code statements will *always* execute, exception (of any type) or not. To illustrate, assume you wish to always power down the car's radio before exiting Main(), regardless of any handled exception:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Handling Multiple Exceptions *****\n");
    Car myCar = new Car("Rusty", 90);
    myCar.CrankTunes(true);

    try
    {
        // Speed up car logic.
    }
    catch(CarIsDeadException e)
    {
        // Process CarIsDeadException.
    }
    catch(ArgumentOutOfRangeException e)
    {
        // Process ArgumentOutOfRangeException.
    }
    catch(Exception e)
    {
        // Process any other Exception.
    }
    finally
    {
        // This will always occur. Exception or not.
        myCar.CrankTunes(false);
    }
    Console.ReadLine();
}
```

If you did not include a finally block, the radio would not be turned off if an exception is encountered (which may or may not be problematic). In a more real-world scenario, when you need to dispose of objects, close a file, detach from a database (or whatever), a finally block ensures a location for proper cleanup.

Who Is Throwing What?

Given that a method in the .NET Framework could throw any number of exceptions under various circumstances, a logical question is, "How do I know which exceptions may be thrown by a given base class library method?" The ultimate answer is simple: consult the .NET Framework 4.0 SDK documentation. Each method in the help system documents the exceptions a given member may throw. As a quick alternative, Visual Studio 2010 allows you to view the list of all exceptions thrown by a base

class library member (if any) simply by hovering your mouse cursor over the member name in the code window (see Figure 7-2).




Figure 7-2. Identifying the exceptions thrown from a given method

For those coming to .NET from a Java background, understand that type members are not prototyped with the set of exceptions they may throw (in other words, C# does not support checked exceptions). For better or for worse, you are not required to handle each and every exception thrown from a given member.

The Result of Unhandled Exceptions

At this point, you might be wondering what would happen if you do not handle an exception thrown in your direction? Assume that the logic in Main() increases the speed of the Car object beyond the maximum speed, without the benefit of try/catch logic:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Handling Multiple Exceptions *****\n");
    Car myCar = new Car("Rusty", 90);
    myCar.Accelerate(500);
    Console.ReadLine();
}
```

The result of ignoring an exception would be rather obstructive to the end user of your application, as an “unhandled exception” dialog box is displayed (see Figure 7-3).




Figure 7-3. The result of not dealing with exceptions

Debugging Unhandled Exceptions Using Visual Studio

Do be aware that Visual Studio 2010 supplies a number of tools that help you debug unhandled custom exceptions. Again, assume you have increased the speed of a Car object beyond the maximum. If you start a debugging session within Visual Studio 2010 (using the Debug ► Start Debugging menu selection), Visual Studio automatically breaks at the time the uncaught exception is thrown. Better yet, you are presented with a window (see Figure 7-4) displaying the value of the Message property.




Figure 7-4. Debugging unhandled custom exceptions with Visual Studio 2010

Note If you fail to handle an exception thrown by a method in the .NET base class libraries, the Visual Studio 2010 debugger breaks at the statement that called the offending method.

If you click the View Detail link, you will find the details regarding the state of the object (see Figure 7-5).




Figure 7-5. Viewing exception details

Source Code The ProcessMultipleExceptions project is included under the Chapter 7 subdirectory.

A Brief Word Regarding Corrupted State Exceptions (CSE)

To wrap up our examination of C#'s structured exception handling support, allow me to mention a brand-new .NET 4.0 namespace called `System.Runtime.ExceptionServices` (which is a member of the `mscorlib.dll` assembly). This namespace is quite small, defining only two class types that can be used if you wish to equip various methods within your application (such as the `Main()` method) with the ability to intercept and process "corrupted state exceptions," otherwise known as *CSEs*.

As you learned back in Chapter 1, the .NET platform sits on top of the hosting operating system (such as Microsoft Windows). Now, based on your background in Windows programming, you may recall that the low-level Windows API has a very unique set of rules regarding the treatment of runtime errors, which look little like .NET's structured exception handling techniques.

Within the Windows API, it is possible to trap extremely low-level errors that represent "corrupted state" errors. Simply put, if the Windows OS sends out a corrupted state error, your program is in very bad shape. So much so, that there is no hope of recovery and the only corrective course of action is to terminate the program.

■ **Note** As a .NET programmer, the only times you may accidentally trigger a CSE error is if your C# code is using platform invocation services (to talk directly to the Windows API) or using C# pointer syntax (see Chapter 12).

Before the release of .NET 4.0, the CLR would allow these very low-level, OS-specific errors to be trapped using a general `System.Exception` catch block. The problem, however, was that if a CSE exception was somehow encountered and trapped within such a catch block, the .NET platform did not (and still does not) provide much by way of elegant recovery code.

Now, with the release of .NET 4.0, the CLR will *not* allow CSEs to be automatically caught within your .NET applications. Most of the time, this is exactly what you would want. However, if you did still wish to receive notifications of these OS-level errors (which would typically be only if you had some legacy code that required such notifications), you can make use of the `[HandledProcessCorruptedStateExceptions]` attribute.

While we have not yet examined the role of .NET attributes (see Chapter 15), for now just understand that this attribute can be applied on any method of your application, and when you do this, the method in question will have a chance to deal with these low-level OS errors. By way of a simple example, assuming you have imported the `System.Runtime.ExceptionServices` namespace into your C# code file, you could build the following `Main()` method:

```
[HandledProcessCorruptedStateExceptions]
static int Main(string[] args)
{
    try
    {
        // Assume Main() is invoking a method which
        // runs the entire program.
        RunMyApplication();
    }
    catch (Exception ex)
    {
        // If we get here, we know something really bad happened.
        // Just print out the message and exit the program...we are
        // doomed!
        Console.WriteLine("Ack! Huge problem: {0}", ex.Message);
        return -1;
    }
    return 0;
}
```

Here we have a `Main()` method that does little more than call a second method that deals with the entire running of the application. For this example, we will assume that `RunMyApplication()` makes liberal use of try/catch logic to deal with any expected error. However, since `Main()` has been marked with the `[HandledProcessCorruptedStateExceptions]` attribute, if a CSE error is encountered, the catching of the `System.Exception` is our last chance to do *something* before the program is terminated.

Here, the `Main()` method returns an `int`, rather than `void`. As explained in Chapter 3, by convention, returning zero to the OS indicates the application exits without error, while any other value (typically a negative number) signifies an error.

This text will not deal with the processing of these low-level Windows OS errors, and therefore, I won't comment on the role of `System.Runtime.ExceptionServices` beyond this point. If you are in need of further details, consult the .NET 4.0 Framework SDK documentation.

Summary

In this chapter, you examined the role of structured exception handling. When a method needs to send an error object to the caller, it will allocate, configure, and throw a specific `System.Exception` derived type via the C# `throw` keyword. The caller is able to handle any possible incoming exceptions using the C# `catch` keyword and an optional `finally` scope.

When you are creating your own custom exceptions, you ultimately create a class type deriving from `System.ApplicationException`, which denotes an exception thrown from the currently executing application. In contrast, error objects deriving from `System.SystemException` represent critical (and fatal) errors thrown by the CLR. Last but not least, this chapter illustrated various tools within Visual Studio 2010 that can be used to create custom exceptions (according to .NET best practices) as well as debug exceptions.

CHAPTER 8



Understanding Object Lifetime

At this point in the text, you have learned a great deal about how to build custom class types using C#. Now you will see how the CLR manages allocated class instances (aka, objects) via *garbage collection*. C# programmers never directly deallocate a managed object from memory (recall there is no `delete` keyword in the C# language). Rather, .NET objects are allocated to a region of memory termed the *managed heap*, where they will be automatically destroyed by the garbage collector “sometime in the future.”

Once you have looked at the core details of the collection process, you’ll learn how to programmatically interact with the garbage collector using the `System.GC` class type. Next, you’ll examine how the virtual `System.Object.Finalize()` method and `IDisposable` interface can be used to build classes that release internal *unmanaged resources* in a timely manner.

You will also delve into some new functionality of the garbage collector introduced with .NET 4.0, including background garbage collections and lazy instantiation using the generic `System.Lazy<T>` class. By the time you have completed this chapter, you will have a solid understanding of how .NET objects are managed by the CLR.

Classes, Objects, and References

To frame the topics covered in this chapter, it is important to further clarify the distinction between classes, objects, and references. Recall that a class is nothing more than a blueprint that describes how an instance of this type will look and feel in memory. Classes, of course, are defined within a code file (which in C# takes a *.cs extension by convention). Consider a simple `Car` class defined within a new C# Console Application project named `SimpleGC`:

```
// Car.cs
public class Car
{
    public int CurrentSpeed {get; set;}
    public string PetName {get; set;}

    public Car(){}
    public Car(string name, int speed)
    {
        PetName = name;
        CurrentSpeed = speed;
    }
}
```

```

public override string ToString()
{
    return string.Format("{0} is going {1} MPH",
        PetName, CurrentSpeed);
}
}

```

Once a class is defined, you can allocate any number of objects using the C# new keyword. Understand, however, that the new keyword returns a *reference* to the object on the heap, not the actual object itself. If you declare the reference variable as a local variable in a method scope, it is stored on the stack for further use in your application. When you wish to invoke members on the object, apply the C# dot operator to the stored reference:

```

class Program
{
    static void Main(string[] args)
    {
        Console.WriteLine("***** GC Basics *****");

        // Create a new Car object on
        // the managed heap. We are
        // returned a reference to this
        // object ("refToMyCar").
        Car refToMyCar = new Car("Zippy", 50);

        // The C# dot operator (.) is used
        // to invoke members on the object
        // using our reference variable.
        Console.WriteLine(refToMyCar.ToString());
        Console.ReadLine();
    }
}

```

Figure 8-1 illustrates the class, object, and reference relationship.




Figure 8-1. References to objects on the managed heap

■ **Note** Recall from Chapter 4 that structures are *value types* that are always allocated directly on the stack and are never placed on the .NET managed heap. Heap allocation only occurs when you are creating instances of classes.

The Basics of Object Lifetime

When you are building your C# applications, you are correct to assume that the .NET runtime environment will take care of the managed heap without your direct intervention. In fact, the golden rule of .NET memory management is simple:

■ **Rule** Allocate a class instance onto the managed heap using the new keyword and forget about it.

Once instantiated, the garbage collector will destroy an object when it is no longer needed. The next obvious question, of course, is, “How does the garbage collector determine when an object is no longer needed?” The short (i.e., incomplete) answer is that the garbage collector removes an object from the heap when it is *unreachable* by any part of your code base. Assume you have a method in your Program class that allocates a local Car object:

```
static void MakeACar()
{
    // If myCar is the only reference to the Car object,
    // it *may* be destroyed when this method returns.
    Car myCar = new Car();
}
```

Notice that this Car reference (*myCar*) has been created directly within the *MakeACar()* method and has not been passed outside of the defining scope (via a return value or ref/out parameters). Thus, once this method call completes, the *myCar* reference is no longer reachable, and the associated Car object is now a candidate for garbage collection. Understand, however, that you can’t guarantee that this object will be reclaimed from memory immediately after *MakeACar()* has completed. All you can assume at this point is that when the CLR performs the next garbage collection, the *myCar* object could be safely destroyed.

As you will most certainly discover, programming in a garbage-collected environment greatly simplifies your application development. In stark contrast, C++ programmers are painfully aware that if they fail to manually delete heap-allocated objects, memory leaks are never far behind. In fact, tracking down memory leaks is one of the most time-consuming (and tedious) aspects of programming in unmanaged environments. By allowing the garbage collector to take charge of destroying objects, the burden of memory management has been lifted from your shoulders and placed onto those of the CLR.

■ **Note** If you happen to have a background in COM development, note that .NET objects do not maintain an internal reference counter, and therefore managed objects do not expose methods such as `AddRef()` or `Release()`.

The CIL of new

When the C# compiler encounters the `new` keyword, it emits a CIL `newobj` instruction into the method implementation. If you compile the current example code and investigate the resulting assembly using `ildasm.exe`, you'd find the following CIL statements within the `MakeACar()` method:

```
.method private hidebysig static void MakeACar() cil managed
{
    // Code size 8 (0x8)
    .maxstack 1
    .locals init ([0] class SimpleGC.Car myCar)
    IL_0000:  nop
    IL_0001:  newobj instance void SimpleGC.Car:::ctor()
    IL_0006:  stloc.0
    IL_0007:  ret
} // end of method Program::MakeACar
```

Before we examine the exact rules that determine when an object is removed from the managed heap, let's check out the role of the CIL `newobj` instruction in a bit more detail. First, understand that the managed heap is more than just a random chunk of memory accessed by the CLR. The .NET garbage collector is quite a tidy housekeeper of the heap, given that it will compact empty blocks of memory (when necessary) for purposes of optimization. To aid in this endeavor, the managed heap maintains a pointer (commonly referred to as the *next object pointer* or *new object pointer*) that identifies exactly where the next object will be located.

That said, the `newobj` instruction tells the CLR to perform the following core operations:

- Calculate the total amount of memory required for the object to be allocated (including the memory required by the data members and the base classes).
- Examine the managed heap to ensure that there is indeed enough room to host the object to be allocated. If there is, the specified constructor is called and the caller is ultimately returned a reference to the new object in memory, whose address just happens to be identical to the last position of the next object pointer.
- Finally, before returning the reference to the caller, advance the next object pointer to point to the next available slot on the managed heap.

The basic process is illustrated in Figure 8-2.




Figure 8-2. The details of allocating objects onto the managed heap

As your application is busy allocating objects, the space on the managed heap may eventually become full. When processing the newobj instruction, if the CLR determines that the managed heap does not have sufficient memory to allocate the requested type, it will perform a garbage collection in an attempt to free up memory. Thus, the next rule of garbage collection is also quite simple:

■ Rule If the managed heap does not have sufficient memory to allocate a requested object, a garbage collection will occur.

Exactly *how* this garbage collection occurs, however, depends on which version of the .NET platform your application is running under. You'll look at the differences a bit later in this chapter.

Setting Object References to null

Those of you who created COM objects using Visual Basic 6.0 know that it was always preferable to set their references to Nothing when you were finished using them. Under the covers, the reference count of the COM object was decremented by one, and the object could be removed from memory if its reference count equaled 0. In a similar fashion, C/C++ programmers often set pointer variables to null to ensure they are no longer referencing unmanaged memory.

Given these facts, you might wonder what the end result is of assigning object references to null under C#. For example, assume the MakeACar() subroutine has now been updated as follows:

```
static void MakeACar()
{
    Car myCar = new Car();
    myCar = null;
}
```

When you assign object references to null, the compiler generates CIL code that ensures the reference (myCar in this example) no longer points to any object. If you once again made use of ildasm.exe to view the CIL code of the modified MakeACar(), you would find the ldnull opcode (which pushes a null value on the virtual execution stack) followed by a stloc.0 opcode (which sets the null reference on the variable):

```
.method private hidebysig static void MakeACar() cil managed
{
    // Code size 10 (0xa)
    .maxstack 1
    .locals init ([0] class SimpleGC.Car myCar)
    IL_0000: nop
    IL_0001: newobj instance void SimpleGC.Car:::.ctor()
    IL_0006: stloc.0
    IL_0007: ldnul
    IL_0008: stloc.0
    IL_0009: ret
} // end of method Program::MakeACar
```

What you must understand, however, is that assigning a reference to `null` does not in any way force the garbage collector to fire up at that exact moment and remove the object from the heap. The only thing you have accomplished is explicitly clipping the connection between the reference and the object it previously pointed to. Given this point, setting references to `null` under C# is far less consequential than doing so in other C-based languages (or VB 6.0); however, doing so will certainly not cause any harm.

The Role of Application Roots

Now, back to the topic of how the garbage collector determines when an object is no longer needed. To understand the details, you need to be aware of the notion of *application roots*. Simply put, a *root* is a storage location containing a reference to an object on the managed heap. Strictly speaking, a root can fall into any of the following categories:

- References to global objects (though these are not allowed in C#, CIL code does permit allocation of global objects)
- References to any static objects/static fields
- References to local objects within an application's code base
- References to object parameters passed into a method
- References to objects waiting to be *finalized* (described later in this chapter)
- Any CPU register that references an object

During a garbage collection process, the runtime will investigate objects on the managed heap to determine whether they are still reachable (i.e., rooted) by the application. To do so, the CLR will build an *object graph*, which represents each reachable object on the heap. Object graphs are explained in some detail during the discussion of object serialization in Chapter 20. For now, just understand that object graphs are used to document all reachable objects. As well, be aware that the garbage collector will never graph the same object twice, thus avoiding the nasty circular reference count found in COM programming.

Assume the managed heap contains a set of objects named A, B, C, D, E, F, and G. During a garbage collection, these objects (as well as any internal object references they may contain) are examined for active roots. Once the graph has been constructed, unreachable objects (which we will assume are objects C and F) are marked as garbage. Figure 8-3 diagrams a possible object graph for the scenario just

described (you can read the directional arrows using the phrase *depends on* or *requires*, for example, E depends on G and B, A depends on nothing, and so on).




Figure 8-3. Object graphs are constructed to determine which objects are reachable by application roots

Once an object has been marked for termination (C and F in this case—as they are not accounted for in the object graph), they are swept from memory. At this point, the remaining space on the heap is compacted, which in turn causes the CLR to modify the set of active application roots (and the underlying pointers) to refer to the correct memory location (this is done automatically and transparently). Last but not least, the next object pointer is readjusted to point to the next available slot. Figure 8-4 illustrates the resulting readjustment.




Figure 8-4. A clean and compacted heap

■ **Note** Strictly speaking, the garbage collector makes use of two distinct heaps, one of which is specifically used to store very large objects. This heap is less frequently consulted during the collection cycle, given possible performance penalties involved with relocating large objects. Regardless, it is safe to consider the managed heap as a single region of memory.

Understanding Object Generations

When the CLR is attempting to locate unreachable objects, it does not literally examine each and every object placed on the managed heap. Doing so, obviously, would involve considerable time, especially in larger (i.e., real-world) applications.

To help optimize the process, each object on the heap is assigned to a specific “generation.” The idea behind generations is simple: the longer an object has existed on the heap, the more likely it is to stay there. For example, the class that defined the main window of a desktop application will be in memory until the program terminates. Conversely, objects that have only recently been placed on the heap (such as an object allocated within a method scope) are likely to be unreachable rather quickly. Given these assumptions, each object on the heap belongs to one of the following generations:

- *Generation 0*: Identifies a newly allocated object that has never been marked for collection.
- *Generation 1*: Identifies an object that has survived a garbage collection (i.e., it was marked for collection but was not removed due to the fact that the sufficient heap space was acquired).
- *Generation 2*: Identifies an object that has survived more than one sweep of the garbage collector.

Note Generations 0 and 1 are termed ephemeral generations. As explained in the next section, you will see that the garbage collection process does treat ephemeral generations differently.

The garbage collector will investigate all generation 0 objects first. If marking and sweeping (or said more plainly, getting rid of) these objects results in the required amount of free memory, any surviving objects are promoted to generation 1. To see how an object’s generation affects the collection process, ponder Figure 8-5, which diagrams how a set of surviving generation 0 objects (A, B, and E) are promoted once the required memory has been reclaimed.




Figure 8-5. Generation 0 objects that survive a garbage collection are promoted to generation 1

If all generation 0 objects have been evaluated, but additional memory is still required, generation 1 objects are then investigated for reachability and collected accordingly. Surviving generation 1 objects are then promoted to generation 2. If the garbage collector *still* requires additional memory, generation 2 objects are evaluated. At this point, if a generation 2 object survives a garbage collection, it remains a generation 2 object given the predefined upper limit of object generations.

The bottom line is that by assigning a generational value to objects on the heap, newer objects (such as local variables) will be removed quickly, while older objects (such as a program's application object) are not "bothered" as often.

Concurrent Garbage Collection under .NET 1.0 - 3.5

Prior to .NET 4.0, the runtime would clean up unused objects using a technique termed *concurrent garbage collection*. Under this model, when a collection takes place for any generation 0 or generation 1 objects (recall these are *ephemeral generations*), the garbage collector temporarily suspends all active *threads* within the current process to ensure that the application does not access the managed heap during the collection process.

We will examine the topic of threads in Chapter 19; however, for the time being, simply regard a thread as a path of execution within a running executable. Once the garbage collection cycle has completed, the suspended threads are permitted to carry on their work. Thankfully, the .NET 3.5 (and earlier) garbage collector was highly optimized; you seldom (if ever) noticed this brief interruption in your application.

As an optimization, concurrent garbage collection allowed objects that were not located in one of the ephemeral generations to be cleaned up on a dedicated thread. This decreased (but didn't eliminate) the need for the .NET runtime to suspect active threads. Moreover, concurrent garbage collection allowed your program to continue allocating objects on the heap during the collection of non-ephemeral generations.

Background Garbage Collection under .NET 4.0

.NET 4.0 changes the way the garbage collector deals with thread suspension when it cleans up objects on the managed heap, using *background garbage collection*. Despite its name, this does not mean that all garbage collection now takes place on additional background threads of execution. Rather, if a background garbage collection is taking place for objects living in a non-ephemeral generation, the .NET runtime is now able to collect objects on the ephemeral generations using a dedicated background thread.

On a related note, the .NET 4.0 garbage collection has been improved to further reduce the amount of time a given thread involved with garbage collection details must be suspended. The end result of these changes is that the process of cleaning up unused objects living in generation 0 or generation 1 has been optimized and can result in better runtime performance of your programs (which is really important for real-time systems that require small (and predictable) GC stop time).

Do understand, however, that the introduction of this new garbage collection model has no effect on how you build your .NET applications. For all practical purposes, you can simply allow the .NET garbage collector to perform its work without your direct intervention (and be happy that the folks at Microsoft are improving the collection process in a transparent manner).

The System.GC Type

The base class libraries provide a class type named `System.GC` that allows you to programmatically interact with the garbage collector using a set of static members. Now, do be very aware that you will seldom (if ever) need to make use of this class directly in your code. Typically, the only time you will use the members of `System.GC` is when you are creating classes that make internal use of *unmanaged resources*. This could be the case if you are building a class that makes calls into the Windows C-based API using the .NET platform invocation protocol, or perhaps due to some very low level and complicated COM interop logic. Table 8-1 provides a rundown of some of the more interesting members (consult the .NET Framework 4.0 SDK documentation for complete details).

Table 8-1. Select Members of the `System.GC` Type

System.GC Member	Description
<code>AddMemoryPressure()</code> <code>RemoveMemoryPressure()</code>	Allows you to specify a numerical value that represents the calling object's "urgency level" regarding the garbage collection process. Be aware that these methods should alter pressure <i>in tandem</i> and thus never remove more pressure than the total amount you have added.
<code>Collect()</code>	Forces the GC to perform a garbage collection. This method has been overloaded to specify a generation to collect, as well as the mode of collection (via the <code>GCCollectionMode</code> enumeration).
<code>CollectionCount()</code>	Returns a numerical value representing how many times a given generation has been swept.
<code>GetGeneration()</code>	Returns the generation to which an object currently belongs.
<code>GetTotalMemory()</code>	Returns the estimated amount of memory (in bytes) currently allocated on the managed heap. A Boolean parameter specifies whether the call should wait for garbage collection to occur before returning.
<code>MaxGeneration</code>	Returns the maximum number of generations supported on the target system. Under Microsoft's .NET 4.0, there are three possible generations: 0, 1, and 2.
<code>SuppressFinalize()</code>	Sets a flag indicating that the specified object should not have its <code>Finalize()</code> method called.
<code>WaitForPendingFinalizers()</code>	Suspends the current thread until all finalizable objects have been finalized. This method is typically called directly after invoking <code>GC.Collect()</code> .

■ **Note** .NET 3.5 Service Pack 1 added the ability to receive notifications when a garbage collection is about to occur using a handful of new members. While this can be helpful in some limited scenarios, most applications will not need such functionality, and therefore I have chosen not to cover the details in this edition. If you are interested, look up “Garbage Collection Notifications” in the .NET Framework 4.0 SDK documentation.

To illustrate how the `System.GC` type can be used to obtain various garbage collection-centric details, consider the following `Main()` method, which makes use of several members of `GC`:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with System.GC *****");

    // Print out estimated number of bytes on heap.
    Console.WriteLine("Estimated bytes on heap: {0}",
        GC.GetTotalMemory(false));

    // MaxGeneration is zero based, so add 1 for display purposes.
    Console.WriteLine("This OS has {0} object generations.\n",
        (GC.MaxGeneration + 1));

    Car refToMyCar = new Car("Zippy", 100);
    Console.WriteLine(refToMyCar.ToString());

    // Print out generation of refToMyCar object.
    Console.WriteLine("Generation of refToMyCar is: {0}",
        GC.GetGeneration(refToMyCar));

    Console.ReadLine();
}
```

Forcing a Garbage Collection

Again, the whole purpose of the .NET garbage collector is to manage memory on our behalf. However, in some very rare circumstances, it may be beneficial to programmatically force a garbage collection using `GC.Collect()`. Specifically:

- Your application is about to enter into a block of code that you don't want interrupted by a possible garbage collection.
- Your application has just finished allocating an extremely large number of objects and you wish to remove as much of the acquired memory as soon as possible.

If you determine it may be beneficial to have the garbage collector check for unreachable objects, you could explicitly trigger a garbage collection, as follows:

```
static void Main(string[] args)
{
```

```
...
// Force a garbage collection and wait for
// each object to be finalized.
GC.Collect();
GC.WaitForPendingFinalizers();
...
}
```

When you manually force a garbage collection, you should always make a call to `GC.WaitForPendingFinalizers()`. With this approach, you can rest assured that all *finalizable objects* (described in the next section) have had a chance to perform any necessary cleanup before your program continues. Under the hood, `GC.WaitForPendingFinalizers()` will suspend the calling “thread” during the collection process. This is a good thing, as it ensures your code does not invoke methods on an object currently being destroyed!

The `GC.Collect()` method can also be supplied a numerical value that identifies the oldest generation on which a garbage collection will be performed. For example, to instruct the CLR to investigate only generation 0 objects, you would write the following:

```
static void Main(string[] args)
{
...
// Only investigate generation 0 objects.
GC.Collect(0);
GC.WaitForPendingFinalizers();
...
}
```

As well, the `Collect()` method can also be passed in a value of the `GCCollectionMode` enumeration as a second parameter, to fine-tune exactly how the runtime should force the garbage collection. This enum defines the following values:

```
public enum GCCollectionMode
{
    Default,      // Forced is the current default.
    Forced,       // Tells the runtime to collect immediately!
    Optimized     // Allows the runtime to determine
                  // whether the current time is optimal to reclaim objects.
}
```

As with any garbage collection, calling `GC.Collect()` promotes surviving generations. To illustrate, assume that our `Main()` method has been updated as follows:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with System.GC *****");

    // Print out estimated number of bytes on heap.
    Console.WriteLine("Estimated bytes on heap: {0}",
        GC.GetTotalMemory(false));

    // MaxGeneration is zero based.
    Console.WriteLine("This OS has {0} object generations.\n",
        (GC.MaxGeneration + 1));
```

```

Car refToMyCar = new Car("Zippy", 100);
Console.WriteLine(refToMyCar.ToString());

// Print out generation of refToMyCar.
Console.WriteLine("\nGeneration of refToMyCar is: {0}",
    GC.GetGeneration(refToMyCar));

// Make a ton of objects for testing purposes.
object[] tonsOfObjects = new object[50000];
for (int i = 0; i < 50000; i++)
    tonsOfObjects[i] = new object();

// Collect only gen 0 objects.
GC.Collect(0, GCCollectionMode.Forced);
GC.WaitForPendingFinalizers();

// Print out generation of refToMyCar.
Console.WriteLine("Generation of refToMyCar is: {0}",
    GC.GetGeneration(refToMyCar));

// See if tonsOfObjects[9000] is still alive.
if (tonsOfObjects[9000] != null)
{
    Console.WriteLine("Generation of tonsOfObjects[9000] is: {0}",
        GC.GetGeneration(tonsOfObjects[9000]));
}
else
    Console.WriteLine("tonsOfObjects[9000] is no longer alive.");

// Print out how many times a generation has been swept.
Console.WriteLine("\nGen 0 has been swept {0} times",
    GC.CollectionCount(0));
Console.WriteLine("Gen 1 has been swept {0} times",
    GC.CollectionCount(1));
Console.WriteLine("Gen 2 has been swept {0} times",
    GC.CollectionCount(2));
Console.ReadLine();
}

```

Here, we have purposely created a very large array of object types (50,000 to be exact) for testing purposes. As you can see from the output that follows, even though this Main() method only made one explicit request for a garbage collection (via the GC.Collect() method), the CLR performed a number of them in the background.

```

***** Fun with System.GC *****
Estimated bytes on heap: 70240
This OS has 3 object generations.

```

Zippy is going 100 MPH

Generation of refToMyCar is: 0

```
Generation of refToMyCar is: 1
Generation of tonsOfObjects[9000] is: 1
```

```
Gen 0 has been swept 1 times
Gen 1 has been swept 0 times
Gen 2 has been swept 0 times
```

At this point, I hope you feel more comfortable regarding the details of object lifetime. In the next section, we'll examine the garbage collection process a bit further by addressing how you can build *finalizable objects* as well as *disposable objects*. Be very aware that the following techniques are useful only if you are building managed classes that maintain internal unmanaged resources.

Source Code The SimpleGC project is included under the Chapter 8 subdirectory.

Building Finalizable Objects

In Chapter 6, you learned that the supreme base class of .NET, `System.Object`, defines a virtual method named `Finalize()`. The default implementation of this method does nothing whatsoever:

```
// System.Object
public class Object
{
    ...
    protected virtual void Finalize() {}
}
```

When you override `Finalize()` for your custom classes, you establish a specific location to perform any necessary cleanup logic for your type. Given that this member is defined as protected, it is not possible to directly call an object's `Finalize()` method from a class instance via the dot operator. Rather, the *garbage collector* will call an object's `Finalize()` method (if supported) before removing the object from memory.

Note It is illegal to override `Finalize()` on structure types. This makes perfect sense given that structures are value types, which are never allocated on the heap to begin with and therefore are not garbage collected! However, if you create a structure that contains unmanaged resources that need to be cleaned up, you can implement the `IDisposable` interface (described shortly).

Of course, a call to `Finalize()` will (eventually) occur during a "natural" garbage collection or when you programmatically force a collection via `GC.Collect()`. In addition, a type's finalizer method will automatically be called when the application domain hosting your application is unloaded from

memory. Depending on your background in .NET, you may know that application domains (or simply AppDomains) are used to host an executable assembly and any necessary external code libraries. If you are not familiar with this .NET concept, you will be by the time you've finished Chapter 16. For now, note that when your AppDomain is unloaded from memory, the CLR automatically invokes finalizers for every finalizable object created during its lifetime.

Now, despite what your developer instincts may tell you, the vast majority of your C# classes will not require any explicit cleanup logic or a custom finalizer. The reason is simple: if your classes are just making use of other managed objects, everything will eventually be garbage-collected. The only time you would need to design a class that can clean up after itself is when you are using *unmanaged* resources (such as raw OS file handles, raw unmanaged database connections, chunks of unmanaged memory, or other unmanaged resources). Under the .NET platform, unmanaged resources are obtained by directly calling into the API of the operating system using Platform Invocation Services (PInvoke) or as a result of some very elaborate COM interoperability scenarios. Given this, consider the next rule of garbage collection:

Rule The only reason to override `Finalize()` is if your C# class is making use of unmanaged resources via `PInvoke` or complex COM interoperability tasks (typically via various members defined by the `System.Runtime.InteropServices.Marshal` type).

Overriding `System.Object.Finalize()`

In the rare case that you do build a C# class that uses unmanaged resources, you will obviously want to ensure that the underlying memory is released in a predictable manner. Suppose you have created a new C# Console Application named `SimpleFinalize` and inserted a class named `MyResourceWrapper` that uses an unmanaged resource (whatever that may be) and you want to override `Finalize()`. The odd thing about doing so in C# is that you can't do it using the expected `override` keyword:

```
class MyResourceWrapper
{
    // Compile-time error!
    protected override void Finalize(){ }
}
```

Rather, when you want to configure your custom C# class types to override the `Finalize()` method, you make use of a (C++-like) destructor syntax to achieve the same effect. The reason for this alternative form of overriding a virtual method is that when the C# compiler processes the finalizer syntax, it automatically adds a good deal of required infrastructure within the implicitly overridden `Finalize()` method (shown in just a moment).

C# finalizers look very similar to constructors in that they are named identically to the class they are defined within. In addition, finalizers are prefixed with a tilde symbol (~). Unlike a constructor, however, a finalizer never takes an access modifier (they are implicitly protected), never takes parameters, and can't be overloaded (only one finalizer per class).

Here is a custom finalizer for `MyResourceWrapper` that will issue a system beep when invoked. Obviously, this example is only for instructional purposes. A real-world finalizer would do nothing more than free any unmanaged resources and would *not* interact with other managed objects, even those

referenced by the current object, as you can't assume they are still alive at the point the garbage collector invokes your `Finalize()` method:

```
// Override System.Object.Finalize() via finalizer syntax.
class MyResourceWrapper
{
    ~MyResourceWrapper()
    {
        // Clean up unmanaged resources here.

        // Beep when destroyed (testing purposes only!)
        Console.Beep();
    }
}
```

If you were to examine this C# destructor using `ildasm.exe`, you would see that the compiler inserts some necessary error-checking code. First, the code statements within the scope of your `Finalize()` method are placed within a `try` block (see Chapter 7). The related `finally` block ensures that your base classes' `Finalize()` method will always execute, regardless of any exceptions encountered within the `try` scope:

```
.method family hidebysig virtual instance void
    Finalize() cil managed
{
    // Code size      13 (0xd)
    .maxstack  1
    .try
    {
        IL_0000: ldc.i4    0x4e20
        IL_0005: ldc.i4    0x3e8
        IL_000a: call
        void [mscorlib]System.Console::Beep(int32, int32)
        IL_000f: nop
        IL_0010: nop
        IL_0011: leave.s   IL_001b
    } // end .try
    finally
    {
        IL_0013: ldarg.0
        IL_0014:
            call instance void [mscorlib]System.Object::Finalize()
        IL_0019: nop
        IL_001a: endfinally
    } // end handler
    IL_001b: nop
    IL_001c: ret
} // end of method MyResourceWrapper::Finalize
```

If you then tested the `MyResourceWrapper` type, you would find that a system beep occurs when the application terminates, given that the CLR will automatically invoke finalizers upon AppDomain shutdown:

```

static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Finalizers *****\n");
    Console.WriteLine("Hit the return key to shut down this app");
    Console.WriteLine("and force the GC to invoke Finalize()");
    Console.WriteLine("for finalizable objects created in this AppDomain.");
    Console.ReadLine();
    MyResourceWrapper rw = new MyResourceWrapper();
}

```

Source Code The SimpleFinalize project is included under the Chapter 8 subdirectory.

Detailing the Finalization Process

Not to beat a dead horse, but always remember that the role of the `Finalize()` method is to ensure that a .NET object can clean up unmanaged resources when it is garbage-collected. Thus, if you are building a class that does not make use of unmanaged entities (by far the most common case), finalization is of little use. In fact, if at all possible, you should design your types to avoid supporting a `Finalize()` method for the very simple reason that finalization takes time.

When you allocate an object onto the managed heap, the runtime automatically determines whether your object supports a custom `Finalize()` method. If so, the object is marked as *finalizable*, and a pointer to this object is stored on an internal queue named the *finalization queue*. The finalization queue is a table maintained by the garbage collector that points to each and every object that must be finalized before it is removed from the heap.

When the garbage collector determines it is time to free an object from memory, it examines each entry on the finalization queue and copies the object off the heap to yet another managed structure termed the *finalization reachable* table (often abbreviated as *freachable*, and pronounced “eff-reachable”). At this point, a separate thread is spawned to invoke the `Finalize()` method for each object on the *freachable* table *at the next garbage collection*. Given this, it will take at the very least two garbage collections to truly finalize an object.

The bottom line is that while finalization of an object does ensure an object can clean up unmanaged resources, it is still nondeterministic in nature, and due to the extra behind-the-curtains processing, considerably slower.

Building Disposable Objects

As you have seen, finalizers can be used to release unmanaged resources when the garbage collector kicks in. However, given that many unmanaged objects are “precious items” (such as raw database or file handles), it may be valuable to release them as soon as possible instead of relying on a garbage collection to occur. As an alternative to overriding `Finalize()`, your class could implement the `IDisposable` interface, which defines a single method named `Dispose()`:

```

public interface IDisposable
{

```

```
    void Dispose();
}
```

If you are new to interface-based programming, Chapter 9 will take you through the details. In a nutshell, an interface is a collection of abstract members a class or structure may support. When you do support the `IDisposable` interface, the assumption is that when the *object user* is finished using the object, the object user manually calls `Dispose()` before allowing the object reference to drop out of scope. In this way, an object can perform any necessary cleanup of unmanaged resources without incurring the hit of being placed on the finalization queue and without waiting for the garbage collector to trigger the class's finalization logic.

Note Structures and class types can both implement `IDisposable` (unlike overriding `Finalize()`, which is reserved for class types), as the object user (not the garbage collector) invokes the `Dispose()` method.

To illustrate the use of this interface, create a new C# Console Application named `SimpleDispose`. Here is an updated `MyResourceWrapper` class that now implements `IDisposable`, rather than overriding `System.Object.Finalize()`:

```
// Implementing IDisposable.
class MyResourceWrapper : IDisposable
{
    // The object user should call this method
    // when they finish with the object.
    public void Dispose()
    {
        // Clean up unmanaged resources...

        // Dispose other contained disposable objects...

        // Just for a test.
        Console.WriteLine("***** In Dispose! *****");
    }
}
```

Notice that a `Dispose()` method is not only responsible for releasing the type's unmanaged resources, but should also call `Dispose()` on any other contained disposable methods. Unlike with `Finalize()`, it is perfectly safe to communicate with other managed objects within a `Dispose()` method. The reason is simple: the garbage collector has no clue about the `IDisposable` interface and will never call `Dispose()`. Therefore, when the object user calls this method, the object is still living a productive life on the managed heap and has access to all other heap-allocated objects. The calling logic is straightforward:

```
class Program
{
    static void Main(string[] args)
    {
        Console.WriteLine("***** Fun with Dispose *****\n");
```

```

    // Create a disposable object and call Dispose()
    // to free any internal resources.
    MyResourceWrapper rw = new MyResourceWrapper();
    rw.Dispose();
    Console.ReadLine();
}
}

```

Of course, before you attempt to call `Dispose()` on an object, you will want to ensure the type supports the `IDisposable` interface. While you will typically know which base class library types implement `IDisposable` by consulting the .NET Framework 4.0 SDK documentation, a programmatic check can be accomplished using the `is` or `as` keywords discussed in Chapter 6.:

```

class Program
{
    static void Main(string[] args)
    {
        Console.WriteLine("***** Fun with Dispose *****\n");
        MyResourceWrapper rw = new MyResourceWrapper();
        if (rw is IDisposable)
            rw.Dispose();
        Console.ReadLine();
    }
}

```

This example exposes yet another rule of working with garbage-collected types:

■ Rule Always call `Dispose()` on any object you directly create if the object supports `IDisposable`. The assumption you should make is that if the class designer chose to support the `Dispose()` method, the type has some cleanup to perform.

There is one caveat to the previous rule. A number of types in the base class libraries that do implement the `IDisposable` interface provide a (somewhat confusing) alias to the `Dispose()` method, in an attempt to make the disposal-centric method sound more natural for the defining type. By way of an example, while the `System.IO.FileStream` class implements `IDisposable` (and therefore supports a `Dispose()` method), it also defines a `Close()` method that is used for the same purpose:

```

// Assume you have imported
// the System.IO namespace...
static void DisposeFileStream()
{
    FileStream fs = new FileStream("myFile.txt", FileMode.OpenOrCreate);

    // Confusing, to say the least!
    // These method calls do the same thing!
    fs.Close();
    fs.Dispose();
}

```

While it does feel more natural to “close” a file rather than “dispose” of one, this doubling up of disposal-centric methods can be confusing. For the few types that do provide an alias, just remember that if a type implements `IDisposable`, calling `Dispose()` is always a correct course of action.

Reusing the C# using Keyword

When you are handling a managed object that implements `IDisposable`, it is quite common to make use of structured exception-handling to ensure the type’s `Dispose()` method is called in the event of a runtime exception:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Dispose *****\n");
    MyResourceWrapper rw = new MyResourceWrapper ();
    try
    {
        // Use the members of rw.
    }
    finally
    {
        // Always call Dispose(), error or not.
        rw.Dispose();
    }
}
```

While this is a fine example of defensive programming, the truth of the matter is that few developers are thrilled by the prospects of wrapping each and every disposable type within a `try/finally` block just to ensure the `Dispose()` method is called. To achieve the same result in a much less obtrusive manner, C# supports a special bit of syntax that looks like this:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Dispose *****\n");
    // Dispose() is called automatically when the
    // using scope exits.
    using(MyResourceWrapper rw = new MyResourceWrapper())
    {
        // Use rw object.
    }
}
```

If you looked at the CIL code of the `Main()` method using `ildasm.exe`, you would find the `using` syntax does indeed expand to `try/final` logic, with the expected call to `Dispose()`:

```
.method private hidebysig static void Main(string[] args) cil managed
{
...
.try
{
}
} // end .try
```

```

finally
{
...
IL_0012: callvirt instance void
    SimpleFinalize.MyResourceWrapper::Dispose()
} // end handler
...
} // end of method Program::Main

```

Note If you attempt to “use” an object that does not implement `IDisposable`, you will receive a compiler error.

While this syntax does remove the need to manually wrap disposable objects within `try/finally` logic, the C# `using` keyword unfortunately now has a double meaning (importing namespaces and invoking a `Dispose()` method). Nevertheless, when you are working with .NET types that support the `IDisposable` interface, this syntactical construct will ensure that the object “being used” will automatically have its `Dispose()` method called once the `using` block has exited.

Also, be aware that it is possible to declare multiple objects *of the same type* within a `using` scope. As you would expect, the compiler will inject code to call `Dispose()` on each declared object:

```

static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Dispose *****\n");

    // Use a comma-delimited list to declare multiple objects to dispose.
    using(MyResourceWrapper rw = new MyResourceWrapper(),
          rw2 = new MyResourceWrapper())
    {
        // Use rw and rw2 objects.
    }
}

```

Source Code The `SimpleDispose` project is included under the Chapter 8 subdirectory.

Building Finalizable and Disposable Types

At this point, we have seen two different approaches to constructing a class that cleans up internal unmanaged resources. On the one hand, you can override `System.Object.Finalize()`. Using this technique, you have the peace of mind that comes with knowing the object cleans itself up when garbage-collected (whenever that may be) without the need for user interaction. On the other hand, you can implement `IDisposable` to provide a way for the object user to clean up the object as soon as it is finished. However, if the caller forgets to call `Dispose()`, the unmanaged resources may be held in memory indefinitely.

As you might suspect, it is possible to blend both techniques into a single class definition. By doing so, you gain the best of both models. If the object user does remember to call `Dispose()`, you can inform the garbage collector to bypass the finalization process by calling `GC.SuppressFinalize()`. If the object user forgets to call `Dispose()`, the object will eventually be finalized and have a chance to free up the internal resources. The good news is that the object's internal unmanaged resources will be freed one way or another.

Here is the next iteration of `MyResourceWrapper`, which is now finalizable and disposable, defined in a C# Console Application named `FinalizableDisposableClass`:

```
// A sophisticated resource wrapper.
public class MyResourceWrapper : IDisposable
{
    // The garbage collector will call this method if the
    // object user forgets to call Dispose().
    ~MyResourceWrapper()
    {
        // Clean up any internal unmanaged resources.
        // Do **not** call Dispose() on any managed objects.
    }

    // The object user will call this method to clean up
    // resources ASAP.
    public void Dispose()
    {
        // Clean up unmanaged resources here.
        // Call Dispose() on other contained disposable objects.

        // No need to finalize if user called Dispose(),
        // so suppress finalization.
        GC.SuppressFinalize(this);
    }
}
```

Notice that this `Dispose()` method has been updated to call `GC.SuppressFinalize()`, which informs the CLR that it is no longer necessary to call the destructor when this object is garbage-collected, given that the unmanaged resources have already been freed via the `Dispose()` logic.

A Formalized Disposal Pattern

The current implementation of `MyResourceWrapper` does work fairly well; however, we are left with a few minor drawbacks. First, the `Finalize()` and `Dispose()` methods each have to clean up the same unmanaged resources. This could result in duplicate code, which can easily become a nightmare to maintain. Ideally, you would define a private helper function that is called by either method.

Next, you'd like to make sure that the `Finalize()` method does not attempt to dispose of any managed objects, while the `Dispose()` method should do so. Finally, you'd also like to be certain the object user can safely call `Dispose()` multiple times without error. Currently, our `Dispose()` method has no such safeguards.

To address these design issues, Microsoft defined a formal, prim-and-proper disposal pattern that strikes a balance between robustness, maintainability, and performance. Here is the final (and annotated) version of `MyResourceWrapper`, which makes use of this official pattern:

```

class MyResourceWrapper : IDisposable
{
    // Used to determine if Dispose()
    // has already been called.
    private bool disposed = false;

    public void Dispose()
    {
        // Call our helper method.
        // Specifying "true" signifies that
        // the object user triggered the cleanup.
        CleanUp(true);

        // Now suppress finalization.
        GC.SuppressFinalize(this);
    }

    private void CleanUp(bool disposing)
    {
        // Be sure we have not already been disposed!
        if (!this.disposed)
        {
            // If disposing equals true, dispose all
            // managed resources.
            if (disposing)
            {
                // Dispose managed resources.
            }
            // Clean up unmanaged resources here.
        }
        disposed = true;
    }

    ~MyResourceWrapper()
    {
        // Call our helper method.
        // Specifying "false" signifies that
        // the GC triggered the cleanup.
        CleanUp(false);
    }
}

```

Notice that `MyResourceWrapper` now defines a private helper method named `CleanUp()`. By specifying `true` as an argument, we indicate that the object user has initiated the cleanup, so we should clean up all managed *and* unmanaged resources. However, when the garbage collector initiates the cleanup, we specify `false` when calling `CleanUp()` to ensure that internal disposable objects are *not* disposed (as we can't assume they are still in memory!). Last but not least, our `bool` member variable (`disposed`) is set to `true` before exiting `CleanUp()` to ensure that `Dispose()` can be called numerous times without error.

■ **Note** After an object has been “disposed”, it’s still possible for the client to invoke members on it as it is still in memory. Therefore, a robust resource wrapper class would also need to update each member of the class with additional coding logic that says, in effect, “if I am disposed, do nothing and return from the member.”

To test our final iteration of `MyResourceWrapper`, add a call to `Console.Beep()` within the scope of your finalizer:

```
~MyResourceWrapper()
{
    Console.Beep();
    // Call our helper method.
    // Specifying "false" signifies that
    // the GC triggered the cleanup.
    CleanUp(false);
}
```

Next, update `Main()` as follows:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Dispose() / Destructor Combo Platter *****");

    // Call Dispose() manually, this will not call the finalizer.
    MyResourceWrapper rw = new MyResourceWrapper();
    rw.Dispose();

    // Don't call Dispose(), this will trigger the finalizer
    // and cause a beep.
    MyResourceWrapper rw2 = new MyResourceWrapper();
}
```

Notice that we are explicitly calling `Dispose()` on the `rw` object, so the destructor call is suppressed. However, we have “forgotten” to call `Dispose()` on the `rw2` object, and therefore, when the application terminates, we hear a single beep. If you were to comment out the call to `Dispose()` on the `rw` object, you would hear two beeps.

■ **Source Code** The `FinalizableDisposableClass` project is included under the Chapter 8 subdirectory.

That concludes our investigation of how the CLR manages your objects via garbage collection. While there are additional (somewhat esoteric) details regarding the collection process I haven’t covered here (such as weak references and object resurrection), you are now in a perfect position for further exploration on your own. To wrap this chapter up, we will examine a brand new .NET 4.0 programming feature called “lazy instantiation” of objects.

Understanding Lazy Object Instantiation

■ **Note** This section assumes you are comfortable with the topics of .NET generics and .NET delegates. If that's not the case, you may want to return to this section once you have completed Chapters 10 and 11.

When you are creating classes, you may occasionally need to account for a particular member variable in code, which may never actually be needed, in that the object user may not call the method (or property) that makes use of it. Fair enough. However, this can be very problematic if the member variable in question requires a large amount of memory to be instantiated.

For example, assume you are writing a class that encapsulates the operations of a digital music player. In addition to the expected methods, such as `Play()`, `Pause()`, and `Stop()`, you also want to provide the ability to return a collection of `Song` objects (via a class named `AllTracks`), which represents every single digital music file on the device.

If you'd like to follow along, create a new Console Application named `LazyObjectInstantiation`, and define the following class types:

```
// Represents a single song.
class Song
{
    public string Artist { get; set; }
    public string TrackName { get; set; }
    public double TrackLength { get; set; }
}

// Represents all songs on a player.
class AllTracks
{
    // Our media player can have a maximum
    // of 10,000 songs.
    private Song[] allSongs = new Song[10000];

    public AllTracks()
    {
        // Assume we fill up the array
        // of Song objects here.
        Console.WriteLine("Filling up the songs!");
    }
}

// The MediaPlayer has-a AllTracks object.
class MediaPlayer
{
    // Assume these methods do something useful.
    public void Play() { /* Play a song */ }
    public void Pause() { /* Pause the song */ }
```

```

public void Stop() { /* Stop playback */ }

private AllTracks allSongs = new AllTracks();

public AllTracks GetAllTracks()
{
    // Return all of the songs.
    return allSongs;
}
}

```

The current implementation of `MediaPlayer` makes the assumption that the object user will want to obtain a list of songs via the `GetAllTracks()` method. Well, what if the object user does *not* need to obtain this list? No matter, the `AllTracks` member variable will create 10,000 `Song` objects in memory:

```

static void Main(string[] args)
{
    // This caller does not care about getting all songs,
    // but indirectly created 10,000 objects!
    MediaPlayer myPlayer = new MediaPlayer();
    myPlayer.Play();

    Console.ReadLine();
}

```

Clearly, you would rather not create 10,000 objects that nobody will use, as that will add a good deal of stress to the .NET garbage collector. While you could manually add some code to ensure the `allSongs` object is only created if used (perhaps using the factory method design pattern), there is an easier way.

With the release of .NET 4.0, the base class libraries provide a very interesting generic class named `Lazy<T>`, defined in the `System` namespace of `mscorlib.dll`. This class allows you to define data that will *not* be created unless your code base actually makes use of it. As this is a generic class, you must specify the type of item to be created on first use, which can be any type with the .NET base class libraries or a custom type you have authored yourself. To enable lazy instantiation of the `AllTracks` member variable, you can simply replace this:

```

// The MediaPlayer has-a AllTracks object.
class MediaPlayer
{
    ...
    private AllTracks allSongs = new AllTracks();

    public AllTracks GetAllTracks()
    {
        // Return all of the songs.
        return allSongs;
    }
}

```

with this:

```
// The MediaPlayer has-a Lazy<AllTracks> object.
```

```

class MediaPlayer
{
...
    private Lazy<AllTracks> allSongs = new Lazy<AllTracks>();

    public AllTracks GetAllTracks()
    {
        // Return all of the songs.
        return allSongs.Value;
    }
}

```

Beyond the fact that we are now representing the `AllTracks` member variable as a `Lazy<>` type, notice that the implementation of the previous `GetAllTracks()` method has also been updated. Specifically, we must make use of the read-only `Value` property of the `Lazy<>` class to obtain the actual stored data (in this case, the `AllTracks` object that is maintaining the 10,000 `Song` objects).

With this simple update, notice how the following updated `Main()` method will indirectly allocate the `Song` objects only if `GetAllTracks()` is indeed called:

```

static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Lazy Instantiation *****\n");

    // No allocation of AllTracks object here!
    MediaPlayer myPlayer = new MediaPlayer();
    myPlayer.Play();

    // Allocation of AllTracks happens when you call GetAllTracks().
    MediaPlayer yourPlayer = new MediaPlayer();
    AllTracks yourMusic = yourPlayer.GetAllTracks();

    Console.ReadLine();
}

```

Customizing the Creation of the Lazy Data

When you declare a `Lazy<>` variable, the actual internal data type is created using the default constructor:

```

// Default constructor of AllTracks is called when the Lazy<>
// variable is used.
private Lazy<AllTracks> allSongs = new Lazy<AllTracks>();

```

While this might be fine in some cases, what if the `AllTracks` class had some additional constructors, and you want to ensure the correct one is called? Furthermore, what if you have some extra work do to (beyond simply creating the `AllTracks` object) when the `Lazy<>` variable is made? As luck would have it, the `Lazy<>` class allows you to specify a generic delegate as an optional parameter, which will specify a method to call during the creation of the wrapped type.

The generic delegate in question is of type `System.Func<>`, which can point to a method that returns the same data type being created by the related `Lazy<>` variable and can take up to 16 arguments (which

are typed using generic type parameters). In most cases, you will not need to specify any parameters to pass to the method pointed to by `Func<>`. Furthermore, to greatly simplify the use of the required `Func<>`, I'd recommend using a lambda expression (see Chapter 11 for details regarding the delegate/lambda relationship).

With this in mind, here is a final version of `MediaPlayer` that adds a bit of custom code when the wrapped `AllTracks` object is created. Remember, this method must return a new instance of the type wrapped by `Lazy<>` before exiting, and you can use any constructor you choose (here, we are still invoking the default constructor of `AllTracks`):

```
class MediaPlayer
{
    ...
    // Use a lambda expression to add additional code
    // when the AllTracks object is made.
    private Lazy<AllTracks> allSongs = new Lazy<AllTracks>(() =>
    {
        Console.WriteLine("Creating AllTracks object!");
        return new AllTracks();
    });
    public AllTracks GetAllTracks()
    {
        // Return all of the songs.
        return allSongs.Value;
    }
}
```

Sweet! Hopefully you can see the usefulness of the `Lazy<>` class. Essentially, this new generic class allows you to ensure expensive objects are only allocated when the object user requires them. If you find this topic useful for your projects, you may also want to look up the `System.Lazy<>` class in the .NET Framework 4.0 SDK documentation for further examples of how to program for "lazy instantiation".

Source Code The `LazyObjectInstantiation` project is included under the Chapter 8 subdirectory.

Summary

The point of this chapter was to demystify the garbage collection process. As you have seen, the garbage collector will only run when it is unable to acquire the necessary memory from the managed heap (or when a given AppDomain unloads from memory). When a collection does occur, you can rest assured that Microsoft's collection algorithm has been optimized by the use of object generations, secondary threads for the purpose of object finalization, and a managed heap dedicated to hosting large objects.

This chapter also illustrated how to programmatically interact with the garbage collector using the `System.GC` class type. As mentioned, the only time you will really need to do so is when you are building finalizable or disposable class types that operate on unmanaged resources.

Recall that finalizable types are classes that have overridden the virtual `System.Object.Finalize()` method to clean up unmanaged resources at the time of garbage collection. Disposable objects, on the other hand, are classes (or structures) that implement the `IDisposable` interface, which should be called by the object user when it is finished using said object. Finally, you learned about an official “disposal” pattern that blends both approaches.

We wrapped up this chapter with a look at a new .NET 4.0 generic class named `Lazy<>`. As you have seen, you can use this class to delay the creation of an expensive (in terms of memory consumption) object until the caller actually requires it. By doing so, you can help reduce the number of objects stored on the managed heap, and therefore ease the stress on the runtime garbage collector.

PART 3

■ ■ ■

Advanced C# Programming Constructs

CHAPTER 9



Working with Interfaces

This chapter builds on your current understanding of object-oriented development by examining the topic of interface-based programming. Here you'll learn how to define and implement interfaces, and come to understand the benefits of building types that support multiple behaviors. Along the way, I'll also discuss a number of related topics, such as obtaining interface references, explicit interface implementation, and the construction of interface hierarchies.

We'll also examine a number of standard interfaces defined within the .NET base class libraries. As you will see, your custom classes and structures are free to implement these predefined interfaces to support a number of advanced behaviors such as object cloning, object enumeration, and object sorting.

Understanding Interface Types

To begin this chapter, allow me to provide a formal definition of the interface type. An *interface* is nothing more than a named set of *abstract members*. Recall from Chapter 6 that abstract methods are pure protocol in that they do not provide a default implementation. The specific members defined by an interface depend on the exact behavior it is modeling. Yes, it's true. An interface expresses a *behavior* that a given class or structure may choose to support. Furthermore, as you will see in this chapter, a class (or structure) can support as many interfaces as necessary, thereby supporting (in essence) multiple behaviors.

As you might guess, the .NET base class libraries ship with hundreds of predefined interface types that are implemented by various classes and structures. For example, as you will see in Chapter 21, ADO.NET ships with multiple data providers that allow you to communicate with a particular database management system. Thus, under ADO.NET we have numerous connection objects to choose among (`SqlConnection`, `OracleConnection`, `OdbcConnection`, etc.).

Regardless of the fact that each connection object has a unique name, is defined within a different namespace, and (in some cases) is bundled within a different assembly, all connection objects implement a common interface named `IDbConnection`:

```
// The IDbConnection interface defines a common
// set of members supported by all connection objects.
public interface IDbConnection : IDisposable
{
    // Methods
    IDbTransaction BeginTransaction();
    IDbTransaction BeginTransaction(IsolationLevel il);
    void ChangeDatabase(string databaseName);
```

```

void Close();
IDbCommand CreateCommand();
void Open();

// Properties
string ConnectionString { get; set; }
int ConnectionTimeout { get; }
string Database { get; }
ConnectionState State { get; }
}

```

Note By convention, .NET interfaces are prefixed with a capital letter “I.” When you are creating your own custom interfaces, it is considered a best practice to do the same.

Don’t concern yourself with the details of what these members actually do at this point. Simply understand that the `IDbConnection` interface defines a set of members that are common to all ADO.NET connection objects. Given this, you are guaranteed that every connection object supports members such as `Open()`, `Close()`, `CreateCommand()`, and so forth. Furthermore, given that interface members are always abstract, each connection object is free to implement these methods in its own unique manner.

Another example: the `System.Windows.Forms` namespace defines a class named `Control`, which is a base class to a number of Windows Forms GUI widgets (`DataGridView`, `Label`, `Statusbar`, `TreeView`, etc.). The `Control` class implements an interface named `IDropTarget`, which defines basic drag-and-drop functionality:

```

public interface IDropTarget
{
    // Methods
    void OnDragDrop(DragEventArgs e);
    void OnDragEnter(DragEventArgs e);
    void OnDragLeave(EventArgs e);
    void OnDragOver(DragEventArgs e);
}

```

Based on this interface, you can correctly assume that any class that extends `System.Windows.Forms.Control` supports four methods named `OnDragDrop()`, `OnDragEnter()`, `OnDragLeave()`, and `OnDragOver()`.

As you work through the remainder of this book, you’ll be exposed to dozens of interfaces that ship with the .NET base class libraries. As you will see, these interfaces can be implemented on your own custom classes and structures to define types that integrate tightly within the framework.

Interface Types vs. Abstract Base Classes

Given your work in Chapter 6, the interface type may seem very similar to an abstract base class. Recall that when a class is marked as abstract, it *may* define any number of abstract members to provide a polymorphic interface to all derived types. However, even when a class does define a set of abstract

members, it is also free to define any number of constructors, field data, nonabstract members (with implementation), and so on. Interfaces, on the other hand, *only* contain abstract member definitions.

The polymorphic interface established by an abstract parent class suffers from one major limitation in that *only derived types* support the members defined by the abstract parent. However, in larger software systems, it is very common to develop multiple class hierarchies that have no common parent beyond `System.Object`. Given that abstract members in an abstract base class apply only to derived types, we have no way to configure types in different hierarchies to support the same polymorphic interface. By way of example, assume you have defined the following abstract class:

```
abstract class CloneableType
{
    // Only derived types can support this
    // "polymorphic interface." Classes in other
    // hierarchies have no access to this abstract
    // member.
    public abstract object Clone();
}
```

Given this definition, only members that extend `CloneableType` are able to support the `Clone()` method. If you create a new set of classes that do not extend this base class, you can't gain this polymorphic interface. Also you may recall, that C# does not support multiple inheritance for classes. Therefore, if you wanted to create a `MiniVan` that is-a `Car` and is-a `CloneableType`, you are unable to do so:

```
// Nope! Multiple inheritance is not possible in C#
// for classes.
public class MiniVan : Car, CloneableType
{ }
```

As you would guess, interface types come to the rescue. Once an interface has been defined, it can be implemented by any class or structure, in any hierarchy, within any namespace or any assembly (written in any .NET programming language). As you can see, interfaces are *highly* polymorphic. Consider the standard .NET interface named `ICloneable` defined in the `System` namespace. This interface defines a single method named `Clone()`:

```
public interface ICloneable
{
    object Clone();
}
```

If you examine the .NET Framework 4.0 SDK documentation, you'll find that a large number of seemingly unrelated types (`System.Array`, `System.Data.SqlClient.SqlConnection`, `System.OperatingSystem`, `System.String`, etc.) all implement this interface. Although these types have no common parent (other than `System.Object`), we can treat them polymorphically via the `ICloneable` interface type.

For example, if you had a method named `CloneMe()` that took an `ICloneable` interface parameter, you could pass this method any object that implements said interface. Consider the following simple `Program` class defined within a Console Application named `ICloneableExample`:

```
class Program
{
    static void Main(string[] args)
```

```

{
    Console.WriteLine("***** A First Look at Interfaces *****\n");

    // All of these classes support the ICloneable interface.
    string myStr = "Hello";
    OperatingSystem unixOS = new OperatingSystem(PlatformID.Unix, new Version());
    System.Data.SqlClient.SqlConnection sqlCnn =
        new System.Data.SqlClient.SqlConnection();

    // Therefore, they can all be passed into a method taking ICloneable.
    CloneMe(myStr);
    CloneMe(unixOS);
    CloneMe(sqlCnn);
    Console.ReadLine();
}

private static void CloneMe(ICloneable c)
{
    // Clone whatever we get and print out the name.
    object theClone = c.Clone();
    Console.WriteLine("Your clone is a: {0}",
        theClone.GetType().Name);
}

```

When you run this application, the class name of each class prints out to the console, via the `GetType()` method you inherit from `System.Object` (Chapter 15 provides full coverage of this method and .NET reflection services).

Source Code The `ICloneableExample` project is located under the Chapter 9 subdirectory.

Another limitation of traditional abstract base classes is that *each derived type* must contend with the set of abstract members and provide an implementation. To see this problem, recall the shapes hierarchy we defined in Chapter 6. Assume we defined a new abstract method in the `Shape` base class named `GetNumberOfPoints()`, which allows derived types to return the number of points required to render the shape:

```

abstract class Shape
{
    ...
    // Every derived class must now support this method!
    public abstract byte GetNumberOfPoints();
}

```

Clearly, the only type that has any points in the first place is `Hexagon`. However, with this update, *every* derived class (`Circle`, `Hexagon`, and `ThreeDCircle`) must now provide a concrete implementation of this function even if it makes no sense to do so.

Again, the interface type provides a solution. If you define an interface that represents the behavior of “having points,” you can simply plug it into the Hexagon type, leaving Circle and ThreeDCircle untouched.

Defining Custom Interfaces

Now that you better understand the overall role of interface types, let’s see an example of defining and implementing custom interfaces. To begin, create a brand-new Console Application named CustomInterface. Using the Project ▶ Add Existing Item menu option, insert the file(s) containing your shape type definitions (`Shapes.cs` in the book’s solution code) created back in Chapter 6 during the Shapes example. Once you have done so, rename the namespace that defines your shape-centric types to CustomInterface (simply to avoid having to import namespace definitions in your new project):

```
namespace CustomInterface
{
    // Your shape types defined here...
}
```

Now, insert a new interface into your project named IPoInty using the Project ▶ Add New Item menu option, as shown in Figure 9-1.




Figure 9-1. Interfaces, like classes, can be defined in any *.cs file

At a syntactic level, an interface is defined using the C# `interface` keyword. Unlike a class, interfaces never specify a base class (not even `System.Object`; however, as you will see later in this chapter, an interface can specify base interfaces). Moreover, the members of an interface never specify an access

modifier (as all interface members are implicitly public and abstract). To get the ball rolling, here is a custom interface defined in C#:

```
// This interface defines the behavior of "having points."
public interface IPoInty
{
    // Implicitly public and abstract.
    byte GetNumberOfPoints();
}
```

Remember that when you define interface members, you do not define an implementation scope for the member in question. Interfaces are pure protocol, and therefore never define an implementation (that is up to the supporting class or structure). Therefore, the following version of IPoInty would result in various compiler errors:

```
// Ack! Errors abound!
public interface IPoInty
{
    // Error! Interfaces cannot have fields!
    public int numbOfPoints;

    // Error! Interfaces do not have constructors!
    public IPoInty() { numbOfPoints = 0;};

    // Error! Interfaces don't provide an implementation of members!
    byte GetNumberOfPoints() { return numbOfPoints; }
}
```

In any case, this initial IPoInty interface defines a single method. However, .NET interface types are also able to define any number of property prototypes. For example, you could create the IPoInty interface to use a read-only property rather than a traditional accessor method:

```
// The pointy behavior as a read-only property.
public interface IPoInty
{
    // A read-write property in an interface would look like:
    // retType PropName { get; set; }
    // while a write-only property in an interface would be:
    // retType PropName { set; }

    byte Points { get; }
}
```

Note Interface types can also contain event (see Chapter 11) and indexer (see Chapter 12) definitions.

Interface types are quite useless on their own, as they are nothing more than a named collection of abstract members. For example, you can't allocate interface types as you would a class or structure:

```
// Ack! Illegal to allocate interface types.
static void Main(string[] args)
{
    IPoInty p = new IPoInty(); // Compiler error!
}
```

Interfaces do not bring much to the table until they are implemented by a class or structure. Here, IPoInty is an interface that expresses the behavior of “having points.” The idea is simple: some classes in the shapes hierarchy have points (such as the Hexagon), while others (such as the Circle) do not.

Implementing an Interface

When a class (or structure) chooses to extend its functionality by supporting interfaces, it does so using a comma-delimited list in the type definition. Be aware that the direct base class must be the first item listed after the colon operator. When your class type derives directly from System.Object, you are free to simply list the interface(s) supported by the class, as the C# compiler will extend your types from System.Object if you do not say otherwise. On a related note, given that structures always derive from System.ValueType (see Chapter 4 for full details), simply list each interface directly after the structure definition. Ponder the following examples:

```
// This class derives from System.Object and
// implements a single interface.
public class Pencil : IPoInty
{...}

// This class also derives from System.Object
// and implements a single interface.
public class SwitchBlade : object, IPoInty
{...}

// This class derives from a custom base class
// and implements a single interface.
public class Fork : Utensil, IPoInty
{...}

// This struct implicitly derives from System.ValueType and
// implements two interfaces.
public struct Arrow : ICloneable, IPoInty
{...}
```

Understand that implementing an interface is an all-or-nothing proposition. The supporting type is not able to selectively choose which members it will implement. Given that the IPoInty interface defines a single read-only property, this is not too much of a burden. However, if you are implementing an interface that defines ten members (such as the IDbConnection interface shown earlier), the type is now responsible for fleshing out the details of all ten abstract entities.

For this example, insert a new class type named Triangle that is-a Shape and supports IPoInty. Note that the implementation of the read-only Points property simply returns the correct number of points (3).

```
// New Shape derived class named Triangle.
class Triangle : Shape, IPoInty
```

```
{
    public Triangle() { }
    public Triangle(string name) : base(name) { }
    public override void Draw()
    { Console.WriteLine("Drawing {0} the Triangle", PetName); }

    // IPoInty Implementation.
    public byte Points
    {
        get { return 3; }
    }
}
```

Now, update your existing Hexagon type to also support the IPoInty interface type:

```
// Hexagon now implements IPoInty.
class Hexagon : Shape, IPoInty
{
    public Hexagon(){ }
    public Hexagon(string name) : base(name){ }
    public override void Draw()
    { Console.WriteLine("Drawing {0} the Hexagon", PetName); }

    // IPoInty Implementation.
    public byte Points
    {
        get { return 6; }
    }
}
```

To sum up the story so far, the Visual Studio 2010 class diagram shown in Figure 9-2 illustrates IPoInty-compatible classes using the popular “lollipop” notation. Notice again that Circle and ThreeDCircle do not implement IPoInty, as this behavior makes no sense for these particular classes.




Figure 9-2. The shapes hierarchy, now with interfaces

■ **Note** To display or hide interface names on the class designer, right-click on the interface icon and select the Collapse or Expand option.

Invoking Interface Members at the Object Level

Now that you have some classes that support the `IPointy` interface, the next question is how you interact with the new functionality. The most straightforward way to interact with functionality supplied by a given interface is to invoke the members directly from the object level (provided the interface members are not implemented explicitly; more details later in the section “Resolving Name Clashes via Explicit Interface Implementation”). For example, consider the following `Main()` method:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Interfaces *****\n");

    // Call Points property defined by IPointy.
    Hexagon hex = new Hexagon();
    Console.WriteLine("Points: {0}", hex.Points);
    Console.ReadLine();
}
```

This approach works fine in this particular case, given that you are well aware that the `Hexagon` type has implemented the interface in question and therefore has a `Points` property. Other times, however, you may not be able to determine which interfaces are supported by a given type. For example, suppose you have an array containing 50 `Shape`-compatible types, only some of which support `IPointy`.

Obviously, if you attempt to invoke the `Points` property on a type that has not implemented `IPointy`, you receive an error. So how can you dynamically determine if a class or structure supports the correct interface?

One way to determine at runtime whether a type supports a specific interface is to make use of an explicit cast. If the type does not support the requested interface, you receive an `InvalidCastException`. To handle this possibility gracefully, use structured exception handling as in the following example:

```
static void Main(string[] args)
{
    ...
    // Catch a possible InvalidCastException.
    Circle c = new Circle("Lisa");
    IPointy itfPt = null;
    try
    {
        itfPt = (IPointy)c;
        Console.WriteLine(itfPt.Points);
    }
    catch (InvalidCastException e)
    {
        Console.WriteLine(e.Message);
    }
}
```

```
    Console.ReadLine();
}
```

While you could use try/catch logic and hope for the best, it would be ideal to determine which interfaces are supported before invoking the interface members in the first place. Let's see two ways of doing so.

Obtaining Interface References: The as Keyword

You can determine whether a given type supports an interface by using the `as` keyword, introduced in Chapter 6. If the object can be treated as the specified interface, you are returned a reference to the interface in question. If not, you receive a `null` reference. Therefore, be sure to check against a `null` value before proceeding:

```
static void Main(string[] args)
{
...
// Can we treat hex2 as IPoInty?
Hexagon hex2 = new Hexagon("Peter");
IPoInty itfPt2 = hex2 as IPoInty;

if(itfPt2 != null)
    Console.WriteLine("Points: {0}", itfPt2.Points);
else
    Console.WriteLine("OOPS! Not poInty...");
```

`Console.ReadLine();`
`}`

Notice that when you use the `as` keyword, you have no need to use try/catch logic, given that if the reference is not `null`, you know you are calling on a valid interface reference.

Obtaining Interface References: The is Keyword

You may also check for an implemented interface using the `is` keyword (also first discussed in Chapter 6). If the object in question is not compatible with the specified interface, you are returned the value `false`. On the other hand, if the type is compatible with the interface in question, you can safely call the members without needing to use try/catch logic.

To illustrate, assume we have an array of `Shape` types containing some members that implement `IPoInty`. Notice how we are able to determine which item in the array supports this interface using the `is` keyword, as shown in this retrofitted `Main()` method:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Interfaces *****\n");

    // Make an array of Shapes.
    Shape[] myShapes = { new Hexagon(), new Circle(),
                        new Triangle("Joe"), new Circle("JoJo") } ;
```

```

for(int i = 0; i < myShapes.Length; i++)
{
    // Recall the Shape base class defines an abstract Draw()
    // member, so all shapes know how to draw themselves.
    myShapes[i].Draw();

    // Who's pointy?
    if(myShapes[i] is IPoInty)
        Console.WriteLine("-> Points: {0}", ((IPoInty) myShapes[i]).Points);
    else
        Console.WriteLine("-> {0}'s not pointy!", myShapes[i].PetName);
    Console.WriteLine();
}
Console.ReadLine();
}

```

The output is as follows:

***** Fun with Interfaces *****

Drawing NoName the Hexagon
-> Points: 6

Drawing NoName the Circle
-> NoName's not pointy!

Drawing Joe the Triangle
-> Points: 3

Drawing JoJo the Circle
-> JoJo's not pointy!

Interfaces As Parameters

Given that interfaces are valid .NET types, you may construct methods that take interfaces as parameters, as illustrated by the `CloneMe()` method earlier in this chapter. For the current example, assume you have defined another interface named `IDraw3D`:

```

// Models the ability to render a type in stunning 3D.
public interface IDraw3D
{
    void Draw3D();
}

```

Next, assume that two of your three shapes (`ThreeDCircle` and `Hexagon`) have been configured to support this new behavior:

```

// Circle supports IDraw3D.
class ThreeDCircle : Circle, IDraw3D
{

```

```

...
    public void Draw3D()
    { Console.WriteLine("Drawing Circle in 3D!"); }
}

// Hexagon supports IPointy and IDraw3D.
class Hexagon : Shape, IPointy, IDraw3D
{
    ...
    public void Draw3D()
    { Console.WriteLine("Drawing Hexagon in 3D!"); }
}

```

Figure 9-3 presents the updated Visual Studio 2010 class diagram.




Figure 9-3. The updated shapes hierarchy

If you now define a method taking an `IDraw3D` interface as a parameter, you can effectively send in any object implementing `IDraw3D`. (If you attempt to pass in a type not supporting the necessary interface, you receive a compile-time error.) Consider the following method defined within your `Program` class:

```

// I'll draw anyone supporting IDraw3D.
static void DrawIn3D(IDraw3D itf3d)
{
    Console.WriteLine("-> Drawing IDraw3D compatible type");
    itf3d.Draw3D();
}

```

We could now test whether an item in the `Shape` array supports this new interface, and if so, pass it into the `DrawIn3D()` method for processing:

```

static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Interfaces *****\n");
    Shape[] myShapes = { new Hexagon(), new Circle(),
                        new Triangle(), new Circle("JoJo") } ;
}

```

```

for(int i = 0; i < myShapes.Length; i++)
{
    ...
    // Can I draw you in 3D?
    if(myShapes[i] is IDraw3D)
        DrawIn3D((IDraw3D)myShapes[i]);
}

```

Here is the output of the updated application. Notice that only the Hexagon object prints out in 3D, as the other members of the Shape array do not implement the IDraw3D interface.

***** Fun with Interfaces *****

```

Drawing NoName the Hexagon
-> Points: 6
-> Drawing IDraw3D compatible type
Drawing Hexagon in 3D!

```

```

Drawing NoName the Circle
-> NoName's not pointy!

```

```

Drawing Joe the Triangle
-> Points: 3

```

```

Drawing JoJo the Circle
-> JoJo's not pointy!

```

Interfaces As Return Values

Interfaces can also be used as method return values. For example, you could write a method that takes an array of Shape objects and returns a reference to the first item that supports IPoInty:

```

// This method returns the first object in the
// array that implements IPoInty.
static IPoInty FindFirstPoIntyShape(Shape[] shapes)
{
    foreach (Shape s in shapes)
    {
        if (s is IPoInty)
            return s as IPoInty;
    }
    return null;
}

```

You could interact with this method as follows:

```

static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Interfaces *****\n");
}

```

```

// Make an array of Shapes.
Shape[] myShapes = { new Hexagon(), new Circle(),
                     new Triangle("Joe"), new Circle("JoJo")};

// Get first pointy item.
// To be safe, you'd want to check firstPointyItem for null before proceeding.
IPointy firstPointyItem = FindFirstPointyShape(myShapes);
Console.WriteLine("The item has {0} points", firstPointyItem.Points);

...
}

```

Arrays of Interface Types

Recall that the same interface can be implemented by numerous types, even if they are not within the same class hierarchy and do not have a common parent class beyond `System.Object`. This can yield some very powerful programming constructs. For example, assume you have developed three new class types within your current project that model kitchen utensils (via `Knife` and `Fork` classes) and another modeling gardening equipment (à la `PitchFork`). Consider Figure 9-4.




Figure 9-4. Recall that interfaces can be “plugged into” any type in any part of a class hierarchy

If you defined the `PitchFork`, `Fork`, and `Knife` types, you could now define an array of `IPointy`-compatible objects. Given that these members all support the same interface, you can iterate through the array and treat each item as an `IPointy`-compatible object, regardless of the overall diversity of the class hierarchies:

```

static void Main(string[] args)
{

```

```

...
// This array can only contain types that
// implement the IPoInty interface.
IPoInty[] myPoIntyObjects = {new Hexagon(), new Knife(),
    new Triangle(), new Fork(), new PitchFork()};

foreach(IPoInty i in myPoIntyObjects)
    Console.WriteLine("Object has {0} points.", i.Points);
Console.ReadLine();
}

```

Source Code The CustomInterface project is located under the Chapter 9 subdirectory.

Implementing Interfaces Using Visual Studio 2010

Although interface-based programming is a very powerful technique, implementing interfaces may entail a healthy amount of typing. Given that interfaces are a named set of abstract members, you are required to type in the definition and implementation for *each* interface method on *each* type that supports the behavior.

As you would hope, Visual Studio 2010 supports various tools that make the task of implementing interfaces less burdensome. By way of a simple test, insert a final class into your current project named PointyTestClass. When you implement IPoInty (or any interface for that matter), you might have noticed that when you complete typing the interface's name (or when you position the mouse cursor on the interface name in the code window), the first letter is underlined (formally termed a *smart tag*). When you click the smart tag, you will be presented with a drop-down list that allows you to implement the interface (see Figure 9-5).




Figure 9-5. Implementing interfaces using Visual Studio 2010

Notice you are presented with two options, the second of which (explicit interface implementation) will be examined in the next section. For the time being, select the first option and you'll see that Visual Studio 2010 has generated stub code (within a named code region) for you to update (note that the default implementation throws a `System.NotImplementedException`, which can obviously be deleted).

```
namespace CustomInterface
{
    class PointyTestClass : IPoInty
    {
        #region IPoInty Members
        public byte Points
        {
            get { throw new NotImplementedException(); }
        }
        #endregion
    }
}
```

Note Visual Studio 2010 also supports extract interface refactoring, available from the Refactor menu. This allows you to pull out a new interface definition from an existing class definition.

Resolving Name Clashes via Explicit Interface Implementation

As shown earlier in this chapter, a single class or structure can implement any number of interfaces. Given this, there is always the possibility you may implement interfaces that contain identical members, and therefore have a name clash to contend with. To illustrate various manners in which you can resolve this issue, create a new Console Application named `InterfaceNameClash`. Now design three interfaces that represent various locations to which an implementing type could render its output:

```
// Draw image to a Form.
public interface IDrawToForm
{
    void Draw();
}

// Draw to buffer in memory.
public interface IDrawToMemory
{
    void Draw();
}

// Render to the printer.
public interface IDrawToPrinter
{
    void Draw();
```

```
}
```

Notice that each interface defines a method named `Draw()`, with the identical signature (which happen to be no arguments). If you now wish to support each of these interfaces on a single class type named `Octagon`, the compiler would allow the following definition:

```
class Octagon : IDrawToForm, IDrawToMemory, IDrawToPrinter
{
    public void Draw()
    {
        // Shared drawing logic.
        Console.WriteLine("Drawing the Octagon...");
    }
}
```

Although the code compiles cleanly, we do have a possible problem. Simply put, providing a single implementation of the `Draw()` method does not allow us to take unique courses of action based on which interface is obtained from an `Octagon` object. For example, the following code will invoke the same `Draw()` method, regardless of which interface you obtain:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Interface Name Clashes *****\n");
    // All of these invocations call the
    // same Draw() method!
    Octagon oct = new Octagon();
    oct.Draw();

    IDrawToForm itfForm = (IDrawToForm)oct;
    itfForm.Draw();

    IDrawToPrinter itfPriner = (IDrawToPrinter)oct;
    itfPriner.Draw();

    IDrawToMemory itfMemory = (IDrawToMemory)oct;
    itfMemory.Draw();

    Console.ReadLine();
}
```

Clearly, the sort of code required to render the image to a window is quite different from the code needed to render the image to a networked printer or a region of memory. When you implement several interfaces that have identical members, you can resolve this sort of name clash using *explicit interface implementation* syntax. Consider the following update to the `Octagon` type:

```
class Octagon : IDrawToForm, IDrawToMemory, IDrawToPrinter
{
    // Explicitly bind Draw() implementations
    // to a given interface.
    void IDrawToForm.Draw()
    {
        Console.WriteLine("Drawing to form...");
    }
}
```

```

void IDrawToMemory.Draw()
{
    Console.WriteLine("Drawing to memory...");
}
void IDrawToPrinter.Draw()
{
    Console.WriteLine("Drawing to a printer...");
}
}

```

As you can see, when explicitly implementing an interface member, the general pattern breaks down to

```
returnType InterfaceName.MethodName(params)
```

Note that when using this syntax, you do not supply an access modifier; explicitly implemented members are automatically private. For example, the following is illegal syntax:

```
// Error! No access modifier!
public void IDrawToForm.Draw()
{
    Console.WriteLine("Drawing to form...");
}
```

Because explicitly implemented members are always implicitly private, these members are no longer available from the object level. In fact, if you were to apply the dot operator to an Octagon type, you would find that IntelliSense does not show you any of the Draw() members (see Figure 9-6).




Figure 9-6. Explicitly implemented interface members are not exposed from the object level

As expected, you must make use of explicit casting to access the required functionality. For example:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Interface Name Clashes *****\n");
}
```

```

Octagon oct = new Octagon();

// We now must use casting to access the Draw()
// members.
IDrawToForm itfform = (IDrawToForm)oct;
itfform.Draw();

// Shorthand notation if you don't need
// the interface variable for later use.
((IDrawToPrinter)oct).Draw();

// Could also use the "as" keyword.
if(oct is IDrawToMemory)
    ((IDrawToMemory)oct).Draw();

Console.ReadLine();
}

```

While this syntax is quite helpful when you need to resolve name clashes, you can use explicit interface implementation simply to hide more “advanced” members from the object level. In this way, when the object user applies the dot operator, he or she will see only a subset of the type’s overall functionality. However, those who require the more advanced behaviors can extract out the desired interface via an explicit cast.

Source Code The InterfaceNameClash project is located under the Chapter 9 subdirectory.

Designing Interface Hierarchies

Interfaces can be arranged in an interface hierarchy. Like a class hierarchy, when an interface extends an existing interface, it inherits the abstract members defined by the parent(s). Of course, unlike class-based inheritance, derived interfaces never inherit true implementation. Rather, a derived interface simply extends its own definition with additional abstract members.

Interface hierarchies can be useful when you wish to extend the functionality of an existing interface without breaking existing code bases. To illustrate, create a new Console Application named InterfaceHierarchy. Now, let’s design a new set of rendering-centric interfaces such that **IDrawable** is the root of the family tree:

```

public interface IDrawable
{
    void Draw();
}

```

Given that **IDrawable** defines a basic drawing behavior, we could now create a derived interface that extends this interface with the ability to render in modified formats, for example:

```

public interface IAdvancedDraw : IDrawable
{
    void DrawInBoundingBox(int top, int left, int bottom, int right);
}

```

```
    void DrawUpsideDown();
}
```

Given this design, if a class were to implement `IAdvancedDraw`, it would now be required to implement each and every member defined up the chain of inheritance (specifically, the `Draw()`, `DrawInBoundingBox()`, and `DrawUpsideDown()` methods):

```
public class BitmapImage : IAdvancedDraw
{
    public void Draw()
    {
        Console.WriteLine("Drawing...");
    }

    public void DrawInBoundingBox(int top, int left, int bottom, int right)
    {
        Console.WriteLine("Drawing in a box...");
    }

    public void DrawUpsideDown()
    {
        Console.WriteLine("Drawing upside down!");
    }
}
```

Now, when we make use of the `BitmapImage`, we are able to invoke each method at the object level (as they are all public), as well as extract out a reference to each supported interface explicitly via casting:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Simple Interface Hierarchy *****");

    // Call from object level.
    BitmapImage myBitmap = new BitmapImage();
    myBitmap.Draw();
    myBitmap.DrawInBoundingBox(10, 10, 100, 150);
    myBitmap.DrawUpsideDown();

    // Get IAdvancedDraw explicitly.
    IAdvancedDraw iAdvDraw;
    iAdvDraw = (IAdvancedDraw)myBitmap;
    iAdvDraw.DrawUpsideDown();

    Console.ReadLine();
}
```

Source Code The `InterfaceHierarchy` project is located under the Chapter 9 subdirectory.

Multiple Inheritance with Interface Types

Unlike class types, a single interface can extend multiple base interfaces, allowing us to design some very powerful and flexible abstractions. Create a new Console Application project named `MInterfaceHierarchy`. Here is another collection of interfaces that model various rendering and shape abstractions. Notice that the `IShape` interface is extending both `IDrawable` and `IPrintable`:

```
// Multiple inheritance for interface types is a-okay.
interface IDrawable
{
    void Draw();
}

interface IPrintable
{
    void Print();
    void Draw(); // <-- Note possible name clash here!
}

// Multiple interface inheritance. OK!
interface IShape : IDrawable, IPrintable
{
    int GetNumberOfSides();
}
```

Figure 9-7 illustrates the current interface hierarchy.



Figure 9-7. Unlike classes, interfaces can extend multiple interface types

Now, the million dollar question is, if you have a class supporting `IShape`, how many methods will it be required to implement? The answer: it depends. If you want to provide a simple implementation of the `Draw()` method, you need only provide three members, as shown in the following `Rectangle` type:

```
class Rectangle : IShape
{
    public int GetNumberOfSides()
    { return 4; }

    public void Draw()
    { Console.WriteLine("Drawing..."); }
```

```
public void Print()
{ Console.WriteLine("Prining..."); }
}
```

If you'd rather have specific implementations for each `Draw()` method (which in this case would make the most sense), you can resolve the name clash using explicit interface implementation, as shown in the following `Square` type:

```
class Square : IShape
{
    // Using explicit implementation to handle member name clash.
    void IPrintable.Draw()
    {
        // Draw to printer ...
    }
    void IDrawable.Draw()
    {
        // Draw to screen ...
    }
    public void Print()
    {
        // Print ...
    }
    public int GetNumberOfSides()
    { return 4; }
}
```

Hopefully, at this point you feel more comfortable with the process of defining and implementing custom interfaces using the C# syntax. To be honest, interface-based programming can take awhile to get comfortable with, so if you are in fact still scratching your head just a bit, this is a perfectly normal reaction.

Do be aware, however, that interfaces are a fundamental aspect of the .NET Framework. Regardless of the type of application you are developing (web-based, desktop GUIs, data-access libraries, etc.), working with interfaces will be part of the process. To summarize the story thus far, remember that interfaces can be extremely useful when

- You have a single hierarchy where only a subset of the derived types supports a common behavior.
- You need to model a common behavior that is found across multiple hierarchies with no common parent class beyond `System.Object`.

Now that you have drilled into the specifics of building and implementing custom interfaces, the remainder of the chapter examines a number of predefined interfaces contained within the .NET base class libraries.

■ **Source Code** The `MInterfaceHierarchy` project is located under the Chapter 9 subdirectory.

Building Enumerable Types (IEnumerable and IEnumerator)

To begin examining the process of implementing existing .NET interfaces, let's first look at the role of `IEnumerable` and `IEnumerator`. Recall that C# supports a keyword named `foreach` that allows you to iterate over the contents of any array type:

```
// Iterate over an array of items.
int[] myArrayOfInts = {10, 20, 30, 40};

foreach(int i in myArrayOfInts)
{
    Console.WriteLine(i);
}
```

While it may seem that only array types can make use of this construct, the truth of the matter is any type supporting a method named `GetEnumerator()` can be evaluated by the `foreach` construct. To illustrate, begin by creating a new Console Application project named `CustomEnumerator`. Next, add the `Car.cs` and `Radio.cs` files defined in the `SimpleException` example of Chapter 7 (via the `Project ▶ Add Existing Item` menu option).

Note You may wish to rename the namespace containing the `Car` and `Radio` types to `CustomEnumerator`, to avoid having to import the `CustomException` namespace within this new project.

Now, insert a new class named `Garage` that stores a set of `Car` objects within a `System.Array`:

```
// Garage contains a set of Car objects.
public class Garage
{
    private Car[] carArray = new Car[4];

    // Fill with some Car objects upon startup.
    public Garage()
    {
        carArray[0] = new Car("Rusty", 30);
        carArray[1] = new Car("Clunker", 55);
        carArray[2] = new Car("Zippy", 30);
        carArray[3] = new Car("Fred", 30);
    }
}
```

Ideally, it would be convenient to iterate over the `Garage` object's subitems using the `foreach` construct, just like an array of data values:

```
// This seems reasonable...
public class Program
{
    static void Main(string[] args)
```

```

{
    Console.WriteLine("***** Fun with IEnumerable / IEnumerator *****\n");
    Garage carLot = new Garage();

    // Hand over each car in the collection?
    foreach (Car c in carLot)
    {
        Console.WriteLine("{0} is going {1} MPH",
            c.PetName, c.CurrentSpeed);
    }
    Console.ReadLine();
}
}

```

Sadly, the compiler informs you that the `Garage` class does not implement a method named `GetEnumerator()`. This method is formalized by the `IEnumerable` interface, which is found lurking within the `System.Collections` namespace.

Note In the next chapter you will learn about the role of generics and the `System.Collections.Generic` namespace. As you will see, this namespace contain generic versions of `IEnumerable/IEnumerator` that provide a more type-safe way to iterate over subobjects.

Classes or structures that support this behavior advertise that they are able to expose contained subitems to the caller (in this example, the `foreach` keyword itself):

```

// This interface informs the caller
// that the object's subitems can be enumerated.
public interface IEnumerable
{
    IEnumerator GetEnumerator();
}

```

As you can see, the `GetEnumerator()` method returns a reference to yet another interface named `System.Collections.IEnumerator`. This interface provides the infrastructure to allow the caller to traverse the internal objects contained by the `IEnumerable`-compatible container:

```

// This interface allows the caller to
// obtain a container's subitems.
public interface IEnumerator
{
    bool MoveNext ();           // Advance the internal position of the cursor.
    object Current { get; }     // Get the current item (read-only property).
    void Reset ();              // Reset the cursor before the first member.
}

```

If you wish to update the `Garage` type to support these interfaces, you could take the long road and implement each method manually. While you are certainly free to provide customized versions of `GetEnumerator()`, `MoveNext()`, `Current`, and `Reset()`, there is a simpler way. As the `System.Array` type (as

well as many other collection classes) already implements `IEnumerable` and `IEnumerator`, you can simply delegate the request to the `System.Array` as follows:

```
using System.Collections;
...
public class Garage : IEnumerable
{
    // System.Array already implements Ienumerator!
    private Car[] carArray = new Car[4];

    public Garage()
    {
        carArray[0] = new Car("FeeFee", 200, 0);
        carArray[1] = new Car("Clunker", 90, 0);
        carArray[2] = new Car("Zippy", 30, 0);
        carArray[3] = new Car("Fred", 30, 0);
    }

    public IEnumerator GetEnumerator()
    {
        // Return the array object's Ienumerator.
        return carArray.GetEnumerator();
    }
}
```

Once you have updated your `Garage` type, you can now safely use the type within the C# `foreach` construct. Furthermore, given that the `GetEnumerator()` method has been defined publicly, the object user could also interact with the `IEnumerator` type:

```
// Manually work with Ienumerator.
IEnumerator i = carLot.GetEnumerator();
i.MoveNext();
Car myCar = (Car)i.Current;
Console.WriteLine("{0} is going {1} MPH", myCar.PetName, myCar.CurrentSpeed);
```

However, if you prefer to hide the functionality of `IEnumerable` from the object level, simply make use of explicit interface implementation:

```
IEnumerator IEnumerable.GetEnumerator()
{
    // Return the array object's Ienumerator.
    return carArray.GetEnumerator();
}
```

By doing so, the casual object user will not find the `Garage`'s `GetEnumerator()` method, while the `foreach` construct will obtain the interface in the background when necessary.

■ Source Code The `CustomEnumerator` project is located under the Chapter 9 subdirectory.

Building Iterator Methods with the `yield` Keyword

Historically, when you wanted to build a custom collection (such as `Garage`) that supported `foreach` enumeration, implementing the `IEnumerable` interface (and possibly the `IEnumerator` interface) was your only option. However, there's an alternative way to build types that work with the `foreach` loop via *iterators*.

Simply put, an iterator is a member that specifies how a container's internal items should be returned when processed by `foreach`. While the iterator method must still be named `GetEnumerator()`, and the return value must still be of type `IEnumerator`, your custom class does not need to implement any of the expected interfaces.

To illustrate, create a new Console Application project named `CustomEnumeratorWithYield` and insert the `Car`, `Radio`, and `Garage` types from the previous example (again, renaming your namespace definitions to the current project if you like). Now, retrofit the current `Garage` type as follows:

```
public class Garage
{
    private Car[] carArray = new Car[4];
    ...
    // Iterator method.
    public I IEnumerator GetEnumerator()
    {
        foreach (Car c in carArray)
        {
            yield return c;
        }
    }
}
```

Notice that this implementation of `GetEnumerator()` iterates over the subitems using internal `foreach` logic and returns each `Car` to the caller using the `yield return` syntax. The `yield` keyword is used to specify the value (or values) to be returned to the caller's `foreach` construct. When the `yield return` statement is reached, the current location in the container is stored, and execution is restarted from this location the next time the iterator is called (you'll see the details behind this "magic" in just a moment).

Iterator methods are not required to make use of the `foreach` keyword to return its contents. It is also permissible to define this iterator method as follows:

```
public I Enumerator GetEnumerator()
{
    yield return carArray[0];
    yield return carArray[1];
    yield return carArray[2];
    yield return carArray[3];
}
```

In this implementation, notice that the `GetEnumerator()` method is explicitly returning a new value to the caller with each pass through. Doing so for this example makes little sense, given that if we were to add more objects to the `carArray` member variable, our `GetEnumerator()` method would now be out of sync. Nevertheless, this syntax can be useful when you wish to return local data from a method for processing by the `foreach` syntax.

Building a Named Iterator

It is also interesting to note that the `yield` keyword can technically be used within any method, regardless of its name. These methods (which are technically called *named iterators*) are also unique in that they can take any number of arguments. When building a named iterator, be very aware that the method will return the `IEnumerable` interface, rather than the expected `IEnumerator`-compatible type. To illustrate, you could add the following method to the `Garage` type:

```
public IEnumerable GetTheCars(bool ReturnReversed)
{
    // Return the items in reverse.
    if (ReturnReversed)
    {
        for (int i = carArray.Length; i != 0; i--)
        {
            yield return carArray[i-1];
        }
    }
    else
    {
        // Return the items as placed in the array.
        foreach (Car c in carArray)
        {
            yield return c;
        }
    }
}
```

Notice that the new method allows the caller to obtain the subitems in sequential order, as well as in reverse order, if the incoming parameter has the value `true`. You could now interact with our new method as follows:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with the Yield Keyword *****\n");
    Garage carLot = new Garage();

    // Get items using GetEnumerator().
    foreach (Car c in carLot)
    {
        Console.WriteLine("{0} is going {1} MPH",
            c.PetName, c.CurrentSpeed);
    }

    Console.WriteLine();

    // Get items (in reverse!) using named iterator.
    foreach (Car c in carLot.GetTheCars(true))
    {
        Console.WriteLine("{0} is going {1} MPH",
            c.PetName, c.CurrentSpeed);
    }
}
```

```
    Console.ReadLine();
}
```

As you may agree, named iterators are helpful constructs, in that a single custom container can define multiple ways to request the returned set.

Internal Representation of an Iterator Method

When the C# compiler encounters an iterator method, it dynamically generates a nested class definition within the scope of the defining type (`Garage` in this case). The autogenerated nested class implements the `GetEnumerator()`, `MoveNext()`, and `Current` members on your behalf (oddly, the `Reset()` method is not implemented, and you will receive a runtime exception if you attempt to call it). If you load the current application into `ildasm.exe`, you'll find two nested types, each of which accounts for the logic required by a specific iterator method. Notice in Figure 9-8 that these compiler-generated types have been named `<GetEnumerator>d_0` and `<GetTheCars>d_6`.




Figure 9-8. Iterator methods are internally implemented with the help of an autogenerated nested class

If you use `ildasm.exe` to view the implementation of the `GetEnumerator()` method of the `Garage` type, you'd find that it has been implemented to make use of the `<GetEnumerator>d_0` type behind the scenes (the nested `<GetTheCars>d_6` type is used by the `GetTheCars()` method in a similar manner).

```
.method public hidebysig instance class
[mscorlib]System.Collections.IEnumerator
GetEnumerator() cil managed
{
...
newobj instance void
CustomEnumeratorWithYield.Garage/'<GetEnumerator>d_0':::ctor(int32)
...
```

```
 } // end of method Garage::GetEnumerator
```

So, to wrap up our look at building enumerable objects, remember that for your custom types to work with the C# `foreach` keyword, the container must define a method named `GetEnumerator()`, which has been formalized by the `IEnumerable` interface type. The implementation of this method is typically achieved by simply delegating it to the internal member that is holding onto the subobjects; however, it is also possible to make use of the `yield return` syntax to provide multiple “named iterator” methods.

Source Code The `CustomEnumeratorWithYield` project is located under the Chapter 9 subdirectory.

Building Cloneable Objects (`ICloneable`)

As you recall from Chapter 6, `System.Object` defines a member named `MemberwiseClone()`. This method is used to obtain a *shallow copy* of the current object. Object users do not call this method directly as it is protected. However, a given object may call this method itself during the *cloning* process. To illustrate, create a new Console Application named `CloneablePoint` that defines a class named `Point`:

```
// A class named Point.
public class Point
{
    public int X {get; set;}
    public int Y {get; set;}

    public Point(int xPos, int yPos) { X = xPos; Y = yPos;}
    public Point(){}
}

// Override Object.ToString().
public override string ToString()
{   return string.Format("X = {0}; Y = {1}", X, Y ); }
```

Given what you already know about reference types and value types (Chapter 4), you are aware that if you assign one reference variable to another, you have two references pointing to the same object in memory. Thus, the following assignment operation results in two references to the same `Point` object on the heap; modifications using either reference affect the same object on the heap:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Object Cloning *****\n");
    // Two references to same object!
    Point p1 = new Point(50, 50);
    Point p2 = p1;
    p2.X = 0;
    Console.WriteLine(p1);
    Console.WriteLine(p2);
    Console.ReadLine();
}
```

When you want to give your custom type the ability to return an identical copy of itself to the caller, you may implement the standard `ICloneable` interface. As shown at the start of this chapter, this type defines a single method named `Clone()`:

```
public interface ICloneable
{
    object Clone();
}
```

Note The usefulness of the `ICloneable` interface is a topic of debate within the .NET community. The problem has to do with the fact that the official specification does not explicitly say that objects implementing this interface must return a *deep copy* of the object (i.e., internal reference types of an object result in brand-new objects with identical state). Thus, it is technically possible that objects implementing `ICloneable` actually return a *shallow copy* of the interface (i.e., internal references point to the same object on the heap), which clearly generates a good deal of confusion. In our example, I am assuming we are implementing `Clone()` to return a full, deep copy of the object.

Obviously, the implementation of the `Clone()` method varies among types. However, the basic functionality tends to be the same: copy the values of your member variables into a new object instance of the same type, and return it to the user. To illustrate, ponder the following update to the `Point` class:

```
// The Point now supports "clone-ability."
public class Point : ICloneable
{
    public int X { get; set; }
    public int Y { get; set; }

    public Point(int xPos, int yPos) { X = xPos; Y = yPos; }
    public Point() { }

    // Override Object.ToString().
    public override string ToString()
    { return string.Format("X = {0}; Y = {1}", X, Y); }

    // Return a copy of the current object.
    public object Clone()
    { return new Point(this.X, this.Y); }
}
```

In this way, you can create exact stand-alone copies of the `Point` type, as illustrated by the following code:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Object Cloning *****\n");
    // Notice Clone() returns a plain object type.
    // You must perform an explicit cast to obtain the derived type.
    Point p3 = new Point(100, 100);
```

```

Point p4 = (Point)p3.Clone();

// Change p4.X (which will not change p3.X).
p4.X = 0;

// Print each object.
Console.WriteLine(p3);
Console.WriteLine(p4);
Console.ReadLine();
}

```

While the current implementation of Point fits the bill, you can streamline things just a bit. Because the Point type does not contain any internal reference type variables, you could simplify the implementation of the Clone() method as follows:

```

public object Clone()
{
    // Copy each field of the Point member by member.
    return this.MemberwiseClone();
}

```

Be aware, however, that if the Point did contain any reference type member variables, MemberwiseClone() will copy the references to those objects (i.e., a *shallow copy*). If you wish to support a true deep copy, you will need to create a new instance of any reference type variables during the cloning process. Let's see an example.

A More Elaborate Cloning Example

Now assume the Point class contains a reference type member variable of type PointDescription. This class maintains a point's friendly name as well as an identification number expressed as a System.Guid (if you don't come from a COM background, know that a globally unique identifier [GUID] is a statistically unique 128-bit number). Here is the implementation:

```

// This class describes a point.
public class PointDescription
{
    public string PetName {get; set;}
    public Guid PointID {get; set;}

    public PointDescription()
    {
        PetName = "No-name";
        PointID = Guid.NewGuid();
    }
}

```

The initial updates to the Point class itself included modifying ToString() to account for these new bits of state data, as well as defining and creating the PointDescription reference type. To allow the outside world to establish a pet name for the Point, you also update the arguments passed into the overloaded constructor:

```

public class Point : ICloneable
{
    public int X { get; set; }
    public int Y { get; set; }
    public PointDescription desc = new PointDescription();

    public Point(int xPos, int yPos, string petName)
    {
        X = xPos; Y = yPos;
        desc.PetName = petName;
    }
    public Point(int xPos, int yPos)
    {
        X = xPos; Y = yPos;
    }
    public Point() { }

    // Override Object.ToString().
    public override string ToString()
    {
        return string.Format("X = {0}; Y = {1}; Name = {2};\nID = {3}\n",
            X, Y, desc.PetName, desc.PointID);
    }

    // Return a copy of the current object.
    public object Clone()
    {
        return this.MemberwiseClone();
    }
}

```

Notice that you did not yet update your `Clone()` method. Therefore, when the object user asks for a clone using the current implementation, a shallow (member-by-member) copy is achieved. To illustrate, assume you have updated `Main()` as follows:

```

static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Object Cloning *****\n");
    Console.WriteLine("Cloned p3 and stored new Point in p4");
    Point p3 = new Point(100, 100, "Jane");
    Point p4 = (Point)p3.Clone();

    Console.WriteLine("Before modification:");
    Console.WriteLine("p3: {0}", p3);
    Console.WriteLine("p4: {0}", p4);
    p4.desc.PetName = "My new Point";
    p4.X = 9;

    Console.WriteLine("\nChanged p4.desc.petName and p4.X");
    Console.WriteLine("After modification:");
    Console.WriteLine("p3: {0}", p3);
    Console.WriteLine("p4: {0}", p4);
    Console.ReadLine();
}

```

Notice in the following output that while the value types have indeed been changed, the internal reference types maintain the same values, as they are “pointing” to the same objects in memory (Specifically, note that the pet name for both objects is now “My new Point”).

***** Fun with Object Cloning *****

```
Cloned p3 and stored new Point in p4
Before modification:
p3: X = 100; Y = 100; Name = Jane;
ID = 133d66a7-0837-4bd7-95c6-b22ab0434509

p4: X = 100; Y = 100; Name = Jane;
ID = 133d66a7-0837-4bd7-95c6-b22ab0434509

Changed p4.desc.petName and p4.X
After modification:
p3: X = 100; Y = 100; Name = My new Point;
ID = 133d66a7-0837-4bd7-95c6-b22ab0434509

p4: X = 9; Y = 100; Name = My new Point;
ID = 133d66a7-0837-4bd7-95c6-b22ab0434509
```

To have your `Clone()` method make a complete deep copy of the internal reference types, you need to configure the object returned by `MemberwiseClone()` to account for the current point’s name (the `System.Guid` type is in fact a structure, so the numerical data is indeed copied). Here is one possible implementation:

```
// Now we need to adjust for the PointDescription member.
public object Clone()
{
    // First get a shallow copy.
    Point newPoint = (Point)this.MemberwiseClone();

    // Then fill in the gaps.
    PointDescription currentDesc = new PointDescription();
    currentDesc.PetName = this.desc.PetName;
    newPoint.desc = currentDesc;
    return newPoint;
}
```

If you rerun the application once again and view the output (see below), you see that the `Point` returned from `Clone()` does copy its internal reference type member variables (note the pet name is now unique for both `p3` and `p4`).

***** Fun with Object Cloning *****

Cloned p3 and stored new Point in p4

Before modification:

```
p3: X = 100; Y = 100; Name = Jane;  
ID = 51f64f25-4b0e-47ac-ba35-37d263496406
```

```
p4: X = 100; Y = 100; Name = Jane;  
ID = 0d3776b3-b159-490d-b022-7f3f60788e8a
```

Changed p4.desc.petName and p4.X

After modification:

```
p3: X = 100; Y = 100; Name = Jane;  
ID = 51f64f25-4b0e-47ac-ba35-37d263496406
```

```
p4: X = 9; Y = 100; Name = My new Point;  
ID = 0d3776b3-b159-490d-b022-7f3f60788e8a
```

To summarize the cloning process, if you have a class or structure that contains nothing but value types, implement your `Clone()` method using `MemberwiseClone()`. However, if you have a custom type that maintains other reference types, you need to create a new object that takes into account each reference type member variable.

■ **Source Code** The `CloneablePoint` project is located under the Chapter 9 subdirectory.

Building Comparable Objects (`IComparable`)

The `System.IComparable` interface specifies a behavior that allows an object to be sorted based on some specified key. Here is the formal definition:

```
// This interface allows an object to specify its  
// relationship between other like objects.  
public interface IComparable  
{  
    int CompareTo(object o);  
}
```

■ **Note** The generic version of this interface (`IComparable<T>`) provides a more type-safe manner to handle comparisons between objects. You'll examine generics in Chapter 10.

Let's assume you have a new Console Application named ComparableCar that defines the following updated Car class (notice that we have basically just added a new property to represent a unique ID for each car and a modified constructor):

```
public class Car
{
...
    public int CarID {get; set;}
    public Car(string name, int currSp, int id)
    {
        CurrentSpeed = currSp;
        PetName = name;
        CarID = id;
    }
...
}
```

Now assume you have an array of Car objects as follows:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Object Sorting *****\n");

    // Make an array of Car objects.
    Car[] myAutos = new Car[5];
    myAutos[0] = new Car("Rusty", 80, 1);
    myAutos[1] = new Car("Mary", 40, 234);
    myAutos[2] = new Car("Viper", 40, 34);
    myAutos[3] = new Car("Mel", 40, 4);
    myAutos[4] = new Car("Chucky", 40, 5);

    Console.ReadLine();
}
```

The System.Array class defines a static method named Sort(). When you invoke this method on an array of intrinsic types (int, short, string, etc.), you are able to sort the items in the array in numeric/alphabetic order as these intrinsic data types implement IComparable. However, what if you were to send an array of Car types into the Sort() method as follows?

```
// Sort my cars?
Array.Sort(myAutos);
```

If you run this test, you would get a runtime exception, as the Car class does not support the necessary interface. When you build custom types, you can implement IComparable to allow arrays of your types to be sorted. When you flesh out the details of CompareTo(), it will be up to you to decide what the baseline of the ordering operation will be. For the Car type, the internal CarID seems to be the logical candidate:

```
// The iteration of the Car can be ordered
// based on the CarID.
public class Car : IComparable
{
...
    // IComparable implementation.
```

```

int IComparable.CompareTo(object obj)
{
    Car temp = obj as Car;
    if (temp != null)
    {
        if (this.CarID > temp.CarID)
            return 1;
        if (this.CarID < temp.CarID)
            return -1;
        else
            return 0;
    }
    else
        throw new ArgumentException("Parameter is not a Car!");
}

```

As you can see, the logic behind `CompareTo()` is to test the incoming object against the current instance based on a specific point of data. The return value of `CompareTo()` is used to discover whether this type is less than, greater than, or equal to the object it is being compared with (see Table 9-1).

Table 9-1. *CompareTo() Return Values*

CompareTo() Return Value	Description
Any number less than zero	This instance comes before the specified object in the sort order.
Zero	This instance is equal to the specified object.
Any number greater than zero	This instance comes after the specified object in the sort order.

We can streamline the previous implementation of `CompareTo()` given the fact that the C# `int` data type (which is just a shorthand notation for the CLR `System.Int32`) implements `IComparable`. You could implement the `Car`'s `CompareTo()` as follows:

```

int IComparable.CompareTo(object obj)
{
    Car temp = obj as Car;
    if (temp != null)
        return this.CarID.CompareTo(temp.CarID);
    else
        throw new ArgumentException("Parameter is not a Car!");
}

```

In either case, so that your `Car` type understands how to compare itself to like objects, you can write the following user code:

```

// Exercise the IComparable interface.
static void Main(string[] args)
{

```

```

// Make an array of Car objects.
...
// Display current array.
Console.WriteLine("Here is the unordered set of cars:");
foreach(Car c in myAutos)
    Console.WriteLine("{0} {1}", c.CarID, c.PetName);

// Now, sort them using IComparable!
Array.Sort(myAutos);
Console.WriteLine();

// Display sorted array.
Console.WriteLine("Here is the ordered set of cars:");
foreach(Car c in myAutos)
    Console.WriteLine("{0} {1}", c.CarID, c.PetName);
Console.ReadLine();
}

```

Here is the output from the previous Main() method:

***** Fun with Object Sorting *****

Here is the unordered set of cars:

1 Rusty
234 Mary
34 Viper
4 Mel
5 Chucky

Here is the ordered set of cars:

1 Rusty
4 Mel
5 Chucky
34 Viper
234 Mary

Specifying Multiple Sort Orders (IComparer)

In this version of the Car type, you used the car's ID as the base of the sort order. Another design might have used the pet name of the car as the basis of the sorting algorithm (to list cars alphabetically). Now, what if you wanted to build a Car that could be sorted by ID *as well as* by pet name? If this is the type of behavior you are interested in, you need to make friends with another standard interface named IComparer, defined within the System.Collections namespace as follows:

```

// A general way to compare two objects.
interface IComparer
{
    int Compare(object o1, object o2);
}

```

■ Note The generic version of this interface (`IComparer<T>`) provides a more type-safe manner to handle comparisons between objects. You'll examine generics in Chapter 10.

Unlike the `IComparable` interface, `IComparer` is typically *not* implemented on the type you are trying to sort (i.e., the `Car`). Rather, you implement this interface on any number of helper classes, one for each sort order (pet name, car ID, etc.). Currently, the `Car` type already knows how to compare itself against other cars based on the internal car ID. Therefore, allowing the object user to sort an array of `Car` object by pet name will require an additional helper class that implements `IComparer`. Here's the code (be sure to import the `System.Collections` namespace in the code file):

```
// This helper class is used to sort an array of Cars by pet name.
public class PetNameComparer : IComparer
{
    // Test the pet name of each object.
    int IComparer.Compare(object o1, object o2)
    {
        Car t1 = o1 as Car;
        Car t2 = o2 as Car;
        if(t1 != null && t2 != null)
            return String.Compare(t1.PetName, t2.PetName);
        else
            throw new ArgumentException("Parameter is not a Car!");
    }
}
```

The object user code is able to make use of this helper class. `System.Array` has a number of overloaded `Sort()` methods, one that just happens to take an object implementing `IComparer`.

```
static void Main(string[] args)
{
    ...
    // Now sort by pet name.
    Array.Sort(myAutos, new PetNameComparer());

    // Dump sorted array.
    Console.WriteLine("Ordering by pet name:");
    foreach(Car c in myAutos)
        Console.WriteLine("{0} {1}", c.CarID, c.PetName);
    ...
}
```

Custom Properties, Custom Sort Types

It is worth pointing out that you can make use of a custom static property in order to help the object user along when sorting your `Car` types by a specific data point. Assume the `Car` class has added a static read-only property named `SortByPetName` that returns an instance of an object implementing the `IComparer` interface (`PetNameComparer`, in this case):

```
// We now support a custom property to return
// the correct IComparer interface.
public class Car : IComparable
{
    ...
    // Property to return the SortByPetName comparer.
    public static IComparer SortByPetName
    { get { return (IComparer)new PetNameComparer(); } }
}
```

The object user code can now sort by pet name using a strongly associated property, rather than just “having to know” to use the stand-alone `PetNameComparer` class type:

```
// Sorting by pet name made a bit cleaner.
Array.Sort(myAutos, Car.SortByPetName);
```

■ **Source Code** The `ComparableCar` project is located under the Chapter 9 subdirectory.

Hopefully, at this point you not only understand how to define and implement your own interfaces, but also understand their usefulness. To be sure, interfaces are found within every major .NET namespace, and you will continue working with various standard interfaces over the remainder of this text.

Summary

An interface can be defined as a named collection of *abstract members*. Because an interface does not provide any implementation details, it is common to regard an interface as a behavior that may be supported by a given type. When two or more classes implement the same interface, you can treat each type the same way (interface-based polymorphism) even if the types are defined within unique class hierarchies.

C# provides the `interface` keyword to allow you to define a new interface. As you have seen, a type can support as many interfaces as necessary using a comma-delimited list. Furthermore, it is permissible to build interfaces that derive from multiple base interfaces.

In addition to building your custom interfaces, the .NET libraries define a number of standard (i.e., framework-supplied) interfaces. As you have seen, you are free to build custom types that implement these predefined interfaces to gain a number of desirable traits such as cloning, sorting, and enumerating.



Understanding Generics

The most primitive container for application data within the .NET platform is the `System.Array` class. As you saw in Chapter 4, C# arrays allow you to define a set of identically typed items (including an array of `System.Objects`, which essentially represents an array of any type of data) of a fixed upper limit. While basic arrays can be useful to manage small amounts of known data, there are many other times where you require a more flexible data structure, such as a dynamically growing and shrinking container, or a container that can only hold objects that meet a specific criteria (e.g., only objects deriving from a specific base class or only objects implementing a particular interface).

When the .NET platform was first released, programmers frequently used the `System.Collections` namespace to account for more flexible ways to manage bits of data in an application. However, in .NET 2.0 the C# programming language was enhanced to support a feature termed *generics*; and with this change, a brand new collection-centric namespace was introduced in the base class libraries: `System.Collections.Generic`.

As you will learn in this chapter, generic containers are far superior in many ways to their non-generic counterparts because they provide greater type safety and performance benefits. Once you've seen the motivation for generics, you will learn about the commonly used classes and interfaces within `System.Collections.Generic`. The remainder of this chapter examines how to build your own generic types. As you do this, you will learn about the role of *constraints*, which allow you to build extremely type safe containers.

■ **Note** It is also possible to create generic delegate types, which you will learn about in the next chapter.

The Issues with Non-Generic Collections

When the .NET platform was first released, programmers frequently used the `System.Collections` namespace of `mscorlib.dll`. Here, developers were provided with a set of classes that allowed them to manage and organize large amounts of data. Table 10-1 documents some of the more commonly used collection classes, and the core interfaces they implement.

Table 10-1. Commonly used Classes of System.Collections

System.Collections Class	Meaning in Life	Key Implemented Interfaces
ArrayList	Represents a dynamically sized collection of objects listed in sequential order.	IList, ICollection, IEnumerable, and ICloneable
Hashtable	Represents a collection of key/value pairs that are organized based on the hash code of the key.	IDictionary, ICollection, IEnumerable, and ICloneable
Queue	Represents a standard first-in, first-out (FIFO) queue.	ICollection, IEnumerable, and ICloneable
SortedList	Represents a collection of key/value pairs that are sorted by the keys and are accessible by key and by index.	IDictionary, ICollection, IEnumerable, and ICloneable
Stack	A last-in, first-out (LIFO) stack providing push and pop (and peek) functionality.	ICollection, IEnumerable, and ICloneable

The interfaces implemented by these classic collection classes provide huge insights into their overall functionality. Table 10-2 documents the overall nature of these key interfaces, some of which you worked with first-hand in Chapter 9.

Table 10-2. Key Interfaces Supported by Classes of System.Collections

System.Collections Interface	Meaning in Life
ICollection	Defines general characteristics (e.g., size, enumeration, and thread safety) for all non-generic collection types.
ICloneable	Allows the implementing object to return a copy of itself to the caller.
IDictionary	Allows a non-generic collection object to represent its contents using key/value pairs.
IEnumerable	Returns an object implementing the IEnumerator interface (see next table entry).
IEnumerator	Enables foreach style iteration of collection items.
IList	Provides behavior to add, remove, and index items in a sequential list of objects.

In addition to these core classes (and interfaces), the `System.Collections.Specialized` namespace of `System.dll` added a few (pardon the redundancy) specialized collection types such as `BitVector32`, `ListDictionary`, `StringDictionary`, and `StringCollection`. This namespace also contains many additional interfaces and abstract base classes that you can use as a starting point for creating custom collection classes.

While it is true that many successful .NET applications have been built over the years using these “classic” collection classes (and interfaces), history has shown that use of these types can result in a number of issues.

The first issue is that using the `System.Collections` and `System.Collections.Specialized` classes can result in some poorly performing code, especially when you are manipulating data structures (e.g., value types). As you’ll see momentarily, the CLR must perform a number of memory transfer operations when you store structures in a classic collection class, which can hurt runtime execution speed.

The second issue is that these classic collection classes are not type safe because they were (by-and-large) developed to operate on `System.Objects`, and they could therefore contain anything at all. If a .NET developer needed to create a highly type safe collection (e.g., a container that can only hold objects implementing a certain interface), the only real choice was to create a brand new collection class by hand. Doing so was not too labor intensive, but it was a tad bit on the tedious side.

Given these (and other) issues, .NET 2.0 introduced a brand new set of collection classes, which are packaged up in the `System.Collections.Generic` namespace. Any new project created with .NET 2.0 and higher should ignore the legacy, non-generic classes in favor of the corresponding generic classes.

Note This is worth repeating: Any .NET application built with .NET 2.0 or higher should ignore the classes in `System.Collections` in favor of the classes in `System.Collections.Generic`.

Before you look at how to use generics in your programs, you’ll find it helpful to examine the issues of non-generic collection classes a bit closer; this will help you understand better the problems generics intend to solve in the first place. If you wish to follow along, create a new Console Application named `IssuesWithNon-genericCollections`. Next, import the `System.Collections` namespace to the top of your C# code file:

```
using System.Collections;
```

The Issue of Performance

As you might recall from Chapter 4, the .NET platform supports two broad categories of data: value types and reference types. Given that .NET defines two major categories of types, you might occasionally need to represent a variable of one category as a variable of the other category. To do so, C# provides a simple mechanism, termed boxing, to store the data in a value type within a reference variable. Assume that you have created a local variable of type `int` in a method called `SimpleBoxUnboxOperation()`:

```
static void SimpleBoxUnboxOperation()
{
    // Make a ValueType (int) variable.
    int myInt = 25;
}
```

If, during the course of your application, you were to represent this value type as a reference type, you would *box* the value, as follows:

```
private static void SimpleBoxUnboxOperation()
{
    // Make a ValueType (int) variable.
    int myInt = 25;

    // Box the int into an object reference.
    object boxedInt = myInt;
}
```

Boxing can be formally defined as the process of explicitly assigning a value type to a `System.Object` variable. When you box a value, the CLR allocates a new object on the heap and copies the value type's value (25, in this case) into that instance. What is returned to you is a reference to the newly allocated heap-based object. If you use this technique, you don't need to use of a set of wrapper classes to treat stack data temporarily as heap-allocated objects.

The opposite operation is also permitted through unboxing. Unboxing is the process of converting the value held in the object reference back into a corresponding value type on the stack. Syntactically speaking, an unboxing operation looks like a normal casting operation. However, the semantics are quite different. The CLR begins by verifying that the receiving data type is equivalent to the boxed type; and if so, it copies the value back into a local stack-based variable. For example, the following unboxing operations work successfully, given that the underlying type of the `boxedInt` is indeed an `int`:

```
private static void SimpleBoxUnboxOperation()
{
    // Make a ValueType (int) variable.
    int myInt = 25;

    // Box the int into an object reference.
    object boxedInt = myInt;

    // Unbox the reference back into a corresponding int.
    int unboxedInt = (int)boxedInt;
}
```

When the C# compiler encounters boxing/unboxing syntax, it emits CIL code that contains the `box/unbox` op codes. If you were to examine your compiled assembly using `ildasm.exe`, you would find the following:

```
.method private hidebysig static void SimpleBoxUnboxOperation() cil managed
{
    // Code size 19 (0x13)
    .maxstack 1
    .locals init ([0] int32 myInt, [1] object boxedInt, [2] int32 unboxedInt)
    IL_0000:  nop
    IL_0001:  ldc.i4.s 25
    IL_0003:  stloc.0
    IL_0004:  ldloc.0
    IL_0005:  box  [mscorlib]System.Int32
```

```

IL_000a:  stloc.1
IL_000b:  ldloc.1
IL_000c:  unbox.any [mscorlib]System.Int32
IL_0011:  stloc.2
IL_0012:  ret
} // end of method Program::SimpleBoxUnboxOperation

```

Remember that unlike when performing a typical cast, you *must* unbox into an appropriate data type. If you attempt to unbox a piece of data into the incorrect variable, an `InvalidCastException` exception will be thrown. To be perfectly safe, you should wrap each unboxing operation in try/catch logic; however, this would be quite labor intensive to do for every unboxing operation. Consider the following code update, which will throw an error because you're attempting to unbox the boxed int into a long:

```

private static void SimpleBoxUnboxOperation()
{
    // Make a ValueType (int) variable.
    int myInt = 25;

    // Box the int into an object reference.
    object boxedInt = myInt;

    // Unbox in the wrong data type to trigger
    // runtime exception.
    try
    {
        long unboxedInt = (long)boxedInt;
    }
    catch (InvalidCastException ex)
    {
        Console.WriteLine(ex.Message);
    }
}

```

At first glance, boxing/unboxing might seem like a rather uneventful language feature that is more academic than practical. After all, You will seldom store a local value type in a local object variable, as seen here. However, it turns out that the boxing/unboxing process is quite helpful because it allows you to assume everything can be treated as a `System.Object`, while the CLR takes care of the memory-related details on your behalf.

Let's look at a practical use of these techniques. Assume you have created a non-generic `System.Collections.ArrayList` to hold onto a batch of numeric (stack-allocated) data. If you were to examine the members of `ArrayList`, you would find they are prototyped to operate on `System.Object` data. Now consider the `Add()`, `Insert()`, `Remove()` methods, as well as the class indexer:

```

public class ArrayList : object,
    IList, ICollection, IEnumerable, ICloneable
{
    ...
    public virtual int Add(object value);
    public virtual void Insert(int index, object value);
    public virtual void Remove(object obj);
}

```

```
    public virtual object this[int index] {get; set; }
}
```

`ArrayList` has been built to operate on `objects`, which represent data allocated on the heap, so it might seem strange that the following code compiles and executes without throwing an error:

```
static void WorkWithArrayList()
{
    // Value types are automatically boxed when
    // passed to a method requesting an object.
    ArrayList myInts = new ArrayList();
    myInts.Add(10);
    myInts.Add(20);
    myInts.Add(35);
    Console.ReadLine();
}
```

Although you pass in numerical data directly into methods requiring an `object`, the runtime automatically boxes the stack-based data on your behalf.

Later, if you wish to retrieve an item from the `ArrayList` using the type indexer, you must unbox the heap-allocated object into a stack-allocated integer using a casting operation. Remember that the indexer of the `ArrayList` is returning `System.Objects`, not `System.Int32`s:

```
static void WorkWithArrayList()
{
    // Value types are automatically boxed when
    // passed to a member requesting an object.
    ArrayList myInts = new ArrayList();
    myInts.Add(10);
    myInts.Add(20);
    myInts.Add(35);

    // Unboxing occurs when a object is converted back to
    // stack based data.
    int i = (int)myInts[0];

    // Now it is reboxed, as WriteLine() requires object types!
    Console.WriteLine("Value of your int: {0}", i);
    Console.ReadLine();
}
```

Again, note that the stack-allocated `System.Int32` is boxed prior to the call to `ArrayList.Add()` so it can be passed in the required `System.Object`. Also note that the `System.Object` is unboxed back into a `System.Int32` once it is retrieved from the `ArrayList` using the type indexer, only to be boxed *again* when it is passed to the `Console.WriteLine()` method, as this method is operating on `System.Object` variables.

Boxing and unboxing are convenient from a programmer's point of view, but this simplified approach to stack/heap memory transfer comes with the baggage of performance issues (in both speed of execution and code size) and a lack of type safety. To understand the performance issues, ponder the steps that must occur to box and unbox a simple integer:

1. A new object must be allocated on the managed heap.
2. The value of the stack-based data must be transferred into that memory location.
3. When unboxed, the value stored on the heap-based object must be transferred back to the stack.
4. The now unused object on the heap will (eventually) be garbage collected.

Although this particular `WorkWithArrayList()` method won't cause a major bottleneck in terms of performance, you could certainly feel the impact if an `ArrayList` contained thousands of integers that your program manipulates on a somewhat regular basis. In an ideal world, you could manipulate stack-based data in a container without any performance issues. Ideally, it would be nice if you did not have to have to bother plucking data from this container using try/catch scopes (this is exactly what generics let you achieve).

The Issue of Type Safety

You touched on the issue of type safety when you looked at unboxing operations. Recall that you must unbox your data into the same data type it was declared as before boxing. However, there is another aspect of type safety you must keep in mind in a generic-free world: the fact that a majority of the classes of `System.Collections` can typically hold anything whatsoever because their members are prototyped to operate on `System.Objects`. For example, this method builds an `ArrayList` of random bits of unrelated data:

```
static void ArrayListOfRandomObjects()
{
    // The ArrayList can hold anything at all.
    ArrayList allMyObjects = new ArrayList();
    allMyObjects.Add(true);
    allMyObjects.Add(new OperatingSystem(PlatformID.MacOSX, new Version(10, 0)));
    allMyObjects.Add(66);
    allMyObjects.Add(3.14);
}
```

In some cases, you will require an extremely flexible container that can hold literally anything (as seen here). However, most of the time you desire a *type-safe* container that can only operate on a particular type of data point. For example, you might need a container that can only hold database connections, bitmaps, or `IPointy`-compatible objects.

Prior to generics, the only way you could address this issue of type safety was to create a custom (strongly typed) collection class manually. Assume you wish to create a custom collection that can only contain objects of type `Person`:

```
public class Person
{
    public int Age {get; set;}
    public string FirstName {get; set;}
    public string LastName {get; set;}
```

```

public Person(){}
public Person(string firstName, string lastName, int age)
{
    Age = age;
    FirstName = firstName;
    LastName = lastName;
}

public override string ToString()
{
    return string.Format("Name: {0} {1}, Age: {2}",
        FirstName, LastName, Age);
}
}

```

To build a *person only collection*, you could define a `System.Collections.ArrayList` member variable within a class named `PersonCollection` and configure all members to operate on strongly typed `Person` objects, rather than on `System.Object` types. Here is a simple example (a production-level custom collection could support many additional members and might extend an abstract base class from the `System.Collections` namespace):

```

public class PersonCollection : IEnumerable
{
    private ArrayList arPeople = new ArrayList();

    // Cast for caller.
    public Person GetPerson(int pos)
    { return (Person)arPeople[pos]; }

    // Only insert Person objects.
    public void AddPerson(Person p)
    { arPeople.Add(p); }

    public void ClearPeople()
    { arPeople.Clear(); }

    public int Count
    { get { return arPeople.Count; } }

    // Foreach enumeration support.
    IEnumerator IEnumerable.GetEnumerator()
    { return arPeople.GetEnumerator(); }
}

```

Notice that the `PersonCollection` class implements the `IEnumerable` interface, which allows a `foreach`-like iteration over each contained item. Also notice that your `GetPerson()` and `AddPerson()` methods have been prototyped to operate only on `Person` objects, not bitmaps, strings, database connections, or other items. With these types defined, you are now assured of type safety, given that the C# compiler will be able to determine any attempt to insert an incompatible data type:

```

static void UsePersonCollection()
{
    Console.WriteLine("***** Custom Person Collection *****\n");
    PersonCollection myPeople = new PersonCollection();
    myPeople.AddPerson(new Person("Homer", "Simpson", 40));
    myPeople.AddPerson(new Person("Marge", "Simpson", 38));
    myPeople.AddPerson(new Person("Lisa", "Simpson", 9));
    myPeople.AddPerson(new Person("Bart", "Simpson", 7));
    myPeople.AddPerson(new Person("Maggie", "Simpson", 2));

    // This would be a compile-time error!
    // myPeople.AddPerson(new Car());

    foreach (Person p in myPeople)
        Console.WriteLine(p);
}

```

While custom collections do ensure type safety, this approach leaves you in a position where you must create an (almost identical) custom collection for each unique data type you wish to contain. Thus, if you need a custom collection that can operate only on classes deriving from the `Car` base class, you need to build a highly similar collection class:

```

public class CarCollection : IEnumerable
{
    private ArrayList arCars = new ArrayList();

    // Cast for caller.
    public Car GetCar(int pos)
    { return (Car) arCars[pos]; }

    // Only insert Car objects.
    public void AddCar(Car c)
    { arCars.Add(c); }

    public void ClearCars()
    { arCars.Clear(); }

    public int Count
    { get { return arCars.Count; } }

    // Foreach enumeration support.
    IEnumerator IEnumerable.GetEnumerator()
    { return arCars.GetEnumerator(); }
}

```

However, a custom collection class does nothing to solve the issue of boxing/unboxing penalties. Even if you were to create a custom collection named `IntCollection` that you designed to operate only on `System.Int32` items, you would have to allocate some type of object to hold the data (e.g., `System.Array` and `ArrayList`):

```

public class IntCollection : IEnumerable
{
    private ArrayList arInts = new ArrayList();

    // Unbox for caller.
    public int GetInt(int pos)
    { return (int)arInts[pos]; }

    // Boxing operation!
    public void AddInt(int i)
    { arInts.Add(i); }

    public void ClearInts()
    { arInts.Clear(); }

    public int Count
    { get { return arInts.Count; } }

    IEnumerator IEnumerable.GetEnumerator()
    { return arInts.GetEnumerator(); }
}

```

Regardless of which type you might choose to hold the integers, you cannot escape the boxing dilemma using non-generic containers.

When you use generic collection classes, you rectify all of the previous issues, including boxing/unboxing penalties and a lack of type safety. Also, the need to build a custom (generic) collection class manually becomes quite rare. Rather than having to build unique classes that can contain people, cars, and integers, you can use a generic collection class and specify the type of type. Consider the following method, which uses a generic `List<>` class (in the `System.Collections.Generic` namespace) to contain various types of data in a strongly typed manner (don't fret the details of generic syntax at this time):

```

static void UseGenericList()
{
    Console.WriteLine("***** Fun with Generics *****\n");

    // This List<> can only hold Person objects.
    List<Person> morePeople = new List<Person>();
    morePeople.Add(new Person ("Frank", "Black", 50));
    Console.WriteLine(morePeople[0]);

    // This List<> can only hold integers.
    List<int> moreInts = new List<int>();
    moreInts.Add(10);
    moreInts.Add(2);
    int sum = moreInts[0] + moreInts[1];

    // Compile-time error! Can't add Person object
    // to a list of ints!
    // moreInts.Add(new Person());
}

```

The first `List<>` object can *only* contain `Person` objects. Therefore, you do not need to perform a cast when plucking the items from the container, which makes this approach more type safe. The second `List<>` can *only* contain integers, all of which are allocated on the stack; in other words, there is no hidden boxing or unboxing as you found with the non-generic `ArrayList`.

Here is a short list of the benefits generic containers provide over their non-generic counterparts:

- Generics provide better performance because they do not result in boxing or unboxing penalties.
- Generics are more type safe because they can only contain the type of type you specify.
- Generics greatly reduce the need to build custom collection types because the base class library provides several prefabricated containers.

■ **Source Code** You can find the `IssuesWithNonGenericCollections` project under the Chapter 10 directory.

The Role of Generic Type Parameters

You can find generic classes, interfaces, structures, and delegates sprinkled throughout the .NET base class libraries, and these might be part of any .NET namespace.

■ **Note** Only classes, structures, interfaces, and delegates can be written generically; enum types cannot.

When you see a generic item listed in the .NET Framework 4.0 SDK documentation or the Visual Studio 2010 object browser, you will notice a pair of angled brackets with a letter or other token sandwiched within. Figure 10-1 shows a number of generic items in the `System.Collections.Generic` namespace, including the highlighted `List<T>` class.




Figure 10-1. Generic Items Supporting Type Parameters

Formally speaking, you call these tokens *type parameters*; however, in more user friendly terms, you can simply call them *placeholders*. You can read the symbol `<T>` as *of T*. Thus, you can read `IEnumerable<T>` as *IEnumerable of T*; or, to say it another way, *an enumeration of type T*.

Note The name of a type parameter (placeholder) is irrelevant, and it is up to the individual who created the generic item. However, typically *T* is used to represent types, *TKey* or *K* is used for keys, and *TValue* or *V* is used for values.

When you create a generic object, implement a generic interface, or invoke a generic member, it is up to you to supply a value to the type parameter. You'll see many examples in this chapter, and throughout the remainder of the text. However, to set the stage, let's see the basics of interacting with generic types and members.

Specifying Type Parameters for Generic Classes / Structures

When you create an instance of a generic class or structure, you specify the type parameter when you declare the variable and when you invoke the constructor. As you saw in the preceding code example, `UseGenericList()` defined two `List<>` objects:

```
// This List<> can only hold Person objects.
List<Person> morePeople = new List<Person>();
```

You can read the preceding snippet as *a List<T> of T, where T is of type Person*. Or, more simply, you can read it as *a list of person objects*. Once you specify the type parameter of a generic item, it cannot be changed (remember: generics are all about type safety). When you specify a type parameter for a generic class or structure, all occurrences of the placeholder(s) are now replaced with your supplied value.

If you were to view the full declaration of the generic `List<T>` class using the Visual Studio 2010 object browser, you would see that the placeholder `T` is used throughout the definition of the `List<T>` type. Here is a partial listing (note the items in bold):

```
// A partial listing of the List<T> class.
namespace System.Collections.Generic
{
    public class List<T> :
        IList<T>, ICollection<T>, IEnumerable<T>,
        IList, ICollection, IEnumerable
    {
        ...
        public void Add(T item);
        public ReadOnlyCollection<T> AsReadOnly();
        public int BinarySearch(T item);
        public bool Contains(T item);
        public void CopyTo(T[] array);
        public int FindIndex(System.Predicate<T> match);
        public T FindLast(System.Predicate<T> match);
        public bool Remove(T item);
        public int RemoveAll(System.Predicate<T> match);
        public T[] ToArray();
        public bool TrueForAll(System.Predicate<T> match);
        public T this[int index] { get; set; }
    }
}
```

When you create a `List<T>` specifying `Person` objects, it is as if the `List<T>` type were defined as follows:

```
namespace System.Collections.Generic
{
    public class List<Person> :
        IList<Person>, ICollection<Person>, IEnumerable<Person>,
        IList, ICollection, IEnumerable
    {
        ...
        public void Add(Person item);
        public ReadOnlyCollection<Person> AsReadOnly();
        public int BinarySearch(Person item);
        public bool Contains(Person item);
        public void CopyTo(Person[] array);
        public int FindIndex(System.Predicate<Person> match);
        public Person FindLast(System.Predicate<Person> match);
        public bool Remove(Person item);
        public int RemoveAll(System.Predicate<Person> match);
        public Person[] ToArray();
```

```

    public bool TrueForAll(System.Predicate<Person> match);
    public Person this[int index] { get; set; }
}
}

```

Of course, when you create a generic `List<T>` variable, the compiler does not literally create a brand new implementation of the `List<T>` class. Rather, it will address only the members of the generic type you actually invoke.

Note In the next chapter, you will learn about generic delegates, which will also require you to specify a type parameter when creating them.

Specifying Type Parameters for Generic Members

It is fine for a non-generic class or structure to support a handful of generic members (e.g., methods and properties). In these cases, you would also need to specify the placeholder value at the time you invoke the method. For example, `System.Array` supports a several generic methods (which were added in .NET 2.0). Specifically, the static `Sort()` method now has a generic counterpart named `Sort<T>()`. Consider the following code snippet, where `T` is of type `int`:

```

int[] myInts = { 10, 4, 2, 33, 93 };

// Specify the placeholder to the generic
// Sort<>() method.
Array.Sort<int>(myInts);

foreach (int i in myInts)
{
    Console.WriteLine(i);
}

```

Specifying Type Parameters for Generic Interfaces

It is common to implement generic interfaces when you building classes or structures that need to support various framework behaviors (e.g., cloning, sorting, and enumeration). In Chapter 9, you learned about a number of non-generic interfaces, such as `IComparable`, `IEnumerable`, `IEnumerator`, and `IComparer`. Recall that the non-generic `IComparable` interface was defined like this:

```

public interface IComparable
{
    int CompareTo(object obj);
}

```

In Chapter 9, you also implemented this interface on your `Car` class to enable sorting in a standard array. However, the code required a several runtime checks and casting operations because the parameter was a general `System.Object`:

```

public class Car : IComparable
{
...
    // IComparable implementation.
    int IComparable.CompareTo(object obj)
    {
        Car temp = obj as Car;
        if (temp != null)
        {
            if (this.CarID > temp.CarID)
                return 1;
            if (this.CarID < temp.CarID)
                return -1;
            else
                return 0;
        }
        else
            throw new ArgumentException("Parameter is not a Car!");
    }
}

```

Now assume you use the generic counterpart of this interface:

```

public interface IComparable<T>
{
    int CompareTo(T obj);
}

```

In this case, your implementation code will be cleaned up considerably:

```

public class Car : IComparable<Car>
{
...
    // IComparable<T> implementation.
    int IComparable<Car>.CompareTo(Car obj)
    {
        if (this.CarID > obj.CarID)
            return 1;
        if (this.CarID < obj.CarID)
            return -1;
        else
            return 0;
    }
}

```

Here you do not need to check whether the incoming parameter is a `Car` because it can *only* be a `Car`! If someone were to pass in an incompatible data type, you would get a compile-time error.

Now that you have a better handle on how to interact with generic items, as well as the role of type parameters (aka placeholders), you're ready to examine the classes and interfaces of the `System.Collections.Generic` namespace.

The System.Collections.Generic Namespace

You can find the bulk of the `System.Collections.Generic` namespace in the `mscorlib.dll` and `System.dll` assemblies. At the opening of this chapter, I briefly mentioned some of the core non-generic interfaces implemented by the non-generic collection classes. Not too surprisingly, the `System.Collections.Generic` namespace defines generic replacements for many of them.

In fact, you can find a number of the generic interfaces that extend their non-generic counterparts! This might seem odd; however, by doing so, implementing classes will also support the legacy functionality found in their non-generic siblings. For example, `IEnumerable<T>` extends `IEnumerable`. Table 10-3 documents the core generic interfaces you'll encounter when working with the generic collection classes.

Note If you have worked with generics prior to .NET 4.0, you should be aware of the new `ISet<T>` and `SortedSet<T>` types, which you'll learn more about later in this chapter.

Table 10-3. Key Interfaces Supported by Classes of `System.Collections.Generic`

System.Collections Interface	Meaning in Life
<code>ICollection<T></code>	Defines general characteristics (e.g., size, enumeration, and thread safety) for all generic collection types.
<code>IComparer<T></code>	Defines a way to compare to objects.
<code>IDictionary< TKey, TValue ></code>	Allows a generic collection object to represent its contents using key/value pairs.
<code>IEnumerable<T></code>	Returns the <code>IEnumerator<T></code> interface for a given object.
<code>IEnumerator<T></code>	Enables <code>foreach</code> -style iteration over a generic collection.
<code>IList<T></code>	Provides behavior to add, remove, and index items in a sequential list of objects.
<code>ISet<T></code>	Provides the base interface for the abstraction of sets.

The `System.Collections.Generic` namespace also defines several classes that implement many of these key interfaces. Table 10-4 describes some commonly used classes of this namespace, the interfaces they implement, and their basic functionality.

Table 10-4. Classes of *System.Collections.Generic*

Generic Class	Supported Key Interfaces	Meaning in Life
Dictionary<TKey, TValue>	ICollection<T>, IDictionary<TKey, TValue>, IEnumerable<T>	This represents a generic collection of keys and values.
List<T>	ICollection<T>, IEnumerable<T>, IList<T>	This is a dynamically resizable sequential list of items.
LinkedList<T>	ICollection<T>, IEnumerable<T>	This represents a doubly linked list.
Queue<T>	ICollection (not a typo! This is the non-generic collection interface), IEnumerable<T>	This is a generic implementation of a first-in, first-out (FIFO) list.
SortedDictionary<TKey, TValue>	ICollection<T>, IDictionary<TKey, TValue>, IEnumerable<T>	This is a generic implementation of a sorted set of key/value pairs.
SortedSet<T>	ICollection<T>, IEnumerable<T>, ISet<T>	This represents a collection of objects that is maintained in sorted order with no duplication.
Stack<T>	ICollection (not a typo! This is the non-generic collection interface), IEnumerable<T>	This is a generic implementation of a last-in, first-out (LIFO) list.

The `System.Collections.Generic` namespace also defines many auxiliary classes and structures that work in conjunction with a specific container. For example, the `LinkedListNode<T>` type represents a node within a generic `LinkedList<T>`, the `KeyNotFoundException` exception is raised when attempting to grab an item from a container using a nonexistent key, and so forth.

It is also worth pointing out that `mscorlib.dll` and `System.dll` are not the only assemblies which add new types to the `System.Collections.Generic` namespace. For example, `System.Core.dll` adds the `HashSet<T>` class to the mix. Be sure to consult the .NET Framework 4.0 SDK documentation for full details of the `System.Collections.Generic` namespace.

In any case, your next task is to learn how to use some of these generic collection classes. Before you do however, allow me to illustrate a C# language feature (first introduced in .NET 3.5) that simplifies the way you populate generic (and non-generic) collection containers with data.

Understanding Collection Initialization Syntax

In Chapter 4, you learned about *object initialization syntax*, which allows you to set properties on a new variable at the time of construction. Closely related to this is *collection initialization syntax*. This C# language feature makes it possible to populate many containers (such as `ArrayList` or `List<T>`) with items by using syntax similar to what you use to populate a basic array.

Note You can only apply collection initialization syntax to classes that support an `Add()` method, which is formalized by the `ICollection<T>/ICollection` interfaces.

Consider the following examples:

```
// Init a standard array.
int[] myArrayOfInts = { 0, 1, 2, 3, 4, 5, 6, 7, 8, 9 };

// Init a generic List<T> of ints.
List<int> myGenericList = new List<int> { 0, 1, 2, 3, 4, 5, 6, 7, 8, 9 };

// Init an ArrayList with numerical data.
ArrayList myList = new ArrayList { 0, 1, 2, 3, 4, 5, 6, 7, 8, 9 };
```

If your container is managing a collection of classes or a structure, you can blend object initialization syntax with collection initialization syntax to yield some functional code. You might recall the `Point` class from Chapter 5, which defined two properties named `X` and `Y`. If you wish to build a generic `List<T>` of `Point` objects, you can write the following:

```
List<Point> myListOfPoints = new List<Point>
{
    new Point { X = 2, Y = 2 },
    new Point { X = 3, Y = 3 },
    new Point(PointColor.BloodRed){ X = 4, Y = 4 }
};

foreach (var pt in myListOfPoints)
{
    Console.WriteLine(pt);
}
```

Again, the benefit of this syntax is that you save yourself numerous keystrokes. While the nested curly brackets can become difficult to read if you don't mind your formatting, imagine the amount of code that would be required to fill the following `List<T>` of `Rectangles` if you did not have collection initialization syntax (you might recall from Chapter 4 that you created a `Rectangle` class that contained two properties encapsulating `Point` objects):

```
List<Rectangle> myListOfRects = new List<Rectangle>
```

```

{
    new Rectangle {TopLeft = new Point { X = 10, Y = 10 },
                  BottomRight = new Point { X = 200, Y = 200}},
    new Rectangle {TopLeft = new Point { X = 2, Y = 2 },
                  BottomRight = new Point { X = 100, Y = 100}},
    new Rectangle {TopLeft = new Point { X = 5, Y = 5 },
                  BottomRight = new Point { X = 90, Y = 75}}
};

foreach (var r in myListOfRects)
{
    Console.WriteLine(r);
}

```

Working with the List<T> Class

Create a brand new Console Application project named `FunWithGenericCollections`. This project type automatically references `mscorlib.dll` and `System.dll`, so you have access to a majority of the common generic collection classes. Also note that your initial C# code file already imports the `System.Collections.Generic` namespace.

The first generic class you will examine is the `List<T>`, which you've already seen once or twice in this chapter. The `List<T>` class is bound to be your most frequently used type in the `System.Collections.Generic` namespace because it allows you to resize the contents dynamically. To illustrate the basics of this type, ponder the following method in your `Program` class, which leverages `List<T>` to manipulate the set of `Person` objects seen earlier in this chapter; you might recall that these `Person` objects defined three properties (`Age`, `FirstName`, and `LastName`) and a custom `ToString()` implementation:

```

private static void UseGenericList()
{
    // Make a List of Person objects, filled with
    // collection / object init syntax.
    List<Person> people = new List<Person>()
    {
        new Person {FirstName= "Homer", LastName="Simpson", Age=47},
        new Person {FirstName= "Marge", LastName="Simpson", Age=45},
        new Person {FirstName= "Lisa", LastName="Simpson", Age=9},
        new Person {FirstName= "Bart", LastName="Simpson", Age=8}
    };

    // Print out # of items in List.
    Console.WriteLine("Items in list: {0}", people.Count);

    // Enumerate over list.
    foreach (Person p in people)
        Console.WriteLine(p);

    // Insert a new person.
    Console.WriteLine("\n->Inserting new person.");
    people.Insert(2, new Person { FirstName = "Maggie", LastName = "Simpson", Age = 2 });
}

```

```

Console.WriteLine("Items in list: {0}", people.Count);

// Copy data into a new array.
Person[] arrayOfPeople = people.ToArray();
for (int i = 0; i < arrayOfPeople.Length; i++)
{
    Console.WriteLine("First Names: {0}", arrayOfPeople[i].FirstName);
}
}

```

Here you use initialization syntax to populate your `List<T>` with objects, as a shorthand notation for calling `Add()` n number of times. Once you print out the number of items in the collection (as well as enumerate over each item), you invoke `Insert()`. As you can see, `Insert()` allows you to plug a new item into the `List<T>` at a specified index.

Finally, notice the call to the `ToArray()` method, which returns an array of `Person` objects based on the contents of the original `List<T>`. From this array, you loop over the items again using the array's indexer syntax. If you call this method from within `Main()`, you get the following output:

***** Fun with Generic Collections *****

```

Items in list: 4
Name: Homer Simpson, Age: 47
Name: Marge Simpson, Age: 45
Name: Lisa Simpson, Age: 9
Name: Bart Simpson, Age: 8

->Inserting new person.
Items in list: 5
First Names: Homer
First Names: Marge
First Names: Maggie
First Names: Lisa
First Names: Bart

```

The `List<T>` class defines many additional members of interest, so be sure to consult the .NET Framework 4.0 SDK documentation for more information. Next, let's look at a few more generic collections, specifically `Stack<T>`, `Queue<T>` and `SortedSet<T>`. This should get you in a great position to understand your basic choices regarding how to hold your custom application data.

Working with the `Stack<T>` Class

The `Stack<T>` class represents a collection that maintains items using a last-in, first-out manner. As you might expect, `Stack<T>` defines members named `Push()` and `Pop()` to place items onto or remove items from the stack. The following method creates a stack of `Person` objects:

```

static void UseGenericStack()
{
    Stack<Person> stackOfPeople = new Stack<Person>();

```

```

stackOfPeople.Push(new Person
    { FirstName = "Homer", LastName = "Simpson", Age = 47 });
stackOfPeople.Push(new Person
    { FirstName = "Marge", LastName = "Simpson", Age = 45 });
stackOfPeople.Push(new Person
    { FirstName = "Lisa", LastName = "Simpson", Age = 9 });

// Now look at the top item, pop it, and look again.
Console.WriteLine("First person is: {0}", stackOfPeople.Peek());
Console.WriteLine("Popped off {0}", stackOfPeople.Pop());

Console.WriteLine("\nFirst person is: {0}", stackOfPeople.Peek());
Console.WriteLine("Popped off {0}", stackOfPeople.Pop());

Console.WriteLine("\nFirst person item is: {0}", stackOfPeople.Peek());
Console.WriteLine("Popped off {0}", stackOfPeople.Pop());

try
{
    Console.WriteLine("\nnFirst person is: {0}", stackOfPeople.Peek());
    Console.WriteLine("Popped off {0}", stackOfPeople.Pop());
}
catch (InvalidOperationException ex)
{
    Console.WriteLine("\nError! {0}", ex.Message);
}
}

```

Here, you build a stack that contains three people, added in the order of their first names: Homer, Marge, and Lisa. As you peek into the stack, you will always see the object at the top first; therefore, the first call to `Peek()` reveals the third `Person` object. After a series of `Pop()` and `Peek()` calls, the stack eventually empties, at which time additional `Peek()` and `Pop()` calls raise a system exception. You can see the output for this here:

***** Fun with Generic Collections *****

```
First person is: Name: Lisa Simpson, Age: 9
Popped off Name: Lisa Simpson, Age: 9
```

```
First person is: Name: Marge Simpson, Age: 45
Popped off Name: Marge Simpson, Age: 45
```

```
First person item is: Name: Homer Simpson, Age: 47
Popped off Name: Homer Simpson, Age: 47
```

```
Error! Stack empty.
```

Working with the Queue<T> Class

Queues are containers that ensure items are accessed in a first-in, first-out manner. Sadly, we humans are subject to queues all day long: lines at the bank, lines at the movie theater, and lines at the morning coffeehouse. When you need to model a scenario in which items are handled on a first-come, first-served basis, you will find the `Queue<T>` class fits the bill. In addition to the functionality provided by the supported interfaces, `Queue` defines the key members shown in Table 10-5.

Table 10-5. Members of the `Queue<T>` Type

Select Member of <code>Queue<T></code>	Meaning in Life
<code>Dequeue()</code>	Removes and returns the object at the beginning of the <code>Queue<T></code> .
<code>Enqueue()</code>	Adds an object to the end of the <code>Queue<T></code> .
<code>Peek()</code>	Returns the object at the beginning of the <code>Queue<T></code> without removing it.

Now let's put these methods to work. You can begin by leveraging your `Person` class again and building a `Queue<T>` object that simulates a line of people waiting to order coffee. First, assume you have the following static helper method:

```
static void GetCoffee(Person p)
{
    Console.WriteLine("{0} got coffee!", p.FirstName);
}
```

Now assume you have this additional helper method, which calls `GetCoffee()` internally:

```
static void UseGenericQueue()
{
    // Make a Q with three people.
    Queue<Person> peopleQ = new Queue<Person>();
    peopleQ.Enqueue(new Person {FirstName= "Homer",
        LastName="Simpson", Age=47});
    peopleQ.Enqueue(new Person {FirstName= "Marge",
        LastName="Simpson", Age=45});
    peopleQ.Enqueue(new Person {FirstName= "Lisa",
        LastName="Simpson", Age=9});

    // Peek at first person in Q.
    Console.WriteLine("{0} is first in line!", peopleQ.Peek().FirstName);

    // Remove each person from Q.
    GetCoffee(peopleQ.Dequeue());
    GetCoffee(peopleQ.Dequeue());
    GetCoffee(peopleQ.Dequeue());
```

```
// Try to de-Q again?
try
{
    GetCoffee(peopleQ.Dequeue());
}
catch(InvalidOperationException e)
{
    Console.WriteLine("Error! {0}", e.Message);
}
```

Here you insert three items into the `Queue<T>` class using its `Enqueue()` method. The call to `Peek()` allows you to view (but not remove) the first item currently in the `Queue`. Finally, the call to `Dequeue()` removes the item from the line and sends it into the `GetCoffee()` helper function for processing. Note that if you attempt to remove items from an empty queue, a runtime exception is thrown. Here is the output you receive when calling this method:

***** Fun with Generic Collections *****

```
Homer is first in line!
Homer got coffee!
Marge got coffee!
Lisa got coffee!
Error! Queue empty.
```

Working with the `SortedSet<T>` Class

The final generic collection class you will look was introduced with the release of .NET 4.0. The `SortedSet<T>` class is useful because it automatically ensures that the items in the set are sorted when you insert or remove items. However, you do need to inform the `SortedSet<T>` class exactly *how* you want it to sort the objects, by passing in as a constructor argument an object that implements the generic `IComparer<T>` interface.

Begin by creating a brand new class named `SortPeopleByAge`, which implements `IComparer<Person>`, where `T` is of type `Person`. Recall that this interface defines a single method named `Compare()`, where you can author whatever logic you require for the comparison. Here is a simple implementation of this class:

```
class SortPeopleByAge : IComparer<Person>
{
    public int Compare(Person firstPerson, Person secondPerson)
    {
        if (firstPerson.Age > secondPerson.Age)
            return 1;
        if (firstPerson.Age < secondPerson.Age)
            return -1;
        else
            return 0;
    }
}
```

Now update your Program class with the following new method, which I assume you will call from Main():

```

private static void UseSortedSet()
{
    // Make some people with different ages.
    SortedSet<Person> setOfPeople = new SortedSet<Person>(new SortPeopleByAge())
    {
        new Person {FirstName= "Homer", LastName="Simpson", Age=47},
        new Person {FirstName= "Marge", LastName="Simpson", Age=45},
        new Person {FirstName= "Lisa", LastName="Simpson", Age=9},
        new Person {FirstName= "Bart", LastName="Simpson", Age=8}
    };

    // Note the items are sorted by age!
    foreach (Person p in setOfPeople)
    {
        Console.WriteLine(p);
    }
    Console.WriteLine();

    // Add a few new people, with various ages.
    setOfPeople.Add(new Person { FirstName = "Saku", LastName = "Jones", Age = 1 });
    setOfPeople.Add(new Person { FirstName = "Mikko", LastName = "Jones", Age = 32 });

    // Still sorted by age!
    foreach (Person p in setOfPeople)
    {
        Console.WriteLine(p);
    }
}
```

When you run your application, the listing of objects is now always ordered based on the value of the Age property, regardless of the order you inserted or removed objects:

***** Fun with Generic Collections *****

```
Name: Bart Simpson, Age: 8
Name: Lisa Simpson, Age: 9
Name: Marge Simpson, Age: 45
Name: Homer Simpson, Age: 47
```

```
Name: Saku Jones, Age: 1
Name: Bart Simpson, Age: 8
Name: Lisa Simpson, Age: 9
Name: Mikko Jones, Age: 32
Name: Marge Simpson, Age: 45
Name: Homer Simpson, Age: 47
```

Awesome! At this point, you should feel more comfortable, but just about the benefits of generic programming, but also with using generic types in the .NET base class libraries. To conclude this chapter, you will learn how to build your own custom generic types and generic methods, as well as why you might want to.

■ **Source Code** You can find the `FunWithGenericCollections` project under the Chapter 10 directory.

Creating Custom Generic Methods

While most developers typically use the existing generic types within the base class libraries, it is also possible to build your own generic members and custom generic types. Let's look at how to incorporate custom generics into your own projects. The first step is to build a generic swap method. Begin by creating a new console application named `CustomGenericMethods`.

When you build custom generic methods, you achieve a supercharged version of traditional method overloading. In Chapter 2, you learned that overloading is the act of defining multiple versions of a single method, which differ by the number of, or type of, parameters.

While overloading is a useful feature in an object oriented language, one problem is that you can easily end up with a ton of methods that essentially do the same thing. For example, assume you need to build some methods that can switch two pieces of data using a simple swap routine. You might begin by authoring a new method that can operate on integers, like this:

```
// Swap two integers.  
static void Swap(ref int a, ref int b)  
{  
    int temp;  
    temp = a;  
    a = b;  
    b = temp;  
}
```

So far, so good. But now assume you also need to swap two `Person` objects; this would require authoring a new version of `Swap()`:

```
// Swap two Person objects.  
static void Swap(ref Person a, ref Person b)  
{  
    Person temp;  
    temp = a;  
    a = b;  
    b = temp;  
}
```

No doubt, you can see where this is going. If you also needed to swap floating point numbers, bitmaps, cars, buttons and whatnot, you would have to build even more methods, which would become a maintenance nightmare. You could build a single (non-generic) method that operated on object

parameters, but then you face all the issues you examined earlier in this chapter, including boxing, unboxing, a lack of type safety, explicit casting, and so on.

Whenever you have a group of overloaded methods that only differ by incoming arguments, this is your clue that generics could make your life easier. Consider the following generic `Swap<T>` method that can swap any two `T`s:

```
// This method will swap any two items.
// as specified by the type parameter <T>.
static void Swap<T>(ref T a, ref T b)
{
    Console.WriteLine("You sent the Swap() method a {0}",
        typeof(T));
    T temp;
    temp = a;
    a = b;
    b = temp;
}
```

Notice how a generic method is defined by specifying the type parameters after the method name, but before the parameter list. Here, you state that the `Swap<T>()` method can operate on any two parameters of type `<T>`. To spice things up a bit, you also print out the type name of the supplied placeholder to the console using C#'s `typeof()` operator. Now consider the following `Main()` method, which swaps integers and strings:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Custom Generic Methods *****\n");

    // Swap 2 ints.
    int a = 10, b = 90;
    Console.WriteLine("Before swap: {0}, {1}", a, b);
    Swap<int>(ref a, ref b);
    Console.WriteLine("After swap: {0}, {1}", a, b);
    Console.WriteLine();

    // Swap 2 strings.
    string s1 = "Hello", s2 = "There";
    Console.WriteLine("Before swap: {0} {1}!", s1, s2);
    Swap<string>(ref s1, ref s2);
    Console.WriteLine("After swap: {0} {1}!", s1, s2);

    Console.ReadLine();
}
```

The output looks like this:

***** Fun with Custom Generic Methods *****

Before swap: 10, 90
 You sent the Swap() method a System.Int32

```
After swap: 90, 10
```

```
Before swap: Hello There!
You sent the Swap() method a System.String
After swap: There Hello!
```

The major benefit of this approach is that you have only one version of `Swap<T>()` to maintain, yet it can operate on any two items of a given type in a type safe manner. Better yet, stack-based items stay on the stack, while heap-based items stay on the heap!

Inference of Type Parameters

When you invoke generic methods such as `Swap<T>`, you can optionally omit the type parameter if (and only if) the generic method requires arguments because the compiler can infer the type parameter based on the member parameters. For example, you could swap two `System.Boolean` values by adding the following code to `Main()`:

```
// Compiler will infer System.Boolean.
bool b1 = true, b2 = false;
Console.WriteLine("Before swap: {0}, {1}", b1, b2);
Swap(ref b1, ref b2);
Console.WriteLine("After swap: {0}, {1}", b1, b2);
```

Even though the compiler is able to discover the correct type parameter based on the data type used to declare `b1` and `b2`, you should get in the habit of always specifying the type parameter explicitly:

```
Swap<bool>(ref b1, ref b2);
```

This makes it clear to your fellow programmers that this method is indeed generic. Moreover, inference of type parameters only works if the generic method has at least one parameter. For example, assume you have the following generic method in your `Program` class:

```
static void DisplayBaseClass<T>()
{
    // BaseType is a method used in reflection,
    // which will be examined in Chapter 15
    Console.WriteLine("Base class of {0} is: {1}.",
        typeof(T), typeof(T).BaseType);
}
```

In this case, you must supply the type parameter upon invocation:

```
static void Main(string[] args)
{
...
    // Must supply type parameter if
    // the method does not take params.
    DisplayBaseClass<int>();
    DisplayBaseClass<string>();
```

```
// Compiler error! No params? Must supply placeholder!
// DisplayBaseClass();
Console.ReadLine();
}
```

Currently, the generic `Swap<T>` and `DisplayBaseClass<T>` methods are defined within the application's `Program` class. Of course, as with any method, you are free to define these members in a separate class type (`MyGenericMethods`) if you would prefer to do it that way:

```
public static class MyGenericMethods
{
    public static void Swap<T>(ref T a, ref T b)
    {
        Console.WriteLine("You sent the Swap() method a {0}",
            typeof(T));
        T temp;
        temp = a;
        a = b;
        b = temp;
    }

    public static void DisplayBaseClass<T>()
    {
        Console.WriteLine("Base class of {0} is: {1}.",
            typeof(T), typeof(T).BaseType);
    }
}
```

The static `Swap<T>` and `DisplayBaseClass<T>` methods have been scoped within a new static class type, so you need to specify the type's name when invoking either member, as in this example:

```
MyGenericMethods.Swap<int>(ref a, ref b);
```

Of course, generic methods do not need to be static. If `Swap<T>` and `DisplayBaseClass<T>` were instance level (and defined in a non-static class), you would simply make an instance of `MyGenericMethods` and invoke them using the object variable:

```
MyGenericMethods c = new MyGenericMethods();
c.Swap<int>(ref a, ref b);
```

■ Source Code You can find the `CustomGenericMethods` project under the Chapter 10 directory.

Creating Custom Generic Structures and Classes

Now that you understand how to define and invoke generic methods, it's time to turn your attention to the construction of a generic structure (the process of building a generic class is identical) within a new Console Application project named `GenericPoint`. Assume you have built a generic `Point` structure that

supports a single type parameter that represents the underlying storage for the (x, y) coordinates. The caller can then create `Point<T>` types as follows:

```
// Point using ints.
Point<int> p = new Point<int>(10, 10);

// Point using double.
Point<double> p2 = new Point<double>(5.4, 3.3);
```

Here is the complete definition of `Point<T>`, with some analysis to follow:

```
// A generic Point structure.
public struct Point<T>
{
    // Generic state data.
    private T xPos;
    private T yPos;

    // Generic constructor.
    public Point(T xVal, T yVal)
    {
        xPos = xVal;
        yPos = yVal;
    }

    // Generic properties.
    public T X
    {
        get { return xPos; }
        set { xPos = value; }
    }

    public T Y
    {
        get { return yPos; }
        set { yPos = value; }
    }

    public override string ToString()
    {
        return string.Format("[{0}, {1}]", xPos, yPos);
    }

    // Reset fields to the default value of the
    // type parameter.
    public void ResetPoint()
    {
        xPos = default(T);
        yPos = default(T);
    }
}
```

The default Keyword in Generic Code

As you can see, `Point<T>` leverages its type parameter in the definition of the field data, constructor arguments, and property definitions. Notice that, in addition to overriding `ToString()`, `Point<T>` defines a method named `ResetPoint()` that uses some new syntax you have not yet seen:

```
// The "default" keyword is overloaded in C#.
// When used with generics, it represents the default
// value of a type parameter.
public void ResetPoint()
{
    X = default(T);
    Y = default(T);
}
```

With the introduction of generics, the C# `default` keyword has been given a dual identity. In addition to its use within a `switch` construct, it can also be used to set a type parameter to its default value. This is helpful because a generic type does not know the actual placeholders up front, which means it cannot safely assume what the default value will be. The defaults for a type parameter are as follows:

- Numeric values have a default value of 0.
- Reference types have a default value of `null`.
- Fields of a structure are set to 0 (for value types) or `null` (for reference types).

For `Point<T>`, you can set the `X` and `Y` values to 0 directly because it is safe to assume the caller will supply only numerical data. However, you can also increase the overall flexibility of the generic type by using the `default(T)` syntax. In any case, you can now exercise the methods of `Point<T>`:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Generic Structures *****\n");

    // Point using ints.
    Point<int> p = new Point<int>(10, 10);
    Console.WriteLine("p.ToString()={0}", p.ToString());
    p.ResetPoint();
    Console.WriteLine("p.ToString()={0}", p.ToString());
    Console.WriteLine();

    // Point using double.
    Point<double> p2 = new Point<double>(5.4, 3.3);
    Console.WriteLine("p2.ToString()={0}", p2.ToString());
    p2.ResetPoint();
    Console.WriteLine("p2.ToString()={0}", p2.ToString());

    Console.ReadLine();
}
```

Here is the output:

```
***** Fun with Generic Structures *****

p.ToString()=[10, 10]
p.ToString()=[0, 0]

p2.ToString()=[5.4, 3.3]
p2.ToString()=[0, 0]
```

Source Code You can find the GenericPoint project under the Chapter 10 subdirectory.

Generic Base Classes

Generic classes can be the base class to other classes, which means they can define any number of virtual or abstract methods. However, the derived types must abide by a few rules to ensure that the nature of the generic abstraction flows through. First, if a non-generic class extends a generic class, the derived class must specify a type parameter:

```
// Assume you have created a custom
// generic list class.
public class MyList<T>
{
    private List<T> listOfData = new List<T>();
}

// Non-generic classes must specify the type
// parameter when deriving from a
// generic base class.
public class MyStringList : MyList<string>
{}
```

Second, if the generic base class defines generic virtual or abstract methods, the derived type must override the generic methods using the specified type parameter:

```
// A generic class with a virtual method.
public class MyList<T>
{
    private List<T> listOfData = new List<T>();
    public virtual void Insert(T data) { }
}

public class MyStringList : MyList<string>
{
    // Must substitute the type parameter used in the
    // parent class in derived methods.
```

```
    public override void Insert(string data) { }
}
```

Third, if the derived type is generic as well, the child class can (optionally) reuse the type placeholder in its definition. However, be aware that any constraints (see next section) placed on the base class must be honored by the derived type, as in this example:

```
// Note that we now have a default constructor constraint (see next section).
public class MyList<T> where T : new()
{
    private List<T> listOfData = new List<T>();

    public virtual void Insert(T data) { }

// Derived type must honor constraints.
public class MyReadOnlyList<T> : MyList<T> where T : new()
{
    public override void Insert(T data) { }
}
```

Again, in your day-to-day programming tasks, creating custom generic class hierarchies will most likely not be a common task. Nevertheless, doing so is possible (as long as you abide by the rules).

Constraining Type Parameters

As this chapter illustrates, any generic item has at least one type parameter that you need to specify at the time you interact with the generic type or member. This alone allows you to build some type safe code; however, the .NET platform allows you to use the `where` keyword to get extremely specific about what a given type parameter must look like.

Using this keyword, you can add a set of constraints to a given type parameter, which the C# compiler will check at compile time. Specifically, you can constrain a type parameter as described in Table 10-6.

Table 10-6. Possible Constraints for Generic Type Parameters

Generic Constraint	Meaning in Life
<code>where T : struct</code>	The type parameter <code><T></code> must have <code>System.ValueType</code> in its chain of inheritance; in other words, <code><T></code> must be a structure.
<code>where T : class</code>	The type parameter <code><T></code> must not have <code>System.ValueType</code> in its chain of inheritance (e.g., <code><T></code> must be a reference type).
<code>where T : new()</code>	The type parameter <code><T></code> must have a default constructor. This is helpful if your generic type must create an instance of the type parameter because you cannot assume you know the format of custom constructors. Note that this constraint must be listed last on a multiconstrained type.

Table 10-6. Possible Constraints for Generic Type Parameters (continued)

Generic Constraint	Meaning in Life
where T : NameOfClass	The type parameter <code><T></code> must be derived from the class specified by <code>NameOfClass</code> .
where T : NameOfInterface	The type parameter <code><T></code> must implement the interface specified by <code>NameOfInterface</code> . You can separate multiple interfaces as a comma-delimited list.

Unless you need to build some extremely type safe custom collections, you might never need to use the `where` keyword in your C# projects. Regardless, the following handful of (partial) code examples illustrate how to work with the `where` keyword.

Examples Using the where Keyword

Begin by assuming that you have created a custom generic class, and you want to ensure that the type parameter has a default constructor. This could be useful when the custom generic class needs to create instances of the `T` because the default constructor is the only constructor that is potentially common to all types. Also, constraining `T` in this way lets you get compile-time checking; if `T` is a reference type, then programmer remembered to redefine the default in the class definition (you might recall that the default constructor is removed in classes when you define your own):

```
// MyGenericClass derives from object, while
// contained items must have a default ctor.
public class MyGenericClass<T> where T : new()
{
    ...
}
```

Notice that the `where` clause specifies which type parameter is being constrained, followed by a colon operator. After the colon operator, you list each possible constraint (in this case, a default constructor). Here is another example:

```
// MyGenericClass derives from object, while
// contained items must be a class implementing IDrawable
// and must support a default ctor.
public class MyGenericClass<T> where T : class, IDrawable, new()
{
    ...
}
```

In this case, `T` has three requirements. It must be a reference type (not a structure), as marked with the `class` token. Second, `T` must implement the `IDrawable` interface. Third, it must also have a default constructor. Multiple constraints are listed in a comma-delimited list; however, you should be aware that the `new()` constraint must always be listed last! Thus, the following code will not compile:

```
// Error! new() constraint must be listed last!
public class MyGenericClass<T> where T : new(), class, IDrawable
{
    ...
}
```

If you ever create a custom generic collection class that specifies multiple type parameters, you can specify a unique set of constraints for each, using separate where clauses:

```
// <K> must extend SomeBaseClass and have a default ctor,
// while <T> must be a structure and implement the
// generic IComparable interface.
public class MyGenericClass<K, T> where K : SomeBaseClass, new()
    where T : struct, IComparable<T>
{
    ...
}
```

You will rarely encounter cases where you need to build a complete custom generic collection class; however, you can use the where keyword on generic methods, as well. For example, if you want to specify that your generic Swap<T>() method can only operate on structures, you would update the method like this:

```
// This method will swap any structure, but not classes.
static void Swap<T>(ref T a, ref T b) where T : struct
{
    ...
}
```

Note that if you were to constrain the Swap() method in this manner, you would no longer be able to swap string objects (as is shown in the sample code) because string is a reference type.

The Lack of Operator Constraints

I want to make one more comment on generic methods and constraints as this chapter draws to a close. When you create generic methods, it might come as a surprise to you that it causes a compiler error if you apply any C# operators (+, -, *, ==, etc.) on the type parameters. For example, imagine the usefulness of a class that can Add(), Subtract(), Multiply(), and Divide() generic types:

```
// Compiler error! Cannot apply
// operators to type parameters!
public class BasicMath<T>
{
    public T Add(T arg1, T arg2)
    { return arg1 + arg2; }
    public T Subtract(T arg1, T arg2)
    { return arg1 - arg2; }
    public T Multiply(T arg1, T arg2)
    { return arg1 * arg2; }
    public T Divide(T arg1, T arg2)
    { return arg1 / arg2; }
}
```

Unfortunately, the preceding `BasicMath` class will not compile. While this might seem like a major restriction, you need to remember that generics are generic. Of course, the numerical data can work just fine with the binary operators of C#. However, for the sake of argument, if `<T>` were a custom class or structure type, the compiler could assume the class supports the `+`, `-`, `*`, and `/` operators. Ideally, C# would allow a generic type to be constrained by supported operators, as in this example:

```
// Illustrative code only!
public class BasicMath<T> where T : operator +, operator -,
    operator *, operator /
{
    public T Add(T arg1, T arg2)
    { return arg1 + arg2; }
    public T Subtract(T arg1, T arg2)
    { return arg1 - arg2; }
    public T Multiply(T arg1, T arg2)
    { return arg1 * arg2; }
    public T Divide(T arg1, T arg2)
    { return arg1 / arg2; }
}
```

Alas, operator constraints are not supported under the current version of C#. However, it is possible (albeit it requires a bit more work) to achieve the desired effect by defining an interface that supports these operators (C# interfaces can define operators!) and then specify an interface constraint of the generic class. In any case, this wraps up this book's initial look at building custom generic types. In the next chapter, you will pick up the topic of generics once again in the course of examining the .NET delegate type.

Summary

This chapter began by examining the issues associated with the classic containers found within the `System.Collections` namespace. While these types remain supported for purposes of backward compatibility, new .NET applications will benefit from using the generic counterparts within the `System.Collections.Generic` namespace instead.

As you have seen, a generic item allows you to specify placeholders (type parameters) that you specify at the time of object creation (or invocation, in the case of generic methods). Essentially, generics provide a solution to the boxing and type-safety issues that plagued .NET 1.1 software development. Also, generic types largely remove the need to build custom collection types. While you will most often simply use the generic types provided in the .NET base class libraries, you will also be able to create your own generic types (and generic methods). When you do so, you have the option of specifying any number of constraints (using the `where` keyword) to increase the level of type safety and ensure that you perform operations on types of a *known quantity* that are guaranteed to exhibit certain basic capabilities.



Delegates, Events, and Lambdas

Up to this point in the text, most of the applications you developed added various bits of code to `Main()`, which, in some way or another, sent requests *to* a given object. However, many applications require that an object be able to communicate *back to* the entity that created it using a callback mechanism. While callback mechanisms can be used in any application, they are especially critical for graphical user interfaces in that controls (such as a button) need to invoke external methods under the correct circumstances (when the button is clicked, when the mouse enters the button surface, and so forth).

Under the .NET platform, the *delegate* type is the preferred means of defining and responding to callbacks within applications. Essentially, the .NET delegate type is a type-safe object that “points to” a method or a list of methods that can be invoked at a later time. Unlike a traditional C++ function pointer, however, .NET delegates are classes that have built-in support for multicasting and asynchronous method invocation.

In this chapter, you will learn how to create and manipulate delegate types, then you’ll investigate the C# event keyword, which streamlines the process of working with delegate types. Along the way, you will also examine several delegate- and event-centric language features of C#, including anonymous methods and method group conversions.

I wrap up this chapter by examining *lambda expressions*. Using the C# lambda operator (`=>`), you can specify a block of code statements (and the parameters to pass to those code statements) wherever a strongly typed delegate is required. As you will see, a lambda expression is little more than an anonymous method in disguise, and provides a simplified approach to working with delegates.

Understanding the .NET Delegate Type

Before formally defining .NET delegates, let’s gain a bit of perspective. Historically, the Windows API made frequent use of C-style function pointers to create entities termed *callback functions*, or simply *callbacks*. Using callbacks, programmers were able to configure one function to report back to (call back) another function in the application. With this approach, Windows developers were able to handle button-clicking, mouse-moving, menu-selecting, and general bidirectional communications between two entities in memory.

The problem with standard C-style callback functions is that they represent little more than a raw address in memory. Ideally, you should be able to configure callbacks to include additional type-safe information such as the number of (and types of) parameters and the return type (if any) of the method pointed to. Sadly, this is not the case in traditional callback functions and, as you may suspect, they can therefore be a frequent source of bugs, hard crashes, and other runtime disasters. Nevertheless, callbacks are useful entities.

In the .NET Framework, callbacks are still possible, and this functionality is accomplished in a much safer and more object-oriented manner using *delegates*. In essence, a delegate is a type-safe object that points to another method (or possibly a list of methods) in the application, which can be invoked at a later time. Specifically, a delegate maintains three important pieces of information:

- The *address* of the method on which it makes calls
 - The *parameters* (if any) of this method
 - The *return type* (if any) of this method
-

■ **Note** .NET delegates can point to either static or instance methods.

Once a delegate object has been created and given the necessary information, it may dynamically invoke the method(s) it points to at runtime. Every delegate in the .NET Framework (including your custom delegates) is automatically endowed with the ability to call its methods *synchronously* or *asynchronously*. This fact greatly simplifies programming tasks, given that you can call a method on a secondary thread of execution without manually creating and managing a Thread object.

■ **Note** We will examine the asynchronous behavior of delegate types during our investigation of the System.Threading namespace in Chapter 19.

Defining a Delegate Type in C#

When you want to create a delegate type in C#, you use the `delegate` keyword. The name of your delegate type can be whatever you desire. However, you must define the delegate to match the signature of the method(s) it will point to. For example, assume you wish to build a delegate type named `BinaryOp` that can point to any method that returns an integer and takes two integers as input parameters:

```
// This delegate can point to any method,
// taking two integers and returning an integer.
public delegate int BinaryOp(int x, int y);
```

When the C# compiler processes delegate types, it automatically generates a sealed class deriving from `System.MulticastDelegate`. This class (in conjunction with its base class, `System.Delegate`) provides the necessary infrastructure for the delegate to hold onto a list of methods to be invoked at a later time. For example, if you examine the `BinaryOp` delegate using `ildasm.exe`, you would find the class shown in Figure 11-1.

As you can see, the compiler-generated `BinaryOp` class defines three public methods. `Invoke()` is perhaps the key method, as it is used to invoke each method maintained by the delegate object in a *synchronous* manner, meaning the caller must wait for the call to complete before continuing on its way. Strangely enough, the synchronous `Invoke()` method need not be called explicitly from your C# code. As you will see in just a bit, `Invoke()` is called behind the scenes when you make use of the appropriate C# syntax.

`BeginInvoke()` and `EndInvoke()` provide the ability to call the current method *asynchronously* on a separate thread of execution. If you have a background in multithreading, you know that one of the most common reasons developers create secondary threads of execution is to invoke methods that require time to complete. Although the .NET base class libraries supply an entire namespace devoted to multithreaded programming (`System.Threading`), delegates provide this functionality out of the box.




Figure 11-1. The C# delegate keyword represents a sealed class deriving from `System.MulticastDelegate`

Now, how exactly does the compiler know how to define the `Invoke()`, `BeginInvoke()`, and `EndInvoke()` methods? To understand the process, here is the crux of the compiler-generated `BinaryOp` class type (***bold italic*** marks the items specified by the defined delegate type):

```
sealed class BinaryOp : System.MulticastDelegate
{
    public int Invoke(int x, int y);
    public IAsyncResult BeginInvoke(int x, int y,
        AsyncCallback cb, object state);
    public int EndInvoke(IAsyncResult result);
}
```

First, notice that the parameters and return type defined for the `Invoke()` method exactly match the definition of the `BinaryOp` delegate. The initial parameters to `BeginInvoke()` members (two integers in our case) are also based on the `BinaryOp` delegate; however, `BeginInvoke()` will always provide two final parameters (of type `AsyncCallback` and `object`) that are used to facilitate asynchronous method invocations. Finally, the return type of `EndInvoke()` is identical to the original delegate declaration and will always take as a sole parameter an object implementing the `IAsyncResult` interface.

Let's see another example. Assume you have defined a delegate type that can point to any method returning a string and receiving three `System.Boolean` input parameters:

```
public delegate string MyDelegate(bool a, bool b, bool c);
```

This time, the compiler-generated class breaks down as follows:

```
sealed class MyDelegate : System.MulticastDelegate
{
```

```

public string Invoke(bool a, bool b, bool c);
public IAsyncResult BeginInvoke(bool a, bool b, bool c,
    AsyncCallback cb, object state);
public string EndInvoke(IAsyncResult result);
}

```

Delegates can also “point to” methods that contain any number of out or ref parameters (as well as array parameters marked with the params keyword). For example, assume the following delegate type:

```
public delegate string MyOtherDelegate(out bool a, ref bool b, int c);
```

The signatures of the `Invoke()` and `BeginInvoke()` methods look as you would expect; however, check out the `EndInvoke()` method, which now includes the set of all out/ref arguments defined by the delegate type:

```

sealed class MyOtherDelegate : System.MulticastDelegate
{
    public string Invoke(out bool a, ref bool b, int c);
    public IAsyncResult BeginInvoke(out bool a, ref bool b, int c,
        AsyncCallback cb, object state);
    public string EndInvoke(out bool a, ref bool b, IAsyncResult result);
}

```

To summarize, a C# delegate type definition results in a sealed class with three compiler-generated methods whose parameter and return types are based on the delegate’s declaration. The following pseudo-code approximates the basic pattern:

```

// This is only pseudo-code!
public sealed class DelegateName : System.MulticastDelegate
{
    public delegateReturnValue Invoke(allDelegateInputRefAndOutParams);

    public IAsyncResult BeginInvoke(allDelegateInputRefAndOutParams,
        AsyncCallback cb, object state);

    public delegateReturnValue EndInvoke(allDelegateRefAndOutParams,
        IAsyncResult result);
}

```

The `System.MulticastDelegate` and `System.Delegate` Base Classes

So, when you build a type using the C# `delegate` keyword, you indirectly declare a class type that derives from `System.MulticastDelegate`. This class provides descendants with access to a list that contains the addresses of the methods maintained by the delegate object, as well as several additional methods (and a few overloaded operators) to interact with the invocation list. Here are some select members of `System.MulticastDelegate`:

```

public abstract class MulticastDelegate : Delegate
{
    // Returns the list of methods "pointed to."
}

```

```

public sealed override Delegate[] GetInvocationList();

// Overloaded operators.
public static bool operator ==(MulticastDelegate d1, MulticastDelegate d2);
public static bool operator !=(MulticastDelegate d1, MulticastDelegate d2);

// Used internally to manage the list of methods maintained by the delegate.
private IntPtr _invocationCount;
private object _invocationList;
}

```

`System.MulticastDelegate` obtains additional functionality from its parent class, `System.Delegate`. Here is a partial snapshot of the class definition:

```

public abstract class Delegate : ICloneable, ISerializable
{
    // Methods to interact with the list of functions.
    public static Delegate Combine(params Delegate[] delegates);
    public static Delegate Combine(Delegate a, Delegate b);
    public static Delegate Remove(Delegate source, Delegate value);
    public static Delegate RemoveAll(Delegate source, Delegate value);

    // Overloaded operators.
    public static bool operator ==(Delegate d1, Delegate d2);
    public static bool operator !=(Delegate d1, Delegate d2);

    // Properties that expose the delegate target.
    public MethodInfo Method { get; }
    public object Target { get; }
}

```

Now, understand that you can never directly derive from these base classes in your code (it is a compiler error to do so). Nevertheless, when you use the `delegate` keyword, you have indirectly created a class that “is-a” `MulticastDelegate`. Table 11-1 documents the core members common to all delegate types.

Table 11-1. Select Members of `System.MulticastDelegate/System.Delegate`

Member	Meaning in Life
Method	This property returns a <code>System.Reflection.MethodInfo</code> object that represents details of a static method maintained by the delegate.
Target	If the method to be called is defined at the object level (rather than a static method), <code>Target</code> returns an object that represents the method maintained by the delegate. If the value returned from <code>Target</code> equals null, the method to be called is a static member.
Combine()	This static method adds a method to the list maintained by the delegate. In C#, you trigger this method using the overloaded <code>+=</code> operator as a shorthand notation.

Table 11-1. Select Members of System.MulticastDelegate/System.Delegate (Continued)

Inherited Member	Meaning in Life
GetInvocationList()	This method returns an array of System.Delegate objects, each representing a particular method that may be invoked.
Remove() RemoveAll()	These static methods remove a method (or all methods) from the delegate's invocation list. In C#, the Remove() method can be called indirectly using the overloaded -= operator.

The Simplest Possible Delegate Example

To be sure, delegates can cause a great deal of confusion when encountered for the first time. Thus, to get the ball rolling, let's take a look at a very simple Console Application program (named SimpleDelegate) that makes use of the BinaryOp delegate type you've seen previously. Here is the complete code, with analysis to follow:

```
namespace SimpleDelegate
{
    // This delegate can point to any method,
    // taking two integers and returning an integer.
    public delegate int BinaryOp(int x, int y);

    // This class contains methods BinaryOp will
    // point to.
    public class SimpleMath
    {
        public static int Add(int x, int y)
        { return x + y; }
        public static int Subtract(int x, int y)
        { return x - y; }
    }

    class Program
    {
        static void Main(string[] args)
        {
            Console.WriteLine("***** Simple Delegate Example *****\n");

            // Create a BinaryOp delegate object that
            // "points to" SimpleMath.Add().
            BinaryOp b = new BinaryOp(SimpleMath.Add);

            // Invoke Add() method indirectly using delegate object.
            Console.WriteLine("10 + 10 is {0}", b(10, 10));
            Console.ReadLine();
        }
    }
}
```

Again, notice the format of the `BinaryOp` delegate type declaration; it specifies that `BinaryOp` delegate objects can point to any method taking two integers and returning an integer (the actual name of the method pointed to is irrelevant). Here, we have created a class named `SimpleMath`, which defines two static methods that (surprise, surprise) match the pattern defined by the `BinaryOp` delegate.

When you want to insert the target method to a given delegate object, simply pass in the name of the method to the delegate's constructor:

```
// Create a BinaryOp delegate object that
// "points to" SimpleMath.Add().
BinaryOp b = new BinaryOp(SimpleMath.Add);
```

At this point, you are able to invoke the member pointed to using a syntax that looks like a direct function invocation:

```
// Invoke() is really called here!
Console.WriteLine("10 + 10 is {0}", b(10, 10));
```

Under the hood, the runtime actually calls the compiler-generated `Invoke()` method on your `MulticastDelegate` derived class. You can verify this for yourself if you open your assembly in `ildasm.exe` and examine the CIL code within the `Main()` method:

```
.method private hidebysig static void Main(string[] args) cil managed
{
...
    callvirt instance int32 SimpleDelegate.BinaryOp::Invoke(int32, int32)
}
```

Although C# does not require you to explicitly call `Invoke()` within your code base, you are free to do so. Thus, the following code statement is also permissible:

```
Console.WriteLine("10 + 10 is {0}", b.Invoke(10, 10));
```

Recall that .NET delegates are *type safe*. Therefore, if you attempt to pass a delegate a method that does not match the pattern, you receive a compile-time error. To illustrate, assume the `SimpleMath` class now defines an additional method named `SquareNumber()`, which takes a single integer as input:

```
public class SimpleMath
{
...
    public static int SquareNumber(int a)
    { return a * a; }
}
```

Given that the `BinaryOp` delegate can *only* point to methods that take two integers and return an integer, the following code is illegal and will not compile:

```
// Compiler error! Method does not match delegate pattern!
BinaryOp b2 = new BinaryOp(SimpleMath.SquareNumber);
```

Investigating a Delegate Object

Let's spice up the current example by creating a static method (named `DisplayDelegateInfo()`) within the `Program` class. This method will print out the names of the method(s) maintained by a delegate object as well as the name of the class defining the method. To do this, we will iterate over the `System.Delegate` array returned by `GetInvocationList()`, invoking each object's `Target` and `Method` properties:

```
static void DisplayDelegateInfo(Delegate delObj)
{
    // Print the names of each member in the
    // delegate's invocation list.
    foreach (Delegate d in delObj.GetInvocationList())
    {
        Console.WriteLine("Method Name: {0}", d.Method);
        Console.WriteLine("Type Name: {0}", d.Target);
    }
}
```

Assuming you have updated your `Main()` method to actually call this new helper method, you would find the output shown below:

***** Simple Delegate Example *****

```
Method Name: Int32 Add(Int32, Int32)
Type Name:
10 + 10 is 20
```

Notice that the name of the type (`SimpleMath`) is currently *not* displayed when calling the `Target` property. The reason has to do with the fact that our `BinaryOp` delegate is pointing to a *static method* and therefore there is no object to reference! However, if we update the `Add()` and `Subtract()` methods to be nonstatic (simply by deleting the `static` keywords), we could create an instance of the `SimpleMath` class and specify the methods to invoke using the object reference:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Simple Delegate Example *****\n");

    // .NET delegates can also point to instance methods as well.
    SimpleMath m = new SimpleMath();
    BinaryOp b = new BinaryOp(m.Add);

    // Show information about this object.
    DisplayDelegateInfo(b);

    Console.WriteLine("10 + 10 is {0}", b(10, 10));
    Console.ReadLine();
}
```

In this case, we would find the output shown here.

***** Simple Delegate Example *****

Method Name: Int32 Add(Int32, Int32)
 Type Name: SimpleDelegate.SimpleMath
 10 + 10 is 20

Source Code The SimpleDelegate project is located under the Chapter 11 subdirectory.

Sending Object State Notifications using Delegates

Clearly, the previous SimpleDelegate example was intended to be purely illustrative in nature, given that there would be no compelling reason to define a delegate simply to add two numbers! To provide a more realistic use of delegate types, let's use delegates to define a Car class that has the ability to inform external entities about its current engine state. To do so, we will take the following steps:

- Define a new delegate type that will send notifications to the caller.
- Declare a member variable of this delegate in the Car class.
- Create a helper function on the Car that allows the caller to specify the method to call back to.
- Implement the Accelerate() method to invoke the delegate's invocation list under the correct circumstances.

To begin, create a new Console Application project named CarDelegate. Now, define a new Car class that looks initially like this:

```
public class Car
{
    // Internal state data.
    public int CurrentSpeed { get; set; }
    public int MaxSpeed { get; set; }
    public string PetName { get; set; }

    // Is the car alive or dead?
    private bool carIsDead;

    // Class constructors.
    public Car() { MaxSpeed = 100; }
    public Car(string name, int maxSp, int currSp)
    {
        CurrentSpeed = currSp;
        MaxSpeed = maxSp;
        PetName = name;
    }
}
```

Now, consider the following updates, which address the first three points:

```

public class Car
{
    ...
    // 1) Define a delegate type.
    public delegate void CarEngineHandler(string msgForCaller);

    // 2) Define a member variable of this delegate.
    private CarEngineHandler listOfHandlers;

    // 3) Add registration function for the caller.
    public void RegisterWithCarEngine(CarEngineHandler methodToCall)
    {
        listOfHandlers = methodToCall;
    }
}

```

Notice in this example that we define the delegate types directly within the scope of the `Car` class. As you explore the base class libraries, you will find it is quite common to define a delegate within the scope of the type it naturally works with. Our delegate type, `CarEngineHandler`, can point to any method taking a single `string` as input and `void` as a return value.

Next, note that we declare a private member variable of our delegate (named `listOfHandlers`), and a helper function (named `RegisterWithCarEngine()`) that allows the caller to assign a method to the delegate's invocation list.

Note Strictly speaking, we could have defined our delegate member variable as `public`, therefore avoiding the need to create additional registration methods. However, by defining the delegate member variable as `private`, we are enforcing encapsulation services and providing a more type-safe solution. You'll revisit the risk of `public` delegate member variables later in this chapter when you look at the C# event keyword.

At this point, we need to create the `Accelerate()` method. Recall, the point here is to allow a `Car` object to send engine-related messages to any subscribed listener. Here is the update:

```

public void Accelerate(int delta)
{
    // If this car is 'dead', send dead message.
    if (carIsDead)
    {
        if (listOfHandlers != null)
            listOfHandlers("Sorry, this car is dead...");
    }
    else
    {
        CurrentSpeed += delta;

        // Is this car 'almost dead'?
        if (10 == (MaxSpeed - CurrentSpeed))

```

```

    && listOfHandlers != null)
{
    listOfHandlers("Careful buddy! Gonna blow!");
}

if (CurrentSpeed >= MaxSpeed)
    carIsDead = true;
else
    Console.WriteLine("CurrentSpeed = {0}", CurrentSpeed);
}
}

```

Notice that before we invoke the methods maintained by the `listOfHandlers` member variable, we are checking it against a `null` value. The reason is that it will be the job of the caller to allocate these objects by calling the `RegisterWithCarEngine()` helper method. If the caller does not call this method and we attempt to invoke the delegate's invocation list, we will trigger a `NullReferenceException` and bomb at runtime—which would obviously be a bad thing! Now that we have the delegate infrastructure in place, observe the updates to the `Program` class:

```

class Program
{
    static void Main(string[] args)
    {
        Console.WriteLine("***** Delegates as event enablers *****\n");

        // First, make a Car object.
        Car c1 = new Car("SlugBug", 100, 10);

        // Now, tell the car which method to call
        // when it wants to send us messages.
        c1.RegisterWithCarEngine(new Car.CarEngineHandler(OnCarEngineEvent));

        // Speed up (this will trigger the events).
        Console.WriteLine("***** Speeding up *****");
        for (int i = 0; i < 6; i++)
            c1.Accelerate(20);
        Console.ReadLine();
    }

    // This is the target for incoming events.
    public static void OnCarEngineEvent(string msg)
    {
        Console.WriteLine("\n***** Message From Car Object *****");
        Console.WriteLine("=> {0}", msg);
        Console.WriteLine("*****\n");
    }
}

```

The `Main()` method begins by simply making a new `Car` object. Since we are interested in hearing about the engine events, our next step is to call our custom registration function, `RegisterWithCarEngine()`. Recall that this method expects to be passed an instance of the nested

`CarEngineHandler` delegate, and as with any delegate, we specify a “method to point to” as a constructor parameter.

The trick in this example is that the method in question is located back in the `Program` class! Again, notice that the `OnCarEngineEvent()` method is a dead-on match to the related delegate in that it takes a `string` as input and returns `void`. Consider the output of the current example:

***** Delegates as event enablers *****

***** Speeding up *****

`CurrentSpeed = 30`

`CurrentSpeed = 50`

`CurrentSpeed = 70`

***** Message From Car Object *****

=> Careful buddy! Gonna blow!

`CurrentSpeed = 90`

***** Message From Car Object *****

=> Sorry, this car is dead...

Enabling Multicasting

Recall that .NET delegates have the built-in ability to *multicast*. In other words, a delegate object can maintain a list of methods to call, rather than just a single method. When you wish to add multiple methods to a delegate object, you simply make use of the overloaded `+=` operator, rather than a direct assignment. To enable multicasting on the `Car` class, we could update the `RegisterWithCarEngine()` method like so:

```
public class Car
{
    // Now with multicasting support!
    // Note we are now using the += operator, not
    // the assignment operator (=).
    public void RegisterWithCarEngine(CarEngineHandler methodToCall)
    {
        listOfHandlers += methodToCall;
    }
    ...
}
```

With this simple change, the caller can now register multiple targets for the same callback notification. Here, our second handler prints the incoming message in uppercase, just for display purposes:

```
class Program
{
    static void Main(string[] args)
```

```

{
    Console.WriteLine("***** Delegates as event enablers *****\n");

    // First, make a Car object.
    Car c1 = new Car("SlugBug", 100, 10);

    // Register multiple targets for the notifications.
    c1.RegisterWithCarEngine(new Car.CarEngineHandler(OnCarEngineEvent));
    c1.RegisterWithCarEngine(new Car.CarEngineHandler(OnCarEngineEvent2));

    // Speed up (this will trigger the events).
    Console.WriteLine("***** Speeding up *****");
    for (int i = 0; i < 6; i++)
        c1.Accelerate(20);
    Console.ReadLine();
}

// We now have TWO methods that will be called by the Car
// when sending notifications.
public static void OnCarEngineEvent(string msg)
{
    Console.WriteLine("\n***** Message From Car Object *****");
    Console.WriteLine("=> {0}", msg);
    Console.WriteLine("*****\n");
}

public static void OnCarEngineEvent2(string msg)
{
    Console.WriteLine("=> {0}", msg.ToUpper());
}
}

```

In terms of CIL code, the `+=` operator resolves to a call to the `Delegate.Combine()` method (in fact, you could call `Delegate.Combine()` directly, but the `+=` operator offers a simpler alternative). Ponder the following CIL implementation of `RegisterWithCarEngine()`:

```

.method public hidebysig instance void RegisterWithCarEngine(
    class CarDelegate.Car/CarEngineHandler methodToCall) cil managed
{
    // Code size 25 (0x19)
    .maxstack 8
    IL_0000:  nop
    IL_0001:  ldarg.0
    IL_0002:  dup
    IL_0003:  ldfld class CarDelegate.Car/CarEngineHandler CarDelegate.Car::listOfHandlers
    IL_0008:  ldarg.1

    IL_0009:  call class [mscorlib]System.Delegate [mscorlib]
              System.Delegate::Combine(class [mscorlib]System.Delegate,
              class [mscorlib]System.Delegate)
}

```

```

IL_000e: castclass CarDelegate.Car/CarEngineHandler
IL_0013: stfld class CarDelegate.Car/CarEngineHandler CarDelegate.Car::listOfHandlers
IL_0018: ret
} // end of method Car::RegisterWithCarEngine

```

Removing Targets from a Delegate's Invocation List

The Delegate class also defines a static Remove() method that allows a caller to dynamically remove a method from a delegate object's invocation list. This makes it simple to allow the caller to "unsubscribe" from a given notification at runtime. While you could call Delegate.Remove() directly in code, C# developers can use the -= operator as a convenient shorthand notation.

Let's add a new method to the Car class that allows a caller to remove a method from the invocation list:

```

public class Car
{
...
    public void UnRegisterWithCarEngine(CarEngineHandler methodToCall)
    {
        listOfHandlers -= methodToCall;
    }
}

```

Again, the -= syntax is simply a shorthand notation for manually calling the static Delegate.Remove() method, as illustrated by the following CIL code for the UnRegisterWithCarEvent() method of the Car class:

```

.method public hidebysig instance void UnRegisterWithCarEngine(
    class CarDelegate.Car/CarEngineHandler methodToCall) cil managed
{
    // Code size 25 (0x19)
    .maxstack 8
    IL_0000: nop
    IL_0001: ldarg.0
    IL_0002: dup
    IL_0003: ldfld class CarDelegate.Car/CarEngineHandler CarDelegate.Car::listOfHandlers
    IL_0008: ldarg.1

    IL_0009: call class [mscorlib]System.Delegate [mscorlib]
        System.Delegate::Remove(class [mscorlib]System.Delegate,
        class [mscorlib]System.Delegate)

    IL_000e: castclass CarDelegate.Car/CarEngineHandler
    IL_0013: stfld class CarDelegate.Car/CarEngineHandler CarDelegate.Car::listOfHandlers
    IL_0018: ret
} // end of method Car::UnRegisterWithCarEngine

```

With the current updates to the Car class, we could stop receiving the engine notification on the second handler by updating Main() as follows:

```

static void Main(string[] args)
{

```

```

Console.WriteLine("***** Delegates as event enablers *****\n");

// First, make a Car object.
Car c1 = new Car("SlugBug", 100, 10);
c1.RegisterWithCarEngine(new Car.CarEngineHandler(OnCarEngineEvent));

// This time, hold onto the delegate object,
// so we can unregister later.
Car.CarEngineHandler handler2 = new Car.CarEngineHandler(OnCarEngineEvent2);
c1.RegisterWithCarEngine(handler2);

// Speed up (this will trigger the events).
Console.WriteLine("***** Speeding up *****");
for (int i = 0; i < 6; i++)
    c1.Accelerate(20);

// Unregister from the second handler.
c1.UnRegisterWithCarEngine(handler2);

// We won't see the 'uppercase' message anymore!
Console.WriteLine("***** Speeding up *****");
for (int i = 0; i < 6; i++)
    c1.Accelerate(20);

Console.ReadLine();
}

```

One difference in Main() is that this time we are creating a `Car.CarEngineHandler` object and storing it in a local variable so we can use this object to unregister with the notification later on. Thus, the second time we speed up the `Car` object, we no longer see the uppercase version of the incoming message data, as we have removed this target from the delegates invocation list.

■ Source Code The `CarDelegate` project is located under the Chapter 11 subdirectory.

Method Group Conversion Syntax

In the previous `CarDelegate` example, we explicitly created instances of the `Car.CarEngineHandler` delegate object in order to register and unregister with the engine notifications:

```

static void Main(string[] args)
{
    Console.WriteLine("***** Delegates as event enablers *****\n");

    Car c1 = new Car("SlugBug", 100, 10);
    c1.RegisterWithCarEngine(new Car.CarEngineHandler(OnCarEngineEvent));

    Car.CarEngineHandler handler2 =

```

```

    new Car.CarEngineHandler(OnCarEngineEvent2);
c1.RegisterWithCarEngine(handler2);
...
}

```

To be sure, if you need to call any of the inherited members of `MulticastDelegate` or `Delegate`, manually creating a delegate variable is the most straightforward way of doing so. However, in most cases, you don't really need to hang onto the delegate object. Rather, you typically only need to use the delegate object in order to pass in the method name as a constructor parameter.

As a simplification, C# provides a shortcut termed *method group conversion*. This feature allows you to supply a direct method name, rather than a delegate object, when calling methods that take delegates as arguments.

Note As you will see later in this chapter, you can also use method group conversion syntax to simplify how you register with a C# event.

To illustrate, create a new Console Application named `CarDelegateMethodGroupConversion` and insert the file containing the `Car` class you defined in the `CarDelegate` project. Now, consider the following `Program` class, which uses method group conversion to register and unregister from the engine notifications:

```

class Program
{
    static void Main(string[] args)
    {
        Console.WriteLine("***** Method Group Conversion *****\n");
        Car c1 = new Car();

        // Register the simple method name.
        c1.RegisterWithCarEngine(CallMeHere);

        Console.WriteLine("***** Speeding up *****");
        for (int i = 0; i < 6; i++)
            c1.Accelerate(20);

        // Unregister the simple method name.
        c1.UnRegisterWithCarEngine(CallMeHere);

        // No more notifications!
        for (int i = 0; i < 6; i++)
            c1.Accelerate(20);

        Console.ReadLine();
    }

    static void CallMeHere(string msg)
    {

```

```

        Console.WriteLine("=> Message from Car: {0}", msg);
    }
}

```

Notice that we are not directly allocating the associated delegate object, but rather simply specifying a method that matches the delegate's expected signature (a method returning void and taking a single string in this case). Understand that the C# compiler is still ensuring type safety. Thus, if the `CallMeHere()` method did not take a `string` and return `void`, we would be issued a compiler error.

Source Code The `CarDelegateMethodGroupConversion` project is located under the Chapter 11 subdirectory.

Understanding Delegate Covariance

As you may have noticed, each of the delegates created thus far point to methods returning simple numerical data types (or `void`). However, assume you have a new Console Application named `DelegateCovariance` that defines a delegate type that can point to methods returning a custom class type (be sure to include your `Car` class definition in this new project):

```
// Define a delegate type pointing to methods that return Car objects.
public delegate Car ObtainCarDelegate();
```

Of course, you would be able to define a target for the delegate as expected:

```

namespace DelegateCovariance
{
    class Program
    {
        // Define a delegate type pointing to methods that return Car object.
        public delegate Car ObtainCarDelegate();

        static void Main(string[] args)
        {
            Console.WriteLine("***** Delegate Covariance *****\n");

            ObtainCarDelegate targetA = new ObtainCarDelegate(GetBasicCar);
            Car c = targetA();
            Console.WriteLine("Obtained a {0}", c);
            Console.ReadLine();
        }

        public static Car GetBasicCar()
        {
            return new Car("Zippy", 100, 55);
        }
    }
}
```

Now, what if you were to derive a new class from the `Car` type named `SportsCar` and you wanted to create a delegate type that can point to methods returning this class type? Prior to .NET 2.0, you would be required to define an entirely new delegate to do so, given that delegates were so type-safe that they did not honor the basic laws of inheritance:

```
// Define a new delegate type pointing to
// methods that return a SportsCar object.
public delegate SportsCar ObtainSportsCarDelegate();
```

As we now have two delegate types, we must create an instance of each to obtain `Car` and `SportsCar` types:

```
class Program
{
    public delegate Car ObtainCarDelegate();
    public delegate SportsCar ObtainSportsCarDelegate();

    public static Car GetBasicCar()
    { return new Car(); }

    public static SportsCar GetSportsCar()
    { return new SportsCar(); }

    static void Main(string[] args)
    {
        Console.WriteLine("***** Delegate Covariance *****\n");

        ObtainCarDelegate targetA = new ObtainCarDelegate(GetBasicCar);
        Car c = targetA();
        Console.WriteLine("Obtained a {0}", c);

        ObtainSportsCarDelegate targetB =
            new ObtainSportsCarDelegate(GetSportsCar);
        SportsCar sc = targetB();
        Console.WriteLine("Obtained a {0}", sc);
        Console.ReadLine();
    }
}
```

Given the laws of classic inheritance, it would be ideal to build a single delegate type that can point to methods returning either `Car` or `SportsCar` objects (after all, a `SportsCar` “is-a” `Car`). *Covariance* (which also goes by the term *relaxed delegates*) allows for this very possibility. Simply put, covariance allows you to build a single delegate that can point to methods returning class types related by classical inheritance.

Note In a similar vein, *contravariance* allows you to create a single delegate that can point to numerous methods that receive objects related by classical inheritance. Consult the .NET Framework 4.0 SDK documentation for further details.

```

class Program
{
    // Define a single delegate type that can point to
    // methods that return a Car or SportsCar.
    public delegate Car ObtainVehicleDelegate();

    public static Car GetBasicCar()
    { return new Car(); }

    public static SportsCar GetSportsCar()
    { return new SportsCar(); }

    static void Main(string[] args)
    {
        Console.WriteLine("***** Delegate Covariance *****\n");
        ObtainVehicleDelegate targetA = new ObtainVehicleDelegate(GetBasicCar);
        Car c = targetA();
        Console.WriteLine("Obtained a {0}", c);

        // Covariance allows this target assignment.
        ObtainVehicleDelegate targetB = new ObtainVehicleDelegate(GetSportsCar);
        SportsCar sc = (SportsCar)targetB();
        Console.WriteLine("Obtained a {0}", sc);
        Console.ReadLine();
    }
}

```

Notice that the `ObtainVehicleDelegate` delegate type has been defined to point to methods returning a strongly typed `Car` type. Given covariance, however, we can point to methods returning derived types as well. To obtain access to the members of the derived type, simply perform an explicit cast.

■ Source Code The `DelegateCovariance` project is located under the Chapter 11 subdirectory.

Understanding Generic Delegates

Recall from the previous chapter that C# does allow you to define generic delegate types. For example, assume you wish to define a delegate type that can call any method returning `void` and receiving a single parameter. If the argument in question may differ, you could model this using a type parameter. To illustrate, consider the following code within a new Console Application named `GenericDelegate`:

```

namespace GenericDelegate
{
    // This generic delegate can call any method
    // returning void and taking a single type parameter.
    public delegate void MyGenericDelegate<T>(T arg);

```

```

class Program
{
    static void Main(string[] args)
    {
        Console.WriteLine("***** Generic Delegates *****\n");

        // Register targets.
        MyGenericDelegate<string> strTarget =
            new MyGenericDelegate<string>(StringTarget);
        strTarget("Some string data");

        MyGenericDelegate<int> intTarget =
            new MyGenericDelegate<int>(IntTarget);
        intTarget(9);
        Console.ReadLine();
    }

    static void StringTarget(string arg)
    {
        Console.WriteLine("arg in uppercase is: {0}", arg.ToUpper());
    }

    static void IntTarget(int arg)
    {
        Console.WriteLine("++arg is: {0}", ++arg);
    }
}

```

Notice that `MyGenericDelegate<T>` defines a single type parameter that represents the argument to pass to the delegate target. When creating an instance of this type, you are required to specify the value of the type parameter as well as the name of the method the delegate will invoke. Thus, if you specified a `string` type, you send a `string` value to the target method:

```

// Create an instance of MyGenericDelegate<T>
// with string as the type parameter.
MyGenericDelegate<string> strTarget =
    new MyGenericDelegate<string>(StringTarget);
strTarget("Some string data");

```

Given the format of the `strTarget` object, the `StringTarget()` method must now take a single `string` as a parameter:

```

static void StringTarget(string arg)
{
    Console.WriteLine("arg in uppercase is: {0}", arg.ToUpper());
}

```

Simulating Generic Delegates Without Generics

Generic delegates offer a more flexible way to specify the method to be invoked in a type-safe manner. Before the introduction of generics in .NET 2.0, you could achieve a similar end result using a `System.Object` parameter:

```
public delegate void MyDelegate(object arg);
```

Although this allows you to send any type of data to a delegate target, you do so without type safety and with possible boxing penalties. For instance, assume you have created two instances of `MyDelegate`, both of which point to the same method, `MyTarget`. Note the boxing/unboxing penalties as well as the inherent lack of type safety:

```
class Program
{
    static void Main(string[] args)
    {
        ...
        // Register target with "traditional" delegate syntax.
        MyDelegate d = new MyDelegate(MyTarget);
        d("More string data");

        // Method group conversion syntax.
        MyDelegate d2 = MyTarget;
        d2(9); // Boxing penalty.
        Console.ReadLine();
    }

    // Due to a lack of type safety, we must
    // determine the underlying type before casting.
    static void MyTarget(object arg)
    {
        if(arg is int)
        {
            int i = (int)arg; // Unboxing penalty.
            Console.WriteLine("++arg is: {0}", ++i);
        }

        if(arg is string)
        {
            string s = (string)arg;
            Console.WriteLine("arg in uppercase is: {0}", s.ToUpper());
        }
    }
}
```

When you send out a value type to the target site, the value is boxed and unboxed once it is received by the target method. As well, given that the incoming parameter could be anything at all, you must dynamically check the underlying type before casting. Using generic delegates, you can still obtain the desired flexibility without the issues.

■ **Source Code** The GenericDelegate project is located under the Chapter 11 directory.

That wraps up our first look at the .NET delegate type. We will look at some additional details of working with delegates at the conclusion of this chapter and again in Chapter 19 during our examination of multithreading. Now let's move on to the related topic of the C# event keyword.

Understanding C# Events

Delegates are fairly interesting constructs in that they enable objects in memory to engage in a two-way conversation. However, working with delegates in the raw can entail the creation of some boilerplate code (defining the delegate, declaring necessary member variables, and creating custom registration and unregistration methods to preserve encapsulation, etc.).

Moreover, when you use delegates in the raw as your application's callback mechanism, if you do not define a class's delegate member variables as private, the caller will have direct access to the delegate objects. In this case, the caller could reassign the variable to a new delegate object (effectively deleting the current list of functions to call) and, worse yet, the caller would be able to directly invoke the delegate's invocation list. To illustrate this problem, consider the following reworking (and simplification) of the previous CarDelegate example:

```
public class Car
{
    public delegate void CarEngineHandler(string msgForCaller);

    // Now a public member!
    public CarEngineHandler listOfHandlers;

    // Just fire out the Exploded notification.
    public void Accelerate(int delta)
    {
        if (listOfHandlers != null)
            listOfHandlers("Sorry, this car is dead...");
    }
}
```

Notice that we no longer have private delegate member variables encapsulated with custom registration methods. Because these members are indeed public, the caller can directly access the `listOfHandlers` member variable and reassign this type to new `CarEngineHandler` objects and invoke the delegate whenever it so chooses:

```
class Program
{
    static void Main(string[] args)
    {
        Console.WriteLine("***** Agh!  No Encapsulation! *****\n");
        // Make a Car.
        Car myCar = new Car();
```

```

// We have direct access to the delegate!
myCar.listOfHandlers = new Car.CarEngineHandler(CallWhenExploded);
myCar.Accelerate(10);

// We can now assign to a whole new object...
// confusing at best.
myCar.listOfHandlers = new Car.CarEngineHandler(CallHereToo);
myCar.Accelerate(10);

// The caller can also directly invoke the delegate!
myCar.listOfHandlers.Invoke("hee, hee, hee...");
Console.ReadLine();
}

static void CallWhenExploded(string msg)
{ Console.WriteLine(msg); }

static void CallHereToo(string msg)
{ Console.WriteLine(msg); }
}

```

Exposing public delegate members breaks encapsulation, which not only can lead to code that is hard to maintain (and debug), but could also open your application to possible security risks! Here is the output of the current example:

***** Agh! No Encapsulation! *****

Sorry, this car is dead...
 Sorry, this car is dead...
 hee, hee, hee...

Obviously, you would not want to give other applications the power to change what a delegate is pointing to or to invoke the members without your permission.

Source Code The PublicDelegateProblem project is located under the Chapter 11 subdirectory.

The C# event Keyword

As a shortcut, so you don't have to build custom methods to add or remove methods to a delegate's invocation list, C# provides the event keyword. When the compiler processes the event keyword, you are automatically provided with registration and unregistration methods as well as any necessary member variables for your delegate types. These delegate member variables are *always* declared private, and therefore they are not directly exposed from the object firing the event. To be sure, the event keyword is little more than syntactic sugar in that it simply saves you some typing time.

Defining an event is a two-step process. First, you need to define a delegate type that will hold the list of methods to be called when the event is fired. Next, you declare an event (using the C# event keyword) in terms of the related delegate type.

To illustrate the event keyword, create a new Console Application named CarEvents. In this iteration of the Car class, we will define two events named `AboutToBlow` and `Exploded`. These events are associated to a single delegate type named `CarEngineHandler`. Here are the initial updates to the Car class:

```
public class Car
{
    // This delegate works in conjunction with the
    // Car's events.
    public delegate void CarEngineHandler(string msg);

    // This car can send these events.
    public event CarEngineHandler Exploded;
    public event CarEngineHandler AboutToBlow;
    ...
}
```

Sending an event to the caller is as simple as specifying the event by name, along with any required parameters as defined by the associated delegate. To ensure that the caller has indeed registered with the event, you will want to check the event against a null value before invoking the delegate's method set. With these points in mind, here is the new iteration of the Car's `Accelerate()` method:

```
public void Accelerate(int delta)
{
    // If the car is dead, fire Exploded event.
    if (carIsDead)
    {
        if (Exploded != null)
            Exploded("Sorry, this car is dead...");
    }
    else
    {
        CurrentSpeed += delta;

        // Almost dead?
        if (10 == MaxSpeed - CurrentSpeed
            && AboutToBlow != null)
        {
            AboutToBlow("Careful buddy! Gonna blow!");
        }

        // Still OK!
        if (CurrentSpeed >= MaxSpeed)
            carIsDead = true;
        else
            Console.WriteLine("CurrentSpeed = {0}", CurrentSpeed);
    }
}
```

With this, you have configured the car to send two custom events without having to define custom registration functions or declare delegate member variables. You will see the usage of this new automobile in just a moment, but first, let's check the event architecture in a bit more detail.

Events under the Hood

A C# event actually expands into two hidden methods, one having an `add_` prefix, the other having a `remove_` prefix. Each prefix is followed by the name of the C# event. For example, the `Exploded` event results in two hidden methods named `add_Exploded()` and `remove_Exploded()`. If you were to check out the CIL instructions behind `add_AboutToBlow()`, you would find a call to `Delegate.Combine()` method. Consider the partial CIL code:

```
.method public hidebysig specialname instance void
add_AboutToBlow(class CarEvents.Car/CarEngineHandler 'value') cil managed
{
...
    call class [mscorlib]System.Delegate
        [mscorlib]System.Delegate::Combine(
            class [mscorlib]System.Delegate, class [mscorlib]System.Delegate)
...
}
```

As you would expect, `remove_AboutToBlow()` will call `Delegate.Remove()` on your behalf:

```
.method public hidebysig specialname instance void
remove_AboutToBlow(class CarEvents.Car/CarEngineHandler 'value')
    cil managed synchronized
{
...
    call class [mscorlib]System.Delegate
        [mscorlib]System.Delegate::Remove(
            class [mscorlib]System.Delegate, class [mscorlib]System.Delegate)
...
}
```

Finally, the CIL code representing the event itself makes use of the `.addon` and `.removeon` directives to map the names of the correct `add_XXX()` and `remove_XXX()` methods to invoke:

```
.event CarEvents.Car/EngineHandler AboutToBlow
{
    .addon void CarEvents.Car::add_AboutToBlow
        (class CarEvents.Car/CarEngineHandler)

    .removeon void CarEvents.Car::remove_AboutToBlow
        (class CarEvents.Car/CarEngineHandler)
}
```

Now that you understand how to build a class that can send C# events (and are aware that events are little more than a typing time-saver), the next big question is how to listen to the incoming events on the caller's side.

Listening to Incoming Events

C# events also simplify the act of registering the caller-side event handlers. Rather than having to specify custom helper methods, the caller simply makes use of the `+=` and `-=` operators directly (which triggers the correct `add_XXX()` or `remove_XXX()` method in the background). When you wish to register with an event, follow the pattern shown here:

```
// NameOfObject.NameOfEvent += new RelatedDelegate(functionToCall);
//
Car.EngineHandler d = new Car.CarEventHandler(CarExplodedEventHandler)
myCar.Exploded += d;
```

When you wish to detach from a source of events, use the `-=` operator, using the following pattern

```
// NameOfObject.NameOfEvent -= new RelatedDelegate(functionToCall);
//
myCar.Exploded -= d;
```

Given these very predictable patterns, here is the refactored `Main()` method, now using the C# event registration syntax:

```
class Program
{
    static void Main(string[] args)
    {
        Console.WriteLine("***** Fun with Events *****\n");
        Car c1 = new Car("SlugBug", 100, 10);

        // Register event handlers.
        c1.AboutToBlow += new Car.CarEngineHandler(CarIsAlmostDoomed);
        c1.AboutToBlow += new Car.CarEngineHandler(CarAboutToBlow);

        Car.CarEngineHandler d = new Car.CarEngineHandler(CarExploded);
        c1.Exploded += d;

        Console.WriteLine("***** Speeding up *****");
        for (int i = 0; i < 6; i++)
            c1.Accelerate(20);

        // Remove CarExploded method
        // from invocation list.
        c1.Exploded -= d;

        Console.WriteLine("\n***** Speeding up *****");
        for (int i = 0; i < 6; i++)
            c1.Accelerate(20);
        Console.ReadLine();
    }

    public static void CarAboutToBlow(string msg)
    { Console.WriteLine(msg); }

    public static void CarIsAlmostDoomed(string msg)
```

```

{ Console.WriteLine("=> Critical Message from Car: {0}", msg); }

public static void CarExploded(string msg)
{ Console.WriteLine(msg); }
}

```

To even further simplify event registration, you can use method group conversion. Consider the following iteration of Main():

```

static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Events *****\n");
    Car c1 = new Car("SlugBug", 100, 10);

    // Register event handlers.
    c1.AboutToBlow += CarIsAlmostDoomed;
    c1.AboutToBlow += CarAboutToBlow;
    c1.Exploded += CarExploded;

    Console.WriteLine("***** Speeding up *****");
    for (int i = 0; i < 6; i++)
        c1.Accelerate(20);

    c1.Exploded -= CarExploded;

    Console.WriteLine("\n***** Speeding up *****");
    for (int i = 0; i < 6; i++)
        c1.Accelerate(20);

    Console.ReadLine();
}

```

Simplifying Event Registration Using Visual Studio 2010

Visual Studio 2010 offers assistance with the process of registering event handlers. When you apply the `+=` syntax during event registration, you will find an IntelliSense window displayed, inviting you to hit the Tab key to autocomplete the associated delegate instance (see Figure 11-2)




Figure 11-2. Delegate selection IntelliSense

After you hit the Tab key, you are invited to enter the name of the event handler to be generated (or simply accept the default name) as shown in Figure 11-3.




Figure 11-3. Delegate target format IntelliSense

When you hit the Tab key again, you will be provided with stub code in the correct format of the delegate target (note that this method has been declared static due to the fact that the event was registered within the static Main() method):

```
static void newCar_AboutToBlow(string msg)
{
    // Add your code!
}
```

IntelliSense is available to all .NET events in the base class libraries. This IDE feature is a massive time-saver, given that it saves you from having to search the .NET help system to figure out both the correct delegate to use with a particular event and the format of the delegate target method.

Source Code The CarEvents project is located under the Chapter 11 subdirectory.

Creating Custom Event Arguments

Truth be told, there is one final enhancement we could make to the current iteration of the Car class that mirrors Microsoft's recommended event pattern. As you begin to explore the events sent by a given type in the base class libraries, you will find that the first parameter of the underlying delegate is a System.Object, while the second parameter is a descendent of System.EventArgs.

The System.Object argument represents a reference to the object that sent the event (such as the Car), while the second parameter represents information regarding the event at hand. The System.EventArgs base class represents an event that is not sending any custom information:

```
public class EventArgs
{
    public static readonly System.EventArgs Empty;
    public EventArgs();
}
```

For simple events, you can pass an instance of EventArgs directly. However, when you wish to pass along custom data, you should build a suitable class deriving from EventArgs. For our example, assume you have a class named CarEventArgs, which maintains a string representing the message sent to the receiver:

```
public class CarEventArgs : EventArgs
{
    public readonly string msg;
    public CarEventArgs(string message)
    {
        msg = message;
    }
}
```

With this, you would now update the CarEngineHandler delegate type definition as follows (the events would be unchanged):

```
public class Car
{
    public delegate void CarEngineHandler(object sender, CarEventArgs e);
    ...
}
```

Here, when firing the events from within the Accelerate() method, you would now need to supply a reference to the current Car (via the this keyword) and an instance of the CarEventArgs type. For example, consider the following partial update:

```
public void Accelerate(int delta)
{
    // If the car is dead, fire Exploded event.
    if (carIsDead)
    {
        if (Exploded != null)
            Exploded(this, new CarEventArgs("Sorry, this car is dead..."));
    }
    ...
}
```

On the caller's side, all you would need to do is update your event handlers to receive the incoming parameters and obtain the message via the read-only field. For example:

```
public static void CarAboutToBlow(object sender, CarEventArgs e)
{
    Console.WriteLine("{0} says: {1}", sender, e.msg);
}
```

If the receiver wishes to interact with the object that sent the event, you can explicitly cast the System.Object. From this reference, you can make use of any public member of the object that sent the event notification:

```
public static void CarAboutToBlow(object sender, CarEventArgs e)
{
    // Just to be safe, perform a
    // runtime check before casting.
    if (sender is Car)
```

```

{
    Car c = (Car)sender;
    Console.WriteLine("Critical Message from {0}: {1}", c.PetName, e.msg);
}

```

■ **Source Code** The PrimAndProperCarEvents project is located under the Chapter 11 subdirectory.

The Generic EventHandler<T> Delegate

Given that so many custom delegates take an object as the first parameter and an EventArgs descendant as the second, you could further streamline the previous example by using the generic EventHandler<T> type, where T is your custom EventArgs type. Consider the following update to the Car type (notice how we no longer need to define a custom delegate type at all):

```

public class Car
{
    public event EventHandler<CarEventArgs> Exploded;
    public event EventHandler<CarEventArgs> AboutToBlow;
}

...

```

The Main() method could then use EventHandler<CarEventArgs> anywhere we previously specified CarEventHandler (or, once again, use method group conversion):

```

static void Main(string[] args)
{
    Console.WriteLine("***** Prim and Proper Events *****\n");

    // Make a car as usual.
    Car c1 = new Car("SlugBug", 100, 10);

    // Register event handlers.
    c1.AboutToBlow += CarIsAlmostDoomed;
    c1.AboutToBlow += CarAboutToBlow;

    EventHandler<CarEventArgs> d = new EventHandler<CarEventArgs>(CarExploded);
    c1.Exploded += d;

}

```

Great! At this point, you have seen the core aspects of working with delegates and events in the C# language. While you could use this information for just about all of your callback needs, we will wrap up this chapter with a look at some final simplifications, specifically anonymous methods and lambda expressions.

■ **Source Code** The PrimAndProperCarEvents (Generic) project is located under the Chapter 11 subdirectory.

Understanding C# Anonymous Methods

As you have seen, when a caller wishes to listen to incoming events, it must define a custom method in a class (or structure) that matches the signature of the associated delegate, for example:

```
class Program
{
    static void Main(string[] args)
    {
        SomeType t = new SomeType();

        // Assume "SomeDelegate" can point to methods taking no
        // args and returning void.
        t.SomeEvent += new SomeDelegate(MyEventHandler);
    }

    // Typically only called by the SomeDelegate object.
    public static void MyEventHandler()
    {
        // Do something when event is fired.
    }
}
```

When you think about it, however, methods such as `MyEventHandler()` are seldom intended to be called by any part of the program other than the invoking delegate. As far as productivity is concerned, it is a bit of a bother (though in no way a showstopper) to manually define a separate method to be called by the delegate object.

To address this point, it is possible to associate an event directly to a block of code statements at the time of event registration. Formally, such code is termed an *anonymous method*. To illustrate the syntax, check out the following `Main()` method, which handles the events sent from the `Car` class using anonymous methods, rather than specifically named event handlers:

```
class Program
{
    static void Main(string[] args)
    {
        Console.WriteLine("***** Anonymous Methods *****\n");
        Car c1 = new Car("SlugBug", 100, 10);

        // Register event handlers as anonymous methods.
        c1.AboutToBlow += delegate
        {
            Console.WriteLine("Eek! Going too fast!");
        };

        c1.AboutToBlow += delegate(object sender, CarEventArgs e)
```

```

{
    Console.WriteLine("Message from Car: {0}", e.msg);
};

c1.Exploded += delegate(object sender, CarEventArgs e)
{
    Console.WriteLine("Fatal Message from Car: {0}", e.msg);
};

// This will eventually trigger the events.
for (int i = 0; i < 6; i++)
    c1.Accelerate(20);

Console.ReadLine();
}
}

```

Note The final curly bracket of an anonymous method must be terminated by a semicolon. If you fail to do so, you are issued a compilation error.

Again, notice that the `Program` type no longer defines specific static event handlers such as `CarAboutToBlow()` or `CarExploded()`. Rather, the unnamed (aka anonymous) methods are defined inline at the time the caller is handling the event using the `+=` syntax. The basic syntax of an anonymous method matches the following pseudo-code:

```

class Program
{
    static void Main(string[] args)
    {
        SomeType t = new SomeType();
        t.SomeEvent += delegate (optionallySpecifiedDelegateArgs)
        { /* statements */ };
    }
}

```

When handling the first `AboutToBlow` event within the previous `Main()` method, notice that you are not specifying the arguments passed from the delegate:

```

c1.AboutToBlow += delegate
{
    Console.WriteLine("Eek! Going too fast!");
};

```

Strictly speaking, you are not required to receive the incoming arguments sent by a specific event. However, if you wish to make use of the possible incoming arguments, you will need to specify the parameters prototyped by the delegate type (as shown in the second handling of the `AboutToBlow` and `Exploded` events). For example:

```
c1.AboutToBlow += delegate(object sender, CarEventArgs e)
```

```
{
    Console.WriteLine("Critical Message from Car: {0}", e.msg);
}
```

Accessing Local Variables

Anonymous methods are interesting in that they are able to access the local variables of the method that defines them. Formally speaking, such variables are termed *outer variables* of the anonymous method. A few important points about the interaction between an anonymous method scope and the scope of the defining method should be mentioned:

- An anonymous method cannot access ref or out parameters of the defining method
- An anonymous method cannot have a local variable with the same name as a local variable in the outer method
- An anonymous method can access instance variables (or static variables, as appropriate) in the outer class scope
- An anonymous method can declare local variables with the same name as outer class member variables (the local variables have a distinct scope and hide the outer class member variables)

Assume our `Main()` method defined a local integer named `aboutToBlowCounter`. Within the anonymous methods that handle the `AboutToBlow` event, we will increment this counter by 1 and print out the tally before `Main()` completes:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Anonymous Methods *****\n");
    int aboutToBlowCounter = 0;

    // Make a car as usual.
    Car c1 = new Car("SlugBug", 100, 10);

    // Register event handlers as anonymous methods.
    c1.AboutToBlow += delegate
    {
        aboutToBlowCounter++;
        Console.WriteLine("Eek! Going too fast!");
    };

    c1.AboutToBlow += (object sender, CarEventArgs e)
    {
        aboutToBlowCounter++;
        Console.WriteLine("Critical Message from Car: {0}", e.msg);
    };

    ...
    Console.WriteLine("AboutToBlow event was fired {0} times.",
        aboutToBlowCounter);
```

```
    Console.ReadLine();
}
```

Once you run this updated `Main()` method, you will find the final `Console.WriteLine()` reports the `AboutToBlow` event was fired twice.

Source Code The `AnonymousMethods` project is located under the Chapter 11 subdirectory.

Understanding Lambda Expressions

To conclude our look at the .NET event architecture, we will examine C# *lambda expressions*. As just explained, C# supports the ability to handle events “inline” by assigning a block of code statements directly to an event using anonymous methods, rather than building a stand-alone method to be called by the underlying delegate. Lambda expressions are nothing more than a very concise way to author anonymous methods and ultimately simplify how we work with the .NET delegate type.

To set the stage for our examination of lambda expressions, create a new Console Application named `SimpleLambdaExpressions`. To begin, consider the `FindAll()` method of the generic `List<T>` class. This method can be called when you need to extract out a subset of items from the collection, and is prototyped like so:

```
// Method of the System.Collections.Generic.List<T> class.
public List<T> FindAll(Predicate<T> match)
```

As you can see, this method returns a new `List<T>` that represents the subset of data. Also notice that the sole parameter to `FindAll()` is a generic delegate of type `System.Predicate<T>`. This delegate can point to any method returning a `bool`, and takes a single type parameter as the only input parameter:

```
// This delegate is used by FindAll() method
// to extract out the subset.
public delegate bool Predicate<T>(T obj);
```

When you call `FindAll()`, each item in the `List<T>` is passed to the method pointed to by the `Predicate<T>` object. The implementation of said method will perform some calculations to see if the incoming data matches the necessary criteria, and return true or false. If this method returns true, the item will be added to the new `List<T>` that represents the subset (got all that?)

Before we see how lambda expressions can simplify working with `FindAll()`, let’s work the problem out in longhand notation, using the delegate objects directly. Add a method (named `TraditionalDelegateSyntax()`) within your `Program` type that interacts with the `System.Predicate<T>` type to discover the even numbers in a `List<T>` of integers:

```
class Program
{
    static void Main(string[] args)
    {
        Console.WriteLine("***** Fun with Lambdas *****\n");
        TraditionalDelegateSyntax();
        Console.ReadLine();
    }
}
```

```

static void TraditionalDelegateSyntax()
{
    // Make a list of integers.
    List<int> list = new List<int>();
    list.AddRange(new int[] { 20, 1, 4, 8, 9, 44 });

    // Call FindAll() using traditional delegate syntax.
    Predicate<int> callback = new Predicate<int>(IsEvenNumber);
    List<int> evenNumbers = list.FindAll(callback);

    Console.WriteLine("Here are your even numbers:");
    foreach (int evenNumber in evenNumbers)
    {
        Console.Write("{0}\t", evenNumber);
    }
    Console.WriteLine();
}

// Target for the Predicate<> delegate.
static bool IsEvenNumber(int i)
{
    // Is it an even number?
    return (i % 2) == 0;
}

```

Here, we have a method (`IsEvenNumber()`) that is in charge of testing the incoming integer parameter to see whether it is even or odd via the C# modulo operator, `%`. If you execute your application, you will find the numbers 20, 4, 8, and 44 print out to the console.

While this traditional approach to working with delegates behaves as expected, the `IsEvenNumber()` method is invoked only in very limited circumstances—specifically when we call `FindAll()`, which leaves us with the baggage of a full method definition. If we were to instead use an anonymous method, our code would clean up considerably. Consider the following new method of the `Program` class:

```

static void AnonymousMethodSyntax()
{
    // Make a list of integers.
    List<int> list = new List<int>();
    list.AddRange(new int[] { 20, 1, 4, 8, 9, 44 });

    // Now, use an anonymous method.
    List<int> evenNumbers = list.FindAll(delegate(int i)
    { return (i % 2) == 0; });

    Console.WriteLine("Here are your even numbers:");
    foreach (int evenNumber in evenNumbers)
    {
        Console.Write("{0}\t", evenNumber);
    }
    Console.WriteLine();
}

```

In this case, rather than directly creating a `Predicate<T>` delegate type and then authoring a stand-alone method, we are able to inline a method anonymously. While this is a step in the right direction, we are still required to use the `delegate` keyword (or a strongly typed `Predicate<T>`), and we must ensure that the parameter list is a dead-on match. As well, as you may agree, the syntax used to define an anonymous method can be viewed as being a bit hard on the eyes, which is even more apparent here:

```
List<int> evenNumbers = list.FindAll(
    delegate(int i)
    {
        return (i % 2) == 0;
    }
);
```

Lambda expressions can be used to simplify the call to `FindAll()` even more. When you make use of lambda syntax, there is no trace of the underlying delegate object whatsoever. Consider the following new method to the `Program` class:

```
static void LambdaExpressionSyntax()
{
    // Make a list of integers.
    List<int> list = new List<int>();
    list.AddRange(new int[] { 20, 1, 4, 8, 9, 44 });

    // Now, use a C# lambda expression.
    List<int> evenNumbers = list.FindAll(i => (i % 2) == 0);

    Console.WriteLine("Here are your even numbers:");
    foreach (int evenNumber in evenNumbers)
    {
        Console.Write("{0}\t", evenNumber);
    }
    Console.WriteLine();
}
```

In this case, notice the rather strange statement of code passed into the `FindAll()` method, which is in fact a lambda expression. In this iteration of the example, there is no trace whatsoever of the `Predicate<T>` delegate (or the `delegate` keyword for that matter). All we have specified is the lambda expression:

```
i => (i % 2) == 0
```

Before I break this syntax down, first understand that lambda expressions can be used anywhere you would have used an anonymous method or a strongly typed delegate (typically with far fewer keystrokes). Under the hood, the C# compiler translates the expression into a standard anonymous method making use of the `Predicate<T>` delegate type (which can be verified using `ildasm.exe` or `reflector.exe`). Specifically, the following code statement:

```
// This lambda expression...
List<int> evenNumbers = list.FindAll(i => (i % 2) == 0);
```

is compiled into the following approximate C# code:

```
// ...becomes this anonymous method.
List<int> evenNumbers = list.FindAll(delegate (int i)
```

```
{
    return (i % 2) == 0;
});
```

Dissecting a Lambda Expression

A lambda expression is written by first defining a parameter list, followed by the `=>` token (C#'s token for the lambda operator found in the *lambda calculus*), followed by a set of statements (or a single statement) that will process these arguments. From a very high level, a lambda expression can be understood as follows:

```
ArgumentsToProcess => StatementsToProcessThem
```

Within our `LambdaExpressionSyntax()` method, things break down like so:

```
// "i" is our parameter list.
// "(i % 2) == 0" is our statement set to process "i".
List<int> evenNumbers = list.FindAll(i => (i % 2) == 0);
```

The parameters of a lambda expression can be explicitly or implicitly typed. Currently, the underlying data type representing the `i` parameter (an integer) is determined implicitly. The compiler is able to figure out that `i` is an integer based on the context of the overall lambda expression and the underlying delegate. However, it is also possible to explicitly define the type of each parameter in the expression, by wrapping the data type and variable name in a pair of parentheses as follows:

```
// Now, explicitly state what the parameter type.
List<int> evenNumbers = list.FindAll((int i) => (i % 2) == 0);
```

As you have seen, if a lambda expression has a single, implicitly typed parameter, the parentheses may be omitted from the parameter list. If you wish to be consistent regarding your use of lambda parameters, you can *always* wrap the parameter list within parentheses, leaving us with this expression:

```
List<int> evenNumbers = list.FindAll((i) => (i % 2) == 0);
```

Finally, notice that currently our expression has not been wrapped in parentheses (we have of course wrapped the modulo statement to ensure it is executed first before the test for equality). Lambda expressions do allow for the statement to be wrapped as follows:

```
// Now, wrap the expression as well.
List<int> evenNumbers = list.FindAll((i) => ((i % 2) == 0));
```

Now that you have seen the various ways to build a lambda expression, how can we read this lambda statement in human-friendly terms? Leaving the raw mathematics behind, the following explanation fits the bill:

```
// My list of parameters (in this case a single integer named i)
// will be processed by the expression (i % 2) == 0.
List<int> evenNumbers = list.FindAll((i) => ((i % 2) == 0));
```

Processing Arguments Within Multiple Statements

Our first lambda expression was a single statement that ultimately evaluated to a Boolean. However, as you know, many delegate targets must perform a number of code statements. For this reason, C# allows

you to build lambda expressions using multiple statement blocks. When your expression must process the parameters using multiple lines of code, you can do so by denoting a scope for these statements using the expected curly brackets. Consider the following example update to our `LambdaExpressionSyntax()` method:

```
static void LambdaExpressionSyntax()
{
    // Make a list of integers.
    List<int> list = new List<int>();
    list.AddRange(new int[] { 20, 1, 4, 8, 9, 44 });

    // Now process each argument within a group of
    // code statements.
    List<int> evenNumbers = list.FindAll((i) =>
    {
        Console.WriteLine("value of i is currently: {0}", i);
        bool isEven = ((i % 2) == 0);
        return isEven;
    });

    Console.WriteLine("Here are your even numbers:");
    foreach (int evenNumber in evenNumbers)
    {
        Console.Write("{0}\t", evenNumber);
    }
    Console.WriteLine();
}
```

In this case, our parameter list (again, a single integer named `i`) is being processed by a set of code statements. Beyond the calls to `Console.WriteLine()`, our modulo statement has been broken into two code statements for increased readability. Assuming each of the methods we've looked at in this section are called from within `Main()`:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Lambdas *****\n");
    TraditionalDelegateSyntax();
    AnonymousMethodSyntax();
    Console.WriteLine();
    LambdaExpressionSyntax();
    Console.ReadLine();
}
```

we will find the following output:

```
***** Fun with Lambdas *****
```

```
Here are your even numbers:
```

```
20      4      8      44
```

```
Here are your even numbers:
```

```
20      4      8      44
```

```

value of i is currently: 20
value of i is currently: 1
value of i is currently: 4
value of i is currently: 8
value of i is currently: 9
value of i is currently: 44
Here are your even numbers:
20      4      8      44

```

Source Code The SimpleLambdaExpressions project can be found under the Chapter 11 subdirectory.

Lambda Expressions with Multiple (or Zero) Parameters

The lambda expressions you have seen here processed a single parameter. This is not a requirement, however, as a lambda expression may process multiple arguments—or none. To illustrate the first scenario, create a Console Application named LambdaExpressionsMultipleParams. Next, assume the following incarnation of the `SimpleMath` type:

```

public class SimpleMath
{
    public delegate void MathMessage(string msg, int result);
    private MathMessage mmDelegate;

    public void SetMathHandler(MathMessage target)
    {mmDelegate = target; }

    public void Add(int x, int y)
    {
        if (mmDelegate != null)
            mmDelegate.Invoke("Adding has completed!", x + y);
    }
}

```

Notice that the `MathMessage` delegate is expecting two parameters. To represent them as a lambda expression, our `Main()` method might be written as follows:

```

static void Main(string[] args)
{
    // Register w/ delegate as a lambda expression.
    SimpleMath m = new SimpleMath();
    m.SetMathHandler((msg, result) =>
        {Console.WriteLine("Message: {0}, Result: {1}", msg, result);});

    // This will execute the lambda expression.
    m.Add(10, 10);
    Console.ReadLine();
}

```

Here, we are leveraging type inference, as our two parameters have not been strongly typed for simplicity. However, we could call `SetMathHandler()` as follows:

```
m.SetMathHandler((string msg, int result) =>
    {Console.WriteLine("Message: {0}, Result: {1}", msg, result);});
```

Finally, if you are using a lambda expression to interact with a delegate taking no parameters at all, you may do so by supplying a pair of empty parentheses as the parameter. Thus, assuming you have defined the following delegate type:

```
public delegate string VerySimpleDelegate();
```

you could handle the result of the invocation as follows:

```
// Prints "Enjoy your string!" to the console.
VerySimpleDelegate d = new VerySimpleDelegate( () => {return "Enjoy your string!";} );
Console.WriteLine(d.Invoke());
```

Source Code The `LambdaExpressionsMultipleParams` project can be found under the Chapter 11 subdirectory.

Retrofitting the CarEvents Example Using Lambda Expressions

Given that the whole reason for lambda expressions is to provide a clean, concise manner to define an anonymous method (and therefore indirectly a manner to simplify working with delegates), let's retrofit the `PrimAndProperCarEvents` project we created earlier in this chapter. Here is a simplified version of that project's `Program` class, which makes use of lambda expression syntax (rather than the raw delegates) to hook into each event sent from the `Car` object:

```
class Program
{
    Console.WriteLine("***** More Fun with Lambdas *****\n");

    // Make a car as usual.
    Car c1 = new Car("SlugBug", 100, 10);

    // Hook into events with lambdas!
    c1.AboutToBlow += (sender, e) => { Console.WriteLine(e.msg); };
    c1.Exploded += (sender, e) => { Console.WriteLine(e.msg); };

    // Speed up (this will generate the events).
    Console.WriteLine("\n***** Speeding up *****");
    for (int i = 0; i < 6; i++)
        c1.Accelerate(20);

    Console.ReadLine();
}
```

Hopefully, at this point you can see the overall role of lambda expressions and understand how they provide a “functional manner” to work with anonymous methods and delegate types. Although the new

lambda operator (`=>`) might take a bit to get used to, always remember a lambda expression can be broken down to the following simple equation:

```
ArgumentsToProcess => StatementsToProcessThem
```

It is worth pointing out that the LINQ programming model also makes substantial use of lambda expressions to help simplify your coding efforts. You will examine LINQ beginning in Chapter 13.

■ **Source Code** The CarDelegateWithLambdas project can be found under the Chapter 11 subdirectory.

Summary

In this chapter, you have examined a number of ways in which multiple objects can partake in a bidirectional conversation. First, you looked at the C# delegate keyword, which is used to indirectly construct a class derived from `System.MulticastDelegate`. As you saw, a delegate object maintains a list of methods to call when told to do so. These invocations may be made synchronously (using the `Invoke()` method) or asynchronously (via the `BeginInvoke()` and `EndInvoke()` methods). Again, the asynchronous nature of .NET delegate types will be examined in Chapter 19.

You then examined the C# event keyword, which, when used in conjunction with a delegate type, can simplify the process of sending your event notifications to waiting callers. As shown via the resulting CIL, the .NET event model maps to hidden calls on the `System.Delegate`/`System.MulticastDelegate` types. In this light, the C# event keyword is purely optional in that it simply saves you some typing time.

This chapter also explored a C# language feature termed *anonymous methods*. Using this syntactic construct, you are able to directly associate a block of code statements to a given event. As you have seen, anonymous methods are free to ignore the parameters sent by the event and have access to the “outer variables” of the defining method. You also examined a simplified way to register events using *method group conversion*.

Finally, we wrapped things up by looking at the C# *lambda operator*, `=>`. As shown, this syntax is a great shorthand notation for authoring anonymous methods, where a stack of arguments can be passed into a group of statements for processing.



Advanced C# Language Features

In this chapter, you'll deepen your understanding of the C# programming language by examining a number of more advanced syntactic constructs. To begin, you'll learn how to implement and use an *indexer method*. This C# mechanism enables you to build custom types that provide access to internal subitems using an array-like syntax. Once you learn how to build an indexer method, you'll see how to overload various operators (+, -, <, >, and so forth), and how to create custom explicit and implicit conversion routines for your types (and you'll learn why you may want to do this).

Next, you'll examine three topics that are particularly useful when working with LINQ-centric APIs (though you can use them outside of the context of LINQ)—extension methods, partial methods, and anonymous types.

To wrap things up, you'll learn how to create an “unsafe” code context in order to directly manipulate unmanaged pointers. While it is certainly true that using pointers in C# applications is a fairly infrequent activity, understanding how to do so can be helpful in some circumstances that involve complex interoperability scenarios.

Understanding Indexer Methods

As a programmer, you are certainly familiar with the process of accessing individual items contained within a simple array using the index operator ([]), for example:

```
static void Main(string[] args)
{
    // Loop over incoming command line arguments
    // using index operator.
    for(int i = 0; i < args.Length; i++)
        Console.WriteLine("Args: {0}", args[i]);

    // Declare an array of local integers.
    int[] myInts = { 10, 9, 100, 432, 9874 };

    // Use the index operator to access each element.
    for(int j = 0; j < myInts.Length; j++)
        Console.WriteLine("Index {0} = {1} ", j, myInts[j]);
    Console.ReadLine();
}
```

This code is by no means a major newsflash. However, the C# language provides the capability to design custom classes and structures that may be indexed just like a standard array, by defining an *indexer method*. This particular feature is most useful when you are creating custom collection classes (generic or nongeneric).

Before examining how to implement a custom indexer, let's begin by seeing one in action. Assume you have added support for an indexer method to the custom `PeopleCollection` type developed in Chapter 10 (specifically, the `CustomNonGenericCollection` project). Observe the following usage within a new Console Application named `SimpleIndexer`:

```
// Indexers allow you to access items in an array-like fashion.
class Program
{
    static void Main(string[] args)
    {
        Console.WriteLine("***** Fun with Indexers *****\n");

        PeopleCollection myPeople = new PeopleCollection();

        // Add objects with indexer syntax.
        myPeople[0] = new Person("Homer", "Simpson", 40);
        myPeople[1] = new Person("Marge", "Simpson", 38);
        myPeople[2] = new Person("Lisa", "Simpson", 9);
        myPeople[3] = new Person("Bart", "Simpson", 7);
        myPeople[4] = new Person("Maggie", "Simpson", 2);

        // Now obtain and display each item using indexer.
        for (int i = 0; i < myPeople.Count; i++)
        {
            Console.WriteLine("Person number: {0}", i);
            Console.WriteLine("Name: {0} {1}",
                myPeople[i].FirstName, myPeople[i].LastName);
            Console.WriteLine("Age: {0}", myPeople[i].Age);
            Console.WriteLine();
        }
    }
}
```

As you can see, indexers behave much like a custom collection supporting the `IEnumerator` and `IEnumerable` interfaces (or their generic counterparts) in that they provide access to a container's subitems. The major difference, of course, is that rather than accessing the contents using the `foreach` construct, you are able to manipulate the internal collection of sub-objects just like a standard array.

Now for the big question: How do you configure the `PeopleCollection` class (or any custom class or structure) to support this functionality? An indexer is represented as a slightly modified C# property definition. In its simplest form, an indexer is created using the `this[]` syntax. Here is the required update for the `PeopleCollection` class from Chapter 10:

```
// Add the indexer to the existing class definition.
public class PeopleCollection : IEnumerable
{
    private ArrayList arPeople = new ArrayList();

    // Custom indexer for this class.
```

```

public Person this[int index]
{
    get { return (Person)arPeople[index]; }
    set { arPeople.Insert(index, value); }
}
...
}

```

Apart from using the `this` keyword, the indexer looks just like any other C# property declaration. For example, the role of the `get` scope is to return the correct object to the caller. Here, we are doing so by delegating the request to the indexer of the `ArrayList` object! The `set` scope is in charge this example, this is achieved by calling the `Insert()` method of the `ArrayList`.

As you can see, indexers are yet another form of syntactic sugar, given that this functionality can also be achieved using “normal” public methods such as `AddPerson()` or `GetPerson()`. Nevertheless, when you support indexer methods on your custom collection types, they integrate well into the fabric of the .NET base class libraries.

While creating indexer methods is quite commonplace when you are building custom collections, do remember that generic types give you this very functionality out of the box. Consider the following method, which makes use of a generic `List<T>` of `Person` objects. Note that you can simply use the indexer of `List<T>` directly, for example:

```

static void UseGenericListOfPeople()
{
    List<Person> myPeople = new List<Person>();
    myPeople.Add(new Person("Lisa", "Simpson", 9));
    myPeople.Add(new Person("Bart", "Simpson", 7));

    // Change first person with indexer.
    myPeople[0] = new Person("Maggie", "Simpson", 2);

    // Now obtain and display each item using indexer.
    for (int i = 0; i < myPeople.Count; i++)
    {
        Console.WriteLine("Person number: {0}", i);
        Console.WriteLine("Name: {0} {1}", myPeople[i].FirstName,
            myPeople[i].LastName);
        Console.WriteLine("Age: {0}", myPeople[i].Age);
        Console.WriteLine();
    }
}

```

Source Code The `SimpleIndexer` project is located under the Chapter 12 subdirectory.

Indexing Data Using String Values

The current `PeopleCollection` class defined an indexer that allowed the caller to identify subitems using a numerical value. Understand, however, that this is not a requirement of an indexer method. Suppose

you'd prefer to contain the Person objects using a `System.Collections.Generic.Dictionary< TKey, TValue >` rather than an `ArrayList`. Given that `ListDictionary` types allow access to the contained types using a string token (such as a person's first name), you could define an indexer as follows:

```
public class PeopleCollection : IEnumerable
{
    private Dictionary<string, Person> listPeople =
        new Dictionary<string, Person>();

    // This indexer returns a person based on a string index.
    public Person this[string name]
    {
        get { return (Person)listPeople[name]; }
        set { listPeople[name] = value; }
    }

    public void ClearPeople()
    { listPeople.Clear(); }

    public int Count
    { get { return listPeople.Count; } }

    IEnumerator IEnumerable.GetEnumerator()
    { return listPeople.GetEnumerator(); }
}
```

The caller would now be able to interact with the contained Person objects as shown here:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Indexers *****\n");

    PeopleCollection myPeople = new PeopleCollection();

    myPeople["Homer"] = new Person("Homer", "Simpson", 40);
    myPeople["Marge"] = new Person("Marge", "Simpson", 38);

    // Get "Homer" and print data.
    Person homer = myPeople["Homer"];
    Console.WriteLine(homer.ToString());

    Console.ReadLine();
}
```

Again, if you were to use the generic `Dictionary< TKey, TValue >` type directly, you'd gain the indexer method functionality out of the box, without building a custom, non-generic class supporting a string indexer.

■ Source Code The `StringIndexer` project is located under the Chapter 12 subdirectory.

Overloading Indexer Methods

Understand that indexer methods may be overloaded on a single class or structure. Thus, if it makes sense to allow the caller to access subitems using a numerical index *or* a string value, you might define multiple indexers for a single type. By way of example, if you have ever programmed with ADO.NET (.NET's native database-access API), you may recall that the `DataSet` type supports a property named `Tables`, which returns to you a strongly typed `DataTableCollection` type. As it turns out, `DataTableCollection` defines three indexers to get and set `DataTable` objects—one by ordinal position, and the others by a friendly string moniker and optional containing namespace:

```
public sealed class DataTableCollection : InternalDataCollectionBase
{
    ...
    // Overloaded indexers!
    public DataTable this[string name] { get; }
    public DataTable this[string name, string tableNamespace] { get; }
    public DataTable this[int index] { get; }
}
```

Note that a number of types in the base class libraries support indexer methods. So be aware, even if your current project does not require you to build custom indexers for your classes and structures, that many types already support this syntax.

Indexers with Multiple Dimensions

You can also create an indexer method that takes multiple parameters. Assume you have a custom collection that stores subitems in a 2D array. If this is the case, you may define an indexer method as follows:

```
public class SomeContainer
{
    private int[,] my2DIntArray = new int[10, 10];

    public int this[int row, int column]
    { /* get or set value from 2D array */ }
}
```

Again, unless you are building a highly stylized custom collection class, you won't have much need to build a multi-dimensional indexer. Still, once again ADO.NET showcases how useful this construct can be. The ADO.NET `DataTable` is essentially a collection of rows and columns, much like a piece of graph paper or the general structure of a Microsoft Excel spreadsheet.

While `DataTable` objects are typically populated on your behalf using a related "data adapter," the following code illustrates how to manually create an in-memory `DataTable` containing three columns (for the first name, last name, and age of each record). Notice how once we have added a single row to the `DataTable`, we use a multidimensional indexer to drill into each column of the first (and only) row. (If you are following along, you'll need to import the `System.Data` namespace into your code file.)

```
static void MultiIndexerWithDataTable()
{
    // Make a simple DataTable with 3 columns.
    DataTable myTable = new DataTable();
```

```

myTable.Columns.Add(new DataColumn("FirstName"));
myTable.Columns.Add(new DataColumn("LastName"));
myTable.Columns.Add(new DataColumn("Age"));

// Now add a row to the table.
myTable.Rows.Add("Mel", "Appleby", 60);

// Use multi-dimension indexer to get details of first row.
Console.WriteLine("First Name: {0}", myTable.Rows[0][0]);
Console.WriteLine("Last Name: {0}", myTable.Rows[0][1]);
Console.WriteLine("Age : {0}", myTable.Rows[0][2]);
}

```

Do be aware that we'll take a rather deep dive into ADO.NET beginning with Chapter 21, so if some of the previous code seems unfamiliar, fear not. The main point of this example is that indexer methods can support multiple dimensions, and if used correctly, can simplify the way you interact with contained subobjects in custom collections.

Indexer Definitions on Interface Types

Indexers can be defined on a given .NET interface type to allow supporting types to provide a custom implementation. Here is a simple example of an interface that defines a protocol for obtaining string objects using a numerical indexer:

```

public interface IStringContainer
{
    // This interface defines an indexer that returns
    // strings based on a numerical index.
    string this[int index] { get; set; }
}

```

With this interface definition, any class or structure that implements this interface must now support a read/write indexer that manipulates subitems using a numerical value.

That wraps up the first major topic of this chapter. While understanding the syntax of C# indexers is important, as explained in Chapter 10, typically the only time a programmer needs to build a custom generic collection class is to add *constraints* to the type parameters. If you happen to build such a class, adding a custom indexer will make your collection class look and feel like the standard collection classes in the .NET base class libraries.

Now let's examine a language feature that lets you build custom classes or structures that respond uniquely to the intrinsic operators of C#. Allow me to introduce *operator overloading*.

Understanding Operator Overloading

C#, like any programming language, has a canned set of tokens that are used to perform basic operations on intrinsic types. For example, you know that the + operator can be applied to two integers in order to yield a larger integer:

```

// The + operator with ints.
int a = 100;

```

```
int b = 240;
int c = a + b; // c is now 340
```

Once again, this is no major newsflash, but have you ever stopped and noticed how the same + operator can be applied to most intrinsic C# data types? For example, consider this code:

```
// + operator with strings.
string s1 = "Hello";
string s2 = " world!";
string s3 = s1 + s2; // s3 is now "Hello world!"
```

In essence, the + operator functions in specific ways based on the supplied data types (strings or integers in this case). When the + operator is applied to numerical types, the result is the summation of the operands. However, when the + operator is applied to string types, the result is string concatenation.

The C# language gives you the capability to build custom classes and structures that also respond uniquely to the same set of basic tokens (such as the + operator). Be aware that you cannot overload every intrinsic C# operator. Table 12-1 outlines the “overloadability” of the core operators.

Table 12-1. Overloadability of C# Operators

C# Operator	Overloadability
+, -, !, ~, ++, --, true, false	These unary operators can be overloaded.
+, -, *, /, %, &, , ^, <<, >>	These binary operators can be overloaded.
==, !=, <, >, <=, >=	These comparison operators can be overloaded. C# demands that “like” operators (i.e., < and >, <= and >=, == and !=) are overloaded together.
[]	The [] operator cannot be overloaded. As you saw earlier in this chapter, however, the indexer construct provides the same functionality.
()	The () operator cannot be overloaded. As you will see later in this chapter, however, custom conversion methods provide the same functionality.
+=, -=, *=, /=, %=, &=, =, ^=, <<=, >>=	Shorthand assignment operators cannot be overloaded; however, you receive them as a freebie when you overload the related binary operator.

Overloading Binary Operators

To illustrate the process of overloading binary operators, assume the following simple Point class is defined in a new Console Application named OverloadedOps:

```
// Just a simple, everyday C# class.
public class Point
{
    public int X {get; set;}
    public int Y {get; set;}

    public Point(int xPos, int yPos)
    {
        X = xPos;
        Y = yPos;
    }

    public override string ToString()
    {
        return string.Format("[{0}, {1}]", this.X, this.Y);
    }
}
```

Now, logically speaking, it makes sense to “add” Points together. For example, if you added together two Point variables, you should receive a new Point that is the summation of the X and Y values. Of course, it may also be helpful to subtract one Point from another. Ideally, you would like to be able to author the following code:

```
// Adding and subtracting two points?
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Overloaded Operators *****\n");

    // Make two points.
    Point ptOne = new Point(100, 100);
    Point ptTwo = new Point(40, 40);
    Console.WriteLine("ptOne = {0}", ptOne);
    Console.WriteLine("ptTwo = {0}", ptTwo);

    // Add the points to make a bigger point?
    Console.WriteLine("ptOne + ptTwo: {0} ", ptOne + ptTwo);

    // Subtract the points to make a smaller point?
    Console.WriteLine("ptOne - ptTwo: {0} ", ptOne - ptTwo);
    Console.ReadLine();
}
```

However, as our Point now stands, we will receive compile-time errors, as the Point type does not know how to respond to the + or - operators.

To equip a custom type to respond uniquely to intrinsic operators, C# provides the `operator` keyword, which you can use only in conjunction with static methods. When you overload a binary operator (such as + and -), you will most often pass in two arguments that are the same type as the defining class (a Point in this example), as illustrated in the following code update:

```
// A more intelligent Point type.
public class Point
{
```

```

...
// overloaded operator +
public static Point operator + (Point p1, Point p2)
{ return new Point(p1.X + p2.X, p1.Y + p2.Y); }

// overloaded operator -
public static Point operator - (Point p1, Point p2)
{ return new Point(p1.X - p2.X, p1.Y - p2.Y); }
}

```

The logic behind operator + is simply to return a brand new Point object based on the summation of the fields of the incoming Point parameters. Thus, when you write pt1 + pt2, under the hood you can envision the following hidden call to the static operator + method:

```
// Pseudo-code: Point p3 = Point.operator+ (p1, p2)
Point p3 = p1 + p2;
```

Likewise, p1 – p2 maps to the following:

```
// Pseudo-code: Point p4 = Point.operator- (p1, p2)
Point p4 = p1 - p2;
```

With this update, our program now compiles, and we find we are able to add and subtract Point objects:

```

ptOne = [100, 100]
ptTwo = [40, 40]
ptOne + ptTwo: [140, 140]
ptOne - ptTwo: [60, 60]

```

When you are overloading a binary operator, you are not required to pass in two parameters of the same type. If it makes sense to do so, one of the arguments can differ. For example, here is an overloaded operator + that allows the caller to obtain a new Point that is based on a numerical adjustment:

```

public class Point
{
...
    public static Point operator + (Point p1, int change)
    {
        return new Point(p1.X + change, p1.Y + change);
    }

    public static Point operator + (int change, Point p1)
    {
        return new Point(p1.X + change, p1.Y + change);
    }
}

```

Notice that you need *both* versions of the method if you want the arguments to be passed in either order (i.e., you can't just define one of the methods and expect the compiler to automatically support the other one). We are now able to use these new versions of operator + as follows:

```
// Prints [110, 110]
Point biggerPoint = ptOne + 10;
Console.WriteLine("ptOne + 10 = {0}", biggerPoint);

// Prints [120, 120]
Console.WriteLine("10 + biggerPoint = {0}", 10 + biggerPoint);
Console.WriteLine();
```

And What of the += and -= Operators?

If you are coming to C# from a C++ background, you may lament the loss of overloading the shorthand assignment operators (+=, -=, and so forth). Don't despair. In terms of C#, the shorthand assignment operators are automatically simulated if a type overloads the related binary operator. Thus, given that the Point structure has already overloaded the + and - operators, you can write the following:

```
// Overloading binary operators results in a freebie shorthand operator.
static void Main(string[] args)
{
    ...
    // Freebie +=
    Point ptThree = new Point(90, 5);
    Console.WriteLine("ptThree = {0}", ptThree);
    Console.WriteLine("ptThree += ptTwo: {0}", ptThree += ptTwo);

    // Freebie -=
    Point ptFour = new Point(0, 500);
    Console.WriteLine("ptFour = {0}", ptFour);
    Console.WriteLine("ptFour -= ptThree: {0}", ptFour -= ptThree);
    Console.ReadLine();
}
```

Overloading Unary Operators

C# also allows you to overload various unary operators, such as ++ and --. When you overload a unary operator, you also define a static method via the operator keyword; however, in this case you simply pass in a single parameter that is the same type as the defining class/structure. For example, if you were to update the Point with the following overloaded operators:

```
public class Point
{
    ...
    // Add 1 to the X/Y values incoming Point.
    public static Point operator ++(Point p1)
    { return new Point(p1.X+1, p1.Y+1); }

    // Subtract 1 from the X/Y values incoming Point.
    public static Point operator --(Point p1)
    { return new Point(p1.X-1, p1.Y-1); }
}
```

you could increment and decrement `Point`'s `x` and `y` values like this:

```
static void Main(string[] args)
{
...
// Applying the ++ and -- unary operators to a Point.
Point ptFive = new Point(1, 1);
Console.WriteLine("++ptFive = {0}", ++ptFive); // [2, 2]
Console.WriteLine("--ptFive = {0}", --ptFive); // [1, 1]

// Apply same operators as postincrement/decrement.
Point ptSix = new Point(20, 20);
Console.WriteLine("ptSix++ = {0}", ptSix++); // [20, 20]
Console.WriteLine("ptSix-- = {0}", ptSix--); // [21, 21]
Console.ReadLine();
}
```

Notice in the preceding code example we are applying our custom `++` and `--` operators in two different manners. In C++, it is possible to overload pre- and postincrement/decrement operators separately. This is not possible in C#. However, the return value of the increment/decrement is automatically handled “correctly” free of charge (i.e., for an overloaded `++` operator, `pt++` has the value of the unmodified object as its value within an expression, while `++pt` has the new value applied before use in the expression).

Overloading Equality Operators

As you may recall from Chapter 6, `System.Object.Equals()` can be overridden to perform value-based (rather than referenced-based) comparisons between reference types. If you choose to override `Equals()` (and the often related `System.Object.GetHashCode()` method), it is trivial to overload the equality operators (`==` and `!=`). To illustrate, here is the updated `Point` type:

```
// This incarnation of Point also overloads the == and != operators.
public class Point
{
...
    public override bool Equals(object o)
    {
        return o.ToString() == this.ToString();
    }

    public override int GetHashCode()
    { return this.ToString().GetHashCode(); }

    // Now let's overload the == and != operators.
    public static bool operator ==(Point p1, Point p2)
    { return p1.Equals(p2); }

    public static bool operator !=(Point p1, Point p2)
    { return !p1.Equals(p2); }
}
```

Notice how the implementation of operator == and operator != simply makes a call to the overridden Equals() method to get the bulk of the work done. Given this, you can now exercise your Point class as follows:

```
// Make use of the overloaded equality operators.
static void Main(string[] args)
{
...
    Console.WriteLine("ptOne == ptTwo : {0}", ptOne == ptTwo);
    Console.WriteLine("ptOne != ptTwo : {0}", ptOne != ptTwo);
    Console.ReadLine();
}
```

As you can see, it is quite intuitive to compare two objects using the well-known == and != operators rather than making a call to Object.Equals(). If you do overload the equality operators for a given class, keep in mind that C# demands that if you override the == operator, you *must* also override the != operator (if you forget, the compiler will let you know).

Overloading Comparison Operators

In Chapter 9, you learned how to implement the IComparable interface in order to compare the relationship between two like objects. You can, in fact, also overload the comparison operators (<, >, <=, and >=) for the same class. As with the equality operators, C# demands that if you overload <, you must also overload >. The same holds true for the <= and >= operators. If the Point type overloaded these comparison operators, the object user could now compare Points as follows:

```
// Using the overloaded < and > operators.
static void Main(string[] args)
{
...
    Console.WriteLine("ptOne < ptTwo : {0}", ptOne < ptTwo);
    Console.WriteLine("ptOne > ptTwo : {0}", ptOne > ptTwo);
    Console.ReadLine();
}
```

Assuming you have implemented the IComparable interface, overloading the comparison operators is trivial. Here is the updated class definition:

```
// Point is also comparable using the comparison operators.
public class Point : IComparable
{
...
    public int CompareTo(object obj)
    {
        if (obj is Point)
        {
            Point p = (Point)obj;
            if (this.X > p.X && this.Y > p.Y)
                return 1;
            if (this.X < p.X && this.Y < p.Y)
                return -1;
            else
                return 0;
        }
    }
}
```

```

        return 0;
    }
    else
        throw new ArgumentException();
}

public static bool operator <(Point p1, Point p2)
{ return (p1.CompareTo(p2) < 0); }

public static bool operator >(Point p1, Point p2)
{ return (p1.CompareTo(p2) > 0); }

public static bool operator <=(Point p1, Point p2)
{ return (p1.CompareTo(p2) <= 0); }

public static bool operator >=(Point p1, Point p2)
{ return (p1.CompareTo(p2) >= 0); }
}

```

The Internal Representation of Overloaded Operators

Like any C# programming element, overloaded operators are represented using specific CIL syntax. To begin examining what takes place behind the scenes, open the `OverloadedOps.exe` assembly using `ildasm.exe`. As you can see from Figure 12-1, the overloaded operators are internally expressed via hidden methods (such as `op_Addition()`, `op_Subtraction()`, `op_Equality()`, and so on).




Figure 12-1. In terms of CIL, overloaded operators map to hidden methods

Now, if you were to examine the specific CIL instructions for the `op_Addition` method (the one that takes two `Point` parameters), you would find that the `specialname` method decoration has also been inserted by the compiler:

```
.method public hidebysig specialname static
    class OverloadedOps.Point
        op_Addition(class OverloadedOps.Point p1,
                    class OverloadedOps.Point p2) cil managed
{
    ...
}
```

The truth of the matter is that any operator that you may overload equates to a specially named method in terms of CIL. Table 12-2 documents the C# operator-to-CIL mapping for the most common C# operators.

Table 12-2. C# Operator-to-CIL Special Name Road Map

Intrinsic C# Operator	CIL Representation
--	<code>op_Decrement()</code>
++	<code>op_Increment()</code>
+	<code>op>Addition()</code>
-	<code>op_Subtraction()</code>
*	<code>op_Multiply()</code>
/	<code>op_Division()</code>
==	<code>op_Equality()</code>
>	<code>op_GreaterThan()</code>
<	<code>op_LessThan()</code>
!=	<code>op_Inequality()</code>
>=	<code>op_GreaterThanOrEqual()</code>
<=	<code>op_LessThanOrEqual()</code>
-=	<code>op_SubtractionAssignment()</code>
+=	<code>op>AdditionAssignment()</code>

Final Thoughts Regarding Operator Overloading

As you have seen, C# provides the capability to build types that can respond uniquely to various intrinsic, well-known operators. Now, before you go and retrofit all your classes to support such behavior, you must be sure that the operator(s) you are about to overload make some sort of logical sense in the world at large.

For example, let's say you overloaded the multiplication operator for the `MiniVan` class. What exactly would it mean to multiply two `MiniVan` objects? Not much. In fact, it would be very confusing for teammates to see the following use of `MiniVan` objects.

```
// Huh?! This is far from intuitive...
MiniVan newVan = myVan * yourVan;
```

Overloading operators is generally useful only when you're building utility types. Strings, points, rectangles, fractions, and hexagons make good candidates for operator overloading. People, managers, cars, database connections, and web pages do not. As a rule of thumb, if an overloaded operator makes it *harder* for the user to understand a type's functionality, don't do it. Use this feature wisely.

Also, be aware that even if you do not generally overload operators for your custom classes, numerous types in the base class libraries have already done so. For example, the `System.Drawing.dll` assembly provides a Windows Forms-centric `Point` definition that overloads numerous operators. Notice the operator icon from the Visual Studio 2010 Object Browser shown in Figure 12-2.




Figure 12-2. Numerous types in the base class libraries have already overloaded operators

■ **Source Code** The `OverloadedOps` project is located under the Chapter 12 subdirectory.

Understanding Custom Type Conversions

Let's now examine a topic closely related to operator overloading: custom type conversions. To set the stage for the discussion, let's quickly review the notion of explicit and implicit conversions between numerical data and related class types.

Recall: Numerical Conversions

In terms of the intrinsic numerical types (sbyte, int, float, etc.), an *explicit conversion* is required when you attempt to store a larger value in a smaller container as this may result in a loss of data. Basically, this is your way to tell the compiler, "Leave me alone, I know what I am trying to do." Conversely, an *implicit conversion* happens automatically when you attempt to place a smaller type in a destination type that will not result in a loss of data:

```
static void Main()
{
    int a = 123;
    long b = a;      // Implicit conversion from int to long
    int c = (int) b; // Explicit conversion from long to int
}
```

Recall: Conversions Among Related Class Types

As shown in Chapter 6, class types may be related by classical inheritance (the "is-a" relationship). In this case, the C# conversion process allows you to cast up and down the class hierarchy. For example, a derived class can always be implicitly cast to a base type. However, if you wish to store a base class type in a derived variable, you must perform an explicit cast:

```
// Two related class types.
class Base{}
class Derived : Base{}

class Program
{
    static void Main(string[] args)
    {
        // Implicit cast between derived to base.
        Base myBaseType;
        myBaseType = new Derived();

        // Must explicitly cast to store base reference
        // in derived type.
        Derived myDerivedType = (Derived)myBaseType;
    }
}
```

This explicit cast works due to the fact that the `Base` and `Derived` classes are related by classical inheritance. However, what if you have two class types in *different hierarchies* with no common parent

(other than `System.Object`) that require conversions? Given that they are not related by classical inheritance, explicit casting offers no help.

On a related note, consider value types, such as structures. Assume you have two .NET structures named `Square` and `Rectangle`. Given that structures cannot leverage classic inheritance (as they are always sealed), you have no natural way to cast between these seemingly related types.

While you could create helper methods in the structures (such as `Rectangle.ToSquare()`), C# lets you build custom conversion routines that allow your types to respond to the `()` casting operator. Therefore, if you configured the structures correctly, you would be able to use the following syntax to explicitly convert between them as follows:

```
// Convert a Rectangle to a Square!
Rectangle rect;
rect.Width = 3;
rect.Height = 10;
Square sq = (Square)rect;
```

Creating Custom Conversion Routines

Begin by creating a new Console Application named `CustomConversions`. C# provides two keywords, `explicit` and `implicit`, that you can use to control how your types respond during an attempted conversion. Assume you have the following class definitions:

```
public class Rectangle
{
    public int Width {get; set;}
    public int Height {get; set;}

    public Rectangle(int w, int h)
    {
        Width = w; Height = h;
    }
    public Rectangle(){}
}

public void Draw()
{
    for (int i = 0; i < Height; i++)
    {
        for (int j = 0; j < Width; j++)
        {
            Console.Write("*");
        }
        Console.WriteLine();
    }
}

public override string ToString()
{
    return string.Format("[Width = {0}; Height = {1}]",
        Width, Height);
}
```

```

public class Square
{
    public int Length {get; set;}

    public Square(int l)
    {
        Length = l;
    }
    public Square(){}
}

public void Draw()
{
    for (int i = 0; i < Length; i++)
    {
        for (int j = 0; j < Length; j++)
        {
            Console.Write("*");
        }
        Console.WriteLine();
    }
}

public override string ToString()
{ return string.Format("[Length = {0}]", Length); }

// Rectangles can be explicitly converted
// into Squares.
public static explicit operator Square(Rectangle r)
{
    Square s = new Square();
    s.Length = r.Height;
    return s;
}
}

```

Notice that this iteration of the `Square` type defines an explicit conversion operator. Like the process of overloading an operator, conversion routines make use of the C# `operator` keyword, in conjunction with the `explicit` or `implicit` keyword, and must be defined as static. The incoming parameter is the entity you are converting *from*, while the operator type is the entity you are converting *to*.

In this case, the assumption is that a square (being a geometric pattern in which all sides are of equal length) can be obtained from the height of a rectangle. Thus, you are free to convert a `Rectangle` into a `Square` as follows:

```

static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Conversions *****\n");

    // Make a Rectangle.
    Rectangle r = new Rectangle(15, 4);
    Console.WriteLine(r.ToString());
    r.Draw();
}

```

```

Console.WriteLine();

// Convert r into a Square,
// based on the height of the Rectangle.
Square s = (Square)r;
Console.WriteLine(s.ToString());
s.Draw();
Console.ReadLine();
}

```

The output can be seen in Figure 12-3.




Figure 12-3. Converting a Rectangle structure to a Square structure

While it may not be all that helpful to convert a Rectangle into a Square within the same scope, assume you have a function that has been designed to take Square parameters.

```

// This method requires a Square type.
static void DrawSquare(Square sq)
{
    Console.WriteLine(sq.ToString());
    sq.Draw();
}

```

Using your explicit conversion operation on the Square type, you can now pass in Rectangle types for processing using an explicit cast:

```

static void Main(string[] args)
{
    ...
    // Convert Rectangle to Square to invoke method.
    Rectangle rect = new Rectangle(10, 5);
    DrawSquare((Square)rect);
    Console.ReadLine();
}

```

Additional Explicit Conversions for the Square Type

Now that you can explicitly convert Rectangles into Squares, let's examine a few additional explicit conversions. Given that a square is symmetrical on all sides, it might be helpful to provide an explicit conversion routine that allows the caller to cast from an integer type into a `Square` (which, of course, will have a side length equal to the incoming integer). Likewise, what if you were to update `Square` such that the caller can cast *from* a `Square` into a `System.Int32`? Here is the calling logic:

```
static void Main(string[] args)
{
...
// Converting an int to a Square.
Square sq2 = (Square)90;
Console.WriteLine("sq2 = {0}", sq2);

// Converting a Square to a int.
int side = (int)sq2;
Console.WriteLine("Side length of sq2 = {0}", side);
Console.ReadLine();
}
```

and here is the update to the `Square` class:

```
public class Square
{
...
public static explicit operator Square(int sideLength)
{
    Square newSq = new Square();
    newSq.Length = sideLength;
    return newSq;
}

public static explicit operator int (Square s)
{return s.Length;}
}
```

To be honest, converting from a `Square` into an integer may not be the most intuitive (or useful) operation. However, it does point out a very important fact regarding custom conversion routines: the compiler does not care what you convert to or from, as long as you have written syntactically correct code.

Thus, as with overloading operators, just because you can create an explicit cast operation for a given type does not mean you should. Typically, this technique will be most helpful when you're creating .NET structure types, given that they are unable to participate in classical inheritance (where casting comes for free).

Defining Implicit Conversion Routines

Thus far, you have created various custom *explicit* conversion operations. However, what about the following *implicit* conversion?

```
static void Main(string[] args)
```

```
{
...
// Attempt to make an implicit cast?
Square s3 = new Square();
s3.Length = 83;
Rectangle rect2 = s3;

Console.ReadLine();
}
```

This code will not compile, given that you have not provided an implicit conversion routine for the Rectangle type. Now here is the catch: it is illegal to define explicit and implicit conversion functions on the same type if they do not differ by their return type or parameter set. This might seem like a limitation; however, the second catch is that when a type defines an *implicit* conversion routine, it is legal for the caller to make use of the *explicit* cast syntax!

Confused? To clear things up, let's add an implicit conversion routine to the Rectangle structure using the C# `implicit` keyword (note that the following code assumes the width of the resulting Rectangle is computed by multiplying the side of the Square by 2):

```
public class Rectangle
{
...
    public static implicit operator Rectangle(Square s)
    {
        Rectangle r = new Rectangle();
        r.Height = s.Length;

        // Assume the length of the new Rectangle with
        // (Length x 2)
        r.Width = s.Length * 2;
        return r;
    }
}
```

With this update, you are now able to convert between types as follows:

```
static void Main(string[] args)
{
...
    // Implicit cast OK!
    Square s3 = new Square();
    s3.Length= 7;
    Rectangle rect2 = s3;
    Console.WriteLine("rect2 = {0}", rect2);
    DrawSquare(s3);

    // Explicit cast syntax still OK!
    Square s4 = new Square();
    s4.Length = 3;
    Rectangle rect3 = (Rectangle)s4;
    Console.WriteLine("rect3 = {0}", rect3);
    Console.ReadLine();
}
```

The Internal Representation of Custom Conversion Routines

Like overloaded operators, methods that are qualified with the `implicit` or `explicit` keywords have “special” names in terms of CIL: `op_Implicit` and `op_Explicit`, respectively (see Figure 12-4).




Figure 12-4. CIL representation of user-defined conversion routines

■ **Note** The Visual Studio 2010 Object Browser shows custom conversion operators using the “explicit operator” and “implicit operator” icons.

That wraps up our look at defining custom conversion routines. As with overloaded operators, remember that this bit of syntax is simply a shorthand notation for “normal” member functions, and in this light it is always optional. When used correctly, however, custom structures can be used more naturally, as they can be treated as true class types related by inheritance.

■ **Source Code** The `CustomConversions` project is located under the Chapter 12 subdirectory.

Understanding Extension Methods

.NET 3.5 introduced the concept of *extension methods*, which allow you to tack on new functionality to precompiled types on the fly. As you know, once a type is defined and compiled into a .NET assembly, its

definition is, more or less, final. The only way to add new members, update members, or remove members is to recode and recompile the code base into an updated assembly (or take more drastic measures, such as using the `System.Reflection.Emit` namespace to dynamically reshape a compiled type in memory).

In C#, it is now possible to define extension methods. In a nutshell, extension methods allow existing compiled types (specifically, classes, structures, or interface implementations) as well as types currently being compiled (such as types in a project that contains extension methods) to gain new functionality without needing to directly update the type being extended.

This technique can be quite helpful when you need to inject new functionality into types for which you do not have an existing code base. It can also be handy when you need to force a type to support a set of members (in the interest of polymorphism), but cannot modify the original type declaration. Using extension methods, you can add functionality to precompiled types while providing the illusion these methods were there all along.

Note Understand that extension methods do not literally change the compiled code base! This technique only adds members to a type within the context of the current application.

When you define extension methods, the first restriction is that they must be defined within a *static class* (see Chapter 5), and therefore each extension method must be declared with the `static` keyword. The second point is that all extension methods are marked as such by using the `this` keyword as a modifier on the first (and only the first) parameter of the method in question. The third point is that every extension method can be called either from the correct instance in memory or *statically* via the defining static class! Sound strange? Let's look at a full example to clarify matters.

Defining Extension Methods

Create a new Console Application named `ExtensionMethods`. Now, assume you are authoring a utility class named `MyExtensions` that defines two extension methods. The first method allows any object in the .NET base class libraries to have a brand-new method named `DisplayDefiningAssembly()` that makes use of types in the `System.Reflection` namespace to display the assembly of the specified type.

Note You will formally examine the reflection API in Chapter 15. If you are new to the topic, simply understand that reflection allows you to discover the structure of assemblies, types, and type members at runtime.

The second extension method, named `ReverseDigits()`, allows any `System.Int32` to obtain a new version of itself where the value is reversed digit by digit. For example, if an integer with the value 1234 called `ReverseDigits()`, the integer returned is set to the value 4321. Consider the following class implementation (be sure to import the `System.Reflection` namespace if you are following along):

```
static class MyExtensions
{
```

```

// This method allows any object to display the assembly
// it is defined in.
public static void DisplayDefiningAssembly(this object obj)
{
    Console.WriteLine("{0} lives here: => {1}\n", obj.GetType().Name,
                      Assembly.GetAssembly(obj.GetType()).GetName().Name);
}

// This method allows any integer to reverse its digits.
// For example, 56 would return 65.
public static int ReverseDigits(this int i)
{
    // Translate int into a string, and then
    // get all the characters.
    char[] digits = i.ToString().ToCharArray();

    // Now reverse items in the array.
    Array.Reverse(digits);

    // Put back into string.
    string newDigits = new string(digits);

    // Finally, return the modified string back as an int.
    return int.Parse(newDigits);
}
}

```

Again, note how the first parameter of each extension method has been qualified with the `this` keyword, before defining the parameter type. It is always the case that the first parameter of an extension method represents the type being extended. Given that `DisplayDefiningAssembly()` has been prototyped to extend `System.Object`, any type in any assembly now has this new member. However, `ReverseDigits()` has been prototyped to only extend integer types, and therefore if anything other than an integer attempts to invoke this method, you will receive a compile-time error.

Understand that a given extension method can have multiple parameters, but *only* the first parameter can be qualified with `this`. For example, here is an overloaded extension method defined in another utility class named `TesterUtilClass`:

```

static class TesterUtilClass
{
    // Every Int32 now has a Foo() method...
    public static void Foo(this int i)
    { Console.WriteLine("{0} called the Foo() method.", i); }

    // ...which has been overloaded to take a string!
    public static void Foo(this int i, string msg)
    { Console.WriteLine("{0} called Foo() and told me: {1}", i, msg); }
}

```

Invoking Extension Methods on an Instance Level

Now that we have these extension methods, look at how all objects (which of course means everything in the .NET base class libraries) have a new method named `DisplayDefiningAssembly()`, while `System.Int32` types (and only integers) have methods named `ReverseDigits()` and `Foo()`:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Extension Methods *****\n");

    // The int has assumed a new identity!
    int myInt = 12345678;
    myInt.DisplayDefiningAssembly();

    // So has the DataSet!
    System.Data.DataSet d = new System.Data.DataSet();
    d.DisplayDefiningAssembly();

    // And the SoundPlayer!
    System.Media.SoundPlayer sp = new System.Media.SoundPlayer();
    sp.DisplayDefiningAssembly();

    // Use new integer functionality.
    Console.WriteLine("Value of myInt: {0}", myInt);
    Console.WriteLine("Reversed digits of myInt: {0}", myInt.ReverseDigits());
    myInt.Foo();
    myInt.Foo("Ints that Foo? Who would have thought it!");

    bool b2 = true;

    // Error! Booleans don't have the Foo() method!
    // b2.Foo();

    Console.ReadLine();
}
```

Here is the output.

```
***** Fun with Extension Methods *****

Int32 lives here: => mscorelib

DataSet lives here: => System.Data

SoundPlayer lives here: => System

Value of myInt: 12345678
Reversed digits of myInt: 87654321
12345678 called the Foo() method.
12345678 called Foo() and told me: Ints that Foo? Who would have thought it!
```

Invoking Extension Methods Statically

Recall that the first parameter of an extension method is marked with the `this` keyword, followed by the type of item the method is applicable to. If you peek at what is happening behind the scenes (as verified by a tool such as `ildasm.exe`), you will find that the compiler simply calls the “normal” static method, passing in the variable calling the method as a parameter (e.g., it is the value of `this`). Consider the following C# code, which approximates the code substitution that took place:

```
private static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Extension Methods *****\n");
    int myInt = 12345678;
    MyExtensions.DisplayDefiningAssembly(myInt);

    System.Data.DataSet d = new DataSet();
    MyExtensions.DisplayDefiningAssembly(d);

    System.Media.SoundPlayer sp = new SoundPlayer();
    MyExtensions.DisplayDefiningAssembly(sp);

    Console.WriteLine("Value of myInt: {0}", myInt);
    Console.WriteLine("Reversed digits of myInt: {0}",
        MyExtensions.ReverseDigits(myInt));

    TesterUtilClass.Foo(myInt);
    TesterUtilClass.Foo(myInt, "Ints that Foo? Who would have thought it!");

    Console.ReadLine();
}
```

Given that calling an extension method from an object (thereby making it seem that the method is in fact an instance-level method) is just some smoke-and-mirrors effect provided by the compiler, you are always free to call extension methods as normal static methods using the expected C# syntax (as just shown).

The Scope of an Extension Method

As just explained, extension methods are essentially static methods that can be invoked from an instance of the extended type. Given this flavor of syntactic sugar, it is really important to point out that unlike a “normal” method, extension methods do not have direct access to the members of the type they are extending; said another way, *extending* is not *inheriting*. Consider the following simple `Car` type:

```
public class Car
{
    public int Speed;
    public int SpeedUp()
    {
        return ++Speed;
    }
}
```

If you were to build an extension method for the `Car` type named `SlowDown()`, you would not have direct access to the members of `Car` within the scope of the extension method as this is not classical inheritance. Therefore, the following would result in a compiler error:

```
public static class CarExtensions
{
    public static int SlowDown(this Car c)
    {
        // Error! This method is not deriving from Car!
        return --Speed;
    }
}
```

The problem here is that the static `SlowDown()` extension method is attempting to access the `Speed` field of the `Car` type. However, because `SlowDown()` is a static member of the `CarExtensions` class, `Speed` does not exist in this context! What is permissible, however, is to make use of the `this`-qualified parameter to access all public members (and *only* the public members) of the type being extending. Thus, the following code compiles as expected:

```
public static class CarExtensions
{
    public static int SlowDown(this Car c)
    {
        // OK!
        return --c.Speed;
    }
}
```

At this point, you could create a `Car` object and invoke the `SpeedUp()` and `SlowDown()` methods as follows:

```
static void UseCar()
{
    Car c = new Car();
    Console.WriteLine("Speed: {0}", c.SpeedUp());
    Console.WriteLine("Speed: {0}", c.SlowDown());
```

Importing Types That Define Extension Methods

When you partition a set of static classes containing extension methods in a unique namespace, other namespaces in that assembly will make use of the standard C# `using` keyword to import not only the static classes themselves, but also each of the supported extension methods. This is important to remember, because if you do not explicitly import the correct namespace, the extension methods are not available for that C# code file.

In effect, although it can appear on the surface that extension methods are global in nature, they are in fact limited to the namespaces that define them or the namespaces that import them. Thus, if we wrap the definitions of our static classes (`MyExtensions`, `TesterUtilClass`, and `CarExtensions`) into a namespace named `MyExtensionMethods` as follows:

```
namespace MyExtensionMethods
{
```

```

static class MyExtensions
{
    ...
}

static class TesterUtilClass
{
    ...
}

static class CarExtensions
{
    ...
}

```

other namespaces in the project would need to explicitly import the `MyExtensionMethods` namespace to gain the extension methods defined by these types. Therefore, the following is a compiler error:

```

// Here is our only using directive.
using System;

namespace MyNewApp
{
    class JustATest
    {
        void SomeMethod()
        {
            // Error! Need to import MyExtensionMethods
            // namespace to extend int with Foo()!
            int i = 0;
            i.Foo();
        }
    }
}

```

The IntelliSense of Extension Methods

Given the fact that extension methods are not literally defined on the type being extended, it is certainly possible to become confused when examining an existing code base. For example, assume you have imported a namespace that defined some number of extension methods authored by a teammate. As you are authoring your code, you might create a variable of the extended type, apply the dot operator, and find dozens of new methods that are not members of the original class definition!

Thankfully, Visual Studio's IntelliSense mechanism marks all extension methods with a unique, blue down-arrow icon (see Figure 12-5).




Figure 12-5. The IntelliSense of extension methods

Any method marked with this visual icon is a friendly reminder that the method is defined outside of the original class definition via an extension method.

■ **Source Code** The ExtensionMethods project can be found under the Chapter 12 subdirectory.

Building and Using Extension Libraries

The previous example extended the functionality of various types (such as the `System.Int32` type) for use by the current console application. However, I am sure you can imagine the usefulness of building a .NET code library that defines extensions that can be referenced by multiple applications. As luck would have it, doing so is very straightforward.

Chapter 14 will delve into the details of creating and configuring custom libraries; however, if you wish to follow along for this example, create a new Class Library project named `MyExtensionsLibrary`. Next, rename your initial C# code file to `MyExtensions.cs` and copy the `MyExtensions` class definition in your new namespace:

```
namespace MyExtensionsLibrary
{
    // Be sure to import System.Reflection.
    public static class MyExtensions
    {
        // Same implementation as before.
        public static void DisplayDefiningAssembly(this object obj)
        {...}
```

```
// Same implementation as before.
public static int ReverseDigits(this int i)
{...}
}
```

Note If you wish to export extension methods from a .NET code library, the defining type must be declared with the public keyword (recall that the default access modifier for a type is internal).

At this point, you can compile your library and reference the MyExtensionsLibrary.dll assembly within new .NET projects. When you do so, the new functionality provided to System.Object and System.Int32 can be used by any application that references the library.

To test this out, add a new Console Application project (named MyExtensionsLibraryClient). Next, add a reference to the MyExtensionsLibrary.dll assembly. Within the initial code file, specify that you are using the MyExtensionsLibrary namespace and author some simple code that invokes these new methods on a local integer:

```
using System;

// Import our custom namespace.
using MyExtensionsLibrary;

namespace MyExtensionsLibraryClient
{
    class Program
    {
        static void Main(string[] args)
        {
            Console.WriteLine("***** Using Library with Extensions *****\n");
            // This time, these extension methods
            // have been defined within an external
            // .NET class library.
            int myInt = 987;
            myInt.DisplayDefiningAssembly();
            Console.WriteLine("{0} is reversed to {1}",
                myInt, myInt.ReverseDigits());
            Console.ReadLine();
        }
    }
}
```

Microsoft recommends placing types that have extension methods in a dedicated assembly (within a dedicated namespace). The reason is simply to reduce cluttering of your programming environment. By way of example, if you were to author a core library for your company that every application was expected to make use of, and if the root namespace of that library defined 30 extension methods, the end result would be that all applications would see these methods pop up in IntelliSense (even if they are not required).

■ Source Code The MyExtensionsLibrary and MyExtensionsLibraryClient projects can be found under the Chapter 12 subdirectory.

Extending Interface Types via Extension Methods

At this point, you have seen how to extend classes (and, indirectly, structures that follow the same syntax) with new functionality via extension methods. To wrap up our investigation of C# extension methods, allow me to point out that it is possible to extend an interface type with new methods; however, the semantics of such an action are sure to be a bit different from what you might expect.

Create a new Console Application named InterfaceExtensions and define a simple interface type (IBasicMath) that contains a single method named Add(). Next, implement this interface on a class type (MyCalc) in a fitting manner, for example:

```
// Define a normal interface in C#.
interface IBasicMath
{
    int Add(int x, int y);
}

// Implementation of IBasicMath.
class MyCalc : IBasicMath
{
    public int Add(int x, int y)
    {
        return x + y;
    }
}
```

Now, assume you do not have access to the code definition of IBasicMath, but wish to add a new member (such as a subtraction method) to expand its behavior. You might attempt to author the following extension class to do so:

```
static class MathExtensions
{
    // Extend IBasicMath with subtraction method?
    public static int Subtract(this IBasicMath itf,
                               int x, int y);
}
```

However, this will result in compile-time errors. When you extend an interface with new members, you must *also supply an implementation* of these members! This seems to fly in the face of the very nature of interface types, as interfaces do not provide implementations, only definitions. Nevertheless, you are required to define your MathExtensions class as follows:

```
static class MathExtensions
{
    // Extend IBasicMath this method and this
    // implementation.
    public static int Subtract(this IBasicMath itf, int x, int y)
```

```

    {
        return x - y;
    }
}

```

At this point, you might assume you could create a variable of type `IBasicMath` and directly invoke `Subtract()`. Again, if this were possible (which it is not), it would destroy the nature of .NET interface types. In reality, what we have actually said here is “Any class in my project implementing `IBasicMath` now has a `Subtract()` method, implemented in this manner.” As before, all the basic rules apply, therefore the namespace defining `MyCalc` must have access to the namespace defining `MathExtensions`. Consider the following `Main()` method:

```

static void Main(string[] args)
{
    Console.WriteLine("***** Extending an interface *****\n");

    // Call IBasicMath members from MyCalc object.
    MyCalc c = new MyCalc();
    Console.WriteLine("1 + 2 = {0}", c.Add(1, 2));
    Console.WriteLine("1 - 2 = {0}", c.Subtract(1, 2));

    // Can also cast into IBasicMath to invoke extension.
    Console.WriteLine("30 - 9 = {0}", ((IBasicMath)c).Subtract(30, 9));

    // This would NOT work!
    // IBasicMath itfBM = new IBasicMath();
    // itfBM.Subtract(10, 10);

    Console.ReadLine();
}

```

That wraps up our examination of C# extension methods. Remember that this particular language feature can be very useful whenever you wish to extend the functionality of a type, even if you do not have access to the original source code (or if the type is sealed), for the purposes of polymorphism. And, much like implicitly typed local variables, extension methods are a key element of working with the LINQ API. As you will see in the next chapter, numerous existing types in the base class libraries have been extended with new functionality, via extension methods, to allow them to integrate with the LINQ programming model.

■ Source Code The `InterfaceExtension` project can be found under the Chapter 12 subdirectory.

Understanding Partial Methods

Since the release of .NET 2.0, it has been possible to build partial class definitions using the `partial` keyword (see Chapter 5). Recall that this bit of syntax allows you to partition the full implementation of a type across multiple code files (or other locations, such as in memory). As long as each aspect of the partial type has the same fully qualified name, the end result is a single “normal” compiled class type in the assembly being constructed.

C# recycles the role of the `partial` keyword in that it can now be applied on the method level. In a nutshell, this allows you to prototype a method in one file, yet implement it in another file. If you have a C++ background, this might remind you of a C++ header/implementation file; however, C# partial methods have a number of important restrictions:

- Partial methods can only be defined within a partial class.
- Partial methods must return `void`.
- Partial methods can be static or instance level.
- Partial methods can have arguments (including parameters modified by `this`, `ref`, or `params`—but not with the `out` modifier).
- Partial methods are always implicitly private.

Even stranger is the fact that a partial method may or may not be emitted into the compiled assembly! Let's see an example to clarify matters.

A First Look at Partial Methods

To see the implications of defining a partial method, create a new Console Application project named `PartialMethods`. Now, define a new class named `CarLocator` within a C# file named `CarLocator.cs`:

```
// CarLocator.cs
partial class CarLocator
{
    // This member will always be part of the
    // CarLocator class.
    public bool CarAvailableInZipCode(string zipCode)
    {
        // This call *may* be part of this method
        // implementation.
        VerifyDuplicates(zipCode);

        // Assume some interesting database logic
        // here...
        return true;
    }

    // This member *may* be part of the CarLocator class!
    partial void VerifyDuplicates(string make);
}
```

Notice that the `VerifyDuplicates()` method has been defined with the `partial` modifier and does not define a method body within this file. Also notice that the `CarAvailableInZipCode()` method is making a call to `VerifyDuplicates()` within its implementation.

If you were to compile this application as it now stands and open the compiled assembly in a tool such as `ildasm.exe` or `reflector.exe`, you would find *no trace* of the `VerifyDuplicates()` method in the `CarLocator` class, and *no trace* of the call to `VerifyDuplicates()` within `CarAvailableInZipCode()`! With the project as it now stands, you really authored the following definition of the `CarLocator` class as far as the compiler is concerned:

```
internal class CarLocator
{
    public bool CarAvailableInZipCode(string zipCode)
    {
        return true;
    }
}
```

The reason for this strange stripping away of code has to do with the fact that the partial `VerifyDuplicates()` method was never given a true implementation. If you were to now add a new file to your project (named perhaps `CarLocatorImpl.cs`) that defined the remainder of the partial method:

```
// CarLocatorImpl.cs
partial class CarLocator
{
    partial void VerifyDuplicates(string make)
    {
        // Assume some expensive data validation
        // takes place here...
    }
}
```

you would find that the full scope of the `CarLocator` class is taken into account at compile time, as shown in the following approximate C# code:

```
internal class CarLocator
{
    public bool CarAvailableInZipCode(string zipCode)
    {
        this.VerifyDuplicates(zipCode);
        return true;
    }

    private void VerifyDuplicates(string make)
    {
    }
}
```

As you can see, when a method is defined with the `partial` keyword, the compiler will determine if it should be emitted into the assembly based on whether the method has a method body or is simply an empty signature. If there is no method body, all traces of the method (invocations, metadata descriptions, prototypes) are stripped out during the compilation cycle.

In some ways, C# partial methods are a strongly typed version of *conditional code compilation* (via the `#if`, `#elif`, `#else`, and `#endif` preprocessor directives). The major difference, however, is that a partial method will be completely ignored during the compilation cycle (regardless of build settings) if there is not a supporting implementation.

Uses of Partial Methods

Given the restrictions that come with partial methods, most notably that they must be implicitly private and always return `void`, it is hard to see many useful applications of this new language feature. Truth be

told, out of all of the language features of C#, partial methods seem among those likely to be used the least.

In the current example, the `VerifyDuplicates()` method was marked as partial for illustrative purposes. However, imagine that this method, if implemented, had to perform some very intensive calculations.

By marking this method with the `partial` modifier, other class builders have the *option* of providing implementation details if they so choose. In this case, partial methods provide a cleaner solution than using preprocessor directives, supplying “dummy” implementations to virtual methods, or throwing `NotImplementedException` objects.

The most common use of this syntax is to define what are termed *lightweight events*. This technique enables class designers to provide method hooks, similar to event handlers, that developers may choose to implement or not. As a naming convention, such lightweight event-handling methods take an `On` prefix, for example:

```
// CarLocator.EventHandler.cs
partial class CarLocator
{
    public bool CarAvailableInZipCode(string zipCode)
    {
        ...
        OnZipCodeLookup(zipCode);
        return true;
    }
    ...
    // A "lightweight" event handler.
    partial void OnZipCodeLookup(string make);
}
```

If any class builders wish to be informed when the `CarAvailableInZipCode()` method has been called, they can provide an implementation of the `OnZipCodeLookup()` method. If they do not care, they simply do nothing.

Source Code The PartialMethods project can be found under the Chapter 12 subdirectory.

Understanding Anonymous Types

As an OO programmer, you know the benefits of defining classes to represent the state and functionality of a given programming entity. To be sure, whenever you need to define a class that is intended to be reused across projects and provides numerous bits of functionality through a set of methods, events, properties, and custom constructors, creating a new C# class is common practice and often mandatory.

However, there are other times when you would like to define a class simply to model a set of encapsulated (and somehow related) data points without any associated methods, events, or other custom functionality. Furthermore, what if this type is only to be used internally to your current application and it's not intended to be reused? If you need such a “temporary” type, earlier versions of C# would require you to nevertheless build a new class definition by hand:

```
internal class SomeClass
{
    // Define a set of private member variables...

    // Make a property for each member variable...

    // Override ToString() to account for each member variable...

    // Override GetHashCode() and Equals() to work with value based equality...
}
```

While building such a class is not rocket science, it can be rather labor-intensive if you are attempting to encapsulate more than a handful of members (although automatic properties do help in this regard). These days, we are provided with a massive shortcut for this very situation (termed *anonymous types*) that in many ways is a natural extension of C#'s anonymous methods syntax (examined in Chapter 11).

When you define an anonymous type, you do so by making use of the `var` keyword (see Chapter 3) in conjunction with object initialization syntax (see Chapter 5). To illustrate, create a new Console Application named `AnonymousTypes`. Now, update `Main()` with the following anonymous class, which models a simple car type:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Anonymous Types *****\n");

    // Make an anonymous type representing a car.
    var myCar = new { Color = "Bright Pink", Make = "Saab", CurrentSpeed = 55 };

    // Now show the color and make.
    Console.WriteLine("My car is a {0} {1}.", myCar.Color, myCar.Make);
    Console.ReadLine();
}
```

Again note that the `myCar` variable must be implicitly typed, which makes good sense as we are not modeling the concept of an automobile using a strongly typed class definition. At compile time, the C# compiler will autogenerate a uniquely named class on our behalf. Given the fact that this class name is not visible from C#, the use of implicit typing using the `var` keyword is mandatory.

Also notice that we have to specify (using object initialization syntax) the set of properties that model the data we are attempting to encapsulate. Once defined, these values can then be obtained using standard C# property invocation syntax.

The Internal Representation of Anonymous Types

All anonymous types are automatically derived from `System.Object`, and therefore support each of the members provided by this base class. Given this, we could invoke `ToString()`, `GetHashCode()`, `Equals()`, or `GetType()` on the implicitly typed `myCar` object. Assume our `Program` class defines the following static helper function:

```
static void ReflectOverAnonymousType(object obj)
{
    Console.WriteLine("obj is an instance of: {0}", obj.GetType().Name);
```

```

Console.WriteLine("Base class of {0} is {1}",
    obj.GetType().Name,
    obj.GetType().BaseType);
Console.WriteLine("obj.ToString() = {0}", obj.ToString());
Console.WriteLine("obj.GetHashCode() = {0}", obj.GetHashCode());
Console.WriteLine();
}

```

Now assume we invoke this method from `Main()`, passing in the `myCar` object as the parameter:

```

static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Anonymous types *****\n");

    // Make an anonymous type representing a car.
    var myCar = new {Color = "Bright Pink", Make = "Saab", CurrentSpeed = 55};

    // Reflect over what the compiler generated.
    ReflectOverAnonymousType(myCar);
    Console.ReadLine();
}

```

The output will look similar to the following:

```

***** Fun with Anonymous types *****

obj is an instance of: <>f__AnonymousType0`3
Base class of <>f__AnonymousType0`3 is System.Object
obj.ToString() = { Color = Bright Pink, Make = Saab, CurrentSpeed = 55 }
obj.GetHashCode() = 2038548792

```

First of all, notice that in this example, the `myCar` object is of type `<>f__AnonymousType0`3` (your name may differ). Remember that the assigned type name is completely determined by the compiler and is not directly accessible in your C# code base.

Perhaps most important, notice that each name/value pair defined using the object initialization syntax is mapped to an identically named read-only property and a corresponding private read-only backing field. The following C# code approximates the compiler-generated class used to represent the `myCar` object (which again can be verified using tools such as `reflector.exe` or `ildasm.exe`):

```

internal sealed class <>f__AnonymousType0<<Color>j__TPar,
    <Make>j__TPar, <CurrentSpeed>j__TPar>
{
    // Read-only fields
    private readonly <Color>j__TPar <Color>i__Field;
    private readonly <CurrentSpeed>j__TPar <CurrentSpeed>i__Field;
    private readonly <Make>j__TPar <Make>i__Field;

    // Default constructor
    public <>f__AnonymousType0(<Color>j__TPar Color,
        <Make>j__TPar Make, <CurrentSpeed>j__TPar CurrentSpeed);
}

```

```

// Overridden methods
public override bool Equals(object value);
public override int GetHashCode();
public override string ToString();

// Read-only properties
public <Color>j_TPar Color { get; }
public <CurrentSpeed>j_TPar CurrentSpeed { get; }
public <Make>j_TPar Make { get; }
}

```

The Implementation of `ToString()` and `GetHashCode()`

All anonymous types automatically derive from `System.Object` and are provided with an overridden version of `Equals()`, `GetHashCode()`, and `ToString()`. The `ToString()` implementation simply builds a string from each name/value pair, for example:

```

public override string ToString()
{
    StringBuilder builder = new StringBuilder();
    builder.Append("{ Color = ");
    builder.Append(this.<Color>i_Field);
    builder.Append(", Make = ");
    builder.Append(this.<Make>i_Field);
    builder.Append(", CurrentSpeed = ");
    builder.Append(this.<CurrentSpeed>i_Field);
    builder.Append(" }");
    return builder.ToString();
}

```

The `GetHashCode()` implementation computes a hash value using each anonymous type's member variables as input to the `System.Collections.Generic.EqualityComparer<T>` type. Using this implementation of `GetHashCode()`, two anonymous types will yield the same hash value if (and only if) they have the same set of properties that have been assigned the same values. Given this implementation, anonymous types are well-suited to be contained within a `Hashtable` container.

The Semantics of Equality for Anonymous Types

While the implementation of the overridden `ToString()` and `GetHashCode()` methods is fairly straightforward, you may be wondering how the `Equals()` method has been implemented. For example, if we were to define two “anonymous cars” variables that specify the same name/value pairs, would these two variables be considered equal or not? To see the results firsthand, update your `Program` type with the following new method:

```

static void EqualityTest()
{
    // Make 2 anonymous classes with identical name/value pairs.
    var firstCar = new { Color = "Bright Pink", Make = "Saab", CurrentSpeed = 55 };
    var secondCar = new { Color = "Bright Pink", Make = "Saab", CurrentSpeed = 55 };
}

```

```

// Are they considered equal when using Equals()?
if (firstCar.Equals(secondCar))
    Console.WriteLine("Same anonymous object!");
else
    Console.WriteLine("Not the same anonymous object!");

// Are they considered equal when using ==?
if (firstCar == secondCar)
    Console.WriteLine("Same anonymous object!");
else
    Console.WriteLine("Not the same anonymous object!");

// Are these objects the same underlying type?
if (firstCar.GetType().Name == secondCar.GetType().Name)
    Console.WriteLine("We are both the same type!");
else
    Console.WriteLine("We are different types!");

// Show all the details.
Console.WriteLine();
ReflectOverAnonymousType(firstCar);
ReflectOverAnonymousType(secondCar);
}

```

Assuming you have called this method from within `Main()`, Figure 12-6 shows the (somewhat surprising) output.

```

C:\Windows\system32\cmd.exe
Same anonymous object!
Not the same anonymous object!
We are both the same type!

obj is an instance of: <>f__AnonymousType0`3
Base class of <>f__AnonymousType0`3 is System.Object
obj.ToString() = { Color = Bright Pink, Make = Saab, CurrentSpeed = 55 }
obj.GetHashCode() = 2038548792

obj is an instance of: <>f__AnonymousType0`3
Base class of <>f__AnonymousType0`3 is System.Object
obj.ToString() = { Color = Bright Pink, Make = Saab, CurrentSpeed = 55 }
obj.GetHashCode() = 2038548792

Press any key to continue . . .

```

Figure 12-6. The equality of anonymous types

When you run this test code, you will see that the first conditional test where you call `Equals()` returns true, and therefore the message “Same anonymous object!” prints out to the screen. This is because the compiler-generated `Equals()` method makes use of value-based semantics when testing for equality (e.g., checking the value of each field of the objects being compared).

However, the second conditional test (which makes use of the C# equality operator, `==`) prints out “Not the same anonymous object!”, which may seem at first glance to be a bit counterintuitive. This result is due to the fact that anonymous types do *not* receive overloaded versions of the C# equality operators (`==` and `!=`). Given this, when you test for equality of anonymous types using the C# equality operators (rather than the `Equals()` method), the *references*, not the values maintained by the objects, are being tested for equality.

Last but not least, in our final conditional test (where we examine the underlying type name), we find that the anonymous types are instances of the same compiler-generated class type (in this example, `<f__AnonymousType0`3`), due to the fact that `firstCar` and `secondCar` have the same properties (`Color`, `Make`, and `CurrentSpeed`).

This illustrates an important but subtle point: the compiler will only generate a new class definition when an anonymous type contains *unique* names of the anonymous type. Thus, if you declare identical anonymous types (again, meaning the same names) within the same assembly, the compiler generates only a single anonymous type definition.

Anonymous Types Containing Anonymous Types

It is possible to create an anonymous type that is composed of other anonymous types. For example, assume you wish to model a purchase order that consists of a timestamp, a price point, and the automobile purchased. Here is a new (slightly more sophisticated) anonymous type representing such an entity:

```
// Make an anonymous type that is composed of another.
var purchaseItem = new {
    TimeBought = DateTime.Now,
    ItemBought = new {Color = "Red", Make = "Saab", CurrentSpeed = 55},
    Price = 34.000};

ReflectOverAnonymousType(purchaseItem);
```

At this point, you should understand the syntax used to define anonymous types, but you may still be wondering exactly where (and when) to use this new language feature. To be blunt, anonymous type declarations should be used sparingly, typically only when making use of the LINQ technology set (see Chapter 14). You would never want to abandon the use of strongly typed classes/structures simply for the sake of doing so, given anonymous types’ numerous limitations, which include the following:

- You don’t control the name of the anonymous type.
- Anonymous types always extend `System.Object`.
- The fields and properties of an anonymous type are always read-only.
- Anonymous types cannot support events, custom methods, custom operators, or custom overrides.
- Anonymous types are always implicitly sealed.
- Anonymous types are always created using the default constructor.

However, when programming with the LINQ technology set, you will find that in many cases this syntax can be very helpful when you want to quickly model the overall *shape* of an entity rather than its functionality.

■ **Source Code** The AnonymousTypes project can be found under the Chapter 12 subdirectory.

Working with Pointer Types

And now, the final topic of the chapter, which most likely will be the least-used of all C# features for the vast majority of your .NET projects. In Chapter 4, you learned that the .NET platform defines two major categories of data: value types and reference types. Truth be told, however, there is a third category: *pointer types*. To work with pointer types, we get specific operators and keywords that allow us to bypass the CLR's memory-management scheme and take matters into our own hands (see Table 12-3).

Table 12-3. Pointer-Centric C# Operators and Keywords

Operator/Keyword	Meaning in Life
*	This operator is used to create a pointer variable (i.e., a variable that represents a direct location in memory). As in C++, this same operator is used for pointer indirection.
&	This operator is used to obtain the address of a variable in memory.
->	This operator is used to access fields of a type that is represented by a pointer (the unsafe version of the C# dot operator).
[]	This operator (in an unsafe context) allows you to index the slot pointed to by a pointer variable (if you're a C++ programmer, you will recall the interplay between a pointer variable and the [] operator).
++, --	In an unsafe context, the increment and decrement operators can be applied to pointer types.
+, -	In an unsafe context, the addition and subtraction operators can be applied to pointer types.
==, !=, <, >, <=, =>	In an unsafe context, the comparison and equality operators can be applied to pointer types.
stackalloc	In an unsafe context, the <code>stackalloc</code> keyword can be used to allocate C# arrays directly on the stack.
fixed	In an unsafe context, the <code>fixed</code> keyword can be used to temporarily fix a variable so that its address may be found.

Now, before we dig into the details, let me again point out that you will *seldom if ever* need to make use of pointer types. Although C# does allow you to drop down to the level of pointer manipulations, understand that the .NET runtime has absolutely no clue of your intentions. Thus, if you mismanage a pointer, you are the one in charge of dealing with the consequences. Given these warnings, when exactly would you need to work with pointer types? There are two common situations:

- You are looking to optimize select parts of your application by directly manipulating memory outside the management of the CLR.
- You are calling methods of a C-based .dll or COM server that demand pointer types as parameters. Even in this case, you can often bypass pointer types in favor of the `System.IntPtr` type and members of the `System.Runtime.InteropServices.Marshal` type.

In the event that you do decide to make use of this C# language feature, you are required to inform the C# compiler (`csc.exe`) of your intentions by enabling your project to support “unsafe code.” To do so at the command line, simply supply the `/unsafe` flag as an argument:

```
csc /unsafe *.cs
```

From Visual Studio 2010, you will need to access your project’s Properties page and check the Allow Unsafe Code box from the Build tab (see Figure 12-7). To experiment with pointer types, create a new Console Application project named `UnsafeCode` and enable unsafe code.




Figure 12-7. Enabling unsafe code using Visual Studio 2010

Note In the examples that follow, I’m assuming you have some background in C++ pointer manipulation. If this is not true, feel free to skip this topic entirely. Again, writing unsafe code will not be a common task for the vast majority of C# applications.

The unsafe Keyword

When you wish to work with pointers in C#, you must specifically declare a block of “unsafe code” using the `unsafe` keyword (any code that is not marked with the `unsafe` keyword is considered “safe” automatically). For example, the following `Program` class declares a scope of unsafe code within the safe `Main()` method:

```
class Program
{
    static void Main(string[] args)
    {
        unsafe
        {
            // Work with pointer types here!
        }
        // Can't work with pointers here!
    }
}
```

In addition to declaring a scope of unsafe code within a method, you can build structures, classes, type members, and parameters that are “unsafe.” Here are a few examples to gnaw on (no need to define these types in your current project):

```
// This entire structure is "unsafe" and can
// be used only in an unsafe context.
public unsafe struct Node
{
    public int Value;
    public Node* Left;
    public Node* Right;
}

// This struct is safe, but the Node2* members
// are not. Technically, you may access "Value" from
// outside an unsafe context, but not "Left" and "Right".
public struct Node2
{
    public int Value;

    // These can be accessed only in an unsafe context!
    public unsafe Node2* Left;
    public unsafe Node2* Right;
}
```

Methods (static or instance level) may be marked as `unsafe` as well. For example, assume that you know a particular static method will make use of pointer logic. To ensure that this method can be called only from an unsafe context, you could define the method as follows:

```
unsafe static void SquareIntPtr(int* myIntPtr)
{
    // Square the value just for a test.
    *myIntPtr *= *myIntPtr;
}
```

The configuration of our method demands that the caller invoke `SquareIntPtr()` as follows:

```
static void Main(string[] args)
{
    unsafe
    {
        int myInt = 10;

        // OK, because we are in an unsafe context.
        SquareIntPtr(&myInt);
        Console.WriteLine("myInt: {0}", myInt);
    }

    int myInt2 = 5;

    // Compiler error! Must be in unsafe context!
    SquareIntPtr(&myInt2);
    Console.WriteLine("myInt: {0}", myInt2);
}
```

If you would rather not force the caller to wrap the invocation within an unsafe context, you could update `Main()` with the `unsafe` keyword. In this case, the following code would compile:

```
unsafe static void Main(string[] args)
{
    int myInt2 = 5;
    SquareIntPtr(&myInt2);
    Console.WriteLine("myInt: {0}", myInt2);
}
```

Working with the * and & Operators

Once you have established an unsafe context, you are then free to build pointers to data types using the `*` operator and obtain the address of said pointer using the `&` operator. Unlike in C or C++, in C# the `*` operator is applied to the underlying type only, not as a prefix to each pointer variable name. For example, consider the following code, which illustrates both the correct and incorrect ways to declare pointers to integer variables:

```
// No! This is incorrect under C#!
int *pi, *pj;

// Yes! This is the way of C#.
int* pi, pj;
```

Consider the following unsafe method:

```
unsafe static void PrintValueAndAddress()
{
    int myInt;

    // Define an int pointer, and
```

```
// assign it the address of myInt.
int* ptrToMyInt = &myInt;

// Assign value of myInt using pointer indirection.
*ptrToMyInt = 123;

// Print some stats.
Console.WriteLine("Value of myInt {0}", myInt);
Console.WriteLine("Address of myInt {0:X}", (int)&ptrToMyInt);
}
```

An Unsafe (and Safe) Swap Function

Of course, declaring pointers to local variables simply to assign their value (as in the previous example) is never required and not altogether useful. To illustrate a more practical example of unsafe code, assume you wish to build a swap function using pointer arithmetic:

```
unsafe public static void UnsafeSwap(int* i, int* j)
{
    int temp = *i;
    *i = *j;
    *j = temp;
}
```

Very C-like, don't you think? However, given your work in Chapter, you should be aware that you could write the following safe version of your swap algorithm using the C# `ref` keyword:

```
public static void SafeSwap(ref int i, ref int j)
{
    int temp = i;
    i = j;
    j = temp;
}
```

The functionality of each method is identical, thus reinforcing the point that direct pointer manipulation is not a mandatory task under C#. Here is the calling logic using a safe `Main()`, with an unsafe context:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Calling method with unsafe code *****");

    // Values for swap.
    int i = 10, j = 20;

    // Swap values "safely."
    Console.WriteLine("\n***** Safe swap *****");
    Console.WriteLine("Values before safe swap: i = {0}, j = {1}", i, j);
    SafeSwap(ref i, ref j);
    Console.WriteLine("Values after safe swap: i = {0}, j = {1}", i, j);

    // Swap values "unsafely."
}
```

```

Console.WriteLine("\n***** Unsafe swap *****");
Console.WriteLine("Values before unsafe swap: i = {0}, j = {1}", i, j);
unsafe { UnsafeSwap(&i, &j); }
Console.WriteLine("Values after unsafe swap: i = {0}, j = {1}", i, j);
Console.ReadLine();
}

```

Field Access via Pointers (the -> Operator)

Now assume you have defined a simple, safe Point structure as follows:

```

struct Point
{
    public int x;
    public int y;

    public override string ToString()
    {
        return string.Format("{0}, {1}", x, y);
    }
}

```

If you declare a pointer to a Point type, you will need to make use of the pointer field-access operator (represented by ->) to access its public members. As shown in Table 12-3, this is the unsafe version of the standard (safe) dot operator (.). In fact, using the pointer indirection operator (*), it is possible to dereference a pointer to (once again) apply the dot operator notation. Check out the unsafe method:

```

unsafe static void UsePointerToPoint()
{
    // Access members via pointer.
    Point point;
    Point* p = &point;
    p->x = 100;
    p->y = 200;
    Console.WriteLine(p->ToString());

    // Access members via pointer indirection.
    Point point2;
    Point* p2 = &point2;
    (*p2).x = 100;
    (*p2).y = 200;
    Console.WriteLine((*p2).ToString());
}

```

The stackalloc Keyword

In an unsafe context, you may need to declare a local variable that allocates memory directly from the call stack (and is therefore not subject to .NET garbage collection). To do so, C# provides the `stackalloc` keyword, which is the C# equivalent to the `_alloca` function of the C runtime library. Here is a simple example:

```
unsafe static void UnsafeStackAlloc()
{
    char* p = stackalloc char[256];
    for (int k = 0; k < 256; k++)
        p[k] = (char)k;
}
```

Pinning a Type via the fixed Keyword

As you saw in the previous example, allocating a chunk of memory within an unsafe context may be facilitated via the `stackalloc` keyword. By the very nature of this operation, the allocated memory is cleaned up as soon as the allocating method has returned (as the memory is acquired from the stack). However, assume a more complex example. During our examination of the `->` operator, you created a value type named `Point`. Like all value types, the allocated memory is popped off the stack once the executing scope has terminated. For the sake of argument, assume `Point` was instead defined as a *reference* type:

```
class PointRef // <= Renamed and retyped.
{
    public int x;
    public int y;
    public override string ToString()
    {
        return string.Format("{0}, {1}", x, y);
    }
}
```

As you are aware, if the caller declares a variable of type `Point`, the memory is allocated on the garbage-collected heap. The burning question then becomes, “What if an unsafe context wishes to interact with this object (or any object on the heap)?” Given that garbage collection can occur at any moment, imagine the problems encountered when accessing the members of `Point` at the very point in time such a sweep of the heap is under way. Theoretically, it is possible that the unsafe context is attempting to interact with a member that is no longer accessible or has been repositioned on the heap after surviving a generational sweep (which is an obvious problem).

To lock a reference type variable in memory from an unsafe context, C# provides the `fixed` keyword. The `fixed` statement sets a pointer to a managed type and “pins” that variable during the execution of the code. Without `fixed`, pointers to managed variables would be of little use, since garbage collection could relocate the variables unpredictably. (In fact, the C# compiler will not allow you to set a pointer to a managed variable except in a `fixed` statement.)

Thus, if you create a `PointRef` type and want to interact with its members, you must write the following code (or receive a compiler error):

```
unsafe public static void UseAndPinPoint()
{
```

```

PointRef pt = new PointRef ();
pt.x = 5;
pt.y = 6;

// pin pt in place so it will not
// be moved or GC-ed.
fixed (int* p = &pt.x)
{
    // Use int* variable here!
}

// pt is now unpinned, and ready to be GC-ed once
// the method completes.
Console.WriteLine ("Point is: {0}", pt);
}

```

In a nutshell, the `fixed` keyword allows you to build a statement that locks a reference variable in memory, such that its address remains constant for the duration of the statement (or scope block). Any time you interact with a reference type from within the context of unsafe code, pinning the reference is a must.

The `sizeof` Keyword

The final unsafe-centric C# keyword to consider is `sizeof`. As in C++, the C# `sizeof` keyword is used to obtain the size in bytes of a value type (never a reference type), and it may only be used within an unsafe context. As you may imagine, this ability can prove helpful when you're interacting with unmanaged C-based APIs. Its usage is straightforward:

```

unsafe static void UseSizeOfOperator()
{
    Console.WriteLine("The size of short is {0}.", sizeof(short));
    Console.WriteLine("The size of int is {0}.", sizeof(int));
    Console.WriteLine("The size of long is {0}.", sizeof(long));
}

```

As `sizeof` will evaluate the number of bytes for any `System.ValueType`-derived entity, you can obtain the size of custom structures as well. For example, we could pass the `Point` structure into `sizeof` as follows:

```

unsafe static void UseSizeOfOperator()
{
    ...
    Console.WriteLine("The size of Point is {0}.", sizeof(Point));
}

```

Source Code The `UnsafeCode` project can be found under the Chapter 12 subdirectory.

That wraps up our look at some of the more powerful features of the C# programming language. In the next chapter, you will see some of these concepts (specifically extension methods and anonymous types) doing very useful things in the context of LINQ to Objects.

Summary

The purpose of this chapter was to deepen your understanding of the C# programming language. First you investigated various advanced type construction techniques (indexer methods, overloaded operators, and custom conversion routines).

Next, you examined the role of extension methods, anonymous types, and partial methods. As you'll see in some detail in the next chapter, these features are very useful when working with LINQ-centric APIs (though you can use them anywhere in your code, should they be useful). Recall that anonymous methods allow you to quickly model the "shape" of a type, while extension methods allow you to tack on new functionality to types, without the need to subclass.

You spent the remainder of this chapter examining a small set of lesser-known keywords (`sizeof`, `unsafe`, and so forth), and during the process learned how to work with raw pointer types. As stated throughout our examination of pointer types, the vast majority of your C# applications will never need to make use of them.



LINQ to Objects

Regardless of the type of application you are creating using the .NET platform, your program will certainly need to access some form of data as it executes. To be sure, data can be found in numerous locations, including XML files, relational databases, in-memory collections, and primitive arrays. Historically speaking, based on the location of said data, programmers needed to make use of very different and unrelated APIs. The Language Integrated Query (LINQ) technology set, introduced initially in .NET 3.5, provides a concise, symmetrical, and strongly typed manner to access a wide variety of data stores. In this chapter you will begin your investigation of LINQ, by focusing on LINQ to Objects.

Before you dive into LINQ to Objects proper, the first part of this chapter quickly reviews the key C# programming constructs which enable LINQ. As you work through this chapter, you will find that implicitly typed local variables, object initialization syntax, lambda expressions, extension methods, and anonymous types will be quite useful.

Once this supporting infrastructure is reviewed, the remainder of the chapter will introduce you to the LINQ model and its role in the .NET platform. Here, you will come to learn the role of query operators and query expressions, which allow you to define statements that will interrogate a data source to yield the requested result set. Along the way, you will build numerous LINQ examples that interact with data contained within arrays as well as various collection types (both generic and nongeneric) and understand the assemblies, namespaces, and types that represent the LINQ to Objects API.

Note The information in this chapter is the foundation for future chapters of the book which examine additional LINQ technologies including LINQ to XML (Chapter 25), Parallel LINQ (Chapter 19), and LINQ to Entities (Chapter 23).

LINQ Specific Programming Constructs

From a very high level, LINQ can be understood as a strongly typed query language, embedded directly into the grammar of C# itself. Using LINQ, you can build any number of expressions which have a look-and-feel similar to that of a database SQL query. However, a LINQ query can be applied to any number of data stores, including stores that have nothing to do with a literal relational database.

■ **Note** Although LINQ queries look similar to SQL queries, the syntax is *not* identical. In fact, many LINQ queries seem to be the exact opposite format of a similar database query! If you attempt to map LINQ directly to SQL, you will surely become frustrated. To keep your sanity, I'd recommend that you try your best to regard LINQ queries as unique entities, which just "happen to look" similar to SQL.

When LINQ was first introduced to the .NET platform in version 3.5, the C# (and VB) languages were each expanded with a large number of new programming constructs used to support the LINQ technology set. Specifically, the C# language uses the following core LINQ-centric features:

- Implicitly typed local variables
- Object/collection initialization syntax
- Lambda expressions
- Extension methods
- Anonymous types

These features have already been explored in detail within various chapters of the text. However, to get the ball rolling, let's quickly review each feature in turn, just to make sure we are all in the proper mindset.

Implicit Typing of Local Variables

In Chapter 3, you learned about the `var` keyword of C#. This keyword allows you to define a local variable without explicitly specifying the underlying data type. The variable, however, is strongly typed as the compiler will determine the correct data type based on the initial assignment. Recall the following code example from Chapter 3:

```
static void DeclareImplicitVars()
{
    // Implicitly typed local variables.
    var myInt = 0;
    var myBool = true;
    var myString = "Time, marches on...";

    // Print out the underlying type.
    Console.WriteLine("myInt is a: {0}", myInt.GetType().Name);
    Console.WriteLine("myBool is a: {0}", myBool.GetType().Name);
    Console.WriteLine("myString is a: {0}", myString.GetType().Name);
}
```

This language feature is very helpful, and often mandatory, when using LINQ. As you will see during this chapter, many LINQ queries will return a sequence of data types which are not known until compile time. Given that the underlying data type is not known until the application is compiled, you obviously can't declare a variable explicitly!

Object and Collection Initialization Syntax

Chapter 5 explored the role of object initialization syntax, which allows you to create a class or structure variable, and set any number of its public properties, in one fell swoop. The end result is a very compact (yet still easy on the eyes) syntax which can be used to get your objects ready for use. Also recall from Chapter 10, the C# language allows you to use a very similar syntax to initialize collections of objects. Consider the following code snippet which uses collection initialization syntax to fill a `List<T>` of `Rectangle` objects, each of which maintains two `Point` objects to represent an (x,y) position:

```
List<Rectangle> myListOfRects = new List<Rectangle>
{
    new Rectangle {TopLeft = new Point { X = 10, Y = 10 },
                  BottomRight = new Point { X = 200, Y = 200 }},
    new Rectangle {TopLeft = new Point { X = 2, Y = 2 },
                  BottomRight = new Point { X = 100, Y = 100 }},
    new Rectangle {TopLeft = new Point { X = 5, Y = 5 },
                  BottomRight = new Point { X = 90, Y = 75 }}
};
```

While you are never required to use collection/object initialization syntax, you do end up with a more compact code base. Furthermore, this syntax, when combined with implicit typing of local variables, allows you to declare an anonymous type, which is very useful when creating a LINQ projection. You'll learn about LINQ projections later in this chapter.

Lambda Expressions

The C# lambda operator (`=>`) was fully explored in Chapter 11. Recall that this operator allows us to build a lambda expression, which can be used any time you invoke a method that requires a strongly typed delegate as an argument. Lambdas greatly simplify how you work with .NET delegates, in that they reduce the amount of code you have to author by hand. Recall that a lambda expression can be broken down into the following usage:

```
ArgumentsToProcess => StatementsToProcessThem
```

In Chapter 11, I walked you through how to interact with the `FindAll()` method of the generic `List<T>` class using three different approaches. After working with the raw `Predicate<T>` delegate and a C# anonymous method, you eventually arrived with the following (extremely concise) iteration which used the following lambda expression:

```
static void LambdaExpressionSyntax()
{
    // Make a list of integers.
    List<int> list = new List<int>();
    list.AddRange(new int[] { 20, 1, 4, 8, 9, 44 });

    // C# lambda expression.
    List<int> evenNumbers = list.FindAll(i => (i % 2) == 0);

    Console.WriteLine("Here are your even numbers:");
    foreach (int evenNumber in evenNumbers)
```

```

    {
        Console.WriteLine("{0}\t", evenNumber);
    }
    Console.WriteLine();
}

```

Lambdas will be very useful when working with the underlying object model of LINQ. As you will soon find out, the C# LINQ query operators are simply a shorthand notation for calling true-blue methods on a class named `System.Linq.Enumerable`. These methods typically always require delegates (the `Func<>` delegate in particular) as parameters, which are used to process your data to yield the correct result set. Using lambdas, you can streamline your code, and allow the compiler to infer the underlying delegate.

Extension Methods

C# extension methods allow you to tack on new functionality to existing classes without the need to subclass. As well, extension methods allow you to add new functionality to sealed classes and structures, which could never be subclassed in the first place. Recall from Chapter 12, when you author an extension method, the first parameter is qualified with the `this` operator, and marks the type being extended. Also recall that extension methods must always be defined within a static class, and must therefore also be declared using the `static` keyword. For an example, see the following code:

```

namespace MyExtensions
{
    static class ObjectExtensions
    {
        // Define an extension method to System.Object.
        public static void DisplayDefiningAssembly(this object obj)
        {
            Console.WriteLine("{0} lives here:\n\t->{1}\n",
                obj.GetType().Name,
                Assembly.GetAssembly(obj.GetType()));
        }
    }
}

```

To use this extension, an application must first set a reference to the external assembly that contains the extension method implementation using the Add Reference dialog of Visual Studio 2010. At this point, simply import the defining namespace, and code away:

```

static void Main(string[] args)
{
    // Since everything extends System.Object, all classes and structures
    // can use this extension.
    int myInt = 12345678;
    myInt.DisplayDefiningAssembly();

    System.Data.DataSet d = new System.Data.DataSet();
    d.DisplayDefiningAssembly();
    Console.ReadLine();
}

```

When you work with LINQ, you will seldom, if ever, be required to manually build your own extension methods. However, as you create LINQ query expressions, you will in fact be making use of numerous extension methods already defined by Microsoft. In fact, each C# LINQ query operator is a shorthand notation for making a manual call on an underlying extension method, typically defined by the `System.Linq.Enumerable` utility class.

Anonymous Types

The final C# language feature I'd like to quickly review is that of anonymous types which was fully explored in Chapter 12. This feature can be used to quickly model the "shape" of data, by allowing the compiler to generate a new class definition at compile time, based on a supplied set of name/value pairs. Recall that this type will be composed using value based semantics, and each virtual method of `System.Object` will be overridden accordingly. To define an anonymous type, declare an implicitly typed variable and specify the data's shape using object initialization syntax:

```
// Make an anonymous type that is composed of another.  
var purchaseItem = new {  
    TimeBought = DateTime.Now,  
    ItemBought = new {Color = "Red", Make = "Saab", CurrentSpeed = 55},  
    Price = 34.00};
```

LINQ makes frequent use of anonymous types when you wish to project new forms of data on the fly. For example, assume you have a collection of `Person` objects, and wish to use LINQ to obtain information on the age and social security number of each. Using a LINQ projection, you can allow the compiler to generate a new anonymous type that contains your information.

Understanding the Role of LINQ

That wraps up our quick review of the C# language features that allow LINQ to work its magic. However, why have LINQ in the first place? Well, as software developers, it is hard to deny that the vast majority of our programming time is spent obtaining and manipulating data. When speaking of "data," it is very easy to immediately envision information contained within relational databases. However, another popular location in which data exists is within XML documents (*.config files, locally persisted `DataSets`, or in-memory data returned from WCF services).

Data can be found in numerous places beyond these two common homes for information. For instance, say you have an array or generic `List<T>` type containing 300 integers, and you want to obtain a subset that meets a given criterion (e.g., only the odd or even members in the container, only prime numbers, only nonrepeating numbers greater than 50). Or perhaps you are making use of the reflection APIs and need to obtain only metadata descriptions for each class deriving from a particular parent class within an array of `Types`. Indeed, data is *everywhere*.

Prior to .NET 3.5, interacting with a particular flavor of data required programmers to make use of very diverse APIs. Consider, for example, Table 13-1, which illustrates several common APIs used to access various types of data (I'm sure you can think of many other examples).

Table 13-1. Ways to Manipulate Various Types of Data

The Data You Want	How to Obtain It
Relational data	<code>System.Data.dll</code> , <code>System.Data.SqlClient.dll</code> , etc.
XML document data	<code>System.Xml.dll</code>
Metadata tables	The <code>System.Reflection</code> namespace
Collections of objects	<code>System.Array</code> and the <code>System.Collections/System.Collections.Generic</code> namespaces

Of course, nothing is wrong with these approaches to data manipulation. In fact, when programming with .NET 4.0/C# 2010, you can (and will) certainly make direct use of ADO.NET, the XML namespaces, reflection services, and the various collection types. However, the basic problem is that each of these APIs is an island unto itself, which offers very little in the way of integration. True, it is possible (for example) to save an ADO.NET `DataSet` as XML, and then manipulate it via the `System.Xml` namespaces, but nonetheless, data manipulation remains rather asymmetrical.

The LINQ API is an attempt to provide a consistent, symmetrical manner in which programmers can obtain and manipulate “data” in the broad sense of the term. Using LINQ, you are able to create directly within the C# programming language constructs called query expressions. These query expressions are based on numerous query operators that have been intentionally designed to look and feel very similar (but not quite identical) to a SQL expression.

The twist, however, is that a query expression can be used to interact with numerous types of data—even data that has nothing to do with a relational database. Strictly speaking, “LINQ” is the term used to describe this overall approach to data access. However, based on where you are applying your LINQ queries, you will encounter various terms, such as the following:

- **LINQ to Objects:** This term refers to the act of applying LINQ queries to arrays and collections.
- **LINQ to XML:** This term refers to the act of using LINQ to manipulate and query XML documents.
- **LINQ to DataSet:** This term refers to the act of applying LINQ queries to ADO.NET `DataSet` objects.
- **LINQ to Entities:** This aspect of LINQ allows you to make use of LINQ queries within the ADO.NET Entity Framework (EF) API.
- **Parallel LINQ** (aka, PLINQ): Allows for parallel processing of data returned from a LINQ query.

To be sure, Microsoft seems quite dedicated to integrating LINQ support deeply within the .NET programming environment. As time goes on, it would be very safe to bet that LINQ will become an integral part of the .NET base class libraries, languages, and Visual Studio itself.

LINQ Expressions Are Strongly Typed

It is also very important to point out that a LINQ query expression (unlike a traditional SQL statement) is *strongly typed*. Therefore, the C# compiler will keep us honest and make sure that these expressions are syntactically well formed. On a related note, query expressions have metadata representation within the assembly that makes use of them, as the C# LINQ query operators always make a rich underlying object model. Tools such as Visual Studio 2010 can use this metadata for useful features such as IntelliSense, autocompletion, and so forth.

The Core LINQ Assemblies

As mentioned in Chapter 2, the New Project dialog of Visual Studio 2010 has the option of selecting which version of the .NET platform you wish to compile against. When you opt to compile against .NET 3.5 or higher, each of the project templates will automatically reference the key LINQ assemblies, which can be viewed using the Solution Explorer. Table 13-2 documents the role of the key LINQ assemblies. However, you will encounter additional LINQ libraries over the remainder of this book.

Table 13-2. Core LINQ-centric Assemblies

Assembly	Meaning in Life
System.Core.dll	Defines the types that represent the core LINQ API. This is the one assembly you must have access to if you wish to use any LINQ API, including LINQ to Objects.
System.Data.DataSetExtensions.dll	Defines a handful of types to integrate ADO.NET types into the LINQ programming paradigm (LINQ to DataSet).
System.Xml.Linq.dll	Provides functionality for using LINQ with XML document data (LINQ to XML).

In order to work with LINQ to Objects, you must make sure that every C# code file that contains LINQ queries imports the `System.Linq` namespace (defined within `System.Core.dll`). If you do not do so, you will run into a number of problems. As a very good rule of thumb, if you see a compiler error looking similar to this:

```
Error 1 Could not find an implementation of the query pattern for source type 'int[]'.
'Where' not found. Are you missing a reference to 'System.Core.dll' or a using directive
for 'System.Linq'?
```

The chances are extremely good that your C# file does not have the following using directive (and believe me, I speak from experience!):

```
using System.Linq;
```

Applying LINQ Queries to Primitive Arrays

To begin examining LINQ to Objects, let's build an application that will apply LINQ queries to various array objects. Create a Console Application named LinqOverArray, and define a static helper method within the `Program` class named `QueryOverStrings()`. In this method, create a `string` array containing six or so items of your liking (here I listed out a batch of video games I am currently attempting to finish). Make sure to have at least two entries which contain numerical values, and a few that have embedded spaces.

```
static void QueryOverStrings()
{
    // Assume we have an array of strings.
    string[] currentVideoGames = {"Morrowind", "Uncharted 2",
                                  "Fallout 3", "Daxter", "System Shock 2"};
}
```

Now, update `Main()` to invoke `QueryOverStrings()`:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with LINQ to Objects *****\n");
    QueryOverStrings();
    Console.ReadLine();
}
```

When you have any array of data, it is very common to extract a subset of items based on a given requirement. Maybe you want to obtain only the subitems that contain a number (e.g., System Shock 2, Uncharted 2, and Fallout 3), have more or less than some number of characters, or don't contain embedded spaces (e.g., Morrowind or Daxter). While you could certainly perform such tasks using members of the `System.Array` type and a bit of elbow grease, LINQ query expressions can greatly simplify the process.

Going on the assumption that you wish to obtain from the array only items that contain an embedded blank space, and you want these items listed in alphabetical order, you could build the following LINQ query expression:

```
static void QueryOverStrings()
{
    // Assume we have an array of strings.
    string[] currentVideoGames = {"Morrowind", "Uncharted 2",
                                  "Fallout 3", "Daxter", "System Shock 2"};

    // Build a query expression to find the items in the array
    // that have an embedded space.
    IEnumerable<string> subset = from g in currentVideoGames
                                  where g.Contains(" ") orderby g select g;

    // Print out the results.
    foreach (string s in subset)
        Console.WriteLine("Item: {0}", s);
}
```

Notice that the query expression created here makes use of the `from`, `in`, `where`, `orderby`, and `select` LINQ query operators. You will dig into the formalities of query expression syntax later in this chapter. However, even now you should be able to read this statement roughly as “Give me the items inside of `currentVideoGames` that contain a space, ordered alphabetically.”

Here, each item that matches the search criteria has been given the name “`g`” (as in “game”); however, any valid C# variable name would do:

```
IEnumerable<string> subset = from game in currentVideoGames
    where game.Contains(" ")
    orderby
    game select game;
```

Notice that the returned sequence is held in a variable named `subset`, typed as a type that implements the generic version of `IEnumerable<T>`, where `T` is of type `System.String` (after all, you are querying an array of strings). Once you obtain the result set, you then simply print out each item using a standard `foreach` construct. If you run your application, you will find the following output:

```
***** Fun with LINQ to Objects *****
Item: Fallout 3
Item: System Shock 2
Item: Uncharted 2
```

Once Again, Without LINQ

To be sure, LINQ is never necessary. If you so choose, you could have found the same result set by forgoing LINQ altogether and making use of programming primitives such as `if` statements and `for` loops. Here is a method which yields the same result as the `QueryOverStrings()` method, but in a much more verbose manner:

```
static void QueryOverStringsLongHand()
{
    // Assume we have an array of strings.
    string[] currentVideoGames = {"Morrowind", "Uncharted 2",
        "Fallout 3", "Daxter", "System Shock 2"};

    string[] gamesWithSpaces = new string[5];

    for (int i = 0; i < currentVideoGames.Length; i++)
    {
        if (currentVideoGames[i].Contains(" "))
            gamesWithSpaces[i] = currentVideoGames[i];
    }

    // Now sort them.
    Array.Sort(gamesWithSpaces);

    // Print out the results.
    foreach (string s in gamesWithSpaces)
    {
```

```

    if( s != null)
        Console.WriteLine("Item: {0}", s);
    }
    Console.WriteLine();
}

```

While I am sure you can think of ways to tweak the previous method, the fact remains that LINQ queries can be used to radically simplify the process of extracting new subsets of data from a source. Rather than building nested loops, complex if/else logic, temporary data types, and so on, the C# compiler will perform the dirty work on your behalf, once you create a fitting LINQ query.

Reflecting Over a LINQ Result Set

Now, assume the `Program` class defines an additional helper function named `ReflectOverQueryResults()` that will print out various details of the LINQ result set (note the parameter is a `System.Object`, to account for multiple types of result sets):

```

static void ReflectOverQueryResults(object resultSet)
{
    Console.WriteLine("***** Info about your query *****");
    Console.WriteLine("resultSet is of type: {0}", resultSet.GetType().Name);
    Console.WriteLine("resultSet location: {0}",
        resultSet.GetType().Assembly.GetName().Name);
}

```

Assuming you have called this method within `QueryOverStrings()` directly after printing out the obtained subset, if you run the application, you will see the subset is really an instance of the generic `OrderedEnumerable<TElement, TKey>` type (represented in terms of CIL code as `OrderedEnumerable`2`), which is an internal abstract type residing in the `System.Core.dll` assembly:

```

***** Info about your query *****
resultSet is of type: OrderedEnumerable`2
resultSet location: System.Core

```

Note Many of the types that represent a LINQ result are hidden by the Visual Studio 2010 object browser. Make use of `ildasm.exe` or `reflector.exe` to see these internal, hidden types if you are interested.

LINQ and Implicitly Typed Local Variables

While the current sample program makes it relatively easy to determine that the result set can be captured as an enumeration of `string` object (e.g., `IEnumerable<string>`), I would guess that it is *not* clear that subset is really of type `OrderedEnumerable<TElement, TKey>`.

Given the fact that LINQ result sets can be represented using a good number of types in various LINQ-centric namespaces, it would be tedious to define the proper type to hold a result set, because in

many cases the underlying type may not be obvious or even directly accessible from your code base (and as you will see, in some cases the type is generated at compile time).

To further accentuate this point, consider the following additional helper method defined within the `Program` class (which I assume you will invoke from within the `Main()` method):

```
static void QueryOverInts()
{
    int[] numbers = {10, 20, 30, 40, 1, 2, 3, 8};

    // Only print items less than 10.
    IEnumerable<int> subset = from i in numbers where i < 10 select i;

    foreach (int i in subset)
        Console.WriteLine("Item: {0}", i);
    ReflectOverQueryResults(subset);
}
```

In this case, the `subset` variable is a completely different underlying type. This time, the type implementing the `IEnumerable<int>` interface is a low-level class named `WhereArrayIterator`1`:

```
Item: 1
Item: 2
Item: 3
Item: 8

***** Info about your query *****
resultSet is of type: WhereArrayIterator`1
resultSet location: System.Core
```

Given the fact that the exact underlying type of a LINQ query is certainly not obvious, these first examples have represented the query results as an `IEnumerable<T>` variable, where `T` is the type of data in the returned sequence (`string`, `int`, etc). However, this is still rather cumbersome. To add insult to injury, given that `IEnumerable<T>` extends the nongeneric `IEnumerable` interface, it would also be permissible to capture the result of a LINQ query as follows:

```
System.Collections.IEnumerable subset =
    from i in numbers where i < 10 select i;
```

Thankfully, implicit typing cleans things up considerably when working with LINQ queries:

```
static void QueryOverInts()
{
    int[] numbers = {10, 20, 30, 40, 1, 2, 3, 8};

    // Use implicit typing here...
    var subset = from i in numbers where i < 10 select i;

    // ...and here.
    foreach (var i in subset)
        Console.WriteLine("Item: {0} ", i);
```

```
    ReflectOverQueryResults(subset);
}
```

As a rule of thumb, you will always want to make use of implicit typing when capturing the results of a LINQ query. Just remember, however, that (in a vast majority of cases), the *real* return value is a type implementing the generic `IEnumerable<T>` interface.

Exactly what this type is under the covers (`OrderedEnumerable<TElement, TKey>`, `WhereArrayIterator<T>`, etc) is irrelevant, and not necessary to discover. As seen in the previous code example, you can simply use the `var` keyword within a `foreach` construct to iterate over the fetched data.

LINQ and Extension Methods

Although the current example does not have you author any extension methods directly, you are in fact using them seamlessly in the background. LINQ query expressions can be used to iterate over data containers that implement the generic `IEnumerable<T>` interface. However, the .NET `System.Array` class type (used to represent our array of strings and array of integers) does *not* implement this contract:

```
// The System.Array type does not seem to implement the correct
// infrastructure for query expressions!
public abstract class Array : ICloneable, IList, ICollection,
    IEnumerable, IStructuralComparable, IStructuralEquatable

{
    ...
}
```

While `System.Array` does not directly implement the `IEnumerable<T>` interface, it indirectly gains the required functionality of this type (as well as many other LINQ-centric members) via the static `System.Linq.Enumerable` class type.

This utility class defines a good number of generic extension methods (such as `Aggregate<T>()`, `First<T>()`, `Max<T>()`, etc.), which `System.Array` (and other types) acquire in the background. Thus, if you apply the dot operator on the `currentVideoGames` local variable, you will find a good number of members *not* found within the formal definition of `System.Array` (see Figure 13-1).




Figure 13-1. The `System.Array` type has been extended with members of `System.Linq.Enumerable`

The Role of Deferred Execution

Another important point regarding LINQ query expressions is that they are not actually evaluated until you iterate over the sequence. Formally speaking, this is termed deferred execution. The benefit of this approach is that you are able to apply the same LINQ query multiple times to the same container, and rest assured you are obtaining the latest and greatest results. Consider the following update to the `QueryOverInts()` method:

```

static void QueryOverInts()
{
    int[] numbers = { 10, 20, 30, 40, 1, 2, 3, 8 };

    // Get numbers less than ten.
    var subset = from i in numbers where i < 10 select i;

    // LINQ statement evaluated here!
    foreach (var i in subset)
        Console.WriteLine("{0} < 10", i);
    Console.WriteLine();

    // Change some data in the array.
    numbers[0] = 4;

    // Evaluated again!
    foreach (var j in subset)

```

```

    Console.WriteLine("{0} < 10", j);

    Console.WriteLine();
    ReflectOverQueryResults(subset);
}

```

If you were to execute the program yet again, you will find the following output. Notice that the second time you iterate over the requested sequence, you find an additional member, as you set the first item in the array to be a value less than ten:

```

1 < 10
2 < 10
3 < 10
8 < 10

4 < 10
1 < 10
2 < 10
3 < 10
8 < 10

```

One very useful aspect of Visual Studio 2010 is that if you set a breakpoint before the evaluation of a LINQ query, you are able to view the contents during a debugging session. Simply locate your mouse cursor above the LINQ result set variable (`subset` in Figure 13-2). When you do, you will be given the option of evaluating the query at that time by expanding the Results View option.




Figure 13-2. Debugging LINQ expressions

The Role of Immediate Execution

When you wish to evaluate a LINQ expression from outside the confines of `foreach` logic, you are able to call any number of extension methods defined by the `Enumerable` type as `ToArray<T>()`, `ToDictionary<TSource, TKey>()`, and `ToList<T>()`. These methods will cause a LINQ query to execute at the exact moment you call them, to obtain a snapshot of the data. Once you have done so, the snapshot of data may be independently manipulated:

```

static void ImmediateExecution()
{
    int[] numbers = { 10, 20, 30, 40, 1, 2, 3, 8 };

    // Get data RIGHT NOW as int[].
    int[] subsetAsIntArray =
        (from i in numbers where i < 10 select i).ToArray<int>();

    // Get data RIGHT NOW as List<int>.
    List<int> subsetAsListOfInts =
        (from i in numbers where i < 10 select i).ToList<int>();
}

```

Notice that the entire LINQ expression is wrapped within parentheses to cast it into the correct underlying type (whatever that may be) in order to call the extension methods of `Enumerable`.

Also recall from Chapter 10 that when the C# compiler can unambiguously determine the type parameter of a generic item, you are not required to specify the type parameter. Thus, you could also call `ToArray<T>()` (or `ToList<T>()` for that matter) as follows:

```

int[] subsetAsIntArray =
    (from i in numbers where i < 10 select i).ToArray();

```

The usefulness of immediate execution is very obvious when you need to return the results of a LINQ query to an external caller. And, as luck would have it, this happens to be the next topic of the chapter!

Source Code The `LinqOverArray` project can be found under the Chapter 13 subdirectory.

Returning the Result of a LINQ Query

It is possible to define a field within a class (or structure) whose value is the result of a LINQ query. To do so, however, you cannot make use of implicit typing (as the `var` keyword cannot be used for fields) and the target of the LINQ query cannot be instance level data, therefore it must be static. Given these limitations, you will seldom need to author code like the following:

```

class LINQBasedFieldsAreClunky
{
    private static string[] currentVideoGames = {"Morrowind", "Uncharted 2",
                                                "Fallout 3", "Daxter", "System Shock 2"};

    // Can't use implicit typing here! Must know type of subset!
    private IEnumerable<string> subset = from g in currentVideoGames
                                            where g.Contains(" ") orderby g select g;

    public void PrintGames()
    {
        foreach (var item in subset)

```

```
    {
        Console.WriteLine(item);
    }
}
```

More often than not, LINQ queries are defined within the scope of a method or property. Moreover, to simplify your programming, the variable used to hold the result set will be stored in an implicitly typed local variable using the `var` keyword. Now, recall from Chapter 3 that implicitly typed variables cannot be used to define parameters, return values, or fields of a class or structure.

Given this point, you may wonder exactly how you could return a query result to an external caller. The answer is, it depends. If you have a result set consisting of strongly typed data such as an array of strings or a `List<T>` of `Cars`, you could abandon the use of the `var` keyword and use a proper `IEnumerable<T>` or `IEnumerable` type (again, as `IEnumerable<T>` extends `IEnumerable`). Consider the following example for a new Console Application named `LinqRetValues`:

```
class Program
{
    static void Main(string[] args)
    {
        Console.WriteLine("***** LINQ Transformations *****\n");
        IEnumerable<string> subset = GetStringSubset();

        foreach (string item in subset)
        {
            Console.WriteLine(item);
        }

        Console.ReadLine();
    }

    static IEnumerable<string> GetStringSubset()
    {
        string[] colors = {"Light Red", "Green",
                           "Yellow", "Dark Red", "Red", "Purple"};

        // Note subset is an IEnumerable<string> compatible object.
        IEnumerable<string> theRedColors = from c in colors
                                             where c.Contains("Red") select c;

        return theRedColors;
    }
}
```

The results are as expected:

Light Red
Dark Red
Red

Returning LINQ Results via Immediate Execution

This example works as expected, only because the return value of the `GetStringSubset()` and the LINQ query within this method has been strongly typed. If you used the `var` keyword to define the `subset` variable, it would be permissible to return the value *only* if the method is still prototyped to return `IEnumerable<string>` (and if the implicitly typed local variable is in fact compatible with the specified return type).

Because it is a tad bit inconvenient to operate on `IEnumerable<T>`, you could make use of immediate execution. For example, rather than returning `IEnumerable<string>`, you could simply return a `string[]`, provided that you transform the sequence to a strongly typed array. Consider this new method of the `Program` class which does this very thing:

```
static string[] GetStringSubsetAsArray()
{
    string[] colors = {"Light Red", "Green",
        "Yellow", "Dark Red", "Red", "Purple"};

    var theRedColors = from c in colors
        where c.Contains("Red") select c;

    // Map results into an array.
    return theRedColors.ToArray();
}
```

With this, the caller can be blissfully unaware that their result came from a LINQ query, and simply work with the array of strings as expected. For an example, see the following code:

```
foreach (string item in GetStringSubsetAsArray())
{
    Console.WriteLine(item);
}
```

Immediate execution is also critical when attempting to return to the caller the results of a LINQ projection. You'll examine this topic a bit later in the chapter. However, next up, let's look at how to apply LINQ queries to generic and nongeneric collection objects.

■ Source Code The `LinqRetValues` project can be found under the Chapter 13 subdirectory.

Applying LINQ Queries to Collection Objects

Beyond pulling results from a simple array of data, LINQ query expressions can also manipulate data within members of the `System.Collections.Generic` namespace, such as the `List<T>` type. Create a new Console Application project named `LinqOverCollections`, and define a basic `Car` class that maintains a current speed, color, make, and pet name as shown in the following code:

```
class Car
{
    public string PetName {get; set;}
```

```

public string Color {get; set;}
public int Speed {get; set;}
public string Make {get; set;}
}

```

Now, within your `Main()` method define a local `List<T>` variable of type `Car`, and make use of object initialization syntax to fill the list with a handful of new `Car` objects:

```

static void Main(string[] args)
{
    Console.WriteLine("***** LINQ over Generic Collections *****\n");

    // Make a List<> of Car objects.
    List<Car> myCars = new List<Car>()
    {
        new Car{ PetName = "Henry", Color = "Silver", Speed = 100, Make = "BMW" },
        new Car{ PetName = "Daisy", Color = "Tan", Speed = 90, Make = "BMW" },
        new Car{ PetName = "Mary", Color = "Black", Speed = 55, Make = "VW" },
        new Car{ PetName = "Clunker", Color = "Rust", Speed = 5, Make = "Yugo" },
        new Car{ PetName = "Melvin", Color = "White", Speed = 43, Make = "Ford" }
    };

    Console.ReadLine();
}

```

Accessing Contained Subobjects

Applying a LINQ query to a generic container is no different than doing so with a simple array, as LINQ to Objects can be used on any type implementing `IEnumerable<T>`. This time, your goal is to build a query expression to select only the `Car` objects within the `myCars` list, where the speed is greater than 55.

Once you get the subset, you will print out the name of each `Car` object by calling the `PetName` property. Assume you have the following helper method (taking a `List<Car>` parameter), which is called from within `Main()`:

```

static void GetFastCars(List<Car> myCars)
{
    // Find all Car objects in the List<>, where the Speed is
    // greater than 55.
    var fastCars = from c in myCars where c.Speed > 55 select c;

    foreach (var car in fastCars)
    {
        Console.WriteLine("{0} is going too fast!", car.PetName);
    }
}

```

Notice that your query expression is only grabbing items from the `List<T>` where the `Speed` property is greater than 55. If you run the application, you will find that “Henry” and “Daisy” are the only two items that match the search criteria.

If you want to build a more complex query, you might wish to only find the BMWs that have a `Speed` value above 90. To do so, simply build a compound Boolean statement using the C# `&&` operator:

```

static void GetFastBMWs(List<Car> myCars)
{
    // Find the fast BMWs!
    var fastCars = from c in myCars where c.Speed > 90 && c.Make == "BMW" select c;
    foreach (var car in fastCars)
    {
        Console.WriteLine("{0} is going too fast!", car.PetName);
    }
}

```

In this case, the only pet name printed out is “Henry”.

Applying LINQ Queries to Nongeneric Collections

Recall that the query operators of LINQ are designed to work with any type implementing `IEnumerable<T>` (either directly or via extension methods). Given that `System.Array` has been provided with such necessary infrastructure, it may surprise you that the legacy (nongeneric) containers within `System.Collections` have not. Thankfully, it is still possible to iterate over data contained within nongeneric collections using the generic `Enumerable.OfType<T>()` extension method.

The `OfType<T>()` method is one of the few members of `Enumerable` that does not extend generic types. When calling this member off a nongeneric container implementing the `IEnumerable` interface (such as the `ArrayList`), simply specify the type of item within the container to extract a compatible `IEnumerable<T>` object. In code, you can store this data point using an implicitly typed variable.

Consider the following new method which fills an `ArrayList` with a set of `Car` objects (be sure to import the `System.Collections` namespace into your `Program.cs` file).

```

static void LINQOverArrayList()
{
    Console.WriteLine("***** LINQ over ArrayList *****");

    // Here is a nongeneric collection of cars.
    ArrayList myCars = new ArrayList() {
        new Car{ PetName = "Henry", Color = "Silver", Speed = 100, Make = "BMW" },
        new Car{ PetName = "Daisy", Color = "Tan", Speed = 90, Make = "BMW" },
        new Car{ PetName = "Mary", Color = "Black", Speed = 55, Make = "VW" },
        new Car{ PetName = "Clunker", Color = "Rust", Speed = 5, Make = "Yugo" },
        new Car{ PetName = "Melvin", Color = "White", Speed = 43, Make = "Ford" }
    };

    // Transform ArrayList into an IEnumerable<T>-compatible type.
    var myCarsEnum = myCars.OfType<Car>();

    // Create a query expression targeting the compatible type.
    var fastCars = from c in myCarsEnum where c.Speed > 55 select c;

    foreach (var car in fastCars)
    {
        Console.WriteLine("{0} is going too fast!", car.PetName);
    }
}

```

Similar to the previous examples, this method, when called from `Main()` will only display the names “Henry” and “Daisy”, based on the format of our LINQ query.

Filtering Data Using `OfType<T>()`

As you know, nongeneric types are capable of containing any combination of items, as the members of these containers (again, such as the `ArrayList`) are prototyped to receive `System.Objects`. For example, assume an `ArrayList` contains a variety of items, only a subset of which are numerical. If you want to obtain a subset that contains only numerical data, you can do so using `OfType<T>()`, since it filters out each element whose type is different from the given type during the iterations:

```
static void OfTypeAsFilter()
{
    // Extract the ints from the ArrayList.
    ArrayList myStuff = new ArrayList();
    myStuff.AddRange(new object[] { 10, 400, 8, false, new Car(), "string data" });
    var myInts = myStuff.OfType<int>();

    // Prints out 10, 400, and 8.
    foreach (int i in myInts)
    {
        Console.WriteLine("Int value: {0}", i);
    }
}
```

Great! At this point, you have had a chance to apply LINQ queries to arrays, generic collections, and nongeneric collections. These containers held both C# primitive types (integers, string data) as well as custom classes. The next task is to learn about many additional LINQ operators which can be used to build more complex, and useful queries.

■ Source Code The `LinqOverCollections` project can be found under the Chapter 13 subdirectory.

Investigating the C# LINQ Query Operators

C# defines a good number of query operators out of the box. Table 13-3 documents some of the more commonly used query operators.

■ Note The .NET Framework 4.0 SDK documentation provides full details regarding each of the C# LINQ operators. Look up the topic “LINQ General Programming Guide” for more information.

Table 13-3. Various LINQ Query Operators

Query Operators	Meaning in Life
from, in	Used to define the backbone for any LINQ expression, which allows you to extract a subset of data from a fitting container.
where	Used to define a restriction for which items to extract from a container.
select	Used to select a sequence from the container.
join, on, equals, into	Performs joins based on specified key. Remember, these “joins” do not need to have anything to do with data in a relational database.
orderby, ascending, descending	Allows the resulting subset to be ordered in ascending or descending order.
group, by	Yields a subset with data grouped by a specified value.

In addition to the partial list of operators shown in Table 13-3, the `System.Linq.Enumerable` class provides a set of methods that do not have a direct C# query operator shorthand notation, but are instead exposed as extension methods. These generic methods can be called to transform a result set in various manners (`Reverse<>()`, `ToArray<>()`, `ToList<>()`, etc.). Some are used to extract singletons from a result set, others perform various set operations (`Distinct<>()`, `Union<>()`, `Intersect<>()`, etc.), and still others aggregate results (`Count<>()`, `Sum<>()`, `Min<>()`, `Max<>()`, etc.).

To begin digging into more intricate LINQ queries, create a new Console Application named `FunWithLinqExpressions`. Next, you need to define an array or collection of some sample data. For this project, you will make an array of `ProductInfo` objects, defined in the following code:

```
class ProductInfo
{
    public string Name {get; set;}
    public string Description {get; set;}
    public int NumberInStock {get; set;}

    public override string ToString()
    {
        return string.Format("Name={0}, Description={1}, Number in Stock={2}",
            Name, Description, NumberInStock);
    }
}
```

Now populate an array with a batch of `ProductInfo` objects within your `Main()` method:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Query Expressions *****\n");

    // This array will be the basis of our testing...
```

```

ProductInfo[] itemsInStock = new[] {
    new ProductInfo{ Name = "Mac's Coffee",
                     Description = "Coffee with TEETH",
                     NumberInStock = 24},
    new ProductInfo{ Name = "Milk Maid Milk",
                     Description = "Milk cow's love",
                     NumberInStock = 100},
    new ProductInfo{ Name = "Pure Silk Tofu",
                     Description = "Bland as Possible",
                     NumberInStock = 120},
    new ProductInfo{ Name = "Cruchy Pops",
                     Description = "Cheezy, peppery goodness",
                     NumberInStock = 2},
    new ProductInfo{ Name = "RipOff Water",
                     Description = "From the tap to your wallet",
                     NumberInStock = 100},
    new ProductInfo{ Name = "Classic Valpo Pizza",
                     Description = "Everyone loves pizza!",
                     NumberInStock = 73}
};

// We will call various methods here!
Console.ReadLine();
}

```

Basic Selection Syntax

Because the syntactical correctness of a LINQ query expression is validated at compile time, you need to remember that the ordering of these operators is critical. In the simplest terms, every LINQ query expression is built using the `from`, `in`, and `select` operators. Here is the general template to follow:

```
var result = from matchingItem in container select matchingItem;
```

The item after the `from` operator represents an item that matches the LINQ query criteria, which can be named anything you choose. The item after the `in` operator, represents the data container to search (an array, collection, or XML document).

Here is a very simple query, doing nothing more than selecting every item in the container (similar in behavior to a database `Select * SQL` statement). Consider the following:

```

static void SelectEverything(ProductInfo[] products)
{
    // Get everything!
    Console.WriteLine("All product details:");
    var allProducts = from p in products select p;

    foreach (var prod in allProducts)
    {
        Console.WriteLine(prod.ToString());
    }
}

```

To be honest, this query expression is not entirely useful, given that your subset is identical to that of the data in the incoming parameter. If you wish, you could use this incoming parameter to extract only the Name values of each car using the following selection syntax:

```
static void ListProductNames(ProductInfo[] products)
{
    // Now get only the names of the products.
    Console.WriteLine("Only product names:");
    var names = from p in products select p.Name;

    foreach (var n in names)
    {
        Console.WriteLine("Name: {0}", n);
    }
}
```

Obtaining Subsets of Data

To obtain a specific subset from a container, you can make use of the `where` operator. When doing so, the general template now becomes the following code:

```
var result = from item in container where BooleanExpression select item;
```

Notice that the `where` operator expects an expression that resolves to a Boolean. For example, to extract from the `ProductInfo[]` argument only the items that have more than 25 items on hand, you could author the following code:

```
static void GetOverstock(ProductInfo[] products)
{
    Console.WriteLine("The overstock items!");

    // Get only the items where we have more than
    // 25 in stock.
    var overstock = from p in products where p.NumberInStock > 25 select p;

    foreach (ProductInfo c in overstock)
    {
        Console.WriteLine(c.ToString());
    }
}
```

As seen earlier in this chapter, when you are building a `where` clause, it is permissible to make use of any valid C# operators to build complex expressions. For example, recall the query that only extracts out the BMWs going at least 100 mph:

```
// Get BMWs going at least 100 mph.
var onlyFastBMW = from c in myCars
                  where c.Make == "BMW" && c.Speed >= 100 select c;
```

```

foreach (Car c in onlyFastBMWs)
{
    Console.WriteLine("{0} is going {1} MPH", c.PetName, c.Speed);
}

```

Projecting New Data Types

It is also possible to project new forms of data from an existing data source. Let's assume that you wish to take the incoming `ProductInfo[]` parameter and obtain a result set that accounts only for the name and description of each item. To do so, you can define a `select` statement that dynamically yields a new anonymous type:

```

static void GetNamesAndDescriptions(ProductInfo[] products)
{
    Console.WriteLine("Names and Descriptions:");
    var nameDesc = from p in products select new { p.Name, p.Description };

    foreach (var item in nameDesc)
    {
        // Could also use Name and Description properties directly.
        Console.WriteLine(item.ToString());
    }
}

```

Always remember that when you have a LINQ query that makes use of a projection, you have no way of knowing the underlying data type, as this is determined at compile time. In these cases, the `var` keyword is mandatory. As well, recall that you cannot create methods with implicitly typed return values. Therefore, the following method would not compile:

```

static var GetProjectedSubset()
{
    ProductInfo[] products = new[] {
        new ProductInfo{ Name = "Mac's Coffee",
                        Description = "Coffee with TEETH",
                        NumberInStock = 24},
        new ProductInfo{ Name = "Milk Maid Milk",
                        Description = "Milk cow's love",
                        NumberInStock = 100},
        new ProductInfo{ Name = "Pure Silk Tofu",
                        Description = "Bland as Possible",
                        NumberInStock = 120},
        new ProductInfo{ Name = "Cruchy Pops",
                        Description = "Cheezy, peppery goodness",
                        NumberInStock = 2},
        new ProductInfo{ Name = "RipOff Water",
                        Description = "From the tap to your wallet",
                        NumberInStock = 100},
        new ProductInfo{ Name = "Classic Valpo Pizza",
                        Description = "Everyone loves pizza!",
                        NumberInStock = 73}
    };

```

```

    var nameDesc = from p in products select new { p.Name, p.Description };
    return nameDesc; // Nope!
}

```

When you wish to return projected data to a caller, one approach is to transform the query result into a .NET `System.Array` object using the `ToArray()` extension method. Thus, if you were to update your query expression as follows:

```

// Return value is now an Array.
static Array GetProjectedSubset()
{
...
    // Map set of anonymous objects to an Array object.
    return nameDesc.ToArray();
}

```

you could invoke and process the data from `Main()` as follows:

```

Array objs = GetProjectedSubset();
foreach (object o in objs)
{
    Console.WriteLine(o); // Calls ToString() on each anonymous object.
}

```

Note that you have to use a literal `System.Array` object and cannot make use of the C# array declaration syntax, given that you don't know the underlying type of type, as you are operating on a compiler generated anonymous class! Also note that you are not specifying the type parameter to the generic `ToArray<T>()` method, as you once again don't know the underlying data type until compile time, which is too late for your purposes.

The obvious problem is that you lose any strong typing, as each item in the `Array` object is assumed to be of type `Object`. Nevertheless, when you need to return a LINQ result set which is the result of a projection operation, transforming the data into an `Array` type (or another suitable container via other members of the `Enumerable` type) is mandatory.

Obtaining Counts Using Enumerable

When you are projecting new batches of data, you may need to discover exactly how many items have been returned into the sequence. Any time you need to determine the number of items returned from a LINQ query expression, simply make use of the `Count()` extension method of the `Enumerable` class. For example, the following method will find all `string` objects in a local array which have a length greater than six characters:

```

static void GetCountFromQuery()
{
    string[] currentVideoGames = {"Morrowind", "Uncharted 2",
        "Fallout 3", "Daxter", "System Shock 2"};

    // Get count from the query.
    int numb =
        (from g in currentVideoGames where g.Length > 6 select g).Count<string>();

```

```

    // Print out the number of items.
    Console.WriteLine("{0} items honor the LINQ query.", numb);
}

```

Reversing Result Sets

You can reverse the items within a result set quite simply using the `Reverse<T>()` extension method of the `Enumerable` class. For example, the following method selects all items from the incoming `ProductInfo[]` parameter in reverse:

```

static void ReverseEverything(ProductInfo[] products)
{
    Console.WriteLine("Product in reverse:");
    var allProducts = from p in products select p;
    foreach (var prod in allProducts.Reverse())
    {
        Console.WriteLine(prod.ToString());
    }
}

```

Sorting Expressions

As you have seen over this chapter's initial examples, a query expression can take an `orderby` operator to sort items in the subset by a specific value. By default, the order will be ascending; thus, ordering by a string would be alphabetical, ordering by numerical data would be lowest to highest, and so forth. If you wish to view the results in a descending order, simply include the `descending` operator. Ponder the following method:

```

static void AlphabetizeProductNames(ProductInfo[] products)
{
    // Get names of products, alphabetized.
    var subset = from p in products orderby p.Name select p;

    Console.WriteLine("Ordered by Name:");
    foreach (var p in subset)
    {
        Console.WriteLine(p.ToString());
    }
}

```

Although ascending order is the default, you are able to make your intentions very clear by making use of the `ascending` operator:

```
var subset = from p in products orderby p.Name ascending select p;
```

If you wish to get the items in descending order, you can do so via the `descending` operator:

```
var subset = from p in products orderby p.Name descending select p;
```

LINQ As a Better Venn Diagramming Tool

The `Enumerable` class supports a set of extension methods which allows you to use two (or more) LINQ queries as the basis to find unions, differences, concatenations, and intersections of data. First of all, consider the `Except()` extension method, which will return a LINQ result set that contains the differences between two containers, which in this case, is the value “Yugo”:

```
static void DisplayDiff()
{
    List<string> myCars = new List<String> {"Yugo", "Aztec", "BMW"};
    List<string> yourCars = new List<String> {"BMW", "Saab", "Aztec" };

    var carDiff =(from c in myCars select c)
        .Except(from c2 in yourCars select c2);

    Console.WriteLine("Here is what you don't have, but I do:");
    foreach (string s in carDiff)
        Console.WriteLine(s); // Prints Yugo.
}
```

The `Intersect()` method will return a result set that contains the common data items in a set of containers. For example, the following method returns the sequence, “Aztec” and “BMW”.

```
static void DisplayIntersection()
{
    List<string> myCars = new List<String> { "Yugo", "Aztec", "BMW" };
    List<string> yourCars = new List<String> { "BMW", "Saab", "Aztec" };

    // Get the common members.
    var carIntersect = (from c in myCars select c)
        .Intersect(from c2 in yourCars select c2);

    Console.WriteLine("Here is what we have in common:");
    foreach (string s in carIntersect)
        Console.WriteLine(s); // Prints Aztec and BMW.
}
```

The `Union()` method, as you would guess, returns a result set that includes all members of a batch of LINQ queries. Like any proper union, you will not find repeating values if a common member appears more than once. Therefore, the following method will print out the values “Yugo”, “Aztec”, “BMW”, and “Saab”:

```
static void DisplayUnion()
{
    List<string> myCars = new List<String> { "Yugo", "Aztec", "BMW" };
    List<string> yourCars = new List<String> { "BMW", "Saab", "Aztec" };

    // Get the union of these containers.
    var carUnion = (from c in myCars select c)
        .Union(from c2 in yourCars select c2);

    Console.WriteLine("Here is everything:");
}
```

```

foreach (string s in carUnion)
    Console.WriteLine(s); // Prints all common members
}

```

Finally, the `Concat()` extension method returns a result set that is a direct concatenation of LINQ result sets. For example, the following method prints out the results “Yugo”, “Aztec”, “BMW”, “BMW”, “Saab”, and “Aztec”:

```

static void DisplayConcat()
{
    List<string> myCars = new List<String> { "Yugo", "Aztec", "BMW" };
    List<string> yourCars = new List<String> { "BMW", "Saab", "Aztec" };

    var carConcat = (from c in myCars select c)
        .Concat(from c2 in yourCars select c2);

    // Prints:
    // Yugo Aztec BMW BMW Saab Aztec.
    foreach (string s in carConcat)
        Console.WriteLine(s);
}

```

Removing Duplicates

When you call the `Concat()` extension method, you could very well end up with redundant entries in the fetched result, which could be exactly what you want in some cases. However, in other cases, you might wish to remove duplicate entries in your data. To do so, simply call the `Distinct()` extension method, as seen here:

```

static void DisplayConcatNoDups()
{
    List<string> myCars = new List<String> { "Yugo", "Aztec", "BMW" };
    List<string> yourCars = new List<String> { "BMW", "Saab", "Aztec" };

    var carConcat = (from c in myCars select c)
        .Concat(from c2 in yourCars select c2);

    // Prints:
    // Yugo Aztec BMW Saab Aztec.
    foreach (string s in carConcat.Distinct())
        Console.WriteLine(s);
}

```

LINQ Aggregation Operations

LINQ queries can also be designed to perform various aggregation operations on the result set. The `Count()` extension method is one such aggregation example. Other possibilities include obtaining an average, max, min, or sum of values using the `Max()`, `Min()`, `Average()`, or `Sum()` members of the `Enumerable` class. Here is a simple example:

```

static void AggregateOps()
{
    double[] winterTemps = { 2.0, -21.3, 8, -4, 0, 8.2 };

    // Various aggregation examples.
    Console.WriteLine("Max temp: {0}",
        (from t in winterTemps select t).Max());

    Console.WriteLine("Min temp: {0}",
        (from t in winterTemps select t).Min());

    Console.WriteLine("Avarage temp: {0}",
        (from t in winterTemps select t).Average());

    Console.WriteLine("Sum of all temps: {0}",
        (from t in winterTemps select t).Sum());
}

```

These examples should give you enough knowledge to feel comfortable with the process of building LINQ query expressions. While there are additional operators you have not yet examined, you will see additional examples later in this text when you learn about related LINQ technologies. To wrap up your first look at LINQ, the remainder of this chapter will dive into the details between the C# LINQ query operators and the underlying object model.

■ Source Code The `FunWithLinqExpressions` project can be found under the Chapter 13 subdirectory.

The Internal Representation of LINQ Query Statements

At this point, you have been introduced to the process of building query expressions using various C# query operators (such as `from`, `in`, `where`, `orderby`, and `select`). Also, you discovered that some functionality of the LINQ to Objects API can only be accessed when calling extension methods of the `Enumerable` class. The truth of the matter, however, is that when compiled, the C# compiler actually translates all C# LINQ operators into calls on methods of the `Enumerable` class. In fact, if you were really a glutton for punishment, you could build all of your LINQ statements using nothing but the underlying object model.

A great many of the methods of `Enumerable` have been prototyped to take delegates as arguments. In particular, many methods require a generic delegate named `Func<T>` defined within the `System` namespace of `System.Core.dll`. For example, consider the `Where()` method of `Enumerable` which is called on your behalf when you use the C# `where` LINQ query operator:

```

// Overloaded versions of the Enumerable.Where<T>() method.
// Note the second parameter is of type System.Func<T>.
public static IEnumerable<TSource> Where<TSource>(this IEnumerable<TSource> source,
    System.Func<TSource,int,bool> predicate)

public static IEnumerable<TSource> Where<TSource>(this IEnumerable<TSource> source,
    System.Func<TSource,bool> predicate)

```

The `Func<>` delegate (as the name implies) represents a pattern for a given function with a set of arguments and a return value. If you were to examine this type using the Visual Studio 2010 object browser, you'll notice that the `Func<>` delegate can take between zero and four input arguments (here typed `T1`, `T2`, `T3`, and `T4` and named `arg1`, `arg2`, `arg3`, and `arg4`), and a return type denoted by `TResult`:

```
// The various formats of the Func<> delegate.
public delegate TResult Func<T1,T2,T3,T4,TResult>(T1 arg1, T2 arg2, T3 arg3, T4 arg4)

public delegate TResult Func<T1,T2,T3,TResult>(T1 arg1, T2 arg2, T3 arg3)

public delegate TResult Func<T1,T2,TResult>(T1 arg1, T2 arg2)

public delegate TResult Func<T1,TResult>(T1 arg1)

public delegate TResult Func<TResult>()
```

Given that many members of `System.Linq.Enumerable` demand a delegate as input, when invoking them, you can either manually create a new delegate type and author the necessary target methods, make use of a C# anonymous method, or define a proper lambda expression. Regardless of which approach you take, the end result is identical.

While it is true that making use of C# LINQ query operators is far and away the simplest way to build a LINQ query expression, let's walk through each of these possible approaches just so you can see the connection between the C# query operators and the underlying `Enumerable` type.

Building Query Expressions with Query Operators (Revisited)

To begin, create a new Console Application named `LinqUsingEnumerable`. The `Program` class will define a series of static helper methods (each of which is called within the `Main()` method) to illustrate the various manners in which you can build LINQ query expressions.

The first method, `QueryStringsWithOperators()`, offers the most straightforward way to build a query expression and is identical to the code seen in the `LinqOverArray` example found earlier in this chapter:

```
static void QueryStringWithOperators()
{
    Console.WriteLine("***** Using Query Operators *****");

    string[] currentVideoGames = {"Morrowind", "Uncharted 2",
        "Fallout 3", "Daxter", "System Shock 2"};

    var subset = from game in currentVideoGames
                where game.Contains(" ") orderby game select game;

    foreach (string s in subset)
        Console.WriteLine("Item: {0}", s);
}
```

The obvious benefit of using C# query operators to build query expressions is the fact that the `Func<>` delegates and calls on the `Enumerable` type are out of sight and out of mind, as it is the job of the C# compiler to perform this translation. To be sure, building LINQ expressions using various query operators (`from`, `in`, `where`, or `orderby`) is the most common and straightforward approach.

Building Query Expressions Using the Enumerable Type and Lambda Expressions

Keep in mind that the LINQ query operators used here are simply shorthand versions for calling various extension methods defined by the `Enumerable` type. Consider the following `QueryStringsWithEnumerableAndLambdas()` method, which is processing the local string array now making direct use of the `Enumerable` extension methods:

```
static void QueryStringsWithEnumerableAndLambdas()
{
    Console.WriteLine("***** Using Enumerable / Lambda Expressions *****");

    string[] currentVideoGames = {"Morrowind", "Uncharted 2",
        "Fallout 3", "Daxter", "System Shock 2"};

    // Build a query expression using extension methods
    // granted to the Array via the Enumerable type.
    var subset = currentVideoGames.Where(game => game.Contains(" "))
        .OrderBy(game => game).Select(game => game);

    // Print out the results.
    foreach (var game in subset)
        Console.WriteLine("Item: {0}", game);
    Console.WriteLine();
}
```

Here, you begin by calling the `Where()` extension method on the `currentVideoGames` string array. Recall the `Array` class receives this via an extension method granted by `Enumerable`. The `Enumerable.Where()` method requires a `System.Func<T1, TResult>` delegate parameter. The first type parameter of this delegate represents the `IEnumerable<T>` compatible data to process (an array of strings in this case), while the second type parameter represents the method result data, which is obtained from a single statement fed into the lambda expression.

The return value of the `Where()` method is hidden from view in this code example, but under the covers you are operating on an `OrderedEnumerable` type. From this object, you call the generic `OrderBy()` method, which also requires a `Func<>` delegate parameter. This time, you are simply passing each item in turn via a fitting lambda expression. The end result of calling `OrderBy()` is a new ordered sequence of the initial data.

Last but not least, you call the `Select()` method off the sequence returned from `OrderBy()`, which results in the final set of data that is stored in an implicitly typed variable named `subset`.

To be sure, this “long hand” LINQ query is a bit more complex to tease apart than the previous C# LINQ query operator example. Part of the complexity is no doubt due to the chaining together of calls using the dot operator. Here is the exact same query, with each step broken into discrete chunks:

```
static void QueryStringsWithEnumerableAndLambdas2()
{
    Console.WriteLine("***** Using Enumerable / Lambda Expressions *****");

    string[] currentVideoGames = {"Morrowind", "Uncharted 2",
        "Fallout 3", "Daxter", "System Shock 2"};

    // Break it down!
```

```

var gamesWithSpaces = currentVideoGames.Where(game => game.Contains(" "));
var orderedGames = gamesWithSpaces.OrderBy(game => game);
var subset = orderedGames.Select(game => game);

foreach (var game in subset)
    Console.WriteLine("Item: {0}", game);
Console.WriteLine();
}

```

As you may agree, building a LINQ query expression using the methods of the `Enumerable` class directly is much more verbose than making use of the C# query operators. As well, given that the methods of `Enumerable` require delegates as parameters, you will typically need to author lambda expressions to allow the input data to be processed by the underlying delegate target.

Building Query Expressions Using the `Enumerable` Type and Anonymous Methods

Given that C# lambda expressions are simply shorthand notations for working with anonymous methods, consider the third query expression created within the `QueryStringsWithAnonymousMethods()` helper function:

```

static void QueryStringsWithAnonymousMethods()
{
    Console.WriteLine("***** Using Anonymous Methods *****");

    string[] currentVideoGames = {"Morrowind", "Uncharted 2",
        "Fallout 3", "Daxter", "System Shock 2"};

    // Build the necessary Func<> delegates using anonymous methods.
    Func<string, bool> searchFilter =
        delegate(string game) { return game.Contains(" "); };
    Func<string, string> itemToProcess = delegate(string s) { return s; };

    // Pass the delegates into the methods of Enumerable.
    var subset = currentVideoGames.Where(searchFilter)
        .OrderBy(itemToProcess).Select(itemToProcess);

    // Print out the results.
    foreach (var game in subset)
        Console.WriteLine("Item: {0}", game);
    Console.WriteLine();
}

```

This iteration of the query expression is even more verbose, because you are manually creating the `Func<>` delegates used by the `Where()`, `OrderBy()`, and `Select()` methods of the `Enumerable` class. On the plus side, the anonymous method syntax does keep all the delegate processing contained within a single method definition. Nevertheless, this method is functionally equivalent to the `QueryStringsWithEnumerableAndLambdas()` and `QueryStringsWithOperators()` methods created in the previous sections.

Building Query Expressions Using the Enumerable Type and Raw Delegates

Finally, if you want to build a query expression using the *really verbose approach*, you could avoid the use of lambdas/anonymous method syntax and directly create delegate targets for each `Func<>` type. Here is the final iteration of your query expression, modeled within a new class type named `VeryComplexQueryExpression`:

```
class VeryComplexQueryExpression
{
    public static void QueryStringsWithRawDelegates()
    {
        Console.WriteLine("***** Using Raw Delegates *****");

        string[] currentVideoGames = {"Morrowind", "Uncharted 2",
            "Fallout 3", "Daxter", "System Shock 2"};

        // Build the necessary Func<> delegates.
        Func<string, bool> searchFilter = new Func<string, bool>(Filter);
        Func<string, string> itemToProcess = new Func<string, string>(ProcessItem);

        // Pass the delegates into the methods of Enumerable.
        var subset = currentVideoGames
            .Where(searchFilter).OrderBy(itemToProcess).Select(itemToProcess);

        // Print out the results.
        foreach (var game in subset)
            Console.WriteLine("Item: {0}", game);
        Console.WriteLine();
    }

    // Delegate targets.
    public static bool Filter(string game) {return game.Contains(" ");}
    public static string ProcessItem(string game) { return game; }
}
```

You can test this iteration of your string processing logic by calling this method within `Main()` method of the `Program` class as follows:

```
VeryComplexQueryExpression.QueryStringsWithRawDelegates();
```

If you were to now run the application to test each possible approach, it should not be too surprising that the output is identical regardless of the path taken. Keep the following points in mind regarding how LINQ query expressions are represented under the covers:

- Query expressions are created using various C# query operators.
- Query operators are simply shorthand notations for invoking extension methods defined by the `System.Linq.Enumerable` type.
- Many methods of `Enumerable` require delegates (`Func<>` in particular) as parameters.

- Any method requiring a delegate parameter can instead be passed a lambda expression.
- Lambda expressions are simply anonymous methods in disguise (which greatly improve readability).
- Anonymous methods are shorthand notations for allocating a raw delegate and manually building a delegate target method.

Whew! That might have been a bit deeper under the hood than you wish to have gone, but I hope this discussion has helped you understand what the user-friendly C# query operators are actually doing behind the scenes.

■ **Note** The LinqOverArrayUsingEnumerable project can be found under the Chapter 13 subdirectory.

Summary

LINQ is a set of related technologies that attempts to provide a single, symmetrical manner to interact with diverse forms of data. As explained over the course of this chapter, LINQ can interact with any type implementing the `IEnumerable<T>` interface, including simple arrays as well as generic and nongeneric collections of data.

As you have seen, working with LINQ technologies is accomplished using several C# language features. For example, given the fact that LINQ query expressions can return any number of result sets, it is common to make use of the `var` keyword to represent the underlying data type. As well, lambda expressions, object initialization syntax, and anonymous types can all be used to build very functional and compact LINQ queries.

More importantly, you have seen how the C# LINQ query operators are simply shorthand notations for making calls on static members of the `System.Linq.Enumerable` type. As shown, most members of `Enumerable` operate on `Func<T>` delegate types, which can take literal method addresses, anonymous methods, or lambda expressions as input to evaluate the query.

PART 4

■ ■ ■

Programming with .NET Assemblies



Configuring .NET Assemblies

Each of the applications in this book's first thirteen chapters was developed along the lines of traditional "stand-alone" applications, with all of the custom programming logic packaged within a single executable file (*.exe). However, a major aspect of the .NET platform is the notion of *binary reuse*, where applications make use of the types contained within various external assemblies (aka code libraries). In this chapter, we'll examine the core details of creating, deploying, and configuring .NET assemblies.

You'll learn the construction of .NET namespaces and the distinction between single-file and multi-file assemblies, as well as private and shared assemblies. Next, you'll explore exactly how the .NET runtime resolves the location of an assembly, and you'll come to understand the global assembly cache (GAC), application configuration files (*.config files), publisher policy assemblies, and the System.Configuration namespace.

Defining Custom Namespaces

Before diving into the details of assembly deployment and configuration, you must know how to create custom .NET namespaces. Up to this point in the text, you've been building small test programs that leverage existing namespaces in the .NET universe (System in particular). However, when you build your own custom applications, it can be very helpful to group your related types into custom namespaces. In C#, this is accomplished using the namespace keyword. Explicitly defining custom namespaces is even more important when creating .NET *.dll assemblies, as other developers will need to import your custom namespaces in order to use your types.

To investigate the issues firsthand, begin by creating a new Console Application named CustomNamespaces. Now, assume you are developing a collection of geometric classes named Square, Circle, and Hexagon. Given their similarities, you would like to group them all together into a unique namespace within the CustomNamespaces.exe assembly called MyShapes. You have two basic approaches. First, you can choose to define all classes in a single C# file (ShapesLib.cs) as follows:

```
// ShapesLib.cs
using System;

namespace MyShapes
{
```

```
// Circle class
public class Circle { /* Interesting members... */ }

// Hexagon class
public class Hexagon { /* More interesting members... */ }

// Square class
public class Square { /* Even more interesting members... */ }
}
```

Alternatively, you can split a single namespace into multiple C# files. To ensure each type is packaged into the same logical group, simply wrap the given class definitions in the same namespace scope:

```
// Circle.cs
using System;

namespace MyShapes
{
    // Circle class
    public class Circle { /* Interesting methods... */ }
}

// Hexagon.cs
using System;

namespace MyShapes
{
    // Hexagon class
    public class Hexagon { /* More interesting methods... */ }
}

// Square.cs
using System;

namespace MyShapes
{
    // Square class
    public class Square { /* Even more interesting methods... */ }
}
```

In both cases, notice how the `MyShapes` namespace acts as the conceptual “container” of these classes. When another namespace (such as `CustomNamespaces`) needs to import types defined within a separate namespace, you make use of the `using` keyword, just as you would when using types in the .NET base class libraries:

```
// Make use of types defined in the MyShape namespace.
using System;
using MyShapes;

namespace CustomNamespaces
{
    public class Program
```

```
{
    static void Main(string[] args)
    {
        Hexagon h = new Hexagon();
        Circle c = new Circle();
        Square s = new Square();
    }
}
```

For this particular example, the assumption is that the C# file(s) that define the `MyShapes` namespace are part of the same Console Application project that contains the file defining the `CustomNamespaces` namespace; in other words, all of the files are used to compile a single .NET executable assembly.

If you defined the `MyShapes` namespace within an external assembly, you might need to set a reference to that library before you could compile successfully. You'll learn all the details of building applications that make use of external libraries during the course of this chapter.

Resolving Name Clashes with Fully Qualified Names

Technically speaking, you are not required to use the C# `using` keyword when referring to types defined in external namespaces. You could use the *fully qualified name* of the type, which, as you recall from Chapter 1, is the type's name prefixed with the defining namespace:

```
// Note we are not importing MyShapes anymore.
using System;

namespace CustomNamespaces
{
    public class Program
    {
        static void Main(string[] args)
        {
            MyShapes.Hexagon h = new MyShapes.Hexagon();
            MyShapes.Circle c = new MyShapes.Circle();
            MyShapes.Square s = new MyShapes.Square();
        }
    }
}
```

Typically there is no need to use a fully qualified name. Not only does it require a greater number of keystrokes, it also makes no difference whatsoever in terms of code size or execution speed. In fact, in CIL code, types are *always* defined with the fully qualified name. In this light, the C# `using` keyword is simply a typing time-saver.

However, fully qualified names can be very helpful (and sometimes necessary) to avoid potential name clashes when using multiple namespaces that contain identically named types. Assume you have a new namespace termed `My3DShapes`, which defines three classes capable of rendering a shape in stunning 3D:

```
// Another shape-centric namespace.
using System;
```

```
namespace My3DShapes
{
    // 3D Circle class
    public class Circle { }

    // 3D Hexagon class
    public class Hexagon { }

    // 3D Square class
    public class Square { }
}
```

If you update the Program class as seen next, you are issued a number of compile-time errors, because both namespaces define identically named classes:

```
// Ambiguities abound!
using System;
using MyShapes;
using My3DShapes;

namespace CustomNamespaces
{
    public class Program
    {
        static void Main(string[] args)
        {
            // Which namespace do I reference?
            Hexagon h = new Hexagon(); // Compiler error!
            Circle c = new Circle(); // Compiler error!
            Square s = new Square(); // Compiler error!
        }
    }
}
```

The ambiguity can be resolved using the type's fully qualified name:

```
// We have now resolved the ambiguity.
static void Main(string[] args)
{
    My3DShapes.Hexagon h = new My3DShapes.Hexagon();
    My3DShapes.Circle c = new My3DShapes.Circle();
    MyShapes.Square s = new MyShapes.Square();
}
```

Resolving Name Clashes with Aliases

The C# `using` keyword also lets you create an alias for a type's fully qualified name. When you do so, you define a token that is substituted for the type's full name at compile time. Defining aliases provides a second way to resolve name-clashes, for example:

```
using System;
using MyShapes;
```

```

using My3DShapes;

// Resolve the ambiguity using a custom alias.
using The3DHexagon = My3DShapes.Hexagon;

namespace CustomNamespaces
{
    class Program
    {
        static void Main(string[] args)
        {
            // This is really creating a My3DShapes.Hexagon class.
            The3DHexagon h2 = new The3DHexagon();
        ...
    }
}

```

This alternative using syntax also lets you create an alias for a lengthy namespace. One of the longer namespaces in the base class library is `System.Runtime.Serialization.Formatters.Binary`, which contains a member named `BinaryFormatter`. If you wish, you can create an instance of the `BinaryFormatter` as follows:

```

using bfHome = System.Runtime.Serialization.Formatters.Binary;

namespace MyApp
{
    class ShapeTester
    {
        static void Main(string[] args)
        {
            bfHome.BinaryFormatter b = new bfHome.BinaryFormatter();
        }
    }
}

```

as well as with a traditional using directive:

```

using System.Runtime.Serialization.Formatters.Binary;

namespace MyApp
{
    class ShapeTester
    {
        static void Main(string[] args)
        {
            BinaryFormatter b = new BinaryFormatter();
        }
    }
}

```

At this point in the game, there is no need to concern yourself with what the `BinaryFormatter` class is used for (you'll examine this class in Chapter 20). For now, simply remember that the C# using keyword

can be used to define aliases for lengthy fully qualified names or, more commonly, to resolve name-clashes that can arise when importing multiple namespaces that define identically named types.

Note Be aware that overuse of C# aliases can result in a confusing code base. If other programmers on your team are unaware of your custom aliases, they may assume the aliases refer to types in the .NET base class libraries and become quite confused when they can't find these tokens in the .NET 4.0 framework SDK documentation!

Creating Nested Namespaces

When organizing your types, you are free to define namespaces within other namespaces. The .NET base class libraries do so in numerous places to provide deeper levels of type organization. For example, the `I0` namespace is nested within `System`, to yield `System.I0`. If you want to create a root namespace containing the existing `My3DShapes` namespace, you can update your code as follows:

```
// Nesting a namespace.
namespace Chapter14
{
    namespace My3DShapes
    {
        // 3D Circle class
        class Circle{ }
        // 3D Hexagon class
        class Hexagon{ }
        // 3D Square class
        class Square{ }
    }
}
```

In many cases, the role of a root namespace is simply to provide a further level of scope, and therefore it may not define any types directly within its scope (as in the case of the `Chapter14` namespace). If this is the case, a nested namespace can be defined using the following compact form:

```
// Nesting a namespace (take two).
namespace Chapter14.My3DShapes
{
    // 3D Circle class
    class Circle{ }
    // 3D Hexagon class
    class Hexagon{ }
    // 3D Square class
    class Square{ }
}
```

Given that you have now nested the `My3DShapes` namespace within the `Chapter14` root namespace, you need to update any existing using directives and type aliases:

```
using Chapter14.My3DShapes;
using The3DHexagon = Chapter14.My3DShapes.Hexagon;
```

The Default Namespace of Visual Studio 2010

On a final namespace-related note, it is worth pointing out that, by default, when you create a new C# project using Visual Studio 2010, the name of your application's default namespace will be identical to the project name. From this point on, when you insert new code files using the Project ➤ Add New Item menu selection, types will automatically be wrapped within the default namespace. If you wish to change the name of the default namespace, simply access the Default namespace option using the Application tab of the project's Properties window (see Figure 14-1).




Figure 14-1. Configuring the default namespace

With this update, any new item inserted into the project will be wrapped within the `MyDefaultNamespace` namespace (and, obviously, if another namespace wishes to use these types, the correct `using` directive must be applied).

So far so good. Now that you have seen some details regarding how to package up your custom types into well-organized namespaces, let's quickly review the benefits and format of the .NET assembly. After this, we will delve into the details of creating, deploying, and configuring your applications.

Source Code The `CustomNamespaces` project is located under the Chapter 14 subdirectory.

The Role of .NET Assemblies

.NET applications are constructed by piecing together any number of *assemblies*. Simply put, an assembly is a versioned, self-describing binary file hosted by the CLR. Now, despite the fact that .NET assemblies have exactly the same file extensions (*.exe or *.dll) as previous Windows binaries (including legacy COM servers), they have very little in common with those files under the hood. Thus, to set the stage for the information to come, let's consider some of the benefits provided by the assembly format.

Assemblies Promote Code Reuse

As you have built your Console Applications over the previous chapters, it may have seemed that *all* of the applications' functionality was contained within the executable assembly you were constructing. In reality, your applications were leveraging numerous types contained within the always accessible .NET code library, `mscorlib.dll` (recall that the C# compiler references `mscorlib.dll` automatically), and in the case of some examples, `System.Windows.Forms.dll`.

As you may know, a *code library* (also termed a *class library*) is a *.dll that contains types intended to be used by external applications. When you are creating executable assemblies, you will no doubt be leveraging numerous system-supplied and custom code libraries as you create your application. Do be aware, however, that a code library need not take a *.dll file extension. It is perfectly possible (although not very common) for an executable assembly to make use of types defined within an external executable file. In this light, a referenced *.exe can also be considered a code library.

Regardless of how a code library is packaged, the .NET platform allows you to reuse types in a language-independent manner. For example, you could create a code library in C# and reuse that library in any other .NET programming language. It is possible not only to allocate types across languages, but also to derive from them. A base class defined in C# could be extended by a class authored in Visual Basic. Interfaces defined in Pascal.NET can be implemented by structures defined in C#, and so forth. The point is that when you begin to break apart a single monolithic executable into numerous .NET assemblies, you achieve a *language-neutral* form of code reuse.

Assemblies Establish a Type Boundary

Recall that a type's *fully qualified name* is composed by prefixing the type's namespace (e.g., `System`) to its name (e.g., `Console`). Strictly speaking, however, the assembly in which a type resides further establishes a type's identity. For example, if you have two uniquely named assemblies (say, `MyCars.dll` and `YourCars.dll`) that both define a namespace (`CarLibrary`) containing a class named `SportsCar`, they are considered unique types in the .NET universe.

Assemblies Are Versionable Units

.NET assemblies are assigned a four-part numerical version number of the form `<major>.<minor>.<build>.<revision>`. (If you do not explicitly provide a version number, the assembly is automatically assigned a version of 1.0.0.0, given the default Visual Studio project settings.) This number, in conjunction with an optional *public key value*, allows multiple versions of the same assembly to coexist in harmony on a single machine. Formally speaking, assemblies that provide public key information are termed *strongly named*. As you will see in this chapter, by using a strong name, the CLR is able to ensure that the correct version of an assembly is loaded on behalf of the calling client.

Assemblies Are Self-Describing

Assemblies are regarded as *self-describing* in part because they record every external assembly they must have access to in order to function correctly. Thus, if your assembly requires `System.Windows.Forms.dll` and `System.Drawing.dll`, this will be documented in the assembly's *manifest*. Recall from Chapter 1 that a manifest is a blob of metadata that describes the assembly itself (name, version, required external assemblies, etc.).

In addition to manifest data, an assembly contains metadata that describes the composition (member names, implemented interfaces, base classes, constructors, and so forth) of every contained type. Because an assembly is documented in such detail, the CLR does *not* consult the Windows system registry to resolve its location (quite the radical departure from Microsoft's legacy COM programming model). As you will discover during this chapter, the CLR makes use of an entirely new scheme to resolve the location of external code libraries.

Assemblies Are Configurable

Assemblies can be deployed as "private" or "shared." Private assemblies reside in the same directory (or possibly a subdirectory) as the client application that uses them. Shared assemblies, on the other hand, are libraries intended to be consumed by numerous applications on a single machine and are deployed to a specific directory termed the *global assembly cache*, or *GAC*.

Regardless of how you deploy your assemblies, you are free to author XML-based configuration files. Using these configuration files, you can instruct the CLR to "probe" for assemblies at a specific location, load a specific version of a referenced assembly for a particular client, or consult an arbitrary directory on your local machine, your network location, or a web-based URL. You'll learn a good deal more about XML configuration files throughout this chapter.

Understanding the Format of a .NET Assembly

Now that you've learned about several benefits provided by the .NET assembly, let's shift gears and get a better idea of how an assembly is composed under the hood. Structurally speaking, a .NET assembly (*.dll or *.exe) consists of the following elements:

- A Windows file header
- A CLR file header
- CIL code
- Type metadata
- An assembly manifest
- Optional embedded resources

While the first two elements (the Windows and CLR headers) are blocks of data you can typically always ignore, they do deserve some brief consideration. Here's an overview of each element.

The Windows File Header

The Windows file header establishes the fact that the assembly can be loaded and manipulated by the Windows family of operating systems. This header data also identifies the kind of application (console-based, GUI-based, or *.dll code library) to be hosted by Windows. If you open a .NET assembly using the dumpbin.exe utility (via a Visual Studio 2010 command prompt) and specify the /headers flag as so:

```
dumpbin /headers CarLibrary.dll
```

you can view an assembly's Windows header information. Here is the (partial) Windows header information for the CarLibrary.dll assembly you will build a bit later in this chapter (if you would like to run dumpbin.exe yourself right now, you can specify the name of any *.dll or *.exe you wrote during this book in place of CarLibrary.dll):

```
Dump of file CarLibrary.dll
```

```
PE signature found
```

```
File Type: DLL
```

FILE HEADER VALUES

```
14C machine (x86)
3 number of sections
4B37DCD8 time date stamp Sun Dec 27 16:16:56 2009
0 file pointer to symbol table
0 number of symbols
E0 size of optional header
2102 characteristics
    Executable
    32 bit word machine
    DLL
```

OPTIONAL HEADER VALUES

```
10B magic # (PE32)
8.00 linker version
E00 size of code
600 size of initialized data
0 size of uninitialized data
2CDE entry point (00402CDE)
2000 base of code
4000 base of data
400000 image base (00400000 to 00407FFF)
2000 section alignment
200 file alignment
4.00 operating system version
0.00 image version
4.00 subsystem version
0 Win32 version
8000 size of image
200 size of headers
0 checksum
```

3 subsystem (Windows CUI)

...

Now, remember that the vast majority of .NET programmers will never need to concern themselves with the format of the header data embedded in a .NET assembly. Unless you happen to be building a new .NET language compiler (where you *would* care about such information), you are free to remain blissfully unaware of the grimy details of the header data. Do be aware, however, that this information is used under the covers when Windows loads the binary image into memory.

The CLR File Header

The CLR header is a block of data that all .NET assemblies must support (and do support, courtesy of the C# compiler) in order to be hosted by the CLR. In a nutshell, this header defines numerous flags that enable the runtime to understand the layout of the managed file. For example, flags exist that identify the location of the metadata and resources within the file, the version of the runtime the assembly was built against, the value of the (optional) public key, and so forth. If you supply the /clrheader flag to dumpbin.exe like so:

```
dumpbin /clrheader CarLibrary.dll
```

you are presented with the internal CLR header information for a given .NET assembly, as shown here:

```
Dump of file CarLibrary.dll
File Type: DLL

clr Header:
    48 cb
    2.05 runtime version
    2164 [      A74] RVA [size] of MetaData Directory
    1 flags
        IL Only
    0 entry point token
    0 [          0] RVA [size] of Resources Directory
    0 [          0] RVA [size] of StrongNameSignature Directory
    0 [          0] RVA [size] of CodeManagerTable Directory
    0 [          0] RVA [size] of VTableFixups Directory
    0 [          0] RVA [size] of ExportAddressTableJumps Directory
    0 [          0] RVA [size] of ManagedNativeHeader Directory

Summary
2000 .reloc
2000 .rsrc
2000 .text
```

Again, as a .NET developer you will not need to concern yourself with the gory details of an assembly's CLR header information. Just understand that every .NET assembly contains this data, which is used behind the scenes by the .NET runtime as the image data loads into memory. Now let's turn our attention to some information that is much more useful in our day-to-day programming tasks.

CIL Code, Type Metadata, and the Assembly Manifest

At its core, an assembly contains CIL code, which, as you recall, is a platform- and CPU-agnostic intermediate language. At runtime, the internal CIL is compiled on the fly using a just-in-time (JIT) compiler, according to platform- and CPU-specific instructions. Given this design, .NET assemblies can indeed execute on a variety of architectures, devices, and operating systems. (Although you can live a happy and productive life without understanding the details of the CIL programming language, Chapter 17 offers an introduction to the syntax and semantics of CIL.)

An assembly also contains metadata that completely describes the format of the contained types, as well as the format of external types referenced by this assembly. The .NET runtime uses this metadata to resolve the location of types (and their members) within the binary, lay out types in memory, and facilitate remote method invocations. You'll check out the details of the .NET metadata format in Chapter 16 during our examination of reflection services.

An assembly must also contain an associated *manifest* (also referred to as *assembly metadata*). The manifest documents each *module* within the assembly, establishes the version of the assembly, and also documents any *external* assemblies referenced by the current assembly (unlike legacy COM type libraries, which did not provide a way to document external dependencies). As you will see over the course of this chapter, the CLR makes extensive use of an assembly's manifest during the process of locating external assembly references.

■ **Note** As you will see a bit later in this chapter, a .NET module is a term used to define the parts in a multifile assembly.

Optional Assembly Resources

Finally, a .NET assembly may contain any number of embedded resources, such as application icons, image files, sound clips, or string tables. In fact, the .NET platform supports *satellite assemblies* that contain nothing but localized resources. This can be useful if you wish to partition your resources based on a specific culture (English, German, etc.) for the purposes of building international software. The topic of building satellite assemblies is outside the scope of this text; however, you will learn how to embed application resources into an assembly during our examination of the Windows Presentation Foundation API in Chapter 30.

Single-File and Multifile Assemblies

Technically speaking, an assembly can be composed of multiple *modules*. A module is really nothing more than a general term for a valid .NET binary file. In most situations, an assembly is in fact composed of a single module. In this case, there is a one-to-one correspondence between the (logical) assembly and the underlying (physical) binary (hence the term *single-file assembly*).

Single-file assemblies contain all of the necessary elements (header information, CIL code, type metadata, manifest, and required resources) in a single *.exe or *.dll package. Figure 14-2 illustrates the composition of a single-file assembly.




Figure 14-2. A single-file assembly

A multifile assembly, on the other hand, is a set of .NET modules that are deployed and versioned as a single logical unit. Formally speaking, one of these modules is termed the primary module and contains the assembly-level manifest (as well as any necessary CIL code, metadata, header information, and optional resources). The manifest of the primary module records each of the related module files it is dependent upon.

As a naming convention, the secondary modules in a multifile assembly take a *.netmodule file extension; however, this is not a requirement of the CLR. Secondary *.netmodules also contain CIL code and type metadata, as well as a *module-level manifest*, which simply records the externally required assemblies of that specific module.

The major benefit of constructing multifile assemblies is that they provide a very efficient way to download content. For example, assume you have a machine that is referencing a remote multifile assembly composed of three modules, where the primary module is installed on the client. If the client requires a type within a secondary remote *.netmodule, the CLR will download the binary to the local machine on demand to a specific location termed the *download cache*. If each *.netmodule is 5MB, I'm sure you can see the benefit (compared with downloading a single 15MB file).

Another benefit of multifile assemblies is that they enable modules to be authored using multiple .NET programming languages (which is very helpful in larger corporations, where individual departments tend to favor a specific .NET language). Once each of the individual modules has been compiled, the modules can be logically “connected” into a logical assembly using the C# command-line compiler.

In any case, do understand that the modules that compose a multifile assembly are not literally linked together into a single (larger) file. Rather, multifile assemblies are only logically related by information contained in the primary module's manifest. Figure 14-3 illustrates a multifile assembly composed of three modules, each authored using a unique .NET programming language.




Figure 14-3. The primary module records secondary modules in the assembly manifest

At this point you should have a better understanding of the internal composition of a .NET binary file. With that out of the way, we are ready to look at the building and configuring a variety of code libraries.

Building and Consuming a Single-File Assembly

To begin exploring the world of .NET assemblies, you'll first create a single-file *.dll assembly (named CarLibrary) that contains a small set of public types. To build a code library using Visual Studio 2010, select the Class Library project workspace via the File ▶ New Project... menu option (see Figure 14-4).




Figure 14-4. Creating a C# code library

The design of your automobile library begins with an abstract base class named `Car` that defines various state data via automatic property syntax. This class also has a single abstract method named `TurboBoost()`, which makes use of a custom enumeration (`EngineState`) representing the current condition of the car's engine:

```
using System;
using System.Collections.Generic;
using System.Linq;
using System.Text;

namespace CarLibrary
{
    // Represents the state of the engine.
    public enum EngineState
    { engineAlive, engineDead }

    // The abstract base class in the hierarchy.
    public abstract class Car
    {
        public string PetName {get; set;}
        public int CurrentSpeed {get; set;}
        public int MaxSpeed {get; set;}

        protected EngineState egnState = EngineState.engineAlive;
        public EngineState EngineState
    }
}
```

```

        get { return egnState; }
    }

    public abstract void TurboBoost();

    public Car(){}
    public Car(string name, int maxSp, int currSp)
    {
        PetName = name; MaxSpeed = maxSp; CurrentSpeed = currSp;
    }
}
}

```

Now assume you have two direct descendants of the `Car` type named `MiniVan` and `SportsCar`. Each overrides the abstract `TurboBoost()` method by displaying an appropriate message via a Windows Forms message box. Insert a new C# class file into your project named `DerivedCars.cs`, which contains the following code:

```

using System;
using System.Windows.Forms;

namespace CarLibrary
{
    public class SportsCar : Car
    {
        public SportsCar(){}
        public SportsCar(string name, int maxSp, int currSp)
            : base(name, maxSp, currSp){}

        public override void TurboBoost()
        {
            MessageBox.Show("Ramming speed!", "Faster is better...");
        }
    }

    public class MiniVan : Car
    {
        public MiniVan(){}
        public MiniVan(string name, int maxSp, int currSp)
            : base(name, maxSp, currSp){}

        public override void TurboBoost()
        {
            // Minivans have poor turbo capabilities!
            egnState = EngineState.engineDead;
            MessageBox.Show("Eek!", "Your engine block exploded!");
        }
    }
}

```

Notice how each subclass implements `TurboBoost()` using the Windows Form's `MessageBox` class, which is defined in the `System.Windows.Forms.dll` assembly. For your assembly to make use of the types

defined within this external assembly, the CarLibrary project must set a reference to this binary via the Add Reference dialog box (see Figure 14-5), which you can access through the Visual Studio Project ► Add Reference menu selection.




Figure 14-5. Referencing external .NET assemblies using the Add Reference dialog box

It is *really* important to understand that the assemblies displayed in the .NET tab of the Add Reference dialog box do not represent each and every assembly on your machine. The Add Reference dialog box will *not* display your custom assemblies, and it does *not* display all assemblies located in the GAC. Rather, this dialog box simply presents a list of common assemblies that Visual Studio 2010 is preprogrammed to display. When you are building applications that require the use of an assembly not listed within the Add Reference dialog box, you need to click the Browse tab to manually navigate to the *.dll or *.exe in question.

■ **Note** Be aware that the Recent tab of the Add Reference dialog box keeps a running list of previously referenced assemblies. This can be handy, as many .NET projects tend to use the same core set of external libraries.

Exploring the Manifest

Before using CarLibrary.dll from a client application, let's check out how the code library is composed under the hood. Assuming you have compiled this project, load CarLibrary.dll into ildasm.exe (see Figure 14-6).




Figure 14-6. *CarLibrary.dll* loaded into *ildasm.exe*

Now, open the manifest of *CarLibrary.dll* by double-clicking the MANIFEST icon. The first code block in a manifest specifies all external assemblies required by the current assembly to function correctly. As you recall, *CarLibrary.dll* made use of types within *mscorlib.dll* and *System.Windows.Forms.dll*, both of which are listed in the manifest using the *.assembly extern* token:

```
.assembly extern mscorlib
{
    .publickeytoken = (B7 7A 5C 56 19 34 E0 89 )
    .ver 4:0:0:0
}
.assembly extern System.Windows.Forms
{
    .publickeytoken = (B7 7A 5C 56 19 34 E0 89 )
    .ver 4:0:0:0
}
```

Here, each *.assembly extern* block is qualified by the *.publickeytoken* and *.ver* directives. The *.publickeytoken* instruction is present only if the assembly has been configured with a *strong name* (more details on strong names in the section “Understanding Strong Names” later in this chapter). The *.ver* token defines (of course) the numerical version identifier of the referenced assembly.

After the external references, you will find a number of *.custom* tokens that identify assembly-level attributes (copyright information, company name, assembly version, etc.). Here is a (very) partial listing of this chunk of MANIFEST data:

```
.assembly CarLibrary
{
    .custom instance void ...AssemblyDescriptionAttribute...
    .custom instance void ...AssemblyConfigurationAttribute...
    .custom instance void ...RuntimeCompatibilityAttribute...
    .custom instance void ...TargetFrameworkAttribute...
    .custom instance void ...AssemblyTitleAttribute...
    .custom instance void ...AssemblyTrademarkAttribute...
    .custom instance void ...AssemblyCompanyAttribute...
    .custom instance void ...AssemblyProductAttribute...
    .custom instance void ...AssemblyCopyrightAttribute...
    ...
}
```

```
.ver 1:0:0:0
}
.module CarLibrary.dll
```

Typically these settings are established visually using the Properties editor of your current project. Now, switching back to Visual Studio 2010, if you double-click on the Properties icon within the Solution Explorer, you can click on the “Assembly Information...” button located on the (automatically selected) Application tab. This will bring up the GUI editor shown in Figure 14-7.




Figure 14-7. Editing assembly information using Visual Studio’s Properties editor

When you save your changes, the GUI editor updates your project’s `AssemblyInfo.cs` file, which is maintained by Visual Studio 2010 and can be viewed by expanding the Properties node of the Solution Explorer; see Figure 14-8).




Figure 14-8. The `AssemblyInfo.cs` file is updated as you use the GUI Properties editor

If you view the contents of this C# file, you'll see a number of .NET *attributes* sandwiched between square brackets, for example:

```
[assembly: AssemblyTitle("CarLibrary")]
[assembly: AssemblyDescription("")]
[assembly: AssemblyConfiguration("")]
[assembly: AssemblyCompany("Microsoft")]
[assembly: AssemblyProduct("CarLibrary")]
[assembly: AssemblyCopyright("Copyright © Microsoft 2010")]
[assembly: AssemblyTrademark("")]
[assembly: AssemblyCulture("")]
```

Chapter 15 examines the role of attributes in depth, so don't sweat the details at this point. For now, just be aware that a majority of the attributes in `AssemblyInfo.cs` will be used to update the `.custom` token values within an assembly MANIFEST.

Exploring the CIL

Recall that an assembly does not contain platform-specific instructions; rather, it contains platform-agnostic common intermediate language (CIL) instructions. When the .NET runtime loads an assembly into memory, the underlying CIL is compiled (using the JIT compiler) into instructions that can be understood by the target platform. For example, if you double-click the `TurboBoost()` method of the `SportsCar` class, `ildasm.exe` will open a new window showing the CIL tokens that implement this method:

```
.method public hidebysig virtual instance void
    TurboBoost() cil managed
{
    // Code size      18 (0x12)
    .maxstack 8
    IL_0000:  nop
    IL_0001:  ldstr   "Ramming speed!"
    IL_0006:  ldstr   "Faster is better..."
    IL_000b:  call    valuetype [System.Windows.Forms]System.Windows.Forms.DialogResult
              [System.Windows.Forms]System.Windows.Forms.MessageBox::Show(string, string)
    IL_0010:  pop
    IL_0011:  ret
} // end of method SportsCar::TurboBoost
```

Again, while most .NET developers don't need to be deeply concerned with the details of CIL on a daily basis, Chapter 17 provides more details on its syntax and semantics. Believe it or not, understanding the grammar of CIL can be helpful when you are building more complex applications that require advanced services, such as runtime construction of assemblies (again, see Chapter 17).

Exploring the Type Metadata

Before we build some applications that make use of our custom .NET library, if you press the `Ctrl+M` keystroke combination, `ildasm.exe` displays the metadata for each type within the `CarLibrary.dll` assembly (see Figure 14-9).




Figure 14-9. Type metadata for the types within CarLibrary.dll

As explained in the next chapter, an assembly's metadata is a very important element of the .NET platform, and serves as the backbone for numerous technologies (object serialization, late binding, extendable applications, etc.). In any case, now that you have looked inside the CarLibrary.dll assembly, you can build some client applications that make use of your types!

■ **Source Code** The CarLibrary project is located under the Chapter 14 subdirectory.

Building a C# Client Application

Because each of the CarLibrary types has been declared using the `public` keyword, other assemblies are able to use them as well. Recall that you may also define types using the C# `internal` keyword (in fact, this is the default C# access mode). Internal types can be used only by the assembly in which they are defined. External clients can neither see nor create types marked with the `internal` keyword.

■ **Note** .NET does provide a way to specify “friend assemblies” that allow internal types to be consumed by a set of specified assemblies. Look up the `InternalsVisibleToAttribute` class in the .NET Framework 4.0 SDK documentation for details if you are interested; however, be aware that the construction of friend assemblies is quite rare.

To use your library's functionality, create a new C# Console Application project named CSharpCarClient. Once you have done so, set a reference to CarLibrary.dll using the Browse tab of the Add Reference dialog box (if you compiled CarLibrary.dll using Visual Studio, your assembly is located under the \bin\Debug subdirectory of the CarLibrary project folder). At this point you can build your client application to make use of the external types. Update your initial C# file as follows:

```
using System;
using System.Collections.Generic;
using System.Linq;
using System.Text;

// Don't forget to import the CarLibrary namespace!
using CarLibrary;

namespace CSharpCarClient
{
    public class Program
    {
        static void Main(string[] args)
        {
            Console.WriteLine("***** C# CarLibrary Client App *****");
            // Make a sports car.
            SportsCar viper = new SportsCar("Viper", 240, 40);
            viper.TurboBoost();

            // Make a minivan.
            MiniVan mv = new MiniVan();
            mv.TurboBoost();
            Console.ReadLine();
        }
    }
}
```

This code looks just like the code of the other applications developed thus far in the text. The only point of interest is that the C# client application is now making use of types defined within a separate custom assembly. Go ahead and run your program. As you'd expect, the execution of this program results in the display of various message boxes.

It is important to point out that Visual Studio 2010 placed a copy of CarLibrary.dll into the \bin\Debug folder of the CSharpCarClient project folder. This can be verified by clicking the Show All Files button of the Solution Explorer (see Figure 14-10).




Figure 14-10. Visual Studio 2010 copies private assemblies to the client's directory

As explained later in this chapter, `CarLibrary.dll` has been configured as a “private” assembly (which is the automatic behavior for all Visual Studio 2010 Class Library projects). When you reference private assemblies in new applications (such as `CSharpCarClient.exe`), the IDE responds by placing a copy of the library in the client application’s output directory.

■ **Source Code** The `CSharpCarClient` project is located under the Chapter 14 subdirectory.

Building a Visual Basic Client Application

To illustrate the language-agnostic attitude of the .NET platform, let’s create another Console Application (VisualBasicCarClient), this time using Visual Basic (see Figure 14-11). Once you have created the project, set a reference to `CarLibrary.dll` using the Add Reference dialog box, which can be activated by the Project ▶ Add Reference menu option.




Figure 14-11. Creating a Visual Basic Console Application

Like C#, Visual Basic requires you to list each namespace used within the current file. However, Visual Basic offers the Imports keyword rather than the C# using keyword, so add the following Imports statement within the Module1.vb code file:

```
Imports CarLibrary
```

```
Module Module1
    Sub Main()
        End Sub
    End Module
```

Notice that the Main() method is defined within a Visual Basic module type (which has nothing to do with a *.netmodule file for a multifile assembly). In a nutshell, modules are a Visual Basic notation for defining a class that can contain only static methods (much like a C# static class). In any case, to exercise the MiniVan and SportsCar types using the syntax of Visual Basic, update your Main() method as follows:

```
Sub Main()
    Console.WriteLine("***** VB CarLibrary Client App *****")

    ' Local variables are declared using the Dim keyword.
    Dim myMiniVan As New MiniVan()
    myMiniVan.TurboBoost()

    Dim mySportsCar As New SportsCar()
    mySportsCar.TurboBoost()
    Console.ReadLine()
End Sub
```

When you compile and run your application, you will once again find a series of message boxes displayed. Furthermore, this new client application has its own local copy of `CarLibrary.dll` located under the `bin\Debug` folder.

Cross-Language Inheritance in Action

A very enticing aspect of .NET development is the notion of *cross-language inheritance*. To illustrate, let's create a new Visual Basic class that derives from `SportsCar` (which was authored using C#). First, add a new class file to your current Visual Basic application (by selecting the `Project ▶ Add Class` menu option) named `PerformanceCar.vb`. Update the initial class definition by deriving from the `SportsCar` type using the `Inherits` keyword. Then, override the abstract `TurboBoost()` method using the `Overrides` keyword:

```
Imports CarLibrary

' This VB class is deriving from the C# SportsCar.
Public Class PerformanceCar
    Inherits SportsCar

    Public Overrides Sub TurboBoost()
        Console.WriteLine("Zero to 60 in a cool 4.8 seconds...")
    End Sub

End Class
```

To test this new class type, update the module's `Main()` method as follows:

```
Sub Main()
    ...
    Dim dreamCar As New PerformanceCar()

    ' Use Inherited property.
    dreamCar.PetName = "Hank"
    dreamCar.TurboBoost()
    Console.ReadLine()
End Sub
```

Notice that the `dreamCar` object is able to invoke any public member (such as the `PetName` property) found up the chain of inheritance, regardless of the fact that the base class was defined in a completely different language and in a completely different assembly! The ability to extend classes across assembly boundaries in a language-independent manner is a very natural aspect of the .NET development cycle. This makes it very easy to use compiled code written by individuals who would rather not build their shared code with C#.

Source Code The `VisualBasicCarClient` project is located under the Chapter 14 subdirectory.

Building and Consuming a Multifile Assembly

Now that you have constructed and consumed a single-file assembly, let's examine the process of building a multifile assembly. Recall that a multifile assembly is simply a collection of related modules that is deployed and versioned as a single logical unit. At the time of this writing, the Visual Studio IDE does not support a C# multifile assembly project template. Therefore, you will need to make use of the command-line compiler (csc.exe) to build such a beast.

To describe the process, you will build a multifile assembly named AirVehicles. The primary module (airvehicles.dll) will contain a single class type named Helicopter. The related manifest (also contained in airvehicles.dll) will catalog an additional *.netmodule file named ufo.netmodule that contains another class type named (of course) Ufo. Although both class types are physically contained in separate binaries, you will group them into a single namespace named AirVehicles. You'll create both classes using C# (although you could certainly mix and match languages if you desire).

To begin, open a simple text editor (such as Notepad) and create the following Ufo class definition and save it to a file named ufo.cs:

```
using System;

namespace AirVehicles
{
    public class Ufo
    {
        public void AbductHuman()
        {
            Console.WriteLine("Resistance is futile");
        }
    }
}
```

To compile this class into a .NET module, open a Visual Studio 2010 Command Prompt, navigate to the folder containing ufo.cs and issue the following command to the C# compiler (the module option of the /target flag instructs csc.exe to produce a *.netmodule as opposed to a *.dll or an *.exe file):

```
csc.exe /t:module ufo.cs
```

If you now look in the folder that contains the ufo.cs file, you should see a new file named ufo.netmodule (take a peek in your working directory). Next, create a new file named helicopter.cs that contains the following class definition:

```
using System;

namespace AirVehicles
{
    public class Helicopter
    {
        public void TakeOff()
        {
            Console.WriteLine("Helicopter taking off!");
        }
    }
}
```

Given that `airvehicles.dll` is the intended name of the primary module of this multifile assembly, you will need to compile `helicopter.cs` using the `/t:library` and `/out:` options. To enlist the `ufo.netmodule` binary into the assembly manifest, you must also specify the `/addmodule` flag. The following command does the trick:

```
csc /t:library /addmodule:ufo.netmodule /out:airvehicles.dll helicopter.cs
```

At this point, your directory should contain the primary `airvehicles.dll` module as well as the secondary `ufo.netmodule` binaries.

Exploring the `ufo.netmodule` File

Now, using `ildasm.exe`, open `ufo.netmodule`. As you can see, `*.netmodules` contain a *module-level manifest*; however, its sole purpose is to list each external assembly referenced by the code base. Given that the `Ufo` class did little more than make a call to `Console.WriteLine()`, you find the following core information:

```
.assembly extern mscorel
{
    .publickeytoken = (B7 7A 5C 56 19 34 E0 89 )
    .ver 4:0:0:0
}
.module ufo.netmodule
```

Exploring the `airvehicles.dll` File

Next, using `ildasm.exe`, open the primary `airvehicles.dll` module and investigate the assembly-level manifest. Notice that the `.file` token documents the associated modules in the multifile assembly (`ufo.netmodule` in this case). The `.class extern` tokens are used to document the names of the external types referenced for use from the secondary module (`Ufo`). Here is the relevant information:

```
.assembly extern mscorel
{
    .publickeytoken = (B7 7A 5C 56 19 34 E0 89 )
    .ver 4:0:0:0
}
.assembly airvehicles
{
    ...
    .hash algorithm 0x00008004
    .ver 0:0:0:0
}
.file ufo.netmodule
...
.class extern public AirVehicles.Ufo
{
    .file ufo.netmodule
    .class 0x02000002
}
.module airvehicles.dll
```

Again, realize that the only entity that links together `airvehicles.dll` and `ufo.netmodule` is the assembly manifest. These two binary files have not been merged into a single, larger `*.dll`.

Consuming a Multifile Assembly

The consumers of a multifile assembly couldn't care less that the assembly they are referencing is composed of numerous modules. To keep things simple, let's create a new C# client application at the command line. Create a new file named `Client.cs` with the following module definition. When you are done, save it in the same location as your multifile assembly.

```
using System;
using AirVehicles;

class Program
{
    static void Main()
    {
        Console.WriteLine("***** Multifile Assembly Client *****");
        Helicopter h = new Helicopter();
        h.TakeOff();

        // This will load the *.netmodule on demand.
        Ufo u = new Ufo();
        u.AbductHuman();
        Console.ReadLine();
    }
}
```

To compile this executable assembly at the command line, use the C# command-line compiler, `csc.exe`, with the following command set:

```
csc /r:airvehicles.dll Client.cs
```

Notice that when you are referencing a multifile assembly, the compiler needs to be supplied only with the name of the primary module (the `*.netmodules` are loaded on demand by the CLR when used by the client's code base). In and of themselves, `*.netmodules` do not have an individual version number and can't be directly loaded by the CLR. Individual `*.netmodules` can be loaded only by the primary module (e.g., the file that contains the assembly manifest).

Note Visual Studio 2010 also allows you to reference a multifile assembly. Simply use the Add References dialog box and select the primary module. Any related `*.netmodules` are copied during the process.

At this point, you should feel comfortable with the process of building both single-file and multifile assemblies. To be completely honest, chances are very good that all of your assemblies will be single-file entities. Nevertheless, multifile assemblies can prove helpful when you wish to break a large physical binary into modular units (which are quite useful for remote download scenarios). Next up, let's formalize the concept of a private assembly.

■ **Source Code** The MultifileAssembly code files are included under the Chapter 14 subdirectory.

Understanding Private Assemblies

Technically speaking, the code libraries you've created thus far in this chapter have been deployed as *private assemblies*. Private assemblies must be located within the same directory as the client application that's using them (the *application directory*) or a subdirectory thereof. Recall that when you set a reference to CarLibrary.dll while building the CSharpCarClient.exe and VisualBasicCarClient.exe applications, Visual Studio 2010 responded by placing a copy of CarLibrary.dll within the client's application directory (at least, after the first compilation).

When a client program uses the types defined within this external assembly, the CLR simply loads the local copy of CarLibrary.dll. Because the .NET runtime does not consult the system registry when searching for referenced assemblies, you can relocate the CSharpCarClient.exe (or VisualBasicCarClient.exe) and CarLibrary.dll assemblies to a new location on your machine and run the application (this is often termed *Xcopy deployment*).

Uninstalling (or replicating) an application that makes exclusive use of private assemblies is a no-brainer: simply delete (or copy) the application folder. Unlike with COM applications, you do not need to worry about dozens of orphaned registry settings. More important, you do not need to worry that the removal of private assemblies will break any other applications on the machine.

The Identity of a Private Assembly

The full identity of a private assembly consists of the friendly name and numerical version, both of which are recorded in the assembly manifest. The *friendly name* is simply the name of the module that contains the assembly's manifest minus the file extension. For example, if you examine the manifest of the CarLibrary.dll assembly, you find the following:

```
.assembly CarLibrary
{
...
    .ver 1:0:0:0
}
```

Given the isolated nature of a private assembly, it should make sense that the CLR does not bother to use the version number when resolving its location. The assumption is that private assemblies do not need to have any elaborate version checking, as the client application is the only entity that "knows" of its existence. because of this, it is (very) possible for a single machine to have multiple copies of the same private assembly in various application directories.

Understanding the Probing Process

The .NET runtime resolves the location of a private assembly using a technique called *probing*, which is much less invasive than it sounds. Probing is the process of mapping an external assembly request to the location of the requested binary file. Strictly speaking, a request to load an assembly may be either

implicit or *explicit*. An implicit load request occurs when the CLR consults the manifest in order to resolve the location of an assembly defined using the `.assembly extern` tokens:

```
// An implicit load request.
.assembly extern CarLibrary
{ ... }
```

An explicit load request occurs programmatically using the `Load()` or `LoadFrom()` method of the `System.Reflection.Assembly` class type, typically for the purposes of late binding and dynamic invocation of type members. You'll examine these topics further in Chapter 15, but for now you can see an example of an explicit load request in the following code:

```
// An explicit load request based on a friendly name.
Assembly asm = Assembly.Load("CarLibrary");
```

In either case, the CLR extracts the friendly name of the assembly and begins probing the client's application directory for a file named `CarLibrary.dll`. If this file cannot be located, an attempt is made to locate an executable assembly based on the same friendly name (for example, `CarLibrary.exe`). If neither file can be located in the application directory, the runtime gives up and throws a `FileNotFoundException` exception at runtime.

Note Technically speaking, if a copy of the requested assembly cannot be found within the client's application directory, the CLR will also attempt to locate a client subdirectory with the exact same name as the assembly's friendly name (e.g., `C:\MyClient\CarLibrary`). If the requested assembly resides within this subdirectory, the CLR will load the assembly into memory.

Configuring Private Assemblies

While it is possible to deploy a .NET application by simply copying all required assemblies to a single folder on the user's hard drive, you will most likely want to define a number of subdirectories to group related content. For example, assume you have an application directory named `C:\MyApp` that contains `CSharpCarClient.exe`. Under this folder might be a subfolder named `MyLibraries` that contains `CarLibrary.dll`.

Regardless of the intended relationship between these two directories, the CLR will *not* probe the `MyLibraries` subdirectory unless you supply a configuration file. Configuration files contain various XML elements that allow you to influence the probing process. Configuration files must have the same name as the launching application and take a `*.config` file extension, and they must be deployed in the client's application directory. Thus, if you wish to create a configuration file for `CSharpCarClient.exe`, it must be named `CSharpCarClient.exe.config`, and be located (for this example) under the `C:\MyApp` directory.

To illustrate the process, create a new directory on your C: drive named `MyApp` using Windows Explorer. Next, copy `CSharpCarClient.exe` and `CarLibrary.dll` to this new folder, and run the program by double-clicking the executable. Your program should run successfully at this point. Next, create a new subdirectory under `C:\MyApp` named `MyLibraries` (see Figure 14-12), and move `CarLibrary.dll` to this location.




Figure 14-12. CarLibrary.dll now resides under the MyLibraries subdirectory

Try to run your client program again. Because the CLR could not locate an assembly named CarLibrary directly within the application directory, you are presented with a rather nasty unhandled FileNotFoundException exception.

To instruct the CLR to probe under the MyLibraries subdirectory, create a new configuration file named CSharpCarClient.exe.config using any text editor, and save the file in the folder containing the CSharpCarClient.exe application, which, in this example is C:\MyApp. Open this file and enter the following content exactly as shown (be aware that XML is case sensitive!):

```
<configuration>
  <runtime>
    <assemblyBinding xmlns="urn:schemas-microsoft-com:asm.v1">
      <probing privatePath="MyLibraries"/>
    </assemblyBinding>
  </runtime>
</configuration>
```

.NET *.config files always open with a root element named `<configuration>`. The nested `<runtime>` element may specify an `<assemblyBinding>` element, which nests a further element named `<probing>`. The `privatePath` attribute is the key point in this example, as it is used to specify the subdirectories relative to the application directory where the CLR should probe.

Once you've finished creating CSharpCarClient.exe.config, run the client by double-clicking the executable in Windows Explorer. You should find that CSharpCarClient.exe executes without a hitch (if this is not the case, double-check your *.config file for typos).

Do note that the `<probing>` element does not specify *which* assembly is located under a given subdirectory. In other words, you cannot say, "CarLibrary is located under the MyLibraries subdirectory, but MathLibrary is located under the OtherStuff subdirectory." The `<probing>` element simply instructs the CLR to investigate all specified subdirectories for the requested assembly until the first match is encountered.

■ **Note** Be very aware that the `privatePath` attribute cannot be used to specify an absolute (`C:\SomeFolder\SomeSubFolder`) or relative (`..\SomeFolder\AnotherFolder`) path! If you wish to specify a directory outside the client's application directory, you will need to use a completely different XML element named `<codeBase>` (more details on this element later in the chapter).

Multiple subdirectories can be assigned to the `privatePath` attribute using a semicolon-delimited list. You have no need to do so at this time, but here is an example that informs the CLR to consult the `MyLibraries` and `MyLibraries\Tests` client subdirectories:

```
<probing privatePath="MyLibraries;MyLibraries\Tests"/>
```

Next, for testing purposes, change the name of your configuration file (in one way or another) and attempt to run the program once again. The client application should now fail. Remember that `*.config` files must be prefixed with the same name as the related client application. By way of a final test, open your configuration file for editing and capitalize any of the XML elements. Once the file is saved, your client should fail to run once again (as XML is case sensitive).

■ **Note** Understand that the CLR will load the very first assembly it finds during the probing process. For example, if the `C:\MyApp` folder did contain a copy of `CarLibrary.dll`, it will be loaded into memory, while the copy under `MyLibraries` is effectively ignored.

Configuration Files and Visual Studio 2010

While you are always able to create XML configuration files by hand using your text editor of choice, Visual Studio 2010 allows you create a configuration file during the development of the client program. To illustrate, load the `CSharpCarClient` solution into Visual Studio 2010 and insert a new Application Configuration File item using the Project ▶ Add New Item menu selection (see Figure 14-13).




Figure 14-13. Inserting a new App.config file into a new Visual Studio 2010 project

Before you click the OK button, take note that the file is named App.config (don't rename it!). If you look in the Solution Explorer window, you will find App.config has been inserted into your current project (Figure 14-14).




Figure 14-14. Edit the App.config file to store the necessary data for client applications.

At this point, you are free to enter the necessary XML elements for the client you happen to be creating. Now, here is the cool thing. Each time you compile your project, Visual Studio 2010 will automatically copy the data in App.config to the \bin\Debug directory using the proper naming convention (such as CSharpCarClient.exe.config). However, this behavior will happen only if your configuration file is indeed named App.config; see Figure 14-15.




Figure 14-15. The contents of `App.config` will be copied to a correctly named `*.config` in your output directory

Using this approach, all you need to do is maintain `App.config`, and Visual Studio 2010 will ensure your application directory contains the latest and greatest configuration data (even if you happen to rename your project).

Note Using `App.config` files within Visual Studio 2010 is always recommended. If you manually add a `*.config` file to your `bin\Debug` folder via Windows Explorer, Visual Studio 2010 may delete or change your file at the next compilation!

Understanding Shared Assemblies

Now that you understand how to deploy and configure a private assembly, you can begin to examine the role of a *shared assembly*. Like a private assembly, a shared assembly is a collection of types and (optional) resources. The most obvious difference between shared and private assemblies is the fact that a single copy of a shared assembly can be used by several applications on the same machine.

Consider all the applications created in this text that required you to set a reference to `System.Windows.Forms.dll`. If you were to look in the application directory of each of these clients, you would *not* find a private copy of this .NET assembly. The reason is that `System.Windows.Forms.dll` has been deployed as a shared assembly. Clearly, if you need to create a machine-wide class library, this is the way to go.

Note Deciding whether a code library should be deployed as a private or shared library is yet another design issue to contend with, and this will be based on many project-specific details. As a rule of thumb, when you are building libraries that need to be used by a wide variety of applications, shared assemblies can be quite helpful in that they can be updated to new versions very easily (as you will see).

As suggested in the previous paragraph, a shared assembly is not deployed within the same directory as the application that uses it. Rather, shared assemblies are installed into the Global Assembly Cache (GAC). The GAC is located in a subdirectory of your Windows directory named Assembly (e.g., C:\Windows\assembly), as shown in Figure 14-16.




Figure 14-16. The global assembly cache

Note You cannot install executable assemblies (*.exe) into the GAC. Only assemblies that take the *.dll file extension can be deployed as a shared assembly.

Understanding Strong Names

Before you can deploy an assembly to the GAC, you must assign it a *strong name*, which is used to uniquely identify the publisher of a given .NET binary. Understand that a “publisher” can be an individual programmer, a department within a given company, or an entire company.

In some ways, a strong name is the modern-day .NET equivalent of the COM globally unique identifier (GUID) identification scheme. If you have a COM background, you may recall that AppIDs are GUIDs that identify a particular COM application. Unlike COM GUID values (which are nothing more than 128-bit numbers), strong names are based (in part) on two cryptographically related keys (*public keys* and *private keys*), which are much more unique and resistant to tampering than a simple GUID.

Formally, a strong name is composed of a set of related data, much of which is specified using assembly-level attributes:

- The friendly name of the assembly (which, you recall, is the name of the assembly minus the file extension)
- The version number of the assembly (assigned using the `[AssemblyVersion]` attribute)
- The public key value (assigned using the `[AssemblyKeyFile]` attribute)
- An optional culture identity value for localization purposes (assigned using the `[AssemblyCulture]` attribute)
- An embedded *digital signature* created using a hash of the assembly’s contents and the private key value

To provide a strong name for an assembly, your first step is to generate public/private key data using the .NET Framework 4.0 SDK’s `sn.exe` utility (which you’ll do in a moment). The `sn.exe` utility generates a file (typically ending with the `*.snk` [Strong Name Key] file extension) that contains data for two distinct but mathematically related keys, the public key and the private key. Once the C# compiler is made aware of the location of your `*.snk` file, it will record the full public key value in the assembly manifest using the `.publickey` token at the time of compilation.

The C# compiler will also generate a hash code based on the contents of the entire assembly (CIL code, metadata, and so forth). As you recall from Chapter 6, a *hash code* is a numerical value that is statistically unique for a fixed input. Thus, if you modify any aspect of a .NET assembly (even a single character in a string literal) the compiler yields a different hash code. This hash code is combined with the private key data within the `*.snk` file to yield a digital signature embedded within the assembly’s CLR header data. The process of strongly naming an assembly is illustrated in Figure 14-17.




Figure 14-17. At compile time, a digital signature is generated and embedded into the assembly based in part on public and private key data

Understand that the actual private key data is not listed anywhere within the manifest, but is used only to digitally sign the contents of the assembly (in conjunction with the generated hash code). Again, the whole idea of using public/private key data is to ensure that no two companies, departments, or individuals have the same identity in the .NET universe. In any case, once the process of assigning a strong name is complete, the assembly may be installed into the GAC.

Note Strong names also provide a level of protection against potential evildoers tampering with your assembly's contents. Given this point, it is considered a .NET best practice to strongly name every assembly (including *.exe assemblies), regardless of whether it is deployed to the GAC.

Generating Strong Names at the Command Line

Let's walk through the process of assigning a strong name to the `CarLibrary` assembly created earlier in this chapter. These days, you will most likely generate the required `*.snk` file using Visual Studio 2010, however in the bad old days (circa 2003), the only option for strongly signing an assembly was to do so at the command line. Let's see how to do this.

The first order of business is to generate the required key data using the `sn.exe` utility. Although this tool has numerous command-line options, all you need to concern yourself with for the moment is the `-k` flag, which instructs the tool to generate a new file containing the public/private key information. Create a new folder on your C drive named `MyTestKeyPair` and change to that directory using the Visual Studio 2010 command prompt. Next, issue the following command to generate a file named `MyTestKeyPair.snk`:

```
sn -k MyTestKeyPair.snk
```

Now that you have your key data, you need to inform the C# compiler exactly where `MyTestKeyPair.snk` is located. Recall from earlier in this chapter, when you create any new C# project workspace using Visual Studio 2010, one of the initial project files (located under the Properties node of Solution Explorer) is named `AssemblyInfo.cs`. This file contains a number of attributes that describe the assembly itself. The `[AssemblyKeyFile]` assembly-level attribute can be added to your `AssemblyInfo.cs` file to inform the compiler of the location of a valid `*.snk` file. Simply specify the path as a string parameter, for example:

```
[assembly: AssemblyKeyFile(@"C:\MyTestKeyPair\MyTestKeyPair.snk")]
```

Note When you manually specify the `[AssemblyKeyFile]` attribute, Visual Studio 2010 will generate a warning informing you to use the `/keyfile` option of `csc.exe` or to establish the key file via the Visual Studio 2010 Properties window. You'll use the IDE to do so in just a moment (so feel free to ignore the generated warning).

Because the version of a shared assembly is one aspect of a strong name, selecting a version number for `CarLibrary.dll` is a necessary detail. In the `AssemblyInfo.cs` file, you will find another attribute named `[AssemblyVersion]`. Initially the value is set to `1.0.0.0`:

```
[assembly: AssemblyVersion("1.0.0.0")]
```

A .NET version number is composed of the four parts (`<major>.<minor>.<build>.<revision>`). While specifying a version number is entirely up to you, you can instruct Visual Studio 2010 to automatically increment the build and revision numbers as part of each compilation using the wildcard token, rather than with a specific build and revision value. We have no need to do so for this example; however, consider the following:

```
// Format: <Major number>.<Minor number>.<Build number>.<Revision number>
// Valid values for each part of the version number are between 0 and 65535.
[assembly: AssemblyVersion("1.0.*")]
```

At this point, the C# compiler has all the information needed to generate strong name data (as you are not specifying a unique culture value via the `[AssemblyCulture]` attribute, you "inherit" the culture of your current machine, which in my case would be US English).

Compile your `CarLibrary` code library, open your assembly into `ildasm.exe`, and check the manifest. You will now see that a new `.publickey` tag is used to document the full public key information, while the `.ver` token records the version specified via the `[AssemblyVersion]` attribute (see Figure 14-18).




Figure 14-18. A strongly named assembly records the public key in the manifest

Great! At this point we could deploy our shared `CarLibrary.dll` assembly to the GAC. However, remember that these days, .NET developers can use Visual Studio to create strongly named assemblies using a friendly user interface rather than the cryptic `sn.exe` command line tool. Before seeing how to do so, be sure you delete (or comment out) the following line of code from your `AssemblyInfo.cs` file (assuming you manually added this line during this section of the text):

```
// [assembly: AssemblyKeyFile(@"C:\MyTestKeyValuePair\MyTestKeyValuePair.snk")]
```

Generating Strong Names using Visual Studio 2010

Visual Studio 2010 allows you to specify the location of an existing `*.snk` file using the project's Properties page, as well as generate a new `*.snk` file. To do so for the `CarLibrary` project, first double-click on the Properties icon of the Solution Explorer, and select the Signing tab. Next, select the Sign the assembly check box, and choose the New... option (see Figure 14-19).




Figure 14-19. Creating a new *.snk file using Visual Studio 2010

Once you have done so, you will be asked to provide a name for your new *.snk file (such as myKeyFile.snk) and you'll have the option to password-protect your file (which is not required for this example); see Figure 14-20.



Figure 14-20. Naming the new *.snk file using Visual Studio 2010

At this point, you will see your *.snk file within the Solution Explorer (Figure 14-21). Every time you build your application, this data will be used to assign a proper strong name to the assembly.




Figure 14-21. Visual Studio 2010 will now strongly sign your assembly with each compilation

■ **Note** Recall that the Application tab of the Properties editor provides a button named Assembly Information. When clicked, the button displays a dialog box that allows you to establish numerous assembly-level attributes, including the version number, copyright information, and so forth.

Installing Strongly Named Assemblies to the GAC

The final step is to install the (now strongly named) `CarLibrary.dll` into the GAC. While the preferred way to deploy assemblies to the GAC in a production setting is to create a Windows MSI installer package (or use a commercial installer program such as InstallShield), the .NET Framework 4.0 SDK ships with a command-line tool named `gacutil.exe`, which can be useful for quick tests.

■ **Note** You must have administrator rights to interact with the GAC on your machine, which may include adjusting the User Access Control (UAC) settings on Windows Vista or Windows 7.

Table 14-1 documents some relevant options of `gacutil.exe` (specify the `/?` flag when you run the program to see each option).

Table 14-1. Various Options of `gacutil.exe`

Option	Meaning in Life
<code>/i</code>	Installs a strongly named assembly into the GAC
<code>/u</code>	Uninstalls an assembly from the GAC
<code>/l</code>	Displays the assemblies (or a specific assembly) in the GAC

To install a strongly named assembly using gacutil.exe, first open a Visual Studio 2010 Command Prompt, change to the directory containing CarLibrary.dll, for example (your path may differ):

```
cd C:\MyCode\CarLibrary\bin\Debug
```

Next, install the library using the -i command:

```
gacutil -i CarLibrary.dll
```

Once you have done so, you can verify that the library has been deployed by specifying the -l command (note that you omit the file extension when using the /l command):

```
gacutil -l CarLibrary
```

If all is well, you should see the following output to the Console window (you will find a unique PublicKeyToken value, as expected):

```
The Global Assembly Cache contains the following assemblies:  
carlibrary, Version=1.0.0.0, Culture=neutral, PublicKeyToken=33a2bc294331e8b9,  
processorArchitecture=MSIL
```

Viewing the .NET 4.0 GAC using Windows Explorer

If you read previous editions of this book that covered .NET 1.0-.NET 3.5, this is where I would be telling you to open your machine's Windows Explorer and view your installed CarLibrary in the GAC, simply by navigating to C:\Windows\assembly.

However (and this is a very big however), if you attempted to do so now, you would be stunned to find that you *cannot* see the expected CarLibrary icon under C:\Windows\assembly, even though gacutil.exe has verified the library has been installed!

With the release of .NET 4.0, the GAC has been split in two. Specifically, under C:\Windows\assembly you will find the location of the .NET 1.0-.NET 3.5 base class libraries (as well as various oddball assemblies, including libraries from third-party vendors). However, when you compile an assembly under .NET 4.0, and deploy it to the GAC using gacutil.exe, your library will be deployed to a brand-new location: C:\Windows\Microsoft.NET\assembly\GAC_MSIL.

Under this new folder, you will find a set of subdirectories, each of which is named identically to the friendly name of a particular code library (for example, \System.Windows.Forms, \System.Core, and so on). Beneath a given friendly name folder, you'll find yet another subdirectory that always takes the following naming convention:

```
v4.0_major.minor.build.revision_publicKeyValue
```

The "v4.0" prefix denotes that the library compiled under .NET version 4.0. That prefix is followed by a single underbar, then the version of the library in question, which in this example is version 1.0.0.0 of CarLibrary.dll. After a pair of underbars, you'll see the publickeytoken value based on your strong name. Figure 14-22 shows the directory structure of my version of CarLibrary.dll on my Windows 7 operating system.




Figure 14-22. The strongly named, shared CarLibrary (version 1.0.0.0)

Consuming a Shared Assembly

When you are building applications that use a shared assembly, the only difference from consuming a private assembly is in how you reference the library using Visual Studio 2010. In reality, there is no difference as far as the tool is concerned—you still use the Add Reference dialog box. However, this dialog box will *not* allow you to reference the assembly by browsing to the C:\Windows\assembly folder, which is specific to .NET 3.5 and earlier.

Note Seasoned .NET developers may recall that even when you navigated to C:\Windows\assembly, the Visual Studio Add Reference dialog refused to let you reference shared libraries! Because of this, developers had to maintain a separate copy of the library, simply for the purpose of referencing the assembly. The story under Visual Studio 2010 is much nicer. Read on...

When you need to reference an assembly that has been deployed to the .NET 4.0 GAC, you will need to browse to the "v4.0_major.minor.build.revision_publicKeyTokenValue" directory for your particular library via the Browse tab (see Figure 14-23).




Figure 14-23. Referencing the strongly named, shared CarLibrary (version 1.0.0.0) using Visual Studio 2010

This (somewhat confusing) fact aside, create a new C# Console Application named SharedCarLibClient and reference your CarLibrary.dll assembly as just described. As you would hope, you can now see an icon in your Solution Explorer's Reference folder. If you select this icon and then view the Properties window (accessible from the Visual Studio View menu), you'll notice that the Copy Local property of the selected CarLibrary is now set to False. In any case, author the following test code in your new client application:

```
using System;
using System.Collections.Generic;
using System.Linq;
using System.Text;

using CarLibrary;

namespace SharedCarLibClient
{
    class Program
    {
        static void Main(string[] args)
        {
            Console.WriteLine("***** Shared Assembly Client *****");
            SportsCar c = new SportsCar();
            c.TurboBoost();
            Console.ReadLine();
        }
    }
}
```

```
    }
}
```

Once you have compiled your client application, navigate to the directory that contains `SharedCarLibClient.exe` using Windows Explorer and notice that Visual Studio 2010 has *not* copied `CarLibrary.dll` to the client's application directory. When you reference an assembly whose manifest contains a `.publickeytoken` value, Visual Studio 2010 assumes the strongly named assembly will most likely be deployed to the GAC, and therefore does not bother to copy the binary.

Exploring the Manifest of SharedCarLibClient

Recall that when you generate a strong name for an assembly, the entire public key is recorded in the assembly manifest. On a related note, when a client references a strongly named assembly, its manifest records a condensed hash value of the full public key, denoted by the `.publickeytoken` tag. If you open the manifest of `SharedCarLibClient.exe` using `ildasm.exe`, you would find the following (your public key token value will of course differ, as it is computed based on the public key value):

```
.assembly extern CarLibrary
{
    .publickeytoken = (33 A2 BC 29 43 31 E8 B9 )
    .ver 1:0:0:0
}
```

If you compare the value of the public key token recorded in the client manifest with the public key token value shown in the GAC, you will find a dead-on match. Recall that a public key represents one aspect of the strongly named assembly's identity. Given this, the CLR will only load version 1.0.0.0 of an assembly named `CarLibrary` that has a public key that can be hashed down to the value `33A2BC294331E8B9`. If the CLR does not find an assembly meeting this description in the GAC (and did not find a private assembly named `CarLibrary` in the client's directory), a `FileNotFoundException` exception is thrown.

■ Source Code The `SharedCarLibClient` application can be found under the Chapter 14 subdirectory.

Configuring Shared Assemblies

Like private assemblies, shared assemblies can be configured using a client `*.config` file. Of course, because shared assemblies are deployed to a well-known location (the .NET 4.0 GAC), you don't use the `<privatePath>` element as you did for private assemblies (although if the client is using both shared and private assemblies, the `<privatePath>` element may still exist in the `*.config` file).

You can use application configuration files in conjunction with shared assemblies whenever you wish to instruct the CLR to bind to a *different* version of a specific assembly, effectively bypassing the value recorded in the client's manifest. This can be useful for a number of reasons. For example, imagine that you have shipped version 1.0.0.0 of an assembly and later discover a major bug. One corrective action would be to rebuild the client application to reference the correct version of the bug-free assembly (say, 1.1.0.0) and redistribute the updated client and new library to every target machine.

Another option is to ship the new code library and a *.config file that automatically instructs the runtime to bind to the new (bug-free) version. As long as the new version has been installed into the GAC, the original client runs without recompilation, redistribution, or fear of having to update your resume.

Here's another example: you have shipped the first version of a bug-free assembly (1.0.0.0), and after a month or two, you add new functionality to the assembly to yield version 2.0.0.0. Obviously, existing client applications that were compiled against version 1.0.0.0 have no clue about these new types, given that their code base makes no reference to them.

New client applications, however, wish to make reference to the new functionality in version 2.0.0.0. Under .NET, you are free to ship version 2.0.0.0 to the target machines, and have version 2.0.0.0 run alongside the older version 1.0.0.0. If necessary, existing clients can be dynamically redirected to load version 2.0.0.0 (to gain access to the implementation refinements), using an application configuration file without needing to recompile and redeploy the client application.

Freezing the Current Shared Assembly

To illustrate how to dynamically bind to a specific version of a shared assembly, open Windows Explorer and copy the current version of the compiled CarLibrary.dll assembly (1.0.0.0) into a distinct subdirectory (I called mine "CarLibrary Version 1.0.0.0") to symbolize the freezing of this version (see Figure 14-24).




Figure 14-24. Freezing the current version of *CarLibrary.dll*

Building Shared Assembly Version 2.0.0.0

Now, open your existing CarLibrary project and update your code base with a new enum type named MusicMedia that defines four possible musical devices:

```
// Which type of music player does this car have?
public enum MusicMedia
```

```
{
    musicCd,
    musicTape,
    musicRadio,
    musicMp3
}
```

As well, add a new public method to the Car type that allows the caller to turn on one of the given media players (be sure to import the System.Windows.Forms namespace within Car.cs if necessary):

```
public abstract class Car
{
    ...
    public void TurnOnRadio(bool musicOn, MusicMedia mm)
    {
        if(musicOn)
            MessageBox.Show(string.Format("Jamming {0}", mm));
        else
            MessageBox.Show("Quiet time...");
    }
    ...
}
```

Update the constructors of the Car class to display a MessageBox that verifies you are indeed using CarLibrary 2.0.0.0:

```
public abstract class Car
{
    ...
    public Car()
    {
        MessageBox.Show("CarLibrary Version 2.0!");
    }
    public Car(string name, int maxSp, int currSp)
    {
        MessageBox.Show("CarLibrary Version 2.0!");
        PetName = name; MaxSpeed = maxSp; CurrentSpeed = currSp;
    }
    ...
}
```

Last but not least, before you recompile your new library, update the version to be 2.0.0.0. Recall you can do so in a visual manner by double-clicking on the Properties icon of the Solution Explorer and clicking on the Assembly Information... button on the Application tab. Once you do, simply update the Assembly Version number (Figure 14-25).



Figure 14-25. Setting the version number of *CarLibrary.dll* to 2.0.0.0

If you look in your project's \bin\Debug folder, you'll see that you have a new version of this assembly (2.0.0.0), while version 1.0.0.0 is safe in storage in the CarLibrary Version 1.0.0.0 directory. Install this new assembly into the 4.0 GAC using gacutil.exe as described earlier in this chapter. Notice that you now have two versions of the same assembly (see Figure 14-26).




Figure 14-26. Side-by-side execution of a shared assembly

If you run the current `SharedCarLibClient.exe` program by double-clicking the icon in Windows Explorer, you should *not* see the “CarLibrary Version 2.0!” message box appear, as the manifest is specifically requesting version 1.0.0.0. How then can you instruct the CLR to bind to version 2.0.0.0? Glad you asked!

Note Visual Studio 2010 will automatically reset references when you compile your applications! Therefore, if you run your `SharedCarLibClient.exe` application within Visual Studio 2010, it will grab `CarLibrary.dll` version 2.0.0.0! If you accidentally ran your application in this way, simply delete the current `CarLibrary.dll` reference and select version 1.0.0.0 (which I suggested you place in a folder named CarLibrary Version 1.0.0.0).

Dynamically Redirecting to Specific Versions of a Shared Assembly

When you want to tell the CLR to load a version of a shared assembly other than the version listed in the manifest, you can build a *.config file that contains a `<dependentAssembly>` element. When doing so, you will need to create an `<assemblyIdentity>` subelement that specifies the friendly name of the assembly listed in the client manifest (`CarLibrary`, for this example) and an optional culture attribute (which can be assigned an empty string or omitted altogether if you wish to use the default culture for the machine). Moreover, the `<dependentAssembly>` element will define a `<bindingRedirect>` subelement to define the version *currently* in the manifest (via the `oldVersion` attribute) and the version in the GAC to load instead (via the `newVersion` attribute).

Create a new configuration file in the application directory of `SharedCarLibClient` named `SharedCarLibClient.exe.config` that contains the following XML data.

Note The value of your public key token will be different from what you see in the following markup, and it can be obtained either by examining the client manifest using `ildasm.exe` or via the GAC.

```

<configuration>
  <runtime>
    <assemblyBinding xmlns="urn:schemas-microsoft-com:asm.v1">
      <dependentAssembly>
        <assemblyIdentity name="CarLibrary"
                          publicKeyToken="33A2BC294331E8B9"
                          culture="neutral"/>
        <bindingRedirect oldVersion= "1.0.0.0"
                        newVersion= "2.0.0.0"/>
      </dependentAssembly>
    </assemblyBinding>
  </runtime>
</configuration>

```

Now run the `SharedCarLibClient.exe` program by double-clicking the executable from Windows Explorer. You should see the message that version 2.0.0.0 has loaded.

Multiple `<dependentAssembly>` elements can appear within a client's configuration file. Although there's no need for this example, assume that the manifest of SharedCarLibClient.exe also references version 2.5.0.0 of an assembly named `MathLibrary`. If you wanted to redirect to version 3.0.0.0 of `MathLibrary` (in addition to version 2.0.0.0 of `CarLibrary`), the `SharedCarLibClient.exe.config` file would look like the following:

```

<configuration>
  <runtime>
    <assemblyBinding xmlns="urn:schemas-microsoft-com:asm.v1">
      <!-- Controls Binding to CarLibrary -->
      <dependentAssembly>
        <assemblyIdentity name="CarLibrary"
          publicKeyToken="33A2BC294331E8B9"
          culture="" />
        <bindingRedirect oldVersion= "1.0.0.0" newVersion= "2.0.0.0"/>
      </dependentAssembly>

      <!-- Controls Binding to MathLibrary -->
      <dependentAssembly>
        <assemblyIdentity name="MathLibrary"
          publicKeyToken="33A2BC294331E8B9"
          culture="" />
        <bindingRedirect oldVersion= "2.5.0.0" newVersion= "3.0.0.0"/>
      </dependentAssembly>
    </assemblyBinding>
  </runtime>
</configuration>

```

Note It is possible to specify a range of old version numbers via the `oldVersion` attribute; for example, `<bindingRedirect oldVersion="1.0.0.0-1.2.0.0" newVersion="2.0.0.0"/>` informs the CLR to use version 2.0.0.0 for any older version within the range of 1.0.0.0 to 1.2.0.0.

Understanding Publisher Policy Assemblies

The next configuration issue we'll examine is the role of *publisher policy assemblies*. As you've just seen, `*.config` files can be constructed to bind to a specific version of a shared assembly, thereby bypassing the version recorded in the client manifest. While this is all well and good, imagine you're an administrator who now needs to reconfigure *all* client applications on a given machine to rebind to version 2.0.0.0 of the `CarLibrary.dll` assembly. Given the strict naming convention of a configuration file, you would need to duplicate the same XML content in numerous locations (assuming you are, in fact, aware of the locations of the executables using `CarLibrary!`). Clearly this would be a maintenance nightmare.

Publisher policy allows the publisher of a given assembly (you, your department, your company, or what have you) to ship a binary version of a `*.config` file that is installed into the GAC along with the newest version of the associated assembly. The benefit of this approach is that client application directories do *not* need to contain specific `*.config` files. Rather, the CLR will read the current manifest

and attempt to find the requested version in the GAC. However, if the CLR finds a publisher policy assembly, it will read the embedded XML data and perform the requested redirection *at the level of the GAC*.

Publisher policy assemblies are created at the command line using a .NET utility named al.exe (the assembly linker). Though this tool provides many options, building a publisher policy assembly requires passing in only the following input parameters:

- The location of the *.config or *.xml file containing the redirecting instructions
- The name of the resulting publisher policy assembly
- The location of the *.snk file used to sign the publisher policy assembly
- The version numbers to assign the publisher policy assembly being constructed

If you wish to build a publisher policy assembly that controls CarLibrary.dll, the command set is as follows (which must be entered on a single line within the command window):

```
al /link: CarLibraryPolicy.xml /out:policy.1.0.CarLibrary.dll
/keyf:C:\MyKey\myKey.snk /v:1.0.0.0
```

Here, the XML content is contained within a file named CarLibraryPolicy.xml. The name of the output file (which must be in the format policy.<major>.<minor>.assemblyToConfigure) is specified using the obvious /out flag. In addition, note that the name of the file containing the public/private key pair will also need to be supplied via the /keyf option. Remember, publisher policy files are shared, and therefore must have strong names!

Once the al.exe tool has executed, the result is a new assembly that can be placed into the GAC to force all clients to bind to version 2.0.0.0 of CarLibrary.dll, without the use of a specific client application configuration file. Using this technique, you can design a machinewide redirection for all applications using a specific version (or range of versions) of an existing assembly.

Disabling Publisher Policy

Now, assume you (as a system administrator) have deployed a publisher policy assembly (and the latest version of the related assembly) to the GAC of a client machine. As luck would have it, nine of the ten affected applications rebind to version 2.0.0.0 without error. However, the remaining client application (for whatever reason) blows up when accessing CarLibrary.dll 2.0.0.0. (As we all know, it is next to impossible to build backward-compatible software that works 100 percent of the time.)

In such a case, it is possible to build a configuration file for a specific troubled client that instructs the CLR to *ignore* the presence of any publisher policy files installed in the GAC. The remaining client applications that are happy to consume the newest .NET assembly will simply be redirected via the installed publisher policy assembly. To disable publisher policy on a client-by-client basis, author a (properly named) *.config file that makes use of the <publisherPolicy> element and set the apply attribute to no. When you do so, the CLR will load the version of the assembly originally listed in the client's manifest.

```
<configuration>
  <runtime>
    <assemblyBinding xmlns="urn:schemas-microsoft-com:asm.v1">
      <publisherPolicy apply="no" />
    </assemblyBinding>
  </runtime>
</configuration>
```

Understanding the <codeBase> Element

Application configuration files can also specify *code bases*. The <codeBase> element can be used to instruct the CLR to probe for dependent assemblies located at arbitrary locations (such as network end points, or an arbitrary machine path outside a client's application directory).

If the value assigned to a <codeBase> element is located on a remote machine, the assembly will be downloaded on demand to a specific directory in the GAC termed the *download cache*. Given what you have learned about deploying assemblies to the GAC, it should make sense that assemblies loaded from a <codeBase> element will need to be assigned a strong name (after all, how else could the CLR install remote assemblies to the GAC?). If you are interested, you can view the content of your machine's download cache by supplying the /ldl option to gacutil.exe:

```
gacutil /ldl
```

■ **Note** Technically speaking, the <codeBase> element can be used to probe for assemblies that do not have a strong name. However, the assembly's location must be relative to the client's application directory (and thus is little more than an alternative to the <privatePath> element).

To see the <codeBase> element in action, create a Console Application named CodeBaseClient, set a reference to CarLibrary.dll version 2.0.0.0, and update the initial file as follows:

```
using System;
using System.Collections.Generic;
using System.Linq;
using System.Text;
using CarLibrary;

namespace CodeBaseClient
{
    class Program
    {
        static void Main(string[] args)
        {
            Console.WriteLine("***** Fun with CodeBases *****");
            SportsCar c = new SportsCar();
            Console.WriteLine("Sports car has been allocated.");
            Console.ReadLine();
        }
    }
}
```

Given that CarLibrary.dll has been deployed to the GAC, you are able to run the program as is. However, to illustrate the use of the <codeBase> element, create a new folder under your C: drive (perhaps C:\MyAsms) and place a copy of CarLibrary.dll version 2.0.0.0 into this directory.

Now, add an `App.config` file to the `CodeBaseClient` project (as explained earlier in this chapter) and author the following XML content (remember that your `.publickeytoken` value will differ; consult your GAC as required):

```
<configuration>
  <runtime>
    <assemblyBinding xmlns="urn:schemas-microsoft-com:asm.v1">
      <dependentAssembly>
        <assemblyIdentity name=" CarLibrary" publicKeyToken="33A2BC294331E8B9" />
        <codeBase version="2.0.0.0" href="file:///C:/MyAsms/CarLibrary.dll" />
      </dependentAssembly>
    </assemblyBinding>
  </runtime>
</configuration>
```

As you can see, the `<codeBase>` element is nested within the `<assemblyIdentity>` element, which makes use of the `name` and `publicKeyToken` attributes to specify the friendly name as associated `publicKeyToken` values. The `<codeBase>` element itself specifies the version and location (via the `href` property) of the assembly to load. If you were to delete version 2.0.0.0 of `CarLibrary.dll` from the GAC, this client would still run successfully, as the CLR is able to locate the external assembly under `C:\MyAsms`.

Note If you place assemblies at random locations on your development machine, you are in effect re-creating the system registry (and the related DLL hell), given that if you move or rename the folder containing your binaries, the current bind will fail. With that in mind, use `<codeBase>` with caution.

The `<codeBase>` element can also be helpful when referencing assemblies located on a remote networked machine. Assume you have permission to access a folder located at `http://www.MySite.com`. To download the remote `*.dll` to the GAC's download cache on your local machine, you could update the `<codeBase>` element as follows:

```
<codeBase version="2.0.0.0"
  href="http://www.MySite.com/Assemblies/CarLibrary.dll" />
```

Source Code The `CodeBaseClient` application can be found under the Chapter 14 subdirectory.

The `System.Configuration` Namespace

Currently, all of the `*.config` files shown in this chapter have made use of well-known XML elements that are read by the CLR to resolve the location of external assemblies. In addition to these recognized elements, it is perfectly permissible for a client configuration file to contain application-specific data that has nothing to do with binding heuristics. Given this, it should come as no surprise that the .NET

Framework provides a namespace that allows you to programmatically read the data within a client configuration file.

The `System.Configuration` namespace provides a small set of types you can use to read custom data from a client's *.config file. These custom settings must be contained within the scope of an `<appSettings>` element. The `<appSettings>` element contains any number of `<add>` elements that define key/value pairs to be obtained programmatically.

For example, assume you have an `App.config` file for a Console Application named `AppConfigReaderApp` that defines two application specific values, listed like so:

```
<configuration>
  <appSettings>
    <add key="TextColor" value="Green" />
    <add key="RepeatCount" value="8" />
  </appSettings>
</configuration>
```

Reading these values for use by the client application is as simple as calling the instance-level `GetValue()` method of the `System.Configuration.AppSettingsReader` type. As shown in the following code, the first parameter to `GetValue()` is the name of the key in the *.config file, whereas the second parameter is the underlying type of the key (obtained via the C# `typeof` operator):

```
using System;
using System.Collections.Generic;
using System.Linq;
using System.Text;
using System.Configuration;

namespace AppConfigReaderApp
{
    class Program
    {
        static void Main(string[] args)
        {
            Console.WriteLine("***** Reading <appSettings> Data *****\n");

            // Get our custom data from the *.config file.
            AppSettingsReader ar = new AppSettingsReader();
            int numbOfTimes = (int)ar.GetValue("RepeatCount", typeof(int));
            string textColor = (string)ar.GetValue("TextColor", typeof(string));

            Console.ForegroundColor =
                (ConsoleColor)Enum.Parse(typeof(ConsoleColor), textColor);

            // Now print a message correctly.
            for (int i = 0; i < numbOfTimes; i++)
                Console.WriteLine("Howdy!");
            Console.ReadLine();
        }
    }
}
```

As you work throughout the remainder of the book, you will find many other important sections that can be found within a client (or web-based) configuration file. To be sure, the deeper you dive into .NET programming, the more critical an understanding of XML configuration files become.

■ **Source Code** The AppConfigReaderApp application can be found under the Chapter 14 subdirectory.

Summary

This chapter drilled down into the details of how the CLR resolves the location of externally referenced assemblies. You began by examining the content within an assembly: headers, metadata, manifests, and CIL. Then you constructed single-file and multifile assemblies and a handful of client applications (written in a language-agnostic manner).

As you have seen, assemblies can be private or shared. Private assemblies are copied to the client's subdirectory, whereas shared assemblies are deployed to the GAC, provided they have been assigned a strong name. Finally, private and shared assemblies can be configured using a client-side XML configuration file or, alternatively, via a publisher policy assembly.



Type Reflection, Late Binding, and Attribute-Based Programming

As shown in the previous chapter, assemblies are the basic unit of deployment in the .NET universe. Using the integrated object browsers of Visual Studio 2010 (and numerous other IDEs), you are able to examine the types within a project's referenced set of assemblies. Furthermore, external tools such as `ildasm.exe` and `reflector.exe` allow you to peek into the underlying CIL code, type metadata, and assembly manifest for a given .NET binary. In addition to this design-time investigation of .NET assemblies, you are also able to *programmatically* obtain this same information using the `System.Reflection` namespace. To this end, the first task of this chapter is to define the role of reflection and the necessity of .NET metadata.

The remainder of the chapter examines a number of closely related topics, all of which hinge upon reflection services. For example, you'll learn how a .NET client may employ dynamic loading and late binding to activate types it has no compile-time knowledge of. You'll also learn how to insert custom metadata into your .NET assemblies through the use of system-supplied and custom attributes. To put all of these (seemingly esoteric) topics into perspective, the chapter closes by demonstrating how to build several "snap-in objects" that you can plug into an extendable Windows Forms application.

The Necessity of Type Metadata

The ability to fully describe types (classes, interfaces, structures, enumerations, and delegates) using metadata is a key element of the .NET platform. Numerous .NET technologies, such as object serialization, .NET remoting, XML web services, and Windows Communication Foundation (WCF), require the ability to discover the format of types at runtime. Furthermore, cross-language interoperability, numerous compiler services, and an IDE's IntelliSense capabilities all rely on a concrete description of *type*.

Regardless of (or perhaps due to) its importance, metadata is not a new idea supplied by the .NET Framework. Java, CORBA, and COM all have similar concepts. For example, COM type libraries (which are little more than compiled IDL code) are used to describe the types contained within a COM server. Like COM, .NET code libraries also support type metadata. Of course, .NET metadata has no syntactic similarities to COM IDL.

Recall that the `ildasm.exe` utility allows you to view an assembly's type metadata using the Ctrl+M keyboard option (see Chapter 1). Thus, if you were to open any of the *.dll or *.exe assemblies created over the course of this book (such as the `CarLibrary.dll` created in the previous chapter) using `ildasm.exe` and press Ctrl+M, you would find the relevant type metadata (see Figure 15-1).




Figure 15-1. Viewing an assembly's metadata using ildasm.exe

As you can see, ildasm.exe's display of .NET type metadata is very verbose (the actual binary format is much more compact). In fact, if I were to list the entire metadata description representing the CarLibrary.dll assembly, it would span several pages. Given that this act would be a woeful waste of paper, let's just glimpse into some key metadata descriptions of the CarLibrary.dll assembly.

■ **Note** Don't be too concerned with the exact syntax of each and every piece of .NET metadata in the next few sections. The bigger point to absorb is that .NET metadata is very descriptive and lists each internally defined (and externally referenced) type found within a given code base.

Viewing (Partial) Metadata for the EngineState Enumeration

Each type defined within the current assembly is documented using a TypeDef #n token (where TypeDef is short for *type definition*). If the type being described uses a type defined within a separate .NET assembly, the referenced type is documented using a TypeRef #n token (where TypeRef is short for *type reference*). A TypeRef token is a pointer (if you will) to the referenced type's full metadata definition in an external assembly. In a nutshell, .NET metadata is a set of tables that clearly mark all type definitions (TypeDefs) and referenced types (TypeRefs), all of which can be viewed using ildasm.exe's metadata window.

As far as CarLibrary.dll goes, one TypeDef is the metadata description of the CarLibrary.EngineState enumeration (your number may differ; TypeDef numbering is based on the order in which the C# compiler processes the file):

```
TypeDef #2 (02000003)
-----
TypeDefName: CarLibrary.EngineState (02000003)
Flags : [Public] [AutoLayout] [Class] [Sealed] [AnsiClass] (00000101)
Extends : 01000001 [TypeRef] System.Enum
Field #1 (04000006)

-----
Field Name: value_ (04000006)
Flags : [Public] [SpecialName] [RTSpecialName] (00000606)
CallCnvntn: [FIELD]
Field type: I4

Field #2 (04000007)

-----
Field Name: engineAlive (04000007)
Flags : [Public] [Static] [Literal] [HasDefault] (00008056)
DefltValue: (I4) 0
CallCnvntn: [FIELD]
Field type: ValueClass CarLibrary.EngineState
...

```

Here, the TypDefName token is used to establish the name of the given type, which in this case is the custom `CarLibrary.EngineState` enum. The Extends metadata token is used to document the base type of a given .NET type (in this case, the referenced type, `System.Enum`). Each field of an enumeration is marked using the Field #n token. For brevity, I have simply listed the metadata for `CarLibrary.EngineState.engineAlive`.

Viewing (Partial) Metadata for the Car Type

Here is a partial dump of the `Car` class that illustrates the following:

- How fields are defined in terms of .NET metadata
- How methods are documented via .NET metadata
- How an automatic property is represented in .NET metadata

```
TypeDef #3 (02000004)
-----
TypeDefName: CarLibrary.Car (02000004)
Flags : [Public] [AutoLayout] [Class] [Abstract]
      [AnsiClass] [BeforeFieldInit] (00100081)
Extends : 01000002 [TypeRef] System.Object
...
Field #2 (0400000a)

-----
Field Name: <PetName>k__BackingField (0400000A)
Flags : [Private] (00000001)
CallCnvntn: [FIELD]
Field type: String
```

...

Method #1 (06000001)

```
MethodName: get_PetName (06000001)
Flags      : [Public] [HideBySig] [ReuseSlot] [SpecialName] (00000886)
RVA       : 0x000020d0
ImplFlags : [IL] [Managed] (00000000)
CallCnvntn: [DEFAULT]
hasThis
ReturnType: String
No arguments.
```

...

Method #2 (06000002)

```
MethodName: set_PetName (06000002)
Flags      : [Public] [HideBySig] [ReuseSlot] [SpecialName] (00000886)
RVA       : 0x000020e7
ImplFlags : [IL] [Managed] (00000000)
CallCnvntn: [DEFAULT]
hasThis
ReturnType: Void
1 Arguments
  Argument #1: String
1 Parameters
  (1) ParamToken : (08000001) Name : value flags: [none] (00000000)
...
```

Property #1 (17000001)

```
Prop.Name : PetName (17000001)
Flags      : [none] (00000000)
CallCnvntn: [PROPERTY]
hasThis
ReturnType: String
No arguments.
DefltValue:
Setter    : (06000002) set_PetName
Getter    : (06000001) get_PetName
0 Others
...
```

First, note that the Car class metadata marks the type's base class (`System.Object`) and includes various flags that describe how this type was constructed (e.g., `[Public]`, `[Abstract]`, and whatnot). Methods (such as our Car's constructor) are described in regard to their parameters, return value, and name.

Note how an automatic property results in a compiler generated private backing field (which was named `<PetName>k__BackingField`) and two compiler generated methods (in the case of a read/write property) named in this example, `get_PetName()` and `set_PetName()`. Finally, the actual property itself is mapped to the internal get/set methods using the .NET metadata `Getter/Setter` tokens.

Examining a TypeRef

Recall that an assembly's metadata will describe not only the set of internal types (Car, EngineState, etc.), but also any external types the internal types reference. For example, given that `CarLibrary.dll` has defined two enumerations, you find a `TypeRef` block for the `System.Enum` type:

```
TypeRef #1 (01000001)
```

```
-----  
Token: 0x01000001  
ResolutionScope: 0x23000001  
TypeRefName: System.Enum
```

Documenting the Defining Assembly

The `ildasm.exe` metadata window also allows you to view the .NET metadata that describes the assembly itself using the `Assembly` token. As you can see from the following (partial) listing, information documented within the `Assembly` table is (surprise, surprise!) the same information that can be viewable via the MANIFEST icon. The following is a partial dump of the manifest of `CarLibrary.dll` (version 2.0.0.0):

```
Assembly
```

```
-----  
Token: 0x20000001  
Name : CarLibrary  
Public Key : 00 24 00 00 04 80 00 00 // Etc...  
  
Hash Algorithm : 0x00008004  
Major Version: 0x00000002  
Minor Version: 0x00000000  
Build Number: 0x00000000  
Revision Number: 0x00000000  
Locale: <null>  
Flags : [PublicKey] ...
```

Documenting Referenced Assemblies

In addition to the `Assembly` token and the set of `TypeDef` and `TypeRef` blocks, .NET metadata also makes use of `AssemblyRef` #n tokens to document each external assembly. Given that the `CarLibrary.dll` makes use of the `System.Windows.Forms.MessageBox` class, you find an `AssemblyRef` for the `System.Windows.Forms` assembly, as shown in the following code:

```
AssemblyRef #2 (23000002)
```

```
-----  
Token: 0x23000002  
Public Key or Token: b7 7a 5c 56 19 34 e0 89  
Name: System.Windows.Forms  
Version: 4.0.0.0  
Major Version: 0x00000004  
Minor Version: 0x00000000  
Build Number: 0x00000000
```

```
Revision Number: 0x00000000
Locale: <null>
HashCode Blob:
Flags: [none] (00000000)
```

Documenting String Literals

The final point of interest regarding .NET metadata is the fact that each and every string literal in your code base is documented under the `User Strings` token.

User Strings

```
70000001 : (11) L"Jamming {0}"
70000019 : (13) L"Quiet time..."
70000035 : (23) L"CarLibrary Version 2.0!"
70000065 : (14) L"Ramming speed!"
70000083 : (19) L"Faster is better..."
700000ab : (16) L"Time to call AAA"
70000ocd : (16) L"Your car is dead"
```

Note As illustrated in this last metadata listing, always be aware that all strings are clearly documented in the assembly metadata. This could have huge security consequences if you were to use string literals to capture passwords, credit card numbers, or other sensitive information.

The next question on your mind may be (in the best-case scenario) “How can I leverage this information in my applications?” or (in the worst-case scenario) “Why should I care about metadata?” To address both points of view, allow me to introduce .NET reflection services. Be aware that the usefulness of the topics presented over the pages that follow may be a bit of a head-scratcher until this chapter’s endgame. So hang tight.

Note You will also find a number of `CustomAttribute` tokens displayed by the `MetaInfo` window, which documents the attributes applied within the code base. You’ll learn about the role of .NET attributes later in this chapter.

Understanding Reflection

In the .NET universe, *reflection* is the process of runtime type discovery. Using reflection services, you are able to programmatically obtain the same metadata information displayed by `ildasm.exe` using a friendly object model. For example, through reflection, you can obtain a list of all types contained within a given `*.dll` or `*.exe` assembly (or even within a `*.netmodule` file, if you have a multi-file assembly),

including the methods, fields, properties, and events defined by a given type. You can also dynamically discover the set of interfaces supported by a given type, the parameters of a method, and other related details (base classes, namespace information, manifest data, and so forth).

Like any namespace, `System.Reflection` (which is defined in `mscorlib.dll`) contains a number of related types. Table 15-1 lists some of the core items you should be familiar with.

Table 15-1. A Sampling of Members of the `System.Reflection` Namespace

Type	Meaning in Life
<code>Assembly</code>	This abstract class contains a number of static methods that allow you to load, investigate, and manipulate an assembly.
<code>AssemblyName</code>	This class allows you to discover numerous details behind an assembly's identity (version information, culture information, and so forth).
<code>EventInfo</code>	This abstract class holds information for a given event.
<code>FieldInfo</code>	This abstract class holds information for a given field.
<code>MethodInfo</code>	This is the abstract base class that defines common behaviors for the <code>EventInfo</code> , <code>FieldInfo</code> , <code>MethodInfo</code> , and <code> PropertyInfo</code> types.
<code>MethodInfo</code>	This abstract class contains information for a given method.
<code>Module</code>	This abstract class allows you to access a given module within a multi-file assembly.
<code>ParameterInfo</code>	This class holds information for a given parameter.
<code> PropertyInfo</code>	This abstract class holds information for a given property.

To understand how to leverage the `System.Reflection` namespace to programmatically read .NET metadata, you need to first come to terms with the `System.Type` class.

The `System.Type` Class

The `System.Type` class defines a number of members that can be used to examine a type's metadata, a great number of which return types from the `System.Reflection` namespace. For example, `Type.GetMethods()` returns an array of `MethodInfo` objects, `Type.GetFields()` returns an array of `FieldInfo` objects, and so on. The complete set of members exposed by `System.Type` is quite expansive; however, Table 15-2 offers a partial snapshot of the members supported by `System.Type` (see the .NET Framework 4.0 SDK documentation for full details).

Table 15-2. Select Members of System.Type

Type	Meaning in Life
IsAbstract	
IsArray	
IsClass	
IsCOMObject	
IsEnum	
IsGenericTypeDefinition	
IsGenericParameter	
IsInterface	
IsPrimitive	
IsNestedPrivate	
IsNestedPublic	
IsSealed	
IsValueType	
GetConstructors()	
GetEvents()	
GetFields()	
GetInterfaces()	
GetMembers()	
GetMethods()	
GetNestedTypes()	
GetProperties()	
FindMembers()	
GetType()	
InvokeMember()	
	These properties (among others) allow you to discover a number of basic traits about the Type you are referring to (e.g., if it is an abstract entity, an array, a nested class, and so forth).
	These methods (among others) allow you to obtain an array representing the items (interface, method, property, etc.) you are interested in. Each method returns a related array (e.g., GetFields() returns a FieldInfo array, GetMethods() returns a MethodInfo array, etc.). Be aware that each of these methods has a singular form (e.g.,GetMethod(),GetProperty(), etc.) that allows you to retrieve a specific item by name, rather than an array of all related items.
	This method returns a MemberInfo array based on search criteria.
	This static method returns a Type instance given a string name.
	This method allows “late binding” for a given item. You’ll learn about late binding later in this chapter.

Obtaining a Type Reference Using System.Object.GetType()

You can obtain an instance of the Type class in a variety of ways. However, the one thing you cannot do is directly create a Type object using the new keyword, as Type is an abstract class. Regarding your first choice, recall that System.Object defines a method named GetType(), which returns an instance of the Type class that represents the metadata for the current object:

```
// Obtain type information using a SportsCar instance.
SportsCar sc = new SportsCar();
Type t = sc.GetType();
```

Obviously, this approach will only work if you have compile-time knowledge of the type you wish to reflect over (SportsCar in this case) and currently have an instance of the type in memory. Given this restriction, it should make sense that tools such as ildasm.exe do not obtain type information by directly

calling `System.Object.GetType()` for each type, given the `ildasm.exe` was not compiled against your custom assemblies!

Obtaining a Type Reference Using `typeof()`

The next way to obtain type information is using the C# `typeof` operator:

```
// Get the Type using typeof.  
Type t = typeof(SportsCar);
```

Unlike `System.Object.GetType()`, the `typeof` operator is helpful in that you do not need to first create an object instance to extract type information. However, your code base must still have compile-time knowledge of the type you are interested in examining, as `typeof` expects the strongly typed name of the type.

Obtaining a Type Reference Using `System.Type.GetType()`

To obtain type information in a more flexible manner, you may call the static `GetType()` member of the `System.Type` class and specify the fully qualified string name of the type you are interested in examining. Using this approach, you do *not* need to have compile-time knowledge of the type you are extracting metadata from, given that `Type.GetType()` takes an instance of the omnipresent `System.String`.

Note When I say you do not need compile-time knowledge when calling `Type.GetType()`, I am referring to the fact that this method can take any string value whatsoever (rather than a strongly typed variable). Of course, you would still need to know the name of the type in a “stringified” format!

The `Type.GetType()` method has been overloaded to allow you to specify two Boolean parameters, one of which controls whether an exception should be thrown if the type cannot be found, and the other of which establishes the case sensitivity of the string. To illustrate, ponder the following:

```
// Obtain type information using the static Type.GetType() method  
// (don't throw an exception if SportsCar cannot be found and ignore case).  
Type t = Type.GetType("CarLibrary.SportsCar", false, true);
```

In the previous example, notice that the string you are passing into `Type.GetType()` makes no mention of the assembly containing the type. In this case, the assumption is that the type is defined within the currently executing assembly. However, when you wish to obtain metadata for a type within an external private assembly, the string parameter is formatted using the type’s fully qualified name, followed by a comma, followed by the friendly name of the assembly containing the type:

```
// Obtain type information for a type within an external assembly.  
Type t = Type.GetType("CarLibrary.SportsCar, Carlibrary");
```

As well, do know that the string passed into `Type.GetType()` may specify a plus token (+) to denote a *nested type*. Assume you wish to obtain type information for an enumeration (`SpyOptions`) nested within a class named `JamesBondCar`. To do so, you would write the following:

```
// Obtain type information for a nested enumeration
// within the current assembly.
Type t = Type.GetType("CarLibrary.JamesBondCar+SpyOptions");
```

Building a Custom Metadata Viewer

To illustrate the basic process of reflection (and the usefulness of `System.Type`), let's create a Console Application named `MyTypeViewer`. This program will display details of the methods, properties, fields, and supported interfaces (in addition to some other points of interest) for any type within `mscorlib.dll` (recall all .NET applications have automatic access to this core framework class library) or a type within `MyTypeViewer` itself. Once the application has been created, be sure to import the `System.Reflection` namespace.

```
// Need to import this namespace to do any reflection!
using System.Reflection;
```

Reflecting on Methods

The `Program` class will be updated to define a number of static methods, each of which takes a single `System.Type` parameter and returns `void`. First you have `ListMethods()`, which (as you might guess) prints the name of each method defined by the incoming type. Notice how `Type.GetMethods()` returns an array of `System.Reflection.MethodInfo` objects, which can be enumerated over using a standard `foreach` loop:

```
// Display method names of type.
static void ListMethods(Type t)
{
    Console.WriteLine("***** Methods *****");
    MethodInfo[] mi = t.GetMethods();
    foreach(MethodInfo m in mi)
        Console.WriteLine("->{0}", m.Name);
    Console.WriteLine();
```

Here, you are simply printing the name of the method using the `MethodInfo.Name` property. As you might guess, `MethodInfo` has many additional members that allow you to determine whether the method is static, virtual, generic, or abstract. As well, the `MethodInfo` type allows you to obtain the method's return value and parameter set. You'll spruce up the implementation of `ListMethods()` in just a bit.

If you wish, you could also build a fitting LINQ query to enumerate the names of each method. Recall from Chapter 13, LINQ to Objects allows you to build strongly typed queries which can be applied to in-memory object collections. As a good rule of thumb, whenever you find blocks of looping or decision programming logic, you could make use of a related LINQ query. For example, you could rewrite the previous method as so:

```
static void ListMethods(Type t)
{
    Console.WriteLine("***** Methods *****");
    var methodNames = from n in t.GetMethods() select n.Name;
    foreach (var name in methodNames)
        Console.WriteLine("->{0}", name);
```

```

        Console.WriteLine();
    }
}

```

Reflecting on Fields and Properties

The implementation of `ListFields()` is similar. The only notable difference is the call to `Type.GetFields()` and the resulting `FieldInfo` array. Again, to keep things simple, you are printing out only the name of each field using a LINQ query.

```

// Display field names of type.
static void ListFields(Type t)
{
    Console.WriteLine("***** Fields *****");
    var fieldNames = from f in t.GetFields() select f.Name;
    foreach (var name in fieldNames)
        Console.WriteLine("->{0}", name);
    Console.WriteLine();
}

```

The logic to display a type's properties is similar as well.

```

// Display property names of type.
static void ListProps(Type t)
{
    Console.WriteLine("***** Properties *****");
    var propNames = from p in t.GetProperties() select p.Name;
    foreach (var name in propNames)
        Console.WriteLine("->{0}", name);
    Console.WriteLine();
}

```

Reflecting on Implemented Interfaces

Next, you will author a method named `ListInterfaces()` that will print out the names of any interfaces supported on the incoming type. The only point of interest here is that the call to `GetInterfaces()` returns an array of `System.Type`s! This should make sense given that interfaces are, indeed, types:

```

// Display implemented interfaces.
static void ListInterfaces(Type t)
{
    Console.WriteLine("***** Interfaces *****");
    var ifaces = from i in t.GetInterfaces() select i;
    foreach(Type i in ifaces)
        Console.WriteLine("->{0}", i.Name);
}

```

■ **Note** Be aware that a majority of the “get” methods of System.Type (GetMethods(), GetInterfaces(), etc) have been overloaded to allow you to specify values from the BindingFlags enumeration. This provides a greater level of control on exactly what should be searched for (e.g., only static members, only public members, include private members, etc). Consult the .NET Framework 4.0 SDK documentation for details.

Displaying Various Odds and Ends

Last but not least, you have one final helper method that will simply display various statistics (indicating whether the type is generic, what the base class is, whether the type is sealed, and so forth) regarding the incoming type:

```
// Just for good measure.
static void ListVariousStats(Type t)
{
    Console.WriteLine("***** Various Statistics *****");
    Console.WriteLine("Base class is: {0}", t.BaseType);
    Console.WriteLine("Is type abstract? {0}", t.IsAbstract);
    Console.WriteLine("Is type sealed? {0}", t.IsSealed);
    Console.WriteLine("Is type generic? {0}", t.IsGenericTypeDefinition);
    Console.WriteLine("Is type a class type? {0}", t.IsClass);
    Console.WriteLine();}
```

Implementing Main()

The Main() method of the Program class prompts the user for the fully qualified name of a type. Once you obtain this string data, you pass it into the Type.GetType() method and send the extracted System.Type into each of your helper methods. This process repeats until the user enters Q to terminate the application:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Welcome to MyTypeViewer *****");
    string typeName = "";

    do
    {
        Console.WriteLine("\nEnter a type name to evaluate");
        Console.Write("or enter Q to quit: ");

        // Get name of type.
        typeName = Console.ReadLine();

        // Does user want to quit?
        if (typeName.ToUpper() == "Q")
        {
            break;
        }
    }
```

```

}

// Try to display type.
try
{
    Type t = Type.GetType(typeName);
    Console.WriteLine("");
    ListVariousStats(t);
    ListFields(t);
    ListProps(t);
    ListMethods(t);
    ListInterfaces(t);
}
catch
{
    Console.WriteLine("Sorry, can't find type");
}
} while (true);
}

```

At this point, `MyTypeViewer.exe` is ready to take out for a test drive. For example, run your application and enter the following fully qualified names (be aware that the manner in which you invoked `Type.GetType()` requires case-sensitive string names):

- `System.Int32`
- `System.Collections.ArrayList`
- `System.Threading.Thread`
- `System.Void`
- `System.IO.BinaryWriter`
- `System.Math`
- `System.Console`
- `MyTypeViewer.Program`

For example, here is some partial output when specifying `System.Math`.

```
***** Welcome to MyTypeViewer *****
```

```
Enter a type name to evaluate
or enter Q to quit: System.Math
```

```
***** Various Statistics *****
Base class is: System.Object
Is type abstract? True
Is type sealed? True
Is type generic? False
Is type a class type? True
```

```
***** Fields *****
->PI
->E

***** Properties *****

***** Methods *****
->Acos
->Asin
->Atan
->Atan2
->Ceiling
->Ceiling
->Cos
...

```

Reflecting on Generic Types

When you call `Type.GetType()` in order to obtain metadata descriptions of generic types, you must make use of a special syntax involving a “back tick” character (`) followed by a numerical value that represents the number of type parameters the type supports. For example, if you wish to print out the metadata description of `System.Collections.Generic.List<T>`, you would need to pass the following string into your application:

```
System.Collections.Generic.List`1
```

Here, you are using the numerical value of 1, given that `List<T>` has only one type parameter. However, if you wish to reflect over `Dictionary< TKey, TValue >`, you would supply the value 2:

```
System.Collections.Generic.Dictionary`2
```

Reflecting on Method Parameters and Return Values

So far, so good! Let’s make a minor enhancement to the current application. Specifically, you will update the `ListMethods()` helper function to list not only the name of a given method, but also the return type and incoming parameter types. The `MethodInfo` type provides the `ReturnType` property and `GetParameters()` method for these very tasks. In the following modified code, notice that you are building a string that contains the type and name of each parameter using a nested `foreach` loop (without the use of LINQ):

```
static void ListMethods(Type t)
{
    Console.WriteLine("***** Methods *****");
    MethodInfo[] mi = t.GetMethods();
    foreach (MethodInfo m in mi)
    {
        // Get return type.
        string retVal = m.ReturnType.FullName;
        string paramInfo = "(";
        foreach (ParameterInfo p in m.GetParameters())
        {
            paramInfo += p.ParameterType.FullName + ", ";
        }
        paramInfo = paramInfo.Substring(0, paramInfo.Length - 2);
        Console.WriteLine(paramInfo + " " + retVal);
    }
}
```

```

// Get params.
foreach (ParameterInfo pi in m.GetParameters())
{
    pInfo += string.Format("{0} {1} ", pi.ParameterType, pi.Name);
}
pInfo += " )";

// Now display the basic method sig.
Console.WriteLine("->{0} {1} {2}", retVal, m.Name, pInfo);
}
Console.WriteLine();
}

```

If you now run this updated application, you will find that the methods of a given type are much more detailed. If you enter your good friend, `System.Object` as input to the program, the following methods will display:

```

***** Methods *****
->System.String ToString ( )
->System.Boolean Equals ( System.Object obj )
->System.Boolean Equals ( System.Object objA System.Object objB )
->System.Boolean ReferenceEquals ( System.Object objA System.Object objB )
->System.Int32 GetHashCode ( )
->System.Type GetType ( )

```

The current implementation of `ListMethods()` is helpful, in that you can directly investigate each parameter and method return type using the `System.Reflection` object model. As an extreme shortcut, be aware that each of the `XXXInfo` types (`MethodInfo`, `PropertyInfo`, `EventInfo`, etc.) have overridden `ToString()` to display the signature of the item requested. Thus, you could also implement `ListMethods()` as follows (once again using LINQ, where you simply select all `MethodInfo` objects, rather than only the `Name` values):

```

static void ListMethods(Type t)
{
    Console.WriteLine("***** Methods *****");
    var methodNames = from n in t.GetMethods() select n;
    foreach (var name in methodNames)
        Console.WriteLine("->{0}", name);
    Console.WriteLine();
}

```

Interesting stuff, huh? Clearly the `System.Reflection` namespace and `System.Type` class allow you to reflect over many other aspects of a type beyond what `MyTypeViewer` is currently displaying. As you would hope, you can obtain a type's events, get the list of any generic parameters for a given member, and glean dozens of other details.

Nevertheless, at this point you have created a (somewhat capable) object browser. The major limitation, of course, is that you have no way to reflect beyond the current assembly (`MyTypeViewer`) or the always accessible `mscorlib.dll`. This begs the question, “How can I build applications that can load (and reflect over) assemblies not referenced at compile time?” Glad you asked.

■ **Source Code** The MyTypeViewer project can be found under the Chapter 15 subdirectory.

Dynamically Loading Assemblies

In the previous chapter, you learned all about how the CLR consults the assembly manifest when probing for an externally referenced assembly. However, there will be many times when you need to load assemblies on the fly programmatically, even if there is no record of said assembly in the manifest. Formally speaking, the act of loading external assemblies on demand is known as a *dynamic load*.

`System.Reflection` defines a class named `Assembly`. Using this class, you are able to dynamically load an assembly as well as discover properties about the assembly itself. Using the `Assembly` type, you are able to dynamically load private or shared assemblies, as well as load an assembly located at an arbitrary location. In essence, the `Assembly` class provides methods (`Load()` and `LoadFrom()` in particular) that allow you to programmatically supply the same sort of information found in a client-side *.config file.

To illustrate dynamic loading, create a brand-new Console Application named `ExternalAssemblyReflector`. Your task is to construct a `Main()` method that prompts for the friendly name of an assembly to load dynamically. You will pass the `Assembly` reference into a helper method named `DisplayTypes()`, which will simply print the names of each class, interface, structure, enumeration, and delegate it contains. The code is refreshingly simple:

```
using System;
using System.Collections.Generic;
using System.Linq;
using System.Text;

using System.Reflection;
using System.IO; // For FileNotFoundException definition.

namespace ExternalAssemblyReflector
{
    class Program
    {
        static void DisplayTypesInAsm(Assembly asm)
        {
            Console.WriteLine("\n***** Types in Assembly *****");
            Console.WriteLine("->{0}", asm.FullName);
            Type[] types = asm.GetTypes();
            foreach (Type t in types)
                Console.WriteLine("Type: {0}", t);
            Console.WriteLine("");
        }

        static void Main(string[] args)
        {
            Console.WriteLine("***** External Assembly Viewer *****");
            string asmName = "";

```

```
Assembly asm = null;

do
{
    Console.WriteLine("\nEnter an assembly to evaluate");
    Console.Write("or enter Q to quit: ");

    // Get name of assembly.
    asmName = Console.ReadLine();

    // Does user want to quit?
    if (asmName.ToUpper() == "Q")
    {
        break;
    }

    // Try to load assembly.
    try
    {
        asm = Assembly.Load(asmName);
        DisplayTypesInAsm(asm);
    }
    catch
    {
        Console.WriteLine("Sorry, can't find assembly.");
    }
} while (true);
}
```

Notice that the static `Assembly.Load()` method has been passed only the friendly name of the assembly you are interested in loading into memory. Thus, if you wish to reflect over `CarLibrary.dll`, you will need to copy the `CarLibrary.dll` binary to the `\bin\Debug` directory of the `ExternalAssemblyReflector` application to run this program. Once you do, you will find output similar to the following:

***** External Assembly Viewer *****

Enter an assembly to evaluate
or enter 0 to quit: CarLibrary

***** Types in Assembly *****

->CarLibrary, Version=2.0.0.0, Culture=neutral, PublicKeyToken=33a2bc294331e8b9

Type: CarLibrary.MusicMedia

Type: CarLibrary.EngineState

Type: CarLibrary.Car

Type: CarLibrary.SportsCar

Type: CarLibrary.MiniVan

If you wish to make `ExternalAssemblyReflector` more flexible, you can update your code to load the external assembly using `Assembly.LoadFrom()` rather than `Assembly.Load()`:

```
try
{
    asm = Assembly.LoadFrom(asmName);
    DisplayTypesInAsm(asn);
}
```

By doing so, you can enter an absolute path to the assembly you wish to view (e.g., `C:\MyApp\MyAsm.dll`). Essentially, `Assembly.LoadFrom()` allows you to programmatically supply a `<codeBase>` value. With this adjustment, you can now pass in a full path to your console application. Thus, if `CarLibrary.dll` was located under `C:\MyCode`, you could enter the following:

```
***** External Assembly Viewer *****
```

Enter an assembly to evaluate
or enter Q to quit: `C:\MyCode\CarLibrary.dll`

```
***** Types in Assembly *****
->CarLibrary, Version=2.0.0.0, Culture=neutral, PublicKeyToken=33a2bc294331e8b9
Type: CarLibrary.EngineState
Type: CarLibrary.Car
Type: CarLibrary.SportsCar
Type: CarLibrary.MiniVan
```

■ Source Code The `ExternalAssemblyReflector` project is included in the Chapter 15 subdirectory.

Reflecting on Shared Assemblies

The `Assembly.Load()` method has been overloaded a number of times. One variation allows you to specify a culture value (for localized assemblies) as well as a version number and public key token value (for shared assemblies). Collectively speaking, the set of items identifying an assembly is termed the *display name*. The format of a display name is a comma-delimited string of name/value pairs that begins with the friendly name of the assembly, followed by optional qualifiers (that may appear in any order). Here is the template to follow (optional items appear in parentheses):

```
Name (,Version = major.minor.build.revision) (,Culture = culture token)
(,PublicKeyToken= public key token)
```

When you're crafting a display name, the convention `PublicKeyToken=null` indicates that binding and matching against a non-strongly named assembly is required. Additionally, `Culture=""` indicates matching against the default culture of the target machine, for example:

```
// Load version 1.0.0.0 of CarLibrary using the default culture.
Assembly a =
```

```
Assembly.Load(@"CarLibrary, Version=1.0.0.0, PublicKeyToken=null, Culture=""");
```

Also be aware that the `System.Reflection` namespace supplies the `AssemblyName` type, which allows you to represent the preceding string information in a handy object variable. Typically, this class is used in conjunction with `System.Version`, which is an OO wrapper around an assembly's version number. Once you have established the display name, it can then be passed into the overloaded `Assembly.Load()` method:

```
// Make use of AssemblyName to define the display name.
AssemblyName asmName;
asmName = new AssemblyName();
asmName.Name = "CarLibrary";
Version v = new Version("1.0.0.0");
asmName.Version = v;
Assembly a = Assembly.Load(asmName);
```

To load a shared assembly from the GAC, the `Assembly.Load()` parameter must specify a `PublicKeyToken` value. For example, assume you have a new Console Application named `SharedAsmReflector`, and wish to load version 4.0.0.0 of the `System.Windows.Forms.dll` assembly provided by the .NET base class libraries. Given that the number of types in this assembly is quite large, the following application only prints out the names of public enums, using a simple LINQ query:

```
using System;
using System.Collections.Generic;
using System.Linq;
using System.Text;

using System.Reflection;
using System.IO;

namespace SharedAsmReflector
{
    public class SharedAsmReflector
    {
        private static void DisplayInfo(Assembly a)
        {
            Console.WriteLine("***** Info about Assembly *****");
            Console.WriteLine("Loaded from GAC? {0}", a.GlobalAssemblyCache);
            Console.WriteLine("Asm Name: {0}", a.GetName().Name);
            Console.WriteLine("Asm Version: {0}", a.GetName().Version);
            Console.WriteLine("Asm Culture: {0}",
                a.GetName().CultureInfo.DisplayName);
            Console.WriteLine("\nHere are the public enums:");

            // Use a LINQ query to find the public enums.
            Type[] types = a.GetTypes();
            var publicEnums = from pe in types where pe.IsEnum &&
                pe.IsPublic select pe;

            foreach (var pe in publicEnums)
            {
                Console.WriteLine(pe);
            }
        }
    }
}
```

```

    }

    static void Main(string[] args)
    {
        Console.WriteLine("***** The Shared Asm Reflector App *****\n");

        // Load System.Windows.Forms.dll from GAC.
        string displayName = null;
        displayName = "System.Windows.Forms," +
            "Version=4.0.0.0," +
            "PublicKeyToken=b77a5c561934e089," +
            @"Culture=""";
        Assembly asm = Assembly.Load(displayName);
        DisplayInfo(asm);
        Console.WriteLine("Done!");
        Console.ReadLine();
    }
}

```

■ **Source Code** The SharedAsmReflector project is included in the Chapter 15 subdirectory.

At this point, you should understand how to use some of the core members of the `System.Reflection` namespace to discover metadata at runtime. Of course, I realize despite the “cool factor,” you likely will not need to build custom object browsers at your place of employment too often. Do recall, however, that reflection services are the foundation for a number of very common programming activities, including *late binding*.

Understanding Late Binding

Simply put, *late binding* is a technique in which you are able to create an instance of a given type and invoke its members at runtime without having hard-coded compile-time knowledge of its existence. When you are building an application that binds late to a type in an external assembly, you have no reason to set a reference to the assembly; therefore, the caller’s manifest has no direct listing of the assembly.

At first glance, it is not easy to see the value of late binding. It is true that if you can “bind early” to an object (e.g., set an assembly reference and allocate the type using the C# `new` keyword), you should opt to do so. For one reason, early binding allows you to determine errors at compile time, rather than at runtime. Nevertheless, late binding does have a critical role in any extendable application you may be building. You will have a chance to build such an “extendable” program at the end of this chapter in the section “Building an Extendable Application”; until then, let’s examine the role of the `Activator` class.

The System.Activator Class

The `System.Activator` class (defined in `mscorlib.dll`) is the key to the .NET late binding process. For the current example, you are only interested in the `Activator.CreateInstance()` method, which is used to create an instance of a type à la late binding. This method has been overloaded numerous times to provide a good deal of flexibility. The simplest variation of the `CreateInstance()` member takes a valid `Type` object that describes the entity you wish to allocate into memory on the fly.

Create a new Console Application named `LateBindingApp`, and import the `System.IO` and `System.Reflection` namespace via the C# `using` keyword. Now, update the `Program` class as follows:

```
// This program will load an external library,
// and create an object using late binding.
public class Program
{
    static void Main(string[] args)
    {
        Console.WriteLine("***** Fun with Late Binding *****");
        // Try to load a local copy of CarLibrary.
        Assembly a = null;
        try
        {
            a = Assembly.Load("CarLibrary");
        }
        catch(FileNotFoundException ex)
        {
            Console.WriteLine(ex.Message);
            return;
        }
        if(a != null)
            CreateUsingLateBinding(a);

        Console.ReadLine();
    }

    static void CreateUsingLateBinding(Assembly asm)
    {
        try
        {
            // Get metadata for the Minivan type.
            Type miniVan = asm.GetType("CarLibrary.MiniVan");

            // Create the Minivan on the fly.
            object obj = Activator.CreateInstance(miniVan);
            Console.WriteLine("Created a {0} using late binding!", obj);
        }
        catch(Exception ex)
        {
            Console.WriteLine(ex.Message);
        }
    }
}
```

Now, before you run this application, you will need to manually place a copy of `CarLibrary.dll` into the `bin\Debug` folder of this new application using Windows Explorer. The reason is that you are calling `Assembly.Load()`, therefore the CLR will only probe in the client folder (if you wish, you could enter a path to the assembly using `Assembly.LoadFrom()`, however there is no need to do so).

Note Don't set a reference to `CarLibrary.dll` using Visual Studio for this example! That will record this library in the client's manifest. The whole point of late binding is that you are trying to create an object which is not known at compile time.

Notice that the `Activator.CreateInstance()` method returns a `System.Object` rather than a strongly typed `MiniVan`. Therefore, if you apply the dot operator on the `obj` variable, you will fail to see any members of the `MiniVan` class. At first glance, you may assume you can remedy this problem with an explicit cast:

```
// Cast to get access to the members of MiniVan?  
// Nope! Compiler error!  
object obj = (MiniVan)Activator.CreateInstance(minivan);
```

However, because your program has not set a reference to `CarLibrary.dll`, you cannot make use of the `C# using` keyword to import the `CarLibrary` namespace, and therefore you can't use a `MiniVan` during the casting operation! Remember that the whole point of late binding is to create instances of objects for which there is no compile-time knowledge. Given this, how can you invoke the underlying methods of the `MiniVan` object stored in the `System.Object` reference? The answer, of course, is by using reflection.

Invoking Methods with No Parameters

Assume you wish to invoke the `TurboBoost()` method of the `MiniVan`. As you recall, this method will set the state of the engine to "dead" and display an informational message box. The first step is to obtain a `MethodInfo` object for the `TurboBoost()` method using `Type.GetMethod()`. From the resulting `MethodInfo`, you are then able to call `MiniVan.TurboBoost` using `Invoke()`. `MethodInfo.Invoke()` requires you to send in all parameters that are to be given to the method represented by `MethodInfo`. These parameters are represented by an array of `System.Object` types (as the parameters for a given method could be any number of various entities).

Given that `TurboBoost()` does not require any parameters, you can simply pass `null` (meaning "this method has no parameters"). Update your `CreateUsingLateBinding()` method as follows:

```
static void CreateUsingLateBinding(Assembly asm)  
{  
    try  
    {  
        // Get metadata for the Minivan type.  
        Type miniVan = asm.GetType("CarLibrary.MiniVan");  
  
        // Create the Minivan on the fly.  
        object obj = Activator.CreateInstance(miniVan);  
        Console.WriteLine("Created a {0} using late binding!", obj);  
    }  
}
```

```

// Get info for TurboBoost.
MethodInfo mi = miniVan.GetMethod("TurboBoost");

// Invoke method ('null' for no parameters).
mi.Invoke(obj, null);
}
catch(Exception ex)
{
    Console.WriteLine(ex.Message);
}
}

```

At this point, you will see the message box shown in Figure 15-2, once the TurboBoost() method is invoked.




Figure 15-2. Late-bound method invocation

Invoking Methods with Parameters

When you wish to use late binding to invoke a method requiring parameters, you will package up the arguments as a loosely typed array of objects. Recall that version 2.0.0.0 of `CarLibrary.dll` defined the following method in the `Car` class:

```

public void TurnOnRadio(bool musicOn, MusicMedia mm)
{
    if (musicOn)
        MessageBox.Show(string.Format("Jamming {0}", mm));
    else
        MessageBox.Show("Quiet time...");
}

```

This method takes two parameters: a Boolean representing if the automobile's music system should be turned on or off, and an enum which represents the type of music player. Recall this enum was structured as so:

```

public enum MusicMedia
{
    musicCd,      // 0
    musicTape,    // 1
    musicRadio,   // 2
    musicMp3      // 3
}

```

Here is a new method of the `Program` class, which invokes `TurnOnRadio()`. Notice that you are using the underlying numerical values of the `MusicMedia` enumeration, to specify a “radio” media player.

```
static void InvokeMethodWithArgsUsingLateBinding(Assembly asm)
{
    try
    {
        // First, get a metadata description of the sports car.
        Type sport = asm.GetType("CarLibrary.SportsCar");

        // Now, create the sports car.
        object obj = Activator.CreateInstance(sport);

        // Invoke TurnOnRadio() with arguments.
        MethodInfo mi = sport.GetMethod("TurnOnRadio");
        mi.Invoke(obj, new object[] { true, 2 });
    }
    catch (Exception ex)
    {
        Console.WriteLine(ex.Message);
    }
}
```

Hopefully, at this point, you can see the relationships among reflection, dynamic loading, and late binding. To be sure, the reflection API provides many additional features beyond what has been covered here, but you should be in good shape to dig into more details if you are interested.

Again, you still may wonder exactly *when* you might make use of these techniques in your own applications. The conclusion of this chapter should shed light on this question; however, the next topic under investigation is the role of .NET attributes.

■ Source Code The `LateBindingApp` project is included in the Chapter 15 subdirectory.

Understanding the Role of .NET Attributes

As illustrated at beginning of this chapter, one role of a .NET compiler is to generate metadata descriptions for all defined and referenced types. In addition to this standard metadata contained within any assembly, the .NET platform provides a way for programmers to embed additional metadata into an assembly using *attributes*. In a nutshell, attributes are nothing more than code annotations that can be applied to a given type (class, interface, structure, etc.), member (property, method, etc.), assembly, or module.

The idea of annotating code using attributes is not new. COM IDL provided numerous predefined attributes that allowed developers to describe the types contained within a given COM server. However, COM attributes were little more than a set of keywords. If a COM developer needed to create a custom attribute, he or she could do so, but it was referenced in code by a 128-bit number (GUID), which was cumbersome at best.

.NET attributes are class types that extend the abstract `System.Attribute` base class. As you explore the .NET namespaces, you will find many predefined attributes that you are able to make use of in your

applications. Furthermore, you are free to build custom attributes to further qualify the behavior of your types by creating a new type deriving from `Attribute`.

The .NET base class library provides a number of attributes in various namespaces. Table 15-3 gives a snapshot of some—but by *absolutely* no means all—predefined attributes.

Table 15-3. A Tiny Sampling of Predefined Attributes

Attribute	Meaning in Life
<code>[CLSCompliant]</code>	Enforces the annotated item to conform to the rules of the Common Language Specification (CLS). Recall that CLS-compliant types are guaranteed to be used seamlessly across all .NET programming languages.
<code>[DllImport]</code>	Allows .NET code to make calls to any unmanaged C- or C++-based code library, including the API of the underlying operating system. Do note that <code>[DllImport]</code> is not used when communicating with COM-based software.
<code>[Obsolete]</code>	Marks a deprecated type or member. If other programmers attempt to use such an item, they will receive a compiler warning describing the error of their ways.
<code>[Serializable]</code>	Marks a class or structure as being “serializable,” meaning it is able to persist its current state into a stream.
<code>[NonSerialized]</code>	Specifies that a given field in a class or structure should not be persisted during the serialization process.
<code>[WebMethod]</code>	Marks a method as being invokable via HTTP requests and instructs the CLR to serialize the method return value as XML.

Understand that when you apply attributes in your code, the embedded metadata is essentially useless until another piece of software explicitly reflects over the information. If this is not the case, the blurb of metadata embedded within the assembly is ignored and completely harmless.

Attribute Consumers

As you would guess, the .NET 4.0 Framework SDK ships with numerous utilities that are indeed on the lookout for various attributes. The C# compiler (`csc.exe`) itself has been preprogrammed to discover the presence of various attributes during the compilation cycle. For example, if the C# compiler encounters the `[CLSCompliant]` attribute, it will automatically check the attributed item to ensure it is exposing only CLS-compliant constructs. By way of another example, if the C# compiler discovers an item attributed with the `[Obsolete]` attribute, it will display a compiler warning in the Visual Studio 2010 Error List window.

In addition to development tools, numerous methods in the .NET base class libraries are preprogrammed to reflect over specific attributes. For example, if you wish to persist the state of an object to file, all you are required to do is annotate your class or structure with the `[Serializable]`

attribute. If the `Serialize()` method of the `BinaryFormatter` class encounters this attribute, the object is automatically persisted to file in a compact binary format.

The .NET CLR is also on the prowl for the presence of certain attributes. One famous .NET attribute is `[WebMethod]`, used to build XML web services using ASP.NET. If you wish to expose a method via HTTP requests and automatically encode the method return value as XML, simply apply `[WebMethod]` to the method and the CLR handles the details. Beyond web service development, attributes are critical to the operation of the .NET security system, Windows Communication Foundation, and COM/.NET interoperability (and so on).

Finally, you are free to build applications that are programmed to reflect over your own custom attributes as well as any attribute in the .NET base class libraries. By doing so, you are essentially able to create a set of “keywords” that are understood by a specific set of assemblies.

Applying Attributes in C#

To illustrate the process of applying attributes in C#, create a new Console Application named `ApplyingAttributes`. Assume you wish to build a class named `Motorcycle` that can be persisted in a binary format. To do so, simply apply the `[Serializable]` attribute to the class definition. If you have a field that should not be persisted, you may apply the `[NonSerialized]` attribute:

```
// This class can be saved to disk.
[Serializable]
public class Motorcycle
{
    // However this field will not be persisted.
    [NonSerialized]
    float weightOfCurrentPassengers;

    // These fields are still serializable.
    bool hasRadioSystem;
    bool hasHeadSet;
    bool hasSissyBar;
}
```

Note An attribute applies to the “very next” item. For example, the only nonserialized field of the `Motorcycle` class is `weightOfCurrentPassengers`. The remaining fields are serializable given that the entire class has been annotated with `[Serializable]`.

At this point, don’t concern yourself with the actual process of object serialization (Chapter 20 examines the details). Just notice that when you wish to apply an attribute, the name of the attribute is sandwiched between square brackets.

Once this class has been compiled, you can view the extra metadata using `ildasm.exe`. Notice that these attributes are recorded using the `serializable` token (see the red triangle immediately inside the `Motorcycle` class) and the `notserialized` token (on the `weightOfCurrentPassengers` field; see Figure 15-3).




Figure 15-3. Attributes shown in ildasm.exe

As you might guess, a single item can be attributed with multiple attributes. Assume you have a legacy C# class type (*HorseAndBuggy*) that was marked as serializable, but is now considered obsolete for current development. Rather than deleting the class definition from your code base (and risk breaking existing software), you can mark the class with the `[Obsolete]` attribute. To apply multiple attributes to a single item, simply use a comma-delimited list:

```
[Serializable, Obsolete("Use another vehicle!")]
public class HorseAndBuggy
{
    // ...
}
```

As an alternative, you can also apply multiple attributes on a single item by stacking each attribute as follows (the end result is identical):

```
[Serializable]
[Obsolete("Use another vehicle!")]
public class HorseAndBuggy
{
    // ...
}
```

C# Attribute Shorthand Notation

If you were consulting the .NET Framework 4.0 SDK documentation, you may have noticed that the actual class name of the `[Obsolete]` attribute is `ObsoleteAttribute`, not `Obsolete`. As a naming convention, all .NET attributes (including custom attributes you may create yourself) are suffixed with the `Attribute` token. However, to simplify the process of applying attributes, the C# language does not require you to type in the `Attribute` suffix. Given this, the following iteration of the *HorseAndBuggy* type is identical to the previous (it just involves a few more keystrokes):

```
[SerializableAttribute]
```

```
[ObsoleteAttribute("Use another vehicle!")]
public class HorseAndBuggy
{
    // ...
}
```

Be aware that this is a courtesy provided by C#. Not all .NET-enabled languages support this shorthand attribute syntax.

Specifying Constructor Parameters for Attributes

Notice that the [Obsolete] attribute is able to accept what appears to be a constructor parameter. If you view the formal definition of the [Obsolete] attribute using the Code Definition window (which can be opened using the View menu of Visual Studio 2010), you will find that this class indeed provides a constructor receiving a System.String:

```
public sealed class ObsoleteAttribute : Attribute
{
    public ObsoleteAttribute(string message, bool error);
    public ObsoleteAttribute(string message);
    public ObsoleteAttribute();
    public bool IsError { get; }
    public string Message { get; }
}
```

Understand that when you supply constructor parameters to an attribute, the attribute is *not* allocated into memory until the parameters are reflected upon by another type or an external tool. The string data defined at the attribute level is simply stored within the assembly as a blurb of metadata.

The Obsolete Attribute in Action

Now that HorseAndBuggy has been marked as obsolete, if you were to allocate an instance of this type:

```
static void Main(string[] args)
{
    HorseAndBuggy mule = new HorseAndBuggy();
}
```

you would find that the supplied string data is extracted and displayed within the Error List window of Visual Studio 2010, as well as one the offending line of code when you hover your mouse cursor above the obsolete type (see Figure 15-4).



Figure 15-4. Attributes in action

In this case, the “other piece of software” that is reflecting on the [Obsolete] attribute is the C# compiler. Hopefully, at this point, you should understand the following key points regarding .NET attributes:

- Attributes are classes that derive from `System.Attribute`.
- Attributes result in embedded metadata.
- Attributes are basically useless until another agent reflects upon them.
- Attributes are applied in C# using square brackets.

Next up, let’s examine how you can build your own custom attributes and a piece of custom software that reflects over the embedded metadata.

■ **Source Code** The ApplyingAttributes project is included in the Chapter 15 subdirectory.

Building Custom Attributes

The first step in building a custom attribute is to create a new class deriving from `System.Attribute`. Keeping in step with the automobile theme used throughout this book, assume you have created a brand new C# Class Library project named `AttributedCarLibrary`. This assembly will define a handful of vehicles, each of which is described using a custom attribute named `VehicleDescriptionAttribute`:

```
// A custom attribute.
public sealed class VehicleDescriptionAttribute : System.Attribute
{
    public string Description { get; set; }

    public VehicleDescriptionAttribute(string vehicalDescription)
    {
        Description = vehicalDescription;
    }
}
```

```

    }
    public VehicleDescriptionAttribute(){ }
}

```

As you can see, `VehicleDescriptionAttribute` maintains a piece of string data manipulated using an automatic property (`Description`). Beyond the fact that this class derived from `System.Attribute`, there is nothing unique to this class definition.

Note For security reasons, it is considered a .NET best practice to design all custom attributes as sealed. In fact, Visual Studio 2010 provides a code snippet named `Attribute` that will dump out a new `System.Attribute`-derived class into your code window. See Chapter 2 for an explication of using code snippets.

Applying Custom Attributes

Given that `VehicleDescriptionAttribute` is derived from `System.Attribute`, you are now able to annotate your vehicles as you see fit. For testing purposes, add the following class definitions to your new class library:

```

// Assign description using a "named property."
[Serializable]
[VehicleDescription("My rocking Harley")]
public class Motorcycle
{
}

[SerializableAttribute]
[ObsoleteAttribute("Use another vehicle!")]
[VehicleDescription("The old gray mare, she ain't what she used to be...")]
public class HorseAndBuggy
{
}

[VehicleDescription("A very long, slow, but feature-rich auto")]
public class Winnebago
{
}

```

Named Property Syntax

Notice that the description of the `Motorcycle` is assigned a description using a new bit of attribute-centric syntax termed a *named property*. In the constructor of the first `[VehicleDescription]` attribute, you set the underlying string data by using the `Description` property. If this attribute is reflected upon by an external agent, the value is fed into the `Description` property (named property syntax is legal only if the attribute supplies a writable .NET property).

In contrast, the HorseAndBuggy and Winnebago types are not making use of named property syntax and are simply passing the string data via the custom constructor. In any case, once you compile the AttributedCarLibrary assembly, you can make use of ildasm.exe to view the injected metadata descriptions for your type. For example, Figure 15-5 shows an embedded description of the Winnebago class, specifically the data within the beforefieldinit item in ildasm.exe.




Figure 15-5. Embedded vehicle description data

Restricting Attribute Usage

By default, custom attributes can be applied to just about any aspect of your code (methods, classes, properties, and so on). Thus, if it made sense to do so, you could use `VehicleDescription` to qualify methods, properties, or fields (among other things):

```

[VehicleDescription("A very long, slow, but feature-rich auto")]
public class Winnebago
{
    [VehicleDescription("My rocking CD player")]
    public void PlayMusic(bool On)
    {
        ...
    }
}

```

In some cases, this is exactly the behavior you require. Other times, however, you may want to build a custom attribute that can be applied only to select code elements. If you wish to constrain the scope of a custom attribute, you will need to apply the `[AttributeUsage]` attribute on the definition of your custom attribute. The `[AttributeUsage]` attribute allows you to supply any -combination of values (via an OR operation) from the `AttributeTargets` enumeration:

```

// This enumeration defines the possible targets of an attribute.
public enum AttributeTargets
{
    All, Assembly, Class, Constructor,
    Delegate, Enum, Event, Field, GenericParameter,
    Interface, Method, Module, Parameter,
    Property, ReturnValue, Struct
}

```

Furthermore, [AttributeUsage] also allows you to optionally set a named property (`AllowMultiple`) that specifies whether the attribute can be applied more than once on the same item (the default is `false`). As well, [AttributeUsage] allows you to establish whether the attribute should be inherited by derived classes using the `Inherited` named property (the default is `true`).

To establish that the `[VehicleDescription]` attribute can be applied only once on a class or structure, you can update the `VehicleDescriptionAttribute` definition as follows:

```
// This time, we are using the AttributeUsage attribute
// to annotate our custom attribute.
[AttributeUsage(AttributeTargets.Class | AttributeTargets.Struct,
    Inherited = false)]
public sealed class VehicleDescriptionAttribute : System.Attribute
{
    ...
}
```

With this, if a developer attempted to apply the `[VehicleDescription]` attribute on anything other than a class or structure, he or she is issued a compile-time error.

Assembly-Level (and Module-Level) Attributes

It is also possible to apply attributes on all types within a given module (for a multi-file assembly; see Chapter 14) or all modules within a given assembly using the `[module:]` and `[assembly:]` tags, respectively. For example, assume you wish to ensure that every public member of every public type defined within your assembly is CLS compliant.

Note Chapter 1 mentioned the role of CLS compliant assemblies. Recall that a CLS compliant assembly can be used by all .NET programming languages out-of-the-box. If you create public members of public types which expose non-CLS compliant programming constructs (such as unsigned data or pointer parameters), other .NET languages may not be able to use your functionality. Therefore, if you are building C# code libraries which need to be used by a wide variety of .NET languages, checking for CLS compliance is a must.

To do so, simply add the following assembly level attribute at the very top of any C# source code file. Be very aware that all assembly or module-level attributes must be listed outside the scope of any namespace scope! If you add assembly (or module) level attributes to your project, here is a recommended file-layout to follow:

```
// List 'using' statements first.
using System;
using System.Collections.Generic;
using System.Linq;
using System.Text;

// Now list any assembly/module level attributes.
// Enforce CLS compliance for all public types in this assembly.
```

```
[assembly: CLSCompliant(true)]  
  
// Now, your namespace(s) and types.  
namespace AttributedCarLibrary  
{  
    // Types...  
}
```

If you now add a bit of code that falls outside the CLS specification (such as an exposed point of unsigned data):

```
// Ulong types don't jibe with the CLS.  
public class Winnebago  
{  
    public ulong notCompliant;  
}
```

you are issued a compiler warning.

The Visual Studio 2010 AssemblyInfo.cs File

By default, Visual Studio 2010 projects receive a file named `AssemblyInfo.cs`, which can be viewed by expanding the Properties icon of the Solution Explorer (see Figure 15-6).




Figure 15-6. The `AssemblyInfo.cs` file

This file is a handy place to put attributes that are to be applied at the assembly level. You may recall from Chapter 14, during the examination of .NET assemblies, that the manifest contains assembly-level metadata, much of which comes from the assembly-level attributes shown in Table 15-4.

Table 15-4. Select Assembly-Level Attributes

Attribute	Meaning in Life
<code>[AssemblyCompany]</code>	Holds basic company information
<code>[AssemblyCopyright]</code>	Holds any copyright information for the product or assembly

Table 15-4. Select Assembly-Level Attributes (continued)

Attribute	Meaning in Life
[AssemblyCulture]	Provides information on what cultures or languages the assembly supports
[AssemblyDescription]	Holds a friendly description of the product or modules that make up the assembly
[AssemblyKeyFile]	Specifies the name of the file containing the key pair used to sign the assembly (i.e., establish a strong name)
[AssemblyProduct]	Provides product information
[AssemblyTrademark]	Provides trademark information
[AssemblyVersion]	Specifies the assembly's version information, in the format <major.minor.build.revision>

■ **Source Code** The AttributedCarLibrary project is included in the Chapter 15 subdirectory.

Reflecting on Attributes Using Early Binding

Remember that attributes are quite useless until another piece of software reflects over its values. Once a given attribute has been discovered, that piece of software can take whatever course of action necessary. Now, like any application, this “other piece of software” could discover the presence of a custom attribute using either early binding or late binding. If you wish to make use of early binding, you’ll require the client application to have a compile-time -definition of the attribute in question (VehicleDescriptionAttribute in this case). Given that the AttributedCarLibrary assembly has defined this custom attribute as a public class, early binding is the best option.

To illustrate the process of reflecting on custom attributes, create a new C# Console Application named VehicleDescriptionAttributeReader. Next, set a reference to the AttributedCarLibrary assembly. Finally, update your initial *.cs file with the following code:

```
// Reflecting on attributes using early binding.
using System;
using System.Collections.Generic;
using System.Linq;
using System.Text;

using AttributedCarLibrary;

namespace VehicleDescriptionAttributeReader
```

```

{
    class Program
    {
        static void Main(string[] args)
        {
            Console.WriteLine("***** Value of VehicleDescriptionAttribute *****\n");
            ReflectOnAttributesUsingEarlyBinding();
            Console.ReadLine();
        }

        private static void ReflectOnAttributesUsingEarlyBinding()
        {
            // Get a Type representing the Winnebago.
            Type t = typeof(Winnebago);

            // Get all attributes on the Winnebago.
            object[] customAtts = t.GetCustomAttributes(false);

            // Print the description.
            foreach (VehicleDescriptionAttribute v in customAtts)
                Console.WriteLine("-> {0}\n", v.Description);
        }
    }
}

```

The `Type.GetCustomAttributes()` method returns an object array that represents all the attributes applied to the member represented by the `Type` (the Boolean parameter controls whether the search should extend up the inheritance chain). Once you have obtained the list of attributes, iterate over each `VehicleDescriptionAttribute` class and print out the value obtained by the `Description` property.

■ Source Code The `VehicleDescriptionAttributeReader` project is included under the Chapter 15 subdirectory.

Reflecting on Attributes Using Late Binding

The previous example made use of early binding to print out the vehicle description data for the `Winnebago` type. This was possible due to the fact that the `VehicleDescriptionAttribute` class type was defined as a public member in the `AttributedCarLibrary` assembly. It is also possible to make use of dynamic loading and late binding to reflect over attributes.

Create a new project called `VehicleDescriptionAttributeReaderLateBinding` and copy `AttributedCarLibrary.dll` to the project's `\bin\Debug` directory. Now, update your `Program` class as follows:

```

using System;
using System.Collections.Generic;
using System.Linq;
using System.Text;

```

```

using System.Reflection;

namespace VehicleDescriptionAttributeReaderLateBinding
{
    class Program
    {
        static void Main(string[] args)
        {
            Console.WriteLine("***** Value of VehicleDescriptionAttribute *****\n");
            ReflectAttributesUsingLateBinding();
            Console.ReadLine();
        }

        private static void ReflectAttributesUsingLateBinding()
        {
            try
            {
                // Load the local copy of AttributedCarLibrary.
                Assembly asm = Assembly.Load("AttributedCarLibrary");

                // Get type info of VehicleDescriptionAttribute.
                Type vehicleDesc =
                    asm.GetType("AttributedCarLibrary.VehicleDescriptionAttribute");

                // Get type info of the Description property.
                PropertyInfo propDesc = vehicleDesc.GetProperty("Description");

                // Get all types in the assembly.
                Type[] types = asm.GetTypes();

                // Iterate over each type and obtain any VehicleDescriptionAttributes.
                foreach (Type t in types)
                {
                    object[] objs = t.GetCustomAttributes(vehicleDesc, false);

                    // Iterate over each VehicleDescriptionAttribute and print
                    // the description using late binding.
                    foreach (object o in objs)
                    {
                        Console.WriteLine("-> {0}: {1}\n",
                            t.Name, propDesc.GetValue(o, null));
                    }
                }
            }
            catch (Exception ex)
            {
                Console.WriteLine(ex.Message);
            }
        }
    }
}

```

If you were able to follow along with the examples in this chapter, this code should be (more or less) self-explanatory. The only point of interest is the use of the `PropertyInfo.GetValue()` method, which is used to trigger the property's accessor. Here is the output of the current example:

```
***** Value of VehicleDescriptionAttribute *****

-> Motorcycle: My rocking Harley

-> HorseAndBuggy: The old gray mare, she ain't what she used to be...

-> Winnebago: A very long, slow, but feature-rich auto
```

Source Code The `VehicleDescriptionAttributeReaderLateBinding` project is included under the Chapter 15 subdirectory.

Putting Reflection, Late Binding, and Custom Attributes in Perspective

Even though you have seen numerous examples of these techniques in action, you may still be wondering when to make use of reflection, dynamic loading, late binding, and custom attributes in your programs? To be sure, these topics can seem a bit on the academic side of programming (which may or may not be a bad thing, depending on your point of view). To help map these topics to a real-world situation, you need a solid example. Assume for the moment that you are on a programming team that is building an application with the following requirement:

- The product must be extendable by the use of additional third-party tools.

What exactly is meant by *extendable*? Well, consider the Visual Studio 2010 IDE. When this application was developed, various “hooks” were inserted into the code base to allow other software vendors to “snap” (or plug-in) custom modules into the IDE. Obviously, the Visual Studio 2010 development team had no way to set references to external .NET assemblies it had not developed yet (thus, no early binding), so how exactly would an application provide the required hooks? Here is one possible way to solve this problem:

- First, an extendable application must provide some input vehicle to allow the user to specify the module to plug in (such as a dialog box or command-line flag). This requires *dynamic loading*.
- Second, an extendable application must be able to determine whether the module supports the correct functionality (such as a set of required interfaces) in order to be plugged into the environment. This requires *reflection*.

- Finally, an extendable application must obtain a reference to the required infrastructure (such as a set of interface types) and invoke the members to trigger the underlying functionality. This may require *late binding*.

Simply put, if the extendable application has been preprogrammed to query for specific interfaces, it is able to determine at runtime whether the type can be activated. Once this verification test has been passed, the type in question may support additional interfaces that provide a polymorphic fabric to their functionality. This is the exact approach taken by the Visual Studio 2010 team, and despite what you may be thinking, is not at all difficult!

Building an Extendable Application

In the sections that follow, I will take you through a complete example that illustrates the process of building an extendable Windows Forms application that can be augmented by the functionality of external assemblies. What I will *not* do at this point is comment on the process of building GUI applications with this tried and true desktop API (see Appendix A for an overview of the Windows Forms API).

■ **Note** Windows Forms was the initial desktop API of the .NET platform. However, since the release of .NET 3.0, the Windows Presentation Foundation (WPF) API is quickly becoming preferred GUI framework. While this is true, I will make use of Windows Forms for a number of client UI examples in this text, as the related code is a tad bit more intuitive than the corresponding WPF code.

If you are not familiar with the process of building Windows Forms applications, feel free to simply open up the supplied sample code and follow along. To serve as a road map, our extendable application entails the following assemblies:

- `CommonSnappableTypes.dll`: This assembly contains type definitions that will be used by each snap-in object and will be directly referenced by the Windows Forms application.
- `CSharpSnapIn.dll`: A snap-in written in C#, which leverages the types of `CommonSnappableTypes.dll`.
- `VbSnapIn.dll`: A snap-in written in Visual Basic, which leverages the types of `CommonSnappableTypes.dll`.
- `MyExtendableApp.exe`: This Windows Forms application will be the entity that may be extended by the functionality of each snap-in.

Again, this application will make use of dynamic loading, reflection, and late binding to dynamically gain the functionality of assemblies it has no prior knowledge of.

Building CommonSnappableTypes.dll

The first order of business is to create an assembly that contains the types that a given snap-in must leverage to be plugged into the expandable Windows Forms application. The CommonSnappableTypes Class Library project defines two types:

```
namespace CommonSnappableTypes
{
    public interface IAppFunctionality
    {
        void DoIt();
    }

    [AttributeUsage(AttributeTargets.Class)]
    public sealed class CompanyInfoAttribute : System.Attribute
    {
        public string CompanyName { get; set; }
        public string CompanyUrl { get; set; }
    }
}
```

The `IAppFunctionality` interface provides a polymorphic interface for all snap-ins that can be consumed by the extendable Windows Forms application. Given that this example is purely illustrative, you supply a single method named `DoIt()`. A more realistic interface (or a set of interfaces) might allow the object to generate scripting code, render an image onto the application's toolbox, or integrate into the main menu of the hosting application.

The `CompanyInfoAttribute` type is a custom attribute that can be applied on any class type that wishes to be snapped into the container. As you can tell by the definition of this class, `[CompanyInfo]` allows the developer of the snap-in to provide some basic details about the component's point of origin.

Building the C# Snap-In

Next up, you need to create a type that implements the `IAppFunctionality` interface. Again, to focus on the overall design of an extendable application, a trivial type is in order. Assume a new C# Class Library project named `CSharpSnapIn` defines a class type named `CSharpModule`. Given that this class must make use of the types defined in `CommonSnappableTypes`, be sure to set a reference to the `CommonSnappableTypes` assembly (as well as `System.Windows.Forms.dll` to display a noteworthy message). This being said, here is the code:

```
using System;
using System.Collections.Generic;
using System.Linq;
using System.Text;

using CommonSnappableTypes;
using System.Windows.Forms;

namespace CSharpSnapIn
{
    [CompanyInfo(CompanyName = "My Company",
        CompanyUrl = "www.MyCompany.com")]
}
```

```
public class CSharpModule : IAppFunctionality
{
    void IAppFunctionality.DoIt()
    {
        MessageBox.Show("You have just used the C# snap in!");
    }
}
```

Notice that I choose to make use of explicit interface implementation (see Chapter 9) when supporting the `IAppFunctionality` interface. This is not required; however, the idea is that the only part of the system that needs to directly interact with this interface type is the hosting Windows application. By explicitly implementing this interface, the `DoIt()` method is not directly exposed from the `CSharpModule` type.

Building the Visual Basic Snap-In

Now, to simulate the role of a third-party vendor who prefers Visual Basic over C#, create a new Visual Basic Class Library (`VbSnapIn`) that references the same external assemblies as the previous `CSharpSnapIn` project.

Note By default, a Visual Basic project will not display the References folder within the Solution Explorer. To add references in a VB project, use the Project | Add Reference... menu option of Visual Studio 2010.

The code is (again) intentionally simple:

```
Imports System.Windows.Forms
Imports CommonSnippableTypes

<CompanyInfo(CompanyName:="Chucky's Software", CompanyUrl:="www.ChuckySoft.com")>
Public Class VbSnapIn
    Implements IAppFunctionality

    Public Sub DoIt() Implements CommonSnippableTypes.IAppFunctionality.DoIt
        MessageBox.Show("You have just used the VB snap in!")
    End Sub
End Class
```

Notice that applying attributes in the syntax of Visual Basic requires angle brackets (`< >`) rather than square brackets (`[]`). Also notice that the `Implements` keyword is used to implement interface types on a given class or structure.

Building an Extendable Windows Forms Application

The final step is to create a new C# Windows Forms application (MyExtendableApp) that allows the user to select a snap-in using a standard Windows Open dialog box. If you have not created a Windows Forms application before, begin this final project of the chapter by selecting a Windows Forms Application project from the New Project dialog box of Visual Studio 2010 (Figure 15-7).




Figure 15-7. Creating a new Windows Forms project with Visual Studio 2010

Now, set a reference to the `CommonSnappableTypes.dll` assembly, but *not* the `CSharpSnapIn.dll` or `VbSnapIn.dll` code libraries. As well, import the `System.Reflection` and `CommonSnappableTypes` namespaces into your form's primary code file (which you can open by right clicking on the form designer and selecting View Code). Remember that the whole goal of this application is to make use of late binding and reflection to determine the “snapability” of independent binaries created by third-party vendors.

Again, I won't bother to examine all the details of Windows Forms development at this point in the text (see Appendix A). However, assuming you have placed a `MenuStrip` component onto the forms designer, define a topmost menu item named `File` that provides a single submenu named `Snap In Module`. As well, the main window will contain a `ListBox` type (which I renamed as `lstLoadedSnapIns`) that will be used to display the names of each snap-in loaded by the user. Figure 15-8 shows the final GUI.




Figure 15-8. GUI for MyExtendableApp

The code that handles the Click event for the File ► Snap In Module menu item (which may be created simply by double-clicking the menu item from the design-time editor) displays a File Open dialog box and extracts the path to the selected file. Assuming the user did not select the CommonSnappableTypes.dll assembly (as this is purely infrastructure), the path is then sent into a helper function named LoadExternalModule() for processing (implemented next). This method will return false when it is unable to find a class implementing IAppFunctionality:

```
private void snapInModuleToolStripMenuItem_Click(object sender,
    EventArgs e)
{
    // Allow user to select an assembly to load.
    OpenFileDialog dlg = new OpenFileDialog();
    if (dlg.ShowDialog() == DialogResult.OK)
    {
        if(dlg.FileName.Contains("CommonSnappableTypes"))
            MessageBox.Show("CommonSnappableTypes has no snap-ins!");
        else if(!LoadExternalModule(dlg.FileName))
            MessageBox.Show("Nothing implements IAppFunctionality!");
    }
}
```

The LoadExternalModule() method performs the following tasks:

- Dynamically loads the selected assembly into memory
- Determines whether the assembly contains any types implementing IAppFunctionality
- Creates the type using late binding

If a type implementing IAppFunctionality is found, the DoIt() method is called, and the fully qualified name of the type is added to the ListBox (note that the foreach loop will iterate over all types in the assembly to account for the possibility that a single assembly has multiple snap-ins).

```
private bool LoadExternalModule(string path)
```

```

{
    bool foundSnapIn = false;
    Assembly theSnapInAsm = null;

    try
    {
        // Dynamically load the selected assembly.
        theSnapInAsm = Assembly.LoadFrom(path);
    }
    catch(Exception ex)
    {
        MessageBox.Show(ex.Message);
        return foundSnapIn;
    }

    // Get all IAppFunctionality compatible classes in assembly.
    var theClassTypes = from t in theSnapInAsm.GetTypes()
                        where t.IsClass &&
                            (t.GetInterface("IAppFunctionality") != null)
                        select t;

    // Now, create the object and call DoIt() method.
    foreach (Type t in theClassTypes)
    {
        foundSnapIn = true;
        // Use late binding to create the type.
        IAppFunctionality itfApp =
            (IAppFunctionality)theSnapInAsm.CreateInstance(t.FullName, true);
        itfApp.DoIt();
        lstLoadedSnapIns.Items.Add(t.FullName);
    }
    return foundSnapIn;
}

```

At this point, you can run your application. When you select the CSharpSnapIn.dll or VbSnapIn.dll assemblies, you should see the correct message displayed. The final task is to display the metadata provided by the [CompanyInfo] attribute. To do so, update LoadExternalModule() to call a new helper function named DisplayCompanyData() before exiting the foreach scope. Notice this method takes a single System.Type parameter.

```

private bool LoadExternalModule(string path)
{
    ...
    foreach (Type t in theClassTypes)
    {
        ...
        // Show company info.
        DisplayCompanyData(t);
    }
    return foundSnapIn;
}

```

Using the incoming type, simply reflect over the [CompanyInfo] attribute:

```

private void DisplayCompanyData(Type t)
{
    // Get [CompanyInfo] data.
    var compInfo = from ci in t.GetCustomAttributes(false) where
        (ci.GetType() == typeof(CompanyInfoAttribute))
        select ci;

    // Show data.
    foreach (CompanyInfoAttribute c in compInfo)
    {
        MessageBox.Show(c.CompanyUrl,
            string.Format("More info about {0} can be found at", c.CompanyName));
    }
}

```

Figure 15-9 shows one possible run.




Figure 15-9. Snapping in external assemblies

Excellent! That wraps up the example application. I hope you can see that the topics presented in this chapter can be quite helpful in the real world and are not limited to the tool builders of the world.

■ **Source Code** The ExtendableApp folder under the Chapter 15 subdirectory contains the CommonSnappableTypes, CSharpSnapIn, VbSnapIn, and MyExtendableApp projects.

Summary

Reflection is a very interesting aspect of a robust OO environment. In the world of .NET, the keys to reflection services revolve around the `System.Type` class and the `System.Reflection` namespace. As you have seen, reflection is the process of placing a type under the magnifying glass at runtime to understand the who, what, where, when, why, and how of a given item.

Late binding is the process of creating a type and invoking its members without prior knowledge of the specific names of said members. Late binding is often a direct result of *dynamic loading*, which allows you to load a .NET assembly into memory programmatically. As shown during this chapter's extendable application example, this is a very powerful technique used by tool builders as well as tool consumers. This chapter also examined the role of attribute-based programming. When you adorn your types with attributes, the result is the augmentation of the underlying assembly metadata.



Processes, AppDomains, and Object Contexts

In the previous two chapters, you examined the steps taken by the CLR to resolve the location of a referenced external assembly as well as the role of .NET metadata. In this chapter, you'll drill deeper into the details of how an assembly is hosted by the CLR and come to understand the relationship between processes, application domains, and object contexts.

In a nutshell, *application domains* (or simply *AppDomains*) are logical subdivisions within a given process that host a set of related .NET assemblies. As you will see, an AppDomain is further subdivided into *contextual boundaries*, which are used to group together like-minded .NET objects. Using the notion of context, the CLR is able to ensure that objects with special runtime requirements are handled appropriately.

While it is true that many of your day-to-day programming tasks may not involve directly working with processes, app domains, or object contexts, understanding these topics is very important when working with numerous .NET APIs including Windows Communication Foundation (WCF), multithreading and parallel processing and object serialization.

The Role of a Windows Process

The concept of a “process” has existed within Windows-based operating systems well before the release of the .NET platform. In simple terms, a process is a running program. However, formally speaking, a process is an operating system level concept used to describe a set of resources (such as external code libraries and the primary thread) and the necessary memory allocations used by a running application. For each *.exe loaded into memory, the OS creates a separate and isolated process for use during its lifetime.

Using this approach to application isolation, the result is a much more robust and stable runtime environment, given that the failure of one process does not affect the functioning of another. Furthermore, data in one process cannot be directly accessed by another process, unless you make use of a distributed computing programming API such as Windows Communication Foundation. Given these points, you can regard the process as a fixed, safe boundary for a running application.

Now, every Windows process is assigned a unique process identifier (PID) and may be independently loaded and unloaded by the OS as necessary (as well as programmatically). As you may be aware, the Processes tab of the Windows Task Manager utility (activated via the Ctrl+Shift+Esc keystroke combination) allows you to view various statistics regarding the processes running on a given machine, including its PID and image name (see Figure 16-1).

Note By default, the PID column of the Process tab will not be shown. To enable this feature, activate the View | Select Columns... menu option, and then check the PID (Process Identifier) checkbox.




Figure 16-1. The Windows Task Manager

The Role of Threads

Every Windows process contains an initial “thread” that functions as the entry point for the application. Chapter 19 examines the details of building multithreaded applications under the .NET platform; however, to facilitate the topics presented here, you need a few working definitions. First of all, a *thread* is a path of execution within a process. Formally speaking, the first thread created by a process’s entry point is termed the *primary thread*. Any .NET executable program (Console Application, Windows Forms application, WPF application, etc.) marks its entry point with the `Main()` method. When this method is invoked, the primary thread is created automatically.

Processes that contain a single primary thread of execution are intrinsically *thread safe*, given the fact that there is only one thread that can access the data in the application at a given time. However, a single-threaded process (especially one that is GUI-based) will often appear a bit unresponsive to the user if this single thread is performing a complex operation (such as printing out a lengthy text file, performing a mathematically intensive calculation, or attempting to connect to a remote server located thousands of miles away).

Given this potential drawback of single-threaded applications, the Windows API (as well as the .NET platform) makes it possible for the primary thread to spawn additional secondary threads (also termed *worker threads*) using a handful of Windows API functions such as `CreateThread()`. Each thread (primary

or secondary) becomes a unique path of execution in the process and has concurrent access to all shared points of data within the process.

As you may have guessed, developers typically create additional threads to help improve the program's overall responsiveness. Multithreaded processes provide the illusion that numerous activities are happening at more or less the same time. For example, an application may spawn a worker thread to perform a labor-intensive unit of work (again, such as printing a large text file). As this secondary thread is churning away, the main thread is still responsive to user input, which gives the entire process the potential of delivering greater performance. However, this may not actually be the case: using too many threads in a single process can actually *degrade* performance, as the CPU must switch between the active threads in the process (which takes time).

On some machines, multithreading is most commonly an illusion provided by the OS. Machines that host a single (non-hyperthreaded) CPU do not have the ability to literally handle multiple threads at the same exact time. Rather, a single CPU will execute one thread for a unit of time (called a *time slice*) based in part on the thread's priority level. When a thread's time slice is up, the existing thread is suspended to allow another thread to perform its business. For a thread to remember what was happening before it was kicked out of the way, each thread is given the ability to write to Thread Local Storage (TLS) and is provided with a separate call stack, as illustrated in Figure 16-2.




Figure 16-2. The Windows process/thread relationship

If the subject of threads is new to you, don't sweat the details. At this point, just remember that a thread is a unique path of execution within a Windows process. Every process has a primary thread (created via the executable's entry point) and may contain additional threads that have been programmatically created.

Interacting with Processes Under the .NET Platform

Although processes and threads are nothing new, the manner in which you interact with these primitives under the .NET platform has changed quite a bit (for the better). To pave the way to understanding the world of building multithreaded assemblies (see Chapter 19), let's begin by checking out how to interact with processes using the .NET base class libraries.

The `System.Diagnostics` namespace defines a number of types that allow you to programmatically interact with processes and various diagnostic-related types such as the system event log and performance counters. In this chapter, you are only concerned with the process-centric types defined in Table 16-1.

Table 16-1. Select Members of the System.Diagnostics Namespace

Process-Centric Types of the System.Diagnostics Namespace	Meaning in Life
Process	The Process class provides access to local and remote processes and also allows you to programmatically start and stop processes.
ProcessModule	This type represents a module (*.dll or *.exe) that is loaded into a particular process. Understand that the ProcessModule type can represent <i>any</i> module—COM-based, .NET-based, or traditional C-based binaries.
ProcessModuleCollection	Provides a strongly typed collection of ProcessModule objects.
ProcessStartInfo	Specifies a set of values used when starting a process via the Process.Start() method.
ProcessThread	Represents a thread within a given process. Be aware that ProcessThread is a type used to diagnose a process's thread set and is not used to spawn new threads of execution within a process.
ProcessThreadCollection	Provides a strongly typed collection of ProcessThread objects.

The System.Diagnostics.Process class allows you to analyze the processes running on a given machine (local or remote). The Process class also provides members that allow you to programmatically start and terminate processes, view (or modify) a process's priority level, and obtain a list of active threads and/or loaded modules within a given process. Table 16-2 lists some of the key properties of System.Diagnostics.Process.

Table 16-2. Select Properties of the Process Type

Property	Meaning in Life
ExitTime	This property gets the timestamp associated with the process that has terminated (represented with a DateTime type).
Handle	This property returns the handle (represented by an IntPtr) associated to the process by the OS. This can be useful when working building .NET applications which need to communicate with unmanaged code.
Id	This property gets the PID for the associated process.
MachineName	This property gets the name of the computer the associated process is running on.

Table 16-2. Select Properties of the Process Type (continued)

Property	Meaning in Life
MainWindowTitle	MainWindowTitle gets the caption of the main window of the process (if the process does not have a main window, you receive an empty string).
Modules	This property provides access to the strongly typed ProcessModuleCollection type, which represents the set of modules (*.dll or *.exe) loaded within the current process.
ProcessName	This property gets the name of the process (which, as you would assume, is the name of the application itself).
Responding	This property gets a value indicating whether the user interface of the process is responding to user input (or is currently “hung”).
StartTime	This property gets the time that the associated process was started (via a DateTime type).
Threads	This property gets the set of threads that are running in the associated process (represented via a collection of ProcessThread objects).

In addition to the properties just examined, `System.Diagnostics.Process` also defines a few useful methods (Table 16-3).

Table 16-3. Select Methods of the Process Type

Method	Meaning in Life
<code>CloseMainWindow()</code>	This method closes a process that has a user interface by sending a close message to its main window.
<code>GetCurrentProcess()</code>	This static method returns a new <code>Process</code> object that represents the currently active process.
<code>GetProcesses()</code>	This static method returns an array of new <code>Process</code> objects running on a given machine.
<code>Kill()</code>	This method immediately stops the associated process.
<code>Start()</code>	This method starts a process.

Enumerating Running Processes

To illustrate the process of manipulating `Process` objects (pardon the redundancy), assume you have a C# Console Application named `ProcessManipulator` that defines the following static helper method within the `Program` class (be sure you import the `System.Diagnostics` namespace in your code file):

```
static void ListAllRunningProcesses()
{
    // Get all the processes on the local machine, ordered by
    // PID.
    var runningProcs =
        from proc in Process.GetProcesses(".") orderby proc.Id select proc;

    // Print out PID and name of each process.
    foreach(var p in runningProcs)
    {
        string info = string.Format("-> PID: {0}\tName: {1}",
            p.Id, p.ProcessName);
        Console.WriteLine(info);
    }
    Console.WriteLine("*****\n");
}
```

The static `Process.GetProcesses()` method returns an array of `Process` objects that represent the running processes on the target machine (the dot notation shown here represents the local computer). Once you have obtained the array of `Process` objects, you are able to invoke any of the members seen in Table 16-2 and Table 16-3. Here, you are simply displaying the PID and the name of each process, ordered by PID. Assuming the `Main()` method has been updated to call `ListAllRunningProcesses()`:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Processes *****\n");
    ListAllRunningProcesses();
    Console.ReadLine();
}
```

you will see the names and PIDs for all processes on your local computer. Here is some partial output from my current machine.

```
***** Fun with Processes *****
```

```
-> PID: 0      Name: Idle
-> PID: 4      Name: System
-> PID: 108    Name: iexplore
-> PID: 268    Name: smss
-> PID: 432    Name: csrss
-> PID: 448    Name: svchost
-> PID: 472    Name: wininit
-> PID: 504    Name: csrss
-> PID: 536    Name: winlogon
-> PID: 560    Name: services
-> PID: 584    Name: lsass
```

```

-> PID: 592      Name: lsm
-> PID: 660      Name: devenv
-> PID: 684      Name: svchost
-> PID: 760      Name: svchost
-> PID: 832      Name: svchost
-> PID: 844      Name: svchost
-> PID: 856      Name: svchost
-> PID: 900      Name: svchost
-> PID: 924      Name: svchost
-> PID: 956      Name: VMwareService
-> PID: 1116     Name: spoolsv
-> PID: 1136     Name: ProcessManipulator.vhost
*****

```

Investigating a Specific Process

In addition to obtaining a full and complete list of all running processes on a given machine, the static `Process.GetProcessById()` method allows you to obtain a single `Process` object via the associated PID. If you request access to a nonexistent PID, an `ArgumentException` exception is thrown. For example, if you were interested in obtaining a `Process` object representing a process with the PID of 987, you could write the following code:

```

// If there is no process with the PID of 987, a
// runtime exception will be thrown.
static void GetSpecificProcess()
{
    Process theProc = null;
    try
    {
        theProc = Process.GetProcessById(987);
    }
    catch(ArgumentException ex)
    {
        Console.WriteLine(ex.Message);
    }
}

```

At this point, you have learned how to get a list of all processes, or a specific process on a machine via a PID lookup. While it is somewhat useful to discover PIDs and process names, the `Process` class also allows you to discover the set of current threads and libraries used within a given process. Let's see how to do so.

Investigating a Process's Thread Set

The set of threads is represented by the strongly typed `ProcessThreadCollection` collection, which contains some number of individual `ProcessThread` objects. To illustrate, assume the following additional static helper function has been added to your current application:

```

static void EnumThreadsForPid(int pID)
{
    Process theProc = null;
    try
    {
        theProc = Process.GetProcessById(pID);
    }
    catch(ArgumentException ex)
    {
        Console.WriteLine(ex.Message);
        return;
    }

    // List out stats for each thread in the specified process.
    Console.WriteLine("Here are the threads used by: {0}",
                      theProc.ProcessName);
    ProcessThreadCollection theThreads = theProc.Threads;

    foreach(ProcessThread pt in theThreads)
    {
        string info =
            string.Format("-> Thread ID: {0}\tStart Time: {1}\tPriority: {2}",
                          pt.Id , pt.StartTime.ToShortTimeString(), pt.PriorityLevel);
        Console.WriteLine(info);
    }
    Console.WriteLine("*****\n");
}

```

As you can see, the `Threads` property of the `System.Diagnostics.Process` type provides access to the `ProcessThreadCollection` class. Here, you are printing out the assigned thread ID, start time, and priority level of each thread in the process specified by the client. Now, update your program's `Main()` method to prompt the user for a PID to investigate, as follows:

```

static void Main(string[] args)
{
    ...
    // Prompt user for a PID and print out the set of active threads.
    Console.WriteLine("**** Enter PID of process to investigate ****");
    Console.Write("PID: ");
    string pID = Console.ReadLine();
    int theProcID = int.Parse(pID);

    EnumThreadsForPid(theProcID);
    Console.ReadLine();
}

```

When you run your program, you can now enter the PID of any process on your machine, and see the threads used in the process. The following output shows the threads used by PID 108 on my machine, which happens to be hosting Microsoft Internet Explorer:

```
***** Enter PID of process to investigate *****
PID: 108
Here are the threads used by: iexplore
-> Thread ID: 680      Start Time: 9:05 AM      Priority: Normal
-> Thread ID: 2040     Start Time: 9:05 AM      Priority: Normal
-> Thread ID: 880      Start Time: 9:05 AM      Priority: Normal
-> Thread ID: 3380     Start Time: 9:05 AM      Priority: Normal
-> Thread ID: 3376     Start Time: 9:05 AM      Priority: Normal
-> Thread ID: 3448     Start Time: 9:05 AM      Priority: Normal
-> Thread ID: 3476     Start Time: 9:05 AM      Priority: Normal
-> Thread ID: 2264     Start Time: 9:05 AM      Priority: Normal
-> Thread ID: 2380     Start Time: 9:05 AM      Priority: Normal
-> Thread ID: 2384     Start Time: 9:05 AM      Priority: Normal
-> Thread ID: 2308     Start Time: 9:05 AM      Priority: Normal
-> Thread ID: 3096     Start Time: 9:07 AM      Priority: Highest
-> Thread ID: 3600     Start Time: 9:45 AM      Priority: Normal
-> Thread ID: 1412     Start Time: 10:02 AM     Priority: Normal
```

The `ProcessThread` type has additional members of interest beyond `Id`, `StartTime`, and `PriorityLevel`. Table 16-4 documents some members of interest.

Table 16-4. Select Members of the `ProcessThread` Type

Member	Meaning in Life
<code>CurrentPriority</code>	Gets the current priority of the thread
<code>Id</code>	Gets the unique identifier of the thread
<code>IdealProcessor</code>	Sets the preferred processor for this thread to run on
<code>PriorityLevel</code>	Gets or sets the priority level of the thread
<code>ProcessorAffinity</code>	Sets the processors on which the associated thread can run
<code>StartAddress</code>	Gets the memory address of the function that the operating system called that started this thread
<code>StartTime</code>	Gets the time that the operating system started the thread
<code>ThreadState</code>	Gets the current state of this thread
<code>TotalProcessorTime</code>	Gets the total amount of time that this thread has spent using the processor
<code>WaitReason</code>	Gets the reason that the thread is waiting

Before you read any further, be very aware that the `ProcessThread` type is *not* the entity used to create, suspend, or kill threads under the .NET platform. Rather, `ProcessThread` is a vehicle used to obtain diagnostic information for the active Windows threads within a running process. Again, you will investigate how to build multithreaded applications using the `System.Threading` namespace in Chapter 19.

Investigating a Process's Module Set

Next up, let's check out how to iterate over the number of loaded modules that are hosted within a given process. When talking about processes, a *module* is a general term used to describe a given *.dll (or the *.exe itself) that is hosted by a specific process. When you access the `ProcessModuleCollection` via the `Process.Modules` property, you are able to enumerate over *all modules* hosted within a process: .NET-based, COM-based, or traditional C-based libraries. Ponder the following additional helper function that will enumerate the modules in a specific process based on the PID:

```
static void EnumModsForPid(int pID)
{
    Process theProc = null;
    try
    {
        theProc = Process.GetProcessById(pID);
    }
    catch(ArgumentException ex)
    {
        Console.WriteLine(ex.Message);
        return;
    }

    Console.WriteLine("Here are the loaded modules for: {0}",
        theProc.ProcessName);
    ProcessModuleCollection theMods = theProc.Modules;
    foreach(ProcessModule pm in theMods)
    {
        string info = string.Format("-> Mod Name: {0}", pm.ModuleName);
        Console.WriteLine(info);
    }
    Console.WriteLine("*****\n");
}
```

To see some possible output, let's check out the loaded modules for the process hosting the current example program (`ProcessManipulator`). To do so, run the application, identify the PID assigned to `ProcessManipulator.exe` (via the Task Manager) and pass this value to the `EnumModsForPid()` method (be sure to update your `Main()` method accordingly). Once you do, you may be surprised to see the list of *.dlls used for a simple Console Application (`GDI32.dll`, `USER32.dll`, `ole32.dll`, and so forth). Consider the following output:

```
Here are the loaded modules for: ProcessManipulator
-> Mod Name: ProcessManipulator.exe
-> Mod Name: ntdll.dll
-> Mod Name: MSCOREE.DLL
-> Mod Name: KERNEL32.dll
```

```

-> Mod Name: KERNELBASE.dll
-> Mod Name: ADVAPI32.dll
-> Mod Name: msvcrt.dll
-> Mod Name: sechost.dll
-> Mod Name: RPCRT4.dll
-> Mod Name: SspiCli.dll
-> Mod Name: CRYPTBASE.dll
-> Mod Name: mscoreei.dll
-> Mod Name: SHLWAPI.dll
-> Mod Name: GDI32.dll
-> Mod Name: USER32.dll
-> Mod Name: LPK.dll
-> Mod Name: USP10.dll
-> Mod Name: IMM32.DLL
-> Mod Name: MSCTF.dll
-> Mod Name: clr.dll
-> Mod Name: MSVCR100_CLR0400.dll
-> Mod Name: mscorlib.ni.dll
-> Mod Name: nlssorting.dll
-> Mod Name: ole32.dll
-> Mod Name: clrjit.dll
-> Mod Name: System.ni.dll
-> Mod Name: System.Core.ni.dll
-> Mod Name: psapi.dll
-> Mod Name: shfolder.dll
-> Mod Name: SHELL32.dll
*****

```

Starting and Stopping Processes Programmatically

The final aspects of the `System.Diagnostics.Process` class examined here are the `Start()` and `Kill()` methods. As you can gather by their names, these members provide a way to programmatically launch and terminate a process, respectively. For example, consider the static `StartAndKillProcess()` helper method:

Note You must be running Visual Studio 2010 with Administrator rights in order to start new processes. If this is not the case, you will receive a runtime error.

```

static void StartAndKillProcess()
{
    Process ieProc = null;

    // Launch Internet Explorer, and go to facebook!
    try
    {
        ieProc = Process.Start("IExplore.exe", "www.facebook.com");

```

```

}
catch (InvalidOperationException ex)
{
    Console.WriteLine(ex.Message);
}

Console.Write("--> Hit enter to kill {0}...", ieProc.ProcessName);
Console.ReadLine();

// Kill the iexplore.exe process.
try
{
    ieProc.Kill();
}
catch (InvalidOperationException ex)
{
    Console.WriteLine(ex.Message);
}
}
}

```

The static `Process.Start()` method has been overloaded a few times. At minimum, you will need to specify the friendly name of the process you wish to launch (such as Microsoft Internet Explorer, `iexplore.exe`). This example makes use of a variation of the `Start()` method that allows you to specify any additional arguments to pass into the program's entry point (i.e., the `Main()` method).

Once you call the `Start()` method, you are returned a reference to the newly activated process. When you wish to terminate the process, simply call the instance-level `Kill()` method. Here, you are wrapping the calls to `Start()` and `Kill()` within a try / catch block, and handling any `InvalidOperationException` errors. This is especially important when calling the `Kill()` method, as this error will be raised if the process has already been terminated prior to calling `Kill()`.

Controlling Process Startup using the `ProcessStartInfo` Class

The `Start()` method also allows you to pass in a `System.Diagnostics.ProcessStartInfo` type to specify additional bits of information regarding how a given process should come to life. Here is a partial definition of `ProcessStartInfo` (see the .NET Framework 4.0 SDK documentation for full details):

```

public sealed class ProcessStartInfo : object
{
    public ProcessStartInfo();
    public ProcessStartInfo(string fileName);
    public ProcessStartInfo(string fileName, string arguments);
    public string Arguments { get; set; }
    public bool CreateNoWindow { get; set; }
    public StringDictionary EnvironmentVariables { get; }
    public bool ErrorDialog { get; set; }
    public IntPtr ErrorDialogParentHandle { get; set; }
    public string FileName { get; set; }
    public bool LoadUserProfile { get; set; }
    public SecureString Password { get; set; }
    public bool RedirectStandardError { get; set; }
}

```

```

public bool RedirectStandardInput { get; set; }
public bool RedirectStandardOutput { get; set; }
public Encoding StandardErrorEncoding { get; set; }
public Encoding StandardOutputEncoding { get; set; }
public bool UseShellExecute { get; set; }
public string Verb { get; set; }
public string[] Verbs { get; }
public ProcessWindowStyle WindowStyle { get; set; }
public string WorkingDirectory { get; set; }
}

```

To illustrate how to fine-tune your process startup, here is a modified version of `StartAndKillProcess()`, which will load Microsoft Internet Explorer, navigate to `www.facebook.com`, and show the window in a maximized state:

```

static void StartAndKillProcess()
{
    Process ieProc = null;

    // Launch Internet Explorer, and go to facebook,
    // with maximized window.
    try
    {
        ProcessStartInfo startInfo = new
            ProcessStartInfo("IExplore.exe", "www.facebook.com");
        startInfo.WindowStyle = ProcessWindowStyle.Maximized;

        ieProc = Process.Start(startInfo);
    }
    catch (InvalidOperationException ex)
    {
        Console.WriteLine(ex.Message);
    }
    ...
}

```

Great! Now that you understand the role of Windows processes and how to interact with them from C# code, you are ready to investigate the concept of a .NET application domain.

■ Source Code The `ProcessManipulator` project is included under the Chapter 16 subdirectory.

Understanding .NET Application Domains

Under the .NET platform, executables are not hosted directly within a Windows process, as is the case in traditional unmanaged applications. Rather, a .NET executable is hosted by a logical partition within a process termed an *application domain*. As you will see, a single process may contain multiple

application domains, each of which is hosting a .NET executable. This additional subdivision of a traditional Windows process offers several benefits, some of which are as follows:

- AppDomains are a key aspect of the OS-neutral nature of the .NET platform, given that this logical division abstracts away the differences in how an underlying OS represents a loaded executable.
- AppDomains are far less expensive in terms of processing power and memory than a full-blown process. Thus, the CLR is able to load and unload application domains much quicker than a formal process, and can drastically improve scalability of server applications.
- AppDomains provide a deeper level of isolation for hosting a loaded application. If one AppDomain within a process fails, the remaining AppDomains remain functional.

As mentioned, a single process can host any number of AppDomains, each of which is fully and completely isolated from other AppDomains within this process (or any other process). Given this fact, be very aware that an application running in one AppDomain is unable to obtain data of any kind (global variables or static fields) within another AppDomain unless they make use of a distributed programming protocol (such as Windows Communication Foundation).

While a single process *may* host multiple AppDomains, this is not typically the case. At the very least, an OS process will host what is termed the *default application domain*. This specific application domain is automatically created by the CLR at the time the process launches. After this point, the CLR creates additional application domains on an as-needed basis.

The System.AppDomain Class

The .NET platform allows you to programmatically monitor app domains, create new app domains (or unload them) at runtime, load assemblies into app domains, and a whole slew of additional tasks, using the AppDomain class in the System namespace of mscorelib.dll. Table 16-5 documents some useful methods of the AppDomain class (consult the .NET Framework 4.0 SDK documentation for full details).

Table 16-5. Select Methods of AppDomain

Method	Meaning in Life
CreateDomain()	This static method allows you to create a new AppDomain in the current process.
CreateInstance()	Creates an instance of a type in an external assembly, after loading said assembly into the calling application domain.
ExecuteAssembly()	This method executes an *.exe assembly within an application domain, given its file name.
GetAssemblies()	This method gets the set of .NET assemblies that have been loaded into this application domain (COM-based or C-based binaries are ignored).

Table 16-5. Select Methods of AppDomain (continued)

Method	Meaning in Life
GetCurrentThreadId()	This static method returns the ID of the active thread in the current application domain.
Load()	This method is used to dynamically load an assembly into the current application domain.
Unload()	This is another static method that allows you to unload a specified AppDomain within a given process.

■ **Note** The .NET platform does not allow you to unload a specific assembly from memory. The only way to programmatically unload libraries is to tear down the hosting application domain via the Unload() method.

In addition, the AppDomain class also defines a set of properties which can be useful when you wish to monitor activity of a given application domain. Table 16-6 documents some core properties of interest.

Table 16-6. Select Properties of AppDomain

Property	Meaning in Life
BaseDirectory	Gets the directory path that the assembly resolver uses to probe for assemblies.
CurrentDomain	This static property gets the application domain for the currently executing thread.
FriendlyName	Gets the friendly name of the current application domain.
MonitoringEnabled	Gets or sets a value that indicates whether CPU and memory monitoring of application domains is enabled for the current process. Once monitoring is enabled for a process, it cannot be disabled.
SetupInformation	Gets the configuration details for a given application domain, represented by an AppDomainSetup object.

Last but not least, the AppDomain class supports a set of events that correspond to various aspects of an application domain's life cycle. Table 16-7 shows some of the more useful events you can hook into.

Table 16-7. Select Events of the AppDomain Type

Event	Meaning in Life
AssemblyLoad	Occurs when an assembly is loaded into memory.
AssemblyResolve	This event will fire when the assembly resolver cannot find the location of a required assembly.
DomainUnload	Occurs when an AppDomain is about to be unloaded from the hosting process.
FirstChanceException	This event allows you to be notified that an exception has been thrown from the application domain, before the CLR will begin looking for a fitting catch statement.
ProcessExit	Occurs on the default application domain when the default application domain's parent process exits.
UnhandledException	Occurs when an exception is not caught by an exception handler.

Interacting with the Default Application Domain

Recall that when a .NET executable starts, the CLR will automatically place it into the default app domain of the hosting process. This is done automatically and transparently, and you never have to author any specific code to do so. However, it is possible for your application to gain access to this default application domain using the static `AppDomain.CurrentDomain` property. Once you have this access point, you are able to hook into any events of interest, or make use of the methods and properties of `AppDomain` to perform some runtime diagnostics.

To learn how to interact with the default application domain, begin by creating a new Console Application named `DefaultAppDomainApp`. Now, update your Program with the following logic, which will simply display some details about the default application domain, using a number of members of the `AppDomain` class:

```
class Program
{
    static void Main(string[] args)
    {
        Console.WriteLine("***** Fun with the default app domain *****\n");
        DisplayDADStats();
        Console.ReadLine();
    }

    private static void DisplayDADStats()
    {
        // Get access to the app domain for the current thread.
    }
}
```

```

AppDomain defaultAD = AppDomain.CurrentDomain;

// Print out various stats about this domain.
Console.WriteLine("Name of this domain: {0}", defaultAD.FriendlyName);
Console.WriteLine("ID of domain in this process: {0}", defaultAD.Id);
Console.WriteLine("Is this the default domain?: {0}",
    defaultAD.IsDefaultAppDomain());
Console.WriteLine("Base directory of this domain: {0}", defaultAD.BaseDirectory);
}
}

```

The output of this example can be seen here:

```

***** Fun with the default app domain *****

Name of this domain: DefaultAppDomainApp.exe
ID of domain in this process: 1
Is this the default domain?: True
Base directory of this domain: E:\MyCode\DefaultAppDomainApp\bin\Debug\

```

Notice that the name of the default application domain will be identical to the name of the executable which is contained within it (`DefaultAppDomainApp.exe` in this example). Also notice, that the base directory value, which will be used to probe for externally required private assemblies, maps to the current location of the deployed executable.

Enumerating Loaded Assemblies

It is also possible to discover all of the loaded .NET assemblies within a given application domain using the instance level `GetAssemblies()` method. This method will return to you an array of `Assembly` objects, which as you recall from the previous chapter, is a member of the `System.Reflection` namespace (so don't forget to import this namespace into your C# code file!)

To illustrate, define a new method named `ListAllAssembliesInAppDomain()` within the `Program` class. This helper method will obtain all loaded assemblies, and print out the friendly name and version of each:

```

static void ListAllAssembliesInAppDomain()
{
    // Get access to the app domain for the current thread.
    AppDomain defaultAD = AppDomain.CurrentDomain;

    // Now get all loaded assemblies in the default app domain.
    Assembly[] loadedAssemblies = defaultAD.GetAssemblies();
    Console.WriteLine("***** Here are the assemblies loaded in {0} *****\n",
        defaultAD.FriendlyName);
    foreach(Assembly a in loadedAssemblies)
    {
        Console.WriteLine("-> Name: {0}", a.GetName().Name);
        Console.WriteLine("-> Version: {0}\n", a.GetName().Version);
    }
}

```

```
    }
}
```

Assuming you have updated your `Main()` method to call this new member, you will see that the application domain hosting your executable is currently making use of the following .NET libraries:

```
***** Here are the assemblies loaded in DefaultAppDomainApp.exe *****
```

```
-> Name: mscorlib
-> Version: 4.0.0.0

-> Name: DefaultAppDomainApp
-> Version: 1.0.0.0
```

Now understand that the list of loaded assemblies can change at any time as you author new C# code. For example, assume you have updated your `ListAllAssembliesInAppDomain()` method to make use of a LINQ query, which will order the loaded assemblies by name:

```
static void ListAllAssembliesInAppDomain()
{
    // Get access to the app domain for the current thread.
    AppDomain defaultAD = AppDomain.CurrentDomain;

    // Now get all loaded assemblies in the default app domain.
    var loadedAssemblies = from a in defaultAD.GetAssemblies()
                           orderby a.GetName().Name select a;

    Console.WriteLine("***** Here are the assemblies loaded in {0} *****\n",
                      defaultAD.FriendlyName);
    foreach (var a in loadedAssemblies)
    {
        Console.WriteLine("-> Name: {0}", a.GetName().Name);
        Console.WriteLine("-> Version: {0}\n", a.GetName().Version);
    }
}
```

If you were to run the program once again, you will see that `System.Core.dll` and `System.dll` have also been loaded into memory, as they are required for the LINQ to Objects API:

```
***** Here are the assemblies loaded in DefaultAppDomainApp.exe *****
```

```
-> Name: DefaultAppDomainApp
-> Version: 1.0.0.0

-> Name: mscorlib
-> Version: 4.0.0.0

-> Name: System
-> Version: 4.0.0.0
```

```
-> Name: System.Core
-> Version: 4.0.0.0
```

Receiving Assembly Load Notifications

If you wish to be informed by the CLR when a new assembly has been loaded into a given application domain, you may handle the `AssemblyLoad` event. This event is typed against the `AssemblyLoadEventHandler` delegate, which can point to any method taking a `System.Object` as the first parameter, and an `AssemblyLoadEventArgs` as the second.

Let's add one final method to the current `Program` class called `InitDAD()`. As the name suggests, this method will initialize the default application domain, specifically by handling the `AssemblyLoad` event via a fitting lambda expression:

```
private static void InitDAD()
{
    // This logic will print out the name of any assembly
    // loaded into the application domain, after it has been
    // created.
    AppDomain defaultAD = AppDomain.CurrentDomain;
    defaultAD.AssemblyLoad += (o, s) =>
    {
        Console.WriteLine("{0} has been loaded!", s.LoadedAssembly.GetName().Name);
    };
}
```

As you would expect, when you run the modified application, you will be notified when a new assembly has been loaded. Here, you are simply printing out the friendly name of the assembly, using the `LoadedAssembly` property of the incoming `AssemblyLoadEventArgs` parameter.

Source Code The `DefaultAppDomainApp` project is included under the Chapter 16 subdirectory.

Creating New Application Domains

Recall that a single process is capable of hosting multiple application domains via the static `AppDomain.CreateDomain()` method. While creating new app domains on the fly is a rather infrequent task for most .NET applications, it is important to understand the basics of doing so. For example, as you will see later in this text, when you build *dynamic assemblies* (see Chapter 17) you will need to install them into a custom app domain. As well, several .NET security APIs require you to understand how to construct new app domains to isolate assemblies based on supplied security credentials.

To investigate how to create new application domains on the fly (and how to load new assemblies into these custom homes), create a new Console Application named `CustomAppDomains`. The `AppDomain.CreateDomain()` method has been overloaded a number of times. At minimum, you will specify the friendly name of the new application domain to be constructed. Update your `Program` class with the following code: Here, you are leveraging the `ListAllAssembliesInAppDomain()` method from the previous example, however this time you are passing in the `AppDomain` object to analyze as an incoming argument:

```

class Program
{
    static void Main(string[] args)
    {
        Console.WriteLine("***** Fun with Custom App Domains *****\n");

        // Show all loaded assemblies in default app domain.
        AppDomain defaultAD = AppDomain.CurrentDomain;
        ListAllAssembliesInAppDomain(defaultAD);

        // Make a new app domain.
        MakeNewAppDomain();
        Console.ReadLine();
    }

    private static void MakeNewAppDomain()
    {
        // Make a new AppDomain in the current process and
        // list loaded assemblies.
        AppDomain newAD = AppDomain.CreateDomain("SecondAppDomain");
        ListAllAssembliesInAppDomain(newAD);
    }

    static void ListAllAssembliesInAppDomain(AppDomain ad)
    {
        // Now get all loaded assemblies in the default app domain.
        var loadedAssemblies = from a in ad.GetAssemblies()
                               orderby a.GetName().Name select a;

        Console.WriteLine("***** Here are the assemblies loaded in {0} *****",
                          ad.FriendlyName);
        foreach (var a in loadedAssemblies)
        {
            Console.WriteLine("-> Name: {0}", a.GetName().Name);
            Console.WriteLine("-> Version: {0}\n", a.GetName().Version);
        }
    }
}

```

If you run the current example, you will see that the default application domain (`CustomAppDomains.exe`) has loaded `mscorlib.dll`, `System.dll`, `System.Core.dll` and `CustomAppDomains.exe`, given the C# code base of the current project. However, the new application domain only contains `mscorlib.dll`, which as you recall is the one .NET assembly which is always loaded by the CLR for each and every application domain:

```

***** Fun with Custom App Domains *****

***** Here are the assemblies loaded in CustomAppDomains.exe *****

```

```

-> Name: CustomAppDomains
-> Version: 1.0.0.0

-> Name: mscorelib
-> Version: 4.0.0.0

-> Name: System
-> Version: 4.0.0.0

-> Name: System.Core
-> Version: 4.0.0.0

***** Here are the assemblies loaded in SecondAppDomain *****

-> Name: mscorelib
-> Version: 4.0.0.0

```

Note If you debug this project (via F5), you will find many additional assemblies are loaded into each AppDomain which are used by the Visual Studio debugging process. Running this project (via Ctrl + F5) will display only the assemblies directly by each app domain.

This may seem counterintuitive if you have a background in traditional Windows (as you might suspect, both application domains have access to the same assembly set). Recall, however, that an assembly loads into an *application domain*, not directly into the process itself.

Loading Assemblies into Custom Application Domains

The CLR will always load assemblies into the default application domain when required. However, if you do ever manually create new app domains, you can load assemblies into said app domain using the `AppDomain.Load()` method. Also, be aware that the `AppDomain.ExecuteAssembly()` method can be called to load an *.exe assembly and execute the `Main()` method.

Assume that you wish to load `CarLibrary.dll` into your new secondary app domain. Provided you have copied this library to the `\bin\Debug` folder of the current application you could update the `MakeNewAppDomain()` method as so (be sure to import the `System.IO` namespace, to gain access to the `FileNotFoundException` class):

```

private static void MakeNewAppDomain()
{
    // Make a new AppDomain in the current process.
    AppDomain newAD = AppDomain.CreateDomain("SecondAppDomain");

    try
    {
        // Now load CarLibrary.dll into this new domain.

```

```
    newAD.Load("CarLibrary");
}
catch (FileNotFoundException ex)
{
    Console.WriteLine(ex.Message);
}

// List all assemblies.
ListAllAssembliesInAppDomain(newAD);
}
```

This time, the output of the program would appear as so (note the presence of `CarLibrary.dll`):

```
***** Fun with Custom App Domains *****

***** Here are the assemblies loaded in CustomAppDomains.exe *****

-> Name: CustomAppDomains
-> Version: 1.0.0.0

-> Name: mscorlib
-> Version: 4.0.0.0

-> Name: System
-> Version: 4.0.0.0

-> Name: System.Core
-> Version: 4.0.0.0

***** Here are the assemblies loaded in SecondAppDomain *****

-> Name: CarLibrary
-> Version: 2.0.0.0

-> Name: mscorlib
-> Version: 4.0.0.0
```

■ **Note** Remember! If you debug this application, you will see many additional libraries loaded into each application domain.

Programmatically Unloading AppDomains

It is important to point out that the CLR does not permit unloading individual .NET assemblies. However, using the `AppDomain.Unload()` method, you are able to selectively unload a given application domain from its hosting process. When you do so, the application domain will unload each assembly in turn.

Recall that the `AppDomain` type defines the `DomainUnload` event, which is fired when a custom application domain is unloaded from the containing process. Another event of interest is the `ProcessExit` event, which is fired when the default application domain is unloaded from the process (which obviously entails the termination of the process itself).

If you wish to programmatically unload `newAD` from the hosting process, and be notified when the associated application domain is torn down, you could update `MakeNewAppDomain()` with the following additional logic:

```
private static void MakeNewAppDomain()
{
    // Make a new AppDomain in the current process.
    AppDomain newAD = AppDomain.CreateDomain("SecondAppDomain");
    newAD.DomainUnload += (o, s) =>
    {
        Console.WriteLine("The second app domain has been unloaded!");
    };

    try
    {
        // Now load CarLibrary.dll into this new domain.
        newAD.Load("CarLibrary");
    }
    catch (FileNotFoundException ex)
    {
        Console.WriteLine(ex.Message);
    }

    // List all assemblies.
    ListAllAssembliesInAppDomain(newAD);

    // Now tear down this app domain.
    AppDomain.Unload(newAD);
}
```

If you wish to be notified when the default application domain is unloaded, modify your `Main()` method to handle the `ProcessEvent` event of the default application domain:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Custom App Domains *****\n");

    // Show all loaded assemblies in default app domain.
    AppDomain defaultAD = AppDomain.CurrentDomain;
    defaultAD.ProcessExit += (o, s) =>
    {
        Console.WriteLine("Default AD unloaded!");
    };

    ListAllAssembliesInAppDomain(defaultAD);

    MakeNewAppDomain();
    Console.ReadLine();
```

```
}
```

That wraps up our look at the .NET application domain. To conclude this chapter, let's look at one further level of partitioning, which is used to group objects into contextual boundaries.

■ **Source Code** The CustomAppDomains project is included under the Chapter 16 subdirectory.

Understanding Object Context Boundaries

As you have just seen, AppDomains are logical partitions within a process used to host .NET assemblies. On a related note, a given application domain may be further subdivided into numerous context boundaries. In a nutshell, a .NET context provides a way for a single AppDomain to establish a “specific home” for a given object.

■ **Note** Friendly FYI, while understanding processes and application domains is quite important, most .NET applications will never demand that you work with object contexts. I've included this material just to paint a more complete picture.

Using context, the CLR is able to ensure that objects that have special runtime requirements are handled in an appropriate and consistent manner by intercepting method invocations into and out of a given context. This layer of interception allows the CLR to adjust the current method invocation to conform to the contextual settings of a given object. For example, if you define a C# class type that requires automatic thread safety (using the [Synchronization] attribute), the CLR will create a “synchronized context” during allocation.

Just as a process defines a default AppDomain, every application domain has a default context. This default context (sometimes referred to as *context 0*, given that it is always the first context created within an application domain) is used to group together .NET objects that have no specific or unique contextual needs. As you may expect, a vast majority of .NET objects are loaded into context 0. If the CLR determines a newly created object has special needs, a new context boundary is created within the hosting application domain. Figure 16-3 illustrates the process/AppDomain/context relationship.




Figure 16-3. Processes, application domains, and context boundaries

Context-Agile and Context-Bound Types

.NET objects that do not demand any special contextual treatment are termed *context-agile* objects. These objects can be accessed from anywhere within the hosting AppDomain without interfering with the object's runtime requirements. Building context-agile objects is very easy, given that you simply do nothing (specifically, you do not adorn the type with any contextual attributes and do not derive from the `System.ContextBoundObject` base class):

```
// A context-agile object is loaded into context zero.
class SportsCar{}
```

On the other hand, objects that do demand contextual allocation are termed *context-bound* objects, and they *must* derive from the `System.ContextBoundObject` base class. This base class solidifies the fact that the object in question can function appropriately only within the context in which it was created. Given the role of .NET context, it should stand to reason that if a context-bound object were to somehow end up in an incompatible context, bad things would be guaranteed to occur at the most inopportune times.

In addition to deriving from `System.ContextBoundObject`, a context-sensitive type will also be adorned by a special category of .NET attributes termed (not surprisingly) *context attributes*. All context attributes derive from the `ContextAttribute` base class. Let's see an example.

Defining a Context-Bound Object

Assume that you wish to define a class (`SportsCarTS`) that is automatically thread safe in nature, even though you have not hard-coded thread synchronization logic within the member implementations. To do so, derive from `ContextBoundObject` and apply the `[Synchronization]` attribute as follows:

```
using System.Runtime.Remoting.Contexts;

// This context-bound type will only be loaded into a
// synchronized (hence thread-safe) context.
```

```
[Synchronization]
class SportsCarTS : ContextBoundObject
{}
```

Types that are attributed with the [Synchronization] attribute are loaded into a thread-safe context. Given the special contextual needs of the SportsCarTS class type, imagine the problems that would occur if an allocated object were moved from a synchronized context into a nonsynchronized context. The object is suddenly no longer thread safe and thus becomes a candidate for massive data corruption, as numerous threads are attempting to interact with the (now thread-volatile) reference object. To ensure the CLR does not move SportsCarTS objects outside of a synchronized context, simply derive from ContextBoundObject.

Inspecting an Object's Context

Although very few of the applications you will write will need to programmatically interact with context, here is an illustrative example. Create a new Console Application named ObjectContextApp. This application defines one context-agile class (SportsCar) and a single context-bound type (SportsCarTS):

```
using System;
using System.Runtime.Remoting.Contexts; // For Context type.
using System.Threading; // For Thread type.

// SportsCar has no special contextual
// needs and will be loaded into the
// default context of the app domain.
class SportsCar
{
    public SportsCar()
    {
        // Get context information and print out context ID.
        Context ctx = Thread.CurrentContext;
        Console.WriteLine("{0} object in context {1}",
            this.ToString(), ctx.ContextID);
        foreach(IContextProperty itfCtxProp in ctx.ContextProperties)
            Console.WriteLine("-> Ctx Prop: {0}", itfCtxProp.Name);
    }
}

// SportsCarTS demands to be loaded in
// a synchronization context.
[Synchronization]
class SportsCarTS : ContextBoundObject
{
    public SportsCarTS()
    {
        // Get context information and print out context ID.
        Context ctx = Thread.CurrentContext;
        Console.WriteLine("{0} object in context {1}",
            this.ToString(), ctx.ContextID);
        foreach(IContextProperty itfCtxProp in ctx.ContextProperties)
            Console.WriteLine("-> Ctx Prop: {0}", itfCtxProp.Name);
    }
}
```

```
    }
}
```

Notice that each constructor obtains a `Context` object from the current thread of execution, via the static `Thread.CurrentContext` property. Using the `Context` object, you are able to print out statistics about the contextual boundary, such as its assigned ID, as well as a set of descriptors obtained via `Context.ContextProperties`. This property returns an array of objects implementing the `IContextProperty` interface, which exposes each descriptor through the `Name` property. Now, update `Main()` to allocate an instance of each class type:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Object Context *****\n");

    // Objects will display contextual info upon creation.
    SportsCar sport = new SportsCar();
    Console.WriteLine();

    SportsCar sport2 = new SportsCar();
    Console.WriteLine();

    SportsCarTS synchroSport = new SportsCarTS();
    Console.ReadLine();
}
```

As the objects come to life, the class constructors will dump out various bits of context-centric information (the "lease life time service property" printout is a low level aspect of the .NET remoting layer, and can be ignored):

```
***** Fun with Object Context *****

ObjectContextApp.SportsCar object in context 0
-> Ctx Prop: LeaseLifeTimeServiceProperty

ObjectContextApp.SportsCar object in context 0
-> Ctx Prop: LeaseLifeTimeServiceProperty

ObjectContextApp.SportsCarTS object in context 1
-> Ctx Prop: LeaseLifeTimeServiceProperty
-> Ctx Prop: Synchronization
```

Given that the `SportsCar` class has not been qualified with a context attribute, the CLR has allocated `sport` and `sport2` into context 0 (i.e., the default context). However, the `SportsCarTS` object is loaded into a unique contextual boundary (which has been assigned a context ID of 1), given the fact that this context-bound type was adorned with the `[Synchronization]` attribute.

■ Source Code The `ObjectContextApp` project is included under the Chapter 16 subdirectory.

Summarizing Processes, AppDomains, and Context

At this point, you hopefully have a much better idea about how a .NET assembly is hosted by the CLR. To summarize the key points:

- A .NET process hosts one to many application domains. Each AppDomain is able to host any number of related .NET assemblies. AppDomains may be independently loaded and unloaded by the CLR (or programmatically via the `System.AppDomain` type).
- A given AppDomain consists of one to many contexts. Using a context, the CLR is able to place a “special needs” object into a logical container, to ensure that its runtime requirements are honored.

If the previous pages have seemed to be a bit too low level for your liking, fear not. For the most part, the .NET runtime automatically deals with the details of processes, application domains, and contexts on your behalf. The good news, however, is that this information provides a solid foundation for understanding multithreaded programming under the .NET platform.

Summary

The point of this chapter was to examine exactly how a .NET-executable image is hosted by the .NET platform. As you have seen, the long-standing notion of a Windows process has been altered under the hood to accommodate the needs of the CLR. A single process (which can be programmatically manipulated via the `System.Diagnostics.Process` type) is now composed of one or more application domains, which represent isolated and independent boundaries within a process.

As you have seen, a single process can host multiple application domains, each of which is capable of hosting and executing any number of related assemblies. Furthermore, a single application domain can contain any number of contextual boundaries. Using this additional level of type isolation, the CLR can ensure that special-need objects are handled correctly.



Understanding CIL and the Role of Dynamic Assemblies

When you are building a full-scale .NET application, you will most certainly make use of C# (or a similar managed language such as Visual Basic), given their inherent productivity and ease of use. However, as you learned in the very first chapter, the role of a managed compiler is to translate *.cs code files into terms of CIL code, type metadata and an assembly manifest. As it turns out, CIL is a full-fledged .NET programming language, with its own syntax, semantics, and compiler (`ilasm.exe`).

In this chapter, you will be given a tour of .NET's mother tongue. Here you will understand the distinction between a CIL *directive*, CIL *attribute*, and CIL *opcode*. You will then learn about the role of round-trip engineering of a .NET assembly and various CIL programming tools. The remainder of the chapter will then walk you through the basics of defining namespaces, types, and members using the grammar of CIL. We wrap up with an examination of the role of the `System.Reflection.Emit` namespace and examine how it is possible to construct an assembly (with CIL instructions) dynamically at runtime.

Of course, few programmers will ever need to work with raw CIL code on a day-to-day basis. Therefore, I will start up this chapter by examining a few reasons why getting to know the syntax and semantics of this low-level .NET language might be worth your while.

Reasons for Learning the Grammar of CIL

CIL is the true mother tongue of the .NET platform. When you build a .NET assembly using your managed language of choice (C#, VB, F#, COBOL.NET, etc.), the associated compiler translates your source code into terms of CIL. Like any programming language, CIL provides numerous structural and implementation-centric tokens. Given that CIL is just another .NET programming language, it should come as no surprise that it is possible to build your .NET assemblies directly using CIL and the CIL compiler (`ilasm.exe`) that ships with the .NET Framework 4.0 SDK.

Now while it is true that few programmers would choose to build an entire .NET application directly with CIL, CIL is still an extremely interesting intellectual pursuit. Simply put, the more you understand the grammar of CIL, the better able you are to move into the realm of advanced .NET development. By way of some concrete examples, individuals who possess an understanding of CIL are capable of the following:

- Talking intelligently about how different .NET programming languages map their respective keywords to CIL tokens.
- Disassembling an existing .NET assembly, editing the CIL code, and recompiling the updated code base into a modified .NET binary. For example, there are some scenarios where you might need to modify CIL in order to interoperate with some advanced COM features.

- Building dynamic assemblies using the `System.Reflection.Emit` namespace. This API allows you to generate an in-memory .NET assembly, which can optionally be persisted to disk.
- Leveraging aspects of the CTS that are not supported by higher-level managed languages, but do exist at the level of CIL. To be sure, CIL is the only .NET language that allows you to access each and every aspect of the CTS. For example, using raw CIL, you are able to define global-level members and fields (which are not permissible in C#).

Again, to be perfectly clear, if you choose *not* to concern yourself with the details of CIL code, you are absolutely able to gain mastery of C# and the .NET base class libraries. In many ways, knowledge of CIL is analogous to a C(++) programmer's understanding of assembly language. Those who know the ins and outs of the low-level "goo" are able to create rather advanced solutions for the task at hand and gain a deeper understanding of the underlying programming (and runtime) environment. So, if you are up for the challenge, let's begin to examine the details of CIL.

Note Understand that this chapter is not intended to be a comprehensive treatment of the syntax and semantics of CIL. If you require a full examination of the topic, I'd recommend downloading the official ECMA specification ([ecma-335.pdf](http://www.ecma-international.org)) from the ECMA International web site (<http://www.ecma-international.org>).

Examining CIL Directives, Attributes, and Opcodes

When you begin to investigate low-level languages such as CIL, you are guaranteed to find new (and often intimidating-sounding) names for very familiar concepts. For example, at this point in the text, if you were shown the following set of items

```
{new, public, this, base, get, set, explicit, unsafe, enum, operator, partial}
```

you would most certainly understand them to be keywords of the C# language (which is correct). However, if you look more closely at the members of this set, you may be able to see that while each item is indeed a C# keyword, it has radically different semantics. For example, the `enum` keyword defines a `System.Enum`-derived type, while the `this` and `base` keywords allow you to reference the current object or the object's parent class, respectively. The `unsafe` keyword is used to establish a block of code that cannot be directly monitored by the CLR, while the `operator` keyword allows you to build a hidden (specially named) method that will be called when you apply a specific C# operator (such as the plus sign).

In stark contrast to a higher-level language such as C#, CIL does not just simply define a general set of keywords, *per se*. Rather, the token set understood by the CIL compiler is subdivided into three broad categories based on semantics:

- CIL directives
- CIL attributes
- CIL operation codes (opcodes)

Each category of CIL token is expressed using a particular syntax, and the tokens are combined to build a valid .NET assembly.

The Role of CIL Directives

First up, there is a set of well-known CIL tokens that are used to describe the overall structure of a .NET assembly. These tokens are called *directives*. CIL directives are used to inform the CIL compiler how to define the namespaces(s), type(s), and member(s) that will populate an assembly.

Directives are represented syntactically using a single dot (.) prefix (e.g., .namespace, .class, .publickeytoken, .method, .assembly, etc.). Thus, if your *.il file (the conventional extension for a file containing CIL code) has a single .namespace directive and three .class directives, the CIL compiler will generate an assembly that defines a single .NET namespace containing three .NET class types.

The Role of CIL Attributes

In many cases, CIL directives in and of themselves are not descriptive enough to fully express the definition of a given .NET type or type member. Given this fact, many CIL directives can be further specified with various CIL *attributes* to qualify how a directive should be processed. For example, the .class directive can be adorned with the public attribute (to establish the type visibility), the extends attribute (to explicitly specify the type's base class), and the implements attribute (to list the set of interfaces supported by the type).

Note Don't confuse a ".NET attribute" (see Chapter 15) with that of a "CIL attribute," the two are very different concepts.

The Role of CIL Opcodes

Once a .NET assembly, namespace, and type set have been defined in terms of CIL using various directives and related attributes, the final remaining task is to provide the type's implementation logic. This is a job for *operation codes*, or simply *opcodes*. In the tradition of other low-level languages, many CIL opcodes tend to be cryptic and completely unpronounceable by us mere humans. For example, if you need to load a string variable into memory, you don't use a friendly opcode named LoadString, but rather ldstr.

Now, to be fair, some CIL opcodes do map quite naturally to their C# counterparts (e.g., box, unbox, throw, and sizeof). As you will see, the opcodes of CIL are always used within the scope of a member's implementation, and unlike CIL directives, they are never written with a dot prefix.

The CIL Opcode/CIL Mnemonic Distinction

As just explained, opcodes such as ldstr are used to implement the members of a given type. In reality, however, tokens such as ldstr are *CIL mnemonics* for the actual *binary CIL opcodes*. To clarify the distinction, assume you have authored the following method in C#:

```
static int Add(int x, int y)
```

```
{
    return x + y;
}
```

The act of adding two numbers is expressed in terms of the CIL opcode 0X58. In a similar vein, subtracting two numbers is expressed using the opcode 0X59, and the act of allocating a new object on the managed heap is achieved using the 0X73 opcode. Given this reality, understand that the “CIL code” processed by a JIT compiler is actually nothing more than blobs of binary data.

Thankfully, for each binary opcode of CIL, there is a corresponding mnemonic. For example, the add mnemonic can be used rather than 0X58, sub rather than 0X59, and newobj rather than 0X73. Given this opcode/mnemonic distinction, realize that CIL decompilers such as ildasm.exe translate an assembly’s binary opcodes into their corresponding CIL mnemonics. For example, here would be the CIL presented by ildasm.exe for the previous C# Add() method:

```
.method private hidebysig static int32 Add(int32 x,
    int32 y) cil managed
{
    // Code size     9 (0x9)
    .maxstack 2
    .locals init ([0] int32 CS$1$0000)
    IL_0000: nop
    IL_0001: ldarg.0
    IL_0002: ldarg.1
    IL_0003: add
    IL_0004: stloc.0
    IL_0005: br.s    IL_0007
    IL_0007: ldloc.0
    IL_0008: ret
}
```

Unless you’re building some extremely low-level .NET software (such as a custom managed compiler), you’ll never need to concern yourself with the literal numeric binary opcodes of CIL. For all practical purposes, when .NET programmers speak about “CIL opcodes” they’re referring to the set of friendly string token mnemonics (as I’ve done within this text, and will do for the remainder of this chapter) rather than the underlying numerical values.

Pushing and Popping: The Stack-Based Nature of CIL

Higher-level .NET languages (such as C#) attempt to hide low-level CIL grunge from view as much as possible. One aspect of .NET development that is particularly well hidden is the fact that CIL is a stack-based programming language. Recall from the examination of the collection namespaces (see Chapter 10) that the `Stack<T>` class can be used to push a value onto a stack as well as pop the topmost value off of the stack for use. Of course, CIL developers do not literally use an object of type `Stack<T>` to load and unload the values to be evaluated; however, the same pushing and popping mind-set still applies.

Formally speaking, the entity used to hold a set of values to be evaluated is termed the *virtual execution stack*. As you will see, CIL provides a number of opcodes that are used to push a value onto the stack; this process is termed *loading*. As well, CIL defines a number of additional opcodes that transfer the topmost value on the stack into memory (such as a local variable) using a process termed *storing*.

In the world of CIL, it is impossible to access a point of data directly, including locally defined variables, incoming method arguments, or field data of a type. Rather, you are required to explicitly load the item onto the stack, only to then pop it off for later use (keep this point in mind, as it will help explain why a given block of CIL code can look a bit redundant).

Note Recall that CIL is not directly executed, but compiled on demand. During the compilation of CIL code, many of these implementation redundancies are optimized away. Furthermore, if you enable the code optimization option for your current project (using the Build tab of the Visual Studio Project Properties window), the compiler will also remove various CIL redundancies.

To understand how CIL leverages a stack-based processing model, consider a simple C# method, `PrintMessage()`, which takes no arguments and returns `void`. Within the implementation of this method, you will simply print out the value of a local string variable to the standard output stream:

```
public void PrintMessage()
{
    string myMessage = "Hello.";
    Console.WriteLine(myMessage);
}
```

If you were to examine how the C# compiler translates this method in terms of CIL, you would first find that the `PrintMessage()` method defines a storage slot for a local variable using the `.locals` directive. The local string is then loaded and stored in this local variable using the `ldstr` (load string) and `stloc.0` opcodes (which can be read as “store the current value in a local variable at storage slot zero”).

The value (again, at index 0) is then loaded into memory using the `ldloc.0` (“load the local argument at index 0”) opcode for use by the `System.Console.WriteLine()` method invocation (specified using the `call` opcode). Finally, the function returns via the `ret` opcode. Here is the (annotated) CIL code for the `PrintMessage()` method:

```
.method public hidebysig instance void PrintMessage() cil managed
{
    .maxstack 1
    // Define a local string variable (at index 0).
    .locals init ([0] string myMessage)

    // Load a string on to the stack with the value "Hello."
    ldstr "Hello."

    // Store string value on the stack in the local variable.
    stloc.0

    // Load the value at index 0.
    ldloc.0

    // Call method with current value.
    call void [mscorlib]System.Console::WriteLine(string)
```

```
    ret
}
```

Note As you can see, CIL supports code comments using the double-slash syntax (as well as the /*...*/ syntax, for that matter). As in C#, code comments are completely ignored by the CIL compiler.

Now that you have the basics of CIL directives, attributes, and opcodes, let's see a practical use of CIL programming, beginning with the topic of round-trip engineering.

Understanding Round-Trip Engineering

You are aware of how to use `ildasm.exe` to view the CIL code generated by the C# compiler (see Chapter 1). What you may not know, however, is that `ildasm.exe` allows you to dump the CIL contained within an assembly loaded into `ildasm.exe` to an external file. Once you have the CIL code at your disposal, you are free to edit and recompile the code base using the CIL compiler, `ilasm.exe`.

Note Also recall that `reflector.exe` can be used to view the CIL code of a given assembly, as well as to translate the CIL code into an approximate C# code base.

Formally speaking, this technique is termed *round-trip engineering*, and it can be useful under a number of circumstances:

- You need to modify an assembly for which you no longer have the source code.
- You are working with a less-than-perfect .NET language compiler that has emitted ineffective (or flat-out incorrect) CIL code, and you wish to modify the code base.
- You are constructing a COM interoperability assemblies and wish to account for some COM IDL attributes that have been lost during the conversion process (such as the COM [helpstring] attribute).

To illustrate the process of round-tripping, begin by creating a new C# code file (`HelloProgram.cs`) using a simple text editor, and define the following class type (you are free to create a new Console Application project using Visual Studio 2010 if you wish. However, be sure to delete the `AssemblyInfo.cs` file to decrease the amount of generated CIL code):

```
// A simple C# console app.
using System;

// Note that we are not wrapping our class in a namespace,
// to help simplify the generated CIL code.
class Program
```

```
{
    static void Main(string[] args)
    {
        Console.WriteLine("Hello CIL code!");
        Console.ReadLine();
    }
}
```

Save your file to a convenient location (for example, C:\RoundTrip) and compile your program using `csc.exe`:

```
csc HelloProgram.cs
```

Now, open `HelloProgram.exe` with `ildasm.exe` and, using the File ▶ Dump menu option, save the raw CIL code to a new `*.il` file (`HelloProgram.il`) in the same folder containing your compiled assembly (all of the default values of the resulting dialog box are fine as is).

Note `ildasm.exe` will also generate a `*.res` file when dumping the contents of an assembly to file. These resource files can be ignored (and deleted) throughout this chapter, as you will not be making use of them.

Now you are able to view this file using your text editor of choice. Here is the (slightly reformatted and annotated) result:

```
// Referenced Assemblies.
.assembly extern mscorlib
{
    .publickeytoken = (B7 7A 5C 56 19 34 E0 89 )
    .ver 4:0:0:0
}

// Our assembly.
.assembly HelloProgram
{
    /**** TargetFrameworkAttribute data removed for clarity! ****/
    .hash algorithm 0x00008004
    .ver 0:0:0:0
}
.module HelloProgram.exe
.imagebase 0x00400000
.file alignment 0x00000200
.stackreserve 0x00100000
.subsystem 0x0003
.corflags 0x00000003

// Definition of Program class.
.class private auto ansi beforefieldinit Program
```

```

    extends [mscorlib]System.Object
{
    .method private hidebysig static void Main(string[] args) cil managed
    {
        // Marks this method as the entry point of the
        // executable.
        .entrypoint
        .maxstack 8
        IL_0000: nop
        IL_0001: ldstr "Hello CIL code!"
        IL_0006: call void [mscorlib]System.Console::WriteLine(string)
        IL_000b: nop
        IL_000c: call string [mscorlib]System.Console::ReadLine()
        IL_0011: pop
        IL_0012: ret
    }

    // The default constructor.
    .method public hidebysig specialname rtspecialname
        instance void .ctor() cil managed
    {
        .maxstack 8
        IL_0000: ldarg.0
        IL_0001: call instance void [mscorlib]System.Object:::.ctor()
        IL_0006: ret
    }
}

```

First, notice that the *.il file opens by declaring each externally referenced assembly the current assembly is compiled against. Here, you can see a single `.assembly extern` token set for the always present `mscorlib.dll`. Of course, if your class library made use of types within other referenced assemblies, you would find additional `.assembly extern` directives.

Next, you find the formal definition of your `HelloProgram.exe` assembly, which has been assigned a default version of `0.0.0.0` (given that you did not specify a value using the `[AssemblyVersion]` attribute). The assembly is further described using various CIL directives (such as `.module`, `.imagebase`, and so forth).

After documenting the externally referenced assemblies and defining the current assembly, you find a definition of the `Program` type. Note that the `.class` directive has various attributes (many of which are actually optional) such as `extends`, which marks the base class of the type:

```

.class private auto ansi beforefieldinit Program
    extends [mscorlib]System.Object
{ ... }

```

The bulk of the CIL code represents the implementation of the class's default constructor and the `Main()` method, both of which are defined (in part) with the `.method` directive. Once the members have been defined using the correct directives and attributes, they are implemented using various opcodes.

It is critical to understand that when interacting with .NET types (such as `System.Console`) in CIL, you will *always* need to use the type's fully qualified name. Furthermore, the type's fully qualified name must *always* be prefixed with the friendly name of the defining assembly (in square brackets). Consider the CIL implementation of `Main()`:

```
.method private hidebysig static void Main(string[] args) cil managed
{
    .entrypoint
    .maxstack 8
    IL_0000: nop
    IL_0001: ldstr "Hello CIL code!"
    IL_0006: call void [mscorlib]System.Console::WriteLine(string)
    IL_000b: nop
    IL_000c: call string [mscorlib]System.Console::ReadLine()
    IL_0011: pop
    IL_0012: ret
}
```

The implementation of the default constructor in terms of CIL code makes use of yet another “load-centric” instruction (`ldarg.0`). In this case, the value loaded onto the stack is not a custom variable specified by you, but the current object reference (more details on this later). Also note that the default constructor explicitly makes a call to the base class constructor, which in this case is your good friend `System.Object`:

```
.method public hidebysig specialname rtspecialname
    instance void .ctor() cil managed
{
    .maxstack 8
    IL_0000: ldarg.0
    IL_0001: call instance void [mscorlib]System.Object::..ctor()
    IL_0006: ret
}
```

The Role of CIL Code Labels

One thing you certainly have noticed is that each line of implementation code is prefixed with a token of the form `IL_XXX:` (e.g., `IL_0000:`, `IL_0001:`, and so on). These tokens are called *code labels* and may be named in any manner you choose (provided they are not duplicated within the same member scope). When you dump an assembly to file using `ildasm.exe`, it will automatically generate code labels that follow an `IL_XXX:` naming convention. However, you may change them to reflect a more descriptive marker:

```
.method private hidebysig static void Main(string[] args) cil managed
{
    .entrypoint
    .maxstack 8
    Nothing_1: nop
    Load_String: ldstr "Hello CIL code!"
    PrintToConsole: call void [mscorlib]System.Console::WriteLine(string)
    Nothing_2: nop
    WaitFor_KeyPress: call string [mscorlib]System.Console::ReadLine()
    RemoveValueFromStack: pop
    Leave_Function: ret
}
```

The truth of the matter is that most code labels are completely optional. The only time code labels are truly mandatory is when you are authoring CIL code that makes use of various branching or looping constructs, as you can specify where to direct the flow of logic via these code labels. For the current example, you can remove these autogenerated labels altogether with no ill effect:

```
.method private hidebysig static void Main(string[] args) cil managed
{
    .entrypoint
    .maxstack 8
    nop
    ldstr "Hello CIL code!"
    call void [mscorlib]System.Console::WriteLine(string)
    nop
    call string [mscorlib]System.Console::ReadLine()
    pop
    ret
}
```

Interacting with CIL: Modifying an *.il File

Now that you have a better understanding of how a basic CIL file is composed, let's complete the round-tripping experiment. The goal here is to update the CIL within the existing *.il file as follows:

- Add a reference to the `System.Windows.Forms.dll` assembly.
- Load a local string within `Main()`.
- Call the `System.Windows.Forms.MessageBox.Show()` method using the local string variable as an argument.

The first step is to add a new `.assembly` directive (qualified with the `extern` attribute) that specifies your assembly requires the `System.Windows.Forms.dll` assembly. To do so, update the *.il file with the following logic after the external reference to `mscorlib`:

```
.assembly extern System.Windows.Forms
{
    .publickeytoken = (B7 7A 5C 56 19 34 E0 89)
    .ver 4:0:0:0
}
```

Be aware that the value assigned to the `.ver` directive may differ depending on which version of the .NET platform you have installed on your development machine. Here, you see that `System.Windows.Forms.dll` version 4.0.0.0 is used and has the public key token of B77A5C561934E089. If you open the GAC (see Chapter 14) and locate your version of the `System.Windows.Forms.dll` assembly, you can simply copy the correct version and public key token value.

Next, you need to alter the current implementation of the `Main()` method. Locate this method within the *.il file and remove the current implementation code (the `.maxstack` and `.entrypoint` directives should remain intact):

```
.method private hidebysig static void Main(string[] args) cil managed
```

```
{
    .entrypoint
    .maxstack 8
    // ToDo: Write new CIL code!
}
```

Again, the goal here is to push a new string onto the stack and call the `MessageBox.Show()` method (rather than the `Console.WriteLine()` method). Recall that when you specify the name of an external type, you must make use of the type's fully qualified name (in conjunction with the friendly name of the assembly). Also notice that in terms of CIL, every method call documents the fully qualified return type. Keeping these things in mind, update the `Main()` method as follows:

```
.method private hidebysig static void Main(string[] args) cil managed
{
    .entrypoint
    .maxstack 8

    ldstr "CIL is way cool"
    call valuetype [System.Windows.Forms]
        System.Windows.Forms.DialogResult
        [System.Windows.Forms]
        System.Windows.Forms.MessageBox::Show(string)
    pop
    ret
}
```

In effect, you have just updated the CIL code to correspond to the following C# class definition:

```
class Program
{
    static void Main(string[] args)
    {
        System.Windows.Forms.MessageBox.Show("CIL is way cool");
    }
}
```

Compiling CIL Code Using ilasm.exe

Assuming you have saved this modified `*.il` file, you can compile a new .NET assembly using the `ilasm.exe` (CIL compiler) utility. While the CIL compiler has numerous command-line options (all of which can be seen by specifying the `-?` option), Table 17-1 shows the core flags of interest.

Table 17-1. Common `ilasm.exe` Command-Line Flags

Flag	Meaning in Life
<code>/debug</code>	Includes debug information (such as local variable and argument names, as well as line numbers).
<code>/dll</code>	Produces a <code>*.dll</code> file as output.

Table 17-1. Common *ilasm.exe* Command-Line Flags (continued)

Flag	Meaning in Life
/exe	Produces an *.exe file as output. This is the default setting and may be omitted.
/key	Compiles the assembly with a strong name using a given *.snk file.
/output	Specifies the output file name and extension. If you do not make use of the /output flag, the resulting file name (minus the file extension) is the same as the name of the first source file.

To compile your updated `HelloProgram.il` file into a new .NET *.exe, you can issue the following command within a Visual Studio 2010 command prompt:

```
ilasm /exe HelloProgram.il /output=NewAssembly.exe
```

Assuming things have worked successfully, you will see the report shown here:

```
Microsoft (R) .NET Framework IL Assembler. Version 4.0.21006.1
Copyright (c) Microsoft Corporation. All rights reserved.
Assembling 'HelloProgram.il' to EXE --> 'NewAssembly.exe'
Source file is UTF-8

Assembled method Program::Main
Assembled method Program::ctor
Creating PE file

Emitting classes:
Class 1:      Program

Emitting fields and methods:
Global
Class 1 Methods: 2;

Emitting events and properties:
Global
Class 1
Writing PE file
Operation completed successfully
```

At this point, you can run your new application. Sure enough, rather than showing a message within the console window, you will now see a message box displaying your message. While the output of this simple example are not all that spectacular, it does illustrate one practical use of programming in CIL—round tripping.

Authoring CIL Code Using SharpDevelop

Back in Chapter 2, I made brief mention of the freely available SharpDevelop IDE (<http://www.sharpdevelop.com>). Beyond supplying a number of C# and VB project templates, when you access the File ▶ New Solution menu option, you will be happy to see one of your choices is to create a CIL project workspace (see Figure 17-1).




Figure 17-1. The SharpDevelop IDE CIL project template

While SharpDevelop does not have IntelliSense support for CIL projects, CIL tokens are color-coded, and you are able to compile and run your application directly within the IDE (rather than running ilasm.exe from a command prompt). When you create this project type, you will be given an initial *.il file looking like so (Figure 17-2).

 A screenshot of the SharpDevelop IDE CIL editor. The code editor window has 'MainClass.il' in the title bar. The code itself is:


```

1 .assembly HelloWorld
2 {
3 }

4 .namespace FunWithCILCode
5 {
6     .class private auto ansi beforefieldinit MainClass
7     {
8         .method public hidebysig static void Main(string[] args) cil managed
9         {
10             .entrypoint
11             .maxstack 1
12             ldstr    "Hello World!"
13             call     void [mscorlib]System.Console::WriteLine(string)
14             ret
15         }
16     }
17 }
18 }
```

Figure 17-2. The SharpDevelop IDE CIL editor

As you work through the remaining examples of this chapter, I'd recommend using SharpDevelop to author the CIL code. Beyond some color coding functionality, the CIL project workspace will also help you quickly locate the position of coding typos via the Errors window.

■ **Note** The MonoDevelop IDE, a free IDE for building .NET applications under the Mono platform, also supports a CIL project template. See Appendix B for details about MonoDevelop.

The Role of pverify.exe

When you are building or modifying assemblies using CIL code, it is always advisable to verify that the compiled binary image is a well-formed .NET image using the `pverify.exe` command-line tool:

```
pverify NewAssembly.exe
```

This tool will examine all opcodes within the specified assembly for valid CIL code. For example, in terms of CIL code, the evaluation stack must always be empty before exiting a function. If you forget to pop off any remaining values, the `ilasm.exe` compiler will still generate a compiled assembly (given that compilers are concerned only with *syntax*). `pverify.exe`, on the other hand, is concerned with *semantics*. If you did forget to clear the stack before exiting a given function, `pverify.exe` will let you know before you try running your code base.

■ **Source Code** The RoundTrip example is included under the Chapter 17 subdirectory.

Understanding CIL Directives and Attributes

Now that you have seen how `ildasm.exe` and `ilasm.exe` can be used to perform a round-trip, you can get down to the business of checking out the syntax and semantics of CIL itself. The next sections will walk you through the process of authoring a custom namespace containing a set of types. However, to keep things simple, these types will not contain any implementation logic for their members (yet). Once you understand how to create empty types, you can then turn your attention to the process of defining “real” members using CIL opcodes.

Specifying Externally Referenced Assemblies in CIL

Create a new file named `Ciltypes.il` using your editor of choice. The first task a CIL project will require is to list the set of external assemblies used by the current assembly. For this example, you will only make use of types found within `mscorlib.dll`. To do so, the `.assembly` directive will be qualified using the `external` attribute. When you are referencing a strongly named assembly, such as `mscorlib.dll`, you'll want to specify the `.publickeytoken` and `.ver` directives as well:

```
.assembly extern mscorel
{
    .publickeytoken = (B7 7A 5C 56 19 34 E0 89 )
    .ver 4:0:0:0
}
```

Note Strictly speaking, you are not required to explicitly reference `mscorlib.dll` as an external reference, as `ilasm.exe` will do so automatically. However, for each external .NET library your CIL project requires, you will need to author a similar `.assembly extern` directive.

Defining the Current Assembly in CIL

The next order of business is to define the assembly you are interested in building using the `.assembly` directive. At the simplest level, an assembly can be defined by specifying the friendly name of the binary:

```
// Our assembly.
.assembly CILTypes { }
```

While this indeed defines a new .NET assembly, you will typically place additional directives within the scope of the assembly declaration. For this example, update your assembly definition to include a version number of 1.0.0.0 using the `.ver` directive (note that each numerical identifier is separated by *colons*, not the C#-centric dot notation):

```
// Our assembly.
.assembly CILTypes
{
    .ver 1:0:0:0
}
```

Given that the `CILTypes` assembly is a single-file assembly, you will finish up the assembly -definition using a single `.module` directive, which marks the official name of your .NET binary, `CILTypes.dll`:

```
.assembly CILTypes
{
    .ver 1:0:0:0
}
// The module of our single-file assembly.
.module CILTypes.dll
```

In addition to `.assembly` and `.module` are CIL directives that further qualify the overall structure of the .NET binary you are composing. Table 17-2 lists a few of the more common assembly-level directives.

Table 17-2. Additional Assembly-Centric Directives

Directive	Meaning in Life
.mresources	If your assembly makes use of internal resources (such as bitmaps or string tables), this directive is used to identify the name of the file that contains the resources to be embedded.
.subsystem	This CIL directive is used to establish the preferred UI that the assembly wishes to execute within. For example, a value of 2 signifies that the assembly should run within a GUI application, whereas a value of 3 denotes a console executable.

Defining Namespaces in CIL

Now that you have defined the look and feel of your assembly (and the required external references), you can create a .NET namespace (`MyNamespace`) using the `.namespace` directive:

```
// Our assembly has a single namespace.
.namespace MyNamespace {}
```

Like C#, CIL namespace definitions can be nested within further namespaces. There is no need to define a root namespace here; however, for the sake of argument, assume you wish to create a root namespace named `MyCompany`:

```
.namespace MyCompany
{
    .namespace MyNamespace {}
}
```

Like C#, CIL allows you to define a nested namespace as follows:

```
// Defining a nested namespace.
.namespace MyCompany.MyNamespace{}
```

Defining Class Types in CIL

Empty namespaces are not very interesting, so let's now check out the process of defining a class type using CIL. Not surprisingly, the `.class` directive is used to define a new class. However, this simple directive can be adorned with numerous additional attributes, to further qualify the nature of the type. To illustrate, add a public class to your namespace named `MyBaseClass`. As in C#, if you do not specify an explicit base class, your type will automatically be derived from `System.Object`.

```
.namespace MyNamespace
{
    // System.Object base class assumed.
    .class public MyBaseClass {}
```

When you are building a class type that derives from any class other than `System.Object`, you make use of the `extends` attribute. Whenever you need to reference a type defined within the same assembly, CIL demands that you also make use of the fully qualified name (however, if the base type is within the same assembly, you can omit the assembly's friendly name prefix). Therefore, the following attempt to extend `MyBaseClass` results in a compiler error:

```
// This will not compile!
.namespace MyNamespace
{
    .class public MyBaseClass {}

    .class public MyDerivedClass
        extends MyBaseClass {}
}
```

To correctly define the parent class of `MyDerivedClass`, you must specify the full name of `MyBaseClass` as follows:

```
// Better!
.namespace MyNamespace
{
    .class public MyBaseClass {}

    .class public MyDerivedClass
        extends MyNamespace.MyBaseClass {}
}
```

In addition to the `public` and `extends` attributes, a CIL class definition may take numerous additional qualifiers that control the type's visibility, field layout, and so on. Table 17-3 illustrates some (but not all) of the attributes that may be used in conjunction with the `.class` directive.

Table 17-3. Various Attributes Used in Conjunction with the `.class` Directive

Attributes	Meaning in Life
<code>public, private, nested assembly, nested famandassem, nested family, nested famorassem, nested public, nested private</code>	CIL defines various attributes that are used to specify the visibility of a given type. As you can see, raw CIL offers numerous possibilities other than those offered by C#. Refer to ECMA 335 for details if you are interested.
<code>abstract, sealed</code>	These two attributes may be tacked onto a <code>.class</code> directive to define an abstract class or sealed class, respectively.
<code>auto, sequential, explicit</code>	These attributes are used to instruct the CLR how to lay out field data in memory. For class types, the default layout flag (<code>auto</code>) is appropriate. Changing this default can be helpful if you need to use P/Invoke to call into unmanaged C code.
<code>extends, implements</code>	These attributes allow you to define the base class of a type (via <code>extends</code>) or implement an interface on a type (via <code>implements</code>).

Defining and Implementing Interfaces in CIL

As odd as it may seem, interface types are defined in CIL using the `.class` directive. However, when the `.class` directive is adorned with the `interface` attribute, the type is realized as a CTS interface type. Once an interface has been defined, it may be bound to a class or structure type using the CIL `implements` attribute:

```
.namespace MyNamespace
{
    // An interface definition.
    .class public interface IMyInterface {}

    // A simple base class.
    .class public MyBaseClass {}

    // MyDerivedClass now implements IMyInterface,
    // and extends MyBaseClass.
    .class public MyDerivedClass
        extends MyNamespace.MyBaseClass
        implements MyNamespace.IMyInterface {}
}
```

Note The `extends` clause must precede the `implements` clause. As well, the `implements` can incorporate a comma-separated list of interfaces.

As you recall from Chapter 9, interfaces can function as the base interface to other interface types in order to build interface hierarchies. However, contrary to what you might be thinking, the `extends` attribute cannot be used to derive interface A from interface B. The `extends` attribute is used only to qualify a type's base class. When you wish to extend an interface, you will make use of the `implements` attribute yet again:

```
// Extending interfaces in terms of CIL.
.class public interface IMyInterface {}

.class public interface IMyOtherInterface
    implements MyNamespace.IMyInterface {}
```

Defining Structures in CIL

The `.class` directive can be used to define a CTS structure if the type extends `System.ValueType`. As well, the `.class` directive must be qualified with the `sealed` attribute (given that structures can never be a base structure to other value types). If you attempt to do otherwise, `ilasm.exe` will issue a compiler error.

```
// A structure definition is always sealed.
.class public sealed MyStruct
```

```
extends [mscorlib]System.ValueType{}
```

Do be aware that CIL provides a shorthand notation to define a structure type. If you use the value attribute, the new type will derive the type from [mscorlib]System.ValueType automatically. Therefore, you could define MyStruct as follows:

```
// Shorthand notation for declaring a structure.  
.class public sealed value MyStruct{}
```

Defining Enums in CIL

.NET enumerations (as you recall) derive from System.Enum, which is a System.ValueType (and therefore must also be sealed). When you wish to define an enum in terms of CIL, simply extend [mscorlib]System.Enum:

```
// An enum.  
.class public sealed MyEnum  
    extends [mscorlib]System.Enum{}
```

Like a structure definition, enumerations can be defined with a shorthand notation using the enum attribute:

```
// Enum shorthand.  
.class public sealed enum MyEnum{}
```

You'll see how to specify the name/value pairs of an enumeration in just a moment.

Note The other fundamental .NET type, the delegate, also has a specific CIL representation. See Chapter 11 for details.

Defining Generics in CIL

Generic types also have a specific representation in the syntax of CIL. Recall from Chapter 10 that a given generic type or generic member may have one or more type parameters. For example, the List<T> type has a single type parameter, while Dictionary< TKey, TValue > has two. In terms of CIL, the number of type parameters is specified using a backward-leaning single tick, ` , followed by a numerical value representing the number of type parameters. Like C#, the actual value of the type parameters is encased within angled brackets.

Note On most keyboards, the ` character can be found on the key above the Tab key (and to the left of the 1 key).

For example, assume you wish to create a List<T> variable, where T is of type System.Int32. In CIL, you would author the following (which could appear in any CIL method scope):

```
// In C#: List<int> myInts = new List<int>();
newobj instance void class [mscorlib]
    System.Collections.Generic.List`1<int32>:::ctor()
```

Notice that this generic class is defined as `List`1<int32>`, as `List<T>` has a single type parameter. However, if you needed to define a `Dictionary<string, int>` type, you would do so as the following:

```
// In C#: Dictionary<string, int> d = new Dictionary<string, int>();
newobj instance void class [mscorlib]
    System.Collections.Generic.Dictionary`2<string,int32>:::ctor()
```

As another example, if you have a generic type that uses another generic type as a type parameter, you would author CIL code such as the following:

```
// In C#: List<List<int>> myInts = new List<List<int>>();
newobj instance void class [mscorlib]
    System.Collections.Generic.List`1<class
        [mscorlib]System.Collections.Generic.List`1<int32>>:::ctor()
```

Compiling the CILTypes.il file

Even though you have not yet added any members or implementation code to the types you have defined, you are able to compile this `*.il` file into a .NET DLL assembly (which you must do, as you have not specified a `Main()` method). Open up a command prompt and enter the following command to `ilasm.exe`:

```
ilasm /dll CILTypes.il
```

Once you have done so, you are able to open your binary into `ildasm.exe` (see Figure 17-3).




Figure 17-3. The `CILTypes.dll` assembly

Once you have confirmed the contents of your assembly, run `pverify.exe` against it:

```
pverify CILTypes.dll
```

Notice that you are issued errors, given that all your types are completely empty. Here is some partial output:

```
Microsoft (R) .NET Framework PE Verifier. Version 4.0.21006.1
Copyright (c) Microsoft Corporation. All rights reserved.

[MD]: Error: Value class has neither fields nor size parameter. [token:0x02000005]
[MD]: Error: Enum has no instance field. [token:0x02000006]
...
```

To understand how to populate a type with content, you first need to examine the fundamental data types of CIL.

.NET Base Class Library, C#, and CIL Data Type Mappings

Table 17-4 illustrates how a .NET base class type maps to the corresponding C# keyword, and how each C# keyword maps into raw CIL. As well, Table 17-4 documents the shorthand constant notations used for each CIL type. As you will see in just a moment, these constants are often referenced by numerous CIL opcodes.

Table 17-4. Mapping .NET Base Class Types to C# Keywords, and C# Keywords to CIL

.NET Base Class Type	C# Keyword	CIL Representation	CIL Constant Notation
System.SByte	sbyte	int8	I1
System.Byte	byte	unsigned int8	U1
System.Int16	short	int16	I2
System.UInt16	ushort	unsigned int16	U2
System.Int32	int	int32	I4
System.UInt32	uint	unsigned int32	U4
System.Int64	long	int64	I8
System.UInt64	ulong	unsigned int64	U8
System.Char	char	char	CHAR
System.Single	float	float32	R4
System.Double	double	float64	R8

Table 17-4. Mapping .NET Base Class Types to C# Keywords, and C# Keywords to CIL (continued)

.NET Base Class Type	C# Keyword	CIL Representation	CIL Constant Notation
System.Boolean	bool	bool	BOOLEAN
System.String	string	string	N/A
System.Object	object	object	N/A
System.Void	void	void	VOID

■ Note The System.IntPtr and System.UIntPtr types map to native int and native unsigned int (this is good to know, as many of COM interoperability and P/Invoke scenarios use these extensively).

Defining Type Members in CIL

As you are already aware, .NET types may support various members. Enumerations have some set of name/value pairs. Structures and classes may have constructors, fields, methods, properties, static members, and so on. Over the course of this book's first 16 chapters, you have already seen partial CIL definitions for the items previously mentioned, but nevertheless, here is a quick recap of how various members map to CIL primitives.

Defining Field Data in CIL

Enumerations, structures, and classes can all support field data. In each case, the .field directive will be used. For example, let's breathe some life into the skeleton MyEnum enumeration and define three name/value pairs (note the values are specified within parentheses):

```
.class public sealed enum MyEnum
{
    .field public static literal valuetype
        MyNamespace.MyEnum A = int32(0)
    .field public static literal valuetype
        MyNamespace.MyEnum B = int32(1)
    .field public static literal valuetype
        MyNamespace.MyEnum C = int32(2)
}
```

Fields that reside within the scope of a .NET System.Enum-derived type are qualified using the static and literal attributes. As you would guess, these attributes set up the field data to be a fixed value accessible from the type itself (e.g., MyEnum.A).

Note The values assigned to an enum value may also be in hexadecimal with an 0x prefix.

Of course, when you wish to define a point of field data within a class or structure, you are not limited to a point of public static literal data. For example, you could update MyBaseClass to support two points of private, instance-level field data, set to default values:

```
.class public MyBaseClass
{
    .field private string stringField = "hello!"
    .field private int32 intField = int32(42)
}
```

As in C#, class field data will automatically be initialized to an appropriate default value. If you wish to allow the object user to supply custom values at the time of creation for each of these points of private field data, you (of course) need to create custom constructors.

Defining Type Constructors in CIL

The CTS supports both instance-level and class-level (static) constructors. In terms of CIL, instance-level constructors are represented using the .ctor token, while a static-level constructor is expressed via .cctor (class constructor). Both of these CIL tokens must be qualified using the rtspecialname (return type special name) and specialname attributes. Simply put, these attributes are used to identify a specific CIL token that can be treated in unique ways by a given .NET language. For example, in C#, constructors do not define a return type; however, in terms of CIL, the return value of a constructor is indeed void:

```
.class public MyBaseClass
{
    .field private string stringField
    .field private int32 intField

    .method public hidebysig specialname rtspecialname
        instance void .ctor(string s, int32 i) cil managed
    {
        // TODO: Add implementation code...
    }
}
```

Note that the .ctor directive has been qualified with the instance attribute (as it is not a static constructor). The cil managed attributes denote that the scope of this method contains CIL code, rather than unmanaged code, which may be used during platform invocation requests.

Defining Properties in CIL

Properties and methods also have specific CIL representations. By way of an example, if `MyBaseClass` were updated to support a public property named `TheString`, you would author the following CIL (note again the use of the `specialname` attribute):

```
.class public MyBaseClass
{
...
.method public hidebysig specialname
    instance string get_TheString() cil managed
{
    // TODO: Add implementation code...
}

.method public hidebysig specialname
    instance void set_TheString(string 'value') cil managed
{
    // TODO: Add implementation code...
}

.property instance string TheString()
{
    .get instance string
        MyNamespace.MyBaseClass::get_TheString()
    .set instance void
        MyNamespace.MyBaseClass::set_TheString(string)
}
}
```

Recall that in terms of CIL, a property maps to a pair of methods that take `get_` and `set_` prefixes. The `.property` directive makes use of the related `.get` and `.set` directives to map property syntax to the correct “specially named” methods.

Note Notice that the incoming parameter to the `set` method of a property is placed in single-tick quotation marks, which represents the name of the token to use on the right-hand side of the assignment operator within the method scope.

Defining Member Parameters

In a nutshell, specifying arguments in CIL is (more or less) identical to doing so in C#. For example, each argument is defined by specifying its data type followed by the parameter name. Furthermore, like C#, CIL provides a way to define input, output, and pass-by-reference parameters. As well, CIL allows you to define a parameter array argument (aka the C# `params` keyword) as well as optional parameters (which are not supported in C# but are used in VB).

To illustrate the process of defining parameters in raw CIL, assume you wish to build a method that takes an int32 (by value), an int32 (by reference), a [mscorlib]System.Collection.ArrayList, and a single output parameter (of type int32). In terms of C#, this method would look something like the following:

```
public static void MyMethod(int inputInt,
    ref int refInt, ArrayList ar, out int outputInt)
{
    outputInt = 0; // Just to satisfy the C# compiler...
}
```

If you were to map this method into CIL terms, you would find that C# reference parameters are marked with an ampersand (&) suffixed to the parameter's underlying data type (int32&).

Output parameters also make use of the & suffix, but they are further qualified using the CIL [out] token. Also notice that if the parameter is a reference type (in this case, the [mscorlib]System.Collections.ArrayList type), the class token is prefixed to the data type (not to be confused with the .class directive!):

```
.method public hidebysig static void MyMethod(int32 inputInt,
    int32& refInt,
    class [mscorlib]System.Collections.ArrayList ar,
    [out] int32& outputInt) cil managed
{
    ...
}
```

Examining CIL Opcodes

The final aspect of CIL code you'll examine in this chapter has to do with the role of various -operational codes (opcodes). Recall that an opcode is simply a CIL token used to build the implementation logic for a given member. The complete set of CIL opcodes (which is fairly large) can be grouped into the following broad categories:

- Opcodes that control program flow
- Opcodes that evaluate expressions
- Opcodes that access values in memory (via parameters, local variables, etc.)

To provide some insight to the world of member implementation via CIL, Table 17-5 defines some of the more useful opcodes that are directly related to member implementation logic, grouped by related functionality.

Table 17-5. Various Implementation-Specific CIL Opcodes

Opcodes	Meaning in Life
add, sub, mul, div, rem	These CIL opcodes allow you to add, subtract, multiply, and divide two values (rem returns the remainder of a division operation).
and, or, not, xor	These CIL opcodes allow you to perform bit-wise operations on two values.
ceq, cgt, clt	These CIL opcodes allow you to compare two values on the stack in various manners, for example: ceq: Compare for equality cgt: Compare for greater than clt: Compare for less than
box, unbox	These CIL opcodes are used to convert between reference types and value types.
ret	This CIL opcode is used to exit a method and return a value to the caller (if necessary).
beq, bgt, ble, blt, switch	These CIL opcodes (in addition to many other related opcodes) are used to control branching logic within a method, for example: beq: Break to code label if equal bgt: Break to code label if greater than ble: Break to code label if less than or equal to blt: Break to code label if less than All of the branch-centric opcodes require that you specify a CIL code label to jump to if the result of the test is true.
call	This CIL opcode is used to call a member on a given type.
newarr, newobj	These CIL opcodes allow you to allocate a new array or new object type into memory (respectively).

The next broad category of CIL opcodes (a subset of which is shown in Table 17-6) are used to load (push) arguments onto the virtual execution stack. Note how these load-specific opcodes take an ld (load) prefix.

Table 17-6. The Primary Stack-Centric Opcodes of CIL

Opcode	Meaning in Life
ldarg (with numerous variations)	Loads a method's argument onto the stack. In addition to the general ldarg (which works in conjunction with a given index that identifies the argument), there are numerous other variations. For example, ldarg opcodes that have a numerical suffix (ldarg_0) hard-code which argument to load. As well, variations of the ldarg opcode allow you to hard-code the data type using the CIL constant notation shown in Table 17-4 (ldarg_I4, for an int32) as well as the data type and value (ldarg_I4_5, to load an int32 with the value of 5).
ldc (with numerous variations)	Loads a constant value onto the stack.
ldfld (with numerous variations)	Loads the value of an instance-level field onto the stack.
ldloc (with numerous variations)	Loads the value of a local variable onto the stack.
ldobj	Obtains all the values gathered by a heap-based object and places them on the stack.
ldstr	Loads a string value onto the stack.

In addition to the set of load-specific opcodes, CIL provides numerous opcodes that *explicitly* pop the topmost value off the stack. As shown over the first few examples in this chapter, popping a value off the stack typically involves storing the value into temporary local storage for further use (such as a parameter for an upcoming method invocation). Given this, note how many opcodes that pop the current value off the virtual execution stack take an st (store) prefix. Table 17-7 hits the highlights.

Table 17-7. Various Pop-Centric Opcodes

Opcode	Meaning in Life
pop	Removes the value currently on top of the evaluation stack, but does not bother to store the value
starg	Stores the value on top of the stack into the method argument at a specified index
stloc (with numerous variations)	Pops the current value from the top of the evaluation stack and stores it in a local variable list at a specified index
stobj	Copies a value of a specified type from the evaluation stack into a supplied memory address
stsfld	Replaces the value of a static field with a value from the evaluation stack

Do be aware that various CIL opcodes will *implicitly* pop values off the stack to perform the task at hand. For example, if you are attempting to subtract two numbers using the sub opcode, it should be clear that sub will have to pop off the next two available values before it can perform the calculation. Once the calculation is complete, the result of the value (surprise, surprise) is pushed onto the stack once again.

The .maxstack Directive

When you write method implementations using raw CIL, you need to be mindful of a special directive named .maxstack. As its name suggests, .maxstack establishes the maximum number of variables that may be pushed onto the stack at any given time during the execution of the method. The good news is that the .maxstack directive has a default value (8), which should be safe for a vast majority of methods you may be authoring. However, if you wish to be very explicit, you are able to manually calculate the number of local variables on the stack and define this value explicitly:

```
.method public hidebysig instance void
    Speak() cil managed
{
    // During the scope of this method, exactly
    // 1 value (the string literal) is on the stack.
    .maxstack 1
    ldstr "Hello there..."
    call void [mscorlib]System.Console::WriteLine(string)
    ret
}
```

Declaring Local Variables in CIL

Let's first check out how to declare a local variable. Assume you wish to build a method in CIL named MyLocalVariables() that takes no arguments and returns void. Within the method, you wish to define three local variables of type System.String, System.Int32, and System.Object. In C#, this member would appear as follows (recall that locally scoped variables do not receive a default value and should be set to an initial state before further use):

```
public static void MyLocalVariables()
{
    string myStr = "CIL code is fun!";
    int myInt = 33;
    object myObj = new object();
}
```

If you were to construct MyLocalVariables() directly in CIL, you could author the following:

```
.method public hidebysig static void
    MyLocalVariables() cil managed
{
    .maxstack 8
    // Define three local variables.
    .locals init ([0] string myStr, [1] int32 myInt, [2] object myObj)
```

```

// Load a string onto the virtual execution stack.
ldstr "CIL code is fun!"
// Pop off current value and store in local variable [0].
stloc.0

// Load a constant of type "i4"
// (shorthand for int32) set to the value 33.
ldc.i4 33
// Pop off current value and store in local variable [1].
stloc.1

// Create a new object and place on stack.
newobj instance void [mscorlib]System.Object::ctor()
// Pop off current value and store in local variable [2].
stloc.2
ret
}

```

As you can see, the first step taken to allocate local variables in raw CIL is to make use of the `.locals` directive, which is paired with the `init` attribute. Within the scope of the related parentheses, your goal is to associate a given numerical index to each variable (seen here as [0], [1], and [2]). As you can see, each index is identified by its data type and an optional variable name. Once the local variables have been defined, you load a value onto the stack (using the various load-centric opcodes) and store the value within the local variable (using the various storage-centric opcodes).

Mapping Parameters to Local Variables in CIL

You have already seen how to declare local variables in raw CIL using the `.locals` init directive; however, you have yet to see exactly how to map incoming parameters to local methods. Consider the following static C# method:

```

public static int Add(int a, int b)
{
    return a + b;
}

```

This innocent-looking method has a lot to say in terms of CIL. First, the incoming arguments (`a` and `b`) must be pushed onto the virtual execution stack using the `ldarg` (load argument) opcode. Next, the `add` opcode will be used to pop the next two values off the stack and find the summation, and store the value on the stack yet again. Finally, this sum is popped off the stack and returned to the caller via the `ret` opcode. If you were to disassemble this C# method using `ildasm.exe`, you would find numerous additional tokens injected by `csc.exe`, but the crux of the CIL code is quite simple:

```

.method public hidebysig static int32  Add(int32 a,
    int32 b) cil managed
{
    .maxstack  2
    ldarg.0    // Load "a" onto the stack.
    ldarg.1    // Load "b" onto the stack.
    add       // Add both values.
}

```

```
    ret
}
```

The Hidden this Reference

Notice that the two incoming arguments (*a* and *b*) are referenced within the CIL code using their indexed position (index 0 and index 1), given that the virtual execution stack begins indexing at position 0.

One thing to be very mindful of when you are examining or authoring CIL code is that every nonstatic method that takes incoming arguments automatically receives an implicit additional parameter, which is a reference to the current object (think the C# *this* keyword). Given this, if the *Add()* method were defined as *nonstatic*:

```
// No longer static!
public int Add(int a, int b)
{
    return a + b;
}
```

the incoming *a* and *b* arguments are loaded using *ldarg.1* and *ldarg.2* (rather than the expected *ldarg.0* and *ldarg.1* opcodes). Again, the reason is that slot 0 actually contains the implicit *this* reference. Consider the following pseudo-code:

```
// This is JUST pseudo-code!
.method public hidebysig static int32 AddTwoIntParams(
    MyClass_HiddenThisPointer this, int32 a, int32 b) cil managed
{
    ldarg.0    // Load MyClass_HiddenThisPointer onto the stack.
    ldarg.1    // Load "a" onto the stack.
    ldarg.2    // Load "b" onto the stack.
...
}
```

Representing Iteration Constructs in CIL

Iteration constructs in the C# programming language are represented using the *for*, *foreach*, *while*, and *do* keywords, each of which has a specific representation in CIL. Consider the classic *for* loop:

```
public static void CountToTen()
{
    for(int i = 0; i < 10; i++)
        ;
}
```

Now, as you may recall, the *br* opcodes (*br*, *blt*, and so on) are used to control a break in flow when some condition has been met. In this example, you have set up a condition in which the *for* loop should break out of its cycle when the local variable *i* is equal to or greater than the value of 10. With each pass, the value of 1 is added to *i*, at which point the test condition is yet again evaluated.

Also recall that when you make use of any of the CIL branching opcodes, you will need to define a specific code label (or two) that marks the location to jump to when the condition is indeed true. Given

these points, ponder the following (augmented) CIL code generated via ildasm.exe (including the autogenerated code labels):

```
.method public hidebysig static void CountToTen() cil managed
{
    .maxstack 2
    .locals init ([0] int32 i) // Init the local integer "i".
    IL_0000: ldc.i4.0          // Load this value onto the stack.
    IL_0001: stloc.0           // Store this value at index "0".
    IL_0002: br.s IL_0008      // Jump to IL_0008.
    IL_0004: ldloc.0           // Load value of variable at index 0.
    IL_0005: ldc.i4.1           // Load the value "1" on the stack.
    IL_0006: add                // Add current value on the stack at index 0.
    IL_0007: stloc.0
    IL_0008: ldloc.0           // Load value at index "0".
    IL_0009: ldc.i4.s 10        // Load value of "10" onto the stack.
    IL_000B: blt.s IL_0004      // Less than? If so, jump back to IL_0004
    IL_000D: ret
}
```

In a nutshell, this CIL code begins by defining the local int32 and loading it onto the stack. At this point, you jump back and forth between code label IL_0008 and IL_0004, each time bumping the value of *i* by 1 and testing to see whether *i* is still less than the value 10. If so, you exit the method.

Source Code The CilTypes example is included under the Chapter 17 subdirectory.

Building a .NET Assembly with CIL

Now that you've taken a tour of the syntax and semantics of raw CIL, it's time to solidify your current understanding by building a .NET application using nothing but ilasm.exe and your text editor of choice. Specifically, your application will consist of a privately deployed, single-file *.dll that contains two class type definitions, and a console-based *.exe that interacts with these types.

Building CILCars.dll

The first order of business is to build the *.dll to be consumed by the client. Open a text editor and create a new *.il file named CILCars.il. This single-file assembly will make use of two external .NET assemblies. Begin by updating your code file as follows:

```
// Reference mscorlib.dll and
// System.Windows.Forms.dll
.assembly extern mscorlib
{
    .publickeytoken = (B7 7A 5C 56 19 34 E0 89 )
    .ver 4:0:0:0
```

```

}

.assembly extern System.Windows.Forms
{
    .publickeytoken = (B7 7A 5C 56 19 34 E0 89 )
    .ver 4:0:0:0
}

// Define the single-file assembly.
.assembly CILCars
{
    .hash algorithm 0x00008004
    .ver 1:0:0:0
}
.module CILCars.dll

```

This assembly will contain two class types. The first type, CILCar, defines two points of field data and a custom constructor. The second type, CarInfoHelper, defines a single static method named `DisplayCarInfo()`, which takes CILCar as a parameter and returns void. Both types are in the `CILCars` namespace. In terms of CIL, CILCar can be implemented as follows:

```

// Implementation of CILCars.CILCar type.
.namespace CILCars
{
    .class public auto ansi beforefieldinit CILCar
        extends [mscorlib]System.Object
    {
        // The field data of the CILCar.
        .field public string petName
        .field public int32 currSpeed

        // The custom constructor simply allows the caller
        // to assign the field data.
        .method public hidebysig specialname rtspecialname
            instance void .ctor(int32 c, string p) cil managed
        {
            .maxstack 8

            // Load first arg onto the stack and call base class ctor.
            ldarg.0 // "this" object, not the int32!
            call instance void [mscorlib]System.Object:::.ctor()

            // Now load first and second args onto the stack.
            ldarg.0 // "this" object
            ldarg.1 // int32 arg

            // Store topmost stack (int 32) member in currSpeed field.
            stfld int32 CILCars.CILCar::currSpeed

            // Load string arg and store in petName field.
            ldarg.0 // "this" object
            ldarg.2 // string arg
            stfld string CILCars.CILCar::petName
        }
    }
}
```

```

        ret
    }
}
}
```

Keeping in mind that the real first argument for any nonstatic member is the current object reference, the first block of CIL simply loads the object reference and calls the base class constructor. Next, you push the incoming constructor arguments onto the stack and store them into the type's field data using the `stfld` (store in field) opcode.

Now let's implement the second type in this namespace: `CILCarInfo`. The meat of the type is found within the static `Display()` method. In a nutshell, the role of this method is to take the incoming `CILCar` parameter, extract the values of its field data, and display it in a Windows Forms message box. Here is the complete implementation of `CILCarInfo` (which should be defined within the `CILCars` namespace) with analysis to follow:

```

.class public auto ansi beforefieldinit CILCarInfo
    extends [mscorlib]System.Object
{
    .method public hidebysig static void
        Display(class CILCars.CILCar c) cil managed
    {
        .maxstack 8

        // We need a local string variable.
        .locals init ([0] string caption)

        // Load string and the incoming CILCar onto the stack.
        ldstr "{0}'s speed is:"
        ldarg.0

        // Now place the value of the CILCar's petName on the
        // stack and call the static String.Format() method.
        ldfld string CILCars.CILCar::petName
        call string [mscorlib]System.String::Format(string, object)
        stloc.0

        // Now load the value of the currSpeed field and get its string
        // representation (note call to ToString()).
        ldarg.0
        ldflda int32 CILCars.CILCar::currSpeed
        call instance string [mscorlib]System.Int32::ToString()
        ldloc.0

        // Now call the MessageBox.Show() method with loaded values.
        call valuetype [System.Windows.Forms]
            System.Windows.Forms.DialogResult
            [System.Windows.Forms]
            System.Windows.Forms.MessageBox::Show(string, string)
        pop
        ret
    }
}
```

Although the amount of CIL code is a bit more than you see in the implementation of `CILCar`, things are still rather straightforward. First, given that you are defining a static method, you don't have to be concerned with the hidden object reference (thus, the `ldarg.0` opcode really does load the incoming `CILCar` argument).

The method begins by loading a string ("`{0}'s speed is`") onto the stack, followed by the `CILCar` argument. Once these two values are in place, you load the value of the `petName` field and call the static `System.String.Format()` method to substitute the curly bracket placeholder with the `CILCar`'s pet name.

The same general procedure takes place when processing the `currSpeed` field, but note that you use the `ldflda` opcode, which loads the argument address onto the stack. At this point, you call `System.Int32.ToString()` to transform the value at said address into a string type. Finally, once both strings have been formatted as necessary, you call the `MessageBox.Show()` method.

At this point, you are able to compile your new `*.dll` using `ilasm.exe` with the following command:

```
ilasm /dl1 CILCars.il
```

and verify the contained CIL using `pverify.exe`:

```
pverify CILCars.dll
```

Building `CILCarClient.exe`

Now you can build a simple `*.exe` assembly with a `Main()` method that will

- Make a `CILCar` object.
- Pass the object into the static `CILCarInfo.Display()` method.

Create a new file named `CarClient.il` and define external references to `mscorlib.dll` and `CILCars.dll` (don't forget to place a copy of this .NET assembly in the client's application directory!). Next, define a single type (`Program`) that manipulates the `CILCars.dll` assembly. Here's the complete code:

```
// External assembly refs.
.assembly extern mscorel
{
    .publickeytoken = (B7 7A 5C 56 19 34 E0 89)
    .ver 4:0:0:0
}
.assembly extern CILCars
{
    .ver 1:0:0:0
}

// Our executable assembly.
.assembly CarClient
{
    .hash algorithm 0x00008004
    .ver 1:0:0:0
}
.module CarClient.exe

// Implementation of Program type
```

```

.namespace CarClient
{
    .class private auto ansi beforefieldinit Program
    extends [mscorlib]System.Object
    {
        .method private hidebysig static void
        Main(string[] args) cil managed
        {
            // Marks the entry point of the *.exe.
            .entrypoint
            .maxstack 8

            // Declare a local CILCar variable and push
            // values on the stack for ctor call.
            .locals init ([0] class
            [CILCars]CILCars.CILCar myCilCar)
            ldc.i4 55
            ldstr "Junior"

            // Make new CilCar; store and load reference.
            newobj instance void
                [CILCars]CILCars.CILCar:::ctor(int32, string)
            stloc.0
            ldloc.0

            // Call Display() and pass in topmost value on stack.
            call void [CILCars]
                CILCars.CILCarInfo::Display(
                    class [CILCars]CILCars.CILCar)
            ret
        }
    }
}

```

The one opcode that is important to point out is `.entrypoint`. Recall from the discussion earlier in this chapter that this opcode is used to mark which method of an `*.exe` functions as the entry point of the module. In fact, given that `.entrypoint` is how the CLR identifies the initial method to execute, this method can be called anything, although here you are using the standard method name of `Main()`. The remainder of the CIL code found in the `Main()` method is your basic pushing and popping of stack-based values.

Do note, however, that the creation of a `CILCar` object involves the use of the `.newobj` opcode. On a related note, recall that when you wish to invoke a member of a type using raw CIL, you make use of the double-colon syntax and, as always, make use of the fully qualified name of the type. With this, you can compile your new file with `ilasm.exe`, verify your assembly with `pverify.exe`, and execute your program. Issue the following commands within your command prompt:

```

ilasm CarClient.il
pverify CarClient.exe
CarClient.exe

```

Figure 17-4 shows the end result.



Figure 17-4. Your CILCar in action

■ **Source Code** The CilCars example is included under the Chapter 17 subdirectory.

Understanding Dynamic Assemblies

To be sure, the process of building a complex .NET application in CIL would be quite the labor of love. On the one hand, CIL is an extremely expressive programming language that allows you to interact with all of the programming constructs allowed by the CTS. On the other hand, authoring raw CIL is tedious, error-prone, and painful. While it is true that knowledge is power, you may indeed wonder just how important it is to commit the laws of CIL syntax to memory. The answer is, “It depends.” To be sure, most of your .NET programming endeavors will not require you to view, edit, or author CIL code. However, with the CIL primer behind you, you are now ready to investigate the world of dynamic assemblies (as opposed to static assemblies) and the role of the `System.Reflection.Emit` namespace.

The first question you may have is, “What exactly is the difference between static and dynamic assemblies?” By definition, *static assemblies* are .NET binaries loaded directly from disk storage, meaning they are located somewhere on your hard drive in a physical file (or possibly a set of files in the case of a multifile assembly) at the time the CLR requests them. As you might guess, every time you compile your C# source code, you end up with a static assembly.

A *dynamic assembly*, on the other hand, is created in memory on the fly using the types provided by the `System.Reflection.Emit` namespace. The `System.Reflection.Emit` namespace makes it possible to create an assembly and its modules, type definitions, and CIL implementation logic at *runtime*. Once you have done so, you are then free to save your in-memory binary to disk. This, of course, results in a new static assembly. To be sure, the process of building a dynamic assembly using the `System.Reflection.Emit` namespace does require some level of understanding regarding the nature of CIL opcodes.

Although creating dynamic assemblies is a fairly advanced (and uncommon) programming task, they can be useful under various circumstances:

- You are building a .NET programming tool that needs to generate assemblies on demand based on user input.
- You are building a program that needs to generate proxies to remote types on the fly based on the obtained metadata.
- You wish to load a static assembly and dynamically insert new types into the binary image.

Several aspects of the .NET runtime engine involve generating dynamic assemblies quietly in the background. For example, ASP.NET makes use of this technique to map markup and server-side script code into a runtime object model. LINQ also can generate code on the fly based on various query expressions. This being said, let's check out the types within `System.Reflection.Emit`.

Exploring the `System.Reflection.Emit` Namespace

Creating a dynamic assembly requires you to have some familiarity with CIL opcodes, but the types of the `System.Reflection.Emit` namespace hide the complexity of CIL as much as possible. For example, rather than directly specifying the necessary CIL directives and attributes to define a class type, you can simply make use of the `TypeBuilder` class. Likewise, if you wish to define a new instance-level constructor, you have no need to emit the `specialname`, `rtspecialname`, or `.ctor` tokens; rather, you can make use of the `ConstructorBuilder`. Table 17-8 documents the key members of the `System.Reflection.Emit` namespace.

Table 17-8. Select Members of the `System.Reflection.Emit` Namespace

Members	Meaning in Life
<code>AssemblyBuilder</code>	Used to create an assembly (*.dll or *.exe) at runtime. *.exes must call the <code>ModuleBuilder.SetEntryPoint()</code> method to set the method that is the entry point to the module. If no entry point is specified, a *.dll will be generated.
<code>ModuleBuilder</code>	Used to define the set of modules within the current assembly.
<code>EnumBuilder</code>	Used to create a .NET enumeration type.
<code>TypeBuilder</code>	May be used to create classes, interfaces, structures, and delegates within a module at runtime.
<code>MethodBuilder</code> <code>LocalBuilder</code> <code>PropertyBuilder</code> <code>FieldBuilder</code> <code>ConstructorBuilder</code> <code>CustomAttributeBuilder</code> <code>ParameterBuilder</code> <code>EventBuilder</code>	Used to create type members (such as methods, local variables, properties, constructors, and attributes) at runtime.
<code>ILGenerator</code>	Emits CIL opcodes into a given type member.
<code>OpCodes</code>	Provides numerous fields that map to CIL opcodes. This type is used in conjunction with the various members of <code>System.Reflection.Emit.ILGenerator</code> .

In general, the types of the `System.Reflection.Emit` namespace allow you to represent raw CIL tokens programmatically during the construction of your dynamic assembly. You will see many of these members in the example that follows; however, the `ILGenerator` type is worth checking out straightforward.

The Role of the `System.Reflection.Emit.ILGenerator`

As its name implies, the `ILGenerator` type's role is to inject CIL opcodes into a given type member. However, you cannot directly create `ILGenerator` objects, as this type has no public constructors, rather you receive an `ILGenerator` type by calling specific methods of the builder-centric types (such as the `MethodBuilder` and `ConstructorBuilder` types), for example:

```
// Obtain an ILGenerator from a ConstructorBuilder
// object named "myCtorBuilder".
ConstructorBuilder myCtorBuilder =
    new ConstructorBuilder(/* ...various args... */);

ILGenerator myCILGen = myCtorBuilder.GetILGenerator();
```

Once you have an `ILGenerator` in your hands, you are then able to emit the raw CIL opcodes using any number of methods. Table 17-9 documents some (but not all) methods of `ILGenerator`.

Table 17-9. Various Methods of `ILGenerator`

Method	Meaning in Life
<code>BeginCatchBlock()</code>	Begins a catch block
<code>BeginExceptionBlock()</code>	Begins an exception block for a nonfiltered exception
<code>BeginFinallyBlock()</code>	Begins a <code>finally</code> block
<code>BeginScope()</code>	Begins a lexical scope
<code>DeclareLocal()</code>	Declares a local variable
<code>DefineLabel()</code>	Declares a new label
<code>Emit()</code>	Is overloaded numerous times to allow you to emit CIL opcodes
<code>EmitCall()</code>	Pushes a <code>call</code> or <code>callvirt</code> opcode into the CIL stream
<code>EmitWriteLine()</code>	Emits a call to <code>Console.WriteLine()</code> with different types of values
<code>EndExceptionBlock()</code>	Ends an exception block
<code>EndScope()</code>	Ends a lexical scope

Table 17-9. Various Methods of *ILGenerator* (continued)

Method	Meaning in Life
ThrowException()	Emits an instruction to throw an exception
UsingNamespace()	Specifies the namespace to be used in evaluating locals and watches for the current active lexical scope

The key method of *ILGenerator* is *Emit()*, which works in conjunction with the *System.Reflection.Emit.OpCodes* class type. As mentioned earlier in this chapter, this type exposes a good number of read-only fields that map to raw CIL opcodes. The full set of these members are all documented within online help, and you will see various examples in the pages that follow.

Emitting a Dynamic Assembly

To illustrate the process of defining a .NET assembly at runtime, let's walk through the process of creating a single-file dynamic assembly named *MyAssembly.dll*. Within this module is a class named *HelloWorld*. The *HelloWorld* class supports a default constructor and a custom constructor that is used to assign the value of a private member variable (*theMessage*) of type *string*. In addition, *HelloWorld* supports a public instance method named *SayHello()*, which prints a greeting to the standard I/O stream, and another instance method named *GetMsg()*, which returns the internal private string. In effect, you are going to programmatically generate the following class type:

```
// This class will be created at runtime
// using System.Reflection.Emit.
public class HelloWorld
{
    private string theMessage;
    HelloWorld() {}
    HelloWorld(string s) {theMessage = s;}

    public string GetMsg() {return theMessage;}
    public void SayHello()
    {
        System.Console.WriteLine("Hello from the HelloWorld class!");
    }
}
```

Assume you have created a new Visual Studio 2010 Console Application project workspace named *DynamicAsmBuilder* and import the *System.Reflection*, *System.Reflection.Emit*, and *-System.Threading* namespaces. Define a static method named *CreateMyAsm()*. This single method is in charge of the following:

- Defining the characteristics of the dynamic assembly (name, version, etc.)
- Implementing the *HelloClass* type
- Saving the in-memory assembly to a physical file

Also note that the `CreateMyAsm()` method takes as a single parameter a `System.AppDomain` type, which will be used to obtain access to the `AssemblyBuilder` type associated with the current application domain (see Chapter 17 for a discussion of .NET application domains). Here is the complete code, with analysis to follow:

```
// The caller sends in an AppDomain type.
public static void CreateMyAsm(AppDomain curAppDomain)
{
    // Establish general assembly characteristics.
    AssemblyName assemblyName = new AssemblyName();
    assemblyName.Name = "MyAssembly";
    assemblyName.Version = new Version("1.0.0.0");

    // Create new assembly within the current AppDomain.
    AssemblyBuilder assembly =
        curAppDomain.DefineDynamicAssembly(assemblyName,
            AssemblyBuilderAccess.Save);

    // Given that we are building a single-file
    // assembly, the name of the module is the same as the assembly.
    ModuleBuilder module =
        assembly.DefineDynamicModule("MyAssembly", "MyAssembly.dll");

    // Define a public class named "HelloWorld".
    TypeBuilder helloWorldClass = module.DefineType("MyAssembly.HelloWorld",
        TypeAttributes.Public);

    // Define a private String member variable named "theMessage".
    FieldBuilder msgField =
        helloWorldClass.DefineField("theMessage", Type.GetType("System.String"),
            FieldAttributes.Private);

    // Create the custom ctor.
    Type[] constructorArgs = new Type[1];
    constructorArgs[0] = typeof(string);
    ConstructorBuilder constructor =
        helloWorldClass.DefineConstructor(MethodAttributes.Public,
            CallingConventions.Standard,
            constructorArgs);
    ILGenerator constructorIL = constructor.GetILGenerator();
    constructorIL.Emit(OpCodes.Ldarg_0);
    Type objectClass = typeof(object);
    ConstructorInfo superConstructor =
        objectClass.GetConstructor(new Type[0]);
    constructorIL.Emit(OpCodes.Call, superConstructor);
    constructorIL.Emit(OpCodes.Ldarg_0);
    constructorIL.Emit(OpCodes.Ldarg_1);
    constructorIL.Emit(OpCodes.Stfld, msgField);
    constructorIL.Emit(OpCodes.Ret);

    // Create the default ctor.
    helloWorldClass.DefineDefaultConstructor(MethodAttributes.Public);
```

```

// Now create the GetMsg() method.
MethodBuilder getMsgMethod =
    helloWorldClass.DefineMethod("GetMsg", MethodAttributes.Public,
        typeof(string), null);
ILGenerator methodIL = getMsgMethod.GetILGenerator();
methodIL.Emit(OpCodes.Ldarg_0);
methodIL.Emit(OpCodes.Ldfld, msgField);
methodIL.Emit(OpCodes.Ret);

// Create the SayHello method.
MethodBuilder sayHiMethod =
    helloWorldClass.DefineMethod("SayHello",
        MethodAttributes.Public, null, null);
methodIL = sayHiMethod.GetILGenerator();
methodIL.EmitWriteLine("Hello from the HelloWorld class!");
methodIL.Emit(OpCodes.Ret);

// "Bake" the class HelloWorld.
// (Baking is the formal term for emitting the type)
helloWorldClass.CreateType();

// (Optionally) save the assembly to file.
assembly.Save("MyAssembly.dll");
}

```

Emitting the Assembly and Module Set

The method body begins by establishing the minimal set of characteristics about your assembly, using the `AssemblyName` and `Version` types (defined in the `System.Reflection` namespace). Next, you obtain an `AssemblyBuilder` type via the instance-level `AppDomain.DefineDynamicAssembly()` method (recall the caller will pass in an `AppDomain` reference into the `CreateMyAsm()` method):

```

// Establish general assembly characteristics
// and gain access to the AssemblyBuilder type.
public static void CreateMyAsm(AppDomain curAppDomain)
{
    AssemblyName assemblyName = new AssemblyName();
    assemblyName.Name = "MyAssembly";
    assemblyName.Version = new Version("1.0.0.0");

    // Create new assembly within the current AppDomain.
    AssemblyBuilder assembly =
        curAppDomain.DefineDynamicAssembly(assemblyName,
            AssemblyBuilderAccess.Save);

    ...
}

```

As you can see, when calling `AppDomain.DefineDynamicAssembly()`, you must specify the access mode of the assembly you wish to define, which can be any of the values shown in Table 17-10.

Table 17-10. Values of the AssemblyBuilderAccess Enumeration

Value	Meaning in Life
ReflectionOnly	Represents that a dynamic assembly that can only be reflected over
Run	Represents that a dynamic assembly can be executed in memory but not saved to disk
RunAndSave	Represents that a dynamic assembly can be executed in memory and saved to disk
Save	Represents that a dynamic assembly can be saved to disk but not executed in memory

The next task is to define the module set for your new assembly. Given that the assembly is a single file unit, you need to define only a single module. If you were to build a multi-file assembly using the `DefineDynamicModule()` method, you would specify an optional second parameter that represents the name of a given module (e.g., `myMod.dotnetmodule`). However, when creating a single-file assembly, the name of the module will be identical to the name of the assembly itself. In any case, once the `DefineDynamicModule()` method has returned, you are provided with a reference to a valid `ModuleBuilder` type:

```
// The single-file assembly.
ModuleBuilder module =
    assembly.DefineDynamicModule("MyAssembly", "MyAssembly.dll");
```

The Role of the ModuleBuilder Type

`ModuleBuilder` is the key type used during the development of dynamic assemblies. As you would expect, `ModuleBuilder` supports a number of members that allow you to define the set of types contained within a given module (classes, interfaces, structures, etc.) as well as the set of embedded resources (string tables, images, etc.) contained within. Table 17-11 describes a few of the creation-centric methods. (Do note that each method will return to you a related type that represents the type you wish to construct.)

Table 17-11. Select Members of the ModuleBuilder Type

Method	Meaning in Life
<code>DefineEnum()</code>	Used to emit a .NET enum definition
<code>DefineResource()</code>	Defines a managed embedded resource to be stored in this module
<code>DefineType()</code>	Constructs a <code>TypeBuilder</code> , which allows you to define value types, interfaces, and class types (including delegates)

The key member of the `ModuleBuilder` class to be aware of is `DefineType()`. In addition to specifying the name of the type (via a simple string), you will also make use of the

`System.Reflection.TypeAttributes` enum to describe the format of the type itself. Table 17-12 lists some (but not all) of the key members of the `TypeAttributes` enumeration.

Table 17-12. Select Members of the `TypeAttributes` Enumeration

Member	Meaning in Life
Abstract	Specifies that the type is abstract
Class	Specifies that the type is a class
Interface	Specifies that the type is an interface
NestedAssembly	Specifies that the class is nested with assembly visibility and is thus accessible only by methods within its assembly
NestedFamAndAssem	Specifies that the class is nested with assembly and family visibility, and is thus accessible only by methods lying in the intersection of its family and assembly
NestedFamily	Specifies that the class is nested with family visibility and is thus accessible only by methods within its own type and any subtypes
NestedFamORAssem	Specifies that the class is nested with family or assembly visibility, and is thus accessible only by methods lying in the union of its family and assembly
NestedPrivate	Specifies that the class is nested with private visibility
NestedPublic	Specifies that the class is nested with public visibility
NotPublic	Specifies that the class is not public
Public	Specifies that the class is public
Sealed	Specifies that the class is concrete and cannot be extended
Serializable	Specifies that the class can be serialized

Emitting the `HelloClass` Type and the `String` Member Variable

Now that you have a better understanding of the role of the `ModuleBuilder.CreateType()` method, let's examine how you can emit the public `HelloWorld` class type and the private string variable:

```
// Define a public class named "MyAssembly.HelloWorld".
TypeBuilder helloWorldClass = module.DefineType("MyAssembly.HelloWorld",
    TypeAttributes.Public);
```

```
// Define a private String member variable named "theMessage".
FieldBuilder msgField =
    helloWorldClass.DefineField("theMessage",
        typeof(string),
        FieldAttributes.Private);
```

Notice how the `TypeBuilder.DefineField()` method provides access to a `FieldBuilder` type. The `TypeBuilder` class also defines other methods that provide access to other “builder” types. For example, `DefineConstructor()` returns a `ConstructorBuilder`, `DefineProperty()` returns a `PropertyBuilder`, and so forth.

Emitting the Constructors

As mentioned earlier, the `TypeBuilder.DefineConstructor()` method can be used to define a constructor for the current type. However, when it comes to implementing the constructor of `HelloClass`, you need to inject raw CIL code into the constructor body, which is responsible for assigning the incoming parameter to the internal private string. To obtain an `ILGenerator` type, you call the `GetILGenerator()` method from the respective “builder” type you have reference to (in this case, the `ConstructorBuilder` type).

The `Emit()` method of the `ILGenerator` class is the entity in charge of placing CIL into a member implementation. `Emit()` itself makes frequent use of the `OpCodes` class type, which exposes the opcode set of CIL using read-only fields. For example, `OpCodes.Ret` signals the return of a method call. `OpCodes.Stfld` makes an assignment to a member variable. `OpCodes.Call` is used to call a given method (in this case, the base class constructor). That said, ponder the following constructor logic:

```
// Create the custom constructor taking
// a single System.String argument.
Type[] constructorArgs = new Type[1];
constructorArgs[0] = typeof(string);
ConstructorBuilder constructor =
    helloWorldClass.DefineConstructor(MethodAttributes.Public,
        CallingConventions.Standard, constructorArgs);

// Now emit the necessary CIL into the ctor.
ILGenerator constructorIL = constructor.GetILGenerator();
constructorIL.Emit(OpCodes.Ldarg_0);
Type objectClass = typeof(object);
ConstructorInfo superConstructor = objectClass.GetConstructor(new Type[0]);
constructorIL.Emit(OpCodes.Call, superConstructor); // Call base class ctor.

// Load the object's "this" pointer on the stack.
constructorIL.Emit(OpCodes.Ldarg_0);

// Load incoming argument on virtual stack and store in msgField.
constructorIL.Emit(OpCodes.Ldarg_1);
constructorIL.Emit(OpCodes.Stfld, msgField); // Assign msgField.
constructorIL.Emit(OpCodes.Ret); // Return.
```

Now, as you are well aware, as soon as you define a custom constructor for a type, the default constructor is silently removed. To redefine the no-argument constructor, simply call the `DefineDefaultConstructor()` method of the `TypeBuilder` type as follows:

```
// Reinsert the default ctor.
helloWorldClass.DefineDefaultConstructor(MethodAttributes.Public);
```

This single call emits the standard CIL code used to define a default constructor:

```
.method public hidebysig specialname rtspecialname
    instance void  .ctor() cil managed
{
    .maxstack  1
    ldarg.0
    call  instance void [mscorlib]System.Object::ctor()
    ret
}
```

Emitting the `SayHello()` Method

Last but not least, let's examine the process of emitting the `SayHello()` method. The first task is to obtain a `MethodBuilder` type from the `helloWorldClass` variable. Once you do this, you define the method and obtain the underlying `ILGenerator` to inject the CIL instructions:

```
// Create the SayHello method.
MethodBuilder sayHiMethod =
    helloWorldClass.DefineMethod("SayHello",
        MethodAttributes.Public, null, null);
methodIL = sayHiMethod.GetILGenerator();

// Write a line to the Console.
methodIL.EmitWriteLine("Hello there!");
methodIL.Emit(OpCodes.Ret);
```

Here you have established a public method (`MethodAttributes.Public`) that takes no parameters and returns nothing (marked by the null entries contained in the `DefineMethod()` call). Also note the `EmitWriteLine()` call. This helper member of the `ILGenerator` class automatically writes a line to the standard output with minimal fuss and bother.

Using the Dynamically Generated Assembly

Now that you have the logic in place to create and save your assembly, all that's needed is a class to trigger the logic. To come full circle, assume your current project defines a second class named `AsmReader`. The logic in `Main()` obtains the current `AppDomain` via the `Thread.GetDomain()` method that will be used to host the assembly you will dynamically create. Once you have a reference, you are able to call the `CreateMyAsm()` method.

To make things a bit more interesting, once the call to `CreateMyAsm()` returns, you will exercise some late binding (see Chapter 15) to load your newly created assembly into memory and interact with the members of the `HelloWorld` class. Update your `Main()` method as follows:

```

static void Main(string[] args)
{
    Console.WriteLine("***** The Amazing Dynamic Assembly Builder App *****");
    // Get the application domain for the current thread.
    AppDomain curAppDomain = Thread.GetDomain();

    // Create the dynamic assembly using our helper f(x).
    CreateMyAsm(curAppDomain);
    Console.WriteLine("-> Finished creating MyAssembly.dll");

    // Now load the new assembly from file.
    Console.WriteLine("-> Loading MyAssembly.dll from file.");
    Assembly a = Assembly.Load("MyAssembly");

    // Get the HelloWorld type.
    Type hello = a.GetType("MyAssembly.HelloWorld");

    // Create HelloWorld object and call the correct ctor.
    Console.Write("-> Enter message to pass HelloWorld class: ");
    string msg = Console.ReadLine();
    object[] ctorArgs = new object[1];
    ctorArgs[0] = msg;
    object obj = Activator.CreateInstance(hello, ctorArgs);

    // Call SayHello and show returned string.
    Console.WriteLine("-> Calling SayHello() via late binding.");
    MethodInfo mi = hello.GetMethod("SayHello");
    mi.Invoke(obj, null);

    // Invoke method.
    mi = hello.GetMethod("GetMsg");
    Console.WriteLine(mi.Invoke(obj, null));
}

```

In effect, you have just created a .NET assembly that is able to create and execute .NET assemblies at runtime! That wraps up the examination of CIL and the role of dynamic assemblies. I hope this chapter has deepened your understanding of the .NET type system and the syntax and semantics of CIL.

■ Source Code The DynamicAsmBuilder project is included under the Chapter 17 subdirectory.

Summary

This chapter provided an overview of the syntax and semantics of CIL. Unlike higher-level managed languages such as C#, CIL does not simply define a set of keywords, but provides directives (used to define the structure of an assembly and its types), attributes (which further qualify a given directive), and opcodes (which are used to implement type members).

You were introduced to a few CIL-centric programming tools (`ilasm.exe`, SharpDevelop and `pverify.exe`), and learned how to alter the contents of a .NET assembly with new CIL instructions using round-trip engineering. After this point, you spent time learning how to establish the current (and referenced) assembly, namespaces, types and members. I wrapped up with a simple example of building a .NET code library and executable using little more than CIL, command line tools, and a bit of elbow grease.

Finally, you took an introductory look at the process of creating a *dynamic assembly*. Using the `System.Reflection.Emit` namespace, it is possible to define a .NET assembly in memory at runtime. As you have seen firsthand, using this particular API requires you to know the semantics of CIL code in some detail. While the need to build dynamic assemblies is certainly not a common task for most .NET applications, it can be very useful for those of you who need to build support tools and other programming utilities.



Dynamic Types and the Dynamic Language Runtime

.NET 4.0 introduces a new keyword to the C# language, specifically, `dynamic`. This keyword allows you to incorporate scripting like behaviors into the strongly typed world of semi-colons and curly brackets. Using this loose typing, you can greatly simplify some complex coding tasks and also gain the ability to interoperate with a number of dynamic languages (such as IronRuby or IronPython) which are .NET savvy.

In this chapter, you will learn all about the `dynamic` keyword, and understand how loosely typed calls are mapped to the correct in memory object using the *Dynamic Language Runtime* (or, DLR). Once you understand the services provided by the DLR, you will see examples of using dynamic types to streamline how you can perform late bound method calls (via reflection services) and to easily communicate with legacy COM libraries.

Note Don't confuse the C# `dynamic` keyword with the concept of a *dynamic assembly* (see Chapter 17). While you could use the `dynamic` keyword when building a dynamic assembly, these are ultimately two independent concepts.

The Role of the C# `dynamic` Keyword

Back in Chapter 3, you learned about the `var` keyword, which allows you to define local variable in such a way that the underlying date type is determined by the initial assignment (recall that this is termed *implicit typing*). Once this initial assignment has been made, you have a strongly typed variable, and any attempt to assign an incompatible value will result in a compiler error.

To begin your investigation into the C# `dynamic` keyword, create a new Console Application named `DynamicKeyword`. Now, author the following method in your `Program` class, and verify that the final code statement will indeed trigger a compile time error if uncommented:

```
static void ImplicitlyTypedVariable()
{
    // a is of type List<int>.
```

```

var a = new List<int>();
a.Add(90);

// This would be a compile time error!
// a = "Hello";
}

```

Using implicit typing simply for the sake of doing so is considered bad style (if you know you need a `List<int>`, just declare a `List<int>`). However, as you have seen in Chapter 13, implicit typing is very useful with LINQ, as many LINQ queries return back enumerations of anonymous class (via projections) which you cannot directly declare in your C# code. However even in such cases, the implicitly typed variable is, in fact, strongly typed.

On a related note, as you also learned back in Chapter 6, `System.Object` is the top-most parent class in the .NET framework, and can represent anything at all. Again, if you declare a variable of type `object`, you have a strongly typed piece of data, however what it points to in memory can differ based on your assignment of the reference. In order to gain access to the members the object reference is pointing to in memory, you need to perform an explicit cast.

Assume you have a simple class named `Person` that defines two automatic properties (`FirstName` and `LastName`) both encapsulating a `string`. Now, observe the following code:

```

static void UseObjectVariable()
{
    // Assume we have a class named Person.
    object o = new Person() { FirstName = "Mike", LastName = "Larson" };

    // Must cast object as Person to gain access
    // to the Person properties.
    Console.WriteLine("Person's first name is {0}", ((Person)o).FirstName);
}

```

With the release of .NET 4.0, the C# language now supports a new keyword named `dynamic`. From a high level, you can consider the `dynamic` keyword a specialized form of `System.Object`, in that any value can be assigned to a dynamic data type. At first glance, this can appear horribly confusing, as it appears you now have three ways to define data whose underlying type is not directly indicated in our code base. For example, this method:

```

static void PrintThreeStrings()
{
    var s1 = "Greetings";
    object s2 = "From";
    dynamic s3 = "Minneapolis";

    Console.WriteLine("s1 is of type: {0}", s1.GetType());
    Console.WriteLine("s2 is of type: {0}", s2.GetType());
    Console.WriteLine("s3 is of type: {0}", s3.GetType());
}

```

would print out the following if invoked from `Main()`:

```
s1 is of type: System.String
s2 is of type: System.String
s3 is of type: System.String
```

What makes a dynamic variable much (much) different from a variable declared implicitly or via a `System.Object` reference is that it is *not strongly typed*. Said another way, dynamic data is not *statically typed*. As far as the C# compiler is concerned, a data point declared with the `dynamic` keyword can be assigned any initial value at all, and can be reassigned to any new (and possibly unrelated) value during its lifetime. Consider the following method, and the resulting output:

```
static void ChangeDynamicDataType()
{
    // Declare a single dynamic data point
    // named 't'.
    dynamic t = "Hello!";
    Console.WriteLine("t is of type: {0}", t.GetType());

    t = false;
    Console.WriteLine("t is of type: {0}", t.GetType());

    t = new List<int>();
    Console.WriteLine("t is of type: {0}", t.GetType());
}
```

```
t is of type: System.String
t is of type: System.Boolean
t is of type: System.Collections.Generic.List`1[System.Int32]
```

Now, at this point in your investigation, do be aware that the previous code would compile and execute identically if you were to declare the `t` variable as a `System.Object`. However, as you will soon see, the `dynamic` keyword offers many additional features.

Calling Members on Dynamically Declared Data

Now, given that a dynamic data type can take on the identity of any type on the fly (just like a variable of type `System.Object`), the next question on your mind might be about calling members on the dynamic variable (properties, methods, indexers, register with events, etc). Well, syntactically speaking, it will again look no different. Just apply the dot operator to the dynamic data variable, specify a public member, and supply any arguments (if required).

However (and this is a very big “however”), the validity of the members you specify will not be checked by the compiler! Remember, unlike a variable defined as a `System.Object`, dynamic data is not statically typed. It is not until runtime that you will know if you invoked the dynamic data supports a specified member, if you passed in the correct parameters, spelled the member correctly, and so on. Thus, as strange as it might seem, the following method compiles perfectly:

```

static void InvokeMembersOnDynamicData()
{
    dynamic textData1 = "Hello";
    Console.WriteLine(textData1.ToUpper());

    // You would expect compiler errors here!
    // But they compile just fine.
    Console.WriteLine(textData1.toupper());
    Console.WriteLine(textData1.Foo(10, "ee", DateTime.Now));
}

```

Notice the second call to `WriteLine()` attempts to call a method named `toupper()` on the dynamic data point. As you can see, `textData1` is of type `string`, and therefore you know it does not have a method of this name in all lower case letters. Furthermore, `string` certainly does not have a method named `Foo()` which takes an `int`, `string` and `DateTime` object!

Nevertheless, the C# compiler is satisfied. However, if you invoke this method from within `Main()`, you will get runtime errors similar to the following output:

```
Unhandled Exception: Microsoft.CSharp.RuntimeBinder.RuntimeBinderException:
'string' does not contain a definition for 'toupper'
```

Another very big distinction between calling members on dynamic data and strongly typed data is that when you apply the dot operator to a piece of dynamic data, you will *not* see the expected Visual Studio 2010 IntelliSense. Instead, you will find the following general message (see Figure 18-1).




Figure 18-1. Dynamic data will not activate IntelliSense

It should make sense that IntelliSense is not possible with dynamic data. However remember that this means you need to be extremely careful when you are typing C# code on such data points! Any misspelling or incorrect capitalization of a member will throw a runtime error, specifically an instance of the `RuntimeBinderException` class.

The Role of the Microsoft.CSharp.dll Assembly

When you create a new Visual Studio 2010 C# project, you will automatically have a reference set to a new .NET 4.0 assembly named `Microsoft.CSharp.dll` (you can see this for yourself by looking in the References folder of the Solution Explorer). This library is very small, and only defines a single namespace (`Microsoft.CSharp.RuntimeBinder`) with two classes (see Figure 18-2).




Figure 18-2. The `Microsoft.CSharp.dll` Assembly

As you can tell by their names, both of these classes are strongly typed exceptions. The most common class, `RuntimeBinderException`, represents an error which will be thrown if you attempt to invoke a member on a dynamic data type which does not actually exist (as in the case of the `toupper()` and `Foo()` methods). This same error will be raised if you specify the wrong parameter data to a member which does exist.

Because dynamic data is so volatile, whenever you are invoking members on a variable declared with the C# `dynamic` keyword you could wrap the calls within a proper try/catch block, and handle the error in a graceful manner.

```
static void InvokeMembersOnDynamicData()
{
    dynamic textData1 = "Hello";

    try
    {
        Console.WriteLine(textData1.ToUpper());
        Console.WriteLine(textData1.toupper());
        Console.WriteLine(textData1.Foo(10, "ee", DateTime.Now));
    }
    catch (Microsoft.CSharp.RuntimeBinder.RuntimeBinderException ex)
    {
        Console.WriteLine(ex.Message);
    }
}
```

If you call this method again, you will find the call to `ToUpper()` (note the capital T and U) works correctly, however you then find the error data displayed to the console:

```
HELLO
'string' does not contain a definition for 'toupper'
```

Of course, the process of wrapping all dynamic method invocations in a try/catch block is rather tedious. As long as you watch your spelling, and parameter passing, this is not required. However, catching exceptions is handy when you might not know in advance if a member will be present on the target type.

The Scope of the dynamic keyword

Recall that implicitly typed data is only possible for local variables in a member scope. The var keyword can never be used as a return value, a parameter or a member of a class/structure. This is not the case with the `dynamic` keyword however. Consider the following class definition:

```
class VeryDynamicClass
{
    // A dynamic field.
    private static dynamic myDynamicField;

    // A dynamic property.
    public dynamic DynamicProperty { get; set; }

    // A dynamic return type and a dynamic parameter type.
    public dynamic DynamicMethod(dynamic dynamicParam)
    {
        // A dynamic local variable.
        dynamic dynamicLocalVar = "Local variable";

        int myInt = 10;

        if (dynamicParam is int)
        {
            return dynamicLocalVar;
        }
        else
        {
            return myInt;
        }
    }
}
```

You could now invoke the public members as expected, however as you are operating on dynamic methods and properties, you cannot be completely sure what the data type will be! To be sure, the `VeryDynamicClass` definition may not be very useful in a real world application, but it does illustrate the scope of where you can apply this C# keyword.

Limitations of the dynamic Keyword

While a great many things can be defined using the `dynamic` keyword, there are some limitations regarding its usage. While they are not show stoppers, do know that a dynamic data item cannot make use of lambda expressions or C# anonymous methods when calling a method. For example, the

following code will always result in errors, even if the target method does indeed take a delegate parameter which takes a `string` value and returns `void`.

```
dynamic a = GetDynamicObject();

// Error! Methods on dynamic data can't use lambdas!
a.Method(arg => Console.WriteLine(arg));
```

To circumvent this restriction, you will need to work with the underlying delegate directly, using the techniques described in Chapter 11 (anonymous methods and lambda expressions, etc). Another limitation is that a dynamic point of data cannot understand any extension methods (see Chapter 12). Unfortunately, this would also include any of the extension methods which come from the LINQ APIs. Therefore, a variable declared with the `dynamic` keyword has very limited use within LINQ to Objects and other LINQ technologies:

```
dynamic a = GetDynamicObject();

// Error! Dynamic data can't find the Select() extension method!
var data = from d in a select d;
```

Practical Uses of the `dynamic` Keyword

Given the fact that dynamic data is not strongly typed, not checked at compile time, has no ability to trigger IntelliSense and cannot be the target of a LINQ query, you are absolutely correct to assume that using the `dynamic` keyword just for the sake of doing so is very poor programming practice.

However, in a few circumstances, the `dynamic` keyword can radically reduce the amount of code you need to author by hand. Specifically, if you are building a .NET application which makes heavy use of late binding (via reflection), the `dynamic` keyword can save you typing time. As well, if you are building a .NET application that needs to communicate with legacy COM libraries (such as Microsoft Office products), you can greatly simplify your codebase via the `dynamic` keyword.

Like any “shortcut,” you need to weigh the pros and cons. The use of the `dynamic` keyword is a tradeoff between brevity of code, and type safety. While C# is a strongly typed language at its core, you can opt in (or opt out) dynamic behaviors on a call by call basis. Always remember that you never need to use the `dynamic` keyword. You could always get to the same end result by authoring alternative code by hand (and typically much more of it).

Source Code The `DynamicKeyword` project is located under the Chapter 18 subdirectory.

The Role of the Dynamic Language Runtime (DLR)

Now that you better understand what “dynamic data” is all about, let’s learn how it is processed. With the release of .NET 4.0, the Common Language Runtime (CLR) has a complementary runtime environment named the Dynamic Language Runtime (DLR). The concept of a ‘dynamic runtime’ is certainly not new. In fact, many programming languages such as Smalltalk, LISP, Ruby and Python have

used them for years. In a nutshell, a dynamic runtime allows a dynamic language the ability to discover types completely at runtime with no compile time checks.

If you have a background in strongly typed languages (including C#, without dynamic types) the very notion of such a runtime may seem undesirable. After all, you typically want to receive compile time errors, not runtime errors, wherever possible. Nevertheless, dynamic languages/runtimes do provide some interesting features including:

- An extremely flexible code base. You can refactor code without making numerous changes to data types.
- A very simple way to interoperate with diverse object types built in different platforms and programming languages.
- A way to add or remove members to a type, in memory, at runtime.

The role of the DLR is to enable various dynamic languages to run with the .NET runtime and give them a way to interoperate with other .NET code. Two popular dynamic languages which make use of the DLR are IronPython and IronRuby. These languages live in a dynamic universe, where type is discovered solely at runtime. And yet, these languages have access to the richness of the .NET base class libraries. Even better, their codebases can interoperate with C# (or vice versa), thanks to the inclusion of the `dynamic` keyword.

The Role of Expression Trees

The DLR makes use of *expression trees* to capture the meaning of a dynamic call in neutral terms. For example, when the DLR encounters some C# code such as the following:

```
dynamic d = GetSomeData();
d.SuperMethod(12);
```

It will automatically build an expression tree which says in effect “Call the method named `SuperMethod` on object `d`, passing in the number 12 as an argument”. This information (formally termed the *payload*) is then passed to the correct runtime binder, which again could be the C# dynamic binder, the IronPython dynamic binder, or even (as explained shortly) legacy COM objects.

From here, the request is mapped into the required call structure for the target object. The nice thing about these expression trees (beyond the fact that you don’t need to manually create them) is that this allows us to write a fixed C# code statement, and not worry about what the underlying target actually is (COM object, IronPython, or IronRuby codebase, etc). Figure 18-3 illustrates the concept of expression trees from a high level.




Figure 18-3. Expression trees capture dynamic calls in neutral terms and are processed by binders

The Role of the System.Dynamic Namespace

With the release of .NET 4.0, Microsoft introduced the `System.Dynamic` namespace within the `System.Core.dll` assembly. Truth be told, the chances that you will need to ever directly use the types within this namespace are slim to none. However, if you were a language vendor, who wanted to enable their dynamic languages to interact with the DLR, you could make use of `System.Dynamic` namespace to build a custom runtime binder.

Again, you won't need to directly dig into the types of `System.Dynamic` in this book, however feel free to check it out using the .NET Framework 4.0 SDK documentation if you are interested. For practical purposes, simply know that this namespace provides the necessary infrastructure to make a dynamic language ".NET aware".

Dynamic Runtime Lookup of Expression Trees

As explained, the DLR will pass the expression trees to a target object, however this dispatching will be influenced by a few factors. If the dynamic data type is pointing in memory to a COM object, the expression tree is sent to a low-level COM interface named `IDispatch`. As you may know, this interface was COM's way of incorporating its own set of dynamic services. COM objects, however, can be used in a .NET application without the use of the DLR or C# `dynamic` keyword. Doing so however (as you will see) tends to result in much more complex C# coding.

If the dynamic data is not pointing to a COM object, the expression tree may be passed to an object implementing the `IDynamicObject` interface. This interface is used behind the scenes to allow a language such as IronRuby to take a DLR expression tree and map it to Ruby-specifics.

Finally, if the dynamic data is pointing to an object which is *not* a COM object and does *not* implement `IDynamicObject`, the object is a normal, everyday .NET object. In this case, the expression tree is dispatched to the C# runtime binder for processing. The process of mapping the expression tree to .NET specifics involves reflection services.

Once the expression tree has been processed by a given binder, the dynamic data will be resolved to the real in-memory data type, after which the correct method is called with any necessary parameters. Now, let's see a few practical uses of the DLR, beginning with the simplification of late bound .NET calls.

Simplifying Late Bound Calls Using Dynamic Types

One place where you might decide to use the `dynamic` keyword is when you are working with reflection services, specifically when making late bound method calls. Back in Chapter 15, you saw a few examples of when this type of method call can be very useful, most commonly when you are building some type of extensible application. At that time, you learned how to use the `Activator.CreateInstance()` method to create an object, for which you have no compile time knowledge of (beyond its display name). You can then make use of the types of the `System.Reflection` namespace to invoke members via late binding. Recall the following example from Chapter 15.

```
static void CreateUsingLateBinding(Assembly asm)
{
    try
    {
        // Get metadata for the Minivan type.
        Type miniVan = asm.GetType("CarLibrary.MiniVan");

        // Create the Minivan on the fly.
        object obj = Activator.CreateInstance(miniVan);

        // Get info for TurboBoost.
        MethodInfo mi = miniVan.GetMethod("TurboBoost");

        // Invoke method ('null' for no parameters).
        mi.Invoke(obj, null);
    }
    catch (Exception ex)
    {
        Console.WriteLine(ex.Message);
    }
}
```

While this is code works as expected, you might agree it is a bit clunky. Here, you have to manually make use of the `MethodInfo` class, manually query the metadata, and so forth. The following is a version of this same method, now using the C# `dynamic` keyword and the DLR:

```
static void InvokeMethodWithDynamicKeyword(Assembly asm)
{
    try
    {
        // Get metadata for the Minivan type.
        Type miniVan = asm.GetType("CarLibrary.MiniVan");
```

```

// Create the Minivan on the fly and call method!
dynamic obj = Activator.CreateInstance(miniVan);
obj.TurboBoost();
}
catch (Exception ex)
{
    Console.WriteLine(ex.Message);
}
}

```

By declaring the `obj` variable using the `dynamic` keyword, the heavy lifting of reflection is done on your behalf courtesy of the DLR!

Leveraging the dynamic Keyword to Pass Arguments

The usefulness of the DLR becomes even more obvious when you need to make late bound calls on methods that take parameters. When you use “longhand” reflection calls, arguments need to be packaged up as an array of objects which are passed to the `Invoke()` method of `MethodInfo`.

To illustrate using a fresh example, begin by creating a new C# Console Application named `LateBindingWithDynamic`. Next, add a Class Library project to the current solution (using the `File | Add | New Project...` menu option) named `MathLibrary`. Rename the initial `Class1.cs` of the `MathLibrary` project to `SimpleMath.cs`, and implement the class like so:

```

public class SimpleMath
{
    public int Add(int x, int y)
    { return x + y; }
}

```

Once you have compiled your `MathLibrary.dll` assembly, place a copy of this library in the `\bin\Debug` folder of the `LateBindingWithDynamic` project (if you click the `Show All Files` button for each project of the Solution Explorer, you can simply drag and drop the file between projects). At this point, your Solution Explorer should look something like see Figure 18-4.




Figure 18-4. The LateBindingWithDynamic project has a private copy of MathLibrary.dll

■ **Note** Remember, the whole point of late binding is allowing an application to create an object for which it has no record of it the MANIFEST. This is why you manually copied MathLibrary.dll into the output folder of the Console project, rather than reference the assembly using Visual Studio.

Now, import the System.Reflection namespace into the Program.cs file of your Console Application project. Next, add the following method to the Program class, which invokes the Add() method using typical reflection API calls:

```
private static void AddWithReflection()
{
    Assembly asm = Assembly.Load("MathLibrary");

    try
    {
        // Get metadata for the SimpleMath type.
        Type math = asm.GetType("MathLibrary.SimpleMath");
```

```

// Create a SimpleMath on the fly.
object obj = Activator.CreateInstance(math);

// Get info for Add.
MethodInfo mi = math.GetMethod("Add");

// Invoke method (with parameters).
object[] args = { 10, 70 };
Console.WriteLine("Result is: {0}", mi.Invoke(obj, args));
}
catch (Exception ex)
{
    Console.WriteLine(ex.Message);
}
}

```

Now, consider the simplification of the previous logic with the `dynamic` keyword:

```

private static void AddWithDynamic()
{
    Assembly asm = Assembly.Load("MathLibrary");

    try
    {
        // Get metadata for the SimpleMath type.
        Type math = asm.GetType("MathLibrary.SimpleMath");

        // Create a SimpleMath on the fly.
        dynamic obj = Activator.CreateInstance(math);
        Console.WriteLine("Result is: {0}", obj.Add(10, 70));
    }
    catch (Microsoft.CSharp.RuntimeBinder.RuntimeBinderException ex)
    {
        Console.WriteLine(ex.Message);
    }
}

```

Not too shabby! If you call both methods from the `Main()` method, you'll see identical output. However, when using the `dynamic` keyword, you saved yourself quite a bit of work. With dynamically defined data, you no longer need to manually package up arguments as an array of objects, query the assembly metadata, or other such details.

Source Code The `LateBindingWithDynamic` project is included under the Chapter 18 subdirectory.

Simplifying COM Interoperability using Dynamic Data

Let's see another useful case for the `dynamic` keyword within the context of a COM interoperability project. Now, if you don't have much background in COM development, do be aware for this next example that a compiled COM library contains metadata, just like a .NET library; however, the format is completely different. Because of this, if a .NET program needs to use a COM object, the first order of business is to generate what is known as an "interop assembly" (described in the following) using Visual Studio 2010. Doing so is quite straightforward. Just activate the Add Reference dialog box, select the COM tab and find the COM library you wish to make use of (see Figure 18-5).




Figure 18-5. The COM tab of the Add Reference dialog box will show you all registered COM libraries on your machine

Once you select a COM library, the IDE will respond by generating a brand new assembly which contains .NET descriptions of COM metadata. Formally speaking, these are termed "interop assemblies" (or simply, *interop assemblies*). Interop assemblies do not contain any implementation code, except for a small amount that helps translate COM events to .NET events. However, these interop assemblies are very useful in that they shield your .NET codebase from the complex underbelly of COM internals.

In your C# code, you can directly program against the interop assembly, allowing the CLR (and if you use the `dynamic` keyword, the DLR) to automatically map .NET data types into COM types, and vice versa. Behind the scenes, data is marshaled between the .NET and COM applications using a Runtime Callable Wrapper (RCW), which is basically a dynamically generated proxy. This RCW proxy will marshal and transform .NET data types into COM types, adjust the COM object's reference counter, and map any COM return values into .NET equivalents. Figure 18-6 shows the big picture of .NET to COM interoperability.




Figure 18-6. .NET programs communicate with COM objects using a proxy termed the RCW

The Role of Primary Interop Assemblies (PIAs)

Many COM libraries created by COM library vendors (such as the Microsoft COM libraries that allow access to the object model of Microsoft Office products) provide an “official” interoperability assembly termed a *primary interop assembly* or PIA. PIAs are optimized interop assemblies, which clean up (and possibly extend) the code typically generated when referencing a COM library using the Add Reference dialog box.

PIAs are typically listed in the .NET tab of the Add Reference dialog box, just like the core .NET libraries. In fact, if you reference a COM library from the COM tab of the Add Reference dialog box, Visual Studio will not generate a new interoperability library as it would normally do, but use the provided PIA instead. Figure 18-7 shows the PIA of the Microsoft Office Excel object model, which you will be using in the next example.




Figure 18-7. PIAs are listed in the .NET tab of the Add Reference dialog box

Embedding Interop Metadata

Before the release of .NET 4.0, when a C# application made use of a COM library (PIA or not), you needed to ensure the client machine has a copy of the interop assembly on their computer. Not only will this increase the size of your application installer package, but the install script must check that the PIA assemblies are indeed present, and if not, install a copy to the GAC.

However, under .NET 4.0, you can now elect to embed the interoperability data directly within your compiled .NET application. When you do so, you are no longer required to ship a copy of the interoperability assembly along with your .NET application, as the necessary interoperability metadata is hardcoded in the .NET program.

By default, when you select a COM library (PIA or not) using the Add References dialog, the IDE will automatically set the Embed Interop Types property of the library to True. You can see this setting first hand by selecting a referenced interop library in the References folder of the Solution Explorer, and then investigate the Properties window (see Figure 18-8).




Figure 18-8. .NET 4.0 allows you to embed the parts of an interop assemblies you make use of into your .NET assembly

The C# compiler will only include the parts of the interop library you are actually making use of. Thus, if the real interop library has .NET descriptions of hundreds of COM objects, you will only bring in the definitions of the subset you are really making use of in your C# code. Beyond reducing the size of the application you need to ship to the client, you also have an easier installation path, as you don't need to install any missing PIAs on the target machine.

Common COM Interop Pain Points

When you are authoring C# code that programs against a COM library (via the interop assembly), you were sure to face a number of challenges before the release of .NET 4.0. For example, many COM libraries defined methods which took optional arguments, which were not supported in C# until the current release. This required you to specify the value `Type.Missing` for every occurrence of the optional argument. For example, if a COM method took five arguments, all of which were optional, you would need to write the following C# code in order to accept the default values:

```
myComObj.SomeMethod(Type.Missing, Type.Missing, Type.Missing, Type.Missing, Type.Missing);
```

Thankfully, under .NET 4.0, you are now able to author the following simplified code, given that the `Type.Missing` values will be inserted at compile time if you don't specify a true blue value.

```
myComObj.SomeMethod();
```

On a related note, many COM methods provided support for named arguments, which as you recall from Chapter 4, allows you to pass values to members in any order you require. Given that C# supports this same feature as of .NET 4.0, it is very simply to "skip" over a set of optional arguments you don't care about, and only set the few you do.

Another common COM interop pain point has to do with the fact that many COM methods were designed to take and return a very particular data type termed the **Variant**. Much like the C# dynamic

keyword, a Variant data type could be assigned to any type of COM data on the fly (strings, interface references, numerical values, etc). Before you had the dynamic keyword, passing or receiving Variant data points required some hoop jumping, typically by way of numerous casting operations.

As of .NET 4.0 and Visual Studio 2010, when you set the Embed Interop Types property to True, all COM variants are automatically mapped to dynamic data. This will not only reduce the need to extraneous casting operations when working with underlying COM Variant data types, but will also further hide some COM-complexities, such as working with COM indexers.

To showcase how the use of C# optional arguments, named arguments and the dynamic keyword all work together to simplify COM interop, you will now build an application which makes use of the Microsoft Office object model. As you work through the example, you will get a chance to make use of the new features, as well as forgo them, and then compare and contrast the workload.

Note Previous editions of this book included a detailed examination of how to make use of legacy COM objects in your .NET projects using the System.Runtime.InteropServices namespace. In the current edition, I have opted to omit that chapter, as the dynamic keyword can be used to communicate with COM objects with far fewer pain points. If you wish to see how to communicate with COM objects in a strongly typed (longhand) notation, consult the .NET Framework 4.0 SDK documentation.

COM Interop using C# 4.0 Language Features

Assume you have a Windows Form GUI application (named ExportDataToOfficeApp), whose main Form defines a DataGridView named dataGridViewCars. This same form has two Button controls, one of which will bring up a dialog box to insert a new row of data to the grid, and the other of which needs to export the grid's data to an Excel spreadsheet. Given the fact that the Excel application exposes a programming model via COM, you can hook into this object model using the interoperability layer. Figure 18-9 shows the completed GUI.




Figure 18-9. The GUI of the COM interop example

You will fill the grid with some initial data by handling the form's Load event as so (the Car class used as the type parameter for the generic List<T> is a simple class in the project with Color, Make, and PetName properties):

```
public partial class MainForm : Form
{
    List<Car> carsInStock = null;

    public MainForm()
    {
        InitializeComponent();
    }

    private void MainForm_Load(object sender, EventArgs e)
    {
        carsInStock = new List<Car>
        {
            new Car {Color="Green", Makes="VW", PetName="Mary"},
            new Car {Color="Red", Make="Saab", PetName="Mel"},
            new Car {Color="Black", Make="Ford", PetName="Hank"},
            new Car {Color="Yellow", Make="BMW", PetName="Davie"}
        };
        UpdateGrid();
    }

    private void UpdateGrid()
    {
        // Reset the source of data.
        dataGridCars.DataSource = null;
        dataGridCars.DataSource = carsInStock;
    }
}
```

The Click event for the “Add” button will launch a custom dialog box to allow the user to enter new data for a Car object, and if they click the OK button, the data is added to the grid. I won't bother to show the code behind the dialog box, so please see the provided solution for details. If you are following however, include the NewCarDialog.cs, NewCarDialog.designer.cs and NewCarDialog.resx files into your project (all of which are part of the code download for this text). Once you have done so, implement the “Add” button click hander as so:

```
private void btnAddNewCar_Click(object sender, EventArgs e)
{
    NewCarDialog d = new NewCarDialog();
    if (d.ShowDialog() == DialogResult.OK)
    {
        // Add new car to list.
        carsInStock.Add(d.theCar);
        UpdateGrid();
    }
}
```

The Click event handler for the , “Export” button is the heart of this example. Using the .NET tab of the Add Reference... dialog box, add a reference to the Microsoft.Office.Interop.Excel.dll primary interop assembly (as shown previously in Figure 18-7). Add the following namespace alias to the form’s primary code file. Be aware that this is not mandatory to define an alias when interacting with COM libraries. However, by doing so, you have a handy qualifier for all of the imported COM objects, which is very handy if some of these COM objects have names which would clash with your .NET types:

```
// Create an alias to the Excel object model.
using Excel = Microsoft.Office.Interop.Excel;
```

Implement this button Click event handler to call a private helper function named ExportToExcel():

```
private void btnExportToExcel_Click(object sender, EventArgs e)
{
    ExportToExcel(carsInStock);
}
```

Because you imported the COM library using Visual Studio 2010, the PIA has been automatically configured so that the used metadata will be embedded into the .NET application (recall the role of the Embed Interop Types property). Therefore, all COM Variants are realized as dynamic data types. Furthermore, because you are compiling your code with C# 4.0, you can make use of optional arguments and named arguments. This being said consider the following implementation of ExportToExcel():

```
static void ExportToExcel(List<Car> carsInStock)
{
    // Load up Excel, then make a new empty workbook.
    Excel.Application excelApp = new Excel.Application();
    excelApp.Workbooks.Add();

    // This example uses a single workSheet.
    Excel._Worksheet workSheet = excelApp.ActiveSheet;

    // Establish column headings in cells.
    workSheet.Cells[1, "A"] = "Make";
    workSheet.Cells[1, "B"] = "Color";
    workSheet.Cells[1, "C"] = "Pet Name";

    // Now, map all data in List<Car> to the cells of the spread sheet.
    int row = 1;
    foreach (Car c in carsInStock)
    {
        row++;
        workSheet.Cells[row, "A"] = c.Make;
        workSheet.Cells[row, "B"] = c.Color;
        workSheet.Cells[row, "C"] = c.PetName;
    }

    // Give our table data a nice look and feel.
    workSheet.Range["A1"].AutoFormat(
        Excel.XlRangeAutoFormat.xlRangeAutoFormatClassic2);
```

```

// Save the file, quit Excel and display message to user.
workSheet.SaveAs(string.Format("{0}\Inventory.xlsx", Environment.CurrentDirectory));
excelApp.Quit();
MessageBox.Show("The Inventory.xlsx file has been saved to your app folder",
    "Export complete!");
}

```

This method begins by loading Excel into memory, however you won't see it visible on your computer desktop. For this application, you are only interested in using the internal Excel object model. However, if you do want to actually display the UI of Excel, update your method with this additional line of code:

```

static void ExportToExcel(List<Car> carsInStock)
{
    // Load up Excel, then make a new empty workbook.
    Excel.Application excelApp = new Excel.Application();

    // Go ahead and make Excel visible on the computer.
    excelApp.Visible = true;

    ...
}

```

Once you create an empty worksheet, you add three columns which are named similar to the properties of the Car class. After this point, you fill the cells with the data of the `List<Car>`, and save your file under the (hard coded) name `Inventory.xlsx`.

At this point if you run your application, add a few new records, and export your data to Excel, you will then be able to open up the `Inventory.xlsx` file, which will be saved to the `\bin\Debug` folder of your Windows Forms application. Figure 18-10 shows a possible export.




Figure 18-10. Exporting your data to an Excel file

COM interop without C# 4.0 Language Features

Now, if you were to select the `Microsoft.Office.Interop.Excel.dll` assembly (in Solution Explorer), and set its `Embed Interop Type` property to `False`, you would have new compiler errors, as the COM Variant data is no longer realized as dynamic data, but as `System.Object` variables. This will require you to update `ExportToExcel()` with a number of casting operations. As well, if this project were compiled under Visual Studio 2008, you no longer have the benefit of optional/named parameters, and must explicitly mark all missing arguments. Here is a version of the `ExportToExcel()` method which would be required in earlier versions of C#:

```
static void ExportToExcel2008(List<Car> carsInStock)
{
    Excel.Application excelApp = new Excel.Application();

    // Must mark missing params!
    excelApp.Workbooks.Add(Type.Missing);

    // Must cast Object as _Worksheet!
    Excel._Worksheet workSheet = (Excel._Worksheet)excelApp.ActiveSheet;

    // Must cast each Object as Range object then call
    // call low level Value2 property!
    ((Excel.Range)excelApp.Cells[1, "A"]).Value2 = "Make";
    ((Excel.Range)excelApp.Cells[1, "B"]).Value2 = "Color";
    ((Excel.Range)excelApp.Cells[1, "C"]).Value2 = "Pet Name";

    int row = 1;
    foreach (Car c in carsInStock)
    {
        row++;
        // Must cast each Object as Range and call low level Value2 prop!
        ((Excel.Range)workSheet.Cells[row, "A"]).Value2 = c.Make;
        ((Excel.Range)workSheet.Cells[row, "B"]).Value2 = c.Color;
        ((Excel.Range)workSheet.Cells[row, "C"]).Value2 = c.PetName;
    }

    // Must call get_Range method and then specify all missing args!.
    excelApp.get_Range("A1", Type.Missing).AutoFormat(
        Excel.XlRangeAutoFormat.xlRangeAutoFormatClassic2,
        Type.Missing, Type.Missing, Type.Missing,
        Type.Missing, Type.Missing, Type.Missing);

    // Must specify all missing optional args!
    workSheet.SaveAs(string.Format("{0}\Inventory.xlsx", Environment.CurrentDirectory),
        Type.Missing, Type.Missing, Type.Missing, Type.Missing, Type.Missing,
        Type.Missing, Type.Missing, Type.Missing);

    excelApp.Quit();
    MessageBox.Show("The Inventory.xlsx file has been saved to your app folder",
        "Export complete!");
}
```

While the end result is identical, as I am sure you agree, this version of the method is much more verbose. As well, since earlier versions of C# (prior to .NET 4.0, to be specific) don't allow you to embedd the COM interop data, you would find that your output directory now contains local copies of a number of interop assemblies, which you would be required to ship to the end user's machine (Figure 18-11).




Figure 18-11. Not embedding interop data requires you to ship standalone interoperability assemblies

That wraps up our look at the C# dynamic keyword and the DLR. Hopefully you can see how these new .NET 4.0 features can simplify complex programming tasks, and (perhaps more importantly) understand the trade offs. When you opt into dynamic data, you do lose a good amount of type safety, and your code base is prone to many more runtime errors.

■ **Source Code** The ExportDataToOfficeApp project is included under the Chapter 18 subdirectory.

Summary

The `dynamic` keyword of C# 4.0 allows you to define data whose true identity is not known until runtime. When processed by the new Dynamic Language Runtime (DLR), the automatically created “expression

tree” will be passed to the correct dynamic language binder, where the payload will be unpackaged and sent to the correct object member.

Using dynamic data and the DLR, a number of complex C# programming tasks can be radically simplified, especially the act of incorporating COM libraries into your .NET applications. As you have also seen in this chapter, .NET 4.0 provides a number of further simplifications to COM interop (which have nothing to do with dynamic data) such as embedding COM interop data into your applications, optional arguments and named arguments.

While these features can certainly simplify your code, always remember that dynamic data makes your C# code much less type safe, and open to runtime errors. Be sure you weigh the pros and cons of using dynamic data in your C# projects, and test accordingly!

PART 5

■ ■ ■

Introducing the .NET Base Class Libraries



Multithreaded and Parallel Programming

Nobody enjoys working with an application which is slow and sluggish during its execution. Moreover, nobody enjoys starting a task in an application (perhaps initiated by the clicking of a toolbar item) which prevents other parts of the program from being as responsive as possible. Before the release of .NET, building applications that had the ability to perform multiple tasks required authoring very complex C++ code and the Windows threading APIs. Thankfully, the .NET platform provides a number of ways for you to build software which can perform complex operations on unique paths of execution, with far less fuss and bother.

This chapter begins by revisiting the .NET delegate type to investigate its intrinsic support for *asynchronous method invocations*. As you'll see, this technique allows you to invoke a method on a secondary thread of execution without needing to manually create or configure the thread itself.

Next, you'll be introduced to the `System.Threading` namespace. Here you'll examine numerous types (`Thread`, `ThreadStart`, etc.) that allow you to easily create additional threads of execution. As well, you will learn about various synchronization primitives that the .NET Framework provides, which helps ensure that multiple threads can share data in a non-volatile manner.

The final part of this chapter will examine the brand new .NET 4.0 Task Parallel Library (TPL) and PLINQ (Parallel LINQ). Using these APIs, you can program against a set of higher level types, which do a good deal to manage thread details on your behalf.

The Process/AppDomain/Context/Thread Relationship

In Chapter 16, a *thread* was defined as a path of execution within an executable application. While many .NET applications can live happy and productive single-threaded lives, an assembly's primary thread (spawned by the CLR when `Main()` executes) may create secondary threads of execution to perform additional units of work. By implementing additional threads, you can build more responsive (but not necessarily faster executing on single-core machines) applications.

Note These days it is quite common for new computers to make use of multicore processors (or at very least a hyperthreaded single-core processor). Without making use of multiple threads, developers are unable to exploit the full power of multicore machines.

The `System.Threading` namespace contains various types that allow you to create multithreaded applications. The `Thread` class is perhaps the core type, as it represents a given thread. If you wish to programmatically obtain a reference to the thread currently executing a given member, simply call the static `Thread.CurrentThread` property:

```
static void ExtractExecutingThread()
{
    // Get the thread currently
    // executing this method.
    Thread currThread = Thread.CurrentThread;
}
```

Under the .NET platform, there is *not* a direct one-to-one correspondence between application domains and threads. In fact, a given `AppDomain` can have numerous threads executing within it at any given time. Furthermore, a particular thread is not confined to a single application domain during its lifetime. Threads are free to cross application domain boundaries as the Windows thread scheduler and CLR see fit.

Although active threads can be moved between `AppDomain` boundaries, a given thread can execute within only a single application domain at any point in time (in other words, it is impossible for a single thread to be doing work in more than one `AppDomain` at once). When you wish to programmatically gain access to the `AppDomain` that is hosting the current thread, call the static `Thread.GetDomain()` method:

```
static void ExtractAppDomainHostingThread()
{
    // Obtain the AppDomain hosting the current thread.
    AppDomain ad = Thread.GetDomain();
}
```

A single thread may also be moved into a particular context at any given time, and it may be relocated within a new context at the whim of the CLR. When you wish to obtain the current context a thread happens to be executing in, make use of the static `Thread.CurrentContext` property (which returns a `System.Runtime.Remoting.Contexts.Context` object):

```
static void ExtractCurrentThreadContext()
{
    // Obtain the context under which the
    // current thread is operating.
    Context ctx = Thread.CurrentContext;
}
```

Again, the CLR is the entity that is in charge of moving threads into (and out of) application domains and contexts. As a .NET developer, you can usually remain blissfully unaware where a given thread ends up (or exactly when it is placed into its new boundary). Nevertheless, you should be aware of the various ways of obtaining the underlying primitives.

The Problem of Concurrency

One of the many “joys” (read: painful aspects) of multithreaded programming is that you have little control over how the underlying operating system or the CLR makes use of its threads. For example, if you craft a block of code that creates a new thread of execution, you cannot guarantee that the thread

executes immediately. Rather, such code only instructs the OS to execute the thread as soon as possible (which is typically when the thread scheduler gets around to it).

Furthermore, given that threads can be moved between application and contextual boundaries as required by the CLR, you must be mindful of which aspects of your application are *thread-volatile* (e.g., subject to multithreaded access) and which operations are *atomic* (thread-volatile operations are the dangerous ones!).

To illustrate the problem, assume a thread is invoking a method of a specific object. Now assume that this thread is instructed by the thread scheduler to suspend its activity, in order to allow another thread to access the same method of the same object.

If the original thread was not completely finished with its operation, the second incoming thread may be viewing an object in a partially modified state. At this point, the second thread is basically reading bogus data, which is sure to give way to extremely odd (and very hard to find) bugs, which are even harder to replicate and debug.

Atomic operations, on the other hand, are always safe in a multithreaded environment. Sadly, there are very few operations in the .NET base class libraries that are guaranteed to be atomic. Even the act of assigning a value to a member variable is not atomic! Unless the .NET Framework 4.0 SDK documentation specifically says an operation is atomic, you must assume it is thread-volatile and take precautions.

The Role of Thread Synchronization

At this point, it should be clear that multithreaded application domains are in themselves quite volatile, as numerous threads can operate on the shared resources at (more or less) the same time. To protect an application's resources from possible corruption, .NET developers must make use of any number of threading primitives (such as locks, monitors, and the [Synchronization] attribute) to control access among the executing threads.

Although the .NET platform cannot make the difficulties of building robust multithreaded applications completely disappear, the process has been simplified considerably. Using types defined within the `System.Threading` namespace, and the .NET 4.0 Task Parallel Library (TPL), you are able to spawn additional threads with minimal fuss and bother. Likewise, when it is time to lock down shared points of data, you will find additional types that provide the same functionality as the Windows API threading primitives (using a much cleaner object model).

Before diving into the `System.Threading` namespace and the TPL, it is important to note that there is one other useful way to incorporate threads into an application. During the examination of the .NET delegate (see Chapter 11), it was mentioned that all delegates have the ability to invoke members asynchronously. This is a *major* benefit of the .NET platform, given that one of the most common reasons a developer creates threads is for the purpose of invoking methods in a nonblocking (a.k.a. asynchronous) manner.

A Brief Review of the .NET Delegate

Recall that the .NET delegate type is essentially a type-safe, object-oriented, function pointer. When you declare a .NET delegate, the C# compiler responds by building a sealed class that derives from `System.MulticastDelegate` (which in turn derives from `System.Delegate`). These base classes provide every delegate with the ability to maintain a list of method addresses, all of which may be invoked at a later time. Consider the `BinaryOp` delegate first defined in Chapter 11:

```
// A C# delegate type.
public delegate int BinaryOp(int x, int y);
```

Based on its definition, `BinaryOp` can point to any method taking two integers (by value) as arguments and returning an integer. Once compiled, the defining assembly now contains a full-blown class definition that is dynamically generated when you build your project, based on the delegate declaration. In the case of `BinaryOp`, this class looks more or less like the following (shown in pseudo-code):

```
public sealed class BinaryOp : System.MulticastDelegate
{
    public BinaryOp(object target, uint functionAddress);
    public void Invoke(int x, int y);
    public IAsyncResult BeginInvoke(int x, int y,
        AsyncCallback cb, object state);
    public int EndInvoke(IAsyncResult result);
}
```

Recall that the generated `Invoke()` method is used to invoke the methods maintained by a delegate object in a *synchronous manner*. Therefore, the calling thread (such as the primary thread of the application) is forced to wait until the delegate invocation completes. Also recall that in C#, the `Invoke()` method does not need to be directly called in code, but can be triggered indirectly under the hood when applying “normal” method invocation syntax.

Consider the following Console Application program (`SyncDelegateReview`), which invokes the static `Add()` method in a synchronous (a.k.a. blocking) manner (be sure to import the `System.Threading` namespace, as you will be calling the `Thread.Sleep()` method).

```
namespace SyncDelegateReview
{
    public delegate int BinaryOp(int x, int y);

    class Program
    {
        static void Main(string[] args)
        {
            Console.WriteLine("***** Synch Delegate Review *****");

            // Print out the ID of the executing thread.
            Console.WriteLine("Main() invoked on thread {0}.",
                Thread.CurrentThread.ManagedThreadId);

            // Invoke Add() in a synchronous manner.
            BinaryOp b = new BinaryOp(Add);

            // Could also write b.Invoke(10, 10);
            int answer = b(10, 10);

            // These lines will not execute until
            // the Add() method has completed.
            Console.WriteLine("Doing more work in Main()!");
            Console.WriteLine("10 + 10 is {0}.", answer);
            Console.ReadLine();
        }

        static int Add(int x, int y)
```

```

{
    // Print out the ID of the executing thread.
    Console.WriteLine("Add() invoked on thread {0}.",
        Thread.CurrentThread.ManagedThreadId);

    // Pause to simulate a lengthy operation.
    Thread.Sleep(5000);
    return x + y;
}
}

```

Within the `Add()` method, you are invoking the static `Thread.Sleep()` method to suspend the calling thread for approximately five seconds to simulate a lengthy task. Given that you are invoking the `Add()` method in a *synchronous* manner, the `Main()` method will not print out the result of the operation until the `Add()` method has completed.

Next, note that the `Main()` method is obtaining access to the current thread (via `Thread.CurrentThread`) and printing out the ID of the thread via the `ManagedThreadId` property. This same logic is repeated in the static `Add()` method. As you might suspect, given that all the work in this application is performed exclusively by the primary thread, you find the same ID value displayed to the console:

```
***** Synch Delegate Review *****
Main() invoked on thread 1.
Add() invoked on thread 1.
Doing more work in Main()!
10 + 10 is 20.
```

Press any key to continue . . .

When you run this program, you should notice that a five-second delay takes place before you see the final `Console.WriteLine()` logic in `Main()` execute. Although many (if not most) methods may be called synchronously without ill effect, .NET delegates can be instructed to call their methods asynchronously if necessary.

Source Code The `SyncDelegateReview` project is located under the Chapter 19 subdirectory.

The Asynchronous Nature of Delegates

If you are new to the topic of multithreading, you may wonder what exactly an *asynchronous* method invocation is all about. As you are no doubt fully aware, some programming operations take time. Although the previous `Add()` was purely illustrative in nature, imagine that you built a single-threaded application that is invoking a method on a remote object, performing a long-running database query, downloading a large document, or writing 500 lines of text to an external file. While performing these operations, the application will appear to hang for some amount of time. Until the task at hand has been

processed, all other aspects of this program (such as menu activation, toolbar clicking, or console output) are unresponsive.

The question therefore is, how can you tell a delegate to invoke a method on a separate thread of execution to simulate numerous tasks performing “at the same time”? The good news is that every .NET delegate type is automatically equipped with this capability. The even better news is that you are *not* required to directly dive into the details of the `System.Threading` namespace to do so (although these entities can quite naturally work hand in hand).

The BeginInvoke() and EndInvoke() Methods

When the C# compiler processes the `delegate` keyword, the dynamically generated class defines two methods named `BeginInvoke()` and `EndInvoke()`. Given the definition of the `BinaryOp` delegate, these methods are prototyped as follows:

```
public sealed class BinaryOp : System.MulticastDelegate
{
    ...
    // Used to invoke a method asynchronously.
    public IAsyncResult BeginInvoke(int x, int y,
        AsyncCallback cb, object state);

    // Used to fetch the return value
    // of the invoked method.
    public int EndInvoke(IAsyncResult result);
}
```

The first stack of parameters passed into `BeginInvoke()` will be based on the format of the C# delegate (two integers in the case of `BinaryOp`). The final two arguments will always be `System.AsyncCallback` and `System.Object`. You’ll examine the role of these parameters shortly; for the time being, though, I’ll supply `null` for each. Also note that the return value of `EndInvoke()` is an integer, based on the return type of `BinaryOp`, while the parameter of this method is of type `IAsyncResult`.

The System.IAsyncResult Interface

The `BeginInvoke()` method always returns an object implementing the `IAsyncResult` interface, while `EndInvoke()` requires an `IAsyncResult`-compatible type as its sole parameter. The `IAsyncResult`-compatible object returned from `BeginInvoke()` is basically a coupling mechanism that allows the calling thread to obtain the result of the asynchronous method invocation at a later time via `EndInvoke()`. The `IAsyncResult` interface (defined in the `System` namespace) is defined as follows:

```
public interface IAsyncResult
{
    object AsyncState { get; }
    WaitHandle AsyncWaitHandle { get; }
    bool CompletedSynchronously { get; }
    bool IsCompleted { get; }
}
```

In the simplest case, you are able to avoid directly invoking these members. All you have to do is cache the `IAsyncResult`-compatible object returned by `BeginInvoke()` and pass it to `EndInvoke()` when

you are ready to obtain the result of the method invocation. As you will see, you are able to invoke the members of an `IAsyncResult`-compatible object when you wish to become “more involved” with the process of fetching the method’s return value.

Note If you asynchronously invoke a method that provides a `void` return value, you can simply “fire and forget.” In such cases, you will never need to cache the `IAsyncResult` compatible object or call `EndInvoke()` in the first place (as there is no return value to retrieve).

Invoking a Method Asynchronously

To instruct the `BinaryOp` delegate to invoke `Add()` asynchronously, you will modify the logic in the previous project (feel free to add code to the existing project, however in your lab downloads, you will find a new Console Application named `AsyncDelegate`). Update the previous `Main()` method as follows:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Async Delegate Invocation *****");

    // Print out the ID of the executing thread.
    Console.WriteLine("Main() invoked on thread {0}.",
        Thread.CurrentThread.ManagedThreadId);

    // Invoke Add() on a secondary thread.
    BinaryOp b = new BinaryOp(Add);
    IAsyncResult iftAR = b.BeginInvoke(10, 10, null, null);

    // Do other work on primary thread...
    Console.WriteLine("Doing more work in Main()!");

    // Obtain the result of the Add()
    // method when ready.
    int answer = b.EndInvoke(iftAR);
    Console.WriteLine("10 + 10 is {0}.", answer);
    Console.ReadLine();
}
```

If you run this application, you will find that two unique thread IDs are displayed, given that there are in fact multiple threads working within the current AppDomain:

```
***** Async Delegate Invocation *****
Main() invoked on thread 1.
Doing more work in Main()!
Add() invoked on thread 3.
10 + 10 is 20.
```

In addition to the unique ID values, you will also notice upon running the application that the Doing more work in Main()! message displays immediately, while the secondary thread is occupied attending to its business.

Synchronizing the Calling Thread

If you think carefully about the current implementation of `Main()`, you might have realized that the time span between calling `BeginInvoke()` and `EndInvoke()` is clearly less than five seconds. Therefore, once Doing more work in Main()! prints to the console, the calling thread is now blocked and waiting for the secondary thread to complete before being able to obtain the result of the `Add()` method. Therefore, you are effectively making yet another *synchronous call*:

```
static void Main(string[] args)
{
...
    BinaryOp b = new BinaryOp(Add);

    // Once the next statement is processed,
    // the calling thread is now blocked until
    // BeginInvoke() completes.
    IAsyncResult iftAR = b.BeginInvoke(10, 10, null, null);

    // This call takes far less than five seconds!
    Console.WriteLine("Doing more work in Main()!");

    int answer = b.EndInvoke(iftAR);
}
}
```

Obviously, asynchronous delegates would lose their appeal if the calling thread had the potential of being blocked under various circumstances. To allow the calling thread to discover if the asynchronously invoked method has completed its work, the `IAsyncResult` interface provides the `IsCompleted` property. Using this member, the calling thread is able to determine whether the asynchronous call has indeed completed before calling `EndInvoke()`.

If the method has not completed, `IsCompleted` returns `false`, and the calling thread is free to carry on its work. If `IsCompleted` returns `true`, the calling thread is able to obtain the result in the “least blocking manner” possible. Ponder the following update to the `Main()` method:

```
static void Main(string[] args)
{
...
    BinaryOp b = new BinaryOp(Add);
    IAsyncResult iftAR = b.BeginInvoke(10, 10, null, null);

    // This message will keep printing until
    // the Add() method is finished.
    while(!iftAR.IsCompleted)
    {
        Console.WriteLine("Doing more work in Main()!");
        Thread.Sleep(1000);
    }
}
```

```
// Now we know the Add() method is complete.
int answer = b.EndInvoke(iftAR);
...
}
```

Here, you enter a loop that will continue processing the `Console.WriteLine()` statement until the secondary thread has completed. Once this has occurred, you can obtain the result of the `Add()` method knowing full well the method has indeed completed. The call to `Thread.Sleep(1000)` is not necessary for this particular application to function correctly; however, by forcing the primary thread to wait for approximately one second during each iteration, it prevents the same message from printing hundreds of times. Here is the output (your output may differ slightly, based on the speed of your machine and when threads come to life):

```
***** Async Delegate Invocation *****
Main() invoked on thread 1.
Doing more work in Main()!
Add() invoked on thread 3.
Doing more work in Main()!
10 + 10 is 20.
```

In addition to the `IsCompleted` property, the `IAsyncResult` interface provides the `AsyncWaitHandle` property for more flexible waiting logic. This property returns an instance of the `WaitHandle` type, which exposes a method named `WaitOne()`. The benefit of `WaitHandle.WaitOne()` is that you can specify the maximum wait time. If the specified amount of time is exceeded, `WaitOne()` returns false. Ponder the following updated while loop, which no longer makes use of a call to `Thread.Sleep()`:

```
while (!iftAR.AsyncWaitHandle.WaitOne(1000, true))
{
    Console.WriteLine("Doing more work in Main()!");
}
```

While these properties of `IAsyncResult` do provide a way to synchronize the calling thread, they are not the most efficient approach. In many ways, the `IsCompleted` property is much like a really annoying manager (or classmate) who is constantly asking, “Are you done yet?” Thankfully, delegates provide a number of additional (and more elegant) techniques to obtain the result of a method that has been called asynchronously.

Source Code The `AsyncDelegate` project is located under the Chapter 19 subdirectory.

The Role of the AsyncCallback Delegate

Rather than polling a delegate to determine whether an asynchronously invoked method has completed, it would be more efficient to have the secondary thread inform the calling thread when the task is finished. When you wish to enable this behavior, you will need to supply an instance of the `System.AsyncCallback` delegate as a parameter to `BeginInvoke()`, which up until this point has been null. However, when you do supply an `AsyncCallback` object, the delegate will call the specified method automatically when the asynchronous call has completed.

Note The callback method will be called on the secondary thread not the primary thread. This has important implications when using threads within a graphical user interface (WPF or Windows Forms) as controls have thread-affinity, meaning they can only be manipulated by the thread which created them. You'll see some examples of working the threads from a GUI later in this chapter during the examination of the Task Parallel Library (TPL).

Like any delegate, `AsyncCallback` can only invoke methods that match a specific pattern, which in this case is a method taking `IAsyncResult` as the sole parameter and returning nothing:

```
// Targets of AsyncCallback must match the following pattern.
void MyAsyncCallbackMethod(IAsyncResult itfAR)
```

Assume you have another Console Application (`AsyncCallbackDelegate`) making use of the `BinaryOp` delegate. This time, however, you will not poll the delegate to determine whether the `Add()` method has completed. Rather, you will define a static method named `AddComplete()` to receive the notification that the asynchronous invocation is finished. Also, this example makes use of a class level static `bool` field, which will be used to keep the primary thread in `Main()` running a task until the secondary thread is finished.

Note The use of this Boolean variable in this example is strictly speaking, not thread safe, as there are two different threads which have access to its value. This will be permissible for the current example; however, as a *very good rule of thumb*, you must ensure data that can be shared among multiple threads is locked down. You'll see how to do so later in this chapter.

```
namespace AsyncCallbackDelegate
{
    public delegate int BinaryOp(int x, int y);

    class Program
    {
        private static bool isDone = false;

        static void Main(string[] args)
        {
```

```

Console.WriteLine("***** AsyncCallbackDelegate Example *****");
Console.WriteLine("Main() invoked on thread {0}.",
    Thread.CurrentThread.ManagedThreadId);

BinaryOp b = new BinaryOp(Add);
IAsyncResult iftAR = b.BeginInvoke(10, 10,
    new AsyncCallback(AddComplete), null);

// Assume other work is performed here...
while (!isDone)
{
    Thread.Sleep(1000);
    Console.WriteLine("Working....");
}
Console.ReadLine();
}

static int Add(int x, int y)
{
    Console.WriteLine("Add() invoked on thread {0}.",
        Thread.CurrentThread.ManagedThreadId);
    Thread.Sleep(5000);
    return x + y;
}

static void AddComplete(IAsyncResult iftAR)
{
    Console.WriteLine("AddComplete() invoked on thread {0}.",
        Thread.CurrentThread.ManagedThreadId);
    Console.WriteLine("Your addition is complete");
    isDone = true;
}
}
}

```

Again, the static `AddComplete()` method will be invoked by the `AsyncCallback` delegate when the `Add()` method has completed. If you run this program, you can confirm that the secondary thread is the thread invoking the `AddComplete()` callback:

```

***** AsyncCallbackDelegate Example *****
Main() invoked on thread 1.
Add() invoked on thread 3.
Working....
Working....
Working....
Working....
Working....
AddComplete() invoked on thread 3.
Your addition is complete

```

Like other examples in this chapter, your output may be slightly different. In fact, you may see one final “Working...” printout occur after the addition is complete. This is just a byproduct of the forced 1-second delay in `Main()`.

The Role of the `AsyncResult` Class

Currently, the `AddComplete()` method is not printing out the actual result of the operation (adding two numbers). The reason is that the target of the `AsyncCallback` delegate (`AddComplete()` in this example) does not have access to the original `BinaryOp` delegate created in the scope of `Main()`, and therefore you can't call `EndInvoke()` from within `AddComplete()`!

While you could simply declare the `BinaryOp` variable as a static member variable in the class to allow both methods to access the same object, a more elegant solution is to use the incoming `IAsyncResult` parameter.

The incoming `IAsyncResult` parameter passed into the target of the `AsyncCallback` delegate is actually an instance of the `AsyncResult` class (note the lack of an `I` prefix) defined in the `System.Runtime.Remoting.Messaging` namespace. The static `AsyncDelegate` property returns a reference to the original asynchronous delegate that was created elsewhere.

Therefore, if you wish to obtain a reference to the `BinaryOp` delegate object allocated within `Main()`, simply cast the `System.Object` returned by the `AsyncDelegate` property into type `BinaryOp`. At this point, you can trigger `EndInvoke()` as expected:

```
// Don't forget to import
// System.Runtime.Remoting.Messaging!
static void AddComplete(IAsyncResult itfAR)
{
    Console.WriteLine("AddComplete() invoked on thread {0}.",
        Thread.CurrentThread.ManagedThreadId);
    Console.WriteLine("Your addition is complete");

    // Now get the result.
   AsyncResult ar = (AsyncResult)itfAR;
    BinaryOp b = (BinaryOp)ar.AsyncDelegate;
    Console.WriteLine("10 + 10 is {0}.", b.EndInvoke(itfAR));
    isDone = true;
}
```

Passing and Receiving Custom State Data

The final aspect of asynchronous delegates you need to address is the final argument to the `BeginInvoke()` method (which has been `null` up to this point). This parameter allows you to pass additional state information to the callback method from the primary thread. Because this argument is prototyped as a `System.Object`, you can pass in any type of data whatsoever, as long as the callback method knows what to expect. Assume for the sake of demonstration that the primary thread wishes to pass in a custom text message to the `AddComplete()` method:

```
static void Main(string[] args)
{
...
IAsyncResult iftar = b.BeginInvoke(10, 10,
```

```

new AsyncCallback(AddComplete),
"Main() thanks you for adding these numbers.");
...
}

```

To obtain this data within the scope of `AddComplete()`, make use of the `AsyncResult` property of the incoming `IAsyncResult` parameter. Notice that an explicit cast will be required; therefore the primary and secondary threads must agree on the underlying type returned from `AsyncResult`.

```

static void AddComplete(IAsyncResult itfAR)
{
...
// Retrieve the informational object and cast it to string.
string msg = (string)itfAR.AsyncState;
Console.WriteLine(msg);
isDone = true;
}

```

Here is the output of the final iteration:

```

***** AsyncCallbackDelegate Example *****
Main() invoked on thread 1.
Add() invoked on thread 3.
Working....
Working....
Working....
Working....
Working....
AddComplete() invoked on thread 3.
Your addition is complete
10 + 10 is 20.
Main() thanks you for adding these numbers.
Working....

```

Now that you understand how a .NET delegate can be used to automatically spin off a secondary thread of execution to handle an asynchronous method invocation, let's turn attention to directly interacting with threads using the `System.Threading` namespace.

Source Code The `AsyncCallbackDelegate` project is located under the Chapter 19 subdirectory.

The `System.Threading` Namespace

Under the .NET platform, the `System.Threading` namespace provides a number of types that enable the direct construction of multithreaded applications. In addition to providing types that allow you to interact with a particular CLR thread, this namespace defines types that allow access to the CLR maintained thread pool, a simple (non-GUI-based) Timer class, and numerous types used to provide

synchronized access to shared resources. Table 19-1 lists some of the core members of this namespace. (Be sure to consult the .NET Framework 4.0 SDK documentation for full details.)

Table 19-1. Select Types of the System.Threading Namespace

Type	Meaning in Life
Interlocked	This type provides atomic operations for variables that are shared by multiple threads.
Monitor	This type provides the synchronization of threading objects using locks and wait/signals. The C# lock keyword makes use of a Monitor object under the hood.
Mutex	This synchronization primitive can be used for synchronization between application domain boundaries.
ParameterizedThreadStart	This delegate allows a thread to call methods that take any number of arguments.
Semaphore	This type allows you to limit the number of threads that can access a resource, or a particular type of resource, concurrently.
Thread	This type represents a thread that executes within the CLR. Using this type, you are able to spawn additional threads in the originating AppDomain.
ThreadPool	This type allows you to interact with the CLR-maintained thread pool within a given process.
ThreadPriority	This enum represents a thread's priority level (Highest, Normal, etc.).
ThreadStart	This delegate is used to specify the method to call for a given thread. Unlike the ParameterizedThreadStart delegate, targets of ThreadStart must always have the same prototype.
ThreadState	This enum specifies the valid states a thread may take (Running, Aborted, etc.).
Timer	This type provides a mechanism for executing a method at specified intervals.
TimerCallback	This delegate type is used in conjunction with Timer types.

The System.Threading.Thread Class

The most primitive of all types in the `System.Threading` namespace is `Thread`. This class represents an object-oriented wrapper around a given path of execution within a particular `AppDomain`. This type also defines a number of methods (both static and instance level) that allow you to create new threads within the current `AppDomain`, as well as to suspend, stop, and destroy a particular thread. Consider the list of core static members in Table 19-2.

Table 19-2. Key Static Members of the Thread Type

Static Member	Meaning in Life
<code>CurrentContext</code>	This read-only property returns the context in which the thread is currently running.
<code>CurrentThread</code>	This read-only property returns a reference to the currently running thread.
<code>GetDomain()</code> <code>GetDomainID()</code>	These methods return a reference to the current <code>AppDomain</code> or the ID of this domain in which the current thread is running.
<code>Sleep()</code>	This method suspends the current thread for a specified time.

The `Thread` class also supports several instance-level members, some of which are shown in Table 19-3.

Table 19-3. Select Instance-Level Members of the Thread Type

Instance-Level Member	Meaning in Life
<code>IsAlive</code>	Returns a Boolean that indicates whether this thread has been started (and has not yet terminated or aborted).
<code>IsBackground</code>	Gets or sets a value indicating whether or not this thread is a “background thread” (more details in just a moment).
<code>Name</code>	Allows you to establish a friendly text name of the thread.
<code>Priority</code>	Gets or sets the priority of a thread, which may be assigned a value from the <code>ThreadPriority</code> enumeration.
<code>ThreadState</code>	Gets the state of this thread, which may be assigned a value from the <code>ThreadState</code> enumeration.

Table 19-3. Select Instance-Level Members of the Thread Type (continued)

Instance-Level Member	Meaning in Life
Abort()	Instructs the CLR to terminate the thread as soon as possible.
Interrupt()	Interrupts (e.g., wakes) the current thread from a suitable wait period.
Join()	Blocks the calling thread until the specified thread (the one on which Join() is called) exits.
Resume()	Resumes a thread that has been previously suspended.
Start()	Instructs the CLR to execute the thread ASAP.
Suspend()	Suspends the thread. If the thread is already suspended, a call to Suspend() has no effect.

■ **Note** Aborting or suspending an active thread is generally considered a bad idea. When you do so, there is a chance (however small) that a thread could “leak” its workload when disturbed or terminated.

Obtaining Statistics About the Current Thread

Recall that the entry point of an executable assembly (i.e., the `Main()` method) runs on the primary thread of execution. To illustrate the basic use of the `Thread` type, assume you have a new Console Application named `ThreadStats`. As you know, the static `Thread.CurrentThread` property retrieves a `Thread` object that represents the currently executing thread. Once you have obtained the current thread, you are able to print out various statistics:

```
// Be sure to import the System.Threading namespace.
static void Main(string[] args)
{
    Console.WriteLine("***** Primary Thread stats *****\n");

    // Obtain and name the current thread.
    Thread primaryThread = Thread.CurrentThread;
    primaryThread.Name = "ThePrimaryThread";

    // Show details of hosting AppDomain/Context.
    Console.WriteLine("Name of current AppDomain: {0}",
        Thread.GetDomain().FriendlyName);
    Console.WriteLine("ID of current Context: {0}",
        Thread.CurrentContext.ContextID);

    // Print out some stats about this thread.
```

```

Console.WriteLine("Thread Name: {0}",
    primaryThread.Name);
Console.WriteLine("Has thread started?: {0}",
    primaryThread.IsAlive);
Console.WriteLine("Priority Level: {0}",
    primaryThread.Priority);
Console.WriteLine("Thread State: {0}",
    primaryThread.ThreadState);
Console.ReadLine();
}

```

Here is the current output:

***** Primary Thread stats *****

Name of current AppDomain: ThreadStats.exe
ID of current Context: 0
Thread Name: ThePrimaryThread
Has thread started?: True
Priority Level: Normal
Thread State: Running

The Name Property

While this code is more or less self-explanatory, do notice that the `Thread` class supports a property called `Name`. If you do not set this value, `Name` will return an empty string. However, once you assign a friendly string moniker to a given `Thread` object, you can greatly simplify your debugging endeavors. If you are making use of Visual Studio 2010, you may access the Threads window during a debugging session (select `Debug > Windows > Threads`). As you can see from Figure 19-1, you can quickly identify the thread you wish to diagnose.




Figure 19-1. Debugging a thread with Visual Studio 2010

The Priority Property

Next, notice that the `Thread` type defines a property named `Priority`. By default, all threads have a priority level of `Normal`. However, you can change this at any point in the thread's lifetime using the `ThreadPriority` property and the related `System.Threading.ThreadPriority` enumeration:

```
public enum ThreadPriority
{
    Lowest,
    BelowNormal,
    Normal, // Default value.
    AboveNormal,
    Highest
}
```

If you were to assign a thread's priority level to a value other than the default (`ThreadPriority.Normal`), understand that you would have no direct control over when the thread scheduler switches between threads. In reality, a thread's priority level offers a hint to the CLR regarding the importance of the thread's activity. Thus, a thread with the value `ThreadPriority.Highest` is not necessarily guaranteed to be given the highest precedence.

Again, if the thread scheduler is preoccupied with a given task (e.g., synchronizing an object, switching threads, or moving threads), the priority level will most likely be altered accordingly. However, all things being equal, the CLR will read these values and instruct the thread scheduler how to best allocate time slices. Threads with an identical thread priority should each receive the same amount of time to perform their work.

In most cases, you will seldom (if ever) need to directly alter a thread's priority level. In theory, it is possible to jack up the priority level on a set of threads, thereby preventing lower-priority threads from executing at their required levels (so use caution).

Source Code The `ThreadStats` project is included under the Chapter 19 subdirectory.

Programmatically Creating Secondary Threads

When you wish to programmatically create additional threads to carry on some unit of work, you will follow a very predictable process:

1. Create a method to be the entry point for the new thread.
2. Create a new `ParameterizedThreadStart` (or `ThreadStart`) delegate, passing the address of the method defined in step 1 to the constructor.
3. Create a `Thread` object, passing the `ParameterizedThreadStart`/`ThreadStart` delegate as a constructor argument.
4. Establish any initial thread characteristics (name, priority, etc.).
5. Call the `Thread.Start()` method. This starts the thread at the method referenced by the delegate created in step 2 as soon as possible.

As stated in step 2, you may make use of two distinct delegate types to “point to” the method that the secondary thread will execute. The `ThreadStart` delegate has been part of the `System.Threading` namespace since .NET 1.0, and it can point to any method that takes no arguments and returns nothing. This delegate can be helpful when the method is designed to simply run in the background without further interaction.

The obvious limitation of `ThreadStart` is that you are unable to pass in parameters for processing. However, the `ParameterizedThreadStart` delegate type allows a single parameter of type `System.Object`. Given that anything can be represented as a `System.Object`, you can pass in any number of parameters via a custom class or structure. Do note, however, that the `ParameterizedThreadStart` delegate can only point to methods that return `void`.

Working with the ThreadStart Delegate

To illustrate the process of building a multithreaded application (as well as to demonstrate the usefulness of doing so), assume you have a Console Application (`SimpleMultiThreadApp`) that allows the end user to choose whether the application will perform its duties using the single primary thread or split its workload using two separate threads of execution.

Assuming you have imported the `System.Threading` namespace, your first step is to define a method to perform the work of the (possible) secondary thread. To keep focused on the mechanics of building multithreaded programs, this method will simply print out a sequence of numbers to the console window, pausing for approximately two seconds with each pass. Here is the full definition of the `Printer` class:

```
public class Printer
{
    public void PrintNumbers()
    {
        // Display Thread info.
        Console.WriteLine("-> {0} is executing PrintNumbers()", 
            Thread.CurrentThread.Name);

        // Print out numbers.
        Console.Write("Your numbers: ");
        for(int i = 0; i < 10; i++)
        {
            Console.Write("{0}, ", i);
            Thread.Sleep(2000);
        }
        Console.WriteLine();
    }
}
```

Now, within `Main()`, you will first prompt the user to determine whether one or two threads will be used to perform the application’s work. If the user requests a single thread, you will simply invoke the `PrintNumbers()` method within the primary thread. However, if the user specifies two threads, you will create a `ThreadStart` delegate that points to `PrintNumbers()`, pass this delegate object into the constructor of a new `Thread` object, and call `Start()` to inform the CLR this thread is ready for processing.

To begin, set a reference to the `System.Windows.Forms.dll` assembly (and import the `System.Windows.Forms` namespace) and display a message within `Main()` using `MessageBox.Show()` (you'll see the point of doing so once you run the program). Here is the complete implementation of `Main()`:

```
static void Main(string[] args)
{
    Console.WriteLine("***** The Amazing Thread App *****\n");
    Console.Write("Do you want [1] or [2] threads? ");
    string threadCount = Console.ReadLine();

    // Name the current thread.
    Thread primaryThread = Thread.CurrentThread;
    primaryThread.Name = "Primary";

    // Display Thread info.
    Console.WriteLine("-> {0} is executing Main()", Thread.CurrentThread.Name);

    // Make worker class.
    Printer p = new Printer();

    switch(threadCount)
    {
        case "2":
            // Now make the thread.
            Thread backgroundThread =
                new Thread(new ThreadStart(p.PrintNumbers));
            backgroundThread.Name = "Secondary";
            backgroundThread.Start();
            break;
        case "1":
            p.PrintNumbers();
            break;
        default:
            Console.WriteLine("I don't know what you want...you get 1 thread.");
            goto case "1";
    }

    // Do some additional work.
    MessageBox.Show("I'm busy!", "Work on main thread...");
    Console.ReadLine();
}
```

Now, if you run this program with a single thread, you will find that the final message box will not display the message until the entire sequence of numbers has printed to the console. As you are explicitly pausing for approximately two seconds after each number is printed, this will result in a less-than-stellar end-user experience. However, if you select two threads, the message box displays instantly, given that a unique `Thread` object is responsible for printing out the numbers to the console (see Figure 19-2).




Figure 19-2. Multithreaded applications provide results in more responsive applications

■ **Source Code** The SimpleMultiThreadApp project is included under the Chapter 19 subdirectory.

Working with the ParameterizedThreadStart Delegate

Recall that the `ThreadStart` delegate can point only to methods that return `void` and take no arguments. While this may fit the bill in many cases, if you wish to pass data to the method executing on the secondary thread, you will need to make use of the `ParameterizedThreadStart` delegate type. To illustrate, let's re-create the logic of the `AsyncCallbackDelegate` project created earlier in this chapter, this time making use of the `ParameterizedThreadStart` delegate type.

To begin, create a new Console Application named `AddWithThreads` and import the `System.Threading` namespace. Now, given that `ParameterizedThreadStart` can point to any method taking a `System.Object` parameter, you will create a custom type containing the numbers to be added:

```
class AddParams
{
    public int a, b;

    public AddParams(int numb1, int numb2)
    {
        a = numb1;
        b = numb2;
    }
}
```

Next, create a static method in the `Program` class that will take an `AddParams` parameter and print out the sum of the two numbers involved:

```
static void Add(object data)
{
    if (data is AddParams)
    {
        Console.WriteLine("ID of thread in Add(): {0}",
            Thread.CurrentThread.ManagedThreadId);
    }
}
```

```

        Thread.CurrentThread.ManagedThreadId);

    AddParams ap = (AddParams)data;
    Console.WriteLine("{0} + {1} is {2}",
        ap.a, ap.b, ap.a + ap.b);
}
}

The code within Main() is straightforward. Simply use ParameterizedThreadStart rather than
ThreadStart:

static void Main(string[] args)
{
    Console.WriteLine("***** Adding with Thread objects *****");
    Console.WriteLine("ID of thread in Main(): {0}",
        Thread.CurrentThread.ManagedThreadId);

    // Make an AddParams object to pass to the secondary thread.
    AddParams ap = new AddParams(10, 10);
    Thread t = new Thread(new ParameterizedThreadStart(Add));
    t.Start(ap);

    // Force a wait to let other thread finish.
    Thread.Sleep(5);

    Console.ReadLine();
}
}

```

The AutoResetEvent Class

In these first few examples, you have made use of a few crude ways to inform the primary thread to wait until the secondary thread has completed. During your examination of asynchronous delegates you used a simple bool variable as a toggle; however, this is not a recommended solution, as both threads can access the same point of data, and this can lead to data corruption. A safer, but still undesirable alternative is to call `Thread.Sleep()` for a fixed amount of time. The problem here is you don't want to wait longer than necessary.

One simple, and thread safe way to force a thread to wait until another is completed is to use the `AutoResetEvent` class. In the thread which needs to wait (such as a `Main()` method), create an instance of this class, and pass in false to the constructor in order to signify you have not yet been notified. Then, at the point at which you are willing to wait, call the `WaitOne()` method. Here is the update to `Program` class which will do this very thing using a static level `AutoResetEvent` member variable:

```

class Program
{
    private static AutoResetEvent waitHandle = new AutoResetEvent(false);

    static void Main(string[] args)
    {
        Console.WriteLine("***** Adding with Thread objects *****");
        Console.WriteLine("ID of thread in Main(): {0}",
            Thread.CurrentThread.ManagedThreadId);
}
}

```

```

AddParams ap = new AddParams(10, 10);
Thread t = new Thread(new ParameterizedThreadStart(Add));
t.Start(ap);

// Wait here until you are notified!
waitHandle.WaitOne();
Console.WriteLine("Other thread is done!");

Console.ReadLine();
}
...
}

```

When the other thread is completed with its workload, it will call the Set() method on the same instance of the AutoResetEvent type:

```

static void Add(object data)
{
    if (data is AddParams)
    {
        Console.WriteLine("ID of thread in Add(): {0}",
            Thread.CurrentThread.ManagedThreadId);

        AddParams ap = (AddParams) data;
        Console.WriteLine("{0} + {1} is {2}",
            ap.a, ap.b, ap.a + ap.b);

        // Tell other thread we are done.
        waitHandle.Set();
    }
}

```

Source Code The AddWithThreads project is included under the Chapter 19 subdirectory.

Foreground Threads and Background Threads

Now that you have seen how to programmatically create new threads of execution using the `System.Threading` namespace, let's formalize the distinction between *foreground threads* and *background threads*.

- *Foreground threads* have the ability to prevent the current application from terminating. The CLR will not shut down an application (which is to say, unload the hosting AppDomain) until all foreground threads have ended.

- *Background threads* (sometimes called *daemon threads*) are viewed by the CLR as expendable paths of execution that can be ignored at any point in time (even if they are currently laboring over some unit of work). Thus, if all foreground threads have terminated, any and all background threads are automatically killed when the application domain unloads.

It is important to note that foreground and background threads are *not* synonymous with primary and worker threads. By default, every thread you create via the `Thread.Start()` method is automatically a foreground thread. Again, this means that the AppDomain will not unload until all threads of execution have completed their units of work. In most cases, this is exactly the behavior you require.

For the sake of argument, however, assume that you wish to invoke `Printer.PrintNumbers()` on a secondary thread that should behave as a background thread. Again, this means that the method pointed to by the `Thread` type (via the `ThreadStart` or `ParameterizedThreadStart` delegate) should be able to halt safely as soon as all foreground threads are done with their work. Configuring such a thread is as simple as setting the `IsBackground` property to `true`:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Background Threads *****\n");

    Printer p = new Printer();
    Thread bgroundThread =
        new Thread(new ThreadStart(p.PrintNumbers()));

    // This is now a background thread.
    bgroundThread.IsBackground = true;
    bgroundThread.Start();
}
```

Notice that this `Main()` method is *not* making a call to `Console.ReadLine()` to force the console to remain visible until you press the Enter key. Thus, when you run the application, it will shut down immediately because the `Thread` object has been configured as a background thread. Given that the `Main()` method triggers the creation of the primary *foreground* thread, as soon as the logic in `Main()` completes, the AppDomain unloads before the secondary thread is able to complete its work.

However, if you comment out the line that sets the `IsBackground` property, you will find that each number prints to the console, as all foreground threads must finish their work before the AppDomain is unloaded from the hosting process.

For the most part, configuring a thread to run as a background type can be helpful when the worker thread in question is performing a noncritical task that is no longer needed when the main task of the program is finished. For example, you may build an application which pings an e-mail server every few minutes for new e-mails, updates current weather conditions, or some other non-critical task.

The Issue of Concurrency

When you build multithreaded applications, your program needs to ensure that any piece of shared data is protected against the possibility of numerous threads changing its value. Given that all threads in an AppDomain have concurrent access to the shared data of the application, imagine what might happen if multiple threads were accessing the same point of data. As the thread scheduler will force threads to suspend their work at random, what if thread A is kicked out of the way before it has fully completed its work? Thread B is now reading unstable data.

To illustrate the problem of concurrency, let's build another Console Application project named MultiThreadedPrinting. This application will once again make use of the Printer class created previously, but this time the PrintNumbers() method will force the current thread to pause for a randomly generated amount of time:

```
public class Printer
{
    public void PrintNumbers()
    {
        ...
        for (int i = 0; i < 10; i++)
        {
            // Put thread to sleep for a random amount of time.
            Random r = new Random();
            Thread.Sleep(1000 * r.Next(5));
            Console.Write("{0}, ", i);
        }
        Console.WriteLine();
    }
}
```

The Main() method is responsible for creating an array of ten (uniquely named) Thread objects, each of which is making calls on the *same instance* of the Printer object:

```
class Program
{
    static void Main(string[] args)
    {
        Console.WriteLine("*****Synchronizing Threads *****\n");

        Printer p = new Printer();

        // Make 10 threads that are all pointing to the same
        // method on the same object.
        Thread[] threads = new Thread[10];
        for (int i = 0; i < 10; i++)
        {
            threads[i] =
                new Thread(new ThreadStart(p.PrintNumbers));
            threads[i].Name = string.Format("Worker thread #{0}", i);
        }

        // Now start each one.
        foreach (Thread t in threads)
            t.Start();
        Console.ReadLine();
    }
}
```

Before looking at some test runs, let's recap the problem. The primary thread within this AppDomain begins life by spawning ten secondary worker threads. Each worker thread is told to make calls on the PrintNumbers() method on the *same* Printer instance. Given that you have taken no precautions to lock down this object's shared resources (the console), there is a good chance that the

current thread will be kicked out of the way before the `PrintNumbers()` method is able to print out the complete results. Because you don't know exactly when (or if) this might happen, you are bound to get unpredictable results. For example, you might find the output shown here:

*****Synchronizing Threads *****

```
-> Worker thread #1 is executing PrintNumbers()
Your numbers: -> Worker thread #0 is executing PrintNumbers()
-> Worker thread #2 is executing PrintNumbers()
Your numbers: -> Worker thread #3 is executing PrintNumbers()
Your numbers: -> Worker thread #4 is executing PrintNumbers()
Your numbers: -> Worker thread #6 is executing PrintNumbers()
Your numbers: -> Worker thread #7 is executing PrintNumbers()
Your numbers: -> Worker thread #8 is executing PrintNumbers()
Your numbers: -> Worker thread #9 is executing PrintNumbers()
Your numbers: Your numbers: -> Worker thread #5 is executing PrintNumbers()
Your numbers: 0, 0, 0, 0, 1, 0, 0, 1, 1, 2, 2, 2, 3, 3, 3, 2, 1, 0, 0, 4, 3,
4, 1, 2, 4, 5, 5, 5, 6, 6, 6, 2, 7, 7, 7, 3, 4, 0, 8, 4, 5, 1, 5, 8, 8, 9,
2, 6, 1, 0, 9, 1,
6, 2, 7, 9,
2, 1, 7, 8, 3, 2, 3, 3, 9,
8, 4, 4, 5, 9,
4, 3, 5, 5, 6, 3, 6, 7, 4, 7, 6, 8, 7, 4, 8, 5, 5, 6, 6, 8, 7, 7, 9,
8, 9,
8, 9,
9,
```

Now run the application a few more times. Here is another possibility (your results will certainly differ).

*****Synchronizing Threads *****

```
-> Worker thread #0 is executing PrintNumbers()
-> Worker thread #1 is executing PrintNumbers()
-> Worker thread #2 is executing PrintNumbers()
Your numbers: -> Worker thread #4 is executing PrintNumbers()
Your numbers: -> Worker thread #5 is executing PrintNumbers()
Your numbers: Your numbers: -> Worker thread #6 is executing PrintNumbers()
Your numbers: -> Worker thread #7 is executing PrintNumbers()
Your numbers: Your numbers: -> Worker thread #8 is executing PrintNumbers()
Your numbers: -> Worker thread #9 is executing PrintNumbers()
Your numbers: -> Worker thread #3 is executing PrintNumbers()
Your numbers: 0, 0, 0, 0, 0, 0, 0, 1, 1, 1, 1, 1, 1, 1, 1, 1, 1, 2, 2,
2, 2, 2, 2, 2, 2, 3, 3, 3, 3, 3, 3, 3, 3, 3, 4, 4, 4, 4, 4, 4, 4, 4, 4,
4, 5, 5, 5, 5, 5, 5, 5, 5, 6, 6, 6, 6, 6, 6, 6, 6, 6, 7, 7, 7, 7, 7, 7
, 7, 7, 7, 7, 8, 8, 8, 8, 8, 8, 8, 8, 8, 9,
9,
```

```
9,  
9,  
9,  
9,  
9,  
9,  
9,  
9,
```

■ **Note** If you are unable to generate unpredictable outputs, increase the number of threads from 10 to 100 (for example) or introduce another call to `Thread.Sleep()` within your program. Eventually, you will encounter the concurrency issue.

There are clearly some problems here. As each thread is telling the `Printer` to print out the numerical data, the thread scheduler is happily swapping threads in the background. The result is inconsistent output. What you need is a way to programmatically enforce synchronized access to the shared resources. As you would guess, the `System.Threading` namespace provides a number of synchronization-centric types. The C# programming language also provides a particular keyword for the very task of synchronizing shared data in multithreaded applications.

Synchronization Using the C# lock Keyword

The first technique you can use to synchronize access to shared resources is the C# `lock` keyword. This keyword allows you to define a scope of statements that must be synchronized between threads. By doing so, incoming threads cannot interrupt the current thread, preventing it from finishing its work. The `lock` keyword requires you to specify a *token* (an object reference) that must be acquired by a thread to enter within the lock scope. When you are attempting to lock down a *private* instance-level method, you can simply pass in a reference to the current type:

```
private void SomePrivateMethod()  
{  
    // Use the current object as the thread token.  
    lock(this)  
    {  
        // All code within this scope is thread-safe.  
    }  
}
```

However, if you are locking down a region of code within a *public* member, it is safer (and a best practice) to declare a private object member variable to serve as the lock token:

```
public class Printer
{
    // Lock token.
    private object threadLock = new object();

    public void PrintNumbers()
    {
        // Use the lock token.
        lock (threadLock)
        {
            ...
        }
    }
}
```

In any case, if you examine the `PrintNumbers()` method, you can see that the shared resource the threads are competing to gain access to is the console window. Therefore, if you scope all interactions with the `Console` type within a lock scope as follows:

```
public void PrintNumbers()
{
    // Use the private object lock token.
    lock (threadLock)
    {
        // Display Thread info.
        Console.WriteLine("-> {0} is executing PrintNumbers()", 
            Thread.CurrentThread.Name);

        // Print out numbers.
        Console.Write("Your numbers: ");
        for (int i = 0; i < 10; i++)
        {
            Random r = new Random();
            Thread.Sleep(1000 * r.Next(5));
            Console.Write("{0}, ", i);
        }
        Console.WriteLine();
    }
}
```

you have effectively designed a method that will allow the current thread to complete its task. Once a thread enters into a lock scope, the lock token (in this case, a reference to the current object) is inaccessible by other threads until the lock is released once the lock scope has exited. Thus, if thread A has obtained the lock token, other threads are unable to enter *any scope* that uses the same lock token until thread A relinquishes the lock token.

Note If you are attempting to lock down code in a static method, simply declare a private static object member variable to serve as the lock token.

If you now run the application, you can see that each thread has ample opportunity to finish its business:

*****Synchronizing Threads *****

```
-> Worker thread #0 is executing PrintNumbers()
Your numbers: 0, 1, 2, 3, 4, 5, 6, 7, 8, 9,
-> Worker thread #1 is executing PrintNumbers()
Your numbers: 0, 1, 2, 3, 4, 5, 6, 7, 8, 9,
-> Worker thread #3 is executing PrintNumbers()
Your numbers: 0, 1, 2, 3, 4, 5, 6, 7, 8, 9,
-> Worker thread #2 is executing PrintNumbers()
Your numbers: 0, 1, 2, 3, 4, 5, 6, 7, 8, 9,
-> Worker thread #4 is executing PrintNumbers()
Your numbers: 0, 1, 2, 3, 4, 5, 6, 7, 8, 9,
-> Worker thread #5 is executing PrintNumbers()
Your numbers: 0, 1, 2, 3, 4, 5, 6, 7, 8, 9,
-> Worker thread #7 is executing PrintNumbers()
Your numbers: 0, 1, 2, 3, 4, 5, 6, 7, 8, 9,
-> Worker thread #6 is executing PrintNumbers()
Your numbers: 0, 1, 2, 3, 4, 5, 6, 7, 8, 9,
-> Worker thread #8 is executing PrintNumbers()
Your numbers: 0, 1, 2, 3, 4, 5, 6, 7, 8, 9,
-> Worker thread #9 is executing PrintNumbers()
Your numbers: 0, 1, 2, 3, 4, 5, 6, 7, 8, 9,
```

■ Source Code The MultiThreadedPrinting project is included under the Chapter 19 subdirectory.

Synchronization Using the System.Threading.Monitor Type

The C# lock statement is really just a shorthand notation for working with the `System.Threading.Monitor` class. Once processed by the C# compiler, a lock scope actually resolves to the following (which you can verify using `ildasm.exe` or `reflector.exe`):

```
public void PrintNumbers()
{
    Monitor.Enter(threadLock);
    try
    {
        // Display Thread info.
        Console.WriteLine("-> {0} is executing PrintNumbers()", Thread.CurrentThread.Name);

        // Print out numbers.
        Console.Write("Your numbers: ");
        for (int i = 0; i < 10; i++)
```

```

{
    Random r = new Random();
    Thread.Sleep(1000 * r.Next(5));
    Console.WriteLine("{0}, {1}", i);
}
Console.WriteLine();
}
finally
{
    Monitor.Exit(threadLock);
}
}

```

First, notice that the `Monitor.Enter()` method is the ultimate recipient of the thread token you specified as the argument to the lock keyword. Next, all code within a lock scope is wrapped within a try block. The corresponding finally clause ensures that the thread token is released (via the `Monitor.Exit()` method), regardless of any possible runtime exception. If you were to modify the `MultiThreadSharedData` program to make direct use of the `Monitor` type (as just shown), you will find the output is identical.

Now, given that the lock keyword seems to require less code than making explicit use of the `System.Threading.Monitor` type, you may wonder about the benefits of using the `Monitor` type directly. The short answer is control. If you make use of the `Monitor` type, you are able to instruct the active thread to wait for some duration of time (via the static `Monitor.Wait()` method), inform waiting threads when the current thread is completed (via the static `Monitor.Pulse()` and `Monitor.PulseAll()` methods), and so on.

As you would expect, in a great number of cases, the C# lock keyword will fit the bill. However, if you are interested in checking out additional members of the `Monitor` class, consult the .NET Framework 4.0 SDK documentation.

Synchronization Using the `System.Threading.Interlocked` Type

Although it always is hard to believe until you look at the underlying CIL code, assignments and simple arithmetic operations are *not atomic*. For this reason, the `System.Threading` namespace provides a type that allows you to operate on a single point of data atomically with less overhead than with the `Monitor` type. The `Interlocked` class defines the following key static members shown in Table 19-4.

Table 19-4. Select Members of the `System.Threading.Interlocked` Type

Member	Meaning in Life
<code>CompareExchange()</code>	Safely tests two values for equality and, if equal, changes one of the values with a third
<code>Decrement()</code>	Safely decrements a value by 1
<code>Exchange()</code>	Safely swaps two values
<code>Increment()</code>	Safely increments a value by 1

Although it might not seem like it from the onset, the process of atomically altering a single value is quite common in a multithreaded environment. Assume you have a method named `AddOne()` that increments an integer member variable named `intVal`. Rather than writing synchronization code such as the following:

```
public void AddOne()
{
    lock(myLockToken)
    {
        intVal++;
    }
}
```

you can simplify your code via the static `Interlocked.Increment()` method. Simply pass in the variable to increment by reference. Do note that the `Increment()` method not only adjusts the value of the incoming parameter, but also returns the new value:

```
public void AddOne()
{
    int newVal = Interlocked.Increment(ref intVal);
}
```

In addition to `Increment()` and `Decrement()`, the `Interlocked` type allows you to atomically assign numerical and object data. For example, if you wish to assign the value of a member variable to the value 83, you can avoid the need to use an explicit lock statement (or explicit Monitor logic) and make use of the `Interlocked.Exchange()` method:

```
public void SafeAssignment()
{
    Interlocked.Exchange(ref myInt, 83);
}
```

Finally, if you wish to test two values for equality and change the point of comparison in a thread-safe manner, you are able to leverage the `Interlocked.CompareExchange()` method as follows:

```
public void CompareAndExchange()
{
    // If the value of i is currently 83, change i to 99.
    Interlocked.CompareExchange(ref i, 99, 83);
}
```

Synchronization Using the [Synchronization] Attribute

The final synchronization primitive examined here is the `[Synchronization]` attribute, which is a member of the `System.Runtime.Remoting.Contexts` namespace. In essence, this class-level attribute effectively locks down *all* instance member code of the object for thread safety. When the CLR allocates objects attributed with `[Synchronization]`, it will place the object within a synchronized context. As you may recall from Chapter 17, objects that should not be removed from a contextual boundary should derive from `ContextBoundObject`. Therefore, if you wish to make the `Printer` class type thread-safe (without explicitly writing thread-safe code within the class members), you could update the definition as follows:

```
using System.Runtime.Remoting.Contexts;
```

```

...
// All methods of Printer are now thread-safe!
[Synchronization]
public class Printer : ContextBoundObject
{
    public void PrintNumbers()
    {
        ...
    }
}

```

In some ways, this approach can be seen as the lazy way to write thread-safe code, given that you are not required to dive into the details about which aspects of the type are truly manipulating thread-sensitive data. The major downfall of this approach, however, is that even if a given method is not making use of thread-sensitive data, the CLR will *still* lock invocations to the method. Obviously, this could degrade the overall functionality of the type, so use this technique with care.

Programming with Timer Callbacks

Many applications have the need to call a specific method during regular intervals of time. For example, you may have an application that needs to display the current time on a status bar via a given helper function. As another example, you may wish to have your application call a helper function every so often to perform noncritical background tasks such as checking for new e-mail messages. For situations such as these, you can use the `System.Threading.Timer` type in conjunction with a related delegate named `TimerCallback`.

To illustrate, assume you have a Console Application (`TimerApp`) that will print the current time every second until the user presses a key to terminate the application. The first obvious step is to write the method that will be called by the `Timer` type (be sure to import `System.Threading` into your code file):

```

class Program
{
    static void PrintTime(object state)
    {
        Console.WriteLine("Time is: {0}",
            DateTime.Now.ToString());
    }

    static void Main(string[] args)
    {
    }
}

```

Notice how this method has a single parameter of type `System.Object` and returns `void`. This is not optional, given that the `TimerCallback` delegate can only call methods that match this signature. The value passed into the target of your `TimerCallback` delegate can be any bit of information whatsoever (in the case of the e-mail example, this parameter might represent the name of the Microsoft Exchange server to interact with during the process). Also note that given that this parameter is indeed a `System.Object`, you are able to pass in multiple arguments using a `System.Array` or custom class/structure.

The next step is to configure an instance of the `TimerCallback` delegate and pass it into the `Timer` object. In addition to configuring a `TimerCallback` delegate, the `Timer` constructor allows you to specify the optional parameter information to pass into the delegate target (defined as a `System.Object`), the interval to poll the method, and the amount of time to wait (in milliseconds) before making the first call, for example:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Working with Timer type *****\n");

    // Create the delegate for the Timer type.
    TimerCallback timeCB = new TimerCallback(PrintTime);

    // Establish timer settings.
    Timer t = new Timer(
        timeCB,          // The TimerCallback delegate object.
        null,           // Any info to pass into the called method (null for no info).
        0,              // Amount of time to wait before starting (in milliseconds).
        1000);         // Interval of time between calls (in milliseconds).

    Console.WriteLine("Hit key to terminate...");
    Console.ReadLine();
}
```

In this case, the `PrintTime()` method will be called roughly every second and will pass in no additional information to said method. Here is the output:

```
***** Working with Timer type *****
```

```
Hit key to terminate...
Time is: 6:51:48 PM
Time is: 6:51:49 PM
Time is: 6:51:50 PM
Time is: 6:51:51 PM
Time is: 6:51:52 PM
Press any key to continue . . .
```

If you did wish to send in some information for use by the delegate target, simply substitute the `null` value of the second constructor parameter with the appropriate information:

```
// Establish timer settings.
Timer t = new Timer(timeCB, "Hello From Main", 0, 1000);
```

You can then obtain the incoming data as follows:

```
static void PrintTime(object state)
{
    Console.WriteLine("Time is: {0}, Param is: {1}",
        DateTime.Now.ToString(), state.ToString());
}
```

■ **Source Code** The TimerApp project is included under the Chapter 19 subdirectory.

Understanding the CLR ThreadPool

The next thread-centric topic you will examine in this chapter is the role of the CLR thread pool. When you invoke a method asynchronously using delegate types (via the `BeginInvoke()` method), the CLR does not literally create a brand-new thread. For purposes of efficiency, a delegate's `BeginInvoke()` method leverages a pool of worker threads that is maintained by the runtime. To allow you to interact with this pool of waiting threads, the `System.Threading` namespace provides the `ThreadPool` class type.

If you wish to queue a method call for processing by a worker thread in the pool, you can make use of the `ThreadPool.QueueUserWorkItem()` method. This method has been overloaded to allow you to specify an optional `System.Object` for custom state data in addition to an instance of the `WaitCallback` delegate:

```
public static class ThreadPool
{
    ...
    public static bool QueueUserWorkItem(WaitCallback callBack);
    public static bool QueueUserWorkItem(WaitCallback callBack,
        object state);
}
```

The `WaitCallback` delegate can point to any method that takes a `System.Object` as its sole parameter (which represents the optional state data) and returns nothing. Do note that if you do not provide a `System.Object` when calling `QueueUserWorkItem()`, the CLR automatically passes a null value. To illustrate queuing methods for use by the CLR thread pool, ponder the following program, which makes use of the `Printer` type once again. In this case, however, you are not manually creating an array of `Thread` objects; rather, you are assigning members of the pool to the `PrintNumbers()` method:

```
class Program
{
    static void Main(string[] args)
    {
        Console.WriteLine("***** Fun with the CLR Thread Pool *****\n");

        Console.WriteLine("Main thread started. ThreadID = {0}",
            Thread.CurrentThread.ManagedThreadId);

        Printer p = new Printer();

        WaitCallback workItem = new WaitCallback(PrintTheNumbers);

        // Queue the method ten times.
        for (int i = 0; i < 10; i++)
        {
            ThreadPool.QueueUserWorkItem(workItem, p);
        }
        Console.WriteLine("All tasks queued");
```

```

    Console.ReadLine();
}

static void PrintTheNumbers(object state)
{
    Printer task = (Printer)state;
    task.PrintNumbers();
}
}

```

At this point, you may be wondering if it would be advantageous to make use of the CLR-maintained thread pool rather than explicitly creating Thread objects. Consider these benefits of leveraging the thread pool:

- The thread pool manages threads efficiently by minimizing the number of threads that must be created, started, and stopped.
- By using the thread pool, you can focus on your business problem rather than the application's threading infrastructure.

However, using manual thread management is preferred in some cases, for example:

- If you require foreground threads or must set the thread priority. Pooled threads are *always* background threads with default priority (`ThreadPriority.Normal`).
- If you require a thread with a fixed identity in order to abort it, suspend it, or discover it by name.

■ Source Code The ThreadPoolApp project is included under the Chapter 19 subdirectory.

That wraps up your investigation of the `System.Threading` namespace. While you can use this information to build some responsive applications, the remainder of this chapter will examine a new addition to the base class libraries brought forth with .NET 4.0- The Task Parallel Library.

Parallel Programming under the .NET Platform

If you go shopping at any electronic “super store,” you will quickly notice that computers which support two or more CPUs (aka, *cores*) are commonplace. Not only are they commonplace, they are quite cost effective; dual core laptops can be purchased for less than \$500.00 USD. When a machine supports multiple CPUs, it has the ability to execute threads in a parallel fashion, which can significantly improve the runtime performance of applications.

Traditionally speaking, if you wanted to build a .NET application which can distribute its workload across multiple cores, you needed to be quite skilled in multithreaded programming techniques (using many of the topics seen in this chapter). While this was certainly possible, doing so was tedious and error prone, given the inherit complexities of building multithreaded applications.

With the release of .NET 4.0, you are provided with a brand new parallel programming library. Using the types of `System.Threading.Tasks`, you can build fine-grained, scalable parallel code without having

to work directly with threads or the thread pool. Furthermore, when you do so, you can make use of strongly typed LINQ queries (via parallel LINQ, or PLINQ) to divide up your workload.

The Task Parallel Library API

Collectively speaking, the types of `System.Threading.Tasks` (as well as some related types in `System.Threading`) are referred to as the *Task Parallel Library*, or TPL. The TPL will automatically distribute your application's workload across available CPUs dynamically using the CLR thread pool. The TPL handles the partitioning of the work, thread scheduling, state management, and other low-level details. The end result is that you can maximize the performance of your .NET applications, while being shielded from many of complexities of directly working with threads. Figure 19-3 shows the members of this new .NET 4.0 namespace.




Figure 19-3. Members of the `System.Threading.Tasks` namespace

Starting with .NET 4.0, use of the TPL is the recommended way to build multithreaded applications. This is certainly not to suggest that having an understanding of traditional multithreading techniques using asynchronous delegates or the classes of `System.Threading` is somehow obsolete. In fact, to effectively use the TPL, you must understand primitives such as threads, locks, and concurrency. Furthermore, many situations that require multiple threads (such as asynchronous calls to remote objects) can be handled without the use of the TPL. Nevertheless, the amount of time you will need to directly work with the `Thread` class decreases significantly.

Finally, be aware that just because you can, does not mean you should. In the same way that creating multiple threads can slow down the execution of your .NET programs, authoring a ton of unnecessary parallel tasks can hurt performance. Use the functionality of the TPL only when you have a workload which truly creates a bottleneck in your programs, such as iterating over hundreds of objects, processing data in multiple files, etc.

■ **Note** The TPL infrastructure is rather intelligent. If it determines that a set of tasks would gain little or no benefit by running in parallel, it will opt to perform them in sequence.

The Role of the Parallel Class

The primary class of the TPL is `System.Threading.Tasks.Parallel`. This class supports a number of methods which allow you to iterate over a collection of data (specifically, an object implementing `IEnumerable<T>`) in a parallel fashion. If you were to look up the `Parallel` class in the .NET Framework 4.0 SDK documentation, you'll see that this class supports two primary static methods, `Parallel.For()` and `Parallel.ForEach()`, each of which defines numerous overloaded versions.

These methods allow you to author a body of code statements which will be processed in a parallel manner. In concept, these statements are the same sort of logic you would write in a normal looping construct (via the `for` or `foreach` C# keywords). The benefit however, is that the `Parallel` class will pluck threads from the thread pool (and manage concurrency) on your behalf.

Both of these methods require you to specify an `IEnumerable` or `IEnumerable<T>` compatible container that holds the data you need to process in a parallel manner. The container could be a simple array, a non-generic collection (such as `ArrayList`), a generic collection (such as `List<T>`), or the results of a LINQ query.

In addition, you will need to make use of the `System.Func<T>` and `System.Action<T>` delegates to specify the target method which will be called to process the data. You've already encountered the `Func<T>` delegate in Chapter 13 during your investigation of LINQ to Objects. Recall that `Func<T>` represents a method which can have a given return value and a varied number of arguments. The `Action<T>` delegate is very similar to `Func<T>`, in that it allows you to point to a method taking some number of parameters. However, `Action<T>` specifies a method which can only return `void`.

While you could call the `Parallel.For()` and `Parallel.ForEach()` methods and pass a strongly typed `Func<T>` or `Action<T>` delegate object, you can simplify your programming by making use of a fitting C# anonymous method or lambda expression.

Understanding Data Parallelism

The first way to use the TPL is to perform *data parallelism*. Simply put, this term refers to the task of iterating over an array or collection in a parallel manner using the `Parallel.For()` or `Parallel.ForEach()` methods. Assume you need to perform some labor intensive File IO operations. Specifically, you need to load a large number of *.jpg files into memory, flip them upside-down, and save the modified image data to a new location.

The .NET Framework 4.0 SDK documentation provides a console based example of this very thing, however we will perform the same overall task using a graphical user interface. To illustrate, create a Windows Forms application named `DataParallelismWithForEach`, and rename the `Form1.cs` to `MainForm.cs`. Once you do, import the following namespaces in your primary code file:

```
// Need these namespaces!
using System.Threading.Tasks;
using System.Threading;
using System.IO;
```

The GUI of the application consists of a multiline TextBox and a single Button (named `btnProcessImages`). The purpose of the text area is to allow you to enter data while the work is being performed in the background, thus illustrating the non-blocking nature of the parallel task. The `Click` event of this Button will eventually make use of the TPL, but for now, author the following blocking code:

```
public partial class MainForm : Form
{
    public MainForm()
    {
        InitializeComponent();
    }

    private void btnProcessImages_Click(object sender, EventArgs e)
    {
        ProcessFiles();
    }

    private void ProcessFiles()
    {
        // Load up all *.jpg files, and make a new folder for the modified data.
        string[] files = Directory.GetFiles
            (@"C:\Users\AndrewTroelsen\Pictures\My Family", "*.jpg",
             SearchOption.AllDirectories);
        string newDir = @"C:\ModifiedPictures";
        Directory.CreateDirectory(newDir);

        // Process the image data in a blocking manner.
        foreach (string currentFile in files)
        {
            string filename = Path.GetFileName(currentFile);

            using (Bitmap bitmap = new Bitmap(currentFile))
            {
                bitmap.RotateFlip(RotateFlipType.Rotate180FlipNone);
                bitmap.Save(Path.Combine(newDir, filename));
                this.Text = string.Format("Processing {0} on thread {1}", filename,
                    Thread.CurrentThread.ManagedThreadId);
            }
        }
        this.Text = "All done!";
    }
}
```

Notice that the `ProcessFiles()` method will rotate each *.jpg file under my personal Pictures\My Family subdirectory, which currently contains a total of 37 files (be sure to update the path sent into `Directory.GetFiles()` as necessary). Currently, all of the work is happening on the primary thread of the executable. Therefore, if the button is clicked, the program will appear to hang. Furthermore, the caption of the window will also report that the same primary thread is processing the file (Figure 19- 4).



Figure 19-4. Currently, all action is taking place on the primary thread

To process the files on as many CPUs as possible, you can rewrite the current foreach loop to make use of `Parallel.ForEach()`. Recall that this method has been overloaded numerous times, however in the simplest form, you must specify the `IEnumerable<T>` compatible object that contains the items to process (that would be the files string array) and an `Action<T>` delegate which points to the method that will perform the work. Here is the relevant update, using the C# lambda operator, in place of a literal `Action<T>` delegate object:

```
// Process the image data in a parallel manner!
Parallel.ForEach(files, currentFile =>
{
    string filename = Path.GetFileName(currentFile);

    using (Bitmap bitmap = new Bitmap(currentFile))
    {
        bitmap.RotateFlip(RotateFlipType.Rotate180FlipNone);
        bitmap.Save(Path.Combine(newDir, filename));
        this.Text = string.Format("Processing {0} on thread {1}", filename,
                                  Thread.CurrentThread.ManagedThreadId);
    }
});
```

Now, if you run program, the TPL will indeed distribute the workload to multiple threads from the thread pool, using as many CPUs as possible. However, you will not see the window's caption display the name of each unique thread and you won't see anything if you type in the text box, until all the images have been processed! The reason is that the primary UI thread is still blocked, waiting for all of the other threads to finish up their business.

The Task Class

To keep the user interface responsive, you could certainly make use of asynchronous delegates or the members of the `System.Threading` namespace directly, but the `System.Threading.Tasks` namespace provides a simpler alternative, via the `Task` class. `Task` allows you to easily invoke a method on a

secondary thread, and can be used as a simple alternative to working with asynchronous delegates. Update the Click handler of your Button control as so:

```
private void btnProcessImages_Click(object sender, EventArgs e)
{
    // Start a new "task" to process the files.
    Task.Factory.StartNew(() =>
    {
        ProcessFiles();
    });
}
```

The Factory property of Task returns a TaskFactory object. When you call its StartNew() method, you pass in an Action<T> delegate (here, hidden away with a fitting lambda expression) which points to the method to invoke in an asynchronous manner. With this small update, you will now find that the window's title will show which thread from the thread pool is processing a given file, and better yet, the text area is able to receive input, as the UI thread is no longer blocked.

Handling Cancelation Request

One improvement you can make to the current example is to provide a way for the user to stop the processing of the image data, via a second (aptly named) Cancel button. Thankfully, the Parallel.For() and Parallel.ForEach() methods both support cancellation through the use of *cancellation tokens*. When you invoke methods on Parallel, you can pass in a ParallelOptions object, which in turn contains a CancellationTokenSource object.

First of all, define a new private member variable in your Form derived class of type CancellationTokenSource named cancelToken:

```
public partial class MainForm : Form
{
    // New Form level variable.
    private CancellationTokenSource cancelToken =
        new CancellationTokenSource();

    ...
}
```

Now, assuming you have added a new Button (named btnCancel) on your designer, handle the Click event, and implement the handler as so:

```
private void btnCancelTask_Click(object sender, EventArgs e)
{
    // This will be used to tell all the worker threads to stop!
    cancelToken.Cancel();
}
```

Now, the real modifications need to occur within the ProcessFiles() method. Consider the final implementation:

```

private void ProcessFiles()
{
    // Use ParallelOptions instance to store the CancellationToken
    ParallelOptions parOpts = new ParallelOptions();
    parOpts.CancellationToken = cancelToken.Token;
    parOpts.MaxDegreeOfParallelism = System.Environment.ProcessorCount;

    // Load up all *.jpg files, and make a new folder for the modified data.
    string[] files = Directory.GetFiles
        (@"C:\Users\AndrewTroelsen\Pictures\My Family", "*.jpg",
         SearchOption.AllDirectories);
    string newDir = @"C:\ModifiedPictures";
    Directory.CreateDirectory(newDir);

    try
    {
        // Process the image data in a parallel manner!
        Parallel.ForEach(files, parOpts, currentFile =>
        {
            parOpts.CancellationToken.ThrowIfCancellationRequested();

            string filename = Path.GetFileName(currentFile);
            using (Bitmap bitmap = new Bitmap(currentFile))
            {
                bitmap.RotateFlip(RotateFlipType.Rotate180FlipNone);
                bitmap.Save(Path.Combine(newDir, filename));
                this.Text = string.Format("Processing {0} on thread {1}", filename,
                    Thread.CurrentThread.ManagedThreadId);
            }
        });
        this.Text = "All done!";
    }
    catch (OperationCanceledException ex)
    {
        this.Text = ex.Message;
    }
}

```

Notice that you begin the method by configuring a `ParallelOptions` object, setting the `CancellationToken` property to use the `CancellationTokenSource` token. Also note that when you call the `Parallel.ForEach()` method, you pass in the `ParallelOptions` object as the second parameter.

Within the scope of the looping logic, you make a call to `ThrowIfCancellationRequested()` on the token, which will ensure if the user clicks the Cancel button, all threads will stop and you will be notified via a runtime exception. When you catch the `OperationCanceledException` error, you will set the text of the main window to the error message.

■ **Source Code** The DataParallelismWithForEach project is included under the Chapter 19 subdirectory.

Understanding Task Parallelism

In addition to data parallelism, the TPL can also be used to easily fire off any number of asynchronous tasks using the `Parallel.Invoke()` method. This approach is a bit more straightforward than using delegates or members from `System.Threading`, however if you require more control over the way tasks are executed, you could forgo use of `Parallel.Invoke()` and make use of the `Task` class directly, as you did in the previous example.

To illustrate task parallelism, create a new Windows Forms application called `MyEBookReader` and import the `System.Threading.Tasks` and `System.Net` namespaces.

This application is a modification of a useful example in the .NET Framework 4.0 SDK documentation, which will fetch a free e-book from Project Gutenberg (<http://www.gutenberg.org>), and then perform a set of lengthy tasks in parallel.

The GUI consists of a multi-line `TextBox` control (named `txtBook`) and two `Button` controls (`btnDownload` and `btnGetStats`). Once you have designed the UI, handle the `Click` event for each `Button`, and in the form's code file, declare a class level `string` variable named `theEBook`. Implement the `Click` handler for the `btnDownload` as so:

```
private void btnDownload_Click(object sender, EventArgs e)
{
    WebClient wc = new WebClient();
    wc.DownloadStringCompleted += (s, eArgs) =>
    {
        theEBook = eArgs.Result;
        txtBook.Text = theEBook;
    };

    // The Project Gutenberg EBook of A Tale of Two Cities, by Charles Dickens
    wc.DownloadStringAsync(new Uri("http://www.gutenberg.org/files/98/98-8.txt"));
}
```

The `WebClient` class is a member of `System.Net`. This class provides a number of methods for sending data to and receiving data from a resource identified by a URI. As it turns out, many of these methods have an asynchronous version, such as `DownloadStringAsyn()`. This method will spin up a new thread from the CLR thread pool automatically. When the `WebClient` is done obtaining the data, it will fire the `DownloadStringCompleted` event, which you are handling here using a C# lambda expression. If you were to call the synchronous version of this method (`DownloadString()`) the form would appear unresponsive for quite some time.

The `Click` event handler for the `btnGetStats` `Button` control is implemented to extract out the individual words contained in the `theEBook` variable, and then pass the string array to a few helper functions for processing:

```
private void btnGetStats_Click(object sender, EventArgs e)
{
    // Get the words from the e-book.
    string[] words = theEBook.Split(new char[]
```

```

{ ' ', '\u000A', ',', '.', ';', ':', '-', '?', '/' },
StringSplitOptions.RemoveEmptyEntries);

// Now, find the ten most common words.
string[] tenMostCommon = FindTenMostCommon(words);

// Get the longest word.
string longestWord = FindLongestWord(words);

// Now that all tasks are complete, build a string to show all
// stats in a message box.
StringBuilder bookStats = new StringBuilder("Ten Most Common Words are:\n");
foreach (string s in tenMostCommon)
{
    bookStats.AppendLine(s);
}
bookStats.AppendFormat("Longest word is: {0}", longestWord);
bookStats.AppendLine();
MessageBox.Show(bookStats.ToString(), "Book info");
}

```

The `FindTenMostCommon()` method uses a LINQ query to obtain a list of `string` objects which occur most often in the `string` array, while `FindLongestWord()` locates, well, the longest word:

```

private string[] FindTenMostCommon(string[] words)
{
    var frequencyOrder = from word in words
        where word.Length > 6
        group word by word into g
        orderby g.Count() descending
        select g.Key;

    string[] commonWords = (frequencyOrder.Take(10)).ToArray();
    return commonWords;
}

private string FindLongestWord(string[] words)
{
    return (from w in words orderby w.Length descending select w).First();
}

```

If you were to run this project, the amount of time to perform all tasks could take a goodly amount of time, based on the CPU count of your machine and overall processor speed. Eventually, you should see the following output (Figure 19-5).




Figure 19-5. Stats about the downloaded Ebook

You can help ensure that your application makes use of all available CPUs on the host machine by invoking the `FindTenMostCommon()` and `FindLongestWord()` method in parallel. To do so, modify your `btnGetStats_Click()` method as so:

```
private void btnGetStats_Click(object sender, EventArgs e)
{
    // Get the words from the e-book.
    string[] words = theEBook.Split(
        new char[] { ' ', '\u000A', ',', '.', ';', ':', '-', '?', '/' },
        StringSplitOptions.RemoveEmptyEntries);
    string[] tenMostCommon = null;
    string longestWord = string.Empty;

    Parallel.Invoke(
        () =>
    {
        // Now, find the ten most common words.
        tenMostCommon = FindTenMostCommon(words);
    },
    () =>
    {
        // Get the longest word.
        longestWord = FindLongestWord(words);
    });

    // Now that all tasks are complete, build a string to show all
    // stats in a message box.
    ...
}
```

The `Parallel.Invoke()` method expects a parameter array of `Action<> delegates`, which you have supplied indirectly using lambda expressions. Again, while the output is identical, the benefit is that the TPL will now make use of all possible processors on the machine to invoke each method in parallel if possible.

■ Source Code The MyEBookReader project is included under the Chapter 19 subdirectory.

Parallel LINQ Queries (PLINQ)

To wrap up your look at the TPL, be aware that there is another way you can incorporate parallel tasks into your .NET applications. If you wish, you can make use of a new set of extension methods, which allow you to construct a LINQ query that will perform its workload in parallel (if possible). Fittingly, LINQ queries that are designed to run in parallel are termed PLINQ queries.

Like parallel code authored using the `Parallel` class, PLINQ has the option of ignoring your request to process the collection in parallel if need be. The PLINQ framework has been optimized in numerous ways, which includes determining if a query would in fact perform faster in a synchronous manner.

At run time, PLINQ analyzes the overall structure of the query and if the query is likely to benefit from parallelization, it will run concurrently. However, if parallelizing a query would hurt performance PLINQ just runs the query sequentially. If PLINQ has a choice between a potentially expensive parallel algorithm or an inexpensive sequential algorithm, it chooses the sequential algorithm by default.

The necessary extension methods are found within the `ParallelEnumerable` class of the `System.Linq` namespace. Table 19-5 documents some useful PLINQ extensions.

Table 19-4. Select members of the `ParallelEnumerable` class

Member	Meaning in Life
<code>AsParallel()</code>	Specifies that the rest of the query should be parallelized, if possible.
<code>WithCancellation()</code>	Specifies that PLINQ should periodically monitor the state of the provided cancellation token and cancel execution if it is requested.
<code>WithDegreeOfParallelism()</code>	Specifies the maximum number of processors that PLINQ should use to parallelize the query.
<code>ForAll()</code>	Enables results to be processed in parallel without first merging back to the consumer thread, as would be the case when enumerating a LINQ result using the <code>foreach</code> keyword.

To see PLINQ in action, create a final Windows Forms application named `PLINQDataProcessingWithCancellation` and import the `System.Threading` and `System.Threading.Tasks` namespaces. This simple form will only need two Button controls named `btnExecute` and `btnCancel`. Then the “Execute” button is clicked, you will fire off a new Task which executes a LINQ query that investigates a very large array of integers, looking for only the items $x \% 3 == 0$ is true. Here is a *non-parallel* version of the query:

```

public partial class MainForm : Form
{
...
    private void btnExecute_Click(object sender, EventArgs e)
    {
        // Start a new "task" to process the ints.
        Task.Factory.StartNew(() =>
        {
            ProcessIntData();
        });
    }

    private void ProcessIntData()
    {
        // Get a very large array of integers.
        int[] source = Enumerable.Range(1, 10000000).ToArray();

        // Find the numbers where num % 3 == 0 is true, returned
        // in descending order.
        int[] modThreeIsZero = (from num in source where num % 3 == 0
                               orderby num descending select num).ToArray();

        MessageBox.Show(string.Format("Found {0} numbers that match query!",
                                      modThreeIsZero.Count()));
    }
}

```

Opting in to a PLINQ Query

If you wish to inform the TPL to execute this query in parallel (if possible), you will want to make use of the `AsParallel()` extension method as so:

```

int[] modThreeIsZero = (from num in source.AsParallel() where num % 3 == 0
                        orderby num descending select num).ToArray();

```

Notice how the overall format of the LINQ query is identical to what you have seen in previous chapters. However, by including a call to `AsParallel()`, the TPL will attempt to pass the workload off to an available CPU.

Canceling a PLINQ Query

It is also possible to use a `CancellationTokenSource` object to inform a PLINQ query to stop processing under the correct conditions (typically due to user intervention). Declare a form level `CancellationTokenSource` object named `cancelToken` and implement the `Click` handler of the `btnCancel` to call the `Cancel()` method on this object. Here is the relevant code update:

```

public partial class MainForm : Form
{
    private CancellationTokenSource cancelToken = new CancellationTokenSource();

```

```

private void btnCancel_Click(object sender, EventArgs e)
{
    cancelToken.Cancel();
}
...
}

```

Now, inform the PLINQ query that it should be on the lookout for an incoming cancellation request by chaining on the `WithCancellation()` extension method, and passing in the token. In addition, you will want to wrap this PLINQ query in a proper try/catch scope, and deal with the possible exception. Here is the final version of the `ProcessIntData()` method.

```

private void ProcessIntData()
{
    // Get a very large array of integers.
    int[] source = Enumerable.Range(1, 10000000).ToArray();

    // Find the numbers where num % 3 == 0 is true, returned
    // in descending order.
    int[] modThreeIsZero = null;
    try
    {
        modThreeIsZero = (from num in
                           source.AsParallel().WithCancellation(cancelToken.Token)
                           where num % 3 == 0 orderby num descending
                           select num).ToArray();
    }
    catch (OperationCanceledException ex)
    {
        this.Text = ex.Message;
    }

    MessageBox.Show(string.Format("Found {0} numbers that match query!",
        modThreeIsZero.Count()));
}

```

That wraps up the introductory look at the Task Parallel Library and PLINQ. As mentioned, these new .NET 4.0 APIs are quickly becoming the preferred manner to work with multithreaded applications. However, effective use of TPL and PLINQ demand a solid understanding of multithreaded concepts and primitives, which you have been exposed to over the course of this chapter.

If you find these topics interesting, be sure to look up the topic “Parallel Programming in the .NET Framework” in the .NET Framework 4.0 SDK documentation. Here you will find a good number of sample projects which will extend what you have seen here.

■ Source Code The `PLINQDataProcessingWithCancellation` project is included under the Chapter 19 subdirectory.

Summary

This chapter began by examining how .NET delegate types can be configured to execute a method in an asynchronous manner. As you have seen, the `BeginInvoke()` and `EndInvoke()` methods allow you to indirectly manipulate a secondary thread with minimum fuss and bother. During this discussion, you were also introduced to the `IAsyncResult` interface and `AsyncResult` class type. As you learned, these types provide various ways to synchronize the calling thread and obtain possible method return values.

The next part of this chapter examined the role of the `System.Threading` namespace. As you learned, when an application creates additional threads of execution, the result is that the program in question is able to carry out numerous tasks at (what appears to be) the same time. You also examined several manners in which you can protect thread-sensitive blocks of code to ensure that shared resources do not become unusable units of bogus data.

This chapter wrapped up by examining a brand new model for working with multithreaded development under .NET 4.0, the Task Parallel Library and PLINQ. Going forward, these APIs are sure to become the preferred way to author multi-tasked systems, in that they allow us to program against a set of higher level types (many of which reside in the `System.Threading.Tasks` namespace) which hide a good amount of complexity.



File I/O and Object Serialization

When you create desktop applications, the ability to save information between user sessions is imperative. This chapter examines a number of I/O-related topics as seen through the eyes of the .NET Framework. The first order of business is to explore the core types defined in the `System.IO` namespace and learn how to modify a machine's directory and file structure programmatically. The next task is to explore various ways to read from and write to character-based, binary-based, string-based, and memory-based data stores.

After you learn how to manipulate files and directories using the core I/O types, you will examine the related topic of *object serialization*. You can use object serialization to persist and retrieve the state of an object to (or from) any `System.IO.Stream`-derived type. The ability to serialize objects is critical when you want to copy an object to a remote machine using various remoting technologies such as Windows Communication Foundation. However, serialization is quite useful in its own right and will likely play a role in many of your .NET applications (distributed or not).

Exploring the `System.IO` Namespace

In the framework of .NET, the `System.IO` namespace is the region of the base class libraries devoted to file-based (and memory-based) input and output (I/O) services. Like any namespace, `System.IO` defines a set of classes, interfaces, enumerations, structures, and delegates, most of which you can find in `mscorlib.dll`. In addition to the types contained within `mscorlib.dll`, the `System.dll` assembly defines additional members of the `System.IO` namespace. Note that all Visual Studio 2010 projects automatically set a reference to both assemblies.

Many of the types within the `System.IO` namespace focus on the programmatic manipulation of physical directories and files. However, additional types provide support to read data from and write data to string buffers, as well as raw memory locations. Table 20-1 outlines the core (non-abstract) classes, providing a road map of the functionality in `System.IO`.

Table 20-1. Key Members of the System.IO Namespace

Non-abstract I/O Class Type	Meaning in Life
BinaryReader BinaryWriter	These classes allow you to store and retrieve primitive data types (integers, Booleans, strings, and whatnot) as a binary value.
BufferedStream	This class provides temporary storage for a stream of bytes that you can commit to storage at a later time.
Directory DirectoryInfo	You use these classes to manipulate a machine's directory structure. The <code>Directory</code> type exposes functionality using <i>static members</i> , while the <code> DirectoryInfo</code> type exposes similar functionality from a valid <i>object reference</i> .
DriveInfo	This class provides detailed information regarding the drives that a given machine uses.
File FileInfo	You use these classes to manipulate a machine's set of files. The <code>File</code> type exposes functionality using <i>static members</i> , while the <code> FileInfo</code> type exposes similar functionality from a valid <i>object reference</i> .
FileStream	This class gives you random file access (e.g., seeking capabilities) with data represented as a stream of bytes.
FileSystemWatcher	This class allows you to monitor the modification of external files in a specified directory.
MemoryStream	This class provides random access to streamed data stored in memory rather than a physical file.
Path	This class performs operations on <code>System.String</code> types that contain file or directory path information in a platform-neutral manner.
StreamWriter StreamReader	You use these classes to store (and retrieve) textual information to (or from) a file. These types do not support random file access.
StringWriter StringReader	Like the <code> StreamReader/StreamWriter</code> classes, these classes also work with textual information. However, the underlying storage is a string buffer rather than a physical file.

In addition to these concrete class types, `System.IO` defines a number of enumerations, as well as a set of abstract classes (e.g., `Stream`, `TextReader`, and `TextWriter`), that define a shared polymorphic interface to all descendants. You will read about many of these types in this chapter.

The Directory(**I**nf^o) and File(**I**nf^o) Types

`System.IO` provides four classes that allow you to manipulate individual files, as well as interact with a machine's directory structure. The first two types, `Directory` and `File`, expose creation, deletion, copying, and moving operations using various static members. The closely related `FileInfo` and `DirectoryInfo` types expose similar functionality as instance-level methods (therefore, you must allocate them with the `new` keyword). In Figure 20-1, the `Directory` and `File` classes directly extend `System.Object`, while `DirectoryInfo` and `FileInfo` derive from the abstract `FileSystemInfo` type.




Figure 20-1. The File- and Directory-centric types

`FileInfo` and `DirectoryInfo` typically serve as better choices for obtaining full details of a file or directory (e.g., time created, and read/write capabilities) because their members tend to return strongly typed objects. In contrast, the `Directory` and `File` class members tend to return simple string values rather than strongly typed objects.

The Abstract FileSystemInfo Base Class

The `DirectoryInfo` and `FileInfo` types receive many behaviors from the abstract `FileSystemInfo` base class. For the most part, you use the members of the `FileSystemInfo` class to discover general characteristics (such as time of creation, various attributes, and so forth) about a given file or directory. Table 20-2 lists some core properties of interest.

Table 20-2. *FileSystemInfo Properties*

Property	Meaning in Life
Attributes	Gets or sets the attributes associated with the current file that are represented by the <code>FileAttributes</code> enumeration (e.g., is the file or directory read-only, encrypted, hidden, or compressed?).
CreationTime	Gets or sets the time of creation for the current file or directory.
Exists	You can use this to determine whether a given file or directory exists.
Extension	Retrieves a file's extension.
FullName	Gets the full path of the directory or file.
LastAccessTime	Gets or sets the time the current file or directory was last accessed.
LastWriteTime	Gets or sets the time when the current file or directory was last written to.
Name	Obtains the name of the current file or directory.

`FileSystemInfo` also defines the `Delete()` method. This is implemented by derived types to delete a given file or directory from the hard drive. Also, you can call `Refresh()` prior to obtaining attribute information to ensure that the statistics regarding the current file (or directory) are not outdated.

Working with the DirectoryInfo Type

The first creatable I/O-centric type you will examine is the `DirectoryInfo` class. This class contains a set of members used for creating, moving, deleting, and enumerating over directories and subdirectories. In addition to the functionality provided by its base class (`FileSystemInfo`), `DirectoryInfo` offers the key members in Table 20-3.

Table 20-3. *Key Members of the DirectoryInfo Type*

Member	Meaning in Life
<code>Create()</code> <code>CreateSubdirectory()</code>	Create a directory (or set of subdirectories) when given a path name.
<code>Delete()</code>	Deletes a directory and all its contents.
<code>GetDirectories()</code>	Returns an array of <code>DirectoryInfo</code> objects that represent all subdirectories in the current directory.

Table 20-3. Key Members of the DirectoryInfo Type (continued)

Member	Meaning in Life
GetFiles()	Retrieves an array of FileInfo objects that represent a set of files in the given directory.
MoveTo()	Moves a directory and its contents to a new path.
Parent	Retrieves the parent directory of this directory.
Root	Gets the root portion of a path.

You begin working with the DirectoryInfo type by specifying a particular directory path as a constructor parameter. Use the ". ." notation if you want to obtain access to the current working directory (the directory of the executing application). Here are some examples:

```
// Bind to the current working directory.
DirectoryInfo dir1 = new DirectoryInfo(".");

// Bind to C:\Windows,
// using a verbatim string.
DirectoryInfo dir2 = new DirectoryInfo(@"C:\Windows");
```

In the second example, you make the assumption that the path passed into the constructor (C:\Windows) already exists on the physical machine. However, if you attempt to interact with a nonexistent directory, a System.IO.DirectoryNotFoundException is thrown. Thus, if you specify a directory that is not yet created, you need to call the Create() method before proceeding:

```
// Bind to a nonexistent directory, then create it.
DirectoryInfo dir3 = new DirectoryInfo(@"C:\MyCode\Testing");
dir3.Create();
```

Once you create a DirectoryInfo object, you can investigate the underlying directory contents using any of the properties inherited from FileSystemInfo. To see this in action, create a new Console Application named DirectoryApp and update your C# file to import System.IO.

Update your Program class with a new static method that creates a new DirectoryInfo object mapped to C:\Windows (adjust your path if need be) that displays a number of interesting statistics:

```
class Program
{
    static void Main(string[] args)
    {
        Console.WriteLine("***** Fun with DirectoryInfo *****\n");
        ShowWindowsDirectoryInfo();
        Console.ReadLine();
    }
}
```

```

static void ShowWindowsDirectoryInfo()
{
    // Dump directory information.
    DirectoryInfo dir = new DirectoryInfo(@"C:\Windows");
    Console.WriteLine("***** Directory Info *****");
    Console.WriteLine("FullName: {0}", dir.FullName);
    Console.WriteLine("Name: {0}", dir.Name);
    Console.WriteLine("Parent: {0}", dir.Parent);
    Console.WriteLine("Creation: {0}", dir.CreationTime);
    Console.WriteLine("Attributes: {0}", dir.Attributes);
    Console.WriteLine("Root: {0}", dir.Root);
    Console.WriteLine("*****\n");
}

```

While your output might differ, you should see something similar to the following:

```

***** Fun with Directory(Info) *****

***** Directory Info *****
FullName: C:\Windows
Name: Windows
Parent:
Creation: 7/13/2009 10:20:08 PM
Attributes: Directory
Root: C:\
*****

```

Enumerating Files with the DirectoryInfo Type

In addition to obtaining basic details of an existing directory, you can extend the current example to use some methods of the `DirectoryInfo` type. First, you can leverage the `GetFiles()` method to obtain information about all `*.jpg` files located under the `C:\Windows\Web\Wallpaper` directory.

Note If your machine does not have a `C:\Windows\Web\Wallpaper` directory, retrofit this code to read files of a directory on your machine (e.g., to read all `*.bmp` files from the `C:\Windows` directory).

The `GetFiles()` method returns an array of `FileInfo` objects, each of which exposes details of a particular file (you will learn the full details of the `FileInfo` type later in this chapter). Assume that you have the following static method of the `Program` class, which you call from `Main()`:

```

static void DisplayImageFiles()
{
    DirectoryInfo dir = new DirectoryInfo(@"C:\Windows\Web\Wallpaper");

```

```

// Get all files with a *.jpg extension.
FileInfo[] imageFiles = dir.GetFiles("*.jpg", SearchOption.AllDirectories);

// How many were found?
Console.WriteLine("Found {0} *.jpg files\n", imageFiles.Length);

// Now print out info for each file.
foreach (FileInfo f in imageFiles)
{
    Console.WriteLine("*****");
    Console.WriteLine("File name: {0}", f.Name);
    Console.WriteLine("File size: {0}", f.Length);
    Console.WriteLine("Creation: {0}", f.CreationTime);
    Console.WriteLine("Attributes: {0}", f.Attributes);
    Console.WriteLine("*****\n");
}
}

```

Notice you specify a search option when you call `GetFiles()`; you do this to look within all subdirectories of the root. Once you run the application, you see a listing of all files that match the search pattern.

Creating Subdirectories with the DirectoryInfo Type

You can programmatically extend a directory structure using the `DirectoryInfo.CreateSubdirectory()` method. This method can create a single subdirectory, as well as multiple nested subdirectories, in a single function call. This method illustrates how to do so, extending the directory structure of the C: drive with some custom subdirectories:

```

static void ModifyAppDirectory()
{
    DirectoryInfo dir = new DirectoryInfo(@"C:\");

    // Create \MyFolder off application directory.
    dir.CreateSubdirectory("MyFolder");

    // Create \MyFolder2\Data off application directory.
    dir.CreateSubdirectory(@"MyFolder2\Data");
}

```

If you call this method from within `Main()` and examine your Windows directory using Windows Explorer, you will see that the new subdirectories are present and accounted for (see Figure 20-2).




Figure 20-2. Creating subdirectories

You are not required to capture the return value of the `CreateSubdirectory()` method, but you should be aware that a `DirectoryInfo` object representing the newly created item is passed back on successful execution. Consider the following update to the previous method:

```
static void ModifyAppDirectory()
{
    DirectoryInfo dir = new DirectoryInfo(".");
    // Create \MyFolder off initial directory.
    dir.CreateSubdirectory("MyFolder");

    // Capture returned DirectoryInfo object.
    DirectoryInfo myDataFolder = dir.CreateSubdirectory(@"MyFolder2\Data");

    // Prints path to ..\MyFolder2\Data.
    Console.WriteLine("New Folder is: {0}", myDataFolder);
}
```

Working with the Directory Type

You have seen the `DirectoryInfo` type in action; now you're ready to learn about the `Directory` type. For the most part, the static members of `Directory` mimic the functionality provided by the instance-level members defined by `DirectoryInfo`. Recall, however, that the members of `Directory` typically return string data rather than strongly typed `FileInfo/DirectoryInfo` objects.

Now let's look at some functionality of the `Directory` type; this final helper function displays the names of all drives mapped to the current computer (using the `Directory.GetLogicalDrives()` method)

and uses the static `Directory.Delete()` method to remove the `\MyFolder` and `\MyFolder2\Data` subdirectories created previously:

```
static void FunWithDirectoryType()
{
    // List all drives on current computer.
    string[] drives = Directory.GetLogicalDrives();
    Console.WriteLine("Here are your drives:");
    foreach (string s in drives)
        Console.WriteLine("--> {0} ", s);

    // Delete what was created.
    Console.WriteLine("Press Enter to delete directories");
    Console.ReadLine();
    try
    {
        Directory.Delete(@"C:\MyFolder");

        // The second parameter specifies whether you
        // wish to destroy any subdirectories.
        Directory.Delete(@"C:\MyFolder2", true);
    }
    catch (IOException e)
    {
        Console.WriteLine(e.Message);
    }
}
```

■ Source Code You can find the `DirectoryApp` project under the Chapter 20 subdirectory.

Working with the `DriveInfo` Class Type

The `System.IO` namespace provides a class named `DriveInfo`. Like `Directory.GetLogicalDrives()`, the static `DriveInfo.GetDrives()` method allows you to discover the names of a machine's drives. Unlike `Directory.GetLogicalDrives()`, however, `DriveInfo` provides numerous other details (e.g., the drive type, available free space, and volume label). Consider the following `Program` class defined within a new Console Application named `DriveInfoApp` (don't forget to import `System.IO`):

```
class Program
{
    static void Main(string[] args)
    {
        Console.WriteLine("***** Fun with DriveInfo *****\n");

        // Get info regarding all drives.
        DriveInfo[] myDrives = DriveInfo.GetDrives();
```

```
// Now print drive stats.  
foreach(DriveInfo d in myDrives)  
{  
    Console.WriteLine("Name: {0}", d.Name);  
    Console.WriteLine("Type: {0}", d.DriveType);  
  
    // Check to see whether the drive is mounted.  
    if(d.IsReady)  
    {  
        Console.WriteLine("Free space: {0}", d.TotalFreeSpace);  
        Console.WriteLine("Format: {0}", d.DriveFormat);  
        Console.WriteLine("Label: {0}", d.VolumeLabel);  
        Console.WriteLine();  
    }  
}  
Console.ReadLine();  
}  
}
```

Here is some possible output:

```
***** Fun with DriveInfo *****
```

```
Name: C:\  
Type: Fixed  
Free space: 587376394240  
Format: NTFS  
Label: Mongo Drive
```

```
Name: D:\  
Type: CDRom  
Name: E:\  
Type: CDRom  
Name: F:\  
Type: CDRom  
Name: H:\  
Type: Fixed  
Free space: 477467508736  
Format: FAT32  
Label: My Passport
```

At this point, you have investigated some core behaviors of the `Directory`, `DirectoryInfo`, and `DriveInfo` classes. Next, you'll learn how to create, open, close, and destroy the files that populate a given directory.

■ **Source Code** You can find the `DriveInfoApp` project under the Chapter 20 subdirectory.

Working with the FileInfo Class

As shown in the previous DirectoryApp example, the `FileInfo` class allows you to obtain details regarding existing files on your hard drive (e.g., time created, size, and file attributes) and aids in the creation, copying, moving, and destruction of files. In addition to the set of functionality inherited by `FileSystemInfo`, you can find some core members unique to the `FileInfo` class, which you can see described in Table 20-4.

Table 20-4. *FileInfo Core Members*

Member	Meaning in Life
<code>AppendText()</code>	Creates a <code>StreamWriter</code> object (described later) that appends text to a file.
<code>CopyTo()</code>	Copies an existing file to a new file.
<code>Create()</code>	Creates a new file and returns a <code>FileStream</code> object (described later) to interact with the newly created file.
<code>CreateText()</code>	Creates a <code>StreamWriter</code> object that writes a new text file.
<code>Delete()</code>	Deletes the file to which a <code>FileInfo</code> instance is bound.
<code>Directory</code>	Gets an instance of the parent directory.
<code>DirectoryName</code>	Gets the full path to the parent directory.
<code>Length</code>	Gets the size of the current file.
<code>MoveTo()</code>	Moves a specified file to a new location, providing the option to specify a new file name.
<code>Name</code>	Gets the name of the file.
<code>Open()</code>	Opens a file with various read/write and sharing privileges.
<code>OpenRead()</code>	Creates a read-only <code>FileStream</code> object.
<code>OpenText()</code>	Creates a <code>StreamReader</code> object (described later) that reads from an existing text file.
<code>OpenWrite()</code>	Creates a write-only <code>FileStream</code> object.

Note that a majority of the methods of the `FileInfo` class return a specific I/O-centric object (e.g., `FileStream` and `StreamWriter`) that allows you to begin reading and writing data to (or reading from) the associated file in a variety of formats. You will check out these types in just a moment; however, before

you see a working example, you'll find it helpful to examine various ways to obtain a file handle using the `FileInfo` class type.

The `FileInfo.Create()` Method

One way you can create a file handle is to use the `FileInfo.Create()` method:

```
static void Main(string[] args)
{
    // Make a new file on the C drive.
    FileInfo f = new FileInfo(@"C:\Test.dat");
    FileStream fs = f.Create();

    // Use the FileStream object...

    // Close down file stream.
    fs.Close();
}
```

Notice that the `FileInfo.Create()` method returns a `FileStream` object, which exposes synchronous and asynchronous write/read operations to/from the underlying file (more details in a moment). Be aware that the `FileStream` object returned by `FileInfo.Create()` grants full read/write access to all users.

Also notice that after you finish with the current `FileStream` object, you must ensure you close down the handle to release the underlying unmanaged stream resources. Given that `FileStream` implements `IDisposable`, you can use the C# `using` scope to allow the compiler to generate the teardown logic (see Chapter 8 for details):

```
static void Main(string[] args)
{
    // Defining a 'using scope' for file I/O
    // types is ideal.
    FileInfo f = new FileInfo(@"C:\Test.dat");
    using (FileStream fs = f.Create())
    {
        // Use the FileStream object...
    }
}
```

The `FileInfo.Open()` Method

You can use the `FileInfo.Open()` method to open existing files, as well as to create new files with far more precision than you can with `FileInfo.Create()`. This works because `Open()` typically takes several parameters to qualify exactly how to iterate the file you want to manipulate. Once the call to `Open()` completes, you are returned a `FileStream` object. Consider the following logic:

```

static void Main(string[] args)
{
    // Make a new file via FileInfo.Open().
    FileInfo f2 = new FileInfo(@"C:\Test2.dat");
    using(FileStream fs2 = f2.Open(FileMode.OpenOrCreate,
        FileAccess.ReadWrite, FileShare.None))
    {
        // Use the FileStream object...
    }
}

```

This version of the overloaded `Open()` method requires three parameters. The first parameter of the `Open()` method specifies the general flavor of the I/O request (e.g., make a new file, open an existing file, and append to a file), which you specify using the `FileMode` enumeration (see Table 20-5 for details):

```

public enum FileMode
{
    CreateNew,
    Create,
    Open,
    OpenOrCreate,
    Truncate,
    Append
}

```

Table 20-5. Members of the `FileMode` Enumeration

Member	Meaning in Life
<code>CreateNew</code>	Informs the OS to make a new file. If it already exists, an <code> IOException</code> is thrown.
<code>Create</code>	Informs the OS to make a new file. If it already exists, it will be overwritten.
<code>Open</code>	Opens an existing file. If the file does not exist, a <code> FileNotFoundException</code> is thrown.
<code>OpenOrCreate</code>	Opens the file if it exists; otherwise, a new file is created.
<code>Truncate</code>	Opens an existing file and truncates the file to 0 bytes in size.
<code>Append</code>	Opens a file, moves to the end of the file, and begins write operations (you can only use this flag with a write-only stream). If the file does not exist, a new file is created.

You use the second parameter of the `Open()` method, a value from the `FileAccess` enumeration, to determine the read/write behavior of the underlying stream:

```
public enum FileAccess
{
    Read,
    Write,
    ReadWrite
}
```

Finally, the third parameter of the `Open()` method, `FileShare`, specifies how to share the file among other file handlers. Here are the core names:

```
public enum FileShare
{
    Delete,
    Inheritable,
    None,
    Read,
    ReadWrite,
    Write
}
```

The `FileInfo.OpenRead()` and `FileInfo.OpenWrite()` Methods

The `FileInfo.Open()` method allows you to obtain a file handle in a flexible manner, but the `FileInfo` class also provides members named `OpenRead()` and `OpenWrite()`. As you might imagine, these methods return a properly configured read-only or write-only `FileStream` object, without the need to supply various enumeration values. Like `FileInfo.Create()` and `FileInfo.Open()`, `OpenRead()` and `OpenWrite()` return a `FileStream` object (note that the following code assumes you have files named `Test3.dat` and `Test4.dat` on your C drive):

```
static void Main(string[] args)
{
    // Get a FileStream object with read-only permissions.
    FileInfo f3 = new FileInfo(@"C:\Test3.dat");
    using(FileStream readOnlyStream = f3.OpenRead())
    {
        // Use the FileStream object...
    }

    // Now get a FileStream object with write-only permissions.
    FileInfo f4 = new FileInfo(@"C:\Test4.dat");
    using(FileStream writeOnlyStream = f4.OpenWrite())
    {
        // Use the FileStream object...
    }
}
```

The FileInfo.OpenText() Method

Another open-centric member of the `FileInfo` type is `OpenText()`. Unlike `Create()`, `Open()`, `OpenRead()`, or `OpenWrite()`, the `OpenText()` method returns an instance of the `StreamReader` type, rather than a `FileStream` type. Assuming you have a file named `boot.ini` on your C drive, the following snippet lets you access to its contents:

```
static void Main(string[] args)
{
    // Get a StreamReader object.
    FileInfo f5 = new FileInfo(@"C:\boot.ini");
    using(StreamReader sreader = f5.OpenText())
    {
        // Use the StreamReader object...
    }
}
```

As you will see shortly, the `StreamReader` type provides a way to read character data from the underlying file.

The FileInfo.CreateText() and FileInfo.AppendText() Methods

The final two `FileInfo` methods of interest at this point are `CreateText()` and `AppendText()`. Both return a `StreamWriter` object, as shown here:

```
static void Main(string[] args)
{
    FileInfo f6 = new FileInfo(@"C:\Test6.txt");
    using(StreamWriter swriter = f6.CreateText())
    {
        // Use the StreamWriter object...
    }

    FileInfo f7 = new FileInfo(@"C:\FinalTest.txt");
    using(StreamWriter swriterAppend = f7.AppendText())
    {
        // Use the StreamWriter object...
    }
}
```

As you might guess, the `StreamWriter` type provides a way to write character data to the underlying file.

Working with the File Type

The `File` type uses several static members to provide functionality almost identical to that of the `FileInfo` type. Like `FileInfo`, `File` supplies `AppendText()`, `Create()`, `CreateText()`, `Open()`, `OpenRead()`, `OpenWrite()`, and `OpenText()` methods. In many cases, you can use the `File` and `FileInfo` types

interchangeably. To see this in action, you can simplify each of the previous `FileStream` examples by using the `File` type instead:

```
static void Main(string[] args)
{
    // Obtain FileStream object via File.Create().
    using(FileStream fs = File.Create(@"C:\Test.dat"))
    {}

    // Obtain FileStream object via File.Open().
    using(FileStream fs2 = File.Open(@"C:\Test2.dat",
        FileMode.OpenOrCreate,
        FileAccess.ReadWrite, FileAccess.None))
    {}

    // Get a FileStream object with read-only permissions.
    using(FileStream readOnlyStream = File.OpenRead(@"Test3.dat"))
    {}

    // Get a FileStream object with write-only permissions.
    using(FileStream writeOnlyStream = File.OpenWrite(@"Test4.dat"))
    {}

    // Get a StreamReader object.
    using(StreamReader sreader = File.OpenText(@"C:\boot.ini"))
    {}

    // Get some StreamWriters.
    using(StreamWriter swriter = File.CreateText(@"C:\Test6.txt"))
    {}

    using(StreamWriter swriterAppend = File.AppendText(@"C:\FinalTest.txt"))
    {}
}
```

Additional File-centric Members

The `File` type also supports a few members shown in Table 20-6, which can greatly simplify the processes of reading and writing textual data.

Table 20-6. Methods of the `File` Type

Method	Meaning in Life
<code>ReadAllBytes()</code>	Opens the specified file, returns the binary data as an array of bytes, and then closes the file.
<code>ReadAllLines()</code>	Opens a specified file, returns the character data as an array of strings, and then closes the file.

Table 20-6. Methods of the `File` Type (continued)

Method	Meaning in Life
<code>ReadAllText()</code>	Opens a specified file, returns the character data as a <code>System.String</code> , and then closes the file.
<code>WriteAllBytes()</code>	Opens the specified file, writes out the byte array, and then closes the file.
<code>WriteAllLines()</code>	Opens a specified file, writes out an array of strings, and then closes the file.
<code>WriteAllText()</code>	Opens a specified file, writes the character data from a specified string, and then closes the file.

You can use these methods of the `File` type to read and write batches of data in only a few lines of code. Even better, each of these members automatically closes down the underlying file handle. For example, the following console program (named `SimpleFileIO`) persists the string data into a new file on the C: drive (and reads it into memory) with minimal fuss (this example assumes you have imported `System.IO`):

```
class Program
{
    static void Main(string[] args)
    {
        Console.WriteLine("***** Simple IO with the File Type *****\n");
        string[] myTasks = {
            "Fix bathroom sink", "Call Dave",
            "Call Mom and Dad", "Play Xbox 360";

        // Write out all data to file on C drive.
        File.WriteAllLines(@"C:\tasks.txt", myTasks);

        // Read it all back and print out.
        foreach (string task in File.ReadAllLines(@"C:\tasks.txt"))
        {
            Console.WriteLine("TODO: {0}", task);
        }
        Console.ReadLine();
    }
}
```

The lesson here: When you wish to obtain a file handle quickly, the `File` type will save you some keystrokes. However, one benefit of creating a `FileInfo` object first is that you can investigate the file using the members of the abstract `FileSystemInfo` base class.

■ **Source Code** You can find the SimpleFileIO project under the Chapter 20 subdirectory.

The Abstract Stream Class

At this point, you have seen many ways to obtain `FileStream`, `StreamReader`, and `StreamWriter` objects, but you have yet to read data from or write data to a file using these types. To understand how to do this, you'll need to familiarize yourself with the concept of a stream. In the world of I/O manipulation, a *stream* represents a chunk of data flowing between a source and a destination. Streams provide a common way to interact with *a sequence of bytes*, regardless of what kind of device (e.g., file, network connection, and printer) stores or displays the bytes in question.

The abstract `System.IO.Stream` class defines several members that provide support for synchronous and asynchronous interactions with the storage medium (e.g., an underlying file or memory location).

■ **Note** The concept of a stream is not limited to file I/O. To be sure, the .NET libraries provide stream access to networks, memory locations, and other stream-centric abstractions.

Again, `Stream` descendants represent data as a raw stream of bytes; therefore, working directly with raw streams can be quite cryptic. Some `Stream`-derived types support *seeking*, which refers to the process of obtaining and adjusting the current position in the stream. Table 20-7 helps you understand the functionality provided by the `Stream` class by describing its core members.

Table 20-7. Abstract Stream Members

Member	Meaning in Life
<code>CanRead</code>	Determines whether the current stream supports reading, seeking, and/or writing.
<code>CanWrite</code>	
<code>CanSeek</code>	
<code>Close()</code>	Closes the current stream and releases any resources (such as sockets and file handles) associated with the current stream. Internally, this method is aliased to the <code>Dispose()</code> method; therefore <i>closing a stream</i> is functionally equivalent to <i>disposing a stream</i> .
<code>Flush()</code>	Updates the underlying data source or repository with the current state of the buffer and then clears the buffer. If a stream does not implement a buffer, this method does nothing.
<code>Length</code>	Returns the length of the stream in bytes.

Table 20-7. Abstract Stream Members (continued)

Member	Meaning in Life
Position	Determines the position in the current stream.
Read() ReadByte()	Reads a sequence of bytes (or a single byte) from the current stream and advances the current position in the stream by the number of bytes read.
Seek()	Sets the position in the current stream.
SetLength()	Sets the length of the current stream.
Write() WriteByte()	Writes a sequence of bytes (or a single byte) to the current stream and advances the current position in this stream by the number of bytes written.

Working with FileStreams

The `FileStream` class provides an implementation for the abstract `Stream` members in a manner appropriate for file-based streaming. It is a fairly primitive stream; it can read or write only a single byte or an array of bytes. However, you will not often need to interact directly with the members of the `FileStream` type. Instead, you will probably use various *stream wrappers*, which make it easier to work with textual data or .NET types. Nevertheless, you will find it helpful to experiment with the synchronous read/write capabilities of the `FileStream` type.

Assume you have a new Console Application named `FileStreamApp`, and you imported `System.IO` and `System.Text` into your C# code file. Your goal is to write a simple text message to a new file named `myMessage.dat`. However, given that `FileStream` can operate only on raw bytes, you will be required to encode the `System.String` type into a corresponding byte array. Fortunately, the `System.Text` namespace defines a type named `Encoding` that provides members that encode and decode strings to (or from) an array of bytes (check out the .NET Framework 4.0 SDK documentation for more details about the `Encoding` type).

Once encoded, the byte array is persisted to file with the `FileStream.Write()` method. To read the bytes back into memory, you must reset the internal position of the stream (using the `Position` property) and call the `ReadByte()` method. Finally, you display the raw byte array and the decoded string to the console. Here is the complete `Main()` method:

```
// Don't forget to import the System.Text and System.IO namespaces.
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with FileStreams *****\n");

    // Obtain a FileStream object.
    using(FileStream fStream = File.Open(@"C:\myMessage.dat",
        FileMode.Create))
    {
        // Encode a string as an array of bytes.
        string msg = "Hello!";
        fStream.Write(Encoding.UTF8.GetBytes(msg));
        fStream.Position = 0;
        byte[] buffer = new byte[1];
        while(fStream.Read(buffer, 0, 1) > 0)
            Console.Write((char)buffer[0]);
    }
}
```

```

byte[] msgAsByteArray = Encoding.Default.GetBytes(msg);

// Write byte[] to file.
fStream.Write(msgAsByteArray, 0, msgAsByteArray.Length);

// Reset internal position of stream.
fStream.Position = 0;

// Read the types from file and display to console.
Console.WriteLine("Your message as an array of bytes: ");
byte[] bytesFromFile = new byte[msgAsByteArray.Length];
for (int i = 0; i < msgAsByteArray.Length; i++)
{
    bytesFromFile[i] = (byte)fStream.ReadByte();
    Console.WriteLine(bytesFromFile[i]);
}

// Display decoded messages.
Console.WriteLine("\nDecoded Message: ");
Console.WriteLine(Encoding.Default.GetString(bytesFromFile));
}
Console.ReadLine();
}

```

This example populates the file with data, but it also punctuates the major downfall of working directly with the `FileStream` type: it demands to operate on raw bytes. Other `Stream`-derived types operate in a similar manner. For example, if you wish to write a sequence of bytes to a region of memory, you can allocate a `MemoryStream`. Likewise, if you wish to push an array of bytes through a network connection, you can use the `NetworkStream` class (in the `System.Net.Sockets` namespace).

As mentioned previously, the `System.IO` namespace provides several *reader* and *writer* types that encapsulate the details of working with `Stream`-derived types.

Source Code You can find the `FileStreamApp` project is under the Chapter 20 subdirectory.

Working with StreamWriters and StreamReaders

The `StreamWriter` and `StreamReader` classes are useful whenever you need to read or write character-based data (e.g., strings). Both of these types work by default with Unicode characters; however, you can change this by supplying a properly configured `System.Text.Encoding` object reference. To keep things simple, assume that the default Unicode encoding fits the bill.

`StreamReader` derives from an abstract type named `TextReader`, as does the related `StringReader` type (discussed later in this chapter). The `TextReader` base class provides a limited set of functionality to each of these descendants; specifically it provides the ability to read and peek into a character stream.

The `StreamWriter` type (as well as `StringWriter`, which you will examine later in this chapter) derives from an abstract base class named `TextWriter`. This class defines members that allow derived types to write textual data to a given character stream.

To aid in your understanding of the core writing capabilities of the `StreamWriter` and `StringWriter` classes, Table 20-8 describes the core members of the abstract `TextWriter` base class.

Table 20-8. Core Members of `TextWriter`

Member	Meaning in Life
<code>Close()</code>	This method closes the writer and frees any associated resources. In the process, the buffer is automatically flushed (again, this member is functionally equivalent to calling the <code>Dispose()</code> method).
<code>Flush()</code>	This method clears all buffers for the current writer and causes any buffered data to be written to the underlying device; however, it does not close the writer.
<code>NewLine</code>	This property indicates the newline constant for the derived writer class. The default line terminator for the Windows OS is a carriage return, followed by a line feed (<code>\r\n</code>).
<code>Write()</code>	This overloaded method writes data to the text stream without a newline constant.
<code>WriteLine()</code>	This overloaded method writes data to the text stream with a newline constant.

■ **Note** The last two members of the `TextWriter` class probably look familiar to you. If you recall, the `System.Console` type has `Write()` and `WriteLine()` members that push textual data to the standard output device. In fact, the `Console.In` property wraps a `TextWriter`, and the `Console.Out` property wraps a `TextReader`.

The derived `StreamWriter` class provides an appropriate implementation for the `Write()`, `Close()`, and `Flush()` methods, and it defines the additional `AutoFlush` property. When set to true, this property forces `StreamWriter` to flush all data every time you perform a write operation. Be aware that you can gain better performance by setting `AutoFlush` to false, provided you always call `Close()` when you finish writing with a `StreamWriter`.

Writing to a Text File

To see the `StreamWriter` type in action, create a new Console Application named `StreamWriterReaderApp` and import `System.IO`. The following `Main()` method creates a new file named `reminders.txt` using the `File.CreateText()` method. Using the obtained `StreamWriter` object, you can add some textual data to the new file:

```
static void Main(string[] args)
{
```

```

Console.WriteLine("***** Fun with StreamWriter / StreamReader *****\n");

// Get a StreamWriter and write string data.
using(StreamWriter writer = File.CreateText("reminders.txt"))
{
    writer.WriteLine("Don't forget Mother's Day this year...");
    writer.WriteLine("Don't forget Father's Day this year...");
    writer.WriteLine("Don't forget these numbers:");
    for(int i = 0; i < 10; i++)
        writer.Write(i + " ");

    // Insert a new line.
    writer.Write(writer.NewLine);
}

Console.WriteLine("Created file and wrote some thoughts...");
Console.ReadLine();
}

```

After you run this program, you can examine the contents of this new file (see Figure 20-3). You will find this file under the bin\Debug folder of your current application because you did not specify an absolute path at the time you called CreateText().




Figure 20-3. The contents of your *.txt file

Reading from a Text File

Next, you will learn to read data from a file programmatically by using the corresponding `StreamReader` type. Recall that this class derives from the abstract `TextReader`, which offers the functionality described in Table 20-9.

Table 20-9. `TextReader` Core Members

Member	Meaning in Life
<code>Peek()</code>	Returns the next available character without actually changing the position of the reader. A value of -1 indicates you are at the end of the stream.
<code>Read()</code>	Reads data from an input stream.

Table 20-9. *TextReader Core Members (continued)*

Member	Meaning in Life
ReadBlock()	Reads a specified maximum number of characters from the current stream and writes the data to a buffer, beginning at a specified index.
ReadLine()	Reads a line of characters from the current stream and returns the data as a string (a null string indicates EOF).
ReadToEnd()	Reads all characters from the current position to the end of the stream and returns them as a single string.

If you now extend the current `MyStreamWriterReader` sample application to use a `StreamReader`, you can read in the textual data from the `reminders.txt` file, as shown here:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with StreamWriter / StreamReader *****\n");
    ...
    // Now read data from file.
    Console.WriteLine("Here are your thoughts:\n");
    using(StreamReader sr = File.OpenText("reminders.txt"))
    {
        string input = null;
        while ((input = sr.ReadLine()) != null)
        {
            Console.WriteLine (input);
        }
    }
    Console.ReadLine();
}
```

Once you run the program, you will see the character data in `reminders.txt` displayed to the console.

Directly Creating StreamWriter/StreamReader Types

One of the confusing aspects of working with the types within `System.IO` is that you can often achieve an identical result using different approaches. For example, you have already seen that you can use the `CreateText()` method to obtain a `StreamWriter` with the `File` or `FileInfo` type. It so happens that you can work with `StreamWriters` and `StreamReaders` another way: by creating them directly. For example, you could retrofit the current application as follows:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with StreamWriter / StreamReader *****\n");
```

```
// Get a StreamWriter and write string data.
using(StreamWriter writer = new StreamWriter("reminders.txt"))
{
    ...
}

// Now read data from file.
using(StreamReader sr = new StreamReader("reminders.txt"))
{
    ...
}
```

Although it can be a bit confusing to see so many seemingly identical approaches to file I/O, keep in mind that the end result is greater flexibility. In any case, you are now ready to examine the role of the `StringWriter` and `StreamReader` classes, given that you have seen how to move character data to and from a given file using the `StreamWriter` and `StreamReader` types.

Source Code You can find the `StreamWriterReaderApp` project under the Chapter 20 subdirectory.

Working with `StringWriters` and `StringReaders`

You can use the `StringWriter` and `StreamReader` types to treat textual information as a stream of in-memory characters. This can prove helpful when you wish to append character-based information to an underlying buffer. The following Console Application (named `StringReaderWriterApp`) illustrates this by writing a block of string data to a `StringWriter` object, rather than to a file on the local hard drive:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with StringWriter / StreamReader *****\n");

    // Create a StringWriter and emit character data to memory.
    using(StringWriter strWriter = new StringWriter())
    {
        strWriter.WriteLine("Don't forget Mother's Day this year...");
        // Get a copy of the contents (stored in a string) and pump
        // to console.
        Console.WriteLine("Contents of StringWriter:\n{0}", strWriter);
    }
    Console.ReadLine();
}
```

`StringWriter` and `StreamWriter` both derive from the same base class (`TextWriter`), so the writing logic is more or less identical. However, given the nature of `StringWriter`, you should also be aware that this class allows you to use the `GetStringBuilder()` method to extract a `System.Text.StringBuilder` object:

```

using (StringWriter strWriter = new StringWriter())
{
    strWriter.WriteLine("Don't forget Mother's Day this year...");
    Console.WriteLine("Contents of StringWriter:\n{0}", strWriter);

    // Get the internal StringBuilder.
    StringBuilder sb = strWriter.GetStringBuilder();
    sb.Insert(0, "Hey!! ");
    Console.WriteLine("-> {0}", sb.ToString());
    sb.Remove(0, "Hey!! ".Length);
    Console.WriteLine("-> {0}", sb.ToString());
}

```

When you wish to read from a stream of character data, you can use the corresponding `StringReader` type, which (as you would expect) functions identically to the related `StreamReader` class. In fact, the `StringReader` class does nothing more than override the inherited members to read from a block of character data, rather than from a file, as shown here:

```

using (StringWriter strWriter = new StringWriter())
{
    strWriter.WriteLine("Don't forget Mother's Day this year...");
    Console.WriteLine("Contents of StringWriter:\n{0}", strWriter);

    // Read data from the StringWriter.
    using (StringReader strReader = new StringReader(strWriter.ToString()))
    {
        string input = null;
        while ((input = strReader.ReadLine()) != null)
        {
            Console.WriteLine(input);
        }
    }
}

```

Source Code You can find the `StringReaderWriterApp` under the Chapter 20 subdirectory.

Working with BinaryWriters and BinaryReaders

The final writer/reader sets you will examine in this section are `BinaryReader` and `BinaryWriter`. Both derive directly from `System.Object`. These types allow you to read and write discrete data types to an underlying stream in a compact binary format. The `BinaryWriter` class defines a highly overloaded `Write()` method to place a data type in the underlying stream. In addition to the `Write()` member, `BinaryWriter` provides additional members that allow you to get or set the Stream-derived type; it also offers support for random access to the data (see Table 20-10).

Table 20-10. *BinaryWriter Core Members*

Member	Meaning in Life
BaseStream	This read-only property provides access to the underlying stream used with the <code>BinaryWriter</code> object.
Close()	This method closes the binary stream.
Flush()	This method flushes the binary stream.
Seek()	This method sets the position in the current stream.
Write()	This method writes a value to the current stream.

The `BinaryReader` class complements the functionality offered by `BinaryWriter` with the members described in Table 20-11.

Table 20-11. *BinaryReader Core Members*

Member	Meaning in Life
BaseStream	This read-only property provides access to the underlying stream used with the <code>BinaryReader</code> object.
Close()	This method closes the binary reader.
PeekChar()	This method returns the next available character without advancing the position in the stream.
Read()	This method reads a given set of bytes or characters and stores them in the incoming array.
ReadXXXX()	The <code>BinaryReader</code> class defines numerous read methods that grab the next type from the stream (e.g., <code>ReadBoolean()</code> , <code>ReadByte()</code> , and <code>ReadInt32()</code>).

The following example (a Console Application named `BinaryWriterReader`) writes a number of data types to a new *.dat file:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Binary Writers / Readers *****\n");

    // Open a binary writer for a file.
    FileInfo f = new FileInfo("BinFile.dat");
    using(BinaryWriter bw = new BinaryWriter(f.OpenWrite()))
    {
```

```

// Print out the type of BaseStream.
// (System.IO.FileStream in this case).
Console.WriteLine("Base stream is: {0}", bw.BaseStream);

// Create some data to save in the file
double aDouble = 1234.67;
int anInt = 34567;
string aString = "A, B, C";

// Write the data
bw.Write(aDouble);
bw.Write(anInt);
bw.Write(aString);
}
Console.ReadLine();
}

```

Notice how the `FileStream` object returned from `FileInfo.OpenWrite()` is passed to the constructor of the `BinaryWriter` type. Using this technique makes it easy to *layer in* a stream before writing out the data. Note that the constructor of `BinaryWriter` takes any `Stream`-derived type (e.g., `FileStream`, `MemoryStream`, or `BufferedStream`). Thus, writing binary data to memory instead is as simple as supplying a valid `MemoryStream` object.

To read the data out of the `BinFile.dat` file, the `BinaryReader` type provides a number of options. Here, you call various read-centric members to pluck each chunk of data from the file stream:

```

static void Main(string[] args)
{
...
    FileInfo f = new FileInfo("BinFile.dat");
...
    // Read the binary data from the stream.
    using(BinaryReader br = new BinaryReader(f.OpenRead()))
    {
        Console.WriteLine(br.ReadDouble());
        Console.WriteLine(br.ReadInt32());
        Console.WriteLine(br.ReadString());
    }
    Console.ReadLine();
}

```

■ Source Code You can find the `BinaryWriterReader` application under the Chapter 20 subdirectory.

Watching Files Programmatically

Now that you have a better handle on the use of various readers and writers, you'll look at the role of the `FileSystemWatcher` class. This type can be quite helpful when you wish to monitor (or “watch”) files on

your system programmatically. Specifically, you can instruct the `FileSystemWatcher` type to monitor files for any of the actions specified by the `System.IO.NotifyFilters` enumeration (many of these members are self-explanatory, but you should still check the .NET Framework 4.0 SDK documentation for more details):

```
public enum NotifyFilters
{
    Attributes, CreationTime,
   DirectoryName, FileName,
    LastAccess, LastWrite,
    Security, Size
}
```

To begin working with the `FileSystemWatcher` type, you need to set the `Path` property to specify the name (and location) of the directory that contains the files you want to monitor, as well as the `Filter` property that defines the file extensions of the files you want to monitor.

At this point, you may choose to handle the `Changed`, `Created`, and `Deleted` events, all of which work in conjunction with the `FileSystemEventHandler` delegate. This delegate can call any method matching the following pattern:

```
// The FileSystemEventHandler delegate must point
// to methods matching the following signature.
void MyNotificationHandler(object source, FileSystemEventArgs e)
```

You can also handle the `Renamed` event using the `RenamedEventHandler` delegate type, which can call methods that match the following signature:

```
// The RenamedEventHandler delegate must point
// to methods matching the following signature.
void MyRenamedHandler(object source, RenamedEventArgs e)
```

Next, let's look at the process of watching a file. Assume you have created a new directory on your C: drive named `MyFolder` that contains various `*.txt` files (named whatever you wish). The following Console Application (named `MyDirectoryWatcher`) monitors the `*.txt` files in the `MyFolder` directory and prints out messages when files are created, deleted, modified, or renamed:

```
static void Main(string[] args)
{
    Console.WriteLine("***** The Amazing File Watcher App *****\n");

    // Establish the path to the directory to watch.
    FileSystemWatcher watcher = new FileSystemWatcher();
    try
    {
        watcher.Path = @"C:\MyFolder";
    }
    catch(ArgumentException ex)
    {
        Console.WriteLine(ex.Message);
        return;
    }
}
```

```

// Set up the things to be on the lookout for.
watcher.NotifyFilter = NotifyFilters.LastAccess
| NotifyFilters.LastWrite
| NotifyFilters.FileName
| NotifyFilters.DirectoryName;

// Only watch text files.
watcher.Filter = "*.txt";

// Add event handlers.
watcher.Changed += new FileSystemEventHandler(OnChanged);
watcher.Created += new FileSystemEventHandler(OnChanged);
watcher.Deleted += new FileSystemEventHandler(OnChanged);
watcher.Renamed += new RenamedEventHandler(OnRenamed);

// Begin watching the directory.
watcher.EnableRaisingEvents = true;

// Wait for the user to quit the program.
Console.WriteLine(@"Press 'q' to quit app.");
while(Console.Read() != 'q');
}

```

The two event handlers simply print out the current file modification:

```

static void OnChanged(object source, FileSystemEventArgs e)
{
    // Specify what is done when a file is changed, created, or deleted.
    Console.WriteLine("File: {0} {1}!", e.FullPath, e.ChangeType);
}

static void OnRenamed(object source, RenamedEventArgs e)
{
    // Specify what is done when a file is renamed.
    Console.WriteLine("File: {0} renamed to\n{1}", e.OldFullPath, e.FullPath);
}

```

To test this program, run the application and open Windows Explorer. Try renaming your files, creating a *.txt file, deleting a *.txt file, and so forth. You will see various bits of information generated about the state of the text files within your MyFolder, as in this example:

***** The Amazing File Watcher App *****

```

Press 'q' to quit app.
File: C:\MyFolder\New Text Document.txt Created!
File: C:\MyFolder\New Text Document.txt renamed to
C:\MyFolder\Hello.txt
File: C:\MyFolder\Hello.txt Changed!
File: C:\MyFolder\Hello.txt Changed!
File: C:\MyFolder\Hello.txt Deleted!

```

■ **Source Code** You can find the MyDirectoryWatcher application under the Chapter 20 subdirectory.

That wraps up this chapter's look at fundamental IO operations within the .NET platform. While you will certainly use these techniques in many of your applications, you might also find that *object serialization* services can greatly simplify how you persist large amounts of data.

Understanding Object Serialization

The term *serialization* describes the process of persisting (and possibly transferring) the state of an object into a stream (e.g., file stream and memory stream). The persisted data sequence contains all the necessary information you need to reconstruct (or *deserialize*) the state of the object for use later. Using this technology makes it trivial to save vast amounts of data (in various formats). In many cases, saving application data using serialization services results in less code than using the readers/writers you find in the `System.IO` namespace.

For example, assume you want to create a GUI-based desktop application that provides a way for end users to save their preferences (e.g., window color and font size). To do this, you might define a class named `UserPrefs` that encapsulates 20 or so pieces of field data. Now, if you were to use a `System.IO.BinaryWriter` type, you would need to save each field of the `UserPrefs` object *manually*. Likewise, if you were to load the data from a file back into memory, you would need to use a `System.IO.BinaryReader` and (once again) *manually* read in each value to reconfigure a new `UserPrefs` object.

This is all doable, but you can save yourself a good amount of time by marking the `UserPrefs` class with the `[Serializable]` attribute:

```
[Serializable]
public class UserPrefs
{
    public string WindowColor;
    public int FontSize;
}
```

Doing this means that you can persist entire state of the object with only a few lines of code. Without getting hung up on the details for the time being, consider the following `Main()` method:

```
static void Main(string[] args)
{
    UserPrefs userData= new UserPrefs();
    userData.WindowColor = "Yellow";
    userData.FontSize = "50";

    // The BinaryFormatter persists state data in a binary format.
    // You would need to import System.Runtime.Serialization.Formatters.Binary
    // to gain access to BinaryFormatter.
    BinaryFormatter binFormat = new BinaryFormatter();
```

```
// Store object in a local file.
using(Stream fStream = new FileStream("user.dat",
    FileMode.Create, FileAccess.Write, FileShare.None))
{
    binFormat.Serialize(fStream, userData);
}
Console.ReadLine();
}
```

.NET object serialization makes it easy to persist objects; however, the processes used behind the scenes are quite sophisticated. For example, when an object is persisted to a stream, all associated data (e.g., base class data and contained objects) are automatically serialized, as well. Therefore, if you attempt to persist a derived class, all data up the chain of inheritance comes along for the ride. As you will see, you use an object graph to represent a set of interrelated objects.

.NET serialization services also allow you to persist an object graph in a variety of formats. The previous code example uses the `BinaryFormatter` type; therefore, the state of the `UserPrefs` object is persisted as a compact binary format. You can also persist an object graph into SOAP or XML format using other types. These formats can be quite helpful when you wish to ensure that your persisted objects travel well across operating systems, languages, and architectures.

Note WCF prefers a slightly different mechanism for serializing objects to/from WCF service operations; it uses the `[DataContract]` and `[DataMember]` attributes. You'll learn more about this in Chapter 25.

Finally, understand that you can persist an object graph into *any* `System.IO.Stream`-derived type. In the previous example, you use the `FileStream` type to persist a `UserPrefs` object into a local file. However, if you would rather store an object to a specific region of memory, you could use a `MemoryStream` type instead. All that matters is the fact that the sequence of data correctly represents the state of objects within the graph.

The Role of Object Graphs

As mentioned previously, the CLR will account for all related objects to ensure that data is persisted correctly when an object is serialized. This set of related objects is referred to as an *object graph*. Object graphs provide a simple way to document how a set of objects refer to each other, and these relationships do not necessarily map to classic OO relationships (such as the *is-a* or *has-a* relationship), although they do model this paradigm quite well.

Each object in an object graph is assigned a unique numerical value. Keep in mind that the numbers assigned to the members in an object graph are arbitrary and have no real meaning to the outside world. Once you assign all objects a numerical value, the object graph can record each object's set of dependencies.

For example, assume you have created a set of classes that model some automobiles (of course). You have a base class named `Car`, which *has-a* `Radio`. Another class named `JamesBondCar` extends the `Car` base type. Figure 20-4 shows a possible object graph that models these relationships.




Figure 20-4. A simple object graph

When reading object graphs, you can use the phrase *depends on* or *refers to* when connecting the arrows. Thus, in Figure 20-4, you can see that the `Car` refers to the `Radio` class (given the *has-a* relationship). `JamesBondCar` refers to `Car` (given the *is-a* relationship), as well as to `Radio` (it inherits this protected member variable).

Of course, the CLR does not paint pictures in memory to represent a graph of related objects. Rather, the relationship documented in the previous diagram is represented by a mathematical formula that looks something like this:

`[Car 3, ref 2], [Radio 2], [JamesBondCar 1, ref 3, ref 2]`

If you parse this formula, you can see that object 3 (the `Car`) has a dependency on object 2 (the `Radio`). Object 2, the `Radio`, is a lone wolf and requires nobody. Finally, object 1 (the `JamesBondCar`) has a dependency on object 3, as well as object 2. In any case, when you serialize or deserialize an instance of `JamesBondCar`, the object graph ensures that the `Radio` and `Car` types also participate in the process.

The beautiful thing about the serialization process is that the graph representing the relationships among your objects is established automatically behind the scenes. As you will see later in this chapter, however, you can become more involved in the construction of a given object graph by customizing the serialization process using attributes and interfaces.

Note Strictly speaking, the `XmlSerializer` type (described later in this chapter) does not persist state using object graphs; however, this type still serializes and deserializes related objects in a predictable manner.

Configuring Objects for Serialization

To make an object available to .NET serialization services, all you need to do is decorate each related class (or structure) with the `[Serializable]` attribute. If you determine that a given type has some member data that should not (or perhaps cannot) participate in the serialization scheme, you can mark such fields with the `[NonSerialized]` attribute. This can be helpful if you wish to reduce the size of the persisted data, and you have member variables in a serializable class that do not need to be remembered (e.g., fixed values, random -values, and transient data).

Defining Serializable Types

To get the ball rolling, create a new Console Application named `SimpleSerialize`. Insert a new class named `Radio`, which has been marked `[Serializable]`, excluding a single member variable (`radioID`) that has been marked `[NonSerialized]` and will therefore not be persisted into the specified data stream:

```
[Serializable]
public class Radio
{
    public bool hasTweeters;
    public bool hasSubWoofers;
    public double[] stationPresets;

    [NonSerialized]
    public string radioID = "XF-552RR6";
}
```

Next, insert two additional class types to represent the `JamesBondCar` and `Car` base classes, both of which are also marked `[Serializable]` and define the following pieces of field data:

```
[Serializable]
public class Car
{
    public Radio theRadio = new Radio();
    public bool isHatchBack;
}

[Serializable]
public class JamesBondCar : Car
{
    public bool canFly;
    public bool canSubmerge;
}
```

Be aware that you cannot inherit the `[Serializable]` attribute from a parent class. Therefore, if you derive a class from a type marked `[Serializable]`, the child class must be marked `[Serializable]` as well, or it cannot be persisted. In fact, all objects in an object graph must be marked with the `[Serializable]` attribute. If you attempt to serialize a nonserializable object using the `BinaryFormatter` or `SoapFormatter`, you will receive a `SerializationException` at runtime.

Public Fields, Private Fields, and Public Properties

Notice that in each of these classes, you define the field data as `public`; this helps keep the example simple. Of course, private data exposed using `public properties` would be preferable from an OO point of view. Also, for the sake of simplicity, this example does not define any custom constructors on these types; therefore, all unassigned field data will receive the expected default values.

OO design principles aside, you might wonder how the various formatters expect a type's field data to be defined in order to be serialized into a stream. The answer is that it depends. If you persist an object's state using the `BinaryFormatter` or `SoapFormatter`, it makes absolutely no difference. These types

are programmed to serialize *all* serializable fields of a type, regardless of whether they are public fields, private fields, or private fields exposed through public properties. Recall, however, that if you have points of data that you do not want to be persisted into the object graph, you can selectively mark public or private fields as [NonSerialized], as you do with the string field of the Radio type.

The situation is quite different if you use the `XmlSerializer` type, however. This type will *only* serialize public data fields or private data exposed by public properties. Private data not exposed from properties will be ignored. For example, consider the following serializable Person type:

```
[Serializable]
public class Person
{
    // A public field.
    public bool isAlive = true;

    // A private field.
    private int personAge = 21;

    // Public property/private data.
    private string fName = string.Empty;
    public string FirstName
    {
        get { return fName; }
        set { fName = value; }
    }
}
```

If you processed the preceding with `BinaryFormatter` or `SoapFormatter`, you would find that the `isAlive`, `personAge`, and `fName` fields are saved into the selected stream. However, the `XmlSerializer` would *not* save the value of `personAge` because this piece of private data is not encapsulated by a public type property. If you wished to persist the age of the person with the `XmlSerializer`, you would need to define the field publicly or encapsulate the private member using a public property.

Choosing a Serialization Formatter

Once you configure your types to participate in the .NET serialization scheme by applying the necessary attributes, your next step is to choose which format (binary, SOAP, or XML) you should use when persisting your object's state. Each possibility is represented by the following classes:

- `BinaryFormatter`
- `SoapFormatter`
- `XmlSerializer`

The `BinaryFormatter` type serializes your object's state to a stream using a compact binary format. This type is defined within the `System.Runtime.Serialization.Formatters.Binary` namespace that is part of `mscorlib.dll`. If you wish to gain access to this type, you can specify the following C# `using` directive:

```
// Gain access to the BinaryFormatter in mscorlib.dll.
using System.Runtime.Serialization.Formatters.Binary;
```

The `SoapFormatter` type persists an object's state as a SOAP message (the standard XML format for passing messages to/from a web service). This type is defined within the `System.Runtime.Serialization.Formatters.Soap` namespace, which is defined in a *separate assembly*. Thus, to format your object graph into a SOAP message, you must first set a reference to `System.Runtime.Serialization.Formatters.Soap.dll` using the Visual Studio 2010 Add Reference dialog box and then specify the following C# using directive:

```
// Must reference System.Runtime.Serialization.Formatters.Soap.dll.
using System.Runtime.Serialization.Formatters.Soap;
```

Finally, if you wish to persist a tree of objects as an XML document, you can use the `XmlSerializer` type. To use this type, you need to specify that you are using the `System.Xml.Serialization` namespace and set a reference to the assembly `System.Xml.dll`. As luck would have it, all Visual Studio 2010 project templates automatically reference `System.Xml.dll`; therefore, all you need to do is use the following namespace:

```
// Defined within System.Xml.dll.
using System.Xml.Serialization;
```

The `IFormatter` and `IRemotingFormatter` Interfaces

Regardless of which formatter you choose to use, be aware that all of them derive directly from `System.Object`, so they do *not* share a common set of members from a serialization-centric base class. However, the `BinaryFormatter` and `SoapFormatter` types do support common members through the implementation of the `IFormatter` and `IRemotingFormatter` interfaces (strange as it might seem, the `XmlSerializer` implements neither).

`System.Runtime.Serialization.IFormatter` defines the core `Serialize()` and `Deserialize()` methods, which do the grunt work to move your object graphs into and out of a specific stream. Beyond these members, `IFormatter` defines a few properties that the implementing type uses behind the scenes:

```
public interface IFormatter
{
    SerializationBinder Binder { get; set; }
    StreamingContext Context { get; set; }
    ISurrogateSelector SurrogateSelector { get; set; }
    object Deserialize(Stream serializationStream);
    void Serialize(Stream serializationStream, object graph);
}
```

The `System.Runtime.Remoting.Messaging.IRemotingFormatter` interface (which is leveraged internally by the .NET remoting layer) overloads the `Serialize()` and `Deserialize()` members into a manner more appropriate for distributed persistence. Note that `IRemotingFormatter` derives from the more general `IFormatter` interface:

```
public interface IRemotingFormatter : IFormatter
{
    object Deserialize(Stream serializationStream, HeaderHandler handler);
    void Serialize(Stream serializationStream, object graph, Header[] headers);
}
```

Although you might not need to interact directly with these interfaces for most of your serialization endeavors, recall that interface-based polymorphism allows you to hold an instance of `BinaryFormatter` or `SoapFormatter` using an `IFormatter` reference. Therefore, if you wish to build a method that can serialize an object graph using either of these classes, you could write the following:

```
static void SerializeObjectGraph(IFormatter itfFormat,
                                Stream destStream, object graph)
{
    itfFormat.Serialize(destStream, graph);
}
```

Type Fidelity Among the Formatters

The most obvious difference among the three formatters is how the object graph is persisted to the stream (binary, SOAP, or XML). You should also be aware of a few more subtle points of distinction; specifically, how the formatters contend with *type fidelity*. When you use the `BinaryFormatter` type, it will persist not only the field data of the objects in the object graph, but also each type's fully qualified name and the full name of the defining assembly (name, version, public key token, and culture). These extra points of data make the `BinaryFormatter` an ideal choice when you wish to transport objects by value (e.g., as a full copy) across machine boundaries for .NET-centric applications.

The `SoapFormatter` persists traces of the assembly of origin through the use of an XML namespace. For example, recall the `Person` type earlier in this chapter. If this type were persisted as a SOAP message, you would find that the opening element of `Person` is qualified by the generated `xmlns`. Consider this partial definition, paying special attention to the `a1` XML namespace:

```
<a1:Person id="ref-1" xmlns:a1=
  "http://schemas.microsoft.com/clr/nsassem/SimpleSerialize/MyApp%2C%20
  Version%3D1.0.0.0%2C%20Culture%3Dneutral%2C%20PublicKeyToken%3Dnull">
  <isAlive>true</isAlive>
  <personAge>21</personAge>
  <fName id="ref-3"></fName>
</a1:Person>
```

However, the `XmlSerializer` does *not* attempt to preserve full type fidelity; therefore, it does not record the type's fully qualified name or assembly of origin. This might seem like a limitation at first glance, but XML serialization is used by classic .NET web services, which can be called from clients on any platform (not just .NET). This means that there is no point serializing full .NET type metadata. Here is a possible XML representation of the `Person` type:

```
<?xml version="1.0"?>
<Person xmlns:xsi="http://www.w3.org/2001/XMLSchema-instance"
  xmlns:xsd="http://www.w3.org/2001/XMLSchema">
  <isAlive>true</isAlive>
  <PersonAge>21</PersonAge>
  <FirstName />
</Person>
```

If you wish to persist an object's state in a manner that can be used by any operating system (e.g., Windows XP, Mac OS X, and various Linux distributions), application framework (e.g., .NET, Java

Enterprise Edition, and COM), or programming language, you do not want to maintain full type fidelity because you cannot assume all possible recipients can understand .NET-specific data types. Given this, `SoapFormatter` and `XmlSerializer` are ideal choices when you wish to ensure as broad a reach as possible for the persisted tree of objects.

Serializing Objects Using the `BinaryFormatter`

You can use the `BinaryFormatter` type to illustrate how easy it is to persist an instance of the `JamesBondCar` to a physical file. Again, the two key methods of the `BinaryFormatter` type to be aware of are `Serialize()` and `Deserialize()`:

- `Serialize()`: Persists an object graph to a specified stream as a sequence of bytes.
- `Deserialize()`: Converts a persisted sequence of bytes to an object graph.

Assume you have created an instance of `JamesBondCar`, modified some state data, and want to persist your spy mobile into a *.dat file. Begin by creating the *.dat file itself. You can achieve this by creating an instance of the `System.IO.FileStream` type. At this point, you can create an instance of the `BinaryFormatter` and pass in the `FileStream` and object graph to persist. Consider the following `Main()` method:

```
// Be sure to import the System.Runtime.Serialization.Formatters.Binary
// and System.IO namespaces.
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Object Serialization *****\n");

    // Make a JamesBondCar and set state.
    JamesBondCar jbc = new JamesBondCar();
    jbc.canFly = true;
    jbc.canSubmerge = false;
    jbc.theRadio.stationPresets = new double[]{89.3, 105.1, 97.1};
    jbc.theRadio.hasTweeters = true;

    // Now save the car to a specific file in a binary format.
    SaveAsBinaryFormat(jbc, "CarData.dat");
    Console.ReadLine();
}
```

You implement the `SaveAsBinaryFormat()` method like this:

```
static void SaveAsBinaryFormat(object objGraph, string fileName)
{
    // Save object to a file named CarData.dat in binary.
    BinaryFormatter binFormat = new BinaryFormatter();

    using(Stream fStream = new FileStream(fileName,
        FileMode.Create, FileAccess.Write, FileShare.None))
    {
        binFormat.Serialize(fStream, objGraph);
    }
}
```

```
        Console.WriteLine("=> Saved car in binary format!");
    }
```

The `BinaryFormatter.Serialize()` method is the member responsible for composing the object graph and moving the byte sequence to some Stream-derived type. In this case, the stream happens to be a physical file. You could also serialize your object types to any Stream-derived type, such as a memory location or network stream.

Once you run your program, you can view the contents of the `CarData.dat` file that represents this instance of the `JamesBondCar` by navigating to the `\bin\Debug` folder of the current project. Figure 20-5 shows this file opened within Visual Studio 2010.



Figure 20-5. *JamesBondCar* serialized using a *BinaryFormatter*

Deserializing Objects Using the BinaryFormatter

Now suppose you want to read the persisted `JamesBondCar` from the binary file back into an object variable. Once you open `CarData.dat` programmatically (with the `File.OpenRead()` method), you can call the `Deserialize()` method of the `BinaryFormatter`. Be aware that `Deserialize()` returns a general `System.Object` type, so you need to impose an explicit cast, as shown here:

```
static void LoadFromBinaryFile(string fileName)
{
    BinaryFormatter binFormat = new BinaryFormatter();

    // Read the JamesBondCar from the binary file.
    using(Stream fStream = File.OpenRead(fileName))
    {
```

```

JamesBondCar carFromDisk =
    (JamesBondCar)binFormat.Deserialize(fStream);
Console.WriteLine("Can this car fly? : {0}", carFromDisk.canFly);
}
}

```

Notice that when you call `Deserialize()`, you pass the Stream-derived type that represents the location of the persisted object graph. Once you cast the object back into the correct type, you will find the state data has been retained from the point at which you saved the object.

Serializing Objects Using the SoapFormatter

Your next choice of formatter is the `SoapFormatter` type, which serializes data in a proper SOAP envelope. In a nutshell, the Simple Object Access Protocol (SOAP) defines a standard process in which you can invoke methods in a platform- and OS-neutral manner.

Assuming you have set a reference to the `System.Runtime.Serialization.Formatters.Soap.dll` assembly (and imported the `System.Runtime.Serialization.Formatters.Soap` namespace), you can persist and retrieve a `JamesBondCar` as a SOAP message simply by replacing each occurrence of `BinaryFormatter` with `SoapFormatter`. Consider the following new method of the `Program` class, which serializes an object to a local file:

```

// Be sure to import System.Runtime.Serialization.Formatters.Soap
// and reference System.Runtime.Serialization.Formatters.Soap.dll.
static void SaveAsSoapFormat (object objGraph, string fileName)
{
    // Save object to a file named CarData.soap in SOAP format.
    SoapFormatter soapFormat = new SoapFormatter();

    using(Stream fStream = new FileStream(fileName,
        FileMode.Create, FileAccess.Write, FileShare.None))
    {
        soapFormat.Serialize(fStream, objGraph);
    }
    Console.WriteLine("> Saved car in SOAP format!");
}

```

As before, you use `Serialize()` and `Deserialize()` to move the object graph into and out of the stream. If you call this method from `Main()` and run the application, you can open the resulting `*.soap` file. Here you can locate the XML elements that mark the stateful values of the current `JamesBondCar`, as well as the relationship between the objects in the graph by using the #ref tokens (see Figure 20-6).



Figure 20-6. JamesBondCar serialized using a SoapFormatter

Serializing Objects Using the XmlSerializer

In addition to the SOAP and binary formatters, the `System.Xml.dll` assembly provides a third formatter, `System.Xml.Serialization.XmlSerializer`. You can use this formatter to persist the *public* state of a given object as pure XML, as opposed to XML data wrapped within a SOAP message. Working with this type is a bit different from working with the `SoapFormatter` or `BinaryFormatter` type. Consider the following code, which assumes you have imported the `System.Xml.Serialization` namespace:

```
static void SaveAsXmlFormat(object objGraph, string fileName)
{
    // Save object to a file named CarData.xml in XML format.
    XmlSerializer xmlFormat = new XmlSerializer(typeof(JamesBondCar));

    using(Stream fStream = new FileStream(fileName,
        FileMode.Create, FileAccess.Write, FileShare.None))
    {
        xmlFormat.Serialize(fStream, objGraph);
    }
    Console.WriteLine("=> Saved car in XML format!");
}
```

The key difference is that the `XmlSerializer` type requires you to specify type information that represents the class you want to serialize. If you were to look within the newly generated XML file (assuming you call this new method from within `Main()`), you would find the XML data shown here:

```
<?xml version="1.0"?>
<JamesBondCar xmlns:xsi="http://www.w3.org/2001/XMLSchema-instance"
  xmlns:xsd="http://www.w3.org/2001/XMLSchema">
  <theRadio>
    <hasTweeters>true</hasTweeters>
    <hasSubWoofers>false</hasSubWoofers>
    <stationPresets>
      <double>89.3</double>
      <double>105.1</double>
      <double>97.1</double>
    </stationPresets>
```

```

<radioID>XF-552RR6</radioID>
</theRadio>
<isHatchBack>false</isHatchBack>
<canFly>true</canFly>
<canSubmerge>false</canSubmerge>
</JamesBondCar>
```

Note The `XmlSerializer` demands that all serialized types in the object graph support a default constructor (so be sure to add it back if you define custom constructors). If this is not the case, you will receive an `InvalidOperationException` at runtime.

Controlling the Generated XML Data

If you have a background in XML technologies, you know that it is often critical to ensure the data within an XML document conforms to a set of rules that establish the *validity* of the data. Understand that a *valid* XML document does not have anything to do with the syntactic well-being of the XML elements (e.g., all opening elements must have a closing element). Rather, valid documents conform to agreed-upon formatting rules (e.g., field X must be expressed as an attribute and not a sub-element), which are typically defined by an XML schema or document-type definition (DTD) file.

By default, `XmlSerializer` serializes all public fields/properties as XML elements, rather than as XML attributes. If you wish to control how the `XmlSerializer` generates the resulting XML document, you can decorate types with any number of additional .NET attributes from the `System.Xml.Serialization` namespace. Table 20-12 documents some (but not all) of the .NET attributes that influence how XML data is encoded to a stream.

Table 20-12. Select Attributes of the `System.Xml.Serialization` Namespace

.NET Attribute	Meaning in Life
<code>[XmlAttribute]</code>	You can use this .NET attribute on a public field or property in a class to tell <code>XmlSerializer</code> to serialize the data as an XML attribute (rather than as a sub-element).
<code>[XmlElement]</code>	The field or property will be serialized as an XML element named as you so choose.
<code>[XmlAttribute]</code>	This attribute provides the element name of an enumeration member.
<code>[XmlRoot]</code>	This attribute controls how the root element will be constructed (namespace and element name).
<code>[XmlText]</code>	The property or field will be serialized as XML text (i.e. the content between the start tag and the end tag of the root element).
<code>[XmlType]</code>	This attribute provides the name and namespace of the XML type.

This simple example illustrates how the field data of JamesBondCar is currently persisted as XML:

```
<?xml version="1.0" encoding="utf-8"?>
<JamesBondCar xmlns:xsi="http://www.w3.org/2001/XMLSchema-instance"
    xmlns:xsd="http://www.w3.org/2001/XMLSchema">
...
    <canFly>true</canFly>
    <canSubmerge>false</canSubmerge>
</JamesBondCar>
```

If you wish to specify a custom XML namespace that qualifies the JamesBondCar and encodes the canFly and canSubmerge values as XML attributes, you can do so by modifying the C# definition of JamesBondCar:

```
[XmlRoot(Namespace = "http://www.MyCompany.com")]
public class JamesBondCar : Car
{
    [XmlAttribute]
    public bool canFly;
    [XmlAttribute]
    public bool canSubmerge;
}
```

This yields the following XML document (note the opening <JamesBondCar> element):

```
<?xml version="1.0""?>
<JamesBondCar xmlns:xsi="http://www.w3.org/2001/XMLSchema-instance"
    xmlns:xsd="http://www.w3.org/2001/XMLSchema"
    canFly="true" canSubmerge="false"
    xmlns="http://www.MyCompany.com">
...
</JamesBondCar>
```

Of course, you can use many other attributes to control how the `XmlSerializer` generates the resulting XML document. For full details, look up the `System.Xml.Serialization` namespace in the .NET Framework 4.0 SDK documentation.

Serializing Collections of Objects

Now that you have seen how to persist a single object to a stream, you're ready to examine how to save a set of objects. As you might have noticed, the `Serialize()` method of the `IFormatter` interface does not provide a way to specify an arbitrary number of objects as input (only a single `System.Object`). On a related note, the return value of `Deserialize()` is, again, a single `System.Object` (the same basic limitation holds true for `XmlSerializer`):

```
public interface IFormatter
{
...
    object Deserialize(Stream serializationStream);
```

```
    void Serialize(Stream serializationStream, object graph);
}
```

Recall that the `System.Object` represents a complete tree of objects. Given this, if you pass in an object that has been marked as `[Serializable]` and contains other `[Serializable]` objects, the entire set of objects is persisted in a single method call. As luck would have it, most of the types you find in the `System.Collections` and `System.Collections.Generic` namespaces have already been marked as `[Serializable]`. Therefore, if you wish to persist a set of objects, simply add the desired set to the container (such as an `ArrayList` or a `List<T>`) and serialize the object to your stream of choice.

Now assume that you want to update the `JamesBondCar` class with a two-argument constructor, so you can set a few pieces of state data (note that you add back the default constructor as required by the `XmlSerializer`):

```
[Serializable,
 XmlRoot(Namespace = "http://www.MyCompany.com")]
public class JamesBondCar : Car
{
    public JamesBondCar(bool skyWorthy, bool seaWorthy)
    {
        canFly = skyWorthy;
        canSubmerge = seaWorthy;
    }
    // The XmlSerializer demands a default constructor!
    public JamesBondCar(){}
    ...
}
```

With this, you can now persist any number of `JamesBondCars`:

```
static void SaveListOfCars()
{
    // Now persist a List<T> of JamesBondCars.
    List<JamesBondCar> myCars = new List<JamesBondCar>();
    myCars.Add(new JamesBondCar(true, true));
    myCars.Add(new JamesBondCar(true, false));
    myCars.Add(new JamesBondCar(false, true));
    myCars.Add(new JamesBondCar(false, false));

    using(Stream fStream = new FileStream("CarCollection.xml",
        FileMode.Create, FileAccess.Write, FileShare.None))
    {
        XmlSerializer xmlFormat = new XmlSerializer(typeof(List<JamesBondCar>));
        xmlFormat.Serialize(fStream, myCars);
    }
    Console.WriteLine("=> Saved list of cars!");
}
```

You use `XmlSerializer` here, so you are required to specify type information for each of the sub-objects within the root object (`List<JamesBondCar>`, in this case). However, the logic would be even more straightforward if you were to use the `BinaryFormatter` or `SoapFormatter` type, instead:

```

static void SaveListOfCarsAsBinary()
{
    // Save ArrayList object (myCars) as binary.
    List<JamesBondCar> myCars = new List<JamesBondCar>();

    BinaryFormatter binFormat = new BinaryFormatter();
    using(Stream fStream = new FileStream("AllMyCars.dat",
        FileMode.Create, FileAccess.Write, FileShare.None))
    {
        binFormat.Serialize(fStream, myCars);
    }
    Console.WriteLine("=> Saved list of cars in binary!");
}

```

■ **Source Code** You can find the SimpleSerialize application under the Chapter 20 subdirectory.

Customizing the Soap/Binary Serialization Process

In a majority of cases, the default serialization scheme provided by the .NET platform will be exactly what you require. Simply apply the `[Serializable]` attribute to your related types and pass the tree of objects to your formatter of choice for processing. In some cases, however, you might wish to become more involved with how a tree is constructed and handled during the serialization process. For example, perhaps you have a business rule that says all field data must be persisted using a particular format, or perhaps you wish to add additional bits of data to the stream that do not map directly to fields in the object being persisted (e.g., timestamps and unique identifiers).

When you wish to become more involved with the process of object serialization, the `System.Runtime.Serialization` namespace provides several types that allow you to do so. Table 20-13 describes some of the core types you should be aware of.

Table 20-13. *System.Runtime.Serialization Namespace Core Types*

Type	Meaning in Life
<code>ISerializable</code>	You can implement this interface on a <code>[Serializable]</code> type to control its serialization and deserialization.
<code>ObjectIDGenerator</code>	This type generates IDs for members in an object graph.
<code>[OnDeserialized]</code>	This attribute allows you to specify a method that will be called immediately after the object has been deserialized.
<code>[OnDeserializing]</code>	This attribute allows you to specify a method that will be called before the deserialization process.

Table 20-13. System.Runtime.Serialization Namespace Core Types (continued)

Type	Meaning in Life
[OnSerialized]	This attribute allows you to specify a method that will be called immediately after the object has been serialized.
[OnSerializing]	This attribute allows you to specify a method that will be called before the serialization process.
[OptionalField]	This attribute allows you to define a field on a type that can be missing from the specified stream.
[SerializationInfo]	In essence, this class is a <i>property bag</i> that maintains name/value pairs representing the state of an object during the serialization process.

A Deeper Look at Object Serialization

Before you examine various ways that you can customize the serialization process, you will find it helpful to take a deeper look at what takes place behind the scenes. When the `BinaryFormatter` serializes an object graph, it is in charge of transmitting the following information into the specified stream:

- The fully qualified name of the objects in the graph (e.g., `MyApp.JamesBondCar`)
- The name of the assembly defining the object graph (e.g., `MyApp.exe`)
- An instance of the `SerializationInfo` class that contains all stateful data maintained by the members in the object graph

During the deserialization process, the `BinaryFormatter` uses this same information to build an identical copy of the object, using the information extracted from the underlying stream. `SoapFormatter` uses a quite similar process.

■ **Note** Recall that the `XmlSerializer` does not persist a type's fully qualified name or the name of the defining assembly; this behavior helps keep the state of the object as mobile as possible. This type is concerned only with persisting exposed public data.

Beyond moving the required data into and out of a stream, formatters also analyze the members in the object graph for the following pieces of infrastructure:

- A check is made to determine whether the object is marked with the `[Serializable]` attribute. If the object is not, a `SerializationException` is thrown.

- If the object is marked [Serializable], a check is made to determine whether the object implements the ISerializable interface. If this is the case, GetObjectData() is called on the object.
- If the object does not implement ISerializable, the default serialization process is used, serializing all fields not marked as [NonSerialized].

In addition to determining whether the type supports ISerializable, formatters are also responsible for discovering whether the types in question support members that have been adorned with the [OnSerializing], [OnSerialized], [OnDeserializing], or [OnDeserialized] attributes. You'll examine the role of these attributes in momentarily, but first you need to look at the role of ISerializable.

Customizing Serialization Using ISerializable

Objects that are marked [Serializable] have the option of implementing the ISerializable interface. Doing so lets you get “involved” with the serialization process and perform any pre- or post-data formatting.

Note Since the release of .NET 2.0, the preferred way to customize the serialization process is to use the serialization attributes (described next). However, knowledge of ISerializable is important for the purpose of maintaining existing systems.

The ISerializable interface is quite simple, given that it defines only a single method, GetObjectData():

```
// When you wish to tweak the serialization process,
// implement ISerializable.
public interface ISerializable
{
    void GetObjectData(SerializationInfo info,
                      StreamingContext context);
}
```

The GetObjectData() method is called automatically by a given formatter during the serialization process. The implementation of this method populates the incoming SerializationInfo parameter with a series of name/value pairs that (typically) map to the field data of the object being persisted. SerializationInfo defines numerous variations on the overloaded AddValue() method, as well as a small set of properties that allow the type to get and set the type's name, defining assembly, and member count. Here is a partial snapshot:

```
public sealed class SerializationInfo
{
    public SerializationInfo(Type type, IFormatterConverter converter);
    public string AssemblyName { get; set; }
    public string FullName { get; set; }
```

```

public int MemberCount { get; }
public void AddValue(string name, short value);
public void AddValue(string name, ushort value);
public void AddValue(string name, int value);
...
}

```

Types that implement the `ISerializable` interface must also define a special constructor that takes the following signature:

```

// You must supply a custom constructor with this signature
// to allow the runtime engine to set the state of your object.
[Serializable]
class SomeClass : ISerializable
{
    protected SomeClass (SerializationInfo si, StreamingContext ctx) {...}
    ...
}

```

Notice that the visibility of this constructor is set as `protected`. This is permissible because the formatter will have access to this member, regardless of its visibility. These special constructors tend to be marked as protected (or private for that matter) to ensure that the casual object user can never create an object in this manner. The first parameter of this constructor is an instance of the `SerializationInfo` type (which you've seen previously).

The second parameter of this special constructor is a `StreamingContext` type, which contains information regarding the source of the bits. The most informative member of `StreamingContext` is the `State` property, which represents a value from the `StreamingContextStates` enumeration. The values of this enumeration represent the basic composition of the current stream.

Unless you intend to implement some low-level custom remoting services, you will seldom need to deal with this enumeration directly. Nevertheless, here are the possible names of the `StreamingContextStates` enum (consult the .NET Framework 4.0 SDK documentation for full details):

```

public enum StreamingContextStates
{
    CrossProcess,
    CrossMachine,
    File,
    Persistence,
    Remoting,
    Other,
    Clone,
    CrossAppDomain,
    All
}

```

Now let's look at how to customize the serialization process using `ISerializable`. Assume you have a new Console Application project (named `CustomSerialization`) that defines a class type containing two points of string data. Also assume that you must ensure that the `string` objects are serialized to the stream all uppercase and deserialized from the stream in lowercase. To account for such rules, you could implement `ISerializable` like this (be sure to import the `System.Runtime.Serialization` namespace):

```
[Serializable]
class StringData : ISerializable
{
    private string dataItemOne = "First data block";
    private string dataItemTwo= "More data";

    public StringData(){}
    protected StringData(SerializationInfo si, StreamingContext ctx)
    {
        // Rehydrate member variables from stream.
        dataItemOne = si.GetString("First_Item").ToLower();
        dataItemTwo = si.GetString("dataItemTwo").ToLower();
    }

    void ISerializable.GetObjectData(SerializationInfo info, StreamingContext ctx)
    {
        // Fill up the SerializationInfo object with the formatted data.
        info.AddValue("First_Item", dataItemOne.ToUpper());
        info.AddValue("dataItemTwo", dataItemTwo.ToUpper());
    }
}
```

Notice that when you fill the `SerializationInfo` type with the `GetObjectData()` method, you are *not* required to name the data points identically to the type's internal member variables. This can obviously be helpful if you need to further decouple the type's data from the persisted format. Be aware, however, that you will need to obtain the values from the special, protected constructor using the same names assigned within `GetObjectData()`.

To test your customization, assume that you want to persist an instance of `MyStringData` using a `SoapFormatter` (so update your assembly references and imports accordingly):

```
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Custom Serialization *****");

    // Recall that this type implements ISerializable.
    StringData myData = new StringData();

    // Save to a local file in SOAP format.
    SoapFormatter soapFormat = new SoapFormatter();
    using(Stream fStream = new FileStream("MyData.soap",
        FileMode.Create, FileAccess.Write, FileShare.None))
    {
        soapFormat.Serialize(fStream, myData);
    }
    Console.ReadLine();
}
```

When you view the resulting *.soap file, you will see that the string fields have been persisted in uppercase (see Figure 20-7).



Figure 20-7. Customizing your serialization with *ISerializable*

Customizing Serialization Using Attributes

Although implementing the *ISerializable* interface is one way to customize the serialization process, the preferred way to customize the serialization process since the release of .NET 2.0 is to define methods that are attributed with any of the new serialization-centric attributes: [*OnSerializing*], [*OnSerialized*], [*OnDeserializing*], or [*OnDeserialized*]. Using these attributes is less cumbersome than implementing *ISerializable* because you do not need to interact manually with an incoming *SerializationInfo* parameter. Instead, you can modify your state data directly, while the formatter operates on the type.

Note You can find these serialization attributes defined in the *System.Runtime.Serialization* namespace.

When you define method decorated with these attributes, you must define the methods so they receive a *StreamingContext* parameter and return nothing (otherwise, you will receive a runtime exception). Note that you are not required to account for each of the serialization-centric attributes, and you can simply contend with the stages of serialization you want to intercept. The following snippet illustrates this. Here, a new *[Serializable]* type has the same requirements as *StringData*, but this time you account for using the *[OnSerializing]* and *[OnDeserialized]* attributes:

```
[Serializable]
class MoreData
{
    private string dataItemOne = "First data block";
    private string dataItemTwo= "More data";

    [OnSerializing]
    private void OnSerializing(StreamingContext context)
    {
        // Called during the serialization process.
        dataItemOne = dataItemOne.ToUpper();
        dataItemTwo = dataItemTwo.ToUpper();
    }
}
```

```
[OnDeserialized]
private void OnDeserialized(StreamingContext context)
{
    // Called once the deserialization process is complete.
    dataItemOne = dataItemOne.ToLower();
    dataItemTwo = dataItemTwo.ToLower();
}
```

If you were to serialize this new type, you would again find that the data has been persisted as uppercase and deserialized as lowercase.

■ **Source Code** You can find the CustomSerialization project under the Chapter 20 subdirectory.

With this example behind you, your exploration of the core details of object serialization services, including various ways to customize the process, is complete. As you have seen, the serialization and deserialization process makes it easy to persist large amounts of data, and it can be less labor-intensive than working with the various reader/writer classes of the `System.IO` namespace.

Summary

You began this chapter by examining the use of the `DirectoryInfo` and `FileInfo` types. As you learned, these classes allow you to manipulate a physical file or directory on your hard drive. Next, you examined a number of classes derived from the abstract `Stream` class. Given that `Stream`-derived types operate on a raw stream of bytes, the `System.IO` namespace provides numerous reader/writer types (e.g., `StreamWriter`, `StringWriter`, and `BinaryWriter`) that simplify the process. Along the way, you also checked out the functionality provided by `DriveType`, learned how to monitor files using the `FileSystemWatcher` type, and saw how to interact with streams in an asynchronous manner.

This chapter also introduced you to the topic of object serialization services. As you have seen, the .NET platform uses an object graph to account for the full set of related objects that you want to persist to a stream. As long as each member in the object graph has been marked with the `[Serializable]` attribute, the data is persisted using your format of choice (binary or SOAP).

You also learned that it is possible to customize the out-of-the-box serialization process using two possible approaches. First, you learned how to implement the `ISerializable` interface (and support a special private constructor), which enables you to become more involved with how formatters persist the supplied data. Second, you learned about a set of .NET attributes that simplify the process of custom serialization. All you need to do is apply the `[OnSerializing]`, `[OnSerialized]`, `[OnDeserializing]`, or `[OnDeserialized]` attribute on members that take a `StreamingContext` parameter, and the formatters will invoke them accordingly.



ADO.NET Part I: The Connected Layer

As you might expect, the .NET platform defines a number of namespaces that allow you to interact directly with machine local and remote relational databases. Collectively speaking, these namespaces are known as *ADO.NET*. In this chapter, you'll learn about the overall role of ADO.NET, then move on to the topic of ADO.NET data providers. The .NET platform supports numerous data providers, each of which is optimized to communicate with a specific database management system (e.g., Microsoft SQL Server, Oracle, and MySQL).

After you understand the common functionality provided by various data providers, you will then look at the data provider factory pattern. As you will see, using types within the `System.Data.Common` namespace (and a related `App.config` file), you can build a single code base that can dynamically pick and choose the underlying data provider without the need to recompile or redeploy the application's code base.

Perhaps most importantly, this chapter will give you the chance to build a custom data access library assembly (`AutoLotDAL.dll`) that encapsulates various database operations performed on a custom database named AutoLot. You will expand this library in Chapters 23 and 24 and leverage it over many of this book's remaining chapters. Finally, you will wrap things up by examining the topic of database transactions.

A High-Level Definition of ADO.NET

If you have a background in Microsoft's previous COM-based data access model (Active Data Objects, or ADO), you need to understand that ADO.NET has little to do with ADO beyond the letters *A*, *D*, and *O*. While it is true that there is some relationship between the two systems (e.g., each has the concept of connection and command objects), some familiar ADO types (e.g., the `Recordset`) no longer exist. Furthermore, you can find many new ADO.NET types that have no direct equivalent under classic ADO (e.g., the `data adapter`).

Unlike classic ADO, which was primarily designed for tightly coupled client/server systems, ADO.NET was built with the disconnected world in mind, using `DataSets`. This type represents a local copy of any number of related data tables, each of which contains a collection of rows and columns. Using the `DataSet`, the calling assembly (such as a web page or desktop executable) is able to manipulate and update a `DataSet`'s contents while disconnected from the data source and send any modified data back for processing using a related *data adapter*.

Perhaps the most fundamental difference between classic ADO and ADO.NET is that ADO.NET is a managed library of code; therefore, it plays by the same rules as any other managed library. The types

that make up ADO.NET use the CLR memory management protocol, adhere to the same type system (e.g., classes, interfaces, enums, structures, and delegates), and can be accessed by any .NET language.

From a programmatic point of view, the bulk of ADO.NET is represented by a core assembly named `System.Data.dll`. Within this binary, you find a good number of namespaces (see Figure 21-1), many of which represent the types of a particular ADO.NET data provider (defined momentarily).




Figure 21-1. *System.Data.dll is the core ADO.NET assembly*

It turns out most Visual Studio 2010 project templates automatically reference this key data access assembly. However, you do need to update your code files to import the namespaces you wish to use, as in this example:

```
using System;

// Bring in some ADO.NET namespaces!
using System.Data;
using System.Data.SqlClient;

namespace MyApp
{
    class Program
    {
        static void Main(string[] args)
        {
        }
    }
}
```

You should also understand that there are other ADO.NET-centric assemblies beyond `System.Data.dll` (e.g., `System.Data.OracleClient.dll` and `System.Data.Entity.dll`) that you might need to reference manually in your current project using the Add Reference dialog box.

The Three Faces of ADO.NET

You can use the ADO.NET libraries in three conceptually unique manners: connected, disconnected, or through the Entity Framework. When you use the *connected layer* (the subject of this chapter), your code base explicitly connects to and disconnects from the underlying data store. When you use ADO.NET in this manner, you typically interact with the data store using connection objects, command objects, and data reader objects.

The disconnected layer (you will learn more about this in Chapter 22) allows you to manipulate a set of `DataTable` objects (contained within a `DataSet`) that functions as a client-side copy of the external data. When you obtain a `DataSet` using a related data adapter object, the connection is automatically opened and closed on your behalf. As you would guess, this approach helps free up connections for other callers quickly and goes a long way toward increasing the scalability of your systems.

Once a caller receives a `DataSet`, it is able to traverse and manipulate the contents without incurring the cost of network traffic. Also, if the caller wishes to submit the changes back to the data store, the data adapter (in conjunction with a set of SQL statements) is used to update the data source; at this point the connection is reopened for the database updates to occur, and then closed again immediately.

With the release of .NET 3.5 SP1, ADO.NET was enhanced to support a new API termed the Entity Framework (or simply, EF). Using EF, you will find that many of the low-level database specifics (such as complex SQL queries) are hidden from view and authored on your behalf when you generate a fitting LINQ query (e.g., LINQ to Entities). You will examine this aspect of ADO.NET in Chapter 23.

Understanding ADO.NET Data Providers

Unlike other database APIs you might have used in the past, ADO.NET does not provide a single set of types that communicate with multiple database management systems (DBMSs). Rather, ADO.NET supports multiple *data providers*, each of which is optimized to interact with a specific DBMS. The first benefit of this approach is that you can program a specific data provider to access any unique features of a particular DBMS. The second benefit is that a specific data provider can connect directly to the underlying engine of the DBMS in question without an intermediate mapping layer standing between the tiers.

Simply put, a *data provider* is a set of types defined in a given namespace that understand how to communicate with a specific type of data source. Regardless of which data provider you use, each defines a set of class types that provide core functionality. Table 21-1 documents some of the core common types, their base class (all defined in the `System.Data.Common` namespace), and the key interfaces (each is defined in the `System.Data` namespace) they implement.

Table 21-1. The Core Objects of an ADO.NET Data Provider

Type of Object	Base Class	Relevant Interfaces	Meaning in Life
Connection	<code>DbConnection</code>	<code>IDbConnection</code>	Provides the ability to connect to and disconnect from the data store. Connection objects also provide access to a related transaction object.
Command	<code>DbCommand</code>	<code>IDbCommand</code>	Represents a SQL query or a stored procedure. Command objects also provide access to the provider's data reader object.
DataReader	<code>DbDataReader</code>	<code>IDataReader</code> , <code>IDataRecord</code>	Provides forward-only, read-only access to data using a server-side cursor.

Table 21-1. The Core Objects of an ADO.NET Data Provider (continued)

Type of Object	Base Class	Relevant Interfaces	Meaning in Life
DataAdapter	DbDataAdapter	IDataAdapter, IDbDataAdapter	Transfers DataSets between the caller and the data store. Data adapters contain a connection and a set of four internal command objects used to select, insert, update, and delete information from the data store.
Parameter	DbParameter	IDataParameter, IDbDataParameter	Represents a named parameter within a parameterized query.
Transaction	DbTransaction	IDbTransaction	Encapsulates a database transaction.

Although the specific names of these core classes will differ among data providers (e.g., SqlConnection vs. OracleConnection vs. OdbcConnection vs. MySqlConnection), each class derives from the same base class (DbConnection, in the case of connection objects) that implements identical interfaces (e.g., IDbConnection). Given this, you would be correct to assume that once you learn how to work with one data provider, the remaining providers prove quite straightforward.

■ **Note** When you refer to a connection object under ADO.NET, you're actually referring to a specific DbConnection-derived type; there is no class literally named *Connection*. The same idea holds true for a *command object*, *data adapter object*, and so forth. As a naming convention, the objects in a specific data provider are prefixed with the name of the related DBMS (e.g., SqlConnection, OracleConnection, and SqlDataReader).

Figure 21-2 shows the big picture behind ADO.NET data providers. Note how the diagram illustrates that the *Client Assembly* can literally be any type of .NET application: console program, Windows Forms application, WPF application, ASP.NET web page, WCF service, a .NET code library, and so on.




Figure 21-2. ADO.NET data providers provide access to a given DBMS

A data provider will supply you with other types beyond the objects shown in Figure 21-2; however, these core objects define a common baseline across all data providers.

The Microsoft-Supplied ADO.NET Data Providers

Microsoft's .NET distribution ships with numerous data providers, including a provider for Oracle, SQL Server, and OLE DB/ODBC-style connectivity. Table 21-2 documents the namespace and containing assembly for each Microsoft ADO.NET data provider.

Table 21-2. Microsoft ADO.NET Data Providers

Data Provider	Namespace	Assembly
OLE DB	System.Data.OleDb	System.Data.dll
Microsoft SQL Server	System.Data.SqlClient	System.Data.dll
Microsoft SQL Server Mobile	System.Data.SqlServerCe	System.Data.SqlServerCe.dll
ODBC	System.Data.Odbc	System.Data.dll

■ **Note** There is no specific data provider that maps directly to the Jet engine (and therefore Microsoft Access). If you wish to interact with an Access data file, you can do so using the OLE DB or ODBC data provider.

The OLE DB data provider, which is composed of the types defined in the `System.Data.OleDb` namespace, allows you to access data located in any data store that supports the classic COM-based OLE DB protocol. You can use this provider to communicate with any OLE DB-compliant database simply by tweaking the `Provider` segment of your connection string.

However, the OLE DB provider interacts with various COM objects behind the scenes, which can affect the performance of your application. By and large, the OLE DB data provider is only useful if you interact with a DBMS that does not define a specific .NET data provider. However, given the fact that these days any DBMS worth its salt should have a custom ADO.NET data provider for download, you should consider `System.Data.OleDb` a legacy namespace that has little use in the .NET 4.0 world (this is even more the case with the advent of the data provider factory model introduced under .NET 2.0, which you will learn about shortly).

■ **Note** There is one case in which using the types of `System.Data.OleDb` is necessary: when you need to communicate with Microsoft SQL Server version 6.5 or earlier. The `System.Data.SqlClient` namespace can only communicate with Microsoft SQL Server version 7.0 or higher.

The Microsoft SQL Server data provider offers direct access to Microsoft SQL Server data stores—and *only* SQL Server data stores (version 7.0 and greater). The `System.Data.SqlClient` namespace contains the types used by the SQL Server provider and offers the same basic functionality as the OLE DB provider. The key difference is that the SQL Server provider bypasses the OLE DB layer and gives numerous performance benefits. The Microsoft SQL Server data provider also allows you to gain access to the unique features of this particular DBMS.

The remaining Microsoft-supplied providers (`System.Data.Odbc` and `System.Data.SqlClientCe`) provide access to ODBC connections, and the SQL Server Mobile edition DBMS (commonly used by handheld devices, such as Windows Mobile). The ODBC types defined within the `System.Data.Odbc` namespace are typically only useful if you need to communicate with a given DBMS for which there is no custom .NET data provider. This is true because ODBC is a widespread model that provides access to a number of data stores.

A Word Regarding `System.Data.OracleClient.dll`

Earlier versions of the .NET platform shipped with an assembly named `System.Data.OracleClient.dll`, which as the name suggests, offered a data provider to communicate with Oracle databases. As of .NET 4.0, however, this assembly has been marked as *obsolete* and will eventually be *deprecated*.

At first glance, this might cause you to fear that ADO.NET is slowly becoming focused squarely on Microsoft-centric data stores; however, this is not the case. Oracle provides its own custom .NET assembly, which follows the same overall design guidelines as the data providers provided by Microsoft.

If you need to obtain this .NET assembly, you can visit the downloads section of Oracle's web site at www.oracle.com/technology/tech/windows/odpnet/index.html.

Obtaining Third-Party ADO.NET Data Providers

In addition to the data providers that ship from Microsoft (as well as Oracle's custom .NET library), numerous third-party data providers exist for various open source and commercial databases. While you will most likely be able to obtain an ADO.NET data provider directly from the database vendor, you should be aware of the following site: www.sqlsummit.com/DataProv.htm.

This web site is one of many sites that document each known ADO.NET data provider and provide links for more information and downloads. Here you will find numerous ADO.NET providers, including SQLite, IBM DB2, MySQL, PostgreSQL, TurboDB, Sybase, and many others.

Given the large number of ADO.NET data providers, the examples in this book will use the Microsoft SQL Server data provider (`System.Data.SqlClient.dll`). Recall that this provider allows you to communicate with Microsoft SQL Server version 7.0 and higher, including SQL Server Express Edition. If you intend to use ADO.NET to interact with another DBMS, you should have no problem doing so once you understand the material presented in the pages that follow.

Additional ADO.NET Namespaces

In addition to the .NET namespaces that define the types of a specific data provider, the .NET base class libraries provide a number of additional ADO.NET-centric namespaces, some of which you can see in Table 21-3 (again, Chapter 24 will address the assemblies and namespaces specific to Entity Framework).

Table 21-3. Select Additional ADO.NET-Centric Namespaces

Namespace	Meaning in Life
<code>Microsoft.SqlServer.Server</code>	This namespace provides types that facilitate CLR and SQL Server 2005 and later integration services.
<code>System.Data</code>	This namespace defines the core ADO.NET types used by all data providers, including common interfaces and numerous types that represent the disconnected layer (e.g., <code>DataSet</code> and <code>DataTable</code>).
<code>System.Data.Common</code>	This namespace contains types shared between all ADO.NET data providers, including the common abstract base classes.
<code>System.Data.Sql</code>	This namespace contains types that allow you to discover Microsoft SQL Server instances installed on the current local network.
<code>System.Data.SqlTypes</code>	This namespace contains native data types used by Microsoft SQL Server. You can always use the corresponding CLR data types, but the <code>SqlTypes</code> are optimized to work with SQL Server (e.g., if your SQL Server database contains an integer value, you can represent it using either <code>int</code> or <code>SqlTypes.SqlInt32</code>).

Note that this chapter does not examine every type within every ADO.NET namespace (that task would require a large book all by itself); however, it is quite important that you understand the types within the `System.Data` namespace.

The Types of the `System.Data` Namespace

Of all the ADO.NET namespaces, `System.Data` is the lowest common denominator. You cannot build ADO.NET applications without specifying this namespace in your data access applications. This namespace contains types that are shared among all ADO.NET data providers, regardless of the underlying data store. In addition to a number of database-centric exceptions (e.g., `NoNullAllowedException`, `RowNotInTableException`, and `MissingPrimaryKeyException`), `System.Data` contains types that represent various database primitives (e.g., tables, rows, columns, and constraints), as well as the common interfaces implemented by data provider objects. Table 21-4 lists some of the core types you should be aware of.

Table 21-4. Core Members of the `System.Data` Namespace

Type	Meaning in Life
Constraint	Represents a constraint for a given <code>DataColumn</code> object.
<code> DataColumn</code>	Represents a single column within a <code>DataTable</code> object.
<code> DataRelation</code>	Represents a parent/child relationship between two <code>DataTable</code> objects.
<code> DataRow</code>	Represents a single row within a <code>DataTable</code> object.
<code> DataSet</code>	Represents an in-memory cache of data consisting of any number of interrelated <code>DataTable</code> objects.
<code> DataTable</code>	Represents a tabular block of in-memory data.
<code> DataTableReader</code>	Allows you to treat a <code>DataTable</code> as a fire-hose cursor (forward only, read-only data access).
<code> DataView</code>	Represents a customized view of a <code>DataTable</code> for sorting, filtering, searching, editing, and navigation.
<code> IDataAdapter</code>	Defines the core behavior of a data adapter object.
<code> IDataParameter</code>	Defines the core behavior of a parameter object.
<code> IDataReader</code>	Defines the core behavior of a data reader object.
<code> IDbCommand</code>	Defines the core behavior of a command object.

Table 21-4. Core Members of the System.Data Namespace (continued)

Type	Meaning in Life
IDbDataAdapter	Extends IDataAdapter to provide additional functionality of a data adapter object.
IDbTransaction	Defines the core behavior of a transaction object.

You use the vast majority of the classes within `System.Data` when programming against the disconnected layer of ADO.NET. In the next chapter, you will get to know the details of the `DataSet` and its related cohorts (e.g., `DataTable`, `DataRelation`, and `DataRow`) and how to use them (and a related data adapter) to represent and manipulate client-side copies of remote data.

However, your next task is to examine the core interfaces of `System.Data` at a high level; this can help you understand the common functionality offered by any data provider. You will also learn specific details throughout this chapter; however, for now it's best to focus on the overall behavior of each interface type.

The Role of the IDbConnection Interface

The `IDbConnection` type is implemented by a data provider's *connection object*. This interface defines a set of members used to configure a connection to a specific data store. It also allows you to obtain the data provider's transaction object. Here is the formal definition of `IDbConnection`:

```
public interface IDbConnection : IDisposable
{
    string ConnectionString { get; set; }
    int ConnectionTimeout { get; }
    string Database { get; }
    ConnectionState State { get; }

    IDbTransaction BeginTransaction();
    IDbTransaction BeginTransaction(IsolationLevel il);
    void ChangeDatabase(string databaseName);
    void Close();
    IDbCommand CreateCommand();
    void Open();
}
```

■ **Note** Like many other types in the .NET base class libraries, the `Close()` method is functionally equivalent to calling the `Dispose()` method directly or indirectly within C# by using scope (see Chapter 8).

The Role of the IDbTransaction Interface

The overloaded `BeginTransaction()` method defined by `IDbConnection` provides access to the provider's *transaction object*. You can use the members defined by `IDbTransaction` to interact programmatically with a transactional session and the underlying data store:

```
public interface IDbTransaction : IDisposable
{
    IDbConnection Connection { get; }
    IsolationLevel IsolationLevel { get; }

    void Commit();
    void Rollback();
}
```

The Role of the IDbCommand Interface

Next up is the `IDbCommand` interface, which will be implemented by a data provider's *command object*. Like other data access object models, command objects allow programmatic manipulation of SQL statements, stored procedures, and parameterized queries. Command objects also provide access to the data provider's data reader type through the overloaded `ExecuteReader()` method:

```
public interface IDbCommand : IDisposable
{
    string CommandText { get; set; }
    int CommandTimeout { get; set; }
    CommandType CommandType { get; set; }
    IDbConnection Connection { get; set; }
    IDataParameterCollection Parameters { get; }
    IDbTransaction Transaction { get; set; }
    UpdateRowSource UpdatedRowSource { get; set; }

    void Cancel();
    IDbDataParameter CreateParameter();
    int ExecuteNonQuery();
    IDataReader ExecuteReader();
    IDataReader ExecuteReader(CommandBehavior behavior);
    object ExecuteScalar();
    void Prepare();
}
```

The Role of the IDbDataParameter and IDataParameter Interfaces

Notice that the `Parameters` property of `IDbCommand` returns a strongly typed collection that implements `IDataParameterCollection`. This interface provides access to a set of `IDbDataParameter`-compliant class types (e.g., parameter objects):

```
public interface IDbDataParameter : IDataParameter
{
```

```

    byte Precision { get; set; }
    byte Scale { get; set; }
    int Size { get; set; }
}

```

`IDbDataParameter` extends the `IDataParameter` interface to obtain the following additional behaviors:

```

public interface IDataParameter
{
    DbType DbType { get; set; }
    ParameterDirection Direction { get; set; }
    bool IsNullable { get; }
    string ParameterName { get; set; }
    string SourceColumn { get; set; }
    DataRowVersion SourceVersion { get; set; }
    object Value { get; set; }
}

```

As you will see, the functionality of the `IDbDataParameter` and `IDataParameter` interfaces allows you to represent parameters within a SQL command (including stored procedures) through specific ADO.NET parameter objects, rather than through hard-coded string literals.

The Role of the `IDbDataAdapter` and `IDataAdapter` Interfaces

You use *data adapters* to push and pull `DataSets` to and from a given data store. The `IDbDataAdapter` interface defines a set of properties that you can use to maintain the SQL statements for the related select, insert, update, and delete operations:

```

public interface IDbDataAdapter : IDataAdapter
{
    IDbCommand DeleteCommand { get; set; }
    IDbCommand InsertCommand { get; set; }
    IDbCommand SelectCommand { get; set; }
    IDbCommand UpdateCommand { get; set; }
}

```

In addition to these four properties, an ADO.NET data adapter also picks up the behavior defined in the base interface, `IDataAdapter`. This interface defines the key function of a data adapter type: the ability to transfer `DataSets` between the caller and underlying data store using the `Fill()` and `Update()` methods. The `IDataAdapter` interface also allows you to map database column names to more user-friendly display names with the `TableMappings` property:

```

public interface IDataAdapter
{
    MissingMappingAction MissingMappingAction { get; set; }
    MissingSchemaAction MissingSchemaAction { get; set; }
    ITableMappingCollection TableMappings { get; }

    int Fill(DataSet dataSet);
    DataTable[] FillSchema(DataSet dataSet, SchemaType schemaType);
}

```

```

    IDataParameter[] GetFillParameters();
    int Update(DataSet dataSet);
}

```

The Role of the IDataReader and IDataRecord Interfaces

The next key interface to be aware of is `IDataReader`, which represents the common behaviors supported by a given data reader object. When you obtain an `IDataReader`-compatible type from an ADO.NET data provider, you can iterate over the result set in a forward-only, read-only manner:

```

public interface IDataReader : IDisposable, IDataRecord
{
    int Depth { get; }
    bool IsClosed { get; }
    int RecordsAffected { get; }

    void Close();
    DataTable GetSchemaTable();
    bool NextResult();
    bool Read();
}

```

Finally, `IDataReader` extends `IDataRecord`, which defines many members that allow you to extract a strongly typed value from the stream, rather than casting the generic `System.Object` retrieved from the data reader's overloaded indexer method. Here is a partial listing of the various `GetXXX()` methods defined by `IDataRecord` (see the .NET Framework 4.0 SDK documentation for a complete listing):

```

public interface IDataRecord
{
    int FieldCount { get; }
    object this[ string name ] { get; }
    object this[ int i ] { get; }
    bool GetBoolean(int i);
    byte GetByte(int i);
    char GetChar(int i);
    DateTime GetDateTime(int i);
    decimal GetDecimal(int i);
    float GetFloat(int i);
    short GetInt16(int i);
    int GetInt32(int i);
    long GetInt64(int i);
    ...
    bool IsDBNull(int i);
}

```

■ **Note** You can use the `IDataReader.IsDBNull()` method to discover programmatically whether a specified field is set to null before obtaining a value from the data reader (to avoid triggering a runtime exception). Also recall that C# supports nullable data types (see Chapter 4), which are ideal for interacting with data columns that could be NULL in the database table.

Abstracting Data Providers Using Interfaces

At this point, you should have a better idea of the common functionality found among all .NET data providers. Recall that even though the exact names of the implementing types will differ among data providers, you can program against these types in a similar manner—that's the beauty of interface-based polymorphism. For example, if you define a method that takes an `IDbConnection` parameter, you can pass in any ADO.NET connection object:

```
public static void OpenConnection(IDbConnection cn)
{
    // Open the incoming connection for the caller.
    cn.Open();
}
```

■ **Note** Interfaces are not strictly required; you can achieve the same level of abstraction using abstract base classes (such as `DbConnection`) as parameters or return values.

The same holds true for member return values. For example, consider the following simple C# Console Application project (named `MyConnectionFactory`), which allows you to obtain a specific connection object based on the value of a custom enumeration. For diagnostic purposes, you simply print out the underlying connection object using reflection services, and then enter the following code:

```
using System;
using System.Collections.Generic;
using System.Linq;
using System.Text;

// Need these to get definitions of common interfaces,
// and various connection objects for our test.
using System.Data;
using System.Data.SqlClient;
using System.Data.Odbc;
using System.Data.OleDb;

namespace MyConnectionFactory
{
```

```

// A list of possible providers.
enum DataProvider
{ SqlServer, OleDb, Odbc, None }

class Program
{
    static void Main(string[] args)
    {
        Console.WriteLine("**** Very Simple Connection Factory *****\n");

        // Get a specific connection.
        IDbConnection myCn = GetConnection(DataProvider.SqlServer);
        Console.WriteLine("Your connection is a {0}", myCn.GetType().Name);

        // Open, use and close connection...

        Console.ReadLine();
    }

    // This method returns a specific connection object
    // based on the value of a DataProvider enum.
    static IDbConnection GetConnection(DataProvider dp)
    {
        IDbConnection conn = null;
        switch (dp)
        {
            case DataProvider.SqlServer:
                conn = new SqlConnection();
                break;
            case DataProvider.OleDb:
                conn = new OleDbConnection();
                break;
            case DataProvider.Odbc:
                conn = new OdbcConnection();
                break;
        }
        return conn;
    }
}
}

```

The benefit of working with the general interfaces of `System.Data` (or for that matter, the abstract base classes of `System.Data.Common`) is that you have a much better chance of building a flexible code base that can evolve over time. For example, today you might be building an application that targets Microsoft SQL Server; however, it's possible your company could switch to Oracle months down the road. If you build a solution that hard-codes the MS SQL Server-specific types of `System.Data.SqlClient`, you would obviously need to edit, recompile, and redeploy the assembly should the back-end database management system change.

Increasing Flexibility Using Application Configuration Files

To increase the flexibility of your ADO.NET applications, you could incorporate a client-side *.config file that uses custom key/value pairs within the <appSettings> element. Recall from Chapter 14 that you can obtain the custom data stored within a *.config file programmatically by using types within the System.Configuration namespace. For example, assume you have specified a data provider value within a configuration file, as in this example:

```
<configuration>
  <appSettings>
    <!-- This key value maps to one of our enum values-->
    <add key="provider" value="SqlServer"/>
  </appSettings>
</configuration>
```

With this, you could update Main() to obtain the underlying data provider programmatically. Doing this essentially builds a *connection object factory* that allows you to change the provider, but without requiring you to recompile your code base (you simply change the *.config file). Here are the relevant updates to Main():

```
static void Main(string[] args)
{
  Console.WriteLine("**** Very Simple Connection Factory ****\n");

  // Read the provider key.
  string dataProvString = ConfigurationManager.AppSettings["provider"];

  // Transform string to enum.
  DataProvider dp = DataProvider.None;
  if(Enum.IsDefined(typeof(DataProvider), dataProvString))
    dp = (DataProvider)Enum.Parse(typeof(DataProvider), dataProvString);
  else
    Console.WriteLine("Sorry, no provider exists!");

  // Get a specific connection.
  IDbConnection myCn = GetConnection(dp);
  if(myCn != null)
    Console.WriteLine("Your connection is a {0}", myCn.GetType().Name);

  // Open, use, and close connection...

  Console.ReadLine();
}
```

Note To use the ConfigurationManager type, be sure to set a reference to the System.Configuration.dll assembly and import the System.Configuration namespace.

At this point, you have authored some ADO.NET code that allows you to specify the underlying connection dynamically. One obvious problem, however, is that this abstraction is only used within the `MyConnectionFactory.exe` application. If you were to rework this example within a .NET code library (e.g., `MyConnectionFactory.dll`), you would be able to build any number of clients that could obtain various connection objects using layers of abstraction.

However, obtaining a connection object is only one aspect of working with ADO.NET. To make a worthwhile data provider factory library, you would also have to account for command objects, data readers, data adapters, transaction objects, and other data-centric types. Building such a code library would not necessarily be difficult, but it would require a considerable amount of code and time.

Since the release of .NET 2.0, the kind folks in Redmond have built this exact functionality directly into the .NET base class libraries. You will examine this formal API in just a moment; however, first you need to create a custom database to use throughout this chapter (and for many chapters to come).

■ **Source Code** You can find the `MyConnectionFactory` project under the Chapter 21 subdirectory.

Creating the AutoLot Database

As you work through this chapter, you will execute queries against a simple SQL Server test database named `AutoLot`. In keeping with the automotive theme used throughout this book, this database will contain three interrelated tables (`Inventory`, `Orders`, and `Customers`) that contain various bits of data representing order information for a fictional automobile sales company.

The assumption in this book is that you have a copy of Microsoft SQL Server (7.0 or higher) or a copy of Microsoft SQL Server 2008 Express Edition (<http://msdn.microsoft.com/vstudio/express/sql>). This lightweight database server is perfect for your needs in this book: it is free, it provides a GUI front end (the SQL Server Management Tool) to create and administer your databases, and it integrates with Visual Studio 2010/Visual C# 2010 Express Edition.

To illustrate the last point, the remainder of this section will walk you through the construction of the `AutoLot` database using Visual Studio 2010. If you use Visual C# Express, you can perform operations similar to what is explained here by using the Database Explorer window (you can load this from the **View ➤ Other Windows** menu option).

■ **Note** You will use the `AutoLot` database throughout the rest of this book.

Creating the Inventory Table

To begin building your testing database, launch Visual Studio 2010 and open the Server Explorer using the View menu of the IDE. Next, right-click the Data Connections node and select the Create New SQL Server Database menu option. In the resulting dialog box, connect to the SQL Server installation on your local machine (with the `(local)` token) and specify `AutoLot` as the database name (Windows Authentication should be fine; see Figure 21-3).

■ Note If you use SQL Server Express, you will need to enter (local)\SQLEXPRESS in the Server name text box.



Figure 21-3. Creating a new SQL Server 2008 Express database with Visual Studio 2010

At this point, the AutoLot database is empty of any database objects (e.g., tables and stored procedures). To insert a new database table, right-click the Tables node and select Add New Table (see Figure 21-4).




Figure 21-4. Adding the Inventory table

Use the table editor to add four columns (CarID, Make, Color, and PetName). Ensure that the CarID column has been set to the Primary Key (do this by right-clicking the CarID row and selecting Set Primary Key). Figure 21-5 shows the final table settings (you don't need to change anything in the Column Properties editor, but you should notice the data types for each column).

Column Name	Data Type	Allow Nulls
CarID	int	<input type="checkbox"/>
Make	varchar(50)	<input checked="" type="checkbox"/>
Color	varchar(50)	<input checked="" type="checkbox"/>
PetName	varchar(50)	<input type="checkbox"/>

Column Properties	
(Name)	CarID
Allow Nulls	No
Data Type	int
Default Value or Binding	NULL
(General)	

Figure 21-5. Designing the Inventory table

Save (and then close) your new table; also, be sure you name this new database object **Inventory**. At this point, you should see the **Inventory** table under the **Tables** node of the Server Explorer. Right-click the **Inventory** table icon and select **Show Table Data**. Enter a handful of new automobiles of your choosing (to make it interesting, be sure to include some cars that have identical colors and makes). Figure 21-6 shows one possible list of inventory.

	CarID	Make	Color	PetName
	1000	BMW	Black	Bimmer
	1001	BMW	Tan	Daisy
▶	904	VW	Black	Hank
	83	Ford	Rust	Rusty
	107	Ford	Red	Snake
	678	Yugo	Green	Clunker
	1992	Saab	Pink	Pinkey
*	NULL	NULL	NULL	NULL

◀ ▶ | 3 of 7 | ▶| ▶| ⏪ |

Figure 21-6. Populating the Inventory table

Authoring the GetPetName() Stored Procedure

Later in this chapter in the chapter, you will learn how to use ADO.NET to invoke stored procedures. As you might already know, stored procedures are routines stored within a particular database that operate often on table data to yield a return value. You will add a single stored procedure that will return an automobile's pet name, based on the supplied CarID value. To do so, right-click the Stored Procedures node of the AutoLot database within the Server Explorer and select Add New Stored Procedure. Enter the following in the editor that pops up:

```
CREATE PROCEDURE GetPetName
@carID int,
@petName char(10) output
AS
SELECT @petName = PetName from Inventory where CarID = @carID
```

When you save your procedure, it will automatically be named GetPetName, based on your CREATE PROCEDURE statement (note that Visual Studio 2010 automatically changes the SQL Script to “ALTER PROCEDURE...” as soon as you save it for the first time). Once you do this, you should see your new stored procedure within the Server Explorer (see Figure 21-7).

Note Stored procedures do not have to return data using output parameters, as shown here; however, doing things this way sets the stage for talking about the Direction property of the SqlParameter later in this chapter.




Figure 21-7. The GetPetName stored procedure

Creating the Customers and Orders Tables

Your testing database will have two additional tables: *Customers* and *Orders*. The *Customers* table (as the name suggests) will contain a list of customers; these which will be represented by three columns: *CustID* (which should be set as the primary key), *FirstName*, and *LastName*. You can create the *Customers* table by following the same steps you used to create the *Inventory* table; be sure to create the *Customers* table using the schema shown in Figure 21-8.

The screenshot shows the Microsoft SQL Server Object Explorer interface. A table named 'dbo.Table2' is selected. The table structure is displayed in a grid with columns: 'Column Name', 'Data Type', and 'Allow Nulls'. The rows define the columns: 'CustID' (int, Allow Nulls checked), 'FirstName' (varchar(50), Allow Nulls checked), and 'LastName' (varchar(50), Allow Nulls checked). Below the table grid is a 'Column Properties' pane. Under the '(General)' section, 'Name' is set to 'CustID', 'Allow Nulls' is set to 'No', and 'Data Type' is set to 'int'. There is also a 'Table Designer' section and a '(General)' section for the table itself.

Figure 21-8. Designing the *Customers* table

After you save your table, add a handful of customer records (see Figure 21-9).

The screenshot shows the Microsoft SQL Server Object Explorer interface with a query window titled 'Customers: Query(a...qlexpress.AutoLot)'. The results grid displays four rows of customer data:

	CustID	FirstName	LastName
▶	1	Dave	Brenner
	2	Matt	Walton
	3	Steve	Hagen
*	4	Pat	Walton
	NULL	NULL	NULL

At the bottom of the window, there are navigation buttons for the query results.

Figure 21-9. Populating the *Customers* table

You will use your final table, *Orders*, to represent the automobile a given customer is interested in purchasing. Do this by mapping *OrderID* values to *CarID/CustID* values. Figure 21-10 shows the structure of your final table (again, note that *OrderID* is the primary key).




Figure 21-10. Designing the Orders table

Now add data to your Orders table. Assuming that the OrderID value begins at 1000, select a unique CarID for each CustID value (see Figure 21-11).

	OrderID	CustID	CarID
▶	1000	1	1000
	1001	2	678
	1002	3	904
	1003	4	1992
*	NULL	NULL	NULL

◀ ▶ | 1 of 4 ▶▶ | ⏪ | ⏩ | ⏴ | ⏵ |

Figure 21-11. Populating the Orders table

For example, the entries used in this text indicate that Dave Brenner (CustID = 1) is interested in the black BMW (CarID = 1000), while Pat Walton (CustID = 4) has her eye on the pink Saab (CarID = 1992).

Visually Creating Table Relationships

The final task is to establish parent/child table relationships between the Customers, Orders, and Inventory tables. It is easy to do this using Visual Studio 2010 because you can elect to insert a new database diagram at design time. Using the Server Explorer, right-click the Database Diagrams node of the AutoLot database and select the Add New Diagram menu option. This brings up a dialog box that lets you pick which tables to add to the diagram. Be sure to select each of the tables from the AutoLot database (Figure 21-12).




Figure 21-12. Selecting tables for your diagram

You can begin establishing the relationships between the tables by clicking the CarID key of the Inventory table and (while holding down the mouse button) drag it to the CarID field of the Orders table. Once you release the mouse, accept all defaults from the resulting dialog boxes.

Now repeat the same process to map the CustID key of the Customers table to the CustID field of the Orders table. Once you do this, you should see the class dialog box shown in Figure 21-13 (note that you enable the display of the table relationship labels by right-clicking the designer and selecting Show Relationship Labels).




Figure 21-13. The interconnected Orders, Inventory, and Customers tables

With this, the AutoLot database is complete! This is a far cry from a real-world corporate database, but it will serve your needs over the remainder of this book. Now that you have a database to test with, you can dive into the details of the ADO.NET data provider factory model.

The ADO.NET Data Provider Factory Model

The .NET data provider factory pattern allows you to build a single code base using generalized data access types. Furthermore, using application configuration files (and the `<connectionStrings>` subelement), you can obtain providers and connection strings declaratively, without the need to recompile or redeploy the assembly that uses the ADO.NET APIs.

To understand the data provider factory implementation, recall from Table 21-1 that the classes within a data provider each derive from the same base classes defined within the `System.Data.Common` namespace:

- `DbCommand`: The abstract base class for all command classes
- `DbConnection`: The abstract base class for all connection classes
- `DbDataAdapter`: The abstract base class for all data adapter classes
- `DbDataReader`: The abstract base class for all data reader classes
- `DbParameter`: The abstract base class for all parameter classes
- `DbTransaction`: The abstract base class for all transaction classes

Each of the Microsoft-supplied data providers contains a class type that derives from `System.Data.Common.DbProviderFactory`. This base class defines several methods that retrieve provider-specific data objects. Here is a snapshot of the relevant members of `DbProviderFactory`:

```
DbProviderFactory
{
...
    public virtual DbCommand CreateCommand();
    public virtual DbCommandBuilder CreateCommandBuilder();
    public virtual DbConnection CreateConnection();
    public virtual DbConnectionStringBuilder CreateConnectionStringBuilder();
    public virtual DbDataAdapter CreateDataAdapter();
    public virtual DbDataSourceEnumerator CreateDataSourceEnumerator();
    public virtual DbParameter CreateParameter();
}
```

To obtain the `DbProviderFactory`-derived type for your data provider, the `System.Data.Common` namespace provides a class type named `DbProviderFactories` (note the plural in this type's name). You can use the static `GetFactory()` method to obtain the specific `DbProviderFactory` object of the specified data provider; do this by specifying a string name that represents the .NET namespace containing the provider's functionality:

```
static void Main(string[] args)
{
    // Get the factory for the SQL data provider.
    DbProviderFactory sqlFactory =
        DbProviderFactories.GetFactory("System.Data.SqlClient");
...
}
```

Of course, rather than obtaining a factory using a hard-coded string literal, you could instead read in this information from a client-side *.config file (much like the earlier `MyConnectionFactory` example). You will learn how to do this shortly; for the moment, you can obtain the associated provider-specific data objects (e.g., connections, commands, and data readers) once you obtain the factory for your data provider.

Note For all practical purposes, you can regard the argument sent to `DbProviderFactories.GetFactory()` as the name of the data provider's .NET namespace. In reality, the `machine.config` value uses this string value to load the correct library dynamically from the Global Assembly Cache.

A Complete Data Provider Factory Example

For a complete example, you can create a new C# Console Application (named `DataProviderFactory`) that prints out the automobile inventory of the `AutoLot` database. For this initial example, you will hard-code the data access logic directly within the `DataProviderFactory.exe` assembly (to keep things simple

for the time being). However, once you begin to dig into the details of the ADO.NET programming model, you will isolate your data logic to a specific .NET code library that you will use for the remainder of this book.

Begin by adding a reference to the `System.Configuration.dll` assembly and importing the `System.Configuration` namespace. Next, insert an `App.config` file to the current project and define an empty `<appSettings>` element. Add a new key-named provider that maps to the namespace name of the data provider you wish to obtain (`System.Data.SqlClient`). Also, define a connection string that represents a connection to the AutoLot database (on the local instance of SQL Server Express):

```
<?xml version="1.0" encoding="utf-8" ?>
<configuration>
  <appSettings>
    <!-- Which provider? -->
    <add key="provider" value="System.Data.SqlClient" />

    <!-- Which connection string? -->
    <add key="cnStr" value= "Data Source=(local)\SQLEXPRESS;
      Initial Catalog=AutoLot;Integrated Security=True"/>
  </appSettings>
</configuration>
```

Note You will learn about connection strings in more detail momentarily; however, if you select your AutoLot database icon within the Server Explorer, you can copy-and-paste the correct connection string from the Connection String property of the Visual Studio 2010 Properties Window.

Now that you have a proper `*.config` file, you can read in the provider and `cnStr` values using the `ConfigurationManager.AppSettings` indexer. The provider value will be passed to `DbProviderFactories.GetFactory()` to obtain the data provider-specific factory type. You will use the `cnStr` value to set the `ConnectionString` property of the `DbConnection`-derived type.

Assuming you have imported the `System.Data` and `System.Data.Common` namespaces, you can update your `Main()` method like this:

```
static void Main(string[] args)
{
  Console.WriteLine("***** Fun with Data Provider Factories *****\n");

  // Get Connection string/provider from *.config.
  string dp =
    ConfigurationManager.AppSettings["provider"];
  string cnStr =
    ConfigurationManager.AppSettings["cnStr"];

  // Get the factory provider.
  DbProviderFactory df = DbProviderFactories.GetFactory(dp);
```

```

// Now get the connection object.
using (DbConnection cn = df.CreateConnection())
{
    Console.WriteLine("Your connection object is a: {0}", cn.GetType().Name);
    cn.ConnectionString = cnStr;
    cn.Open();

    // Make command object.
    DbCommand cmd = df.CreateCommand();
    Console.WriteLine("Your command object is a: {0}", cmd.GetType().Name);
    cmd.Connection = cn;
    cmd.CommandText = "Select * From Inventory";

    // Print out data with data reader.
    using (DbDataReader dr = cmd.ExecuteReader())
    {
        Console.WriteLine("Your data reader object is a: {0}", dr.GetType().Name);

        Console.WriteLine("\n***** Current Inventory *****");
        while (dr.Read())
            Console.WriteLine("-> Car #{0} is a {1}.",
                dr["CarID"], dr["Make"].ToString());
    }
    Console.ReadLine();
}

```

Notice that, for diagnostic purposes, you use reflection services to print the name of the underlying connection, command, and data reader. If you run this application, you will find the current data in the Inventory table of the AutoLot database printed to the console:

***** Fun with Data Provider Factories *****

Your connection object is a: SqlConnection
 Your command object is a: SqlCommand
 Your data reader object is a: SqlDataReader

***** Current Inventory *****
 -> Car #83 is a Ford.
 -> Car #107 is a Ford.
 -> Car #678 is a Yugo.
 -> Car #904 is a VW.
 -> Car #1000 is a BMW.
 -> Car #1001 is a BMW.
 -> Car #1992 is a Saab.

Now change the *.config file to specify System.Data.OleDb as the data provider (and update your connection string with a Provider segment):

```
<configuration>
  <appSettings>
    <!-- Which provider? -->
    <add key="provider" value="System.Data.OleDb" />

    <!-- Which connection string? -->
    <add key="cnStr" value=
      "Provider=SQLOLEDB;Data Source=(local)\SQLEXPRESS;
       Integrated Security=SSPI;Initial Catalog=AutoLot"/>
  </appSettings>
</configuration>
```

Doing this indicates that the `System.Data.OleDb` types are used behind the scenes:

***** Fun with Data Provider Factories *****

Your connection object is a: `OleDbConnection`
 Your command object is a: `OleDbCommand`
 Your data reader object is a: `OleDbDataReader`

***** Current Inventory *****

- > Car #83 is a Ford.
- > Car #107 is a Ford.
- > Car #678 is a Yugo.
- > Car #904 is a VW.
- > Car #1000 is a BMW.
- > Car #1001 is a BMW.
- > Car #1992 is a Saab.

Of course, based on your experience with ADO.NET, you might be a bit unsure exactly what the connection, command, and data reader objects actually *do*. Don't sweat the details for the time being (quite a few pages remain in this chapter, after all!). At this point, it's enough to know that you can use the ADO.NET data provider factory model to build a single code base that can consume various data providers in a declarative manner.

A Potential Drawback with the Provide Factory Model

Although this is a powerful model, you must make sure that the code base uses only types and methods common to all providers through the members of the abstract base classes. Therefore, when authoring your code base, you are limited to the members exposed by `DbConnection`, `DbCommand`, and the other types of the `System.Data.Common` namespace.

Given this, you might find that this generalized approach prevents you from directly accessing some of the bells and whistles of a particular DBMS. If you must be able to invoke specific members of the underlying provider (e.g., `SqlConnection`), you can do so using an explicit cast, as in this example:

```
using (DbConnection cn = df.CreateConnection())
{
  Console.WriteLine("Your connection object is a: {0}", cn.GetType().Name);
```

```

cn.ConnectionString = cnStr;
cn.Open();
if (cn is SqlConnection)
{
    // Print out which version of SQL Server is used.
    Console.WriteLine(((SqlConnection)cn).ServerVersion);
}
...
}

```

When doing this, however, your code base becomes a bit harder to maintain (and less flexible) because you must add a number of runtime checks. Nevertheless, if you need to build data access libraries in the most flexible way possible, the data provider factory model provides a great mechanism for doing so.

The <connectionStrings> Element

Currently your connection string data is in the <appSettings> element of your *.config file. Application configuration files might define an element named <connectionStrings>. Within this element, you can define any number of name/value pairs that can be programmatically read into memory using the ConfigurationManager.ConnectionStrings indexer. One advantage of this approach (as opposed to using the <appSettings> element and the ConfigurationManager.AppSettings indexer) is that you can define multiple connection strings for a single application in a consistent manner.

To see this in action, update your current App.config file as follows (note that each connection string is documented using the name and connectionString attributes rather than the key and value attributes you find in <appSettings>):

```

<configuration>
  <appSettings>
    <!-- Which provider? -->
    <add key="provider" value="System.Data.SqlClient" />
  </appSettings>

  <!-- Here are the connection strings -->
  <connectionStrings>
    <add name ="AutoLotSqlProvider" connectionString =
      "Data Source=(local)\SQLEXPRESS;
       Integrated Security=SSPI;Initial Catalog=AutoLot"/>

    <add name ="AutoLotOleDbProvider" connectionString =
      "Provider=SQLOLEDB;Data Source=(local)\SQLEXPRESS;
       Integrated Security=SSPI;Initial Catalog=AutoLot"/>
  </connectionStrings>
</configuration>

```

You can now update your Main() method as follows:

```

static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Data Provider Factories *****\n");
    string dp =

```

```

    ConfigurationManager.AppSettings["provider"];
    string cnStr =
        ConfigurationManager.ConnectionStrings["AutoLotSqlProvider"].ConnectionString;
...
}

```

At this point, you have an application that can display the results of the *Inventory* table of the *AutoLot* database using a neutral code base. Offloading the provider name and connection string to an external *.config file, means that the data provider factory model can dynamically load the correct provider in the background. With this first example behind you, you can now dive into the details of working with the connected layer of ADO.NET.

Note Now that you understand the role of ADO.NET data provider factories, the remaining examples in this book will focus on the task at hand by explicitly using the types within the `System.Data.SqlClient` namespace. If you use a different database management system (such as Oracle), you need to update your code base accordingly.

Source Code You can find the `DataProviderFactory` project under the Chapter 21 subdirectory.

Understanding the Connected Layer of ADO.NET

Recall that the *connected layer* of ADO.NET allows you to interact with a database using the connection, command, and data reader objects of your data provider. You have already used these objects in the previous `DataProviderFactory` application, now you'll walk through the process again, this time using an expanded example. You need to perform the following steps when you wish to connect to a database and read the records using a data reader object:

1. Allocate, configure, and open your connection object.
2. Allocate and configure a command object, specifying the connection object as a constructor argument or with the `Connection` property.
3. Call `ExecuteReader()` on the configured command class.
4. Process each record using the `Read()` method of the data reader.

To get the ball rolling, create a new Console Application named `AutoLotDataReader` and import the `System.Data` and `System.Data.SqlClient` namespaces. Here is the complete code within `Main()`; an analysis will follow:

```

class Program
{
    static void Main(string[] args)
    {
        Console.WriteLine("***** Fun with Data Readers *****\n");

        // Create an open a connection.
        using(SqlConnection cn = new SqlConnection())
        {
            cn.ConnectionString =
                @"Data Source=(local)\SQLEXPRESS;Integrated Security=SSPI;" +
                "Initial Catalog=AutoLot";
            cn.Open();

            // Create a SQL command object.
            string strSQL = "Select * From Inventory";
            SqlCommand myCommand = new SqlCommand(strSQL, cn);

            // Obtain a data reader a la ExecuteReader().
            using(SqlDataReader myDataReader = myCommand.ExecuteReader())
            {
                // Loop over the results.
                while (myDataReader.Read())
                {
                    Console.WriteLine("-> Make: {0}, PetName: {1}, Color: {2}.",
                        myDataReader["Make"].ToString(),
                        myDataReader["PetName"].ToString(),
                        myDataReader["Color"].ToString());
                }
            }
            Console.ReadLine();
        }
    }
}

```

Working with Connection Objects

The first step to take when working with a data provider is to establish a session with the data source using the connection object (which, as you recall, derives from `DbConnection`). .NET connection objects are provided with a formatted *connection string*; this string contains a number of name/value pairs, separated by semicolons. You use this information to identify the name of the machine you wish to connect to, required security settings, the name of the database on that machine, and other data provider-specific information.

As you can infer from the preceding code, the `Initial Catalog` name refers to the database you want to establish a session with. The `Data Source` name identifies the name of the machine that maintains the database. Here, `(local)` allows you to define a single token to specify the current local machine (regardless of the literal name of said machine), while the `\SQLEXPRESS` token informs the SQL server provider that you are connecting to the default SQL Server Express edition installation (if you created `AutoLot` on a full version of Microsoft SQL Server on your local computer, specify `Data Source=(local)`).

Beyond this, you can supply any number of tokens that represent security credentials. Here, you set the `Integrated Security` to `SSPI` (equivalent to `true`), which uses the current Windows account credentials for user authentication.

Note Look up the `ConnectionString` property of your data provider's connection object in the .NET Framework 4.0 SDK documentation to learn more about each name/value pair for your specific DBMS.

Once you establish your construction string, you can use a call to `Open()` to establish a connection with the DBMS. In addition to the `ConnectionString`, `Open()`, and `Close()` members, a connection object provides a number of members that let you configure additional settings regarding your connection, such as timeout settings and transactional information. Table 21-5 lists some (but not all) members of the `DbConnection` base class.

Table 21-5. Members of the `DbConnection` Type

Member	Meaning in Life
<code>BeginTransaction()</code>	You use this method to begin a database transaction.
<code>ChangeDatabase()</code>	You use this method to change the database on an open connection.
<code>ConnectionTimeout</code>	This read-only property returns the amount of time to wait while establishing a connection before terminating and generating an error (the default value is 15 seconds). If you wish to change the default, specify a <code>Connect Timeout</code> segment in the connection string (e.g., <code>Connect Timeout=30</code>).
<code>Database</code>	This read-only property gets the name of the database maintained by the connection object.
<code>DataSource</code>	This read-only property gets the location of the database maintained by the connection object.
<code>GetSchema()</code>	This method returns a <code>DataTable</code> object that contains schema information from the data source.
<code>State</code>	This read-only property gets the current state of the connection, which is represented by the <code>ConnectionState</code> enumeration.

The properties of the `DbConnection` type are typically read-only in nature and are only useful when you wish to obtain the characteristics of a connection at runtime. When you wish to override default settings, you must alter the construction string itself. For example, the connection string sets the `connection timeout` setting from 15 seconds to 30 seconds:

```

static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Data Readers *****\n");

    using(SqlConnection cn = new SqlConnection())
    {
        cn.ConnectionString =
            @"Data Source=(local)\SQLEXPRESS;" +
            "Integrated Security=SSPI;Initial Catalog=AutoLot;Connect Timeout=30";
        cn.Open();

        // New helper function (see below).
        ShowConnectionStatus(cn);
    }
}

```

In the preceding code, you pass your connection object as a parameter to a new static helper method in the `Program` class named `ShowConnectionStatus()`, which you implement as follows:

```

static void ShowConnectionStatus(SqlConnection cn)
{
    // Show various stats about current connection object.
    Console.WriteLine("***** Info about your connection *****");
    Console.WriteLine("Database location: {0}", cn.DataSource);
    Console.WriteLine("Database name: {0}", cn.Database);
    Console.WriteLine("Timeout: {0}", cn.ConnectionTimeout);
    Console.WriteLine("Connection state: {0}\n", cn.State.ToString());
}

```

While most of these properties are self-explanatory, the `State` property is worth special mention. You can assign this property any value of the `ConnectionState` enumeration:

```

public enum ConnectionState
{
    Broken, Closed,
    Connecting, Executing,
    Fetching, Open
}

```

However, the only valid `ConnectionState` values are `ConnectionState.Open` and `ConnectionState.Closed` (the remaining members of this enum are reserved for future use). Also, it is always safe to close a connection where connection state is currently `ConnectionState.Closed`.

Working with ConnectionStringBuilder Objects

Working with connection strings programmatically can be cumbersome because they are often represented as string literals, which are difficult to maintain and error-prone at best. The Microsoft-supplied ADO.NET data providers support *connection string builder objects*, which allow you to establish the name/value pairs using strongly typed properties. Consider the following update to the current `Main()` method:

```

static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Data Readers *****\n");

    // Create a connection string via the builder object.
    SqlConnectionStringBuilder cnStrBuilder =
        new SqlConnectionStringBuilder();
    cnStrBuilder.InitialCatalog = "AutoLot";
    cnStrBuilder.DataSource = @"(local)\SQLEXPRESS";
    cnStrBuilder.ConnectTimeout = 30;
    cnStrBuilder.IntegratedSecurity = true;

    using(SqlConnection cn = new SqlConnection())
    {
        cn.ConnectionString = cnStrBuilder.ConnectionString;
        cn.Open();

        ShowConnectionStatus(cn);
    ...
    }
    Console.ReadLine();
}

```

In this iteration, you create an instance of `SqlConnectionStringBuilder`, set the properties accordingly, and obtain the internal string using the `ConnectionString` property. Also note that you use the default constructor of the type. If you so choose, you can also create an instance of your data provider's connection string builder object by passing in an existing connection string as a starting point (this can be helpful when you read these values dynamically from an `App.config` file). Once you have hydrated the object with the initial string data, you can change specific name/value pairs using the related properties, as in this example:

```

static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Data Readers *****\n");

    // Assume you really obtained the cnStr value from a *.config file.
    string cnStr = @"Data Source=(local)\SQLEXPRESS;" +
                  "Integrated Security=SSPI;Initial Catalog=AutoLot";

    SqlConnectionStringBuilder cnStrBuilder =
        new SqlConnectionStringBuilder(cnStr);

    // Change timeout value.
    cnStrBuilder.ConnectTimeout = 5;
...
}

```

Working with Command Objects

Now that you understand better the role of the connection object, the next order of business is to check out how to submit SQL queries to the database in question. The `SqlCommand` type (which derives from `DbCommand`) is an OO representation of a SQL query, table name, or stored procedure. You specify the type of command using the `CommandType` property, which can take any value from the `CommandType` enum:

```
public enum CommandType
{
    StoredProcedure,
    TableDirect,
    Text // Default value.
}
```

When you create a command object, you can establish the SQL query as a constructor parameter or directly by using the `CommandText` property. Also when you create a command object, you need to specify the connection you want to use. Again, you can do so as a constructor parameter or by using the `Connection` property. Consider this code snippet:

```
// Create command object via ctor args.
string strSQL = "Select * From Inventory";
SqlCommand myCommand = new SqlCommand(strSQL, cn);

// Create another command object via properties.
SqlCommand testCommand = new SqlCommand();
testCommand.Connection = cn;
testCommand.CommandText = strSQL;
```

Realize that at this point that you have not literally submitted the SQL query to the `AutoLot` database, but instead prepared the state of the command object for future use. Table 21-6 highlights some additional members of the `DbCommand` type.

Table 21-6. Members of the `DbCommand` Type

Member	Meaning in Life
<code>CommandTimeout</code>	Gets or sets the time to wait while executing the command before terminating the attempt and generating an error. The default is 30 seconds.
<code>Connection</code>	Gets or sets the <code>DbConnection</code> used by this instance of the <code>DbCommand</code> .
<code>Parameters</code>	Gets the collection of <code>DbParameter</code> objects used for a parameterized query.
<code>Cancel()</code>	Cancels the execution of a command.
<code>ExecuteReader()</code>	Executes a SQL query and returns the data provider's <code>DbDataReader</code> object, which provides forward-only, read-only access for the result of the query.

Table 21-6. Members of the *DbCommand* Type (continued)

Member	Meaning in Life
ExecuteNonQuery()	Executes a SQL non-query (e.g., an insert, update, delete, or create table).
ExecuteScalar()	A lightweight version of the ExecuteReader() method that was designed specifically for singleton queries (e.g., obtaining a record count).
Prepare()	Creates a prepared (or compiled) version of the command on the data source. As you might know, a <i>prepared query</i> executes slightly faster and is useful when you wish to execute the same query multiple times (typically with different parameters each time).

Working with Data Readers

Once you establish the active connection and SQL command, the next step is to submit the query to the data source. As you might guess, you have a number of ways to do this. The *DbDataReader* type (which implements *IDataReader*) is the simplest and fastest way to obtain information from a data store. Recall that data readers represent a read-only, forward-only stream of data returned one record at a time. Given this, data readers are useful only when submitting SQL selection statements to the underlying data store.

Data readers are useful when you need to iterate over large amounts of data quickly and you do not need to maintain an in-memory representation. For example, if you request 20,000 records from a table to store in a text file, it would be rather memory-intensive to hold this information in a *DataSet* (because a *DataSet* holds the entire result of the query in memory at the same time).

A better approach is to create a data reader that spins over each record as rapidly as possible. Be aware, however, that data reader objects (unlike data adapter objects, which you'll examine later) maintain an open connection to their data source until you explicitly close the connection.

You obtain data reader objects from the command object using a call to *ExecuteReader()*. The data reader represents the current record it has read from the database. The data reader has an indexer method (e.g., `[]` syntax in C#) that allows you to access a column in the current record. You can access the column either by name or by zero-based integer.

The following use of the data reader leverages the *Read()* method to determine when you have reached the end of your records (using a `false` return value). For each incoming record that you read from the database, you use the type indexer to print out the make, pet name, and color of each automobile. Also note that you call *Close()* as soon as you finish processing the records; this frees up the connection object:

```
static void Main(string[] args)
{
...
// Obtain a data reader via ExecuteReader().
using(SqlDataReader myDataReader = myCommand.ExecuteReader())
{
    // Loop over the results.
    while (myDataReader.Read())
```

```

{
    Console.WriteLine("-> Make: {0}, PetName: {1}, Color: {2}.",
        myDataReader["Make"].ToString(),
        myDataReader["PetName"].ToString(),
        myDataReader["Color"].ToString());
}
}
Console.ReadLine();
}

```

In the preceding snippet, you overload the indexer of a data reader object to take either a `string` (representing the name of the column) or an `int` (representing the column's ordinal position). Thus, you can clean up the current reader logic (and avoid hard-coded string names) with the following update (note the use of the `FieldCount` property):

```

while (myDataReader.Read())
{
    Console.WriteLine("***** Record *****");
    for (int i = 0; i < myDataReader.FieldCount; i++)
    {
        Console.WriteLine("{0} = {1} ",
            myDataReader.GetName(i),
            myDataReader.GetValue(i).ToString());
    }
    Console.WriteLine();
}

```

If you compile and run your project at this point, you should see a list of all automobiles in the `Inventory` table of the `AutoLot` database. The following output shows the initial few records from my own version of `AutoLot`:

```

***** Fun with Data Readers *****

***** Info about your connection *****
Database location: (local)\SQLEXPRESS
Database name: AutoLot
Timeout: 30
Connection state: Open

***** Record *****
CarID = 83
Make = Ford
Color = Rust
PetName = Rusty

***** Record *****
CarID = 107
Make = Ford
Color = Red
PetName = Snake

```

Obtaining Multiple Result Sets Using a Data Reader

Data reader objects can obtain multiple result sets using a single command object. For example, if you want to obtain all rows from the *Inventory* table, as well as all rows from the *Customers* table, you can specify both SQL select statements using a semicolon delimiter:

```
string strSQL = "Select * From Inventory;Select * from Customers";
```

Once you obtain the data reader, you can iterate over each result set using the *NextResult()* method. Note that you are always returned the first result set automatically. Thus, if you wish to read over the rows of each table, you can build the following iteration construct:

```
do
{
    while (myDataReader.Read())
    {
        Console.WriteLine("***** Record *****");
        for (int i = 0; i < myDataReader.FieldCount; i++)
        {
            Console.WriteLine("{0} = {1}",
                myDataReader.GetName(i),
                myDataReader.GetValue(i).ToString());
        }
        Console.WriteLine();
    }
} while (myDataReader.NextResult());
```

At this point, you should be more aware of the functionality data reader objects bring to the table. Always remember that a data reader can only process SQL Select statements; you cannot use them to modify an existing database table using Insert, Update, or Delete requests. Modifying an existing database requires additional investigation of command objects.

Source Code You can find the *AutoLotDataReader* project under the Chapter 21 subdirectory.

Building a Reusable Data Access Library

The *ExecuteReader()* method extracts a data reader object that allows you to examine the results of a SQL Select statement using a forward-only, read-only flow of information. However, when you wish to submit SQL statements that result in the modification of a given table (or any other non-query SQL statement, such as creating tables or granting permissions), you call the *ExecuteNonQuery()* method of your command object. This single method performs inserts, updates, and deletes based on the format of your command text.

■ **Note** Technically speaking, a *nonquery* is a SQL statement that does not return a result set. Thus, Select statements are queries, while Insert, Update, and Delete statements are not. Given this, ExecuteNonQuery() returns an int that represents the number of rows affected, not a new set of records.

Next, you will learn how to modify an existing database using nothing more than a call to ExecuteNonQuery(); your next goal is to build a custom data access library that can encapsulate the process of operating upon the AutoLot database. In a production-level environment, your ADO.NET logic will almost always be isolated to a .NET *.dll assembly for one simple reason: code reuse! The first examples of this chapter have not done, simply so you can keep focused on the task at hand; however, it would be a waste of time to author the *same* connection logic, the *same* data reading logic, and the *same* command logic for every application that needs to interact with the AutoLot database.

Isolating data access logic to a .NET code library means that multiple applications using any sort of front end (e.g., console-based, desktop-based, and web based) can reference the library at hand in a language-independent manner. Thus, if you author your data library using C#, other .NET programmers can build a UI in the language of their choice (e.g., VB or C++/CLI).

In this chapter, your data library (AutoLotDAL.dll) will contain a single namespace (AutoLotConnectedLayer) that interacts with AutoLot using the connected types of ADO.NET. In the next chapter, you will add a new namespace (AutoLotDisconnectionLayer) to this same *.dll that contains types to communicate with AutoLot using the disconnected layer. Multiple applications will take advantage of this library throughout the remainder of this book.

Begin by creating a new C# Class Library project named AutoLotDAL (short for *AutoLot Data Access Layer*) and renaming your initial C# code file to AutoLotConnDAL.cs. Next, rename your namespace scope to AutoLotConnectedLayer and change the name of your initial class to InventoryDAL; this class will define various members to interact with the Inventory table of the AutoLot database. Finally, import the following .NET namespaces:

```
using System;
using System.Collections.Generic;
using System.Text;

// You will use the SQL server
// provider; however, it would also be
// permissible to use the ADO.NET
// factory pattern for greater flexibility.
using System.Data;
using System.Data.SqlClient;

namespace AutoLotConnectedLayer
{
    public class InventoryDAL
    {
    }
}
```

■ **Note** You might recall from Chapter 8 that when objects use types that manage raw resources (e.g., a database connection), it is a good practice to implement `IDisposable` and author a proper finalizer. In a production environment, classes such as `InventoryDAL` would do the same; however, you won't do that here, so you can stay focused on the particulars of ADO.NET.

Adding the Connection Logic

The first task you must attend to is to define some methods that allow the caller to connect to and disconnect from the data source using a valid connection string. You will hard-code your `AutoLotDAL.dll` assembly to use of the types of `System.Data.SqlClient`, so you need to define a private member variable of `SqlConnection` that is allocated at the time the `InventoryDAL` object is created. Also, define a method named `OpenConnection()` and another named `CloseConnection()` to interact with this member variable:

```
public class InventoryDAL
{
    // This member will be used by all methods.
    private SqlConnection = null;

    public void OpenConnection(string connectionString)
    {
        sqlCn = new SqlConnection();
        sqlCn.ConnectionString = connectionString;
        sqlCn.Open();
    }

    public void CloseConnection()
    {
        sqlCn.Close();
    }
}
```

For the sake of brevity, your `InventoryDAL` type will not test for possible exceptions, nor will it throw custom exceptions under various circumstances (e.g., a malformed connection string). If you were to build an industrial-strength data access library, you would absolutely want to use structured exception handling techniques to account for any runtime anomalies.

Adding the Insertion Logic

Inserting a new record into the `Inventory` table is as simple as formatting the SQL `Insert` statement (based on user input) and calling the `ExecuteNonQuery()` using your command object. You can see this in action by adding a public method to your `InventoryDAL` type named `InsertAuto()` that takes four parameters that map to the four columns of the `Inventory` table (`CarID`, `Color`, `Make`, and `PetName`). You use these arguments to format a string type to insert the new record. Finally, use your `SqlConnection` object to execute the SQL statement:

```

public void InsertAuto(int id, string color, string make, string petName)
{
    // Format and execute SQL statement.
    string sql = string.Format("Insert Into Inventory" +
        "(CarID, Make, Color, PetName) Values" +
        "('{0}', '{1}', '{2}', '{3}')", id, make, color, petName);

    // Execute using our connection.
    using(SqlCommand cmd = new SqlCommand(sql, this.sqlCn))
    {
        cmd.ExecuteNonQuery();
    }
}

```

This method is syntactically fine, but you could supply an overloaded version that allows the caller to pass in a strongly typed class that represents the data for the new row. Define a new `NewCar` class, which represents a new row in the `Inventory` table:

```

public class NewCar
{
    public int CarID { get; set; }
    public string Color { get; set; }
    public string Make { get; set; }
    public string PetName { get; set; }
}

```

Now add the following version of `InsertAuto()` to your `InventoryDAL` class:

```

public void InsertAuto(NewCar car)
{
    // Format and execute SQL statement.
    string sql = string.Format("Insert Into Inventory" +
        "(CarID, Make, Color, PetName) Values" +
        "('{0}', '{1}', '{2}', '{3}')", car.CarID, car.Make, car.Color, car.PetName);

    // Execute using our connection.
    using (SqlCommand cmd = new SqlCommand(sql, this.sqlCn))
    {
        cmd.ExecuteNonQuery();
    }
}

```

Defining classes that represent records in a relational database is a common way to build a data access library. In fact, as you will see in Chapter 23, the ADO.NET Entity Framework automatically generates strongly typed classes that allow you to interact with database data. On a related note, the *disconnected layer* of ADO.NET (see Chapter 22) generates strongly typed `DataSet` objects to represent data from a given table in a relational database.

Note As you might know, building a SQL statement using string concatenation can be risky from a security point of view (think: SQL injection attacks). The preferred way to build command text is to use a parameterized query, which you will learn about shortly.

Adding the Deletion Logic

Deleting an existing record is as simple as inserting a new record. Unlike when you created the code listing for `InsertAuto()`, this time you will learn about an important `try/catch` scope that handles the possibility of attempting to delete a car that is currently on order for an individual in the `Customers` table. Add the following method to the `InventoryDAL` class type:

```
public void DeleteCar(int id)
{
    // Get ID of car to delete, then do so.
    string sql = string.Format("Delete from Inventory where CarID = '{0}'",
        id);
    using(SqlCommand cmd = new SqlCommand(sql, this.sqlCn))
    {
        try
        {
            cmd.ExecuteNonQuery();
        }
        catch(SqlException ex)
        {
            Exception error = new Exception("Sorry! That car is on order!", ex);
            throw error;
        }
    }
}
```

Adding the Update Logic

When it comes to the act of updating an existing record in the `Inventory` table, the first thing you must decide is what you want to allow the caller to change, whether it's the car's color, the pet name, the make, or all of the above. One way to give the caller complete flexibility is to define a method that takes a `string` type to represent any sort of SQL statement, but that is risky at best.

Ideally, you want to have a set of methods that allow the caller to update a record in a variety of ways. However, for this simple data access library, you will define a single method that allows the caller to update the pet name of a given automobile:

```
public void UpdateCarPetName(int id, string newPetName)
{
    // Get ID of car to modify and new pet name.
    string sql = string.Format("Update Inventory Set PetName = '{0}' Where CarID = '{1}'",
        newPetName, id);
```

```

using(SqlCommand cmd = new SqlCommand(sql, this.sqlCn))
{
    cmd.ExecuteNonQuery();
}
}

```

Adding the Selection Logic

Next, you need to add a selection method. As you saw earlier in this chapter, a data provider's data reader object allows for a selection of records using a read-only, forward-only server-side cursor. As you call the `Read()` method, you can process each record in a fitting manner. While this is all well and good, you need to contend with the issue of how to return these records to the calling tier of your application.

One approach would be to populate and return a multidimensional array (or other such return value, such as a generic `List<NewCar>` object) with the data obtained by the `Read()` method. Here is a second way to obtain data from the `Inventory` table that uses the latter approach:

```

public List<NewCar> GetAllInventoryAsList()
{
    // This will hold the records.
    List<NewCar> inv = new List<NewCar>();

    // Prep command object.
    string sql = "Select * From Inventory";
    using (SqlCommand cmd = new SqlCommand(sql, this.sqlCn))
    {
        SqlDataReader dr = cmd.ExecuteReader();
        while (dr.Read())
        {
            inv.Add(new NewCar
            {
                CarID = (int)dr["CarID"],
                Color = (string)dr["Color"],
                Make = (string)dr["Make"],
                PetName = (string)dr["PetName"]
            });
        }
        dr.Close();
    }
    return inv;
}

```

Still another approach is to return a `System.Data.DataTable` object, which is actually part of the disconnected layer of ADO.NET. You will find complete coverage of the disconnected layer in the next chapter; however, for the time being, you should understand that a `DataTable` is a class type that represents a tabular block of data (e.g., a grid on a spreadsheet).

Internally, the `DataTable` class represents data as a collection of rows and columns. While you can fill these collections programmatically, the `DataTable` type provides a method named `Load()` that automatically populates these collections using a data reader object! Consider the following methods, which return data from `Inventory` as a `DataTable`:

```

public DataTable GetAllInventoryAsDataTable()
{
    // This will hold the records.
    DataTable inv = new DataTable();

    // Prep command object.
    string sql = "Select * From Inventory";
    using(SqlCommand cmd = new SqlCommand(sql, this.sqlCn))
    {
        SqlDataReader dr = cmd.ExecuteReader();
        // Fill the DataTable with data from the reader and clean up.
        inv.Load(dr);
        dr.Close();
    }
    return inv;
}

```

Working with Parameterized Command Objects

Currently, the insert, update, and delete logic for the `InventoryDAL` type uses hard-coded string-literals for each SQL query. As you might know, you can use a *parameterized query* to treat SQL parameters as objects, rather than as a simple blob of text. Treating SQL queries in a more object-oriented manner helps reduce the number of typos (given strongly typed properties); plus, parameterized queries typically execute much faster than a literal SQL string because they are parsed exactly once (rather than each time the SQL string is assigned to the `CommandText` property). Parameterized queries also help protect against SQL injection attacks (a well-known data access security issue).

To support parameterized queries, ADO.NET command objects maintain a collection of individual parameter objects. By default, this collection is empty, but you can insert any number of parameter objects that map to a *placeholder parameter* in the SQL query. When you wish to associate a parameter within a SQL query to a member in the command object's `parameters` collection, you can prefix the SQL text parameter with the @ symbol (at least when using Microsoft SQL Server; not all DBMSs support this notation).

Specifying Parameters Using the `DbParameter` Type

Before you build a parameterized query, you need to familiarize yourself with the `DbParameter` type (which is the base class to a provider's specific parameter object). This class maintains a number of properties that allow you to configure the name, size, and data type of the parameter, as well as other characteristics, including the parameter's direction of travel. Table 21-7 describes some key properties of the `DbParameter` type.

Table 21-7. Key Members of the DbParameter Type

Property	Meaning in Life
DbType	Gets or sets the native data type of the parameter, represented as a CLR data type.
Direction	Gets or sets whether the parameter is input-only, output-only, bidirectional, or a return value parameter.
IsNullable	Gets or sets whether the parameter accepts null values.
ParameterName	Gets or sets the name of the DbParameter.
Size	Gets or sets the maximum parameter size of the data in bytes; this is only useful for textual data.
Value	Gets or sets the value of the parameter.

Now let's look at how to populate a command object's collection of DBParameter-compatible objects by reworking the following version of the `InsertAuto()` method to leverage parameter objects (you could perform a similar reworking for your remaining methods; however, that's not necessary for this example):

```
public void InsertAuto(int id, string color, string make, string petName)
{
    // Note the "placeholders" in the SQL query.
    string sql = string.Format("Insert Into Inventory" +
        "(CarID, Make, Color, PetName) Values" +
        "(@CarID, @Make, @Color, @PetName)");

    // This command will have internal parameters.
    using(SqlCommand cmd = new SqlCommand(sql, this.sqlCn))
    {
        // Fill params collection.
        SqlParameter param = new SqlParameter();
        param.ParameterName = "@CarID";
        param.Value = id;
        param.SqlDbType = SqlDbType.Int;
        cmd.Parameters.Add(param);

        param = new SqlParameter();
        param.ParameterName = "@Make";
        param.Value = make;
        param.SqlDbType = SqlDbType.Char;
        param.Size = 10;
        cmd.Parameters.Add(param);

        param = new SqlParameter();
        param.ParameterName = "@Color";
    }
}
```

```

param.Value = color;
param.SqlDbType = SqlDbType.Char;
param.Size = 10;
cmd.Parameters.Add(param);

param = new SqlParameter();
param.ParameterName = "@PetName";
param.Value = petName;
param.SqlDbType = SqlDbType.Char;
param.Size = 10;
cmd.Parameters.Add(param);

cmd.ExecuteNonQuery();
}
}

```

Again, notice that your SQL query consists of four embedded placeholder symbols, each of which is prefixed with the @ token. You can use the SqlParameter type to map each placeholder using the ParameterName property and specify various details (e.g., its value, data type, and size) in a strongly typed manner. Once each parameter object is hydrated, it is added to the command object's collection through a call to Add().

Note This example uses various properties to establish a parameter object. Note, however, that parameter objects support a number of overloaded constructors that allow you to set the values of various properties (which will result in a more compact code base). Also be aware that Visual Studio 2010 provides many graphical designers that will generate a good deal of this grungy parameter-centric code on your behalf (see Chapters 22 and 23).

While building a parameterized query often requires more code, the end result is a more convenient way to tweak SQL statements programmatically, as well as to achieve better overall performance. While you are free to use this technique whenever a SQL query is involved, parameterized queries prove most helpful when you wish to trigger a stored procedure.

Executing a Stored Procedure

Recall that a *stored procedure* is a named block of SQL code stored in the database. You can construct stored procedures so they return a set of rows or scalar data types or do anything else that makes sense (e.g., insert, update, or delete); you can also have them take any number of optional parameters. The end result is a unit of work that behaves like a typical function, except that it is located on a data store rather than a binary business object. Currently, your AutoLot database defines a single stored procedure named GetPetName, which you formatted as follows:

```

GetPetName
@carID int,
@petName char(10) output

```

AS

```
SELECT @petName = PetName from Inventory where CarID = @carID
```

Now consider the following final method of the `InventoryDAL` type, which invokes your stored procedure:

```
public string LookUpPetName(int carID)
{
    string carPetName = string.Empty;

    // Establish name of stored proc.
    using (SqlCommand cmd = new SqlCommand("GetPetName", this.sqlCn))
    {
        cmd.CommandType = CommandType.StoredProcedure;

        // Input param.
        SqlParameter param = new SqlParameter();
        param.ParameterName = "@carID";
        param.SqlDbType = SqlDbType.Int;
        param.Value = carID;

        // The default direction is in fact Input, but to be clear:
        param.Direction = ParameterDirection.Input;
        cmd.Parameters.Add(param);

        // Output param.
        param = new SqlParameter();
        param.ParameterName = "@petName";
        param.SqlDbType = SqlDbType.Char;
        param.Size = 10;
        param.Direction = ParameterDirection.Output;
        cmd.Parameters.Add(param);

        // Execute the stored proc.
        cmd.ExecuteNonQuery();

        // Return output param.
        carPetName = (string)cmd.Parameters["@petName"].Value;
    }
    return carPetName;
}
```

One important aspect of invoking a stored procedure is to keep in mind that a command object can represent a SQL statement (the default) or the name of a stored procedure. When you wish to inform a command object that it will be invoking a stored procedure, you pass in the name of the procedure (as a constructor argument or by using the `CommandText` property) and must set the `CommandType` property to the value `CommandType.StoredProcedure` (if you fail to do this, you will receive a runtime exception because the command object is expecting a SQL statement by default):

```
SqlCommand cmd = new SqlCommand("GetPetName", this.sqlCn);
cmd.CommandType = CommandType.StoredProcedure;
```

Next, notice that the `Direction` property of a parameter object allows you to specify the direction of travel for each parameter passed to the stored procedure (e.g., input parameter, output parameter, in/out parameter, or return value). As before, you add each parameter object to the command object's `parameters` collection:

```
// Input param.
SqlParameter param = new SqlParameter();
param.ParameterName = "@carID";
param.SqlDbType = SqlDbType.Int;
param.Value = carID;
param.Direction = ParameterDirection.Input;
cmd.Parameters.Add(param);
```

After the stored procedure completes with a call to `ExecuteNonQuery()`, you can obtain the value of the output parameter by investigating the command object's `parameter` collection and casting accordingly:

```
// Return output param.
carPetName = (string)cmd.Parameters["@petName"].Value;
```

At this point, your initial iteration of the `AutoLotDAL.dll` data access library is complete! You can use this assembly to build any sort of front end to display and edit your data you want (e.g., console based, Windows Forms based, Windows Presentation Foundation based, or an HTML-based web application). You have not yet examined how to build graphical user interfaces, so next you will test your data library from a new console application.

■ Source Code You can find the `AutoLotDAL` project under the Chapter 21 subdirectory.

Creating a Console UI-Based Front End

Create a new Console Application named `AutoLotCUIClient`. After you create your new project, be sure to add a reference to your `AutoLotDAL.dll` assembly, as well as `System.Configuration.dll`. Next, add the following `using` statements to your C# code file:

```
using AutoLotConnectedLayer;
using System.Configuration;
using System.Data;
```

Now insert a new `App.config` file into your project that contains a `<connectionStrings>` element, which you will use to connect to your instance of the `AutoLot` database, as in this example:

```
<configuration>
  <connectionStrings>
    <add name ="AutoLotSqlProvider" connectionString =
      "Data Source=(local)\SQLEXPRESS;
      Integrated Security=SSPI;Initial Catalog=AutoLot"/>
```

```
</connectionStrings>
</configuration>
```

Implementing the Main() Method

The `Main()` method is responsible for prompting the user for a specific course of action and executing that request using a `switch` statement. This program allows the user to enter the following commands:

- `I`: Inserts a new record into the `Inventory` table.
- `U`: Updates an existing record in the `Inventory` table.
- `D`: Deletes an existing record from the `Inventory` table.
- `L`: Displays the current inventory using a data reader.
- `S`: Shows these options to the user.
- `P`: Looks up pet name from *car* ID.
- `Q`: Quits the program.

Each possible option is handled by a unique static method within the `Program` class. The next snippet shows the complete implementation of `Main()`. Notice that each method invoked from the `do/while` loop (with the exception of the `ShowInstructions()` method) takes an `InventoryDAL` object as its sole parameter:

```
static void Main(string[] args)
{
    Console.WriteLine("***** The AutoLot Console UI *****\n");

    // Get connection string from App.config.
    string cnStr =
        ConfigurationManager.ConnectionStrings["AutoLotSqlProvider"].ConnectionString;
    bool userDone = false;
    string userCommand = "";

    // Create our InventoryDAL object.
    InventoryDAL invDAL = new InventoryDAL();
    invDAL.OpenConnection(cnStr);

    // Keep asking for input until user presses the Q key.
    try
    {
        ShowInstructions();
        do
        {
            Console.Write("\nPlease enter your command: ");
            userCommand = Console.ReadLine();
            Console.WriteLine();
            switch (userCommand.ToUpper())
            {
```

```

        case "I":
            InsertNewCar(invDAL);
            break;
        case "U":
            UpdateCarPetName(invDAL);
            break;
        case "D":
            DeleteCar(invDAL);
            break;
        case "L":
            ListInventory(invDAL);
            break;
        case "S":
            ShowInstructions();
            break;
        case "P":
            LookUpPetName(invDAL);
            break;
        case "Q":
            userDone = true;
            break;
        default:
            Console.WriteLine("Bad data! Try again");
            break;
    }
} while (!userDone);
}
catch (Exception ex)
{
    Console.WriteLine(ex.Message);
}
finally
{
    invDAL.CloseConnection();
}
}

```

Implementing the ShowInstructions() Method

The `ShowInstructions()` method does what you would expect:

```

private static void ShowInstructions()
{
    Console.WriteLine("I: Inserts a new car.");
    Console.WriteLine("U: Updates an existing car.");
    Console.WriteLine("D: Deletes an existing car.");
    Console.WriteLine("L: Lists current inventory.");
    Console.WriteLine("S: Shows these instructions.");
    Console.WriteLine("P: Looks up pet name.");
    Console.WriteLine("Q: Quits program.");
}

```

Implementing the ListInventory() Method

You could implement the `ListInventory()` method in either of two ways, based on how you constructed your data access library. Recall that the `GetAllInventoryAsDataTable()` method of `InventoryDAL` returns a `DataTable` object. You could implement this approach like this:

```
private static void ListInventory(InventoryDAL invDAL)
{
    // Get the list of inventory.
    DataTable dt = invDAL.GetAllInventoryAsDataTable();

    // Pass DataTable to helper function to display.
    DisplayTable(dt);
}
```

The `DisplayTable()` helper method displays the table data using the `Rows` and `Columns` properties of the incoming `DataTable` (again, you will learn the full details of the `DataTable` object the next chapter, so don't fret over the details):

```
private static void DisplayTable(DataTable dt)
{
    // Print out the column names.
    for (int curCol = 0; curCol < dt.Columns.Count; curCol++)
    {
        Console.Write(dt.Columns[curCol].ColumnName + "\t");
    }
    Console.WriteLine("\n-----");

    // Print the DataTable.
    for (int curRow = 0; curRow < dt.Rows.Count; curRow++)
    {
        for (int curCol = 0; curCol < dt.Columns.Count; curCol++)
        {
            Console.Write(dt.Rows[curRow][curCol].ToString() + "\t");
        }
        Console.WriteLine();
    }
}
```

If you would prefer to call the `GetAllInventoryAsList()` method of `InventoryDAL`, you could implement a method named `ListInventoryViaList()`:

```
private static void ListInventoryViaList(InventoryDAL invDAL)
{
    // Get the list of inventory.
    List<NewCar> record = invDAL.GetAllInventoryAsList();

    foreach (NewCar c in record)
    {
        Console.WriteLine("CarID: {0}, Make: {1}, Color: {2}, PetName: {3}",
            c.CarID, c.Make, c.Color, c.PetName);
    }
}
```

Implementing the DeleteCar() Method

Deleting an existing automobile is as simple as asking the user for the ID of the car and passing this to the DeleteCar() method of the InventoryDAL type:

```
private static void DeleteCar(InventoryDAL invDAL)
{
    // Get ID of car to delete.
    Console.WriteLine("Enter ID of Car to delete: ");
    int id = int.Parse(Console.ReadLine());

    // Just in case you have a referential integrity
    // violation!
    try
    {
        invDAL.DeleteCar(id);
    }
    catch(Exception ex)
    {
        Console.WriteLine(ex.Message);
    }
}
```

Implementing the InsertNewCar() Method

Inserting a new record into the Inventory table is a simple matter of asking the user for the new bits of data (using Console.ReadLine() calls) and passing this data into the InsertAuto() method of InventoryDAL:

```
private static void InsertNewCar(InventoryDAL invDAL)
{
    // First get the user data.
    int newCarID;
    string newCarColor, newCarMake, newCarPetName;

    Console.WriteLine("Enter Car ID: ");
    newCarID = int.Parse(Console.ReadLine());

    Console.WriteLine("Enter Car Color: ");
    newCarColor = Console.ReadLine();

    Console.WriteLine("Enter Car Make: ");
    newCarMake = Console.ReadLine();

    Console.WriteLine("Enter Pet Name: ");
    newCarPetName = Console.ReadLine();

    // Now pass to data access library.
    invDAL.InsertAuto(newCarID, newCarColor, newCarMake, newCarPetName);
}
```

Recall that you overloaded `InsertAuto()` to take a `NewCar` object, rather than a set of independent arguments. Thus, you could have implemented `InsertNewCar()` like this:

```
private static void InsertNewCar(InventoryDAL invDAL)
{
    // First get the user data.
    ...

    // Now pass to data access library.
    NewCar c = new NewCar { CarID = newCarID, Color = newCarColor,
                           Make = newCarMake, PetName = newCarPetName };
    invDAL.InsertAuto(c);
}
```

Implementing the `UpdateCarPetName()` Method

The implementation of `UpdateCarPetName()` looks similar:

```
private static void UpdateCarPetName(InventoryDAL invDAL)
{
    // First get the user data.
    int carID;
    string newCarPetName;

    Console.Write("Enter Car ID: ");
    carID = int.Parse(Console.ReadLine());
    Console.Write("Enter New Pet Name: ");
    newCarPetName = Console.ReadLine();

    // Now pass to data access library.
    invDAL.UpdateCarPetName(carID, newCarPetName);
}
```

Implementing `LookUpPetName()`

Obtaining the pet name of a given automobile works similarly to the previous methods; this is so because the data access library encapsulates all of the lower-level ADO.NET calls:

```
private static void LookUpPetName(InventoryDAL invDAL)
{
    // Get ID of car to look up.
    Console.Write("Enter ID of Car to look up: ");
    int id = int.Parse(Console.ReadLine());
    Console.WriteLine("Petname of {0} is {1}.",
                      id, invDAL.LookUpPetName(id));
}
```

With this, your console-based front end is finished! It's time to run your program and test each method. Here is some partial output that tests the L, P, and Q commands:

***** The AutoLot Console UI *****

I: Inserts a new car.
U: Updates an existing car.
D: Deletes an existing car.
L: Lists current inventory.
S: Shows these instructions.
P: Looks up pet name.
Q: Quits program.

Please enter your command: L

CarID	Make	Color	PetName
83	Ford	Rust	Rusty
107	Ford	Red	Snake
678	Yugo	Green	Clunker
904	VW	Black	Hank
1000	BMW	Black	Bimmer
1001	BMW	Tan	Daisy
1992	Saab	Pink	Pinkey

Please enter your command: P

Enter ID of Car to look up: 904
Petname of 904 is Hank.

Please enter your command: Q

Press any key to continue . . .

■ **Source Code** You can find the AutoLotCUIClient application under the Chapter 21 subdirectory.

Understanding Database Transactions

Let's wrap up this examination of the connected layer of ADO.NET by taking a look at the concept of a database transaction. Simply put, a *transaction* is a set of database operations that must either *all* work or *all* fail as a collective unit. As you might imagine, transactions are quite important to ensure that table data is safe, valid, and consistent.

Transactions are important when a database operation involves interacting with multiple tables or multiple stored procedures (or a combination of database atoms). The classic transaction example involves the process of transferring monetary funds between two bank accounts. For example, if you were to transfer \$500.00 from your savings account into your checking account, the following steps should occur in a transactional manner:

- The bank should remove \$500.00 from your savings account.
- The bank should add \$500.00 to your checking account.

It would be an extremely bad thing if the money were removed from the savings account, but not transferred to the checking account (due to some error on the bank's part) because then you would be out \$500.00! However, if these steps are wrapped up into a database transaction, the DBMS ensures that all related steps occur as a single unit. If any part of the transaction fails, the entire operation is *rolled back* to the original state. On the other hand, if all steps succeed, the transaction is *committed*.

Note You might be familiar with the acronym ACID from looking at transactional literature. This represents the four key properties of a prim-and-proper transaction: *Atomic* (all or nothing); *Consistent* (data remains stable throughout the transaction); *Isolated* (transactions do not step on each other's feet); and *Durable* (transactions are saved and logged).

It turns out that the .NET platform supports transactions in a variety of ways. This chapter will look at the transaction object of your ADO.NET data provider (`SqlTransaction`, in the case of `System.Data.SqlClient`). The .NET base class libraries also provide transactional support within numerous APIs, including the following:

- `System.EnterpriseServices`: This namespace (located in the `System.EnterpriseServices.dll` assembly) provides types that allow you to integrate with the COM+ runtime layer, including its support for distributed transactions.
- `System.Transactions`: This namespace (located in the `System.Transactions.dll` assembly) contains classes that allow you to write your own transactional applications and resource managers for a variety of services (e.g., MSMQ, ADO.NET, and COM+).
- *Windows Communication Foundation*: The WCF API provides services to facilitate transactions with various distributed binding classes.
- *Windows Workflow Foundations*: The WF API provides transactional support for workflow activities.

In addition to the baked-in transactional support found within the .NET base class libraries, it is also possible to use the SQL language of your database management system. For example, you could author a stored procedure that uses the `BEGIN TRANSACTION`, `ROLLBACK`, and `COMMIT` statements.

Key Members of an ADO.NET Transaction Object

While transactional-aware types exist throughout the base class libraries, you will focus on transaction objects found within an ADO.NET data provider, all of which derive from `DBTransaction` and implement the `IDbTransaction` interface. Recall from the beginning of this chapter that `- IDbTransaction` defines a handful of members:

```
public interface IDbTransaction : IDisposable
{
    IDbConnection Connection { get; }
    IsolationLevel IsolationLevel { get; }

    void Commit();
    void Rollback();
}
```

Notice the `Connection` property, which returns a reference to the connection object that initiated the current transaction (as you'll see, you obtain a transaction object from a given connection object). You call the `Commit()` method when each of your database operations have succeeded. Doing this causes each of the pending changes to be persisted in the data store. Conversely, you can call the `Rollback()` method in the event of a runtime exception, which informs the DMBS to disregard any pending changes, leaving the original data intact.

■ **Note** The `IsolationLevel` property of a transaction object allows you to specify how aggressively a transaction should be guarded against the activities of other parallel transactions. By default, transactions are isolated completely until committed. Consult the .NET Framework 4.0 SDK documentation for full details regarding the values of the `IsolationLevel` enumeration.

Beyond the members defined by the `IDbTransaction` interface, the `SqlTransaction` type defines an additional member named `Save()`, which allows you to define *save points*. This concept allows you to roll back a failed transaction up until a named point, rather than rolling back the entire transaction. Essentially, when you call `Save()` using a `SqlTransaction` object, you can specify a friendly string moniker. When you call `Rollback()`, you can specify this same moniker as an argument to perform an effective *partial rollback*. Calling `Rollback()` with no arguments causes all of the pending changes to be rolled back.

Adding a CreditRisks Table to the AutoLot Database

Now let's look at how you use ADO.NET transactions. Begin by using the Server Explorer of Visual Studio 2010 to add a new table named `CreditRisks` to the `AutoLot` database, which has the same exact columns as the `Customers` table you created earlier in this chapter: `CustID`, which is the primary key; `FirstName`; and `LastName`. As its name suggests, `CreditRisks` is where you banish the undesirable customers who fail a credit check. Assuming you have added this new table to your database diagram, you should now see the `AutoLot` implementation shown in Figure 21-14.




Figure 21-14. The interconnected Orders, Inventory, and Customers tables

Like the earlier savings-to-checking money transfer example, this example, where you move a risky customer from the **Customers** table into the **CreditRisks** table, should occur under the watchful eye of a transactional scope (after all, you will want to remember the ID and names of those who are not creditworthy). Specifically, you need to ensure that *either* you successfully delete the current credit risks from the **Customers** table and add them to the **CreditRisks** table, *or* you need to ensure that neither of these database operations occurs.

Note In a production environment, you would not need to build a whole new database table to capture high risk customers; instead, you could add a Boolean column named **IsCreditRisk** to the existing **Customers** table. However, this new table lets you play with a simple transaction.

Adding a Transaction Method to InventoryDAL

Now let's look at how you work with ADO.NET transactions programmatically. Begin by opening the **AutoLotDAL** Code Library project you created earlier and add a new public method named **ProcessCreditRisk()** to the **InventoryDAL** class to deal with perceived a credit risks (note that this example avoids using a parameterized query to keep the implementation simple; however, you'd want use such a query for a production-level method):

```
// A new member of the InventoryDAL class.
public void ProcessCreditRisk(bool throwEx, int custID)
```

```

{
    // First, look up current name based on customer ID.
    string fName = string.Empty;
    string lName = string.Empty;
    SqlCommand cmdSelect = new SqlCommand(
        string.Format("Select * from Customers where CustID = {0}", custID), sqlCn);
    using (SqlDataReader dr = cmdSelect.ExecuteReader())
    {
        if(dr.HasRows)
        {
            dr.Read();
            fName = (string)dr["FirstName"];
            lName = (string)dr["LastName"];
        }
        else
            return;
    }

    // Create command objects that represent each step of the operation.
    SqlCommand cmdRemove = new SqlCommand(
        string.Format("Delete from Customers where CustID = {0}", custID), sqlCn);

    SqlCommand cmdInsert = new SqlCommand(string.Format("Insert Into CreditRisks" +
        "(CustID, FirstName, LastName) Values" +
        "({0}, '{1}', '{2}')", custID, fName, lName), sqlCn);

    // You will get this from the connection object.
    SqlTransaction tx = null;
    try
    {
        tx = sqlCn.BeginTransaction();

        // Enlist the commands into this transaction.
        cmdInsert.Transaction = tx;
        cmdRemove.Transaction = tx;

        // Execute the commands.
        cmdInsert.ExecuteNonQuery();
        cmdRemove.ExecuteNonQuery();

        // Simulate error.
        if (throwEx)
        {
            throw new Exception("Sorry! Database error! Tx failed...");
        }

        // Commit it!
        tx.Commit();
    }
    catch (Exception ex)
    {
}

```

```

        Console.WriteLine(ex.Message);
        // Any error will roll back transaction.
        tx.Rollback();
    }
}

```

Here, you use an incoming bool parameter to represent whether you will throw an arbitrary exception when you attempt to process the offending customer. This allows you to simulate an unforeseen circumstance that will cause the database transaction to fail. Obviously, you do this here only for illustrative purposes; a true database transaction method would not want to allow the caller to force the logic to fail on a whim!

Note that you use two `SqlCommand` objects to represent each step in the transaction you will kick off. Once you obtain the customer's first and last name based on the incoming `custID` parameter, you can obtain a valid `SqlTransaction` object from the connection object using `BeginTransaction()`. Next, and most importantly, you must *enlist each command object* by assigning the `Transaction` property to the transaction object you have just obtained. If you fail to do so, the Insert/Delete logic will not be under a transactional context.

After you call `ExecuteNonQuery()` on each command, you throw an exception if (and only if) the value of the `bool` parameter is true. In this case, all pending database operations are rolled back. If you do not throw an exception, both steps will be committed to the database tables once you call `Commit()`. Now compile your modified `AutoLotDAL` project to ensure you do not have any typos.

Testing Your Database Transaction

You could update your previous `AutoLotCUIClient` application with a new option to invoke the `ProcessCreditRisk()` method; instead, however, you will create a new Console Application named `AdoNetTransaction` to accomplish this. Set a reference to your `AutoLotDAL.dll` assembly and import the `AutoLotConnectedLayer` namespace.

Next, open your `Customers` table for data entry by right-clicking the table icon from the Server Explorer and selecting Show Table Data. Now add a new customer who will be the victim of a low credit score:

- `CustID: 333`
- `FirstName: Homer`
- `LastName: Simpson`

Finally, update your `Main()` method as follows:

```

static void Main(string[] args)
{
    Console.WriteLine("***** Simple Transaction Example *****\n");

    // A simple way to allow the tx to succeed or not.
    bool throwEx = true;
    string userAnswer = string.Empty;

    Console.Write("Do you want to throw an exception (Y or N): ");
    userAnswer = Console.ReadLine();
    if (userAnswer.ToLower() == "n")

```

```

{
    throwEx = false;
}

InventoryDAL dal = new InventoryDAL();
dal.OpenConnection(@"Data Source=(local)\SQLEXPRESS;Integrated Security=SSPI;" +
    "Initial Catalog=AutoLot");

// Process customer 333.
dal.ProcessCreditRisk(throwEx, 333);

Console.WriteLine("Check CreditRisk table for results");
Console.ReadLine();
}

```

If you were to run your program and elect to throw an exception, you would find that Homer is *not* removed from the *Customers* table because the entire transaction has been rolled back. However, if you did not throw an exception, you would find that Customer ID 333 is no longer in the *Customers* table and has been placed in the *CreditRisks* table instead.

Source Code You can find the *AdoNetTransaction* project under the Chapter 21 subdirectory.

Summary

ADO.NET is the native data access technology of the .NET platform, and you can use it in three distinct manners: connected, disconnected, or through the Entity Framework. In this chapter, you examined the connected layer and learned the role of data providers, which are essentially concrete implementations of several abstract base classes (in the *System.Data.Common*) namespace and interface types (in the *System.Data* namespace). You also saw that it is possible to build a provider-neutral code base using the ADO.NET data provider factory model.

You also learned that you can use connection objects, transaction objects, command objects, and data reader objects of the connected layer to select, update, insert, and delete records. Also, recall that command objects support an internal parameter collection, which you can use to add some type safety to your SQL queries; these also prove quite helpful when triggering stored procedures.



ADO.NET Part II: The Disconnected Layer

The previous chapter gave you a chance to examine the *connected layer* of ADO.NET, which allows you to submit SQL statements to a database using the connection, command, and data reader objects of your data provider. In this chapter, you will learn about the *disconnected layer* of ADO.NET. Using this facet of ADO.NET lets you model database data in memory within the calling tier by leveraging numerous members of the `System.Data` namespace (most notably: `DataSet`, `DataTable`, `DataRow`, `DataColumn`, `DataView`, and `DataRelation`). By doing so, you can provide the illusion that the calling tier is continuously connected to an external data source; the reality is that the caller is operating on a local copy of relational data.

While it is possible to use this *disconnected* aspect of ADO.NET without ever making a literal connection to a relational database, you will most often obtain populated `DataSet` objects using the data adapter object of your data provider. As you will see, data adapter objects function as a bridge between the client tier and a relational database. Using these objects, you can obtain `DataSet` objects, manipulate their contents, and send modified rows back for processing. The end result is a highly scalable data-centric .NET application.

This chapter will also illustrate some data-binding techniques, using the context of a Windows Forms GUI desktop application, and examine the role of a *strongly typed DataSet*. You will also update the `AutoLotDAL.dll` data library you created in Chapter 21 with a new namespace that uses the disconnected layer of ADO.NET. Last but not least, you will learn about the role of LINQ to `DataSet`, which allows you to apply LINQ queries to your in-memory data cache.

Note You will learn about data-binding techniques for Windows Presentation Foundation and ASP.NET applications later in this book.

Understanding the Disconnected Layer of ADO.NET

As you saw in the previous chapter, working with the connected layer allows you to interact with a database using the primary connection, command, and data reader objects. You can use this handful of classes to select, insert, update, and delete records to your heart's content (as well as invoke stored procedures or perform other data operations [e.g., DDL to create table and DCL to grant permissions]). However, you have seen only part of the ADO.NET story. Recall that you can use the ADO.NET object model in a disconnected manner.

Using the disconnected layer, it is possible to model relational data using an in-memory object model. Far beyond simply modeling a tabular block of rows and columns, the types within `System.Data` allow you to represent table relationships, column constraints, primary keys, views, and other database primitives. Once you model the data, you can apply filters, submit in-memory queries, and persist (or load) your data in XML and binary formats. You can do all of this without ever making a literal connection to a DBMS (hence the term, *disconnected layer*) by loading data from a local XML file or manually building a `DataSet` in code.

You could use the disconnected types without ever connecting to a database, but you will typically still use connection and command objects. In addition, you will leverage a specific object, the *data adapter* (which extends the abstract `DbDataAdapter` class), to fetch and update data. Unlike the connected layer, data obtained with a data adapter is not processed using data reader objects. Rather, data adapter objects use `DataSet` objects to move data between the caller and data source. The `DataSet` type is a container for any number of `DataTable` objects, each of which contains a collection of `DataRow` and `DataColumn` objects.

The data adapter object of your data provider handles the database connection automatically. In an effort to increase scalability, data adapters keep the connection open for the shortest amount of time possible. Once the caller receives the `DataSet` object, the calling tier is completely disconnected from the database and left with a local copy of the remote data. The caller is free to insert, delete, or update rows from a given `DataTable`, but the physical database is not updated until the caller explicitly passes the `DataSet` to the data adapter for updating. In a nutshell, `DataSets` allow the clients to pretend they are always connected; however, they actually operate on an in-memory database (see Figure 22-1).




Figure 22-1. Data adapter objects move `DataSets` to and from the client tier

Given that the centerpiece of the disconnected layer is the `DataSet` class, the first task of this chapter is to learn how to manipulate a `DataSet` manually. Once you can do this, you will have no problem manipulating the contents of a `DataSet` retrieved from a data adapter object.

Understanding the Role of the `DataSet`

As noted previously, a `DataSet` is an in-memory representation of relational data. More specifically, a `DataSet` is a class type that internally maintains three strongly typed collections (see Figure 22-2).




Figure 22-2. The anatomy of a *DataSet*

The *Tables* property of the *DataSet* allows you to access the *DataTableCollection* that contains the individual *DataTables*. Another important collection used by the *DataSet*: *DataRelationCollection*. Given that a *DataSet* is a disconnected version of a database schema, you can use it to represent the parent/child relationships programmatically between its tables. For example, you can create a relation between two tables to model a foreign key constraint using the *DataRelation* type. You can add this object to the *DataRelationCollection* with the *Relations* property. At this point, you can navigate between the related tables as you search for data. You will see how to do this later in the chapter.

The *ExtendedProperties* property provides access to the *PropertyCollection* object, which allows you to associate any extra information to the *DataSet* as name/value pairs. This information can be literally anything, even if it has no bearing on the database data itself. For example, you can associate your company's name to a *DataSet*, which can then function as in-memory metadata. Other examples of extended properties might include time stamps, an encrypted password that must be supplied to access the contents of the *DataSet*, a number representing a data refresh rate, and so forth.

■ **Note** The *DataTable* and *DataColumn* classes also support the *ExtendedProperties* property.

Key Properties of the *DataSet*

Before exploring too many other programmatic details, let's take a look at some core members of the *DataSet*. Table 22-1 describes some additional properties of interest beyond the *Tables*, *Relations*, and *ExtendedProperties* properties.

Table 22-1. Properties of the *DataSet*

Property	Meaning in Life
<i>CaseSensitive</i>	Indicates whether string comparisons in <i>DataTable</i> objects are case sensitive (or not). The default is <i>false</i> (string comparisons are not case sensitive by default).
<i>DataSetName</i>	Represents the friendly name of this <i>DataSet</i> . Typically, you establish this value as a constructor parameter.

Table 22-1. Properties of the DataSet (continued)

Property	Meaning in Life
EnforceConstraints	Gets or sets a value indicating whether constraint rules are followed when attempting any update operations (the default is true).
HasErrors	Gets a value indicating whether there are errors in any of the rows in any of the DataTables of the DataSet.
RemotingFormat	Allows you to define how the DataSet should serialize its content (binary or XML, which is the default).

Key Methods of the DataSet

The methods of the DataSet work in conjunction with some of the functionality provided by the aforementioned properties. In addition to interacting with XML streams, the DataSet provides methods that allow you to copy the contents of your DataSet, navigate between the internal tables, and establish the beginning and ending points of a batch of updates. Table 22-2 describes some core methods.

Table 22-2. Select Methods of the DataSet

Methods	Meaning in Life
AcceptChanges()	Commits all the changes made to this DataSet since it was loaded or the last time AcceptChanges() was called.
Clear()	Completely clears the DataSet data by removing every row in each DataTable.
Clone()	Clones the structure, but not the data, of the DataSet, including all DataTables, as well as all relations and any constraints.
Copy()	Copies both the structure and data for this DataSet.
GetChanges()	Returns a copy of the DataSet containing all changes made to it since it was last loaded or since AcceptChanges() was called. This method is overloaded, so that you can get just the new rows, just the modified rows, or just the deleted rows.
HasChanges()	Gets a value indicating whether the DataSet has changes, including new, deleted, or modified rows.
Merge()	Merges this DataSet with a specified DataSet.

Table 22-2. Select Methods of the DataSet (continued)

Methods	Meaning in Life
ReadXml()	Allows you to define the structure of a DataSet object and populate it with data, based on XML schema and data read from a stream.
RejectChanges()	Rolls back all the changes made to this DataSet since it was created or since the last time AcceptChanges() was called.
WriteXml()	Allow you to write out the contents of a DataSet into a valid stream.

Building a DataSet

Now that you have a better understanding of the role of the `DataSet` (and some idea of what you can do with one), create a new Console Application named `SimpleDataSet` and import the `System.Data` namespace. Within the `Main()` method, define a new `DataSet` object that contains three extended properties that represent a time stamp, a unique identifier (represented as a `System.Guid` type), and your company's name:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with DataSets *****\n");

    // Create the DataSet object and add a few properties.
    DataSet carsInventoryDS = new DataSet("Car Inventory");

    carsInventoryDS.ExtendedProperties["TimeStamp"] = DateTime.Now;
    carsInventoryDS.ExtendedProperties["DataSetID"] = Guid.NewGuid();
    carsInventoryDS.ExtendedProperties["Company"] =
        "Mikko's Hot Tub Super Store";
    Console.ReadLine();
}
```

You might be unfamiliar with the concept of a globally unique identifier (GUID); all you need to know is that it is a statically unique 128-bit number. While GUIDs are used throughout the COM framework to identify numerous things (e.g., classes, interfaces, and applications), the `System.Guid` type remains helpful under .NET when you need to generate a unique identifier quickly.

In any case, a `DataSet` object is not interesting until you insert any number of `DataTables`. Therefore, the next task is to examine the internal composition of the `DataTable`, beginning with the `DataColumn` type.

Working with `DataColumns`

The `DataColumn` type represents a single column within a `DataTable`. Collectively speaking, the set of all `DataColumn` types bound to a given `DataTable` represents the foundation of a table's *schema* information. For example, if you were to model the `Inventory` table of the `AutoLot` database (see Chapter 21), you

would create four `DataColumns`, one for each column (`CarID`, `Make`, `Color`, and `PetName`). Once you create your `DataColumn` objects, you typically add them into the `columns` collection of the `DataTable` type (using the `Columns` property).

Based on your background, you might know that you can assign a given column in a database table a set of constraints (e.g., configured as a primary key, assigned a default value, or configured to contain read-only information). Also, every column in a table must map to an underlying data type. For example, the `Inventory` table's schema requires that the `CarID` column map to an integer, while `Make`, `Color`, and `PetName` map to an array of characters. The `DataColumn` class has numerous properties that allow you to configure precisely these things. Table 22-3 provides a rundown of some core properties.

Table 22-3. Properties of the `DataColumn`

Properties	Meaning in Life
<code>AllowDBNull</code>	You use this property to indicate whether a row can specify <code>null</code> values in this column. The default value is <code>true</code> .
<code>AutoIncrement</code> <code>AutoIncrementSeed</code> <code>AutoIncrementStep</code>	You use these properties to configure the autoincrement behavior for a given column. This can be helpful when you wish to ensure unique values in a given <code> DataColumn</code> (such as a primary key). By default, a <code> DataColumn</code> does not support autoincrement behavior.
<code>Caption</code>	This property gets or sets the caption you want to display for this column. This allows you to define a user-friendly version of a literal database column name.
<code>ColumnMapping</code>	This property determines how a <code> DataColumn</code> is represented when a <code>DataSet</code> is saved as an XML document using the <code>DataSet.WriteXml()</code> method. You can specify that the data column should be written out as an XML element, an XML attribute, simple text content, or ignored altogether.
<code>ColumnName</code>	This property gets or sets the name of the column in the <code>Columns</code> collection (meaning how it is represented internally by the <code>DataTable</code>). If you do not set the <code>ColumnName</code> explicitly, the default values are <code>Column</code> with $(n+1)$ numerical suffixes (e.g., <code>Column1</code> , <code>Column2</code> , and <code>Column3</code>).
<code>DataType</code>	This property defines the data type (e.g., <code>Boolean</code> , <code>string</code> , or <code>float</code>) stored in the column.
<code>DefaultValue</code>	This property gets or sets the default value assigned to this column when you insert new rows.
<code>Expression</code>	This property gets or sets the expression used to filter rows, calculate a column's value, or create an aggregate column.

Table 22-3. Properties of the DataColumn (continued)

Properties	Meaning in Life
Ordinal	This property gets the numerical position of the column in the Columns collection maintained by the DataTable.
ReadOnly	This property determines whether this column is read only once a row has been added to the table. The default is false.
Table	This property gets the DataTable that contains this DataColumn.
Unique	This property gets or sets a value indicating whether the values in each row of the column must be unique or if repeating values are permissible. If you assign a column a primary key constraint, then you must set the Unique property to true.

Building a DataColumn

To continue with the SimpleDataSet project (and illustrate the use of the DataColumn), assume you wish to model the columns of the Inventory table. Given that the CarID column will be the table's primary key, you will configure this DataColumn object as read-only, unique, and non-null (using the ReadOnly, Unique, and AllowDBNull properties). Next, update the Program class with a new method named FillDataSet(), which you use to build four DataColumn objects. Note this method takes a DataSet object as its only parameter:

```
static void FillDataSet(DataSet ds)
{
    // Create data columns that map to the
    // 'real' columns in the Inventory table
    // of the AutoLot database.
    DataColumn carIDColumn = new DataColumn("CarID", typeof(int));
    carIDColumn.Caption = "Car ID";
    carIDColumn.ReadOnly = true;
    carIDColumn.AllowDBNull = false;
    carIDColumn.Unique = true;

    DataColumn carMakeColumn = new DataColumn("Make", typeof(string));
    DataColumn carColorColumn = new DataColumn("Color", typeof(string));
    DataColumn carPetNameColumn = new DataColumn("PetName", typeof(string));
    carPetNameColumn.Caption = "Pet Name";
}
```

Notice that when you configure the carIDColumn object, you assign a value to the Caption property. This property is helpful because it allows you to define a string value for display purposes, which can be distinct from the literal database table column name (column names in a literal database table are typically better suited for programming purposes [e.g., au_fname] than display purposes [e.g., Author

`First Name]).` Here, you set the caption for the `PetName` column for the same reason, because *Pet Name* looks nicer than `PetName` to the end user.

Enabling Autoincrementing Fields

One aspect of the `DataTable` you can choose to configure is its ability to *autoincrement*. You use an autoincrementing column to ensure that when a new row is added to a given table, the value of this column is assigned automatically, based on the current step of the increase. This can be helpful when you wish to ensure that a column has no repeating values (e.g., a primary key).

You control this behavior using the `AutoIncrement`, `AutoIncrementSeed`, and `AutoIncrementStep` properties. You use the seed value to mark the starting value of the column; you use the step value to identify the number to add to the seed when incrementing. Consider the following update to the construction of the `carIDColumn` `DataTable`:

```
static void FillDataSet(DataSet ds)
{
    DataColumn carIDColumn = new DataColumn("CarID", typeof(int));
    carIDColumn.ReadOnly = true;
    carIDColumn.Caption = "Car ID";
    carIDColumn.AllowDBNull = false;
    carIDColumn.Unique = true;
    carIDColumn.AutoIncrement = true;
    carIDColumn.AutoIncrementSeed = 0;
    carIDColumn.AutoIncrementStep = 1;
    ...
}
```

Here, you configure the `carIDColumn` object to ensure that, as rows are added to the respective table, the value for this column is incremented by 1. You set the seed at 0, so this column would be numbered 0, 1, 2, 3, and so forth.

Adding DataColumn Objects to a DataTable

The `DataColumn` type does not typically exist as a stand-alone entity; however, you do typically insert it into a related `DataTable`. For example, create a new `DataTable` object (fully detailed in a moment) and insert each `DataColumn` object in the `Columns` collection using the `Columns` property:

```
static void FillDataSet(DataSet ds):
{
    ...
    // Now add DataColumns to a DataTable.
    DataTable inventoryTable = new DataTable("Inventory");
    inventoryTable.Columns.AddRange(new DataColumn[]
    {
        carIDColumn, carMakeColumn, carColorColumn, carPetNameColumn
    });
}
```

At this point, the `DataTable` object contains four `DataColumn` objects that represent the schema of the in-memory `Inventory` table. However, the table is currently devoid of data, and the table is currently

outside of the table collection maintained by the `DataSet`. You will deal with both of these shortcomings, beginning by populating the table with data using a `DataRow` objects.

Working with `DataRow`s

As you have seen, a collection of `DataColumn` objects represents the schema of a `DataTable`. In contrast, a collection of `DataRow` objects represents the actual data in the table. Thus, if you have 20 rows in the `Inventory` table of the `AutoLot` database, you can represent these records using 20 `DataRow` objects. Table 22-4 documents some (but not all) of the members of the `DataRow` type.

Table 22-4. Key Members of the `DataRow` Type

Members	Meaning in Life
<code>HasErrors</code> <code>GetColumnsInError()</code> <code>GetColumnError()</code> <code>ClearErrors()</code> <code>RowError</code>	The <code>HasErrors</code> property returns a Boolean value indicating whether there are errors in a <code> DataRow</code> . If so, you can use the <code>GetColumnsInError()</code> method to obtain the offending columns and <code>GetColumnError()</code> to obtain the error description. Similarly, you can use the <code>ClearErrors()</code> method to remove each error listing for the row. The <code>RowError</code> property allows you to configure a textual description of the error for a given row.
<code>ItemArray</code>	This property gets or sets all of the column values for this row using an array of objects.
<code>RowState</code>	You use this property to pinpoint the current <i>state</i> of the <code> DataRow</code> in the <code> DataTable</code> containing the <code> DataRow</code> , using values of the <code> RowState</code> enumeration (e.g., a row can be flagged as new, modified, unchanged, or deleted).
<code>Table</code>	You use this property to obtain a reference to the <code> DataTable</code> containing this <code> DataRow</code> .
<code>AcceptChanges()</code> <code>RejectChanges()</code>	These methods commit or reject all changes made to this row since the last time <code>AcceptChanges()</code> was called.
<code>BeginEdit()</code> <code>EndEdit()</code> <code>CancelEdit()</code>	These methods begin, end, or cancel an edit operation on a <code> DataRow</code> object.
<code>Delete()</code>	This method marks a row you want to remove when the <code>AcceptChanges()</code> method is called.
<code>IsNull()</code>	This method gets a value indicating whether the specified column contains a null value.

Working with a `DataRow` is a bit different from working with a `DataColumn`; you cannot create a direct instance of this type because there is no public constructor:

```
// Error! No public constructor!
DataRow r = new DataRow();
```

Instead, you obtain a new `DataRow` object from a given `DataTable`. For example, assume you wish to insert two rows in the `Inventory` table. The `DataTable.NewRow()` method allows you to obtain the next slot in the table, at which point you can fill each column with new data using the type indexer. When doing so, you can specify either the string name assigned to the `DataColumn` or its (zero-based) ordinal position:

```
static void FillDataSet(DataSet ds)
{
...
// Now add some rows to the Inventory Table.
DataRow carRow = inventoryTable.NewRow();
carRow["Make"] = "BMW";
carRow["Color"] = "Black";
carRow["PetName"] = "Hamlet";
inventoryTable.Rows.Add(carRow);

carRow = inventoryTable.NewRow();
// Column 0 is the autoincremented ID field,
// so start at 1.
carRow[1] = "Saab";
carRow[2] = "Red";
carRow[3] = "Sea Breeze";
inventoryTable.Rows.Add(carRow);
}
```

Note If you pass the `DataRow`'s indexer method an invalid column name or ordinal position, you will receive a runtime exception.

At this point, you have a single `DataTable` containing two rows. Of course, you can repeat this general process to create a number of `DataTables` to define the schema and data content. Before you insert the `inventoryTable` object into your `DataSet` object, you should check out the all-important `RowState` property.

Understanding the RowState Property

The `RowState` property is useful when you need to identify programmatically the set of all rows in a table that have changed from their original value, have been newly inserted, and so forth. You can assign this property any value from the `DataRowState` enumeration, as shown in Table 22-5.

Table 22-5. Values of the DataRowState Enumeration

Value	Meaning in Life
Added	The row has been added to a DataRowCollection, and AcceptChanges() has not been called.
Deleted	The row has been marked for deletion using the Delete() method of the DataRow, and AcceptChanges() has not been called.
Detached	The row has been created but is not part of any DataRowCollection. A DataRow is in this state immediately after it has been created, but before it is added to a collection. It is also in this state if it has been removed from a collection.
Modified	The row has been modified, and AcceptChanges() has not been called.
Unchanged	The row has not changed since AcceptChanges() was last called.

When you manipulate the rows of a given DataTable programmatically, the RowState property is set automatically. For example, add a new method to your Program class, which operates on a local DataRow object, printing out its row state along the way:

```
private static void ManipulateDataRowState()
{
    // Create a temp DataTable for testing.
    DataTable temp = new DataTable("Temp");
    temp.Columns.Add(new DataColumn("TempColumn", typeof(int)));

    // RowState = Detached (i.e. not part of a DataTable yet)
    DataRow row = temp.NewRow();
    Console.WriteLine("After calling NewRow(): {0}", row.RowState);

    // RowState = Added.
    temp.Rows.Add(row);
    Console.WriteLine("After calling Rows.Add(): {0}", row.RowState);

    // RowState = Added.
    row["TempColumn"] = 10;
    Console.WriteLine("After first assignment: {0}", row.RowState);

    // RowState = Unchanged.
    temp.AcceptChanges();
    Console.WriteLine("After calling AcceptChanges: {0}", row.RowState);

    // RowState = Modified.
    row["TempColumn"] = 11;
    Console.WriteLine("After first assignment: {0}", row.RowState);

    // RowState = Deleted.
    temp.Rows[0].Delete();
}
```

```

    Console.WriteLine("After calling Delete: {0}", row.RowState);
}

```

The ADO.NET DataRow is smart enough to remember its current state of affairs. Given this, the owning DataTable is able to identify which rows have been added, updated, or deleted. This is a key feature of the DataSet because, when it comes time to send updated information to the data store, only the modified data is submitted.

Understanding the DataRowVersion Property

Beyond maintaining the current state of a row with the RowState property, a DataRow object maintains three possible versions of the data it contains using the DataRowVersion property. When a DataRow object is first constructed, it contains only a single copy of data, represented as the current version. However, as you programmatically manipulate a DataRow object (using various method calls), additional versions of the data spring to life. Specifically, you can set the DataRowVersion to any value of the related DataRowVersion enumeration (see Table 22-6).

Table 22-6. Values of the DataRowVersion Enumeration

Value	Meaning in Life
Current	This represents the current value of a row, even after changes have been made.
Default	This is the default version of DataRowState. For a DataRowState value of Added, Modified, or Deleted, the default version is Current. For a DataRowState value of Detached, the version is Proposed.
Original	This represents the value first inserted into a DataRow or the value the last time AcceptChanges() was called.
Proposed	This is the value of a row currently being edited due to a call to BeginEdit().

As suggested in Table 22-6, the value of the DataRowVersion property is dependent on the value of the DataRowState property in many cases. As mentioned previously, the DataRowVersion property will be changed behind the scenes when you invoke various methods on the DataRow (or, in some cases, the DataTable) object. Here is a breakdown of the methods that can affect the value of a row's DataRowVersion property:

- If you call the `DataRow.BeginEdit()` method and change the row's value, the Current and Proposed values become available.
- If you call the `DataRow.CancelEdit()` method, the Proposed value is deleted.
- After you call `DataRow.EndEdit()`, the Proposed value becomes the Current value.
- After you call the `DataRow.AcceptChanges()` method, the Original value becomes identical to the Current value. The same transformation occurs when you call `DataTable.AcceptChanges()`.

- After you call `DataRow.RejectChanges()`, the `Proposed` value is discarded, and the `version` becomes `Current`.

Yes, this is a bit convoluted, not least because a `DataRow` might or might not have all versions at any given time (you'll receive runtime exceptions if you attempt to obtain a row version that is not currently tracked). Regardless of the complexity, given that the `DataRow` maintains three copies of data, it becomes simple to build a front end that allows an end user to alter values, change his or her mind and roll back values, or commit values permanently. You'll see various examples of manipulating these methods over the remainder of this chapter.

Working with DataTables

The `DataTable` type defines many members, many of which are identical in name and functionality to those of the `DataSet`. Table 22-7 describes some core members of the `DataTable` type beyond `Rows` and `Columns`.

Table 22-7. Key Members of the `DataTable` Type

Member	Meaning in Life
<code>CaseSensitive</code>	Indicates whether string comparisons within the table are case sensitive. The default value is <code>false</code> .
<code>ChildRelations</code>	Returns the collection of child relations for this <code>DataTable</code> (if any).
<code>Constraints</code>	Gets the collection of constraints maintained by the table.
<code>Copy()</code>	A method that copies the schema and data of a given <code>DataTable</code> into a new instance.
<code>DataSet</code>	Gets the <code>DataSet</code> that contains this table (if any).
<code>DefaultView</code>	Gets a customized view of the table that might include a filtered view or a cursor position.
<code>ParentRelations</code>	Gets the collection of parent relations for this <code>DataTable</code> .
<code>PrimaryKey</code>	Gets or sets an array of columns that function as primary keys for the data table.
<code>RemotingFormat</code>	Allows you to define how the <code>DataSet</code> should serialize its content (binary or XML) for the .NET remoting layer.
<code>TableName</code>	Gets or sets the name of the table. This same property might also be specified as a constructor parameter.

To continue with the current example, you can set the `PrimaryKey` property of the `DataTable` to the `carIDColumn` `DataColumn` object. Be aware that the `PrimaryKey` property is assigned a collection of `DataColumn` objects to account for a multicolumned key. In this case, however, you need to specify only the `CarID` column (being the first ordinal position in the table):

```
static void FillDataSet(DataSet ds)
{
...
    // Mark the primary key of this table.
    inventoryTable.PrimaryKey = new DataColumn[] { inventoryTable.Columns[0] };
}
```

Inserting DataTables into DataSets

At this point, your `DataTable` object is complete. The final step is to insert the `DataTable` into the `carsInventoryDS` `DataSet` object using the `Tables` collection:

```
static void FillDataSet(DataSet ds)
{
...
    // Finally, add our table to the DataSet.
    ds.Tables.Add(inventoryTable);
}
```

Now update your `Main()` method to call `FillDataSet()`, passing in your local `DataSet` object as an argument. Next, pass the same object into a new (yet to be written) helper method named `PrintDataSet()`:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with DataSets *****\n");
...
    FillDataSet(carsInventoryDS);
    PrintDataSet(carsInventoryDS);
    Console.ReadLine();
}
```

Obtaining Data in a DataSet

The `PrintDataSet()` method simply iterates over the `DataSet` metadata (using the `ExtendedProperties` collection) and each `DataTable` in the `DataSet`, printing out the column names and row values using the type indexers:

```
static void PrintDataSet(DataSet ds)
{
    // Print out the DataSet name and any extended properties.
    Console.WriteLine("DataSet is named: {0}", ds.DataSetName);
    foreach (System.Collections.DictionaryEntry de in ds.ExtendedProperties)
    {
```

```

    Console.WriteLine("Key = {0}, Value = {1}", de.Key, de.Value);
}
Console.WriteLine();

// Print out each table.
foreach (DataTable dt in ds.Tables)
{
    Console.WriteLine("> {0} Table:", dt.TableName);

    // Print out the column names.
    for (int curCol = 0; curCol < dt.Columns.Count; curCol++)
    {
        Console.Write(dt.Columns[curCol].ColumnName + "\t");
    }
    Console.WriteLine("\n-----");

    // Print the DataTable.
    for (int curRow = 0; curRow < dt.Rows.Count; curRow++)
    {
        for (int curCol = 0; curCol < dt.Columns.Count; curCol++)
        {
            Console.Write(dt.Rows[curRow][curCol].ToString() + "\t");
        }
        Console.WriteLine();
    }
}
}

```

If you run your program now, you'll see the following output (your time stamp and GUID value will differ of course):

```

***** Fun with DataSets *****

DataSet is named: Car Inventory
Key = TimeStamp, Value = 1/22/2010 6:41:09 AM
Key = DataSetID, Value = 11c533ed-d1aa-4c82-96d4-b0f88893ab21
Key = Company, Value = Mikko's Hot Tub Super Store

=> Inventory Table:
CarID  Make   Color   PetName
-----
0      BMW    Black   Hamlet
1      Saab   Red    Sea Breeze

```

Processing DataTable Data Using DataTableReader Objects

Given your work in the previous chapter, you should notice that the manner in which you process data using the connected layer (e.g., data reader objects) and the disconnected layer (e.g., DataSet objects) is

quite different. Working with a data reader typically involves establishing a while loop, calling the `Read()` method, and using an indexer to pluck out the name/value pairs. On the other hand, `DataSet` processing typically involves a series of iteration constructs to drill into the data within the tables, rows, and columns (remember that `DataReader` requires an open database connection so that it can read the data from the actual database).

`DataTables` support a method named `CreateDataReader()`. This method allows you to obtain the data within a `DataTable` using a data reader–like navigation scheme (the data reader will now read data from the in-memory `DataTable`, not from the actual database, so there's no database connection involved here). The major benefit of this approach is that you now use a single model to process data, regardless of which layer of ADO.NET you use to obtain it. Assume you have authored a new method in your `Program` class named `PrintTable()`:

```
static void PrintTable(DataTable dt)
{
    // Get the DataTableReader type.
    DataTableReader dtReader = dt.CreateDataReader();

    // The DataTableReader works just like the DataReader.
    while (dtReader.Read())
    {
        for (int i = 0; i < dtReader.FieldCount; i++)
        {
            Console.WriteLine("{0}\t", dtReader.GetValue(i).ToString().Trim());
        }
        Console.WriteLine();
    }
    dtReader.Close();
}
```

Notice that the `DataTableReader` works identically to the data reader object of your data provider. A `DataTableReader` can be an ideal choice when you wish to pump out the data within a `DataTable` quickly, without needing to traverse the internal row and column collections. Now assume you have updated the previous `PrintDataSet()` method to invoke `PrintTable()`, rather than drilling into the `Rows` and `Columns` collections:

```
static void PrintDataSet(DataSet ds)
{
    // Print out the DataSet name, plus any extended properties.
    Console.WriteLine("DataSet is named: {0}", ds.DataSetName);
    foreach (System.Collections.DictionaryEntry de in ds.ExtendedProperties)
    {
        Console.WriteLine("Key = {0}, Value = {1}", de.Key, de.Value);
    }
    Console.WriteLine();

    foreach (DataTable dt in ds.Tables)
    {
        Console.WriteLine("=> {0} Table:", dt.TableName);

        // Print out the column names.
        for (int curCol = 0; curCol < dt.Columns.Count; curCol++)
```

```

{
    Console.Write(dt.Columns[curCol].ColumnName.Trim() + "\t");
}
Console.WriteLine("\n-----");

// Call our new helper method.
PrintTable(dt);
}
}

```

When you run the application, the output is identical to that shown previously. The only difference is how you access the `DataTable`'s contents internally.

Serializing `DataTable`/`DataSet` Objects As XML

`DataSets` and `DataTables` both support the `WriteXml()` and `ReadXml()` methods. `WriteXml()` allows you to persist an object's content to a local file (as well as into any `System.IO.Stream`-derived type) as an XML document. `ReadXml()` allows you to hydrate the state of a `DataSet` (or `DataTable`) from a given XML document. In addition, `DataSets` and `DataTables` both support `WriteXmlSchema()` and `ReadXmlSchema()` for saving or loading an `*.xsd` file.

To test this out for yourself, update your `Main()` method to call the following helper function (notice that you pass a `DataSet` as the sole parameter):

```

static void SaveAndLoadAsXml(DataSet carsInventoryDS)
{
    // Save this DataSet as XML.
    carsInventoryDS.WriteXml("carsDataSet.xml");
    carsInventoryDS.WriteXmlSchema("carsDataSet.xsd");

    // Clear out DataSet.
    carsInventoryDS.Clear();

    // Load DataSet from XML file.
    carsInventoryDS.ReadXml("carsDataSet.xml");
}

```

If you open the `carsDataSet.xml` file (which you will find under the `\bin\Debug` folder of your project), you will find that each column in the table has been encoded as an XML element:

```

<?xml version="1.0" standalone="yes"?>
<Car_x0020_Inventory>
<Inventory>
    <CarID>0</CarID>
    <Make>BMW</Make>
    <Color>Black</Color>
    <PetName>Hamlet</PetName>
</Inventory>
<Inventory>
    <CarID>1</CarID>
    <Make>Saab</Make>

```

```

<Color>Red</Color>
<PetName>Sea Breeze</PetName>
</Inventory>
</Car_x0020_Inventory>

```

If you were to double click on the generated *.xsd file (also found under your \bin\Debug folder) within Visual Studio, you will open the IDE's XML schema editor (Figure 22-3).




Figure 22-3. The XSD editor of Visual Studio 2010

■ **Note** Chapter 24 will introduce you to the LINQ to XML API, which is the preferred manner for manipulating XML data in the .NET platform.

Serializing DataTable/DataSet Objects in a Binary Format

It is also possible to persist the contents of a DataSet (or an individual DataTable) as a compact binary format. This can be especially helpful when a DataSet object needs to be passed across a machine boundary (in the case of a distributed application); one drawback of XML data representation is that its descriptive nature can result in a good deal of overhead.

To persist DataTables or DataSets in a binary format, set the RemotingFormat property to `SerializationFormat.Binary`. At this point, you can use the `BinaryFormatter` type (see Chapter 20) as expected. Consider the following final method of the SimpleDataSet project (don't forget to import the `System.IO` and `System.Runtime.Serialization.Formatters.Binary` namespaces):

```

static void SaveAndLoadAsBinary(DataSet carsInventoryDS)
{
    // Set binary serialization flag.
    carsInventoryDS.RemotingFormat = SerializationFormat.Binary;

    // Save this DataSet as binary.
    FileStream fs = new FileStream("BinaryCars.bin", FileMode.Create);

```

```

BinaryFormatter bFormat = new BinaryFormatter();
bFormat.Serialize(fs, carsInventoryDS);
fs.Close();

// Clear out DataSet.
carsInventoryDS.Clear();

// Load DataSet from binary file.
fs = new FileStream("BinaryCars.bin", FileMode.Open);
DataSet data = (DataSet)bFormat.Deserialize(fs);
}

```

If you call this method from `Main()`, you can find the *.bin file in your bin\Debug folder. Figure 22-4 shows the contents of the `BinaryCars.bin` file.




Figure 22-4. A DataSet saved to a binary format

■ **Source Code** You can find the SimpleDataSet application under the Chapter 22 subdirectory.

Binding DataTable Objects to Windows Forms GUIs

So far, you have examined how to create, hydrate, and iterate over the contents of a `DataSet` object manually using the inherit object model of ADO.NET. While understanding how to do so is quite important, the .NET platform ships with numerous APIs that have the ability to *bind* data to user interface elements automatically.

For example, the original GUI toolkit of .NET, Windows Forms, supplies a control named `DataGridView` that includes the built-in ability to display the contents of a `DataSet` or `DataTable` object using only a few lines of code. ASP.NET (.NET's web development API) and the Windows Presentation Foundation API (a supercharged GUI API introduced with .NET 3.0) also support the notion of data binding. You will learn to bind data to WPF and ASP.NET GUI elements later in this book; however, in

this chapter, you will use Windows Forms because it is a fairly simple and straightforward programming model.

■ **Note** The next example assumes you have some experience using Windows Forms to build graphical user interfaces. If this is not the case, you might wish to open the solution and follow along or return to this section once you have read Appendix A.

Your next task is to build a Windows Forms application that will display the contents of a `DataTable` object within its user interface. Along the way, you will also examine how to filter and change table data. You will also learn about the role of the `DataView` object.

Begin by creating a brand-new Windows Forms project workspace named `WindowsFormsDataBinding`. Rename your initial `Form1.cs` file to the more fitting `MainForm.cs` using the Solution Explorer. Next, use the Visual Studio 2010 Toolbox to drag a `DataGridView` control (renamed to `carInventoryGridView` using the `(Name)` property of the Properties window) onto the designer surface. Notice that when you do this, you activate a context menu that allows you to connect to a physical data source. For the time being, ignore this aspect of the designer because you will be binding your `DataTable` object programmatically. Finally, add a descriptive `Label` to your designer for information purposes. Figure 22-5 shows one possible look-and-feel.



Figure 22-5. The initial GUI of your Windows Forms application

Hydrating a `DataTable` from a `Generic List<T>`

Similar to the previous `SimpleDataSet` example, the `WindowsFormsDataBinding` application will construct a `DataTable` that contains a set of `DataColumns` representing various columns and rows of data.

This time, however, you will fill the rows using a generic `List<T>` member variable. First, insert a new C# class into your project (named `Car`), which you define as follows:

```
public class Car
{
    public int ID { get; set; }
    public string PetName { get; set; }
    public string Make { get; set; }
    public string Color { get; set; }
}
```

Within the default constructor of your main form, populate a `List<T>` member variable (named `listCars`) with a set of new `Car` objects:

```
public partial class MainForm : Form
{
    // A collection of Car objects.
    List<Car> listCars = null;

    public MainForm()
    {
        InitializeComponent();

        // Fill the list with some cars.
        listCars = new List<Car>
        {
            new Car { ID = 100, PetName = "Chucky", Make = "BMW", Color = "Green" },
            new Car { ID = 101, PetName = "Tiny", Make = "Yugo", Color = "White" },
            new Car { ID = 102, PetName = "Ami", Make = "Jeep", Color = "Tan" },
            new Car { ID = 103, PetName = "Pain Inducer", Make = "Caravan",
                      Color = "Pink" },
            new Car { ID = 104, PetName = "Fred", Make = "BMW", Color = "Green" },
            new Car { ID = 105, PetName = "Sidd", Make = "BMW", Color = "Black" },
            new Car { ID = 106, PetName = "Mel", Make = "Firebird", Color = "Red" },
            new Car { ID = 107, PetName = "Sarah", Make = "Colt", Color = "Black" },
        };
    }
}
```

Next, add a new member variable named `inventoryTable` of type `DataTable` to your `MainForm` class type:

```
public partial class MainForm : Form
{
    // A collection of Car objects.
    List<Car> listCars = null;

    // Inventory information
    DataTable inventoryTable = new DataTable();
    ...
}
```

Now add a new helper function to your class named `CreateDataTable()` and call this method within the default constructor of the `MainForm` class:

```
private void CreateDataTable()
{
    // Create table schema.
    DataColumn carIDColumn = new DataColumn("ID", typeof(int));
    DataColumn carMakeColumn = new DataColumn("Make", typeof(string));
    DataColumn carColorColumn = new DataColumn("Color", typeof(string));
    DataColumn carPetNameColumn = new DataColumn("PetName", typeof(string));
    carPetNameColumn.Caption = "Pet Name";
    inventoryTable.Columns.AddRange(new DataColumn[] { carIDColumn,
        carMakeColumn, carColorColumn, carPetNameColumn });

    // Iterate over the List<T> to make rows.
    foreach (Car c in listCars)
    {
        DataRow newRow = inventoryTable.NewRow();
        newRow["ID"] = c.ID;
        newRow["Make"] = c.Make;
        newRow["Color"] = c.Color;
        newRow["PetName"] = c.PetName;
        inventoryTable.Rows.Add(newRow);
    }

    // Bind the DataTable to the carInventoryGridView.
    carInventoryGridView.DataSource = inventoryTable;
}
```

The method implementation begins by creating the schema of the `DataTable` by creating four `DataColumn` objects (for the sake of simplicity, you don't need to bother autoincrementing the `ID` field or set it as a primary key). After you do this, you can add them to the column collection of the `DataTable` member variable. You map the row data from your `List<Car>` collection into the `DataTable` using a `foreach` iteration construct and the native ADO.NET object model.

However, notice that the final code statement within the `CreateDataTable()` method assigns the `inventoryTable` to the `DataSource` property of the `DataGridView` object. This single property is all you need to set to bind a `DataTable` to a Windows Forms `DataGridView` object. Under the hood, this GUI control reads the row and column collections internally, much like what happens with the `PrintDataSet()` method of the `SimpleDataSet` example. At this point, you should be able to run your application and see the `DataTable` within the `DataGridView` control, as shown in Figure 22-6.




Figure 22-6. Binding a `DataTable` to a Windows Forms `DataGridView`

Deleting Rows from a DataTable

Now, assume you wish to update your graphical interface to allow the user to delete a row from the in-memory DataTable that is bound to the DataGridView. One approach is to call the Delete() method of the DataRow object that represents the row to terminate. In this case, you specify the index (or DataRow object) representing the row to remove. To allow the user to specify which row to delete, add a TextBox (named txtCarToRemove) and a Button control (named btnRemoveCar) to the current designer. Figure 22-7 shows one possible UI update (note this example wraps the two controls in a GroupBox control, illustrating how they are related).




Figure 22-7. Updating the UI to enable removal of rows from the underlying DataTable

The following logic behind the new Button's Click event handler removes the user-specified row, based on the ID of a car, from your in-memory DataTable. The Select() method of the DataTable class allows you to specify a search criteria, which is modeled after normal SQL syntax. The return value is an array of DataRow objects that matches the search criteria:

```
// Remove this row from the DataRowCollection.
private void btnRemoveCar_Click (object sender, EventArgs e)
{
    try
    {
        // Find the correct row to delete.
        DataRow[] rowToDelete = inventoryTable.Select(
            string.Format("ID={0}", int.Parse(txtCarToRemove.Text)));

        // Delete it!
        rowToDelete[0].Delete();
        inventoryTable.AcceptChanges();
    }
    catch (Exception ex)
    {
        MessageBox.Show(ex.Message);
    }
}
```

You should now be able to run your application and specify a car ID to delete from the DataTable. As you remove DataRow objects from the DataTable, you will notice that the grid's UI is updated immediately; this occurs because it is bound to the state of the DataTable object.

Selecting Rows Based on Filter Criteria

Many data-centric applications require the need to view a small subset of a DataTable's data, as specified by some sort of filtering criteria. For example, assume you wish to see only a certain make of automobile from the in-memory DataTable (e.g., only BMWs). You've already seen how the Select() method of the DataTable class allows you to find a row to delete; however you can also use this method to grab a subset of records for display purposes.

To see this in action, update your UI again, this time allowing users to specify a string that represents the make of the automobile they want to see (see Figure 22-8) using a new TextBox (named txtMakeToView) and a new Button (named btnDisplayMakes).



Figure 22-8. Updating the UI to enable row filtering

The `Select()` method has been overloaded a number of times to provide different selection semantics. At its most basic level, the parameter sent to `Select()` is a string that contains some conditional operation. To begin, observe the following logic for the `Click` event handler of your new button:

```
private void btnDisplayMakes_Click(object sender, EventArgs e)
{
    // Build a filter based on user input.
    string filterStr = string.Format("Make= '{0}'", txtMakeToView.Text);

    // Find all rows matching the filter.
    DataRow[] makes = inventoryTable.Select(filterStr);

    if (makes.Length == 0)
        MessageBox.Show("Sorry, no cars...", "Selection error!");
    else
    {
        string strMake = "";
        for (int i = 0; i < makes.Length; i++)
        {
            // From the current row, get the PetName value.
            strMake += makes[i]["PetName"] + "\n";
        }

        // Show the names of all cars matching the specified Make.
        MessageBox.Show(strMake,
    }
```

```

        string.Format("We have {0}s named:", txtMakeToView.Text));
    }
}

```

Here, you begin by building a simple filter based on the value in the associated TextBox. If you specify BMW, your filter looks like this:

```
Make = 'BMW'
```

When you send this filter to the Select() method, you get back an array of DataRow types that represent each row that matches the filter (see Figure 22-9).




Figure 22-9. Displaying filtered data

Again, the filtering logic is based on standard SQL syntax. For example, assume you wish to obtain the results of the previous Select() invocation alphabetically, based on the pet name. In terms of SQL, this translates into a sort based on the PetName column. Fortunately, the Select() method has been overloaded to send in a sort criterion:

```
// Sort by PetName.
makes = inventoryTable.Select(filterStr, "PetName");
```

Call Select() as seen here if you want the results in descending order:

```
// Return results in descending order.
makes = inventoryTable.Select(filterStr, "PetName DESC");
```

In general, the sort string contains the column name, followed by ASC (ascending, which is the default) or DESC (descending). If necessary, you can separate multiple columns by commas. Finally,

understand that a filter string can be composed of any number of relational operators. For example, assume you want to find all cars with an ID greater than 5. This helper function lets you accomplish that:

```
private void ShowCarsWithIdGreater ThanFive()
{
    // Now show the pet names of all cars with ID greater than 5.
    DataRow[] properIDs;
    string newFilterStr = "ID > 5";
    properIDs = inventoryTable.Select(newFilterStr);
    string strIDs = null;
    for(int i = 0; i < properIDs.Length; i++)
    {
        DataRow temp = properIDs[i];
        strIDs += temp["PetName"]
            + " is ID " + temp["ID"] + "\n";
    }
    MessageBox.Show(strIDs, "Pet names of cars where ID > 5");
}
```

Updating Rows Within a DataTable

The final aspect of the `DataTable` you should be aware of is the process of updating an existing row with new values. One approach is to first obtain the row(s) that match a given filter criterion using the `Select()` method. Once you obtain the `DataRow`(s) in question, modify them accordingly. For example, assume you have a new Button on your form named `btnChangeMakes` that (when clicked) searches the `DataTable` for all rows where `Make` is equal to `BMW`. Once you identify these items, you change the `Make` from `BMW` to `Yugo`:

```
// Find the rows you want to edit with a filter.
private void btnChangeMakes_Click(object sender, EventArgs e)
{
    // Confirm selection.
    if (DialogResult.Yes ==
        MessageBox.Show("Are you sure?? BMWs are much nicer than Yugos!",
            "Please Confirm!", MessageBoxButtons.YesNo))
    {
        // Build a filter.
        string filterStr = "Make='BMW'";
        string strMake = string.Empty;

        // Find all rows matching the filter.
        DataRow[] makes = inventoryTable.Select(filterStr);

        // Change all Beemers to Yugos!
        for (int i = 0; i < makes.Length; i++)
        {
            makes[i]["Make"] = "Yugo";
        }
    }
}
```

Working with the DataView Type

A *view object* is an alternative representation of a table (or set of tables). For example, you can use Microsoft SQL Server to create a view for your *Inventory* table that returns a new table containing automobiles only of a given color. In ADO.NET, the *DataView* type allows you to extract a subset of data programmatically from the *DataTable* into a stand-alone object.

One great advantage of holding multiple views of the same table is that you can bind these views to various GUI widgets (such as the *DataGridView*). For example, one *DataGridView* might be bound to a *DataView* showing all autos in the *Inventory*, while another might be configured to display only green automobiles.

To see this in action, update the current UI with an additional *DataGridView* type named *dataGridYugosView* and a descriptive *Label*. Next, define a member variable named *yugosOnlyView* of type *DataView*:

```
public partial class MainForm : Form
{
    // View of the DataTable.
    DataView yugosOnlyView;
    ...
}
```

Now create a new helper function named *CreateDataView()* and call this method within the form's default constructor immediately after the *DataTable* has been fully constructed, as shown here:

```
public MainForm()
{
    ...
    // Make a data table.
    CreateDataTable();

    // Make a view.
    CreateDataView();
}
```

Here is the implementation of this new helper function. Notice that the constructor of each *DataView* has been passed the *DataTable* that you will use to build the custom set of data rows:

```
private void CreateDataView()
{
    // Set the table that is used to construct this view.
    yugosOnlyView = new DataView(inventoryTable);

    // Now configure the views using a filter.
    yugosOnlyView.RowFilter = "Make = 'Yugo'";

    // Bind to the new grid.
    dataGridYugosView.DataSource = yugosOnlyView;
}
```

As you can see, the `DataView` class supports a property named `RowFilter`, which contains the string representing the filtering criteria used to extract matching rows. Once you establish your view, set the grid's `DataSource` property accordingly. Figure 22-10 shows the completed Windows Forms data-binding application in action.



Figure 22-10. Displaying a unique view of your data

■ **Source Code** You can find the `WindowsFormsDataBinding` project under the Chapter 22 subdirectory.

Working with Data Adapters

Now that you understand the ins-and-outs of manipulating ADO.NET `DataSets` manually, it's time to turn your attention to the topic of *data adapter objects*. A data adapter is a class used to fill a `DataSet` with `DataTable` objects; this class can also send modified `DataTable`s back to the database for processing. Table 22-8 documents the core members of the `DbDataAdapter` base class, the common parent to every data adapter object (e.g., `SqlDataAdapter` and `OdbcDataAdapter`).

Table 22-8. Core Members of the *DbDataAdapter* Class

Members	Meaning in Life
Fill()	Executes a SQL SELECT command (as specified by the <i>SelectCommand</i> property) to query the database for data and loads the data into a <i>DataTable</i> .
SelectCommand InsertCommand UpdateCommand DeleteCommand	Establishes the SQL commands that you will issue to the data store when the <i>Fill()</i> and <i>Update()</i> methods are called.
Update()	Executes SQL INSERT, UPDATE, and DELETE commands (as specified by the <i>InsertCommand</i> , <i>UpdateCommand</i> , and <i>DeleteCommand</i> properties) to persist <i>DataTable</i> changes to the database.

Notice that a data adapter defines four properties: *SelectCommand*, *InsertCommand*, *UpdateCommand*, and *DeleteCommand*. When you create the data adapter object for your particular data provider (e.g., *SqlDataAdapter*), you can pass in a string that represents the command text used by the *SelectCommand*'s command object.

Assuming each of the four command objects has been properly configured, you can then call the *Fill()* method to obtain a *DataSet* (or a single *DataTable*, if you wish). To do so, you have the data adapter execute the SQL SELECT statement specified by the *SelectCommand* property.

Similarly, if you wish to persist a modified *DataSet* (or *DataTable*) object back to the database, you can call the *Update()* method, which will use any of the remaining command objects, based on the state of each row in the *DataTable* (you'll learn more about this in a bit).

One of the strangest aspects of working with a data adapter object is the fact that you are never required to open or close a connection to the database. Rather, the underlying connection to the database is managed on your behalf. However, you will still need to supply the data adapter with a valid connection object or a connection string (which you will use to build a connection object internally) to inform the data adapter exactly which database you wish to communicate with.

■ **Note** A data adapter is agnostic by nature. You can plug in different connection objects and command objects on the fly and fetch data from a diverse variety of databases. For example, a single *DataSet* could contain table data obtained from SQL server, Oracle, and MySQL database providers.

A Simple Data Adapter Example

The next step is to add new functionality to the data access library assembly (*AutoLotDAL.dll*) you created in Chapter 21. Begin by creating a simple example that fills a *DataSet* with a single table using an ADO.NET data adapter object.

Create a new Console Application named *FillDataSetUsingSqlDataAdapter* and import the *System.Data* and *System.Data.SqlClient* namespaces into your initial C# code file. Now update your

`Main()` method as follows (you might need to change the connection string, based on how you created the AutoLot database in the previous chapter):

```
static void Main(string[] args)
{
    Console.WriteLine("***** Fun with Data Adapters *****\n");

    // Hard-coded connection string.
    string cnStr = "Integrated Security = SSPI;Initial Catalog=AutoLot;" +
        @"Data Source=(local)\SQLEXPRESS";

    // Caller creates the DataSet object.
    DataSet ds = new DataSet("AutoLot");

    // Inform adapter of the Select command text and connection string.
    SqlDataAdapter dAdapt =
        new SqlDataAdapter("Select * From Inventory", cnStr);

    // Fill our DataSet with a new table, named Inventory.
    dAdapt.Fill(ds, "Inventory");

    // Display contents of DataSet.
    PrintDataSet(ds);
    Console.ReadLine();
}
```

Notice that you construct the data adapter by specifying a string literal that will map to the SQL `Select` statement. You will use this value to build a command object internally, which you can obtain later using the `SelectCommand` property.

Next, notice that it is the job of the caller to create an instance of the `DataSet` type, which is passed into the `Fill()` method. Optionally, you can pass the `Fill()` method as a second argument a string name that you use to set the `TableName` property of the new `DataTable` (if you do not specify a table name, the data adapter will simply name the table, `Table`). In most cases, the name you assign a `DataTable` will be identical to the name of the physical table in the relational database; however, this is not required.

■ **Note** The `Fill()` method returns an integer that represents the number of rows returned by the SQL query.

Finally, notice that you do not explicitly open or close the connection to the database anywhere in the `Main()` method. You preprogram the `Fill()` method of a given data adapter to open and then close the underlying connection before returning from the `Fill()` method. Therefore, when you pass the `DataSet` to the `PrintDataSet()` method (implemented earlier in this chapter), you are operating on a local copy of disconnected data, incurring no round-trips to fetch the data.

Mapping Database Names to Friendly Names

As mentioned previously, database administrators tend to create table and column names that are less than friendly to end users (e.g., au_id, au_fname, and au_lname). The good news is that data adapter objects maintain an internal strongly typed collection (named `DataTableMappingCollection`) of `System.Data.Common.DataTableMapping` objects. You can access this collection using the `TableMappings` property of your data adapter object.

If you so choose, you can manipulate this collection to inform a `DataTable` which *display names* it should use when asked to print its contents. For example, assume that you wish to map the table name `Inventory` to `Current_Inventory` for display purposes. For example, assume you wish to display the `CarID` column name as `Car_ID` (note the extra space) and the `PetName` column name as `Name_of_Car`. To do so, add the following code before calling the `Fill()` method of your data adapter object (be sure to import the `System.Data.Common` namespace to gain the definition of the `DataTableMapping` type):

```
static void Main(string[] args)
{
...
    // Now map DB column names to user-friendly names.
    DataTableMapping custMap =
        dAdapt.TableMappings.Add("Inventory", "Current Inventory");
    custMap.ColumnMappings.Add("CarID", "Car ID");
    custMap.ColumnMappings.Add("PetName", "Name of Car");
    dAdapt.Fill(ds, "Inventory");
...
}
```

If you were to run this program again, you would find that the `PrintDataSet()` method now displays the friendly names of the `DataTable` and `DataRow` objects, rather than the names established by the database schema:

***** Fun with Data Adapters *****

```
DataSet is named: AutoLot

=> Current Inventory Table:
Car ID  Make  Color  Name of Car
-----
83      Ford   Rust   Rusty
107     Ford   Red    Snake
678     Yugo   Green  Clunker
904     VW     Black  Hank
1000    BMW    Black  Bimmer
1001    BMW    Tan    Daisy
1992    Saab   Pink   Pinkey
2003    Yugo   Rust   Mel
```

■ **Source Code** You can find the `FillDataSetUsingSqlDataAdapter` project under the Chapter 22 subdirectory.

Adding Disconnection Functionality to AutoLotDAL.dll

To illustrate the process of using a data adapter to push changes in a `DataTable` back to the database for processing, you will now update the `AutoLotDAL.dll` assembly created back in Chapter 21 to include a new namespace (named `AutoLotDisconnectedLayer`). This namespace contains a new class, `InventoryDALDisLayer`, that uses a data adapter to interact with a `DataTable`.

A good way to begin is by copying the entire `AutoLot` project folder you created in Chapter 21 to a new location on your hard drive and rename this folder to `AutoLot (Version Two)`. Now use Visual Studio 2010 to activate the `File ▶ Open Project/Solution...` menu option, and then open the `AutoLotDAL.sln` file in your `AutoLot (Version Two)` folder.

Defining the Initial Class Type

Insert a new class named `InventoryDALDisLayer` using the `Project ▶ Add Class` menu option. Next, ensure you have a public class type in your new code file. Change the name of the namespace wrapping this class to `AutoLotDisconnectedLayer` and import the `System.Data` and `System.Data.SqlClient` namespaces.

Unlike the connection-centric `InventoryDAL` type, this new class doesn't need to provide custom open/close methods because the data adapter handles the details automatically.

Begin by adding a custom constructor that sets a private `string` variable representing the connection string. Also, define a private `SqlDataAdapter` member variable, which you configure by calling a (yet to be created) helper method called `ConfigureAdapter()`, which takes a `SqlDataAdapter` output parameter:

```
namespace AutoLotDisconnectedLayer
{
    public class InventoryDALDisLayer
    {
        // Field data.
        private string cnString = string.Empty;
        private SqlDataAdapter dAdapt = null;

        public InventoryDALDisLayer(string connectionString)
        {
            cnString = connectionString;

            // Configure the SqlDataAdapter.
            ConfigureAdapter(out dAdapt);
        }
    }
}
```

Configuring the Data Adapter Using the SqlCommandBuilder

When you use a data adapter to modify tables in a `DataSet`, the first order of business is to assign the `UpdateCommand`, `DeleteCommand`, and `InsertCommand` properties with valid command objects (until you do so, these properties return null references).

Configuring the command objects manually for the `InsertCommand`, `UpdateCommand`, and `DeleteCommand` properties can entail a significant amount of code, especially if you use parameterized queries. Recall from Chapter 21 that a parameterized query allows you to build a SQL statement using a set of parameter objects. Thus, if you were to take the long road, you could implement `ConfigureAdapter()` to create three new `SqlCommand` objects manually, each of which contains a set of `SqlParameter` objects. At this point, you could set each object to the `UpdateCommand`, `DeleteCommand`, and `InsertCommand` properties of the adapter.

Visual Studio 2010 provides several designer tools to take care of this mundane and tedious code on your behalf. These designers differ a bit based on which API you use (e.g., Windows Forms, WPF, or ASP.NET), but their overall functionality is similar. You'll see examples of using these designers throughout this book, including some Windows Forms designers later in this chapter.

You won't need to author the numerous code statements to configure a data adapter fully at this time; instead, you can take a massive shortcut by implementing `ConfigureAdapter()` like this:

```
private void ConfigureAdapter(out SqlDataAdapter dAdapt)
{
    // Create the adapter and set up the SelectCommand.
    dAdapt = new SqlDataAdapter("Select * From Inventory", cnString);

    // Obtain the remaining command objects dynamically at runtime
    // using the SqlCommandBuilder.
    SqlCommandBuilder builder = new SqlCommandBuilder(dAdapt);
}
```

To simplify the construction of data adapter objects, each of the Microsoft-supplied ADO.NET data providers provides a *command builder* type. The `SqlCommandBuilder` automatically generates the values contained within the `SqlDataAdapter`'s `InsertCommand`, `UpdateCommand`, and `DeleteCommand` properties, based on the initial `SelectCommand`. The benefit here is that you do not need to build all the `SqlCommand` and `SqlParameter` types by hand.

Here's an obvious question at this point: how is a command builder able to build these SQL command objects on the fly? The short answer is metadata. When you call the `Update()` method of a data adapter at runtime, the related command builder will read the database's schema data to autogenerate the underlying insert, delete, and update command objects.

Obviously, doing so requires additional roundtrips to the remote database; this means it will hurt performance if you use the `SqlCommandBuilder` numerous times in a single application. Here, you minimize the negative effect by calling your `ConfigureAdapter()` method at the time the `InventoryDALDisLayer` object is constructed, retaining the configured `SqlDataAdapter` for use throughout the object's lifetime.

In the previous code snippet, you did not use the command builder object (`SqlCommandBuilder`, in this case) beyond passing in the data adapter object as a constructor parameter. As odd as this might seem, this is all you must do (at a minimum). Under the hood, this type configures the data adapter with the remaining command objects.

While you might love the idea of getting something for nothing, you should understand that command builders come with some critical restrictions. Specifically, a command builder is only able to autogenerate SQL commands for use by a data adapter if all of the following conditions are true:

- The SQL Select command interacts with only a single table (e.g., no joins).
- The single table has been attributed with a primary key.
- The table must have a column or columns representing the primary key that you include in your SQL Select statement.

Based on the way you constructed your AutoLot database, these restrictions pose no problem. However, in a more industrial-strength database, you will need to consider whether this type is at all useful (if not, remember that Visual Studio 2010 will autogenerate a good deal of the required code using various database designer tools, as you will see later).

Implementing GetAllInventory()

Now that your data adapter is ready to go, the first method of your new class type will use the `Fill()` method of the `SqlDataAdapter` object to fetch a `DataTable` representing all records in the `Inventory` table of the `AutoLot` database:

```
public DataTable GetAllInventory()
{
    DataTable inv = new DataTable("Inventory");
    dAdapt.Fill(inv);
    return inv;
}
```

Implementing UpdateInventory()

The `UpdateInventory()` method is simple:

```
public void UpdateInventory(DataTable modifiedTable)
{
    dAdapt.Update(modifiedTable);
}
```

Here, the data adapter object examines the `RowState` value of each row of the incoming `DataTable`. Based on this value (e.g., `RowState.Added`, `RowState.Deleted`, or `RowState.Modified`), the correct command object is leveraged behind the scenes.

Setting Your Version Number

Great! At this point, the logic of the second version of your data access library is complete. You are not required to do so, but set the version number of this library to 2.0.0.0, just for good housekeeping. As described in Chapter 14, you can change the version of a .NET assembly by double-clicking the Properties node of your Solution Explorer, and then clicking the Assembly Information... button located in the Application tab. In the resulting dialog box, set the Major number of the Assembly Version to the value of 2 (see Chapter 14 for more details). Once you do this, recompile your application to update the assembly manifest.

■ **Source Code** You can find the AutoLotDAL (Version 2) project under the Chapter 22 subdirectory.

Testing the Disconnected Functionality

At this point, you can build a front end to test your new `InventoryDALDisLayer` class. Once again, you will use the Windows Forms API to display your data on a graphical user interface. Create a new Windows Forms application named `InventoryDALDisconnectedGUI` and change your initial `Form1.cs` file to `MainForm.cs` using the Solution Explorer. Once you create the project, set a reference to your updated `AutoLotDAL.dll` assembly (be sure you pick version 2.0.0.0!) and import the following namespace:

```
using AutoLotDisconnectedLayer;
```

The design of the form consists of a single Label, `DataGridView` (named `inventoryGrid`), and Button control (named `btnUpdateInventory`), which you configure to handle the `Click` event. Here is the definition of the form:

```
public partial class MainForm : Form
{
    InventoryDALDisLayer dal = null;

    public MainForm()
    {
        InitializeComponent();

        string cnStr =
            @"Data Source=(local)\SQLEXPRESS;Initial Catalog=AutoLot;" +
            "Integrated Security=True;Pooling=False";

        // Create our data access object.
        dal = new InventoryDALDisLayer(cnStr);

        // Fill up our grid!
        inventoryGrid.DataSource = dal.GetAllInventory();
    }

    private void btnUpdateInventory_Click(object sender, EventArgs e)
    {
        // Get modified data from the grid.
        DataTable changedDT = (DataTable)inventoryGrid.DataSource;

        try
        {
            // Commit our changes.
            dal.UpdateInventory(changedDT);
        }
        catch(Exception ex)
        {
```

```
        MessageBox.Show(ex.Message);  
    }  
}
```

Once you create the `InventoryDAL` object, you can bind the `DataTable` returned from `GetAllInventory()` to the `DataGridView` object. When the user clicks the `Update` button, you extract the modified `DataTable` from the grid (with the `DataSource` property) and pass it into your `UpdateInventory()` method.

That's it! After you run this application, add a set of new rows to the grid and update/delete a few others. Assuming you click the **Button** control, you will see your changes have persisted into the AutoLot database.

■ **Source Code** You can find the updated InventoryDALDisconnectedGUI project under the Chapter 22 subdirectory.

Multitabled DataSet Objects and Data Relationships

So far, all of this chapter's examples have operated on a single `DataTable` object. However, the power of the disconnected layer shines through when a `DataSet` object contains numerous interrelated `DataTable`s. In this case, you can define any number of `DataRelation` objects in the `DataSet`'s `DataRelation` collection to account for the interdependencies of the tables. The client tier can use these objects to navigate between the table data without incurring network roundtrips.

Note Rather than updating AutoLotDAL.dll to account for the Customers and Orders tables, this example isolates all of the data access logic within a new Windows Forms project. However, intermixing UI and data logic in a production-level application is not recommended. The final examples of this chapter leverage various database design tools to decouple the UI logic from the data logic code.

Begin this example by creating a new Windows Forms application named MultitabledDataSetApp. The GUI is simple enough. In Figure 22-11, you can see three DataGridView widgets (`dataGridViewInventory`, `dataGridViewCustomers`, and `dataGridViewOrders`) that hold the data retrieved from the `Inventory`, `Orders`, and `Customers` tables of the AutoLot database. In addition, the initial Button (named `btnUpdateDatabase`) submits any and all changes entered within the grids back to the database for processing using data adapter objects.




Figure 22-11. The initial UI will display data from each table of the AutoLot database

Prepping the Data Adapters

To keep the data access code as simple as possible, the `MainForm` will make use of command builder objects to autogenerate the SQL commands for each of the three `SqlDataAdapter`s (one for each table). Here is the initial update to the `Form`-derived type (don't forget to import the `System.Data.SqlClient` namespace):

```
public partial class MainForm : Form
{
    // Form wide DataSet.
    private DataSet autoLotDS = new DataSet("AutoLot");

    // Make use of command builders to simplify data adapter configuration.
    private SqlCommandBuilder sqlCBInventory;
    private SqlCommandBuilder sqlCBCustomers;
    private SqlCommandBuilder sqlCBOOrders;

    // Our data adapters (for each table).
    private SqlDataAdapter invTableAdapter;
    private SqlDataAdapter custTableAdapter;
    private SqlDataAdapter ordersTableAdapter;

    // Form wide connection string.
    private string cnStr = string.Empty;
    ...
}
```

The constructor does the grunt work of creating your data-centric member variables and filling the DataSet. This example assumes you have authored an App.config file that contains the correct connection string data (and that you have referenced System.Configuration.dll and imported the System.Configuration namespace), as in this example:

```
<configuration>
  <connectionStrings>
    <add name="AutoLotSqlProvider" connectionString =
      "Data Source=(local)\SQLEXPRESS;
       Integrated Security=SSPI;Initial Catalog=AutoLot"
    />
  </connectionStrings>
</configuration>
```

Also note that you include a call to a private helper function, BuildTableRelationship():

```
public MainForm()
{
  InitializeComponent();

  // Get connection string from *.config file.
  cnStr =
    ConfigurationManager.ConnectionStrings[
      "AutoLotSqlProvider"].ConnectionString;

  // Create adapters.
  invTableAdapter = new SqlDataAdapter("Select * from Inventory", cnStr);
  custTableAdapter = new SqlDataAdapter("Select * from Customers", cnStr);
  ordersTableAdapter = new SqlDataAdapter("Select * from Orders", cnStr);

  // Autogenerate commands.
  sqlCBIventory = new SqlCommandBuilder(invTableAdapter);
  sqlCBOders = new SqlCommandBuilder(ordersTableAdapter);
  sqlCBCustomers = new SqlCommandBuilder(custTableAdapter);

  // Fill tables in DS.
  invTableAdapter.Fill(autoLotDS, "Inventory");
  custTableAdapter.Fill(autoLotDS, "Customers");
  ordersTableAdapter.Fill(autoLotDS, "Orders");

  // Build relations between tables.
  BuildTableRelationship();

  // Bind to grids
  dataGridViewInventory.DataSource = autoLotDS.Tables["Inventory"];
  dataGridViewCustomers.DataSource = autoLotDS.Tables["Customers"];
  dataGridViewOrders.DataSource = autoLotDS.Tables["Orders"];
}
```

Building the Table Relationships

The `BuildTableRelationship()` helper function does the grunt work to add two `DataRelation` objects into the `autoLotDS` object. Recall from Chapter 21 that the AutoLot database expresses a number of parent/child relationships, which you can account for with the following code:

```
private void BuildTableRelationship()
{
    // Create CustomerOrder data relation object.
    DataRelation dr = new DataRelation("CustomerOrder",
        autoLotDS.Tables["Customers"].Columns["CustID"],
        autoLotDS.Tables["Orders"].Columns["CustID"]);
    autoLotDS.Relations.Add(dr);

    // Create InventoryOrder data relation object.
    dr = new DataRelation("InventoryOrder",
        autoLotDS.Tables["Inventory"].Columns["CarID"],
        autoLotDS.Tables["Orders"].Columns["CarID"]);
    autoLotDS.Relations.Add(dr);
}
```

Note that you establish a friendly string moniker with the first parameter when you create a `DataRelation` object (you'll see the usefulness of doing so in just a minute). You also establish the keys used to build the relationship itself. Notice that the parent table (the second constructor parameter) is specified before the child table (the third constructor parameter).

Updating the Database Tables

Now that the `DataSet` has been filled with data from the data source, you can manipulate each `DataTable` locally. To do so, run the application and insert, update, or delete values from any of the three `DataGridViews`. When you are ready to submit the data back for processing, click the `Update` button. You should find it easy to follow along with the code behind the related `Click` event at this point:

```
private void btnUpdateDatabase_Click(object sender, EventArgs e)
{
    try
    {
        invTableAdapter.Update(autoLotDS, "Inventory");
        custTableAdapter.Update(autoLotDS, "Customers");
        ordersTableAdapter.Update(autoLotDS, "Orders");
    }
    catch (Exception ex)
    {
        MessageBox.Show(ex.Message);
    }
}
```

Now run your application and perform various updates. When you rerun the application, you should find that your grids are populated with the recent changes.

Navigating Between Related Tables

Now let's look at how a `DataRelation` allows you to move between related tables programmatically. Extend your UI to include a new Button (named `btnGetOrderInfo`), a related TextBox (named `txtCustID`), and a descriptive Label (you can group these controls within a `GroupBox` for more visual appeal). Figure 22-12 shows one possible UI of the application.



Figure 22-12. The updated UI allows the user to look up customer order information

This updated UI lets the user enter the ID of a customer and retrieve all the relevant information about that customer's order (e.g., name, order ID, and car order). This information will be formatted into a string type that is eventually displayed within a message box. Consider the code behind the new Button's Click event handler:

```
private void btnGetOrderInfo_Click(object sender, System.EventArgs e)
{
    string strOrderInfo = string.Empty;
    DataRow[] drsCust = null;
    DataRow[] drsOrder = null;

    // Get the customer ID in the text box.
    int custID = int.Parse(this.txtCustID.Text);

    // Now based on custID, get the correct row in Customers table.
    drsCust = autoLotDS.Tables["Customers"].Select(
        string.Format("CustID = {0}", custID));
    strOrderInfo += string.Format("Customer {0}: {1} {2}\n",
        drsCust[0]["CustID"].ToString(),
        drsCust[0]["FirstName"].ToString(),
        drsCust[0]["LastName"].ToString());
```

```

// Navigate from Customers table to Orders table.
drsOrder = drsCust[0].GetChildRows(autoLotDS.Relations["CustomerOrder"]);

// Loop through all orders for this customer.
foreach (DataRow order in drsOrder)
{
    strOrderInfo += string.Format("----\nOrder Number:
{0}\n", order["OrderID"]);

    // Get the car referenced by this order.
    DataRow[] drsInv = order.GetParentRows(autoLotDS.Relations[
    "InventoryOrder"]);

    // Get info for (SINGLE) car info for this order.
    DataRow car = drsInv[0];
    strOrderInfo += string.Format("Make: {0}\n", car["Make"]);
    strOrderInfo += string.Format("Color: {0}\n", car["Color"]);
    strOrderInfo += string.Format("Pet Name: {0}\n", car["PetName"]);
}

MessageBox.Show(strOrderInfo, "Order Details");
}

```

Figure 22-13 shows one possible output when specifying a customer ID with the value of 3 (this is Steve Hagen in my copy of the AutoLot database, who currently has two orders pending).




Figure 22-13. Navigating data relations

This last example should probably convince you of the usefulness of the `DataSet` class. Given that a `DataSet` is completely disconnected from the underlying data source, you can work with an in-memory copy of data and navigate around each table to make any necessary updates, deletes, or inserts without incurring any roundtrips to the database. Once you finish this, you can submit your changes to the data store for processing. The end result is a scalable and robust application.

■ **Source Code** You can find the `MultitabledDataSetApp` project under the Chapter 22 subdirectory.

The Windows Forms Database Designer Tools

All of the examples thus far have involved a fair amount of elbow grease in the sense that you had to author all data access logic by hand. While you did offload a good amount of this code to a .NET code library (`AutoLotDAL.dll`) for reuse in later chapters of the book, you still had to create the various objects of your data provider manually before interacting with the relational database. The next task in this chapter is to look at how you use various Windows Forms database designer tools, which can produce a good deal of data access code on your behalf.

■ **Note** Windows Presentation Foundation and ASP.NET web projects have similar database designer tools; you'll look at some of these later in this chapter.

One way you can use these integrated tools is to use the designers supported by the Windows Forms `DataGridView` control. The problem with this approach is that the database designer tools will embed all of the data access code directly into your GUI code base! Ideally, you want to isolate all of this designer generated code in a dedicated .NET code library, so you can easily reuse your database access logic across multiple projects.

Nevertheless, it might be helpful to begin with an examination of how you can use the `DataGridView` control to generate the required data access code, given that this approach does have some usefulness in small-scale projects and application prototypes. Next, you will learn how to isolate the same designer generated code into a third version of `AutoLot.dll`.

Visually Designing the `DataGridView`

The `DataGridView` control has an associated wizard that can generate data access code on your behalf. Begin by creating a brand-new Windows Forms application project named `DataGridViewDesigner`. Rename the initial form to `MainForm.cs` using the Solution Explorer, and then add an instance of the `DataGridView` control (named `inventoryDataGridView`) to your initial form. Note that an inline editor opens to the right-hand side of the control when you do this. From the Choose Data Source drop-down box, select the Add Project Data Source link (see Figure 22-14).




Figure 22-14. The DataGridView editor

This launches the Data Source Configuration Wizard. This tool guides you through a series of steps that allow you to select and configure a data source, which you can then bind to the DataGridView. The first step of the wizard asks you to identify the type of data source you wish to interact with. Select Database (see Figure 22-15) and click the Next button.




Figure 22-15. Selecting the type of data source

The next step (which will differ slightly based on your selection in step 1) asks whether you wish to use the DataSet database model or the Entity data model. Be sure you pick the DataSet database model (see Figure 22-16) because you have not yet looked at the Entity Framework (you'll learn more about this in the next chapter).




Figure 22-16. Choosing the database model

The next step allows you to configure your database connection. If you have a database currently added to Server Explorer, you should find it listed automatically in the dropdown list. If this is not the case (or if you ever need to connect to a database you have not previously added to Server Explorer), click the New Connection button. Figure 22-17 shows the result of selecting the local instance of AutoLot (notice that this tool will also generate the required connection string).




Figure 22-17. Choosing the database

In the wizard's final step, you select the database objects that will be accounted for by the autogenerated DataSet and related data adapters. While you could select each of the data objects of the AutoLot database, here you concern yourself only with the Inventory table. Given this, change the suggested name of the DataSet to InventoryDataSet (see Figure 22-18), check the Inventory table, and click the Finish button.




Figure 22-18. Selecting the Inventory table

Once you do this, you will see that the visual designer has been updated in many ways. The most noticeable change is the fact that the DataGridView displays the schema of the Inventory table, as illustrated by the column headers. Also, you will see three components on the bottom of the form designer (in a region dubbed the *component tray*): a DataSet component, a BindingSource component, and a TableAdapter component (see Figure 22-19).




Figure 22-19. Your Windows Forms project, after running the Data Source Configuration Wizard

At this point, you can run your application, and lo and behold, the grid is filled with the records of the Inventory table! Of course, there is no magic to speak of in this case. The IDE has authored a good amount of code on your behalf and set up the grid control to use it. Let's dig into some of this autogenerated code.

The Generated app.config File

If you examine your Solution Explorer, you will find your project now contains an `app.config` file that contains a `<connectionStrings>` element that has been given a somewhat peculiar name:

```
<?xml version="1.0" encoding="utf-8" ?>
<configuration>
  <configSections>
  </configSections>
  <connectionStrings>
    <add name="DataGridViewDesigner.Properties.Settings.AutoLotConnectionString"
        connectionString=
          "Data Source=(local)\SQLEXPRESS;
           Initial Catalog=AutoLot;Integrated Security=True"
        providerName="System.Data.SqlClient" />
  </connectionStrings>
</configuration>
```

The autogenerated data adapter object (which you will learn more about momentarily) uses the lengthy value, `"DataGridViewDesigner.Properties.Settings.AutoLotConnectionString"`.

Examining the Strongly Typed DataSet

In addition to your configuration file, the IDE generates what is termed a *strongly typed DataSet*. This term describes a custom class that extends `DataSet` and exposes a number of members that allow you to interact with the database using a more intuitive object model. For example, strongly typed `DataSet` objects contain properties that map directly to the database tables names. Thus, you can use the `Inventory` property to nab the rows and columns directly, rather than having to drill into the collection of tables using the `Tables` property.

If you insert a new class diagram file into your project (by selecting the project icon in Solution Explorer and clicking the View Class Diagram button), you'll notice that the wizard has created a class named `InventoryDataSet`. This class defines a handful of members, the most important of which is a property named `Inventory` (see Figure 22-20).




Figure 22-20. The Data Source Configuration Wizard created a strongly typed DataSet

If you double-click the `InventoryDataSet.xsd` file within Solution Explorer, you will load the Visual Studio 2010 Dataset Designer (you'll learn more details about this designer momentarily). If you right-click anywhere within this designer and select the View Code option, you will notice a fairly empty partial class definition:

```
public partial class InventoryDataSet { }
```

If necessary, you can add custom members to this partial class definition; however, the real action takes place within the designer-maintained file, `InventoryDataSet.Designer.cs`. If you open this file using Solution Explorer, you will see that `InventoryDataSet` extends the `DataSet` parent class. Consider the following partial code, with comments added for clarity:

```
// This is all designer-generated code!
public partial class InventoryDataSet : global::System.Data.DataSet
{
    // A member variable of type InventoryDataTable.
    private InventoryDataTable tableInventory;

    // Each constructor calls a helper method named InitClass().
    public InventoryDataSet()
    {
        ...
        this.InitClass();
    }

    // InitClass() preps the DataSet and adds the InventoryDataTable
    // to the Tables collection.
    private void InitClass()
    {
        this.DataSetName = "InventoryDataSet";
        this.Prefix = "";
        this.Namespace = "http://tempuri.org/InventoryDataSet.xsd";
        this.EnforceConstraints = true;
        this.SchemaSerializationMode =
```

```

global::System.Data.SchemaSerializationMode.IncludeSchema;
this.tableInventory = new InventoryDataTable();
base.Tables.Add(this.tableInventory);
}

// The read-only Inventory property returns
// the InventoryDataTable member variable.
public InventoryDataTable Inventory
{
    get { return this.tableInventory; }
}
}

```

Notice that your strongly typed DataSet has a member variable that is a *strongly typed DataTable*; in this case, the class is named `InventoryDataTable`. The constructor of the strongly typed DataSet class makes a call to a private initialization method named `InitClass()`, which adds an instance of this strongly typed `DataTable` to the `Tables` collection of the `DataSet`. Last but not least, notice that the implementation of the `Inventory` property returns the `InventoryDataTable` member variable.

Examining the Strongly Typed DataTable

Now return to the class diagram file and open up the Nested Types node on the `InventoryDataSet` icon. Here you will see the strongly typed `DataTable` class named `InventoryDataTable` and a *strongly typed* `DataRow` class named `InventoryRow`.

The `InventoryDataTable` class (which is the same type as the member variable of the strongly typed `DataSet` you examined) defines a set of properties that are based on the column names of the physical `Inventory` table (`CarIDColumn`, `ColorColumn`, `MakeColumn`, and `PetNameColumn`), as well as a custom indexer and a `Count` property to obtain the current number of records.

More interestingly, this strongly typed `DataTable` class defines a set of methods that allow you to insert, locate, and delete rows within the table using strongly typed members (an attractive alternative to navigating the `Rows` and `Columns` indexers manually). For example, `AddInventoryRow()` lets you add a new record row to the table in memory, `FindByCarID()` lets you do a look up based on the primary key of the table, and `RemoveInventoryRow()` lets you remove a row from the strongly typed table (see Figure 22-21).




Figure 22-21. The strongly typed DataTable is nested in the strongly typed DataSet

Examining the Strongly Typed DataRow

The strongly typed DataRow class, which is also nested in the strongly typed DataSet, extends the DataRow class and exposes properties that map directly to the schema of the Inventory table. Also, the data designer tool has created a method (`IsPetNameNull()`) that will perform a check on whether this column has a value (see Figure 22-22).




Figure 22-22. The strongly typed `DataRow`

Examining the Strongly Typed Data Adapter

Strong typing for your disconnected types is a solid benefit of using the Data Source Configuration Wizard, given that creating these classes by hand would be tedious (but entirely possible). This same wizard was kind enough to generate a custom data adapter object that can fill and update the `InventoryDataSet` and `InventoryDataTable` objects in a strongly typed manner. Locate the `InventoryTableAdapter` on the visual class designer and examine the generated members in Figure 22-23.




Figure 22-23. A customized data adapter that operates on the strongly typed `DataSet` and `DataTable`

The autogenerated `InventoryTableAdapter` type maintains a collection of `SqlCommand` objects (which you can access using the `CommandCollection` property), each of which has a fully populated set of `SqlParameter` objects. Furthermore, this custom data adapter provides a set of properties to extract the underlying connection, transaction, and data adapter objects, as well as a property to obtain an array representing each command type.

Completing the Windows Forms Application

If you examine the `Load` event handler of the form-derived type (in other words, if you view the code for `MainForm.cs` and locate the `MainForm_Load()` method) you will find that the `Fill()` method of the custom table adapter is called upon startup, passing in the custom `DataTable` maintained by the custom `DataSet`:

```
private void MainForm_Load(object sender, EventArgs e)
{
    this.inventoryTableAdapter.Fill(this.inventoryDataSet.Inventory);
}
```

You can use this same custom data adapter object to update changes to the grid. Update the UI of your form with a single `Button` control (named `btnUpdateInventory`). Next, handle the `Click` event and author the following code within the event handler:

```
private void btnUpdateInventory_Click(object sender, EventArgs e)
{
    try
    {
        // Save changes with the Inventory table back to the database.
        this.inventoryTableAdapter.Update(this.inventoryDataSet.Inventory);
    }
    catch(Exception ex)
    {
        MessageBox.Show(ex.Message);
    }

    // Get fresh copy for grid.
    this.inventoryTableAdapter.Fill(this.inventoryDataSet.Inventory);
}
```

Run your application again; add, delete, or update the records displayed in the grid; and click the `Update` button. When you run the program again, you will find your changes are present and accounted for.

Great! This example shows how helpful the `DataGridView` control designer can be. It lets you work with strongly typed data generates a majority of the necessary database logic on your behalf. The obvious problem is that this code is tightly connected to the window that uses it. Ideally, this sort of code belongs in your `AutoLotDAL.dll` assembly (or some other data access library). However, you might wonder how to harvest the code generated using the `DataGridView`'s associated wizard in a Class Library project, given that there is no form designer by default.

■ **Source Code** You can find the DataGridViewDataDesigner project under the Chapter 22 subdirectory.

Isolating Strongly Typed Database Code into a Class Library

Fortunately, you can activate the data design tools of Visual Studio 2010 from any sort of project (UI-based or otherwise) without the need to copy-and-paste massive amounts of code between projects. You can see this in action by adding more functionality to AutoLot.dll.

This time, try copying the entire AutoLot (Version two) project folder you created earlier in this chapter to a new location on your hard drive and rename this folder to AutoLot (Version Three). Next, activate the Visual Studio 2010 File ▶ Open Project/Solution... menu option, and open the AutoLotDAL.sln file in your new AutoLot (Version Three) folder.

Now, insert a new strongly typed DataSet class (named AutoLotDataSet.xsd) into your new project using the Project ▶ Add New Item menu option (see Figure 22-24).




Figure 22-24. Inserting a new strongly typed DataSet

This opens a blank Dataset Designer surface. At this point, you can use the Server Explorer to connect to a given database (you should already have a connection to AutoLot), and drag-and-drop each table and stored procedure you wish to generate onto the surface. In Figure 22-25, you can see each of the custom aspects of AutoLot are accounted for, and their relationships are realized automatically (this example does not drag over the CreditRisk table).




Figure 22-25. Your custom strongly typed types, this time within a Class Library project

Viewing the Generated Code

The DataSet designer created the exact same sort of code that the DataGridView wizard did in the previous Windows Forms example. However, this time you account for the Inventory, Customers, and Orders tables, as well as the GetPetName stored procedure, so you have many more generated classes. Basically, each database table you drag onto the designer surface gives you a strongly typed DataSet, DataTable, DataRow, and data adapter class.

The strongly typed DataSet, DataTable, and DataRow classes will be placed into the root namespace of the project (AutoLot). The custom table adapters will be placed within a nested namespace. You can view all of the generated types most easily by using the Class View tool, which you open from the Visual Studio View menu (see Figure 22-26).




Figure 22-26. The autogenerated strongly typed data of the AutoLot database

For the sake of completion, you might want use the Visual Studio 2010 Properties editor (see Chapter 14 for details) to set the version of this latest incarnation of AutoLot.dll to 3.0.0.0.

■ **Source Code** You can find the AutoLotDAL (Version 3) project under the Chapter 22 subdirectory.

Selecting Data with the Generated Code

At this point, you can use your strongly typed data within any .NET application that needs to communicate with the AutoLot database. To make sure you understand the basic mechanics, create a Console application named `StronglyTypedDataSetConsoleClient`. Next, add a reference to your latest-and-greatest version of AutoLot.dll and import the `AutoLotDAL` and the `AutoLotDAL.AutoLotDataSetTableAdapters` namespace into your initial C# code file.

Here is a `Main()` method that uses the `InventoryTableAdapter` object to retrieve all data in the `Inventory` table. Notice that you do not need to specify a connection string because that information is now part of the strongly typed object model. Once you fill the table, you print out the results using a

helper method named `PrintInventory()`. Note that you can manipulate the strongly typed `DataTable` just as you do a “normal” `DataTable` using the `Rows` and `Columns` collections:

```
class Program
{
    static void Main(string[] args)
    {
        Console.WriteLine("***** Fun with Strongly Typed DataSets *****\n");

        AutoLotDataSet.InventoryDataTable table =
            new AutoLotDataSet.InventoryDataTable();

        InventoryTableAdapter dAdapt = new InventoryTableAdapter();
        dAdapt.Fill(table);

        PrintInventory(table);
        Console.ReadLine();
    }

    static void PrintInventory(AutoLotDataSet.InventoryDataTable dt)
    {
        // Print out the column names.
        for (int curCol = 0; curCol < dt.Columns.Count; curCol++)
        {
            Console.Write(dt.Columns[curCol].ColumnName + "\t");
        }
        Console.WriteLine("\n-----");

        // Print the data.
        for (int curRow = 0; curRow < dt.Rows.Count; curRow++)
        {
            for (int curCol = 0; curCol < dt.Columns.Count; curCol++)
            {
                Console.Write(dt.Rows[curRow][curCol].ToString() + "\t");
            }
            Console.WriteLine();
        }
    }
}
```

Inserting Data with the Generated Code

Now assume you want to insert new records using this strongly typed object model. The following helper function adds two new rows to the current `InventoryDataTable`, then updates the database using the data adapter. You add the first row manually by configuring a strongly typed `DataRow`; you add the second row by passing in the needed column data, which allows the `DataRow` to be created in the background automatically:

```
public static void AddRecords(AutoLotDataSet.InventoryDataTable tb,
    InventoryTableAdapter dAdapt)
{
```

```

// Get a new strongly typed row from the table.
AutoLotDataSet.InventoryRow newRow = tb.NewInventoryRow();

// Fill row with some sample data.
newRow.CarID = 999;
newRow.Color = "Purple";
newRow.Make = "BMW";
newRow.PetName = "Saku";

// Insert the new row.
tb.AddInventoryRow(newRow);

// Add one more row, using overloaded Add method.
tb.AddInventoryRow(888, "Yugo", "Green", "Zippy");

// Update database.
dAdapt.Update(tb);
}

```

The Main() method can invoke this method; doing so updates the database table with these new records:

```

static void Main(string[] args)
{
...
// Add rows, update and reprint.
AddRecords(table, dAdapt);
table.Clear();
dAdapt.Fill(table);
PrintInventory(table);
Console.ReadLine();
}

```

Deleting Data with the Generated Code

Deleting records with this strongly typed object model is also simple. The autogenerated FindByXXXX() method (where XXXX is the name of the primary key column) of the strongly typed DataTable returns the correct (strongly typed) DataRow using the primary key. Here is another helper method that deletes the two records you just created:

```

private static void RemoveRecords(AutoLotDataSet.InventoryDataTable tb,
    InventoryTableAdapter dAdapt)
{
    AutoLotDataSet.InventoryRow rowToDelete = tb.FindByCarID(999);
    dAdapt.Delete(rowToDelete.CarID, rowToDelete.Make,
        rowToDelete.Color, rowToDelete.PetName);
    rowToDelete = tb.FindByCarID(888);
    dAdapt.Delete(rowToDelete.CarID, rowToDelete.Make,
        rowToDelete.Color, rowToDelete.PetName);
}

```

If you call this from your `Main()` method and reprint the table, you should find these two test records are no longer displayed.

Note If you run this app twice and call the `AddRecord()` method each time, you get a VIOLATION CONSTRAINT ERROR because the `AddRecord()` method tries to insert the same `CarID` primary key value each time. If you wish to make this example more flexible, you can gather data from the user.

Invoking a Stored Procedure using the Generated Code

Let's look at one more example of using the strongly typed object model. In this case, you create a final method that invokes the `GetPetName` stored procedure. When the data adapters for the AutoLot database were created, there was a special class created named `QueriesTableAdapter`, which as the name implies, encapsulates the process of invoking stored procedures in the relational database. This final helper function displays the name of the specified car when called from `Main()`:

```
public static void CallStoredProcedure()
{
    QueriesTableAdapter q = new QueriesTableAdapter();
    Console.Write("Enter ID of car to look up: ");
    string carID = Console.ReadLine();
    string carName = "";
    q.GetPetName(int.Parse(carID), ref carName);
    Console.WriteLine("CarID {0} has the name of {1}", carID, carName);
}
```

At this point, you know how to use strongly typed database types, and package them up into a dedicated class library. You can find more aspects of this object model to play around with, but you should be in a perfect position to dig deeper if that interests you. To wrap things up for this chapter, you will learn how to apply LINQ queries to an ADO.NET `DataSet` object.

Source Code You can find the `StronglyTypedDataSetConsoleClient` project under the Chapter 22 subdirectory.

Programming with LINQ to DataSet

You have seen in this chapter that you can manipulate the data within a `DataSet` in three distinct manners:

- By using the `Tables`, `Rows`, and `Columns` collections
- By using data table readers
- By using strongly typed data classes

When you use the various indexers of the `DataSet` and `DataTable` type, you can interact with the contained data in a straightforward but loosely typed manner. Recall that this approach requires you to treat the data as a tabular block of cells, as in this example:

```
static void PrintDataWithIdxers(DataTable dt)
{
    // Print the DataTable.
    for (int curRow = 0; curRow < dt.Rows.Count; curRow++)
    {
        for (int curCol = 0; curCol < dt.Columns.Count; curCol++)
        {
            Console.Write(dt.Rows[curRow][curCol].ToString() + "\t");
        }
        Console.WriteLine();
    }
}
```

The `CreateDataReader()` method of the `DataTable` type offers a second approach, where you can treat the data in the `DataSet` as a linear set of rows to be processed in a sequential manner. This allows you to apply a connected data reader programming model to a disconnected `DataSet`:

```
static void PrintDataWithDataTableReader(DataTable dt)
{
    // Get the DataTableReader type.
    DataTableReader dtReader = dt.CreateDataReader();
    while (dtReader.Read())
    {
        for (int i = 0; i < dtReader.FieldCount; i++)
        {
            Console.Write("{0}\t", dtReader.GetValue(i));
        }
        Console.WriteLine();
    }
    dtReader.Close();
}
```

Finally, you can use a strongly typed `DataSet` to yield a code base that allows you to interact with data in the object using properties that map to the column names in the relational database. Using strongly typed objects allows you to author code such as the following:

```
static void AddRowWithTypedDataSet()
{
    InventoryTableAdapter invDA = new InventoryTableAdapter();
    AutoLotDataSet.InventoryDataTable inv = invDA.GetData();
    inv.AddInventoryRow(999, "Ford", "Yellow", "Sal");
    invDA.Update(inv);
}
```

While all of these approaches have their place, the LINQ to DataSet API provides yet another option to manipulate DataSet data using LINQ query expressions.

■ **Note** You only use the LINQ to DataSet to apply LINQ queries to DataSet objects returned by a data adapter, but this has nothing to do with applying LINQ queries directly to the database engine itself. Chapter 23 will introduce you to LINQ to Entities and the ADO.NET Entity Framework, which provide a way to represent SQL queries as LINQ queries.

Out of the box, the ADO.NET DataSet (and related types such as DataTable and DataView) do not have the necessary infrastructure to be a direct target for a LINQ query. For example, the following method (which uses types in the AutoLotDisconnectedLayer namespace) results in a compile-time error:

```
static void LinqOverDataTable()
{
    // Get a DataTable of data.
    InventoryDALDisLayer dal = new InventoryDALDisLayer(
        @"Data Source=(local)\SQLEXPRESS;" +
        "Initial Catalog=AutoLot;Integrated Security=True");
    DataTable data = dal.GetAllInventory();

    // Apply a LINQ query to the DataSet?
    var moreData = from c in data where (int)c["CarID"] > 5 select c;
}
```

If you were to compile the `LinqOverDataTable()` method, the compiler would inform you that the `DataTable` type provides a *query pattern implementation*. Similar to the process of applying LINQ queries to objects that do not implement `IEnumerable<T>`, ADO.NET objects must be transformed into a compatible type. To understand how to do so requires examining the types of `System.Data.DataSetExtensions.dll`.

The Role of the DataSet Extensions Library

The `System.Data.DataSetExtensions.dll` assembly, which is referenced by default in all Visual Studio 2010 projects, augments the `System.Data` namespace with a handful of new types (see Figure 22-27).




Figure 22-27. The `System.Data.DataSetExtensions.dll` assembly

The two most useful types by far are `DataTableExtensions` and `DataRowExtensions`. These classes extend the functionality of `DataTable` and `DataRow` by using a set of extension methods (see Chapter 12). The other key class is `TypedTableBaseExtensions`, which defines extension methods that you can apply to strongly typed `DataSet` objects to make the internal `DataTable` objects LINQ aware. All of the remaining members within the `System.Data.DataSetExtensions.dll` assembly are pure infrastructure, and they are not intended to be used directly in your code base.

Obtaining a LINQ-Compatible `DataTable`

Now let's look at how you use the `DataSet` extensions. Assume you have a new C# Console Application named `LinqToDataSetApp`. Add a reference to the latest and greatest version (3.0.0.0) of the `AutoLotDAL.dll` assembly and update your initial code file with the following logic:

```
using System;
using System.Data;

// Location of strongly typed data containers.
using AutoLotDAL;

// Location of strongly typed data adapters.
using AutoLotDAL.AutoLotDataSetTableAdapters;

namespace LinqToDataSetApp
{
    class Program
    {
        static void Main(string[] args)
        {
            Console.WriteLine("***** LINQ over DataSet *****\n");

            // Get a strongly typed DataTable containing the current Inventory
            // of the AutoLot database.
        }
    }
}
```

```

AutoLotDataSet dal = new AutoLotDataSet();
InventoryTableAdapter da = new InventoryTableAdapter();
AutoLotDataSet.InventoryDataTable data = da.GetData();

// Invoke the methods that follow here!

Console.ReadLine();
}
}
}

```

When you wish to transform an ADO.NET DataTable (including a strongly typed DataTable) into a LINQ-compatible object, you must call the `AsEnumerable()` extension method defined by the `DataTableExtensions` type. This returns an `EnumerableRowCollection` object that contains a collection of `DataRow`s.

You can then use the `EnumerableRowCollection` type to operate on each row using basic `DataRow` syntax (e.g., indexer syntax). Consider the following new method of your `Program` class, which takes a strongly typed `DataTable`, obtains an enumerable copy of the data, and prints out each `CarID` value:

```

static void PrintAllCarIDs(DataTable data)
{
    // Get enumerable version of DataTable.
    EnumerableRowCollection enumData = data.AsEnumerable();

    // Print the car ID values.
    foreach (DataRow r in enumData)
        Console.WriteLine("Car ID = {0}", r["CarID"]);
}

```

At this point, you have not applied a LINQ query; however, the point here is that the `enumData` object can now be the target of a LINQ query expression. Again, notice that the `EnumerableRowCollection` contains a collection of `DataRow` objects because you are applying a type indexer against each sub-object to print out the value of the `CarID` column.

In most cases, you do not need to declare a variable of type `EnumerableRowCollection` to hold the return value of `AsEnumerable()`. Rather, you can invoke this method from within the query expression itself. Here is a more interesting method of the `Program` class, which obtains a projection of `CarID + Makes` from all entries in the `DataTable` where the color is red (if you don't have any red autos in your `Inventory` table, you update this LINQ query as necessary):

```

static void ShowRedCars(DataTable data)
{
    // Project a new result set containing
    // the ID/color for rows where Color = Red.
    var cars = from car in data.AsEnumerable()
               where
                   (string)car["Color"] == "Red"
               select new
               {
                   ID = (int)car["CarID"],
                   Make = (string)car["Make"]
               };
}

```

```

Console.WriteLine("Here are the red cars we have in stock:");
foreach (var item in cars)
{
    Console.WriteLine("-> CarID = {0} is {1}", item.ID, item.Make);
}

```

The Role of the `DataRowExtensions.Field<T>()` Extension Method

One undesirable aspect of the current LINQ query expression is that you use numerous casting operations and `DataRow` indexers to gather the result set, which could result in runtime exceptions if you attempt to cast to an incompatible data type. To inject some strong typing into your query, you can use the `Field<T>()` extension method of the `DataRow` type. Doing so lets you increase the type safety of your query because the compatibility of data types is checked at compile time. Consider the following update:

```

var cars = from car in data.AsEnumerable()
    where
        car.Field<string>("Color") == "Red"
    select new
    {
        ID = car.Field<int>("CarID"),
        Make = car.Field<string>("Make")
    };

```

In this case, you can invoke `Field<T>()` and specify a type parameter to represent the underlying data type of the column. As an argument to this method, you pass in the column name itself. Given the additional compile-time checking, you should consider it a best practice to use `Field<T>()` (rather than the `DataRow` indexer) when you process the roles of a `EnumerableRowCollection`.

Beyond the fact that you call the `AsEnumerable()` method, the overall format of the LINQ query is identical to what you have already seen in Chapter 13. Given this, there is no reason to repeat the details of the various LINQ operators here. If you wish to see additional examples, you can look up the topic “LINQ to DataSet Examples” in the .NET Framework 4.0 SDK documentation.

Hydrating New `DataTable`s from LINQ Queries

It is also possible to populate the data of a new `DataTable` easily, based on the results of a LINQ query and provided that you are *not* using projections. When you have a result set where the underlying type can be represented as `IEnumerable<T>`, you can call the `CopyToDataTable<T>()` extension method on the result, as in this example:

```

static void BuildDataTableFromQuery(DataTable data)
{
    var cars = from car in data.AsEnumerable()
        where
            car.Field<int>("CarID") > 5
        select car;

    // Use this result set to build a new DataTable.
    DataTable newTable = cars.CopyToDataTable();
}

```

```
// Print the DataTable.
for (int curRow = 0; curRow < newTable.Rows.Count; curRow++)
{
    for (int curCol = 0; curCol < newTable.Columns.Count; curCol++)
    {
        Console.WriteLine(newTable.Rows[curRow][curCol].ToString().Trim() + "\t");
    }
    Console.WriteLine();
}
```

Note It is also possible to transform a LINQ query to a `DataView` type by using the `AsDataView<T>()` extension method.

You might find this technique helpful when you wish to use the result of a LINQ query as the source of a data binding operation. Recall that the `DataGridView` of Windows Forms (as well as an ASP.NET or WPF grid control) supports a property named `DataSource`. You could bind a LINQ result to the grid as follows:

```
// Assume myDataGrid is a GUI-based grid object.
myDataGrid.DataSource = (from car in data.AsEnumerable()
    where
        car.Field<int>("CarID") > 5
    select car).CopyToDataTable();
```

This wraps up the examination of the disconnected layer of ADO.NET. Using this aspect of the API, you can fetch data from a relational database, muck on the data, and return it for processing while keeping the database connection open for the shortest possible amount of time.

Source Code You can find the `LinqOverDataSet` example under the Chapter 22 subdirectory.

Summary

This chapter dove into the details of the disconnected layer of ADO.NET. As you have seen, the centerpiece of the disconnected layer is the `DataSet`. This type is an in-memory representation of any number of tables and any number of optional interrelationships, constraints, and expressions. The beauty of establishing relations on your local tables is that you can programmatically navigate between them while disconnected from the remote data store.

You also examined the role of the data adapter type in this chapter. Using this type (and the related `SelectCommand`, `InsertCommand`, `UpdateCommand`, and `DeleteCommand` properties), the adapter can resolve changes in the `DataSet` with the original data store. You also learned how to navigate the object model of

a `DataSet` using the brute-force manual approach, as well as with strongly typed objects, which the `Dataset` Designer tools of Visual Studio 2010 typically generate.

You wrapped up by looking at one aspect of the LINQ technology set named LINQ to `DataSet`. This allows you to obtain a queryable copy of the `DataSet`, which can receive well formatted LINQ queries.



ADO.NET Part III: The Entity Framework

The previous two chapters examined the fundamental ADO.NET programming models—the connected and disconnected layers, specifically. These approaches have enabled .NET programmers to work with relational data (in a relatively straightforward manner) since the initial release of the platform. However, Microsoft introduced a brand new component of the ADO.NET API called the *Entity Framework* (or simply, *EF*) in .NET 3.5 Service Pack 1.

The overarching goal of EF is to allow you to interact with relational databases using an object model that maps directly to the business objects in your application. For example, rather than treating a batch of data as a collection of rows and columns, you can operate on a collection of strongly typed objects termed *entities*. These entities are also natively LINQ aware, and you can query against them using the same LINQ grammar you learned about in Chapter 13. The EF runtime engine translates your LINQ queries into proper SQL queries on your behalf.

This chapter will introduce you to the EF programming model. You will learn about various bits of infrastructure, including object services, entity client, LINQ to Entities, and Entity SQL. You will also learn about the format of the all-important *.edmx file and its role in the Entity Framework API. Next, you will learn how to generate *.edmx files using Visual Studio 2010 and at the command line using the EDM generator utility (edmgenc.exe).

By the time you complete this chapter, you will have the final version of AutoLotDAL.dll, and you will learn how to bind entity objects to a Windows Forms desktop application.

Understanding the Role of Entity Framework

The connected and disconnected layers of ADO.NET provide you with a fabric that lets you select, insert, update, and delete data with connections, commands, data readers, data adapters, and *DataSet* objects. While this is all well and good, these aspects of ADO.NET force you to treat the fetched data in a manner that is tightly coupled to the physical database schema. Recall for example, that when you use the connected layer, you typically iterate over each record by specifying column names to a data reader. On the other hand, if you opt to use the disconnected layer, you find yourself traversing the *rows* and *columns* collections of a *DataTable* object within a *DataSet* container.

If you use the disconnected layer in conjunction with strongly typed *DataSets*/data adapters, you end up with a programming abstraction that provides some helpful benefits. First, the strongly typed *DataSet* class exposes table data using class properties. Second, the strongly typed table adapter supports methods that encapsulate the construction of the underlying SQL statements. Recall the *AddRecords()* method from Chapter 22:

```

public static void AddRecords(AutoLotDataSet.InventoryDataTable tb,
                             InventoryTableAdapter dAdapt)
{
    // Get a new strongly typed row from the table.
    AutoLotDataSet.InventoryRow newRow = tb.NewInventoryRow();

    // Fill row with some sample data.
    newRow.CarID = 999;
    newRow.Color = "Purple";
    newRow.Make = "BMW";
    newRow.PetName = "Saku";

    // Insert the new row.
    tb.AddInventoryRow(newRow);

    // Add one more row, using overloaded Add method.
    tb.AddInventoryRow(888, "Yugo", "Green", "Zippy");

    // Update database.
    dAdapt.Update(tb);
}

```

Things get even better if you combine the disconnected layer with LINQ to DataSet. In this case, you can apply LINQ queries to your in-memory data to obtain a new result set, which you can then optionally map to a standalone object such as a new DataTable, a List<T>, Dictionary<K,V>, or array of data, as follows:

```

static void BuildDataTableFromQuery(DataTable data)
{
    var cars = from car in data.AsEnumerable()
               where car.Field<int>"CarID" > 5 select car;

    // Use this result set to build a new DataTable.
    DataTable newTable = cars.CopyToDataTable();

    // Work with DataTable...
}

```

LINQ to DataSet is useful; however, you need to remember that the target of your LINQ query is the *data returned from the database*, not the database engine itself. Ideally, you could build a LINQ query that you send directly to the database engine for processing, and get back some strongly typed data in return (which is exactly what the ADO.NET Entity Framework lets you accomplish).

When you use either the connected or disconnected layer of ADO.NET, you must always be mindful of the physical structure of the back-end database. You must know the schema of each data table, author complex SQL queries to interact with said table data, and so forth. This can force you to author some fairly verbose C# code because as C# itself does not speak the language of database schema directly.

To make matters worse, the way in which a physical database is constructed (by your friendly DBA) is squarely focused on database constructs such as foreign keys, views, and stored procedures. The databases constructed by your friendly DBA can grow quite complex as the DBA endeavors to account for security and scalability. This also complicates the sort of C# code you must author in order to interact with the data store.

The ADO.NET Entity Framework (EF) is a programming model that attempts to lessen the gap between database constructs and object-oriented programming constructs. Using EF, you can interact with a relational database without ever seeing a line of SQL code (if you so choose). Rather, when you apply LINQ queries to your strongly typed classes, the EF runtime generates proper SQL statements on your behalf.

■ **Note** *LINQ to Entities* is the term that describes the act of applying LINQ queries to ADO.NET EF entity objects.

Another possible approach: Rather than updating database data by finding a row, updating the row, and sending the row back for processing with a batch of SQL queries, you can simply change properties on an object and save its state. Again, the EF runtime updates the database automatically.

As far as Microsoft is concerned, the ADO.NET Entity Framework is a new member of the data access family, and it is not intended to replace the connected or disconnected layers. However, once you spend some time working with EF, you might quickly find yourself preferring this rich object model over the more primitive world of SQL queries and row/column collections.

Nevertheless, chances are you will find uses for all three approaches in your .NET projects; in some cases, the EF model might complicate your code base. For example, if you want to build an in-house application that needs to communicate only with a single database table, you might prefer to use the connected layer to hit a batch of related stored procedures. Larger applications can particularly benefit from EF, especially if the development team is comfortable working with LINQ. As with any new technology, you will need to determine how (and when) ADO.NET EF is appropriate for the task at hand.

■ **Note** You might recall a database programming API introduced with .NET 3.5 called LINQ to SQL. This API is close in concept (and fairly close in terms of programming constructs) to ADO.NET EF. While LINQ to SQL is not formally dead, the official word from those kind folks in Redmond is that you should put your efforts into EF, not LINQ to SQL.

The Role of Entities

The strongly typed classes mentioned previously are called *entities*. Entities are a conceptual model of a physical database that maps to your business domain. Formally speaking, this model is termed *an Entity Data Model (EDM)*. The EDM is a client-side set of classes that map to a physical database, but you should understand that the entities need not map directly to the database schema in so far as naming conventions go. You are free to restructure your entity classes to fit your needs, and the EF runtime will map your unique names to the correct database schema.

For example, you might recall that you created the simple `Inventory` table in the `AutoLot` database using the database schema shown in Figure 23-1.




Figure 23-1. Structure of the *Inventory* table of the *AutoLot* database

If you were to generate an EDM for the *Inventory* table of the *AutoLot* database (you'll see how to do so momentarily), the entity will be called *Inventory* by default. However, you could rename this class to *Car* and define uniquely named properties of your choosing, which will be mapped to the columns of the *Inventory* table. This loose coupling means that you can shape the entities so they closely model your business domain. Figure 23-2 shows such an entity class.




Figure 23-2. The *Car* entity is a client-side reshaping of the *Inventory* schema

■ **Note** In many cases, the client-side entity class will be identically named to the related database table. However, remember that you can always reshape the entity to match your business situation.

Now, consider the following *Program* class, which uses the *Car* entity class (and a related class named *AutoLotEntities*) to add a new row to the *Inventory* table of *AutoLot*. This class is termed an *object context*; the job of this class is to communicate with the physical database on your behalf (you will learn more details soon):

```
class Program
{
    static void Main(string[] args)
    {
        // Connection string automatically read from
        // generated config file.
        using (AutoLotEntities context = new AutoLotEntities())
        {
```

```

// Add a new record to Inventory table, using our entity.
context.Cars.AddObject(new Car() { AutoIDNumber = 987, CarColor = "Black",
                                    MakeOfCar = "Pinto",
                                    NicknameOfCar = "Pete" });
context.SaveChanges();
}
}
}

```

It is up to the EF runtime to take the client-side representation of the `Inventory` table (here, a class named `Car`) and map it back to the correct columns of the `Inventory` table. Notice that you see no trace of any sort of SQL `INSERT` statement; you simply add a new `Car` object to the collection maintained by the aptly named `Cars` property of the context object and save your changes. Sure enough, if you view the table data using the Server Explorer of Visual Studio 2010, you will see a brand new record (see Figure 23-3).

	CarlID	Make	Color	PetName
	83	Ford	Rust	Rusty
	107	Ford	Red	Snake
	555	VW	Purple	Grape
	678	Yugo	Green	Clunker
	904	VW	Black	Hank
▶	987	Pinto	Black	Pete
	999	BMW	Red	FooFoo
	1000	BMW	Black	Bimmer

Figure 23-3. The result of saving the context

There is no magic in the preceding example. Under the covers, a connection to the database is made, a proper SQL statement is generated, and so forth. The benefit of EF is that these details are handled on your behalf. Now let's look at the core services of EF that make this possible.

The Building Blocks of the Entity Framework

The EF API sits on top of the existing ADO.NET infrastructure you have already examined in the previous two chapters. Like any ADO.NET interaction, the entity framework uses an ADO.NET data provider to communicate with the data store. However, the data provider must be updated so it supports a new set of services before it can interact with the EF API. As you might expect, the Microsoft SQL Server data provider has been updated with the necessary infrastructure, which is accounted for when using the `System.Data.Entity.dll` assembly.

■ **Note** Many third party databases (e.g., Oracle and MySQL) provide EF-aware data providers. Consult your database vendor for details or log onto www.sqlsummit.com/dataprov.htm for a list of known ADO.NET data providers.

In addition to adding the necessary bits to the Microsoft SQL Server data provider, the `System.Data.Entity.dll` assembly contains various namespaces that account for the EF services themselves. The two key pieces of the EF API to concentrate on for the time being are *object services* and *entity client*.

The Role of Object Services

Object services is the name given to the part of EF that manages the client-side entities as you work with them in code. For example, object services track the changes you make to an entity (e.g., changing the color of a car from green to blue), manage relationships between the entities (e.g., looking up all orders for a customer named Steve Hagen), and provide ways to save your changes to the database, as well as ways to persist the state of an entity with XML and binary serialization services.

Programmatically speaking, the object services layer micromanages any class that extends the `EntityObject` base class. As you might suspect, `EntityObject` is in the inheritance chain for all entity classes in the EF programming model. For example, if you look at the inheritance chain of the `Car` entity class used in the previous example, you see that `Car Is-A EntityObject` (see Figure 23-4).




Figure 23-4. EF's object service layer can manage any class that extends `EntityObject`

The Role of the Entity Client

Another major aspect of the EF API is the entity client layer. This part of the EF API is in charge of working with the underlying ADO.NET data provider to make connections to the database, generate the necessary SQL statements based on the state of your entities and LINQ queries, map fetched database

data into the correct shape of your entities, and manage other details you would normally perform by hand if you were not using the Entity Framework.

You can find the functionality of the entity client layer in the `System.Data.EntityClient` namespace. This namespace includes a set of classes that map EF concepts (such as LINQ to Entity queries) to the underlying ADO.NET data provider. These classes (e.g., `EntityCommand` and `EntityConnection`) are eerily similar to the classes you find in an ADO.NET data provider; for example, Figure 23-5 illustrates how the classes of the entity client layer extend the same abstract base classes of any other provider (e.g., `DbCommand` and `DbConnection`; you can also see Chapter 22 for more details on this subject).




Figure 23-5. The entity client layer maps entity commands to the underlying ADO.NET data provider

The entity client layer typically works behind the scenes, but it is entirely possible to work directly with an entity client if you require full control over how it performs its duties (most notably, how it generates the SQL queries and handles the returned database data).

If you require greater control over how the entity client builds a SQL statement based on the incoming LINQ query, you can use *Entity SQL*. Entity SQL is a database-independent dialect of SQL that works directly with entities. Once you build an entity SQL query, it can be sent directly to entity client services (or if you wish, to object services), where it will be formatted into a proper SQL statement for the underlying data provider. You will not work with Entity SQL to any significant extent in this chapter, but you will see a few examples of this new SQL-based grammar later in the chapter.

If you require greater control over how a fetched result set is manipulated, you can forego the automatic mapping of database results to entity objects and manually process the records using the `EntityDataReader` class. Unsurprisingly, the `EntityDataReader` allows you to process fetched data using a forward only, read only stream of data, just as `SqlDataReader` does. You will see a working example of this approach later in the chapter.

The Role of the *.edmx File (and Friends)

Recapping the story thus far, entities are client-side classes, which function as an Entity Data Model. While the client side entities will eventually be mapped to the correct database table, there is no tight coupling between the property names of your entity classes and the column names on the data table.

For the Entity Framework API to map entity class data to database table data correctly, you need a proper definition of the mapping logic. In any data model-driven system, the entities, the real database, and the mapping layers are separated into three related parts: a *conceptual model*, a *logical model*, and a *physical model*.

- The conceptual model defines the entities and their relationships (if any).
- The logical model maps the entities and relationships into tables with any required foreign key constraints.
- The physical model represents the capabilities of a particular data engine by specifying storage details, such table schema, partitioning, and indexing.

In the world of EF, each of these three layers is captured in an XML-based file format. When you use the integrated Entity Framework designers of Visual Studio 2010, you end up with a file that takes an *.edmx file extension (remember, EDM = entity data model). This file includes XML descriptions of the entities, the physical database, and instructions on how to map this information between the conceptual and physical models. You will examine the format of the *.edmx file in the first example of this chapter (which you will see in a moment).

When you compile your EF-based projects using Visual Studio 2010, the *.edmx file is used to generate three standalone XML files: one for the conceptual model data (*.csdl), one for the physical model (*.ssdl), and one for the mapping layer (*.msl). The data of these three XML-based files is then bundled into your application in the form of binary resources. Once compiled, your .NET assembly has all the necessary data for the EF API calls you make in your code base.

The Role of the ObjectContext and ObjectSet<T> Classes

The final part of the EF puzzle is the `ObjectContext` class, which is a member of the `System.Data.Objects` namespace. When you generate your *.edmx file, you get the entity classes that map to the database tables and a class that extends `ObjectContext`. You typically use this class to interact with object services and entity client functionality indirectly.

`ObjectContext` provides a number of core services to child classes, including the ability to save all changes (which results in a database update), tweak the connection string, delete objects, call stored procedures, and handle other fundamental details. Table 23-1 describes some of the core members of the `ObjectContext` class (be aware that a majority of these members stay in memory until you call `SaveChanges()`).

Table 23-1. Common Members of ObjectContext

Member of ObjectContext	Meaning in Life
AcceptAllChanges()	Accepts all changes made to entity objects within the object context.
AddObject()	Adds an object to the object context.
DeleteObject()	Marks an object for deletion.
ExecuteFunction<T>()	Executes a stored procedure in the database.
ExecuteStoreCommand()	Allows you to send a SQL command to the data store directly.
GetObjectByKey()	Locates an object within the object context by its key.
SaveChanges()	Sends all updates to the data store.
CommandTimeout	This property gets or sets the timeout value in seconds for all object context operations.
Connection	This property returns the connection string used by the current object context.
SavingChanges	This event fires when the object context saves changes to the data store.

The `ObjectContext` derived class serves as a container that manages entity objects, which are stored in a collection of type `ObjectSet<T>`. For example, if you generate an `*.edmx` file for the `Inventory` table of the `AutoLot` database, you end up with a class named (by default) `AutoLotEntities`. This class supports a property named `Inventories` (note the plural name) that encapsulates an `ObjectSet<Inventory>` data member. If you create an EDM for the `Orders` table of the `AutoLot` database, the `AutoLotEntities` class will define a second property named `Orders` that encapsulates an `ObjectSet<Order>` member variable. Table 23-2 defines some common members of `System.Data.Objects.ObjectSet<T>`.

Table 23-2. Common members of ObjectSet<T>

Member of ObjectSet<T>	Meaning in Life
AddObject()	Allows you to insert a new entity object into the collection.
CreateObject<T>()	Creates a new instance of the specified entity type.
DeleteObject	Marks an object for deletion.

Once you drill into the correct property of the object context, you can call any member of `ObjectSet<T>`. Consider again the sample code shown in the first few pages of this chapter:

```
using (AutoLotEntities context = new AutoLotEntities())
{
    // Add a new record to Inventory table, using our entity.
    context.Cars.AddObject(new Car() { AutoIDNumber = 987, CarColor = "Black",
                                      MakeOfCar = "Pinto",
                                      NicknameOfCar = "Pete" });

    context.SaveChanges();
}
```

Here, `AutoLotEntities` is-a `ObjectContext`. The `Cars` property gives you access to the `ObjectSet<Car>` variable. You use this reference to insert a new `Car` entity object and tell the `ObjectContext` to save all changes to the database.

`ObjectSet<T>` is typically the target of LINQ to Entity queries; as such, `ObjectSet<T>` supports the same extension methods you learned about in Chapter 13. Moreover, `ObjectSet<T>` gains a good deal of functionality from its direct parent class, `ObjectQuery<T>`, which is a class that represents a strongly typed LINQ (or Entity SQL) query.

All Together Now!

Before you build your first Entity Framework example, take a moment to ponder Figure 23-6, which shows you how the EF API is organized.




Figure 23-6. The major components of the ADO.NET Entity Framework

The moving parts illustrated by Figure 23-6 are not as complex as they might seem at first glance. For example, consider this common scenario. You author some C# code that applies a LINQ query to an entity you received from your context. This query is passed into object services, where it formats the LINQ command into a tree entity client can understand. In turn, the entity client formats this tree into a proper SQL statement for the underlying ADO.NET provider. The provider returns a data reader (e.g., a `DbDataReader` derived object) that client services use to stream data to object services using an `EntityDataReader`. What your C# code base gets back is an enumeration of entity data (`IEnumerable<T>`).

Here is another scenario to consider. Your C# code base wants more control over how client services constructs the eventual SQL statement to send to the database. Thus, you author some C# code using Entity SQL that can be passed directly to entity client or object services. The end result returns as an `IEnumerable<T>`.

In either of these scenarios, you must make the XML data of the `*.edmx` file known to client services; this enables it to understand how to map database atoms to entities. Finally, remember that the client (e.g., your C# code base) can also nab the results sent from entity client by using the `EntityDataReader` directly.

Building and Analyzing your First EDM

Now that you have a better understanding of what the ADO.NET Entity Framework is attempting to accomplish, as well as a high-level idea of how it all works, it's time to look at your first full example. To keep things simple for now, you will build an EDM that only allow access to the `Inventory` table of `AutoLot`. Once you understand the basics, you will build a new EDM that accounts for the entire `AutoLot` database, and then display your data in a graphical user interface.

Generating the `*.edmx` File

Begin by creating a new Console Application named `InventoryEDMConsoleApp`. When you wish to use the Entity Framework, your first step is to generate the necessary conceptual, logical, and physical model data defined by the `*.edmx` file. One way to do this is to use the .NET 4.0 SDK command line tool, `EdmGen.exe`. Open a Visual Studio 2010 Command Prompt and enter the following instruction:

```
EdmGen.exe -?
```

You should see a list of options that you can supply to the tool to generate the necessary files based on an existing database; you should also see options to generate a brand new database based on existing entity files! Table 23-3 documents some common options of `EdmGen.exe`.

Table 23-3. Common command-line flags of `EdmGen.exe`


EdmGen.exe Option	Meaning in Life
<code>/mode:FullGeneration</code>	Generate the <code>*.ssdl</code> , <code>*.msl</code> , <code>*.csdl</code> files and client entities from a specified database.
<code>/project:</code>	This is the base name to be used for the generated code and files. Typically, this is the name of the database you pull data from (it can use the short form, <code>/p:</code>).

Table 23-3. Common command-line flags of EdmGen.exe (continued)

EdmGen.exe Option	Meaning in Life
/connectionstring:	This is the connection string you use to interact with the database (it can use the short form, /c:).
/language:	Allows you to specify whether you wish to use C# or VB syntax for the generated code.
/pluralize	Automatically pluralize or singularize the entity set name, entity type name, and navigation property name using English language rules.

As of .NET 4.0, the EF programming model supports *domain first* programming, which allows you to create your entities (with typical object-oriented techniques) and use them to generate a brand new database. In this introductory look at ADO.NET EF, you will not use this model-first mentality, nor will you use EdmGen.exe to generate your client-side entity model. Instead, you will use the graphical EDM designers of Visual Studio 2010.

Now activate the Project ▶ Add New Item... menu option and insert a new ADO.NET Entity Data Model item (see Figure 23-7) named InventoryEDM.edmx.

**Figure 23-7.** Inserting a new ADO.NET EDM project item

Clicking the Add button launches the Entity Model Data Wizard. The wizard's first step allows you to select whether you wish to generate an EDM from an existing database or define an empty model (for model-first development). Select the Generate from database option and click the Next button (see Figure 23-8).




Figure 23-8. Generating an EDM from an existing database

You can select your database in the wizard's second step. If you already have a connection to a database within the Visual Studio 2010 Server Explorer, you will see it listed in the dropdown combo box. If this is not the case, you can click the New Connection button. Either way, pick your AutoLot database, and then make certain you save the connection string data in the (autogenerated) App.config file (Figure 23-9).




Figure 23-9. Selecting the database to generate the EDM from

Before you click the Next button, take a moment to examine the format of your connection string:

```
metadata=res://*/InventoryEDM.csdl|res://*/InventoryEDM.ssdl|res://*/InventoryEDM.msl;
provider=System.Data.SqlClient; provider connection string=
"Data Source=(local)\SQLEXPRESS;
Initial Catalog=AutoLot;Integrated Security=True;Pooling=False"
```

The point of interest here is the `metadata` flag, which you use to denote the names of the embedded XML resource data for your conceptual, physical, and mapping files (recall that the single `*.edmx` file will be broken into three separate files at compile time, and the data in these files takes the form of binary resources embedded in your assembly).

In the wizard's final step, you can select the items from the database you wish to use to generate the EDM. Again, you are only concerned with the `Inventory` table in this example (Figure 23-10).




Figure 23-10. Selecting the database items

Now, click the Finish button to generate your EDM data.

Reshaping the Entity Data

Once you complete the wizard, you will see the EDM designer open within the IDE, where you should see a single entity named *Inventory*. You can view the composition of any entity on the designer using the Entity Data Model Browser window (you open this using the View ▶ Other Windows menu option). Now look at the format of your conceptual model for the *Inventory* database table under the Entity Types folder (see Figure 23-11). You can see the physical model of the database under the Store node, where the name of your store will be based on the name of the database itself (AutoLotModel.Store, in this case).




Figure 23-11. The Entity designer and Model Browser window

By default, the names of your entities will be based on the original database object names; however, recall that the names of entities in your conceptual model can be anything you choose. You can change the entity name, as well as property names of the entity, by selecting an item on the designer and renaming it using the Name property in the Visual Studio 2010 Properties window. Next, rename the *Inventory* entity to *Car* and the *PetName* property to *CarNickname* (see Figure 23-12).




Figure 23-12. Reshaping entities using the Properties window

At this point, your conceptual model should look similar to what is shown in Figure 23-13.




Figure 23-13. The client side model, reshaped to match your business domain

Now select the entire Car entity on the designer and look at the Properties window again. You should see that the Entity Set Name field has also been renamed from Inventories to Cars (see Figure 23-14). The Entity Set value is important because this corresponds to the name of the property on the data context class, which you will use to modify the database. Recall that this property encapsulates an `ObjectSet<T>` member variable in the `ObjectContext` derived class.




Figure 23-14. The name of the `ObjectSet<T>` property wrapper

Before moving on, compile your application; doing so refreshes your code base and generates the *.csdl, *.msl, and *.ssdl files based on your *.edmx file data.

Viewing the Mappings

Now that you have reshaped the data, you can view the mappings between the conceptual layer and the physical layer using the Mapping Details window (you open this using the `View > Other Windows...` menu option). Next, look at Figure 23-15 and notice how the nodes on the left-hand side of the tree represent the data names in the physical layer, while the nodes on the right-hand side represent the names of your conceptual model.




Figure 23-15. The Mapping Details window shows the mappings of your conceptual and physical models

Viewing the Generated *.edmx File Data

Now, let's see exactly what the EDM Wizard generated for you. Right-click the `InventoryEDM.edmx` file in the Solution Explorer and select the Open With... menu option. From the resulting dialog box, pick the XML Editor option. This allows you to see the underlying XML data seen in the EDM designer. The structure of this XML document is broken down into four parts; you can find all of them in the `<edmx:Edmx>` root element.

The `<edmx:Runtime>` sub-elements define the XML data for your conceptual, physical, and mapping layer models. First, you have the definition of the physical `Inventory` database table:

```
<!-- SSDL content -->
<edmx:StorageModels>
  <Schema Namespace="AutoLotModel.Store" Alias="Self"
    Provider="System.Data.SqlClient"
    ProviderManifestToken="2008"
    xmlns:store=
    "http://schemas.microsoft.com/ado/2007/12/edm/EntityStoreSchemaGenerator"
    xmlns="http://schemas.microsoft.com/ado/2009/02/edm/ssdl">
    <EntityContainer Name="AutoLotModelStoreContainer">
      <EntityType Name="Inventory" EntityType="AutoLotModel.Store.Inventory"
        store:Type="Tables" Schema="dbo" />
    </EntityContainer>
    <EntityType Name="Inventory">
      <Key>
        <PropertyRef Name="CarID" />
      </Key>
      <Property Name="CarID" Type="int" Nullable="false" />
      <Property Name="Make" Type="varchar" Nullable="false" MaxLength="50" />
      <Property Name="Color" Type="varchar" Nullable="false" MaxLength="50" />
      <Property Name="PetName" Type="varchar" MaxLength="50" />
    </EntityType>
  </Schema>
</edmx:StorageModels>
```

Note that the `<Schema>` node defines the name of the ADO.NET data provider that will use this information when communicating with the database (`System.Data.SqlClient`). The `<EntityType>` node marks the name of the physical database table, as well as each column in the table.

The next major chunk of the *.edmx file is the `<edmx:ConceptualModels>` element, which defines the shaped client-side entities. Notice that the `Cars` entity defines the `CarNickname` property, which you change using the designer:

```
<!-- CSDL content -->
<edmx:ConceptualModels>
  <Schema Namespace="AutoLotModel" Alias="Self"
    xmlns:annotation="http://schemas.microsoft.com/ado/2009/02/edm/annotation"
    xmlns="http://schemas.microsoft.com/ado/2008/09/edm">
    <EntityContainer
      Name="AutoLotEntities" annotation:LazyLoadingEnabled="true">
      <EntitySet Name="Cars" EntityType="AutoLotModel.Car" />
    </EntityContainer>
    <EntityType Name="Car">
      <Key>
        <PropertyRef Name="CarID" />
      </Key>
      <Property Name="CarID" Type="Int32" Nullable="false" />
      <Property Name="Make" Type="String" Nullable="false" MaxLength="50"
        Unicode="false" FixedLength="false" />
      <Property Name="Color" Type="String" Nullable="false" MaxLength="50"
        Unicode="false" FixedLength="false" />
      <Property Name="CarNickname" Type="String" MaxLength="50"
        Unicode="false" FixedLength="false" />
    </EntityType>
  </Schema>
</edmx:ConceptualModels>
```

That brings you to the mapping layer, which the Mapping Details window (and the EF runtime) uses to connect names in the conceptual model to the physical model:

```
<!-- C-S mapping content -->
<edmx:Mappings>
  <Mapping Space="C-S"
    xmlns="http://schemas.microsoft.com/ado/2008/09/mapping/cs">
    <EntityContainerMapping StorageEntityContainer="AutoLotModel.StoreContainer"
      CdmEntityContainer="AutoLotEntities">
      <EntitySetMapping Name="Cars">
        <EntityTypeMapping TypeName="AutoLotModel.Car">
          <MappingFragment StoreEntitySet="Inventory">
            <ScalarProperty Name="CarID" ColumnName="CarID" />
            <ScalarProperty Name="Make" ColumnName="Make" />
            <ScalarProperty Name="Color" ColumnName="Color" />
            <ScalarProperty Name="CarNickname" ColumnName="PetName" />
          </MappingFragment></EntityTypeMapping>
        </EntitySetMapping>
      </EntityContainerMapping>
    </Mapping>
  </edmx:Mappings>
```

The last part of the *.edmx file is the <Designer> element, which is not used by the EF runtime. If you view this data, you will see it contains instructions used by Visual Studio to display your entities on the visual designer surface.

Again, ensure that you have compiled your project at least once and click the Show All Files button of the Solution Explorer. Next, begin by drilling into the obj\Debug folder; and then drill into the edmxResourcesToEmbed subdirectory. Here you will find three XML files that are based on the entirety of your *.edmx file (see Figure 23-16).




Figure 23-16. You use the *.edmx file to generate three separate XML files

The data in these files will be embedded as binary resources in your assembly. Thus, your .NET application has all the information it needs to understand the conceptual, physical, and mapping layers of the EDM.

Viewing the Generated Source Code

You are almost ready to author some code to use your EDM; before you do, however, you should check out the generated C# code base. Open the Class View window and expand your default namespace. You will see that, in addition to the Program class, the EDM Wizard generated an entity class (which you renamed to Car) and another class named AutoLotEntities.

If you go to the Solution Explorer and expand the InventoryEDM.edmx node, you will see an IDE-maintained file named InventoryEDM.Designer.cs. As with any IDE-maintained file, you should not directly edit this file because the IDE will recreate it each time you compile. However, you can open this file for viewing by double-clicking it.

The AutoLotEntities class extends the ObjectContext class, which (as you probably recall) is your entry point to the EF programming model. The constructors of AutoLotEntities provide various ways for you to feed in connection string data. The default constructor has been configured to read the connection string data automatically from the wizard-generated App.config file:

```
public partial class AutoLotEntities : ObjectContext
{
    public AutoLotEntities() : base("name=AutoLotEntities", "AutoLotEntities")
```

```

        this.ContextOptions.LazyLoadingEnabled = true;
        OnContextCreated();
    }
...
}

```

Next, notice that the `Cars` property of the `AutoLotEntities` class encapsulates the `ObjectSet<Car>` data member. You can use this property to work with the EDM model to modify the physical back-end database indirectly:

```

public partial class AutoLotEntities : ObjectContext
{
...
    public ObjectSet<Car> Cars
    {
        get
        {
            if (_Cars == null)
            {
                _Cars = base.CreateObjectSet<Car>("Cars");
            }
            return _Cars;
        }
    }
    private ObjectSet<Car> _Cars;
}

```

Note You will also see various methods in your `ObjectContext`-derived classes that begin with `AddTo`. While you can use them to add new entities to the `ObjectSet<T>` member variables, the preferred way to do this is with the `ObjectSet<T>` member obtained from the strongly typed properties.

The last item of interest in the designer code file is the `Car` entity class. The bulk of the code for each entity class is a collection of properties that model the shape of your conceptual model. Each of these properties implement its set logic using a call to the static `StructuralObject.SetValidValue()` method of the EF API.

Also, the set logic includes code that informs the EF runtime that the state of an entity has changed, which is important because the `ObjectContext` must know about these changes to push updates to the physical database.

In addition, the set logic makes calls on two partial methods. Recall that a C# partial method provides a simple way to deal with change notifications in your applications. If you don't implement a partial method, it is ignored by the compiler and stripped away. Here is the implementation of the `CarNickname` property of the `Car` entity class:

```

public partial class Car : EntityObject
{
...
}

```

```

public global::System.String CarNickname
{
    get
    {
        return _CarNickname;
    }
    set
    {
        OnCarNicknameChanging(value);
        ReportPropertyChanging("CarNickname");
        _CarNickname = StructuralObject.SetValidValue(value, true);
        ReportPropertyChanged("CarNickname");
        OnCarNicknameChanged();
    }
}
private global::System.String _CarNickname;
partial void OnCarNicknameChanging(global::System.String value);
partial void OnCarNicknameChanged();
}

```

Enhancing the Generated Source Code

All of the designer generated classes have been declared with the `partial` keyword, which as you recall allows you to implement a class across multiple C# code files. This is especially useful when working with the EF programming model because it means you can add “real” methods to your entity classes that help you model your business domain better.

In this example, you override the `ToString()` method of the `Car` entity class to return the state of the entity with a well formatted string. You also complete the definitions of the partial `OnCarNicknameChanging()` and `OnCarNicknameChanged()` methods to serve as simple diagnostic notifications. You define the following partial class declaration in a new `Car.cs` file:

```

public partial class Car
{
    public override string ToString()
    {
        // Since the PetName column could be empty, supply
        // the default name of **No Name**.
        return string.Format("{0} is a {1} {2} with ID {3}.",
            this.CarNickname ?? "**No Name**",
            this.Color, this.Make, this.CarID);
    }

    partial void OnCarNicknameChanging(global::System.String value)
    {
        Console.WriteLine("\t-> Changing name to: {0}", value);
    }
    partial void OnCarNicknameChanged()
    {
        Console.WriteLine("\t-> Name of car has been changed!");
    }
}

```

A friendly reminder: When you provide implementations to these partial methods, you can receive notifications if the properties of the *entity classes* have changed or are being changed, but not when the physical database has changed. If you need to know when the physical database has changed, you can handle the *SavingChanges* event on your *ObjectContext* derived class.

Programming Against the Conceptual Model

Now you can author some code that interacts with your EDM. Begin by updating your *Program* class to call a helper method from *Main()*, which will print out each item in the *Inventory* database using your conceptual model, and another which will insert a new record to the *Inventory* table:

```
class Program
{
    static void Main(string[] args)
    {
        Console.WriteLine("***** Fun with ADO.NET EF *****");
        AddNewRecord();
        PrintAllInventory();
        Console.ReadLine();
    }

    private static void AddNewRecord()
    {
        // Add record to the Inventory table of the AutoLot
        // database.
        using (AutoLotEntities context = new AutoLotEntities())
        {
            try
            {
                // Hard code data for a new record, for testing.
                context.Cars.AddObject(new Car() { CarID = 2222,
                    Make = "Yugo", Color = "Brown" });
                context.SaveChanges();
            }
            catch(Exception ex)
            {
                Console.WriteLine(ex.InnerException.Message);
            }
        }
    }

    private static void PrintAllInventory()
    {
        // Select all items from the Inventory table of AutoLot,
        // and print out the data using our custom ToString()
        // of the Car entity class.
        using (AutoLotEntities context = new AutoLotEntities())
        {
            foreach (Car c in context.Cars)
```

```
        }  
    }  
}
```

You have seen code similar to this earlier in the chapter, but now you should have a much better idea about how it works. Each helper method creates an instance of the `ObjectContext` derived class (`AutoLotEntities`), and uses the strongly typed `Cars` property to interact with the `ObjectSet<Car>` field. Enumerating each item exposed by the `Cars` property enables you to submit a SQL SELECT statement indirectly to the underlying ADO.NET data provider. By inserting a new `Car` object with the `AddObject()` method of `ObjectSet<Car>`, and then calling `SaveChanges()` on the context, you have performed a SQL INSERT.

Deleting a Record

When you wish to remove a record from the database, you will first need to locate the correct item in the `ObjectSet<T>`, which you can find by passing an `EntityKey` object (which is a member of the `System.Data` namespace) to the `GetObjectByKey()` method. Assuming you have imported this namespace into your C# code file, you can now author the following helper method:

```
private static void RemoveRecord()
{
    // Find a car to delete by primary key.
    using (AutoLotEntities context = new AutoLotEntities())
    {
        // Define a key for the entity we are looking for.
        EntityKey key = new EntityKey("AutoLotEntities.Cars", "CarID", 2222);

        // See if we have it, and delete it if we do.
        Car carToDelete = (Car)context.GetObjectByKey(key);
        if (carToDelete != null)
        {
            context.DeleteObject(carToDelete);
            context.SaveChanges();
        }
    }
}
```

■ **Note** For better or for worse, calling `GetObjectByKey()` requires a roundtrip to the database before you can delete the object.

Notice that when you are creating an EntityKey object, you need use a string object to inform it which `ObjectSet<T>` to evaluate in a given `ObjectContext` derived class. The second argument is another string; this one represents the property name on the entity class that is marked as the key, and the final

constructor argument is the value of the primary key. Once you find the object in question, you can call `DeleteObject()` off your context and save the changes.

Updating a Record

Updating a record is also straightforward; locate the object you wish to change, set new property values on the returned entity, and save the changes:

```
private static void UpdateRecord()
{
    // Find a car to delete by primary key.
    using (AutoLotEntities context = new AutoLotEntities())
    {
        // Define a key for the entity we are looking for.
        EntityKey key = new EntityKey("AutoLotEntities.Cars", "CarID", 2222);

        // Grab the car, change it, save!
        Car carToUpdate = (Car)context.GetObjectByKey(key);
        if (carToUpdate != null)
        {
            carToUpdate.Color = "Blue";
            context.SaveChanges();
        }
    }
}
```

The preceding method might seem a bit off, at least until you remember that the entity object returned from `GetObjectByKey()` is a reference to an existing object in the `ObjectSet<T>` field. Thus, when you set properties to change the state, you are changing the same object in memory.

Note Much like an ADO.NET `DataRow` object (see Chapter 22), any descendent of `EntityObject` (meaning, all of your entity classes) has a property named `EntityState`, which is used by the object context to determine whether the item has been modified, deleted, is detached, and so forth. This is set on your behalf as you work with the programming model; however, you can change this manually as required.

Querying with LINQ to Entities

So far, you have been working with a few simple methods on the object context and entity objects to perform selections, inserts, updates, and deletes. This is useful all by itself; however, EF becomes much more powerful when you incorporate LINQ queries. If you wish to use LINQ to update or delete records, you don't need to make an `EntityKey` object manually. Consider the following update to the `RemoveRecord()` method, which will *not work* as expected at this point:

```
private static void RemoveRecord()
{
```

```
// Find a car to delete by primary key.
using (AutoLotEntities context = new AutoLotEntities())
{
    // See if we have it?
    var carToDelete = from c in context.Cars where c.CarID == 2222 select c;

    if (carToDelete != null)
    {
        context.DeleteObject(carToDelete);
        context.SaveChanges();
    }
}
```

This code compiles, but you will receive a runtime exception when you attempt to call the `DeleteObject()` method. The reason: This particular LINQ query returns an `ObjectQuery<T>` object, not a `Car` object. Always remember that when you build a LINQ query that attempts to locate a single entity, you will get back an `ObjectQuery<T>` representing a query that is capable of bringing back the data you are looking for. To execute the query (and bring back the `Car` entity), you must execute a method such as `FirstOrDefault()` on the query object, as in the following example:

```
var carToDelete =
    (from c in context.Cars where c.CarID == 2222 select c).FirstOrDefault();
```

By calling `FirstOrDefault()` on the `ObjectQuery<T>`, you find the item you want; or, if there is no `Car` with the ID of 2222, a default value of `null`.

Given that you have already worked with many LINQ expressions in Chapter 13, a few more examples will suffice for the time being:

```
private static void FunWithLINQQueries()
{
    using (AutoLotEntities context = new AutoLotEntities())
    {
        // Get a projection of new data.
        var colorsMakes = from item in context.Cars select
            new { item.Color, item.Make };
        foreach (var item in colorsMakes)
        {
            Console.WriteLine(item);
        }

        // Get only items where CarID < 1000
        var idsLessThan1000 = from item in context.Cars
            where item.CarID < 1000 select item;
        foreach (var item in idsLessThan1000)
        {
            Console.WriteLine(item);
        }
    }
}
```

While the syntax of these queries is simple enough, remember that you are hitting a database each time you apply a LINQ query to the object context! Recall that when you wish to obtain an independent copy of data, which can be the target of new LINQ queries, you want to use immediate execution with the `ToList<T>()`, `ToArray<T>()` or `ToDictionary<K,V>()` extension methods (among others). Here is an update of the previous method, which performs the equivalent of a SELECT *, caches the entities as an array, and manipulates the array data using LINQ to Objects:

```
using (AutoLotEntities context = new AutoLotEntities())
{
    // Get all data from the Inventory table.
    // could also write:
    // var allData = (from item in context.Cars select item).ToArray();
    var allData = context.Cars.ToArray();

    // Get a projection of new data.
    var colorsMakes = from item in allData select new { item.Color, item.Make };

    // Get only items where CarID < 1000
    var idsLessThan1000 = from item in allData where
        item.CarID < 1000 select item;
}
```

Working with LINQ to Entities is much more enticing when your EDM contains multiple related tables. You'll see some example that illustrate this in a moment; however, let's wrap up this current example by looking at two other ways you can interact with your object context.

Querying with Entity SQL

To be sure, you will be querying and `ObjectSet<T>` with LINQ a majority of the time. The entity client will break down your LINQ query into a fitting SQL statement, passing it onto the database for processing. However, you can use Entity SQL if you wish to have more control over how the query is formatted.

Entity SQL is a SQL-like query language that can be applied to entities. While the format of an Entity SQL statement is similar to a traditional SQL statement, it is not identical. Entity SQL has a unique syntax because the entities receive the query, not the physical database. Like a LINQ to Entities query, an Entity SQL query is used to pass a "real" SQL query to the database.

This chapter will not dive into the details of building Entity SQL commands, so please consult the .NET Framework 4.0 SDK documentation if you want more information. However, one example might be helpful. Consider the following method, which builds an Entity SQL statement that finds all black cars in the `ObjectSet<Car>` collection:

```
private static void FunWithEntitySQL()
{
    using (AutoLotEntities context = new AutoLotEntities())
    {
        // Build a string containing Entity SQL syntax.
        string query = "SELECT VALUE car FROM AutoLotEntities.Cars " +
            "AS car WHERE car.Color='black'";

        // Now build a ObjectQuery<T> based on the string.
        var blackCars = context.CreateQuery<Car>(query);
```

```
foreach (var item in blackCars)
{
    Console.WriteLine(item);
}
```

Notice that you pass in the formatted Entity SQL statement as an argument to the `CreateQuery<T>` method of your object context.

Working with the Entity Client Data Reader Object

When you use LINQ to Entities or Entity SQL, the fetched data is mapped back to your entity classes automatically, thanks to the entity client service. Typically this is exactly what you require; however, you can intercept the result set before it makes its way to your entity objects and process it manually using the `EntityDataReader`.

Here is a final helper method for this example, which uses several members of the `System.Data.EntityClient` namespace to build a connection manually through a command object and data reader. This code should look familiar due to your previous work in Chapter 21; the major difference is that you use Entity SQL, rather than “normal” SQL:

```
private static void FunWithEntityDataReader()
{
    // Make a connection object, based on our *.config file.
    using (EntityConnection cn = new EntityConnection("name=AutoLotEntities"))
    {
        cn.Open();

        // Now build an Entity SQL query.
        string query = "SELECT VALUE car FROM AutoLotEntities.Cars AS car";

        // Create a command object.
        using (EntityCommand cmd = cn.CreateCommand())
        {
            cmd.CommandText = query;

            // Finally, get the data reader and process records.
            using (EntityDataReader dr =
                cmd.ExecuteReader(CommandBehavior.SequentialAccess))
            {
                while (dr.Read())
                {
                    Console.WriteLine("***** RECORD *****");
                    Console.WriteLine("ID: {0}", dr["CarID"]);
                    Console.WriteLine("Make: {0}", dr["Make"]);
                    Console.WriteLine("Color: {0}", dr["Color"]);
                    Console.WriteLine("Pet Name: {0}", dr["CarNickname"]);
                    Console.WriteLine();
                }
            }
        }
    }
}
```

```

    }
}
}
}
```

Great! This initial example should go a long way toward helping you understand the nuts and bolts of working with the Entity Framework. As mentioned previously, things become much more interesting when your EDM contains interrelated tables, which you will learn about next.

Source Code You can find the `InventoryEDMConsoleApp` example under the Chapter 23 subdirectory.

AutoLotDAL Version 4.0, Now with Entities

Next, you will learn how to build an EDM that captures the bulk of the AutoLot database, including your `GetPetName` stored procedure. I strongly suggest that you make a copy of the AutoLotDAL (Version 3) project you created in Chapter 22 and rename this copy to AutoLotDAL (Version 4).

Open the latest version of the AutoLotDAL project in Visual Studio 2010 and insert a new ADO.NET Entity Data Model project item named `AutoLotDAL_EF.edmx`. On step three of the wizard, you should select the `Inventory`, `Orders`, and `Customers` tables (there's no need to nab the `CreditRisks` table at this time), as well as the custom stored procedure (see Figure 23-17).




Figure 23-17. The *.edmx file for a majority of the AutoLot database

In contrast to the first EDM example, this time you don't bother renaming your entity class names or their properties.

Mapping the Stored Procedure

Here's one aspect of the EDM Wizard that is quite odd: even when you check off the name of a stored procedure to include in your conceptual model, your work is not done. At this point all you have done is make the IDE aware of the physical stored procedure; to make it materialize in code, you need to import the function into the conceptual layer. Open the Model browser (using the View ► Other Windows ► Entity Data Model Browser menu) and notice that you can see GetPetName in the physical database (located under AutoLotModel.Store); however, the Function Imports folder (highlighted in Figure 23-18) is currently empty.




Figure 23-18. Stored procedures must be imported before you can call them!

You can begin mapping this to your conceptual layer by right-clicking on the Function Imports folder and selecting the Add Function Import... menu option (see Figure 23-19).




Figure 23-19. Choosing to import a stored procedure into your conceptual model

In the resulting dialog box, you want to pick the name of the physical stored procedure (from the Stored Procedure Name dropdown box), and then supply a name of the method to map to in your conceptual model. In this case, the names will map directly. Now recall that your stored procedure does not literally return a set of records; however, it does return an output parameter. Thus, you need to make sure that you check the None radio button (see Figure 23-20).




Figure 23-20. Mapping the physical stored procedure to the conceptual model

The Role of Navigation Properties

If you look at the EDM designer now, you will see each table is accounted for, including new entries in the Navigation Properties section of a given entity class (see Figure 23-21).




Figure 23-21. Navigation properties

As the name suggests, *navigation properties* allow you to capture JOIN operations in the Entity Framework programming model (without the need to author complex SQL statements). To account for these foreign key relationships, each entity in the *.edmx file now contains some new XML data that shows how entities are connected through key data. Feel free to open the *.edmx file using the XML editor if you wish to see the markup directly; however, you can see this same information in the Model Browser window, under the Associations folder (see Figure 23-22).




Figure 23-22. Viewing your entity relationships

If you wish, change the version number of this new library to 4.0.0.0 (using the Assembly Information button within Applications tab of Properties window). Now compile your modified AutoLot.dll assembly before moving to the first client application.


Source Code You can find the AutoLotDAL (Version 4) project under the Chapter 23 subdirectory.

Using Navigation Properties within LINQ to Entity Queries

Next, you will learn how to use these navigation properties within the context of LINQ to Entity queries (you could also use them with Entity SQL; however, this book doesn't delve into that aspect of this topic). Before you bind your data to a Windows Forms GUI, you make one final Console Application named AutoLotEDMClient. Once you create the project, set a reference to System.Data.Entity.dll and the latest and greatest version of AutoLotDAL.dll.

Next, insert the App.config file from your AutoLotDAL project (using the Project ► Add Existing Item menu option) and import the AutoLotDAL namespace. Recall that the App.Config file generated by the EDM tools defines the correct connection string required by the Entity Framework.

Next, you will update the physical Orders table with a few new records. Specifically, you want to ensure that a single customer has multiple orders. Using the Visual Studio 2010 Server Explorer, update the Orders table with one or two new records to ensure that a single customer has two or more orders. For example, in Figure 23-23, customer #4 has two pending orders, for cars #1992 and #83.



Orders: Query(andr...sqlexpress.AutoLot)			
	OrderID	CustID	CarID
	1000	1	1000
	1001	2	678
	1002	3	904
	1003	4	1992
	1005	4	83
*	NULL	NULL	NULL

Navigation controls at the bottom show page 5 of 5.

Figure 23-23. A single customer with multiple orders

Now update your Program with a new helper method (called from Main()). This method uses the navigation properties to select each Inventory object on order for a given customer:

```
private static void PrintCustomerOrders(string custID)
{
    int id = int.Parse(custID);

    using (AutoLotEntities context = new AutoLotEntities())
    {
        var carsOnOrder = from o in context.Orders
                         where o.CustID == id select o.Inventory;
```

```

Console.WriteLine("\nCustomer has {0} orders pending:", carsOnOrder.Count());
foreach (var item in carsOnOrder)
{
    Console.WriteLine("-> {0} {1} named {2}.",
        item.Color, item.Make, item.PetName);
}
}

```

When you run your application, you see something similar to the following output (notice that you specify a customer ID of four when you call `PrintCustomerOrders()` from `Main()`):

```

***** Navigation Properties *****
Please enter customer ID: 4

Customer has 2 orders pending:
-> Pink Saab named Pinky.
-> Rust Ford named Rusty.

```

Here, you find a single Customer entity in the context, which has the specified `CustID` value. Once you find the given customer, you can navigate to the `Inventory` table to select each car on order. The return value of your LINQ query is an enumeration of `Inventory` objects, which you print out using a standard `foreach` loop.

Invoking a Stored Procedure

In the AutoLotDAL EMD, you now have the information you need to invoke the `GetPetName` stored procedure. You can do this using either of two approaches:

```

private static void CallStoredProcedure()
{
    using (AutoLotEntities context = new AutoLotEntities())
    {
        ObjectParameter input = new ObjectParameter("carID", 83);
        ObjectParameter output = new ObjectParameter("petName", typeof(string));

        // Call ExecuteFunction off the context....
        context.ExecuteFunction("GetPetName", input, output);

        // ....or use the strongly typed method on the context.
        context.GetPetName(83, output);

        Console.WriteLine("Car #83 is named {0}", output.Value);
    }
}

```

The first approach is to call the `ExecuteFunction()` method of your object context. In this case, the stored procedure is identified by a string name, and each parameter is represented by an object of type

`ObjectParameter`, which is in the `System.Data.Objects` namespace (don't forget to import this into your C# code file!).

The second approach is to use the strongly typed name in your object context. This approach proves a tad simpler because you can send input parameters (such as the car ID) as typed data, rather than as an `ObjectParameter` object.

■ **Source Code** You can find the `AutoLotEDMClient` example under the Chapter 23 subdirectory.

Data Binding Entities to Windows Forms GUIs

To conclude this introductory examination of the ADO.NET Entity Framework, you will create a simple example where you bind entity objects to a Windows Forms GUI. As mentioned earlier in this chapter, you will examine data-binding operations in WPF and ASP.NET projects.

Create a new Windows Forms application named `AutoLotEDM_GUI` and rename your initial form to `MainForm`. After you create the project (and similar to the previous client application you created), you set a reference to `System.Data.Entity.dll` and the latest and greatest version of `AutoLotDAL.dll`. Next, insert the `App.config` file from your `AutoLotDAL` project (using the `Project > Add Existing Item` menu option) and import the `AutoLotDAL` namespace into your Form's primary code file.

Now add a `DataGridView` object to the form designer and rename the control to `gridInventory`. Once you place this control on the designer, select the inline grid editor (the tiny arrow on the upper right of the widget). From the Choose Data Source dropdown box, add a project data source (see Figure 23-24).




Figure 23-24. Designing the Windows Forms `DataGridView` control

In this case, you do not bind directly to the database; instead, you bind to an entity class, so pick the Object option (see Figure 23-25).




Figure 23-25. Binding to a strongly typed object

In the final step, check off the Inventory table of AutoLotDAL.dll as shown in Figure 23-26 (if you don't see it listed, you probably forgot to reference this library).



Figure 23-26. Selecting the *Inventory* table

Once you click the Finish button, you'll see that the grid displays each property of the *Inventory* entity class, including the navigation properties! To remove them from the grid, activate the inline editor again (that tiny little arrow) and this time click the *Edit Columns...* link. Select the *Orders* column in the *Edit Columns* dialog and remove it from view (see Figure 23-27).




Figure 23-27. Cleaning up the grid's UI

To finish the UI, add a single Button control and rename it to `btnUpdate`. At this point, your designer should look something like what you see in Figure 23-28.




Figure 23-28. The final UI

Adding the Data Binding Code

At this point, you have a grid that can display any number of `Inventory` objects; however, you need to write the code to do so. Thanks to the runtime engine of the EF, the code could not be simpler. Begin by handling the `FormClosed` and `Load` events of your `MainForm` class (using the Properties window) and the `Click` event of the Button control. Once you do this, update your code file with the following snippet:

```
public partial class MainForm : Form
{
    AutoLotEntities context = new AutoLotEntities();

    public MainForm()
    {
        InitializeComponent();
    }

    private void MainForm_Load(object sender, EventArgs e)
    {
        // Bind the ObjectSet<Inventory> collection to the grid.
        gridInventory.DataSource = context.Inventories;
    }
}
```

```

private void btnUpdate_Click(object sender, EventArgs e)
{
    context.SaveChanges();
    MessageBox.Show("Data saved!");
}

private void MainForm_FormClosed(object sender, FormClosedEventArgs e)
{
    context.Dispose();
}
}

```

This is all you need to do! If you run your application, you can now add new records to the grid, select a row and delete it, and modify existing rows. When you click your Update button, the `Inventory` database is updated automatically because the object context has been kind enough to generate all the necessary SQL statements for selecting, updating, deleting, and inserting automatically. Figure 23-29 shows the completed Windows Forms application.




Figure 23-29. The completed application

Here are some key takeaways from this preceding example:

- The context remains allocated throughout the application.
- The call to `context.Inventories` executes SQL to fetch all rows from the `Inventory` table into memory.
- The context tracks *dirty* entities, so it knows what SQL to execute upon `SaveChanges()`.
- After `SaveChanges()`, the entities are considered *clean* again.

That wraps up this chapter's examination of the ADO.NET Entity Framework. While there is so much more to this programming model than this chapter can address, you should now have a solid understanding about what problems EF attempts to solve and how to work with the overall programming model. Be sure to consult the .NET Framework 4.0 SDK documentation for more details of this slick data programming API.

Summary

This chapter wrapped up your formal investigation of database programming using ADO.NET by examining the role of the Entity Framework. EF allows you to program against a conceptual model that closely maps to your business domain. While you can reshape your entities in any way you choose, the EF runtime ensures that the changed data is mapped to the correct physical table data.

You learned about the role of (and composition of) *.edmx files and how to generate them using the Visual Studio 2010 IDE. Along the way, you also learned how to map stored procedures to functions in your conceptual layer, how to apply LINQ queries to the object model, the role of Entity SQL, and how to consume fetched data at the lowest level using the `EntityDataReader`.

You wrapped up this chapter with a simple example of binding entity classes to graphical user interfaces within the context of a Windows Forms application. You'll see other examples of binding entities to GUI applications when you examine Windows Presentation Foundation and ASP.NET.



Introducing LINQ to XML

As a .NET developer, you are bound to encounter XML-based data in numerous places. Application and web-based configuration files store information as XML. ADO.NET DataSets can easily save out (or load in) data as XML. Windows Presentation Foundation, Silverlight, and Windows Workflow Foundation all make use of an XML-based grammar (XAML) to represent desktop UIs, browser-based UIs, and workflows respectively. Even Windows Communication Foundation (as well as the original .NET remoting APIs) also stores numerous settings as the well-formatted string called XML.

Although XML is indeed everywhere, programming with XML has historically been very tedious, very verbose, and very complex if one is not well versed in a great number of XML technologies (XPath, XQuery, XSLT, DOM, SAX, etc.). Since the inception of the .NET platform, Microsoft has provided a specific assembly devoted to programming with XML documents named `System.Xml.dll`. Within this binary are a number of namespaces and types to various XML programming techniques, as well as a few .NET-specific XML APIs such as the `XmlReader`/`XmlWriter` classes.

These days, most .NET programmers prefer to interact with XML data using the LINQ to XML API. As you will see in this chapter, the LINQ to XML programming model allows you to capture the structure of an XML data in code, and provides a much simpler way to create, manipulate, load, and save XML data. While you could use LINQ to XML as little more than a simpler way to create XML documents, you can also easily incorporate LINQ query expressions into the mix, to quickly query a document for information.

A Tale of Two XML APIs

When the .NET platform was first introduced, programmers were able to manipulate XML documents using the types within the `System.Xml.dll` assembly. Using the contained namespaces and types, you were able to generate XML data in memory and save it to disk storage. As well, the `System.Xml.dll` assembly provided types allowing you to load XML documents into memory, search an XML document for specific nodes, validate a document against a given schema, and other common programming tasks.

While this original library has been used successfully in many .NET projects, working with these types was a tad bit cumbersome (to put it politely), as the programming model bore no relationship to the structure of the XML document itself. For example, assume you needed to build an XML file in memory and save it to the file system. If you were to use the types of `System.Xml.dll`, you might author code like the following (if you want to follow along, create a new Console Application project named `LinqToXmlFirstLook`, and import the `System.Xml` namespace):

```
private static void BuildXmlDocWithDOM()
{
    // Make a new XML document in memory.
    XmlDocument doc = new XmlDocument();

    // Fill this document with a root element
    // named <Inventory>.
    XmlElement inventory = doc.CreateElement("Inventory");

    // Now, make a sub element named <Car> with
    // an ID attribute.
    XmlElement car = doc.CreateElement("Car");
    car.SetAttribute("ID", "1000");

    // Build the data within the <Car> element.
    XmlElement name = doc.CreateElement("PetName");
    name.InnerText = "Jimbo";
    XmlElement color = doc.CreateElement("Color");
    color.InnerText = "Red";
    XmlElement make = doc.CreateElement("Make");
    make.InnerText = "Ford";

    // Add <PetName>, <Color> and <Make> to the <Car>
    // element.
    car.AppendChild(name);
    car.AppendChild(color);
    car.AppendChild(make);

    // Add the <Car> element to the <Inventory> element.
    inventory.AppendChild(car);

    // Insert the complete XML into the XmlDocument object,
    // and save to file.
    doc.AppendChild(inventory);
    doc.Save("Inventory.xml");
}
```

If you were to call this method, you could be able to see that the `Inventory.xml` file (located in the `bin\Debug` folder) contains the following data:

```
<Inventory>
  <Car ID="1000">
    <PetName>Jimbo</PetName>
    <Color>Red</Color>
    <Make>Ford</Make>
  </Car>
</Inventory>
```

While this method works as expected, a few observations are in order. First, the programming model of `System.Xml.dll` is Microsoft's implementation of the W3C Document Object Model (DOM) specification. Under this model, an XML document is created from the bottom up. First you create a document, then you create sub-elements, and finally you add the elements to the document. To account for this in code, you need to author quite a bit of function calls off the `XmlDocument`, and `XmlElement` classes (among others).

For this example, it took 16 lines of code (not including code comments) to build even this very simple XML document. If you needed to build a more complex document with the `System.Xml.dll` assembly, you could end up with a great deal of code. While you could certainly streamline this code, by building nodes via various looping or decision constructs, the fact remains that the body of code has little visual indicators regarding the final XML tree.

LINQ to XML As a Better DOM

The LINQ to XML API is an alternative manner to create, manipulate, and query XML documents, which uses a much more functional approach than the `System.Xml` DOM model. Rather than building an XML document by assembling elements individually and updating the XML tree through a set of function calls, you can author top-down code such as the following:

```
private static void BuildXmlDocWithLINQToXml()
{
    // Create a XML document in a more 'functional' manner.
    XElement doc =
        new XElement("Inventory",
            new XElement("Car", new XAttribute("ID", "1000"),
                new XElement("PetName", "Jimbo"),
                new XElement("Color", "Red"),
                new XElement("Make", "Ford")
            )
        );
    // Save to file.
    doc.Save("InventoryWithLINQ.xml");
}
```

Here, you are using a new set of types from the `System.Xml.Linq` namespace, specifically `XElement` and `XAttribute`. If you were to call this method, you will find the same XML data has been created, this time with much less fuss and bother. Notice how, through some careful indentation, your source code has the same overall structure of the resulting XML document. This is very useful in and of itself, but also notice that you have a much smaller body of code than the previous example (based on how you space your code, you saved about 10 lines!).

Here, you have not made use of any LINQ query expressions, but have simply used the types of the `System.Xml.Linq` namespace to generate an in-memory XML document which is then saved to file. Effectively, you have used LINQ to XML as a better DOM. As you will see later in this chapter, the classes of `System.Xml.Linq` are LINQ-aware, and can be the target for the same sort of LINQ queries you learned about in Chapter 13.

As you learn more about LINQ to XML, you will most likely find it much easier to work with than the initial XML libraries of .NET. However, this is not to say you will never use the namespaces of the original System.Xml.dll library. But chances are the times you will opt to use System.Xml.dll for new projects will be significantly reduced.

VB Literal Syntax As a Better LINQ to XML

Before you begin your formal examination into LINQ to XML as seen through C#, I do want to briefly mention that the Visual Basic language takes the functional approach of this API to the next level. In VB, you can define *XML literals*, which allow you to assign an XElement to a stream of inline XML markup, directly in code. Assuming you had a VB project, you could build the following method:

```
Public Class XmlLiteralExample
    Public Sub MakeXmlFileUsingLiterals()
        ' Notice that we can inline XML data
        ' to an XElement.
        Dim doc As XElement = _
            <Inventory>
                <Car ID="1000">
                    <PetName>Jimbo</PetName>
                    <Color>Red</Color>
                    <Make>Ford</Make>
                </Car>
            </Inventory>

        ' Save to file.
        doc.Save("InventoryVBStyle.xml")
    End Sub
End Class
```

Once the VB compiler processes the XML literal, it will map the XML data into the correct underlying LINQ to XML object model. In fact, when you are working with LINQ to XML within a VB project, the IDE already understands that your XML literal syntax is just a shorthand notation for the related code. In Figure 24-1, notice how you can apply the dot operator to the </Inventory> end tag and see the same members as you would find if you apply the dot operator to a strongly typed XElement.




Figure 24-1. VB XML literal syntax is a shorthand notation for working with the LINQ to XML object model

Although this book is about the C# programming language, few developers can argue that VB's XML support is quite awesome. Even if you are the sort of developer who can't imagine using a language from the BASIC family for your data to day development, I encourage you to check out VB literal syntax using the .NET Framework 4.0 SDK documentation. You may find yourself isolating your XML data manipulation routines to a dedicated *.dll, just so you can make use of VB to do so!

Members of the System.Xml.Linq Namespace

Somewhat surprisingly, the core LINQ to XML assembly (System.Xml.Linq.dll) defines a very small number of types in three distinct namespaces, specifically System.Xml.Linq, System.Xml.Schema, and System.Xml.XPath (see Figure 24-2).




Figure 24-2. The namespaces of `System.Xml.Linq.dll`

The core namespace, `System.Xml.Linq`, contains a very manageable set of classes that represent various aspects of an XML document (its elements and their attributes, XML namespaces, XML comments, and processing instructions, etc.). Table 24-1 documents the core members of `System.Xml.Linq`.


Table 24-1. Select Members of the `System.Xml.Linq` Namespace

Member of <code>System.Xml.Linq</code>	Meaning in Life
<code>XAttribute</code>	Represents an XML attribute on a given XML element.
<code>CDATA</code>	Represents a CDATA section in the XML document. Information in a CDATA section represents data in an XML document which must be included, but does not conform to the rules of XML grammars (for example, script code).
<code>XComment</code>	Represents an XML comment.
<code>XDeclaration</code>	Represents the opening declaration of an XML document.
<code>XDocument</code>	Represents the entirety of an XML document.

Table 24-1. Select Members of the System.Xml.Linq Namespace (continued)

Member of System.Xml.Linq	Meaning in Life
XElement	Represents a given element within an XML document, including the root element.
XName	Represents the name of an XML element or XML attribute.
XNamespace	Represents an XML namespace.
XNode	Represents the abstract concept of a node (element, comment, document type, processing instruction, or text node) in the XML tree.
XProcessingInstruction	Represents an XML processing instruction.
XStreamingElement	Represents elements in an XML tree that supports deferred streaming output.

Figure 24-3 shows how the inheritance chain of the key class types.

**Figure 24-3.** The LINQ to XML core class hierarchy

The LINQ to XML Axis Methods

In addition to the X* classes, `System.Xml.Linq` defines a class named `Extensions`, which (of course) defines a set of extension methods which typically extend `IEnumerable<T>`, where `T` is some descendent of `XNode` or `XContainer`. Table 24-2 documents some of the important extension methods to be aware of (as you will see, these are very useful when you wish to work with LINQ queries).

Table 24-2. Select Members of the LINQ to XML Extensions Class

Member of Extensions	Meaning in Life
<code>Ancestors<T>()</code>	Returns a filtered collection of elements that contains the ancestors of every node in the source collection.
<code>Attributes()</code>	Returns a filtered collection of the attributes of every element in the source collection.
<code>DescendantNodes<T>()</code>	Returns a collection of the descendant nodes of every document and element in the source collection.
<code>Descendants<T></code>	Returns a filtered collection of elements that contains the descendant elements of every element and document in the source collection.
<code>Elements<T></code>	Returns a collection of the child elements of every element and document in the source collection.
<code>Nodes<T></code>	Returns a collection of the child nodes of every document and element in the source collection.
<code>Remove()</code>	Removes every attribute in the source collection from its parent element.
<code>Remove<T>()</code>	Removes all occurrences of a given node from the source collection.

As you can tell from their names, these methods allow query a loaded XML tree to find elements, attributes, and their values. Collectively, these methods are termed *axis methods*, or simply *axes*. You can apply these methods directly to parts of a tree of nodes, or use them to build more elaborate LINQ queries.

Note The abstract `XContainer` class support a number of methods which are identically named to the members of `Extensions`. `XContainer` is the parent to both `XElement` and `XDocument`, and therefore they both support the same overall functionality.

You'll see examples of using some of these axis methods over the chapter. However, here is a quick example:

```
private static void DeleteNodeFromDoc()
{
    XElement doc =
        new XElement("Inventory",
            new XElement("Car", new XAttribute("ID", "1000"),
                new XElement("PetName", "Jimbo"),
                new XElement("Color", "Red"),
                new XElement("Make", "Ford")
            )
        );
    // Delete the PetName element from the tree.
    doc.Descendants("PetName").Remove();
    Console.WriteLine(doc);
}
```

If you invoke this method, you'd see the following “pruned” XML tree:

```
<Inventory>
  <Car ID="1000">
    <Color>Red</Color>
    <Make>Ford</Make>
  </Car>
</Inventory>
```

The Oddness of XName (and XNamespace)

If you examine the signatures of the LINQ to XML axis methods (or the identically named members of `XContainer`), you'll notice that they typically require you to specify what looks to be an `XName` object. Consider the signature of the `Descendants()` method defined by `XContainer`:

```
public IEnumerable< XElement > Descendants(XName name)
```

`XName` is “odd” in that you will never really directly make use of it in your code. In fact, since this class has no public constructor, you cannot make an `XName` object:

```
// Error! Can't make XName objects!
doc.Descendants(new XName("PetName")).Remove();
```

If you were to view the formal definition of `XName`, you will see that this class defines a custom implicit conversion operator (see Chapter 12 for information of defining custom conversion operators), which will map a simple `System.String` to the correct `XName` object:

```
// We really make an XName in the background!
doc.Descendants("PetName").Remove();
```

■ Note The XNamespace class also supports the same flavor of implicit string conversion.

The good news is that you can use textual values to represent the names of elements or attributes when you work with these axis methods, and allow the LINQ to XML API to map your string data to the necessary object types.

■ Source Code The LinqToXmlFirstLook example can be found under the Chapter 24 subdirectory.

Working with XElement and XDocument

Let's continue the investigation of LINQ to XML with a new Console Application named ConstructingXmlDocs. Once you have done so, import the System.Xml.Linq namespace in your initial code file. As you have already seen, XDocument represents the entirety of an XML document in the LINQ to XML programming model, as it can be used to define a root element, and all contained elements, processing instructions and XML declarations. Here is another example of building XML data using XDocument:

```
static void CreateFullXDocument()
{
    XDocument inventoryDoc =
        new XDocument(
            new XDeclaration("1.0", "utf-8", "yes"),
            new XComment("Current Inventory of cars!"),
            new XProcessingInstruction("xml-stylesheet",
                "href='MyStyles.css' title='Compact' type='text/css'"),
            new XElement("Inventory",
                new XElement("Car", new XAttribute("ID", "1"),
                    new XElement("Color", "Green"),
                    new XElement("Make", "BMW"),
                    new XElement("PetName", "Stan")),
                new XElement("Car", new XAttribute("ID", "2"),
                    new XElement("Color", "Pink"),
                    new XElement("Make", "Yugo"),
                    new XElement("PetName", "Melvin"))
            )
        );
    // Save to disk.
    inventoryDoc.Save("SimpleInventory.xml");
}
```

Again, notice that the constructor of the `XDocument` object is in fact a tree of additional LINQ to XML objects. The constructor called here takes as the first parameter an `XDeclaration`, followed by a parameter array of objects (recall, C# parameter arrays allow you to pass in a comma delimited list of arguments, which are packaged as an array on your behalf):

```
public XDocument(System.Xml.Linq.XDeclaration declaration, params object[] content)
```

If you were to invoke this method from `Main()`, you'd see the following data in the `SimpleInventory.xml` file:

```
<?xml version="1.0" encoding="utf-8" standalone="yes"?>
<!--Current Inventory of cars!-->
<?xmlstylesheet href='MyStyles.css' title='Compact' type='text/css'?>
<Inventory>
  <Car ID="1">
    <Color>Green</Color>
    <Make>BMW</Make>
    <PetName>Stan</PetName>
  </Car>
  <Car ID="2">
    <Color>Pink</Color>
    <Make>Yugo</Make>
    <PetName>Melvin</PetName>
  </Car>
</Inventory>
```

As it turns out, the default XML declaration for any `XDocument` is to use utf-8 encoding, XML version 1.0, as a standalone document. Therefore, you could completely delete the creation of the `XDeclaration` object and end up with the same data; given that just about every document requires this same declaration, use of `XDeclaration` is typically not that common.

If you do not need to define processing instructions or a custom XML declaration, you can avoid the use of `XDocument` all together, and simply use `XElement`. Remember, `XElement` can be used to represent the root element of the XML document and all sub-objects. Thus, you could generate a commented list of inventory items as so:

```
static void CreateRootAndChildren()
{
  XElement inventoryDoc =
    new XElement("Inventory",
      new XComment("Current Inventory of cars!"),
      new XElement("Car", new XAttribute("ID", "1"),
        new XElement("Color", "Green"),
        new XElement("Make", "BMW"),
        new XElement("PetName", "Stan")
      ),
      new XElement("Car", new XAttribute("ID", "2"),
        new XElement("Color", "Pink"),
        new XElement("Make", "Yugo"),
        new XElement("PetName", "Melvin")
      )
    );
}
```

```

        )
};

// Save to disk.
inventoryDoc.Save("SimpleInventory.xml");
}

```

The output is more or less identical, sans the custom processing instruction for a hypothetical style sheet:

```

<?xml version="1.0" encoding="utf-8"?>
<Inventory>
    <!--Current Inventory of cars!-->
    <Car ID="1">
        <Color>Green</Color>
        <Make>BMW</Make>
        <PetName>Stan</PetName>
    </Car>
    <Car ID="2">
        <Color>Pink</Color>
        <Make>Yugo</Make>
        <PetName>Melvin</PetName>
    </Car>
</Inventory>

```

Generating Documents from Arrays and Containers

So far you have been building XML documents using fixed hard coded constructor values. More commonly, you will need to generate `XElements` (or `XDocuments`) by reading data from arrays, ADO.NET objects, file data, or whatnot. One way to map in-memory data to a new `XElement` is by using a set of standard “for loops” to move data into the LINQ to XML object model. While this is certainly doable, it is more streamlined to embed a LINQ query within the construction of the `XElement` directly.

Assume you have an anonymous array of anonymous classes (just to avoid the amount of code for this example; any array, `List<T>` or other container would do here). You could map this data into an `XElement` as so:

```

static void Make XElementFromArray()
{
    // Create an anonymous array of anonymous types.
    var people = new[] {
        new { FirstName = "Mandy", Age = 32 },
        new { FirstName = "Andrew", Age = 40 },
        new { FirstName = "Dave", Age = 41 },
        new { FirstName = "Sara", Age = 31 }
    };

    XElement peopleDoc =
        new XElement("People",

```

```

    from c in people select new XElement("Person", new XAttribute("Age", c.Age),
                                         new XElement("FirstName", c.FirstName))
);
Console.WriteLine(peopleDoc);
}

```

Here, the `peopleDoc` object defines the root `<People>` element with the results of a LINQ query. This LINQ query creates new `XElements` based on each item in the `people` array. If this embedded query is a bit hard on the eyes, you could break things down into explicit steps, like so:

```

static void Make XElementFromArray()
{
    // Create an anonymous array of anonymous types.
    var people = new[] {
        new { FirstName = "Mandy", Age = 32 },
        new { FirstName = "Andrew", Age = 40 },
        new { FirstName = "Dave", Age = 41 },
        new { FirstName = "Sara", Age = 31 }
    };

    var arrayDataAsXElements = from c in people
                               select
                                   new XElement("Person",
                                       new XAttribute("Age", c.Age),
                                       new XElement("FirstName", c.FirstName));

    XElement peopleDoc = new XElement("People", arrayDataAsXElements);
    Console.WriteLine(peopleDoc);
}

```

Either way, the output is the same:

```

<People>
  <Person Age="32">
    <FirstName>Mandy</FirstName>
  </Person>
  <Person Age="40">
    <FirstName>Andrew</FirstName>
  </Person>
  <Person Age="41">
    <FirstName>Dave</FirstName>
  </Person>
  <Person Age="31">
    <FirstName>Sara</FirstName>
  </Person>
</People>

```

Loading and Parsing XML Content

The XElement and XDocument types both support Load() and Parse() methods, which allow you to hydrate an XML object model from string objects containing XML data or external XML files. Consider the following method, which illustrates both approaches:

```
static void ParseAndLoadExistingXml()
{
    // Build an XElement from string.
    string myElement =
        @"<Car ID ='3'>
            <Color>Yellow</Color>
            <Make>Yugo</Make>
        </Car>";
    XElement newElement = XElement.Parse(myElement);
    Console.WriteLine(newElement);
    Console.WriteLine();

    // Load the SimpleInventory.xml file.
    XDocument myDoc = XDocument.Load("SimpleInventory.xml");
    Console.WriteLine(myDoc);
}
```

■ **Source Code** The ConstructingXmlDocs example can be found under the Chapter 24 subdirectory.

Manipulating an in Memory XML Document

So, that this point you have seen various ways in which LINQ to XML can be used to create, save, parse, and load XML data. The next aspect of LINQ to XML you need to examine is how to navigate a given document to locate and change specific items in the tree using LINQ queries and the LINQ to XML axis methods.

To do so, you will build a Windows Forms application which will display the data within a XML document saved on the hard drive. The GUI will allow the user to enter data for a new node, which will be added to the same XML document. Finally, you will provide a few ways for the user to perform searches on the document, via a handful of LINQ queries.

■ **Note** Given that you have already built a number of LINQ queries in Chapter 13, I won't bother to relist numerous queries. If you are interested in seeing some additional LINQ to XML specific examples, look up the topic "Querying XML Trees" in the .NET Framework 4.0 SDK documentation.

Building the UI of the LINQ to XML App

Create a Windows Forms application named LinqToXmlWinApp and change the name of your initial Form1.cs file to MainForm.cs (using the Solution Explorer). The GUI of this window is quite simple. On the left of the window, you have a TextBox control (named txtInventory), which has the Multiline property set to true, and the ScrollBars property set to Both.

Beyond that, you have one group of simple TextBox controls (txtMake, txtColor and txtPetName) and a Button btnAddNewItem, which will allow the user to add a new entry to the XML document. Finally, you have another group of controls (a TextBox named txtMakeToLookUp and a final Button named btnLookUpColors) which allows the user to query the XML document for a set of specified nodes. Figure 24-4 shows one possible layout.




Figure 24-4. The GUI of the LINQ to XML application

Handle the Click event for each button to generate the event handler methods. Also handle the Load event of the Form itself. You will implement these handlers in a bit.

Import the Inventory.xml File

The downloadable code for this book contains a file named `Inventory.xml` within the solution code for this example. It supports a set of entries within the root `<Inventory>` element. Import this file into your project by selecting the Project ➤ Add Existing Item menu option. As you look at the data, you will see the root element defines a set of `<Car>` elements, each of which is defined similar to the following:

```
<Car carID ="0">
  <Make>Ford</Make>
  <Color>Blue</Color>
  <PetName>Chuck</PetName>
</Car>
```

Before you continue on, be sure you select this file in the Solution Explorer, and then, using the Properties window, set the Copy to Output Directory property to Copy Always. This will ensure the data is deployed to your \bin\Debug folder when you compile the application.

Defining a LINQ to XML Helper Class

To isolate the LINQ to XML data, insert a new class to your project named `LinqToXmlObjectModel`. This class will define a set of static methods which encapsulate some LINQ to XML logic. First of all, define a method which returns a populated `XDocument` based on the contents of the `Inventory.xml` file (be sure to import the `System.Xml.Linq` and `System.Windows.Forms` namespaces into this new file):

```
public static XDocument GetXmlInventory()
{
    try
    {
        XDocument inventoryDoc = XDocument.Load("Inventory.xml");
        return inventoryDoc;
    }
    catch (System.IO.FileNotFoundException ex)
    {
        MessageBox.Show(ex.Message);
        return null;
    }
}
```

The `InsertNewElement()` method (shown in the following) receives the values of the “Add Inventory Item” TextBox controls to place a new node into the `<Inventory>` element using the `Descendants()` axis method. After this is done, you will save the document.

```
public static void InsertNewElement(string make, string color, string petName)
{
    // Load current document.
    XDocument inventoryDoc = XDocument.Load("Inventory.xml");

    // Generate a random number for the ID.
    Random r = new Random();

    // Make new XElement based on incoming parameters.
    XElement createElement = new XElement("Car", new XAttribute("ID", r.Next(50000)),
        new XElement("Color", color),
        new XElement("Make", make),
        new XElement("PetName", petName));
```

```

// Add to in-memory object.
inventoryDoc.Descendants("Inventory").First().Add(newElement);

// Save changes to disk.
inventoryDoc.Save("Inventory.xml");
}

```

The final method, `LookUpColorsForMake()` will receive the data in the final `TextBox` to build a string that contains the colors of a specified make, using a LINQ query. Consider the following implementation:

```

public static void LookUpColorsForMake(string make)
{
    // Load current document.
    XDocument inventoryDoc = XDocument.Load("Inventory.xml");

    // Find the colors for a given make.
    var makeInfo = from car in inventoryDoc.Descendants("Car")
                   where (string)car.Element("Make") == make
                   select car.Element("Color").Value;

    // Build a string representing each color.
    string data = string.Empty;
    foreach (var item in makeInfo.Distinct())
    {
        data += string.Format("- {0}\n", item);
    }

    // Show colors.
    MessageBox.Show(data, string.Format("{0} colors:", make));
}

```

Rigging up the UI to Your Helper Class

All you need to do at this point is fill in the details of your event handlers. Doing so is as simple as making calls to your static helper methods:

```

public partial class MainForm : Form
{
    public MainForm()
    {
        InitializeComponent();
    }

    private void MainForm_Load(object sender, EventArgs e)
    {
        // Display current XML inventory document in TextBox control.
        txtInventory.Text = LinqToXmlObjectModel.GetXmlInventory().ToString();
    }
}

```

```

private void btnAddNewItem_Click(object sender, EventArgs e)
{
    // Add new item to doc.
    LinqToXmlObjectModel.InsertNewElement(txtMake.Text, txtColor.Text, txtPetName.Text);

    // Display current XML inventory document in TextBox control.
    txtInventory.Text = LinqToXmlObjectModel.GetXmlInventory().ToString();
}

private void btnLookUpColors_Click(object sender, EventArgs e)
{
    LinqToXmlObjectModel.LookUpColorsForMake(txtMakeToLookUp.Text);
}
}

```

Figure 24-5 shows the end result.




Figure 24-5. The completed LINQ to XML application

That wraps up the introductory look at LINQ to XML and your investigation of LINQ. You first encountered LINQ in Chapter 13, where you learned about LINQ to Objects. Chapter 19 showed various examples using PLINQ, while Chapter 23 showcased how you can apply LINQ queries to ADO.NET Entity objects. Using all of this information, you are in good shape to dig deeper, which you should. Microsoft has made it very clear that LINQ will continue to evolve as the .NET platform grows.

■ **Source Code** The LinqToXmlWinApp to XML example can be found under the Chapter 24 subdirectory.

Summary

This chapter examined the role of LINQ to XML. As you have seen, this API is an alternative to the initial XML manipulation library which shipped with the .NET platform, `System.Xml.dll`. Using `System.Xml.Linq.dll`, you are able to generate new XML documents using a top down approach, where the structure of your code has a striking resemblance to the final XML data. In this light, LINQ to XML is a better DOM. You also learned how to build `XDocument` and `XElement` objects in a variety of ways (parsing, loading from file, mapping from in-memory objects) and how to navigate and manipulate data using LINQ queries.



Introducing Windows Communication Foundation

.NET 3.0 introduced an API designed specifically for the process of building distributed systems: Windows Communication Foundation (WCF). Unlike other distributed APIs you might have used in the past (e.g., DCOM, .NET remoting, XML web services, message queuing), WCF provides a single, unified, and extendable programming object model that you can use to interact with a number of previously diverse distributed technologies.

This chapter begins by framing the need for WCF and examining the problems it intends to solve by way of a quick review of previous distributed computing APIs. After you look at the services provided by WCF, you'll turn your attention to examining the key .NET assemblies, namespaces, and types that represent this programming model.

Over the remainder of this chapter, you'll build several WCF services, hosts, and clients using various WCF development tools. You'll also learn about a few helpful simplifications and shortcuts that .NET 4.0 provides. You'll also build one simple example under .NET 4.0 that walks you through how the task of building hosting configuration files becomes much easier (if you are not sure what a *configuration file* is at this point, you'll see many examples of such files in the pages to come).

A Potpourri of Distributed Computing APIs

The Windows operating system has historically provided many APIs for building distributed systems. While it is true that most people consider a *distributed system* to involve at least two networked computers, this term in the broader sense can refer to two executables that need to exchange data, even if they happen to be running on the same physical machine. Using this definition, selecting a distributed API for your current programming task typically involves asking the following pivotal question:

Will this system be used exclusively in house, or will external users require access to the application's functionality?

If you build a distributed system for in-house use, you have a far greater chance of ensuring that each connected computer is running the same operating system and using the same programming framework (e.g., .NET, COM, or the Java platform). Running in-house systems also means that you can leverage your existing security system for purposes of authentication, authorization, and so forth. In this situation, you might be willing to select a particular distributed API that will tie you to a specific operating system/programming framework for the purposes of performance.

In contrast, if you build a system that others must reach from outside of your walls, you have a whole other set of issues to contend with. First, you will most likely *not* be able to dictate to external users which operating system/s they can use, which programming framework/s they can use, or how they configure their security settings.

Second, if you happen to work for a larger company or in a university setting that uses numerous operating systems and programming technologies, an in-house application suddenly faces the same challenges as an outward-facing application. In either of these cases, you need to limit yourself to a more flexible distributed API to ensure the furthest reach of your application.

Based on your answer to this key distributed computing question, the next task is to pinpoint exactly which API (or set of APIs) to use. The following sections provide a quick recap of some of the major distributed APIs historically used by Windows software developers. Once you finish this brief history lesson, you will be able to see the usefulness of Windows Communication Foundation quite easily.

Note To ensure we are on the same page here, I feel compelled to point out that WCF (and the technologies it encompasses) has nothing to do with building an HTML-based web site. While it is true that web applications can be considered distributed because two machines are typically involved in the exchange, WCF is about establishing connections between machines to share the functionality of remote components—not for displaying HTML in a web browser. Chapter 32 will initiate your examination of building websites with the .NET platform.

The Role of DCOM

Prior to the release of the .NET platform, the Distributed Component Object Model (DCOM) was the remoting API of choice for Microsoft-centric development endeavors. Using DCOM, it was possible to build distributed systems using COM objects, the system registry, and a good amount of elbow grease. One benefit of DCOM was that it allowed for *location transparency* of components. Simply put, this allowed you to program client software in such a way that the physical locations of the remote objects were not hard-coded in the application. Regardless of whether the remote object was on the same machine or a secondary networked machine, the code base could remain neutral because the actual location was recorded externally in the system registry.

While DCOM did enjoy some degree of success, for all practical purposes it was a Windows-centric API. DCOM alone did not provide a fabric to build comprehensive solutions involving multiple operating systems (e.g., Windows, Unix, and Mac) or promote sharing of data between diverse architectures (e.g., COM, Java, or CORBA).

Note There were some attempts to port DCOM to various flavors of Unix/Linux, but the end results were lackluster and eventually became technology footnotes.

By and large, DCOM was best suited for in-house application development because exposing COM objects outside company walls entailed a set of additional complications (firewalls and so forth). With

the release of the .NET platform, DCOM quickly became a legacy programming model; and unless you maintain legacy DCOM systems, you can consider it a deprecated technology.

The Role of COM+/Enterprise Services

DCOM alone did little more than define a way to establish a communication channel between two pieces of COM-based software. To fill in the missing pieces required for building a feature-rich distributed computing solution, Microsoft eventually released Microsoft Transaction Server (MTS), which was later renamed to COM+.

Despite its name, COM+ is not used only by COM programmers—it is completely accessible to .NET professionals, as well. Since the first release of the .NET platform, the base class libraries provided a namespace named `System.EnterpriseServices`. Here, .NET programmers could build managed libraries that could be installed into the COM+ runtime to access the same set of services as a traditional COM+-aware COM server. In either case, once a COM+-aware library was installed into the COM+ runtime, it was termed a *serviced component*.

COM+ provides a number of features that serviced components can leverage, including transaction management, object lifetime management, pooling services, a role-based security system, a loosely coupled event model, and so on. This was a major benefit at the time, given that most distributed systems require the same set of services. Rather than forcing developers to code them by hand, COM+ provided an out-of-the-box solution.

One of the compelling aspects of COM+ was the fact that all of these settings could be configured in a declarative manner using administrative tools. Thus, if you wished to ensure an object was monitored under a transactional context or belonged to a particular security role, you simply selected the correct check boxes.

While COM+/Enterprise Services is still in use today, this technology is a Windows-only solution that is best suited for in-house application development or as a back-end service indirectly manipulated by more agnostic front ends (e.g., a public website that makes calls on serviced components [aka COM+ objects] in the background).

■ **Note** WCF does not provide a way to build serviced components. However, it does provide a manner for WCF services to communicate with existing COM+ objects. If you need to build serviced components using C#, you will need to make direct use of the `System.EnterpriseServices` namespace. Consult the .NET Framework 4.0 SDK documentation for details.

The Role of MSMQ

The Microsoft Message Queuing (MSMQ) API allows developers to build distributed systems that need to ensure reliable delivery of message data on the network. As developers know all too well, in any distributed system there is the risk that a network server is down, a database is offline, or connections are inexplicably lost. Furthermore, you must construct many applications in such a way that they hold message data for delivery at a later time (this process is known as *queuing data*).

Microsoft initially packaged MSMQ as a set of low-level C-based APIs and COM objects. With the release of the .NET platform, C# programmers could use `System.Messaging` namespace to hook into

MSMQ and build software that communicated with intermittently connected applications in a dependable fashion.

On a related note, the COM+ layer incorporated MSMQ functionality into the runtime (in a simplified format) using a technology termed Queued Components (QC). This manner of communicating with MSMQ was packaged up into the `System.EnterpriseServices` namespace mentioned in the previous section.

Regardless of which programming model you used to interact with the MSMQ runtime, the end result ensured that applications could deliver messages in a reliable and timely fashion. Like COM+, MSMQ is still part of the fabric of building distributed software on the Windows operating system.

The Role of .NET Remoting

As mentioned previously, DCOM quickly became a legacy distributed API after the release of the .NET platform. In its place, the .NET base class libraries shipped with the .NET remoting layer, represented by the `System.Runtime.Remoting` namespace. This API allows multiple computers to distribute objects, provided they all run the applications under the .NET platform.

The .NET remoting APIs provided a number of useful features. Most important was the use of XML-based configuration files to define declaratively the underlying plumbing used by the client and the server software. Using *.config files, it was easy to alter the functionality of your distributed system radically simply by changing the content of the configuration files and restarting the application.

Also, given that only .NET applications can use this API is usable, you can gain various performance benefits because data can be encoded in a compact binary format, and you can use the Common Type System (CTS) when defining parameters and return values. While it is possible to use .NET remoting to build distributed systems that span multiple operating systems (using Mono, which was briefly mentioned in Chapter 1 and detailed in Appendix B), interoperability between other programming architectures (e.g., Java) was still not directly possible.

The Role of XML Web Services

Each of the previous distributed APIs provided little (if any) support to allow external callers to access the supplied functionality in an *agnostic manner*. When you need to expose the services of remote objects to *any* operating system and *any* programming model, XML web services provide the most straightforward way of doing so.

Unlike a traditional browser-based web application, a web service provides a way to expose the functionality of remote components using standard web protocols. Since the initial release of .NET, programmers have been provided with superior support for building and consuming XML web services with the `System.Web.Services` namespace. In many cases, building a feature-complete web service is no more complicated than applying the `[WebMethod]` attribute to each public method you wish to provide access to. Furthermore, Visual Studio 2010 allows you to connect to a remote web service with the click of a button (or two).

Web services allow developers to build .NET assemblies containing types that can be accessed using simple HTTP. Furthermore, a web service encodes its data as simple XML. Given the fact that web services are based on open industry standards (e.g., HTTP, XML, and SOAP) rather than proprietary type systems and proprietary wire formats (as is the case with DCOM or .NET remoting), they allow for a high degree of interoperability and data exchange. Figure 25-1 illustrates the agnostic nature of XML web services.




Figure 25-1. XML web services allow for a high degree of interoperability

Of course, no distributed API is perfect. One potential drawback of web services is the fact that they can suffer from some performance issues (given the use of HTTP and XML data representation); another drawback is that they might not be an ideal solution for in-house applications where you could use a TCP-based protocol and binary formatting of data without incurring a penalty.

A .NET Web Service Example

For many years, .NET programmers have created web services using the ASP.NET Web Service project template of Visual Studio, which can be accessed using the File ▶ New ▶ Web Site dialog box. This particular project template creates a commonly used directory structure and a handful of initial files to represent the web service itself. While this project template is helpful in getting you up and running, you can build a .NET XML web service with a simple text editor and test it immediately with the ASP.NET development web server (Chapter 32 examines this utility in more detail).

For example, assume you have authored the following programming logic in a new file named HelloWebService.asmx (*.asmx is the default file extension for a .NET XML web service file). Once you do this, save it into a folder such as C:\HelloWebService:

```
<%@ WebService Language="C#" Class="HelloWebService" %>
using System;
using System.Web.Services;
```

```
public class HelloWebService
{
    [WebMethod]
    public string HelloWorld()
    {
        return "Hello World";
    }
}
```

While this simple service doesn't do anything particularly useful, notice that the file opens with the <%@WebService%> directive, which you use to specify which .NET programming language the file uses and the name of the class type that represents the service. Beyond this, the only point of interest is that you decorate the `HelloWorld()` method with the `[WebMethod]` attribute. In many cases, this is all you need to do to expose a method to external callers using HTTP. Finally, notice that you do not need to do anything special to encode the return value into XML because the runtime does this automatically.

If you wish to test this web service, simply press the F5 key to start a debugging session or Ctrl+F5 to run the project. At this point, your browser should launch, showing each *web method* exposed from this endpoint. At this point, you can click the `HelloWorld` link to invoke the method using HTTP. Once you do this, the browser displays the return value encoded as XML:

```
<?xml version="1.0" encoding="utf-8" ?>
<string xmlns="http://tempuri.org/">
    Hello World
</string>
```

Simple stuff, right? Even better, when you wish to build a “real” client to communicate with the service, you can generate a client-side proxy that you can use to invoke web methods. As you might know, a *proxy* is a class that encapsulates the low-level details of communicating with another object; in this case, that is the service itself.

You can generate proxies for a classic XML web service in two ways. First, you can use the command-line tool, `wsdl.exe`, which is useful when you want full control over how the proxy is generated. Second, you can simplify matters by using Visual Studio’s Add Web Reference option under the Project menu. Both of these approaches also generate a required client-side `*.config` file, which contains various configuration settings for the proxy (such as the web service location).

Assuming you have generated a proxy for this simple web service (you don’t need to do so here), the client application can invoke the web method in a simple manner:

```
static void Main(string[] args)
{
    // The proxy type contains code to read the *.config file
    // to resolve the location of the web service.
    HelloWebServiceProxy proxy = new HelloWebServiceProxy();
    Console.WriteLine(proxy.HelloWorld());
    Console.ReadLine();
}
```

While it remains possible to build this traditional flavor of XML web service under .NET 4.0, most new service projects will benefit from using the WCF templates instead. In fact, WCF is the preferred manner to build service-oriented systems since the release of .NET 3.0.

■ **Source Code** You can find the HelloWorldWebService project under the Chapter 25 subdirectory.

Web Service Standards

A major problem that web services faced early on was the fact that all of the big industry players (e.g., Microsoft, IBM, and Sun Microsystems) created web service implementations that were not 100-percent compatible with other web service implementations. Obviously, this was an issue because the whole point of web services is to achieve a high degree of interoperability across platforms and operating systems!

To ensure the interoperability of web services, groups such as the World Wide Web Consortium (W3C: www.w3.org) and the Web Services Interoperability Organization (WS-I: www.ws-i.org) began to author several specifications that laid out how a software vendor (e.g., IBM, Microsoft, or Sun Microsystems) should build web service-centric software libraries to ensure compatibility.

Collectively, all of these specifications are given the blanket name WS-*, and they cover such issues as security, attachments, the description of web services (using the *Web Service Description Language*, or *WSDL*), policies, SOAP formats, and a slew of other important details.

Microsoft's implementation of most of these standards (for both managed and unmanaged code) is embodied in the Web Services Enhancements (WSE) toolkit, which you can download for free from the supporting website: <http://msdn2.microsoft.com/en-us/webservices>.

When you build WCF service applications, you do not need to use the assemblies that are part of the WSE toolkit directly. Rather, if you build a WCF service that uses an HTTP-based binding (you'll learn more details about this later in the chapter), these same WS-* specifications are given to you out of the box (exactly which ones depend on the binding you choose).

Named Pipes, Sockets, and P2P

As if choosing from DCOM, .NET remoting, web services, COM+, and MSMQ were not challenging enough, the list of distributed APIs continues. Programmers can also use additional interprocess communication APIs such as named pipes, sockets, and peer-to-peer (P2P) services. These lower-level APIs typically provide better performance (especially for machines on the same LAN); however, using these APIs becomes more complex (if not impossible) for outward-facing applications.

If you build a distributed system involving a set of applications running on the same physical machine, you can use the named pipes API with the `System.IO.Pipes` namespace. This approach can provide the absolute fastest way to push data between applications on the same machine.

Also, if you build an application that requires absolute control over how network access is obtained and maintained, you can implement sockets and P2P functionality under the .NET platform using the `System.Net.Sockets` and `System.Net.PeerToPeer` namespaces, respectively.

The Role of WCF

The wide array of distributed technologies makes it difficult to pick the right tool for the job. This is further complicated by the fact that several of these technologies overlap in the services they provide (most notably in the areas of transactions and security).

Even when a .NET developer has selected what appear to be the correct technologies for the task at hand, building, maintaining, and configuring such an application is complex, at best. Each API has its own programming model, its own unique set of configuration tools, and so forth.

Prior to .NET 3.0, this meant that it was difficult to *plug and play* distributed APIs without authoring a considerable amount of custom infrastructure. For example, if you build your system using the .NET remoting APIs, and you later decide that XML web services are a more appropriate solution, you need to reengineer your code base.

WCF is a distributed computing toolkit introduced with .NET 3.0 that integrates these previously independent distributed technologies into a streamlined API represented primarily by the `System.ServiceModel` namespace. Using WCF, you can expose services to callers using a wide variety of techniques. For example, if you build an in-house application where all connected machines are Windows based, you can use various TCP protocols to ensure the fastest-possible performance. You can also expose this same service with the XML web service-based protocol to allow external callers to leverage its functionality, regardless of the programming language or operating system.

Given the fact that WCF allows you to pick the correct protocol for the job (using a common programming model), you will find that it becomes quite easy to plug and play the underlying plumbing of your distributed application. In most cases, you can do so without having to recompile or redeploy the client/service software because the grungy details are often relegated to application configuration files (much like the older .NET remoting APIs).

An Overview of WCF Features

Interoperability and integration of diverse APIs are only two (important) aspects of WCF. WCF also provides a rich software fabric that complements the remoting technologies it exposes. Consider the following list of major WCF features:

- Support for strongly typed *as well as* untyped messages. This approach allows .NET applications to share custom types efficiently, while software created using other platforms (such as Java) can consume streams of loosely typed XML.
- Support for several *bindings* (e.g., raw HTTP, TCP, MSMQ, and named pipes) allows to choose the most appropriate plumbing to transport message data.
- Support for the latest and greatest web service specifications (WS-*).
- A fully integrated security model encompassing both native Windows/.NET security protocols and numerous neutral-security techniques built on web service standards.
- Support for session-like state management techniques, as well as support for one-way or stateless messages.

As impressive as this list of features might be, it only scratches the surface of the functionality WCF provides. WCF also offers tracing and logging facilities, performance counters, a publish-and-subscribe event model, and transactional support, among other features.

An Overview of Service-Oriented Architecture

Yet another benefit of WCF is that it is based on the design principles established by *service-oriented architecture* (SOA). To be sure, SOA is a major buzzword in the industry; and like most buzzwords, SOA can be defined in numerous ways. Simply put, SOA is a way to design a distributed system where several autonomous *services* work in conjunction by passing *messages* across boundaries (either networked machines or two processes on the same machine) using well-defined *interfaces*.

In the world of WCF, you typically create these well-defined interfaces using CLR interface types (see Chapter 9). In a more general sense, however, the interface of a service simply describes the set of members that might be invoked by external callers.

The team that designed WCF observed the four tenets of SOA design principles. While these tenets are typically honored automatically simply by building a WCF application, understanding these four cardinal design rules of SOA can help you understand WCF better. The sections that follow provide a brief overview of each tenet.

Tenet 1: Boundaries Are Explicit

This tenet reiterates the fact that the functionality of a WCF service is expressed using well-defined interfaces (e.g., descriptions of each member, its parameters, and its return values). The only way that an external caller can communicate with a WCF service is through the interface, and the external caller remains blissfully unaware of the underlying implementation details.

Tenet 2: Services Are Autonomous

The term *autonomous entities* refers to the fact that a given WCF service is (as much as possible) an island unto itself. An autonomous service should be independent with regard to version, deployment, and installation issues. To help promote this tenet, you can fall back on a key aspect of interface-based programming. Once an interface is in production, it should never be changed (or you will risk breaking existing clients). When you need to extend the functionality of your WCF service, you author new interfaces that model the desired functionality.

Tenet 3: Services Communicate via Contract, Not Implementation

The third tenet is yet another byproduct of interface-based programming. The implementation details of a WCF service (e.g., the language it was written in how it gets accomplishes its work, etc.) are of no concern to the external caller. WCF clients interact with services solely through their exposed public interfaces. Furthermore, if the members of a service interface expose custom complex types, they need to be fully detailed as a *data contract* to ensure that all callers can map the content to a particular data structure.

Tenet 4: Service Compatibility Is Based on Policy

Because CLR interfaces provide strongly typed contracts for all WCF clients (and can also be used to generate a related WSDL document based on your choice of binding), it is important to realize that interfaces and WSDL alone are not expressive enough to detail aspects of what the service is capable of doing. Given this, SOA allows you to define *policies* that further qualify the semantics of the service (e.g.,

the expected security requirements used to talk to the service). Using these policies, you can basically separate the low-level syntactic description of your service (the exposed interfaces) from the semantic details of how they work and how they need to be invoked.

WCF: The Bottom Line

The preceding short history lesson explains why WCF is the preferred approach for building distributed applications under .NET 3.0 and later. WCF is the recommended API whether you want to build an in-house application using TCP protocols, move data between programs on the same machine using named pipes, or expose data to the world at large using web service protocols.

This is not to say that you cannot use the original .NET distributed-centric namespaces (e.g., `System.Runtime.Remoting`, `System.Messaging`, `System.EnterpriseServices`, and `System.Web.Services`) in new development efforts. In some cases (e.g., if you need to build COM+ objects), you must do so. In any case, if you have used these APIs in previous projects, you will find learning WCF straightforward. Like the technologies that preceded it, WCF makes considerable use of XML-based configuration files, .NET attributes, and proxy generation utilities.

With this introductory foundation behind you, you can concentrate on the topic of building WCF applications. Again, you should understand that full coverage of WCF would require an entire book because each of the supported services (e.g., MSMQ, COM+, P2P, and named pipes) could be a chapter unto itself. Here, you will learn the overall process of building WCF programs using both TCP- and HTTP-based (e.g., web service) protocols. This should put you in a good position to study these topics further, as you see fit.

Investigating the Core WCF Assemblies

As you might expect, the programming fabric of WCF is represented by a set of .NET assemblies installed into the GAC. Table 25-1 describes the overall role of the core WCF assemblies you need to use in just about any WCF application.

Table 25-1. Core WCF Assemblies

Assembly	Meaning in Life
<code>System.Runtime.Serialization.dll</code>	Defines namespaces and types that you can use for serializing and deserializing objects in the WCF framework.
<code>System.ServiceModel.dll</code>	This core assembly contains the types used to build any sort of WCF application.

These two assemblies define many new namespaces and types. You should consult the .NET Framework 4.0 SDK documentation for complete details; however, Table 25-2 documents the roles of some of the important namespaces.

Table 25-2. Core WCF Namespaces

Namespace	Meaning in Life
System.Runtime.Serialization	Defines many types you use to control how data is serialized and deserialized within the WCF framework.
System.ServiceModel	This primary WCF namespace defines binding and hosting types, as well as basic security and transactional types.
System.ServiceModel.Configuration	Defines numerous types that provide programmatic access to WCF configuration files.
System.ServiceModel.Description	Defines types that provide an object model to the addresses, bindings, and contracts defined within WCF configuration files.
System.ServiceModel.MsmqIntegration	Contains types to integrate with the MSMQ service.
System.ServiceModel.Security	Defines numerous types to control aspects of the WCF security layers.

A Brief Word Regarding CardSpace

In addition to `System.ServiceModel.dll` and `System.Runtime.Serialization.dll`, WCF provides a third assembly named `System.IdentityModel.dll`. This assembly contains many additional namespaces and types that support the CardSpace API. This technology allows you to establish and manage digital identities within a WCF application. Essentially, the CardSpace API provides a unified programming model to account for various security-related details for WCF applications, such as caller identity, user authentication/authorization services, and so on.

You will not examine CardSpace further in this edition of the book, so be sure to consult the .NET Framework 4.0 SDK documentation if you want to learn more.

The Visual Studio WCF Project Templates

As will be explained in more detail later in this chapter, a WCF application is typically represented by three interrelated assemblies, one of which is a *.dll that contains the types that external callers can communicate with (in other words, the WCF service itself). When you wish to build a WCF service, it is perfectly permissible to select a standard Class Library project template (see Chapter 14) as a starting point and manually reference the WCF assemblies.

Alternatively, you can create a new WCF service by selecting the WCF Service Library project template of Visual Studio 2010 (see Figure 25-2). This project type automatically sets references to the

required WCF assemblies; however, it also generates a good deal of starter code, which you will more likely than not delete.




Figure 25-2. The Visual Studio 2010 WCF Service Library project template

One benefit of selecting the WCF Service Library project template is that it also supplies you with an `App.config` file, which might seem strange because you are building a .NET *.dll, not a .NET *.exe. However, this file is useful because, when you debug or run your WCF Service Library project, the Visual Studio 2010 IDE will automatically launch the WCF Test Client application. This program (`WcfTestClient.exe`) will look up the settings in the `App.config` file, so it can host your service for testing purposes. You'll learn more about the WCF Test Client later in this chapter.

Note The `App.config` file of the WCF Service Library project is also useful because it shows you the bare-bones settings used to configure a WCF host application. In fact, you can copy and paste much of this code into your host's actual configuration file.

In addition to the basic WCF Service Library template, the WCF project category of the New Project dialog box defines two WCF library projects that integrate Windows Workflow Foundation (WF) functionality into a WCF service, as well as a template to build an RSS library (see Figure 25-2). The next chapter will introduce you to the Windows Workflow Foundation, so you'll ignore these particular WCF project templates for the time being (I'll leave it to the interested reader to dig into the RSS feed project template).

The WCF Service Website Project Template

You can find yet another Visual Studio 2010 WCF-centric project template in the New Web Site dialog box, which you activate using the File ▶ New ▶ Web Site menu option (see -Figure 25-3).




Figure 25-3. The Visual Studio 2010 web-based WCF Service project template

This WCF Service project template is useful when you know from the outset that your WCF service will use web service–based protocols rather than, for example, TCP or named pipes. This option can automatically create a new Internet Information Services (IIS) virtual directory to contain your WCF program files, create a proper `Web.config` file to expose the service through HTTP, and author the necessary `*.svc` file (you'll learn more about `*.svc` files later in this chapter). Thus, the web-based WCF Service project is a time-saver because the IDE automatically sets up the required IIS infrastructure.

In contrast, if you build a new WCF service using the WCF Service Library option, you have the ability to host the service in a variety of ways (e.g., custom host, Windows service, or manually built IIS virtual directory). This option is more appropriate when you wish to build a custom host for your WCF service that can work with any number of WCF bindings.

The Basic Composition of a WCF Application

When you build a WCF distributed system, you will typically do so by creating three interrelated assemblies:

- *The WCF Service assembly:* This `*.dll` contains the classes and interfaces that represent the overall functionality you want to expose to external callers.

- *The WCF Service host:* This software module is the entity that hosts your WCF service assembly.
- *The WCF client:* This is the application that accesses the service's functionality through an intervening proxy.

As mentioned previously, the WCF service assembly is a .NET class library that contains a number of WCF contracts and their implementations. The key difference is that the interface contracts are adorned with various attributes that control data type representation, how the WCF runtime interacts with the exposed types, and so forth.

The second assembly, the WCF host, can be literally any .NET executable. As you will see later in this chapter, WCF was set up so that you can expose services easily from any type of application (e.g., Windows Forms, a Windows service, and WPF applications). When you build a custom host, you use the `ServiceHost` type and possibly a related `*.config` file. The latter contains details regarding the server-side plumbing you wish to use. However, if you use IIS as the host for your WCF service, you don't need to build a custom host programmatically because IIS will use the `ServiceHost` type behind the scenes.

Note It is also possible to host a WCF service using the Windows Activation Service (WAS); you can consult the .NET Framework 4.0 SDK documentation for details.

The final assembly represents the client that makes calls into the WCF service. As you might expect, this client can be any type of .NET application. Similar to the host, client applications typically use a client-side `*.config` file that defines the client-side plumbing. You should also be aware that you can easily have a client application written in another framework (e.g., Java) if you build your WCF service using HTTP-based bindings.

Figure 25-4 illustrates the relationship between these three interrelated WCF assemblies (from a high level). Behind the scenes, several lower-level details are used to represent the required plumbing (e.g., factories, channels, and listeners). These low-level details are usually hidden from view; however, they can be extended or customized if required. In most cases, the default plumbing fits the bill sufficiently.




Figure 25-4. A high-level look at a typical WCF application

It is also worth pointing out that using a server-side or client-side `*.config` file is technically optional. If you wish, you can hard-code the host (as well as the client) to specify the necessary plumbing (e.g., endpoints, binding, and addresses). The obvious problem with this approach is that if

you need to change the plumbing details, you will need to recode, recompile, and redeploy a number of assemblies. Using a *.config file keeps your code base much more flexible because changing the plumbing is as simple as updating the file's content and restarting the application. On the other hand, programmatic configuration allows an application more dynamic flexibility—it can choose how to configure the plumbing based on *if-tests*, for example.

The ABCs of WCF

Hosts and clients communicate with each other by agreeing on the ABCs, a friendly mnemonic for remembering the core building blocks of a WCF application *address*, *binding*, and *contract*:

- *Address*: Describes the location of the service. In code, you represent this with a System.Uri type; however, you typically store the value in *.config files.
- *Binding*: WCF ships with a many different bindings that specify network protocols, encoding mechanisms, and the transport layer.
- *Contract*: Provides a description of each method exposed from the WCF service.

You should realize that the ABC abbreviation does not imply that a developer must define the address first, followed by binding, and ending with the contract. In many cases, a WCF developer begins by defining a contract for the service, followed by establishing an address and bindings (any order will do, as long as each aspect is accounted for). Before you build your first WCF application, you will take a more detailed walk through of the ABCs.

Understanding WCF Contracts

Understanding the notion of a *contract* is the key to building a WCF service. While not mandatory, the vast majority of your WCF applications will begin by defining a set of .NET interface types that are used to represent the set of members a given WCF service will support. Specifically, interfaces that represent a WCF contract are called *service contracts*. The classes (or structures) that implement them are called *service types*.

WCF service contracts are adorned with various attributes, the most common of which are defined in the System.ServiceModel namespace. When the members of a service contract (the methods in the interface) contain only simple data types (e.g., numerical data, Booleans, and string data), you can build a complete WCF service using nothing more than the [ServiceContract] and [OperationContract] attributes.

However, if your members expose custom types, you will need to use types in the System.Runtime.Serialization namespace (see Figure 25-5) of the System.Runtime.Serialization.dll assembly. Here you will find additional attributes (e.g., [DataMember] and [DataContract]) to fine-tune the process of defining how your composite types are serialized to and from XML when they are passed to and from service operations.

Strictly speaking, you are not required to use CLR interfaces to define a WCF contract. Many of these same attributes can be applied on public members of a public class (or structure). However, given the many benefits of interface-based programming (e.g., polymorphism and elegant versioning), it is safe to consider using CLR interfaces to describe a WCF contract a best practice.




Figure 25-5. *System.Runtime.Serialization* defines a number of attributes used when building WCF data contracts

Understanding WCF Bindings

Once you define and implement a contract (or a set of contracts) in your service library, the next logical step is to build a hosting agent for the WCF service itself. As mentioned previously, you have a variety of possible hosts to choose from, all of which must specify the *bindings* used by remote callers to gain access to the service type's functionality.

Choosing a set of bindings is one area that makes WCF development quite different from .NET remoting and/or XML web service development. WCF ships with many of binding choices, each of which is tailored to a specific need. If none of the out-of-the-box bindings fits the bill, you can create your own by extending the *CustomBinding* type (something you will not do in this chapter). A WCF binding can specify the following characteristics:

- The transport layer used to move data (HTTP, MSMQ, named pipes, and TCP)
- The channels used by the transport (one-way, request-reply, and duplex)
- The encoding mechanism used to deal with the data itself (e.g., XML and binary)
- Any supported web service protocols (if permitted by the binding), such as WS-Security, WS-Transactions, WS-Reliability, and so on

Let's take a look at your basic choices.

HTTP-Based Bindings

The `BasicHttpBinding`, `WSHttpBinding`, `WSDualHttpBinding`, and `WSFederationHttpBinding` options are geared toward exposing contract types through XML web service protocols. If you require the furthest reach possible for your service (e.g., multiple operating systems and multiple programming architectures), you want to focus on these bindings because all of these binding types encode data based on XML representation and use HTTP on the wire.

Table 25-3 shows how you can represent a WCF binding in code (using class types within the `System.ServiceModel` namespace) or as XML attributes defined within `*.config` files.

Table 25-3. The HTTP-Centric WCF Bindings

Binding Class	Binding Element	Meaning in Life
<code>BasicHttpBinding</code>	<code><basicHttpBinding></code>	You use this to build a WS-Basic Profile-conformant (WS-I Basic Profile 1.1) WCF service. This binding uses HTTP as the transport and Text/XML as the default message encoding.
<code>WSHttpBinding</code>	<code><wsHttpBinding></code>	This is similar to <code>BasicHttpBinding</code> , but provides more web service features. This binding adds support for transactions, reliable messaging, and WS-Addressing.
<code>WSDualHttpBinding</code>	<code><wsDualHttpBinding></code>	This is similar to <code>WSHttpBinding</code> , but intended for use with duplex contracts (e.g., the service and client can send messages back and forth). This binding supports only SOAP security and requires reliable messaging.
<code>WSFederationHttpBinding</code>	<code><wsFederationHttpBinding></code>	This is a secure and interoperable binding that supports the WS-Federation protocol, enabling organizations that are in a federation to authenticate and authorize users efficiently.

As its name suggests, `BasicHttpBinding` is the simplest of all web service-centric protocols. Specifically, this binding ensures that your WCF service conforms to a specification named WS-I Basic Profile 1.1 (defined by WS-I). The main reason to use this binding is for maintaining backward compatibility with applications that were previously built to communicate with ASP.NET web services (which have been part of the .NET libraries since version 1.0).

The `WSHttpBinding` protocol not only incorporates support for a subset of the WS-* specification (transactions, security, and reliable sessions), but also supports the ability to handle binary data encoding using Message Transmission Optimization Mechanism (MTOM).

The main benefit of `WSDualHttpBinding` is that it adds the ability to allow the caller and sender to communicate using *duplex messaging*, which is a fancy way of saying they can engage in a two-way conversation. When selecting `WSDualHttpBinding`, you can hook into the WCF publish/subscribe event model.

Finally, `WSFederationHttpBinding` is the web service-based protocol you might wish to consider when security among a group of organizations is of the utmost importance. This binding supports the WS-Trust, WS-Security, and WS-SecureConversation specifications, which are represented by the WCF CardSpace APIs.

TCP-Based Bindings

If you build a distributed application involving machines that are configured with the .NET 4.0 libraries (in other words, all machines are running the Windows operating system), you can gain performance benefits by bypassing web service bindings and opting for a TCP binding, which ensures that all data is encoded in a compact binary format, rather than XML. Again, when you use the bindings shown in Table 25-4, the client and host must be .NET applications.

Table 25-4. The TCP-Centric WCF Bindings

Binding Class	Binding Element	Meaning in Life
<code>NetNamedPipeBinding</code>	<code><netNamedPipeBinding></code>	Serves as a secure, reliable, optimized binding for on-the-same-machine communication between .NET applications.
<code>NetPeerTcpBinding</code>	<code><netPeerTcpBinding></code>	Provides a secure binding for P2P network applications.
<code>NetTcpBinding</code>	<code><netTcpBinding></code>	Serves as a secure and optimized binding suitable for cross-machine communication between .NET applications.

The `NetTcpBinding` class uses TCP to move binary data between the client and WCF service. As mentioned previously, this will result in higher performance than the web service protocols, but limits you to an in-house Windows solution. On the plus side, `NetTcpBinding` supports transactions, reliable sessions, and secure communications.

Like `NetTcpBinding`, `NetNamedPipeBinding` supports transactions, reliable sessions, and secure communications; however, it has no ability to make cross-machine calls. If you want to find the fastest way to push data between WCF applications on the same machine (e.g., cross-application domain communications), `NetNamedPipeBinding` is the binding choice of champions. For more information on `NetPeerTcpBinding`, consult the .NET Framework 4.0 documentation for details regarding P2P networking.

MSMQ-Based Bindings

Finally, the `NetMsmqBinding` and `MsmqIntegrationBinding` bindings are of immediate interest if you want to integrate with a Microsoft MSMQ server. This chapter will not examine the details of using MSMQ bindings, but Table 25-5 documents the basic role of each.

Table 25-5. The MSMQ-Centric WCF Bindings

Binding Class	Binding Element	Meaning in Life
<code>MsmqIntegrationBinding</code>	<code><msmqIntegrationBinding></code>	You can use this binding to enable WCF applications to send and receive messages to and from existing MSMQ applications that use COM, native C++, or the types defined in the <code>System.Messaging</code> namespace.
<code>NetMsmqBinding</code>	<code><netMsmqBinding></code>	You can use this queued binding for cross-machine communication between .NET applications. This is the preferred approach among the MSMQ-centric bindings.

Understanding WCF Addresses

Once you establish the contracts and bindings, the final piece of the puzzle is to specify an *address* for the WCF service. This is important because remote callers will be unable to communicate with the remote types if they cannot locate them! Like most aspects of WCF, an address can be hard-coded in an assembly (using the `System.Uri` type) or offloaded to a *.config file.

In either case, the exact format of the WCF address will differ based on your choice of binding (HTTP based, named pipes, TCP based, or MSMQ based). From a high level, WCF addresses can specify the following bits of information:

- Scheme: The transport protocol (e.g., HTTP)
- MachineName: The fully qualified domain of the machine
- Port: This is optional in many cases; for example, the default for HTTP bindings is port 80.
- Path: The path to the WCF service

This information can be represented by the following generalized template (the Port value is optional because some bindings don't use them):

`scheme://<MachineName>[:Port]/Path`

When you use a web service-based binding (e.g., `basicHttpBinding`, `wsHttpBinding`, `wsDualHttpBinding`, or `wsFederationHttpBinding`), the address breaks down like this (recall that HTTP-based protocols default to port 80 if you do not specify a port number):

`http://localhost:8080/MyWCFService`

If you use TCP-centric bindings (e.g., `NetTcpBinding` or `NetPeerTcpBinding`), the URI takes the following format:

`net.tcp://localhost:8080/MyWCFService`

The MSMQ-centric bindings (`NetMsmqBinding` and `MsmqIntegrationBinding`) are unique in their URI format because MSMQ can use public or private queues (which are available only on the local machine), and port numbers have no meaning in an MSMQ-centric URI. Consider the following URI, which describes a private queue named `MyPrivateQ`:

`net.msmq://localhost/private$/MyPrivateQ`

Last but not least, the address format used for the named-pipe binding, `NetNamedPipeBinding`, breaks down like this (recall that named pipes allow for interprocess communication for applications on the same physical machine):

`net.pipe://localhost/MyWCFService`

While a single WCF service might expose only a single address (based on a single binding), it is possible to configure a collection of unique addresses (with different bindings). You can do this in a `*.config` file by defining multiple `<endpoint>` elements. Here, you can specify any number of ABCs for the same service. This approach can be helpful when you want to allow callers to select which protocol they would like to use when communicating with the service.

Building a WCF Service

Now that you have a better understanding about the building blocks of a WCF application, it's time to create your first sample application and see how the ABCs are accounted for in code and configuration. This first example avoids using the Visual Studio 2010 WCF project templates, so you can focus on the specific steps involved in making a WCF service.

Begin by creating a new C# Class Library project named `MagicEightBallServiceLib`. Next, rename your initial file from `Class1.cs` to `MagicEightBallService.cs`, and then add a reference to the `System.ServiceModel.dll` assembly. In the initial code file, specify that you are using the `System.ServiceModel` namespace. At this point, your C# file should look like this:

```
using System;
using System.Collections.Generic;
using System.Linq;
using System.Text;

// The key WCF namespace.
using System.ServiceModel;

namespace MagicEightBallServiceLib
{
```

```
public class MagicEightBallService
{
}
}
```

Your class type implements a single WCF service contract represented by a strongly typed CLR interface named `IEightBall`. As you most likely know, the Magic 8-Ball is a toy that allows you to view one of a handful of fixed answers to a question you might ask. Your interface here will define a single method that allows the caller to pose a question to the Magic 8-Ball to obtain a random answer.

WCF service interfaces are adorned with the `[ServiceContract]` attribute, while each interface member is decorated with the `[OperationContract]` attribute (you'll learn more details regarding these two attributes in just a moment). Here is the definition of the `IEightBall` interface:

```
[ServiceContract]
public interface IEightBall
{
    // Ask a question, receive an answer!
    [OperationContract]
    string ObtainAnswerToQuestion(string userQuestion);
}
```

Note It is permissible to define a service contract interface that contains methods not adorned with the `[OperationContract]` attribute; however, such members will not be exposed through the WCF runtime.

As you know from your study of the interface type (see Chapter 9), interfaces are quite useless until they are implemented by a class or structure that fleshes out their functionality. Like a real Magic 8-Ball, the implementation of your service type (`MagicEightBallService`) will randomly return a canned answer from an array of strings. Also, your default constructor will display an information message that will be (eventually) displayed within the host's console window (for diagnostic purposes):

```
public class MagicEightBallService : IEightBall
{
    // Just for display purposes on the host.
    public MagicEightBallService()
    {
        Console.WriteLine("The 8-Ball awaits your question...");
    }

    public string ObtainAnswerToQuestion(string userQuestion)
    {
        string[] answers = { "Future Uncertain", "Yes", "No",
            "Hazy", "Ask again later", "Definitely" };

        // Return a random response.
        Random r = new Random();
        return answers[r.Next(answers.Length)];
    }
}
```

At this point, your WCF service library is complete. However, before you construct a host for this service, you need to examine some additional details of the [ServiceContract] and [OperationContract] attributes.

The [ServiceContract] Attribute

For a CLR interface to participate in the services provided by WCF, it must be adorned with the [ServiceContract] attribute. Like many other .NET attributes, the ServiceContractAttribute type supports many properties that further qualify its intended purpose. You can set two properties, Name and Namespace, to control the name of the service type and the name of the XML namespace that defines the service type. If you use a web service–specific binding, you use these values to define the <portType> elements of the related WSDL document.

Here, you do not bother to assign a Name value because the default name of the service type is directly based on the C# class name. However, the default name for the underlying XML namespace is simply <http://tempuri.org> (you should change this for all of your WCF services).

When you build a WCF service that will send and receive custom data types (which you are not currently doing), it is important that you establish a meaningful value to the underlying XML namespace because this ensures that your custom types are unique. As you might know from your experience building XML web services, XML namespaces provide a way to wrap your custom types in a unique container to ensure that your types do not clash with types in another organization.

For this reason, you can update your interface definition with a more fitting definition, which, much like the process of defining an XML namespace in a .NET Web Service project, is typically the URI of the service's point of origin, as in the following example:

```
[ServiceContract(Namespace = "http://MyCompany.com")]
public interface IEightBall
{
    ...
}
```

Beyond Namespace and Name, the [ServiceContract] attribute can be configured with the additional properties shown in Table 25-6. Be aware that some of these settings will be ignored, depending on your binding selection.

Table 25-6. Various Named Properties of the [ServiceContract] Attribute

Property	Meaning in Life
CallbackContract	Establishes whether this service contract requires callback functionality for two-way message exchange (e.g., duplex bindings).
ConfigurationName	You use this name to locate the service element in an application configuration file. The default is the name of the service implementation class.
ProtectionLevel	Allows you to specify the degree to which the contract binding requires encryption, digital signatures, or both for endpoints that expose the contract.

Table 25-6. Various Named Properties of the [ServiceContract] Attribute (continued)

Property	Meaning in Life
SessionMode	You use this to establish whether sessions are allowed, not allowed, or required by this service contract.

The [OperationContract] Attribute

Methods that you wish to use within the WCF framework must be attributed with the [OperationContract] attribute, which can also be configured with various named properties. You can use the properties shown in Table 25-7 to declare that a given method is intended to be one-way in nature, supports asynchronous invocation, requires encrypted message data, and so forth (again, many of these values might be ignored based on your binding selection).

Table 25-7. Various Named Properties of the [OperationContract] Attribute

Property	Meaning in Life
AsyncPattern	Indicates whether the operation is implemented asynchronously using a Begin/End method pair on the service. This allows the service to offload processing to another server-side thread; this has nothing to do with the client calling the method asynchronously!
IsInitiating	Specifies whether this operation can be the initial operation in a session.
IsOneWay	Indicates whether the operation consists of only a single input message (and no associated output).
IsTerminating	Specifies whether the WCF runtime should attempt to terminate the current session after the operation completes.

For the initial example, you don't need to configure the ObtainAnswerToQuestion() method with additional traits; this means you can use the [OperationContract] attribute as currently defined.

Service Types As Operational Contracts

Finally, recall that the use of interfaces is not required when building WCF service types. In fact, it is possible to apply the [ServiceContract] and [OperationContract] attributes directly to the service type itself:

```
// This is only for illustrative purposes
// and not used for the current example.
[ServiceContract(Namespace = "http://MyCompany.com")]
public class ServiceTypeAsContract
```

```
{
    [OperationContract]
    void SomeMethod() { }

    [OperationContract]
    void AnotherMethod() { }
}
```

You can take this approach; however, you receive many benefits if you explicitly define an interface type to represent the service contract. The most obvious benefit is that you can apply a given interface to multiple service types (authored in a variety of languages and architectures) to achieve a high degree of polymorphism. Another benefit: You can use a service contract interface as the basis of new contracts (using interface inheritance), without having to carry any implementation baggage.

In any case, your first WCF service library is now complete. Compile your project to ensure you do not have any typos.

Source Code You can find the `MagicEightBallServiceLib` project under the `MagicEightBallServiceHTTP` directory of Chapter 25.

Hosting the WCF Service

You are now ready to define a host. Although you would host a production-level service from a Windows service or an IIS virtual directory, you will make your first host a simple console named `MagicEightBallServiceHost`.

Once you create this new Console Application project, add a reference to the `System.ServiceModel.dll` and `MagicEightBallServiceLib.dll` assemblies, and then update your initial code file by importing the `System.ServiceModel` and `MagicEightBallServiceLib` namespaces:

```
using System;
using System.Collections.Generic;
using System.Linq;
using System.Text;

using System.ServiceModel;
using MagicEightBallServiceLib;

namespace MagicEightBallServiceHost
{
    class Program
    {
        static void Main(string[] args)
        {
            Console.WriteLine("***** Console Based WCF Host *****");
            Console.ReadLine();
        }
    }
}
```

The first step you must take when building a host for a WCF service type is to decide whether you want to define the necessary hosting logic completely in code or to relegate several low-level details to an application configuration file. As mentioned previously, the benefit of *.config files is that the host can change the underlying plumbing without requiring you to recompile and redeploy the executable. However, always remember this is strictly optional because you can hard-code the hosting logic using the types within the System.ServiceModel.dll assembly.

This console-based host will use an application configuration file, so insert a new Application Configuration File into your current project using the Project ➤ Add New Item menu option.

Establishing the ABCs Within an App.config File

When you build a host for a WCF service type, you follow a predictable set of steps—some that rely on configuration and some that rely on code:

1. Define the *endpoint* for the WCF service being hosted within the host's configuration file.
2. Programmatically use the ServiceHost type to expose the service types available from this endpoint.
3. Ensure the host remains running to service incoming client requests.
Obviously, this step is not required if you host your service types using a Windows service or IIS.

In the world of WCF, the term *endpoint* represents the address, binding, and contract rolled together in a nice, tidy package. In XML, an endpoint is expressed using the <endpoint> element and the address, binding, and contract elements. Update your *.config file to specify a single endpoint (reachable through port 8080) exposed by this host:

```
<?xml version="1.0" encoding="utf-8" ?>
<configuration>
  <system.serviceModel>
    <services>
      <service name="MagicEightBallServiceLib.MagicEightBallService">
        <endpoint address ="http://localhost:8080/MagicEightBallService"
                  binding="basicHttpBinding"
                  contract="MagicEightBallServiceLib.IEightBall"/>
      </service>
    </services>
  </system.serviceModel>
</configuration>
```

Notice that the <system.serviceModel> element is the root for all of a host's WCF settings. Each service exposed by the host is represented by a <service> element that is wrapped by the <services> base element. Here, your single <service> element uses the (optional) name attribute to specify the friendly name of the service type.

The nested <endpoint> element handles the task of defining the address, the binding model (basicHttpBinding, in this example), and the fully qualified name of the interface type defining the WCF service contract (IEightBall). Because you are using an HTTP-based binding, you use the http:// scheme, specifying an arbitrary port ID.

Coding Against the ServiceHost Type

With the current configuration file in place, the actual programming logic required to complete the host is simple. When your executable starts up, you will create an instance of the `ServiceHost` class and inform it which WCF service it is responsible for hosting. At runtime, this object will automatically read the data within the scope of the `<system.serviceModel>` element of the host's `*.config` file to determine the correct address, binding, and contract. It will then create the necessary plumbing:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Console Based WCF Host *****");

    using (ServiceHost serviceHost = new ServiceHost(typeof(MagicEightBallService)))
    {
        // Open the host and start listening for incoming messages.
        serviceHost.Open();

        // Keep the service running until the Enter key is pressed.
        Console.WriteLine("The service is ready.");
        Console.WriteLine("Press the Enter key to terminate service.");
        Console.ReadLine();
    }
}
```

If you run this application now, you will find that the host is alive in memory, ready to take incoming requests from remote clients.

Specifying Base Addresses

Currently, you create your `ServiceHost` using a constructor that requires only the service's type information. However, it is also possible to pass in an array of `System.Uri` types as a constructor argument to represent the collection of addresses this service is accessible from. Currently, you find the address using the `*.config` file. However, assume that you were to update the using scope like this:

```
using (ServiceHost serviceHost = new
    ServiceHost(typeof(MagicEightBallService),
    new Uri[]{new Uri("http://localhost:8080/MagicEightBallService")}))
{
    ...
}
```

If you did, you could now define your endpoint like this:

```
<endpoint address =""
           binding="basicHttpBinding"
           contract="MagicEightBallServiceLib.IEightBall"/>
```

Of course, too much hard-coding within a host's code base decreases flexibility. Therefore, the current host example assumes you create the service host simply by supplying the type information, as you did before:

```
using (ServiceHost serviceHost = new ServiceHost(typeof(MagicEightBallService)))
{
    ...
}
```

One of the (slightly frustrating) aspects of authoring host *.config files is that you have several ways to construct the XML descriptors, based on the amount of hard-coding you have in the code base (as you have just seen in the case of the optional Uri array). Here's a reworking that shows yet another way to author *.config files:

```
<?xml version="1.0" encoding="utf-8" ?>
<configuration>
    <system.serviceModel>
        <services>
            <service name="MagicEightBallServiceLib.MagicEightBallService">

                <!-- Address obtained from <baseAddresses> -->
                <endpoint address =""
                           binding="basicHttpBinding"
                           contract="MagicEightBallServiceLib.IEightBall"/>

                <!-- List all of the base addresses in a dedicated section-->
                <host>
                    <baseAddresses>
                        <add baseAddress ="http://localhost:8080/MagicEightBallService"/>
                    </baseAddresses>
                </host>
            </service>
        </services>
    </system.serviceModel>
</configuration>
```

In this case, the address attribute of the `<endpoint>` element is still empty; regardless of the fact that you do not specify an array of Uri objects in code when creating the `ServiceHost`, the application runs as before because the value is pulled from the `baseAddresses` scope. The benefit of storing the base address in a `<host>`'s `<baseAddresses>` region is that other parts of a *.config file (such as, which you'll learn about shortly) also need to know the address of the service's endpoint. Thus, rather than having to copy and pass address values within a single *.config file, you can isolate the single value, as shown in the preceding snippet.

Note In a later example, you'll be introduced to a graphical configuration tool that allows you to author configuration files in a less tedious manner.

In any case, you have a bit more work to do before you build a client application to communicate with your service. Specifically, you will dig a bit deeper into the role of the `ServiceHost` class type and `<service.serviceModel>` element, as well as the role of metadata exchange (MEX) services.

Details of the ServiceHost Type

You use the `ServiceHost` class type to configure and expose a WCF service from the hosting executable. However, be aware that you will only use this type directly when building a custom *.exe to host your services. If you use IIS (or the Vista and Windows 7 specific WAS) to expose a service, the `ServiceHost` object is created automatically on your behalf.

As you have seen, this type requires a complete service description, which is obtained dynamically through the configuration settings of the host's *.config file. While this happens automatically when you create a `ServiceHost` object, it is possible to configure the state of your `ServiceHost` object manually using a number of members. In addition to `Open()` and `Close()` (which communicate with your service in a synchronous manner), Table 25-8 illustrates some further members of interest.

Table 25-8. Select Members of the `ServiceHost` Type

Members	Meaning in Life
<code>Authorization</code>	This property gets the authorization level for the service being hosted.
<code>AddDefaultEndpoints()</code>	This method is new to .NET 4.0, and you can use it to configure a WCF service host programmatically so it uses any number of prebuilt endpoints supplied by the framework.
<code>AddServiceEndpoint()</code>	This method allows you to register an endpoint to the host programmatically.
<code>BaseAddresses</code>	This property obtains the list of registered base addresses for the current service.
<code>BeginOpen()</code> <code>BeginClose()</code>	These methods allow you to open and close a <code>ServiceHost</code> object asynchronously, using the standard asynchronous .NET delegate syntax.
<code>CloseTimeout</code>	This property allows you to set and get the time allowed for the service to close down.
<code>Credentials</code>	This property obtains the security credentials used by the current service.
<code>EndOpen()</code> <code>EndClose()</code>	These methods are the asynchronous counterparts to <code>BeginOpen()</code> and <code>BeginClose()</code> .
<code>OpenTimeout</code>	This property allows you to set and get the time allowed for the service to start up.

Table 25-8. Select Members of the ServiceHost Type (continued)

Members	Meaning in Life
State	This property gets a value that indicates the current state of the communication object, which is represented by the <code>CommunicationState</code> enum (e.g., opened, closed, and created).

You can see some additional aspects of `ServiceHost` in action by updating your `Program` class with a new static method that prints out the ABCs of each endpoint used by the host:

```
static void DisplayHostInfo(ServiceHost host)
{
    Console.WriteLine();
    Console.WriteLine("***** Host Info *****");

    foreach (System.ServiceModel.Description.ServiceEndpoint se
        in host.Description.Endpoints)
    {
        Console.WriteLine("Address: {0}", se.Address);
        Console.WriteLine("Binding: {0}", se.Binding.Name);
        Console.WriteLine("Contract: {0}", se.Contract.Name);
        Console.WriteLine();
    }
    Console.WriteLine("*****");
}
```

Now assuming that you call this new method from within `Main()` after opening your host:

```
using (ServiceHost serviceHost = new ServiceHost(typeof(MagicEightBallService)))
{
    // Open the host and start listening for incoming messages.
    serviceHost.Open();
    DisplayHostInfo(serviceHost);
...
}
```

Doing this will generate the statistics shown in the following output:

```
***** Console Based WCF Host *****
***** Host Info *****
Address: http://localhost:8080/MagicEightBallService
Binding: BasicHttpBinding
Contract: IEightBall
*****
The service is ready.
Press the Enter key to terminate service.
```

Details of the <system.serviceModel> Element

Like any XML element, <system.serviceModel> can define a set of sub-elements, each of which can be qualified using various attributes. While you should consult the .NET Framework 4.0 SDK documentation for full details regarding the set of possible attributes, here is a skeleton that lists the critical sub-elements:

```
<system.serviceModel>
  <behaviors>
  </behaviors>
  <client>
  </client>
  <commonBehaviors>
  </commonBehaviors>
  <diagnostics>
  </diagnostics>
  <comContracts>
  </comContracts>
  <services>
  </services>
  <bindings>
  </bindings>
</system.serviceModel>
```

You'll see more exotic configuration files as you move through the chapter; however, you can see the crux of each sub-element in Table 25-9.

Table 25-9. Sub-elements of <service.serviceModel>

Sub-element	Meaning in Life
behaviors	WCF supports various endpoint and service behaviors. In a nutshell, a <i>behavior</i> allows you to qualify further the functionality of a host, service, or client.
bindings	This element allows you to fine-tune each of the WCF-supplied bindings (e.g., basicHttpBinding and netMsmqBinding), as well as to specify any custom bindings used by the host.
client	This element contains a list of endpoints a client uses to connect to a service. Obviously, this is not particularly useful in a host's *.config file.
comContracts	This element defines COM contracts enabled for WCF and COM interoperability.
commonBehaviors	This element can only be set within a machine.config file. You can use it to define all of the behaviors used by each WCF service on a given machine.

Table 25-9. Sub-elements of `<service.serviceModel>` (continued)

Sub-element	Meaning in Life
diagnostics	This element contains settings for the diagnostic features of WCF. The user can enable/disable tracing, performance counters, and the WMI provider; the user can also add custom message filters.
services	This element contains a collection of WCF services exposed by the host.

Enabling Metadata Exchange

Recall that WCF client applications communicate with the WCF service through an intervening proxy type. While you could author the proxy code completely by hand, doing so would be tedious and error-prone. Ideally, you could use a tool to generate the necessary grunge code (including the client-side `*.config` file). Thankfully, the .NET Framework 4.0 SDK provides a command-line tool (`svchost.exe`) for this purpose. Also, Visual Studio 2010 provides similar functionality through its Project ➤ Add Service Reference menu option.

For these tools to generate the necessary proxy code/`*.config` file, however, they must be able to discover the format of the WCF service interfaces and any defined data contracts (e.g., the method names and type of parameters).

Metadata exchange (MEX) is a WCF *service behavior* that you can use to fine-tune how the WCF runtime handles your service. Simply put, each `<behavior>` element can define a set of activities a given service can subscribe to. WCF provides numerous behaviors out of the box, and it is possible to build your own.

The MEX behavior (which is disabled by default) will intercept any metadata requests sent through HTTP GET. You must enable MEX if you want to allow `svchost.exe` or Visual Studio 2010 to automate the creation of the required client-side proxy `*.config` file.

Enabling MEX is a matter of tweaking the host's `*.config` file with the proper settings (or authoring the corresponding C# code). First, you must add a new `<endpoint>` just for MEX. Second, you need to define a WCF behavior to allow HTTP GET access. Third, you need to associate this behavior by name to your service using the `behaviorConfiguration` attribute on the opening `<service>` element. Finally, you need to add a `<host>` element to define the base address of this service (MEX will look here to figure out the locations of the types to describe).

■ **Note** You can bypass this final step if you pass in a `System.Uri` object to represent the base address as a parameter to the `ServiceHost` constructor.

Consider the following updated host `*.config` file, which creates a custom `<behavior>` element (named `EightBallServiceMEXBehavior`) that is associated to your service through the `behaviorConfiguration` attribute within the `<service>` definition:

```

<?xml version="1.0" encoding="utf-8" ?>
<configuration>
  <system.serviceModel>
    <services>
      <service name="MagicEightBallServiceLib.MagicEightBallService"
              behaviorConfiguration = "EightBallServiceMEXBehavior">
        <endpoint address =""
                  binding="basicHttpBinding"
                  contract="MagicEightBallServiceLib.IEightBall"/>

        <!-- Enable the MEX endpoint -->
        <endpoint address="mex"
                  binding="mexHttpBinding"
                  contract="IMetadataExchange" />

        <!-- Need to add this so MEX knows the address of our service -->
        <host>
          <baseAddresses>
            <add baseAddress ="http://localhost:8080/MagicEightBallService"/>
          </baseAddresses>
        </host>
      </service>
    </services>

    <!-- A behavior definition for MEX -->
    <behaviors>
      <serviceBehaviors>
        <behavior name="EightBallServiceMEXBehavior" >
          <serviceMetadata httpGetEnabled="true" />
        </behavior>
      </serviceBehaviors>
    </behaviors>
  </system.serviceModel>
</configuration>

```

You can now restart the service and view its metadata description using the web browser of your choice. To do so, enter the address as the URL while the host is still running:

<http://localhost:8080/MagicEightBallService>

Once you are at the homepage for your WCF service (see Figure 25-6), you are provided with basic details regarding how to interact with this service programmatically, as well as a way to view the WSDL contract by clicking the hyperlink at the top of the page. Recall that Web Service Description Language (WSDL) is a grammar that describes the structure of web services at a given endpoint.




Figure 25-6. Ready to view metadata using MEX

Your host now exposes two different endpoints (one for the service and one for MEX), so your host's console output will appear like this:

```
***** Console Based WCF Host *****

***** Host Info *****
Address: http://localhost:8080/MagicEightBallService
Binding: BasicHttpBinding
Contract: IEightBall

Address: http://localhost:8080/MagicEightBallService/mex
Binding: MetadataExchangeHttpBinding
Contract: IMetadataExchange
*****
```

The service is ready.

Source Code You can find the MagicEightBallServiceHost project under the MagicEightBallServiceHTTP directory of Chapter 25.

Building the WCF Client Application

Now that your host is in place, the final task is to build a piece of software to communicate with this WCF service type. While you could take the long road and build the necessary infrastructure by hand (a feasible, but labor-intensive task), the .NET Framework 4.0 SDK provides several approaches to generate a client-side proxy quickly. Begin by creating a new Console Application named `MagicEightBallServiceClient`.

Generating Proxy Code Using `svctutil.exe`

The first way you can build a client-side proxy is to use the `svctutil.exe` command-line tool. Using `svctutil.exe`, you can generate a new C# language file that represents the proxy code itself, as well as a client-side configuration file. You can do this by specifying the service's endpoint as the first parameter. You use the `/out:` flag to define the name of the `*.cs` file containing the proxy, and you use the `/config:` option to specify the name of the generated client-side `*.config` file.

Assuming your service is currently running, the following command set passed into `svctutil.exe` will generate two new files in the working directory (which should, of course, be entered as a single line within a Visual Studio 2010 command prompt):

```
svctutil http://localhost:8080/MagicEightBallService
          /out:myProxy.cs /config:app.config
```

If you open the `myProxy.cs` file, you will find a client-side representation of the `IEightBall` interface, as well as a new class named `EightBallClient`, which is the proxy class itself. This class derives from the generic class, `System.ServiceModel.ClientBase<T>`, where `T` is the registered service interface.

In addition to a number of custom constructors, each method of the proxy (which is based on the original interface methods) will be implemented to use the inherited `Channel` property to invoke the correct service method. Here is a partial snapshot of the proxy type:

```
[System.Diagnostics.DebuggerStepThrough()]
[System.CodeDom.Compiler.GeneratedCodeAttribute("System.ServiceModel",
    "4.0.0.0")]
public partial class EightBallClient :
    System.ServiceModel.ClientBase<IEightBall>, IEightBall
{
    ...
    public string ObtainAnswerToQuestion(string userQuestion)
    {
        return base.Channel.ObtainAnswerToQuestion(userQuestion);
    }
}
```

When you create an instance of the proxy type in your client application, the base class will establish a connection to the endpoint using the settings specified in the client-side application configuration file. Much like the server-side configuration file, the generated client-side `App.config` file contains an `<endpoint>` element and details about the `basicHttpBinding` used to communicate with the service.

You will also find the following `<client>` element, which (again) establishes the ABCs from the client's perspective:

```
<client>
<endpoint
  address="http://localhost:8080/MagicEightBallService"
  binding="basicHttpBinding" bindingConfiguration="BasicHttpBinding_IEightBall"
  contract="IEightBall" name="BasicHttpBinding_IEightBall" />
</client>
```

At this point, you could include these two files into a client project (and reference the `System.ServiceModel.dll` assembly), and then use the proxy type to communicate with the remote WCF service. However, you'll take a different approach here, looking at how Visual Studio can help you further automate the creation of client-side proxy files.

Generating Proxy Code Using Visual Studio 2010

Like any good command-line tool, `svcutil.exe` provides a great number of options that you can use to control how the client proxy is generated. If you do not require these advanced options, you can generate the same two files using the Visual Studio 2010 IDE. For the client project, simply select the Add Service Reference option from the Project menu.

Once you activate this menu option, you will be prompted to enter the service URI. At this point, click the Go button to see the service description (see Figure 25-7).




Figure 25-7. Generating the proxy files using Visual Studio 2010

Beyond creating and inserting the proxy files into your current project, this tool is kind enough to reference the WCF assemblies automatically on your behalf. In accordance with a naming convention, the proxy class is defined within a namespace called ServiceReference, which is nested in the client's namespace (to avoid possible name clashes). Here is the complete client code:

```
// Location of the proxy.  
using MagicEightBallServiceClient.ServiceReference1;  
  
namespace MagicEightBallServiceClient  
{  
    class Program  
    {  
        static void Main(string[] args)  
        {  
            Console.WriteLine("***** Ask the Magic 8 Ball *****\n");  
  
            using (EightBallClient ball = new EightBallClient())  
            {  
                Console.Write("Your question: ");  
                string question = Console.ReadLine();  
                string answer =  
                    ball.ObtainAnswerToQuestion(question);  
                Console.WriteLine("8-Ball says: {0}", answer);  
            }  
            Console.ReadLine();  
        }  
    }  
}
```

Now assume your WCF console host is running, so you can execute the client. Here is one possible response to a question I've been asking quite a bit during the authoring of this edition of the book (with apologies to fine folks at Apress!)

```
***** Ask the Magic 8 Ball *****
```

```
Your question: Will I get this book done soon?  
8-Ball says: No
```

```
Press any key to continue . . .
```

■ **Source Code** You can find the MagicEightBallServiceClient project located under the MagicEightBallServiceHTTP directory of Chapter 25.

Configuring a TCP-Based Binding

At this point, the host and client applications are both configured to use the simplest of the HTTP-based bindings, `basicHttpBinding`. Recall that the benefit of offloading settings to configuration files is that you can change the underlying plumbing in a declarative manner and expose multiple bindings for the same service.

To illustrate this, you can try a little experiment. Create a new folder on your C: drive (or wherever you happen to be saving your code) named EightBallTCP; in this new folder, create two subdirectories named Host and Client.

Next, use Windows Explorer to navigate to the `\bin\Debug` folder of the host project and copy `MagicEightBallServiceHost.exe`, `MagicEightBallServiceHost.exe.config`, and `MagicEightBallServiceLib.dll` to the `C:\EightBallTCP\Host` folder. Now use a simple text editor to open the `*.config` file for editing and modify the existing contents as follows:

```
<?xml version="1.0" encoding="utf-8" ?>
<configuration>
  <system.serviceModel>
    <services>
      <service name="MagicEightBallServiceLib.MagicEightBallService">
        <endpoint address =""
          binding="netTcpBinding"
          contract="MagicEightBallServiceLib.IEightBall"/>
      </host>
      <baseAddresses>
        <add baseAddress = "net.tcp://localhost:8090/MagicEightBallService"/>
      </baseAddresses>
    </host>
  </services>
</system.serviceModel>
</configuration>
```

Essentially, this host's `*.config` file strips out all the MEX settings (because you already built the proxy) and establishes that it is using the `netTcpBinding` binding type through a unique port. Now run the application by double-clicking the `*.exe`. If all is well, you should see the host output shown here:

```
***** Console Based WCF Host *****

***** Host Info *****
Address: net.tcp://localhost:8090/MagicEightBallService
Binding: NetTcpBinding
Contract: IEightBall

*****
The service is ready.
Press the Enter key to terminate service.
```

To complete the test, copy the `MagicEightBallServiceClient.exe` and `MagicEightBallServiceClient.exe.config` files from the `\bin\Debug` folder of the client application into the `C:\EightBallTCP\Client` folder. Update the client configuration file like this:

```
<?xml version="1.0" encoding="utf-8" ?>
<configuration>
  <system.serviceModel>
    <client>
      <endpoint address="net.tcp://localhost:8090/MagicEightBallService"
        binding="netTcpBinding"
        contract="ServiceReference1.IEightBall"
        name="netTcpBinding_IEightBall" />
    </client>
  </system.serviceModel>
</configuration>
```

This client-side configuration file is a massive simplification compared to what the Visual Studio proxy generator authored. Notice how you have completely removed the existing `<bindings>` element. Originally, the `*.config` file contained a `<bindings>` element with a `<basicHttpBinding>` sub-element that supplied numerous details of the client's binding settings (e.g., timeouts).

The truth is you never needed that detail for this example because you automatically obtain the default values of the underlying `BasicHttpBinding` object. If you needed to, you could of course update the existing `<bindings>` element to define details of the `<netTcpBinding>` sub-element; however, doing so is not required if you are happy with the default values of the `NetTcpBinding` object.

In any case, you should now be able to run your client application. Assuming the host is still running in the background, you will be able to move data between your assemblies using TCP.

Source Code You can find the `MagicEightBallTCP` project under the Chapter 25 subdirectory.

Simplifying Configuration Settings with WCF 4.0

As you were working through the first example of the chapter, you might have noticed that the hosting configuration logic is quite verbose. For example, your host's `*.config` file (for the original basic HTTP binding) needed to define an `<endpoint>` element for the service, a second `<endpoint>` element for MEX, a `<baseAddresses>` element (technically optional) to reduce redundant URIs, and then a `<behaviors>` section to define the runtime nature of metadata exchange.

To be sure, learning how to author hosting `*.config` files can be a major hurdle when building WCF services. To make matters more frustrating, a good number of WCF services tend to require the same basic settings in a host configuration file. For example, if you were to make a brand new WCF service and a brand new host, and you wanted to expose this service using `<basicHttpBinding>` with MEX support, the required `*.config` file would look almost identical to the one you previously authored.

Thankfully, under .NET 4.0, the Windows Communication Foundation API ships with a number of simplifications, including default settings (and other shortcuts) that make the process of building host configuration files much easier.

Default Endpoints in WCF 4.0

Under .NET 3.5, if you call `Open()` on the `ServiceHost` object, and you have not yet specified at least one `<endpoint>` element in your configuration file, the runtime will throw an exception. And you get a similar result if you call `AddServiceEndpoint()` in code to specify an endpoint. However, with the release of .NET 4.0, every WCF service is automatically provided with *default endpoints* that capture commonplace configuration details for each supported protocol.

If you were to open the `machine.config` file for .NET 4.0, you would find a new element named `<protocolMapping>`. This element documents which WCF bindings to use by default, if you do not specify any:

```
<system.serviceModel>
...
<protocolMapping>
    <add scheme="http" binding="basicHttpBinding"/>
    <add scheme="net.tcp" binding="netTcpBinding"/>
    <add scheme="net.pipe" binding="netNamedPipeBinding"/>
    <add scheme="net.msmq" binding="netMsmqBinding"/>
</protocolMapping>
...
</system.serviceModel>
```

To use these default bindings, all you need to do is specify base addresses in your host configuration file. To see this in action, open the HTTP-based `MagicEightBallServiceHost` project in Visual Studio. Now update your hosting `*.config` file by completely removing the `<endpoint>` element for your WCF service and all MEX-specific data. Your configuration file should now look like this:

```
<configuration>
    <system.serviceModel>
        <services>
            <service name="MagicEightBallServiceLib.MagicEightBallService" >
                <host>
                    <baseAddresses>
                        <add baseAddress="http://localhost:8080/MagicEightBallService"/>
                    </baseAddresses>
                </host>
            </service>
        </services>
    </system.serviceModel>
</configuration>
```

Because you specified a valid HTTP `<baseAddress>`, your host will automatically use `basicHttpBinding`. If you run your host again, you will see the same listing of ABC data:

***** Console Based WCF Host *****

***** Host Info *****
 Address: `http://localhost:8080/MagicEightBallService`
 Binding: `BasicHttpBinding`
 Contract: `IEightBall`

```
*****
```

The service is ready.
Press the Enter key to terminate service.

You have not yet enabled MEX, but you will do so in a moment using another .NET 4.0 simplification known as *default behavior configurations*. First, however, you will learn how to expose a single WCF service using multiple bindings.

Exposing a Single WCF Service Using Multiple Bindings

Since its first release, WCF has had the ability to allow a single host to expose a WCF service using multiple endpoints. For example, you could expose the MagicEightBallService using HTTP, TCP, and named pipe bindings simply by adding new endpoints to your configuration file. Once you restart the host, all of the necessary plumbing is created automatically.

This is a huge benefit for many reasons. Before WCF, it was difficult to expose a single service using multiple bindings because each type of binding (e.g., HTTP and TCP) had its own programming model. Nevertheless, the ability to allow a caller to pick the most appropriate binding is extremely useful. In-house callers might like to use TCP bindings that an outwardly facing client (outside of your company firewall) would need to use HTTP to access, while clients on the same machine might wish to use a named pipe.

To do this before .NET 4.0, your hosting configuration file would need to define multiple `<endpoint>` elements manually. It would also have to define multiple `<baseAddress>` elements for each protocol. However, today you can simply author the following configuration file:

```
<configuration>
  <system.serviceModel>
    <services>
      <service name="MagicEightBallServiceLib.MagicEightBallService" >
        <host>
          <baseAddresses>
            <add baseAddress="http://localhost:8080/MagicEightBallService"/>
            <add baseAddress=
                  "net.tcp://localhost:8099/MagicEightBallService"/>
          </baseAddresses>
        </host>
      </service>
    </services>
  </system.serviceModel>
</configuration>
```

If you compile your project (to refresh the deployed *.config file) and restart the host, you would now see the following endpoint data:

```
***** Console Based WCF Host *****
```

```
***** Host Info *****
Address: http://localhost:8080/MagicEightBallService
Binding: BasicHttpBinding
Contract: IEightBall
```

```
Address: net.tcp://localhost:8099/MagicEightBallService
Binding: NetTcpBinding
Contract: IEightBall
```

```
*****
```

The service is ready.
Press the Enter key to terminate service.

Now that your WCF service can be reachable from two unique endpoints, you might wonder how the caller is able to select between them. When you generate a client-side proxy, the Add Service reference tool will give each exposed endpoint a string name in the client side *.config file. In code, you can pass in the correct string name to the proxy's constructor, and sure enough, the correct binding will be used. Before you can do this, however, you need to reestablish MEX for this modified hosting configuration file and learn how to tweak the settings of a default binding.

Changing Settings for a WCF Binding

If you specify the ABCs of a service in C# code (which you will do later in this chapter), it becomes obvious how you change the default settings of a WCF binding; you simply change the property values of the object! For example, if you want to use `BasicHttpBinding`, but also want to change the timeout settings, you could do so as follows:

```
void ConfigureBindingInCode()
{
    BasicHttpBinding binding = new BasicHttpBinding();
    binding.OpenTimeout = TimeSpan.FromSeconds(30);
    ...
}
```

It has always been possible to configure settings for a binding in a declarative manner. For example,.NET 3.5 let you build a host configuration file that changes the `OpenTimeout` property of `BasicHttpBinding`:

```
<configuration>
  <system.serviceModel>

    <bindings>
      <basicHttpBinding>
        <binding name = "myCustomHttpBinding"
          openTimeout = "00:00:30" />
      </basicHttpBinding>
    </bindings>

    <services>
      <service name = "WcfMathService.MyCalc">
        <endpoint address = "http://localhost:8080/MyCalc"
          binding = "basicHttpBinding"
          bindingConfiguration = "myCustomHttpBinding"
          contract = "WcfMathService.IBasicMath" />
      </service>
    </services>
  </system.serviceModel>
</configuration>
```

```

</service>
</services>
</system.serviceModel>
</configuration>

```

Here, you have a configuration file for a service named `WcfMathService.MyCalc`, which supports a single interface named `IBasicMath`. Note how the `<bindings>` section allows you to define a named `<binding>` element, which tweaks settings for a given binding. Within the `<endpoint>` of the service, you can connect your specific settings using the `bindingConfiguration` attribute.

This sort of hosting configuration still works as expected under .NET 4.0; however if you leverage a default endpoint, you can't connect the `<binding>` to the `<endpoint>`! As luck would have it, you can control the settings of a default endpoint simply by omitting the name attribute of the `<binding>` element. For example, this snippet changes some properties of the default `BasicHttpBinding` and `NetTcpBinding` objects used in the background:

```

<configuration>
  <system.serviceModel>
    <services>
      <service name="MagicEightBallServiceLib.MagicEightBallService" >
        <host>
          <baseAddresses>
            <add baseAddress="http://localhost:8080/MagicEightBallService"/>
            <add baseAddress=
                  "net.tcp://localhost:8099/MagicEightBallService"/>
          </baseAddresses>
        </host>
      </service>
    </services>

    <bindings>
      <basicHttpBinding>
        <binding openTimeout = "00:00:30" />
      </basicHttpBinding>
      <netTcpBinding>
        <binding closeTimeout="00:00:15"/>
      </netTcpBinding>
    </bindings>
  </system.serviceModel>
</configuration>

```

The WCF 4.0 Default MEX Behavior Configuration

A proxy generation tool must discover the composition of a service at runtime before it can do its work. In WCF, you allow this runtime discovery to occur by enabling MEX. Again, most host configuration files need to enable MEX (at least during development); fortunately, the way you configure MEX seldom changes, so .NET 4.0 provides a few handy shortcuts.

The most useful shortcut is out-of-the-box MEX support. You don't need to add a MEX endpoint, define a named MEX service behavior, and then connect the named binding to the service (as you did in the HTTP version of the `MagicEightBallServiceHost`); instead, you can now simply add the following:

```

<configuration>
  <system.serviceModel>
    <services>
      <service name="MagicEightBallServiceLib.MagicEightBallService" >
        <host>
          <baseAddresses>
            <add baseAddress="http://localhost:8080/MagicEightBallService"/>
            <add baseAddress=
                  "net.tcp://localhost:8099/MagicEightBallService"/>
          </baseAddresses>
        </host>
      </service>
    </services>

    <bindings>
      <basicHttpBinding>
        <binding openTimeout = "00:00:30" />
      </basicHttpBinding>
      <netTcpBinding>
        <binding closeTimeout="00:00:15"/>
      </netTcpBinding>
    </bindings>

    <behaviors>
      <serviceBehaviors>
        <behavior>
          <!-- To get default MEX,
              don't name your <serviceMetadata> element-->
          <serviceMetadata httpGetEnabled="true"/>
        </behavior>
      </serviceBehaviors>
    </behaviors>
  </system.serviceModel>
</configuration>

```

The trick is that the `<serviceMetadata>` element no longer has a `name` attribute (also notice the `<service>` element no longer needs the `behaviorConfiguration` attribute). With this adjustment, you get free MEX support at runtime. To test this, you can run your host (after you compile to refresh the configuration file) and type in the following URL in a browser:

`http://localhost:8080/MagicEightBallService`

Once you do this, you can click the `wsdl` link at the top of the web page to see the WSDL description of the service (see Figure 25-6 for a refresher). Note that you do not see the host's console window print out data for the MEX endpoint because you have not explicitly defined an endpoint for `IMetadataExchange` in your configuration file. Nevertheless, MEX is enabled, and you can start to build client proxies.

Refreshing the Client Proxy and Selecting the Binding

Assuming your updated host has been compiled and is running in the background, you will now want to open the client application and refresh the current service reference. Begin by opening the Service References folder found in the Solution Explorer. Next, right-click the current ServiceReference and pick the Update Service Reference menu option (see Figure 25-8).




Figure 25-8. Refreshing the proxy and client side *.config file

Once you done this, you will see that the client side *.config file has two bindings to select from: one for HTTP and one for TCP. As you can see, you give each binding a fitting name. Here is a partial listing of the refreshed configuration file:

```
<configuration>
  <system.serviceModel>

    <bindings>
      <basicHttpBinding>
        <binding name="BasicHttpBinding_IEightBall" ... />
      </basicHttpBinding>

      <netTcpBinding>
        <binding name="NetTcpBinding_IEightBall" ... />
      </netTcpBinding>
    </bindings>
  ...
  </system.serviceModel>
</configuration>
```

The client can use these names when it creates the proxy object to select the binding it wishes to use. Thus, if your client would like to use TCP, you could update the client side C# code as follows:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Ask the Magic 8 Ball *****\n");

    using (EightBallClient ball = new EightBallClient("NetTcpBinding_IEightBall"))
    {
        ...
    }
    Console.ReadLine();
}
```

If a client would rather use the HTTP binding, you could write:

```
using (EightBallClient ball = new
    EightBallClient("BasicHttpBinding_IEightBall"))
{
...
}
```

That wraps up the current example, which showcased a number of WCF 4.0's useful features. These features simplify how you can author hosting configuration files. Next up, you will see how to use the WCF Service Library Project template.

■ Source Code You can find the `MagicEightBallServiceHTTPDefaultBindings` project located under the Chapter 25 subdirectory.

Using the WCF Service Library Project Template

You need to do one more thing before you build a more exotic WCF service that communicates with the AutoLot database you created in Chapter 21. The next example will illustrate a number of important topics, including the benefits of the WCF Service Library project template, the WCF Test Client, the WCF configuration editor, hosting WCF services within a Windows service, and asynchronous client calls. To stay focused on these new concepts, this WCF service will be kept intentionally simple.

Building a Simple Math Service

To begin, create a brand-new WCF Service Library project named `MathServiceLibrary`, making sure you select the correct option under the WCF node of the New Project dialog box (see Figure 25-2 if you need a nudge). Now change the name of the initial `IService1.cs` file to `IBasicMath.cs`. Once you do so, *delete* all of the example code within the `MathServiceLibrary` namespace and replace it with the following code:

```
[ServiceContract(Namespace="http://MyCompany.com")]
public interface IBasicMath
{
    [OperationContract]
    int Add(int x, int y);
}
```

Next, change the name of the Service1.cs file to MathService.cs, delete all the example code within the MathServiceLibrary namespace (again), and implement your service contract as follows:

```
public class MathService : IBasicMath
{
    public int Add(int x, int y)
    {
        // To simulate a lengthy request.
        System.Threading.Thread.Sleep(5000);
        return x + y;
    }
}
```

Finally, open the supplied App.config file and verify all occurrences of IService1 with IBasicMath, as well as all occurrences of Service1 with MathService. Also take a moment to notice that this *.config file has already been enabled to support MEX; by default, your service endpoint uses the wsHttpBinding protocol.

Testing the WCF Service with WcfTestClient.exe

One benefit of using the WCF Service Library project is that when you debug or run your library, it will read the settings in the *.config file and use them to load the WCF Test Client application (WcfTestClient.exe). This GUI-based application allows you to test each member of your service interface as you build the WCF service; this means you don't have to build a host/client manually simply for testing purposes, as you did previously.

Figure 25-9 shows the testing environment for MathService. Notice that when you double-click an interface method, you can specify input parameters and invoke the member.




Figure 25-9. Testing the WCF service using *WcfTestClient.exe*

This utility works out of the box when you have created a WCF Service Library project; however, be aware that you can use this tool to test any WCF service when you start it at the command line by specifying a MEX endpoint. For example, if you were to start the *MagicEightBallServiceHost.exe* application, you could specify the following command at a Visual Studio 2010 command prompt:

```
wcftestclient http://localhost:8080/MagicEightBallService
```

Once you do this, you can invoke *ObtainAnswerToQuestion()* in a similar manner.

Altering Configuration Files Using SvcConfigEditor.exe

Another benefit of making use of the WCF Service Library project is that you are able to right-click on the *App.config* file within the Solution Explorer to activate the GUI-based Service Configuration Editor, *SvcConfigEditor.exe* (see Figure 29-10). This same technique can be used from a client application that has referenced a WCF service.




Figure 25-10. GUI-based *.config file editing starts here

Once you activate this tool, you can change the XML-based data using a friendly user interface. Using a tool such as this to maintain your *.config files provides many benefits. First (and foremost), you can rest assured that the generated markup conforms to the expected format and is typo-free. Second, it is a great way to see the valid values that could be assigned to a given attribute. Finally, you no longer need to author tedious XML data manually.

Figure 25-11 shows the overall look-and-feel of the Service Configuration Editor. Truth be told, an entire chapter could be devoted to describing all of the interesting options SvcConfigEditor.exe supports (e.g., COM+ integration and creation of new *.config files). Be sure to take time to investigate this tool; also be aware that you can access a fairly detailed help system by pressing F1.

Note The SvcConfigEditor.exe utility can edit (or create) configuration files, even if you do not select an initial WCF Service Library project. Use a Visual Studio 2010 command window to launch the tool, and then use the File > Open menu option to load an existing *.config file for editing.




Figure 25-11. Working with the WCF Service Configuration Editor

You have no need to further configure your WCF MathService; at this point, you can move on to the task of building a custom host.

Hosting the WCF Service within a Windows Service

Hosting a WCF service from within a console application (or within a GUI desktop application, for that matter) is not an ideal choice for a production-level server, given that the host must remain running visibly in the background to service clients. Even if you were to minimize the hosting application to the Windows taskbar, it would still be far too easy to accidentally shut down the host, thereby terminating the connection with any client applications.

■ **Note** While it is true that a desktop Windows application does not *have* to show a main window, a typical *.exe does require user interaction to load the executable. However, you can configure a Windows service (described next) to run even if no users are currently logged on to the workstation.

If you build an in-house WCF application, another alternative you have is to host your WCF service library from within a dedicated Windows service. One benefit of doing so is that you can configure a Windows service to start automatically when the target machine boots up. Another benefit is that

Windows services run invisibly in the background (unlike your console application) and do not require user interactivity.

Next, you will learn how to build such a host. Begin by creating a new Windows service project named MathWindowsServiceHost (see Figure 25-12). Once you do this, rename your initial Service1.cs file to MathWinService.cs using Solution Explorer.




Figure 25-12. Creating a Windows service to host your WCF service

Specifying the ABCs in Code

Now assume you have set a reference to your MathServiceLibrary.dll and System.ServiceModel.dll assemblies. All you need to do is use the ServiceHost type in the OnStart() and OnStop() methods of your Windows service type. Open the code file for your service host class (by right-clicking the designer and selecting View Code) and add the following logic:

```
// Be sure to import these namespaces:
using MathServiceLibrary;
using System.ServiceModel;

namespace MathWindowsServiceHost
{
    public partial class MathWinService: ServiceBase
    {
        // A member variable of type ServiceHost.
        private ServiceHost myHost;

        public MathWinService()
        {
```

```

        InitializeComponent();
    }

    protected override void OnStart(string[] args)
    {
        // Just to be really safe.
        if (myHost != null)
        {
            myHost.Close();
            myHost = null;
        }

        // Create the host.
        myHost = new ServiceHost(typeof(MathService));

        // The ABCs in code!
        Uri address = new Uri("http://localhost:8080/MathServiceLibrary");
        WSHttpBinding binding = new WSHttpBinding();
        Type contract = typeof(IBasicMath);

        // Add this endpoint.
        myHost.AddServiceEndpoint(contract, binding, address);

        // Open the host.
        myHost.Open();
    }

    protected override void OnStop()
    {
        // Shut down the host.
        if(myHost != null)
            myHost.Close();
    }
}

```

While nothing prevents you from using a configuration file when building a Windows service host for a WCF service, here (for a change of pace) you establish the endpoint programmatically using the Uri, WSHttpBinding, and Type classes, rather than by using a *.config file. Once you create each aspect of the ABCs, you inform the host programmatically by calling AddServiceEndpoint().

If you wish to inform the runtime that you want to gain access to each of the default endpoint bindings stored in the .NET 4.0 machine.config file, you can simplify your programming logic by specifying base addresses when you invoke the constructor of ServiceHost. In this case, you do not need to specify the ABCs manually in code or call AddServiceEndpoint(); instead, you call AddDefaultEndpoints(). Consider the following update:

```

protected override void OnStart(string[] args)
{
    if (myHost != null)
    {
        myHost.Close();
    }
}

```

```

// Create the host and specify a URL for an HTTP binding.
myHost = new ServiceHost(typeof(MathService),
    new Uri("http://localhost:8080/MathServiceLibrary"));

// Opt in for the default endpoints!
myHost.AddDefaultEndpoints();

// Open the host.
myHost.Open();
}

```

Enabling MEX

While you could enable MEX programmatically as well, here you will opt for a WCF 4.0 configuration file. Insert a new App.config file into your Windows service project that contains the following default MEX settings:

```

<?xml version="1.0" encoding="utf-8" ?>
<configuration>
  <system.serviceModel>
    <services>
      <service name="MathServiceLibrary.MathService">
        </service>
    </services>

    <behaviors>
      <serviceBehaviors>
        <behavior>
          <serviceMetadata httpGetEnabled="true"/>
        </behavior>
      </serviceBehaviors>
    </behaviors>
  </system.serviceModel>
</configuration>

```

Creating a Windows Service Installer

To register your Windows service with the operating system, you need to add an installer to your project that contains the necessary code to allow you to register the service. To do so, right-click the Windows service designer surface and select Add Installer (see Figure 25-13).




Figure 25-13. Adding an installer for the Windows service

Once you do this, you can see two components have been added to a new designer surface representing the installer. The first component (named `serviceProcessInstaller1` by default) represents an item that can install a new Windows service on the target machine. Select this item on the designer and use the Properties window to set the `Account` property to `LocalSystem` (see Figure 25-14).




Figure 25-14. Be sure to run the Windows service as a local system account

The second component (named `serviceInstaller1`) represents a type that will install your particular Windows service. Again, use the Properties window to change the `ServiceName` property to `MathService` (as you might have guessed, this represents the friendly display name of the registered Windows service), set the `StartType` property to `Automatic`, and add a friendly description of your Windows service using the `Description` property (see Figure 25-15).




Figure 25-15. Configuring installer details

At this point, you can compile your application.

Installing the Windows Service

A Windows service can be installed on the host machine using a traditional setup program (such as an *.msi installer) or via the `installutil.exe` command-line tool. Using a Visual Studio 2010 command prompt, change into the `\bin\Debug` folder of your `MathWindowsServiceHost` project. Now, enter the following command:

```
installutil MathWindowsServiceHost.exe
```

Assuming the installation succeeded, you can now open the Services applet located under the Administrative Tools folder of your Control Panel. You should see the friendly name of your Windows service listed alphabetically. Once you locate it, make sure you start the service on your local machine using the Start link (see Figure 25-16).




Figure 25-16. Viewing your Windows service, which hosts your WCF service

Now that the service is alive and kicking, the last step is to build a client application to consume its services.

■ **Source Code** You can find the MathWindowsServiceHost project located under the Chapter 25 subdirectory.

Invoking a Service Asynchronously from the Client

Create a new Console Application named MathClient and set a Service Reference to your running WCF service (that is currently hosted by the Windows service running in the background) using the Add Service Reference option of Visual Studio (you'll need to type the URL in the Addresses box). Don't click the OK button yet, however! Notice that the Add Service Reference dialog box has an Advanced button in the lower-left corner (see Figure 25-17).




Figure 25-17. Referencing your MathService and getting ready to configure advanced settings

Click this button now to view the additional proxy configuration settings (see Figure 25-18). You can use this dialog box to generate code that allows you to call the remote methods in an asynchronous manner, provided you check the Generate Asynchronous Operators check box. Go ahead and check this option for the time being.




Figure 25-18. Advanced client-side proxy configuration options

At this point, the proxy code contains additional methods that allow you to invoke each member of the service contract using the expected Begin/End asynchronous invocation pattern described in Chapter 19. Here is a simple implementation that uses a lambda expression rather than a strongly typed AsyncCallback delegate:

```
using System;
using MathClient.ServiceReference;
using System.Threading;

namespace MathClient
{
    class Program
    {
        static void Main(string[] args)
        {
            Console.WriteLine("***** The Async Math Client *****\n");

            using (BasicMathClient proxy = new BasicMathClient())
            {
                proxy.Open();
```

```
// Add numbers in an async manner, using a lambda expression.  
IAsyncResult result = proxy.BeginAdd(2, 3,  
    ar =>  
    {  
        Console.WriteLine("2 + 5 = {0}", proxy.EndAdd(ar));  
    },  
    null);  
  
while (!result.IsCompleted)  
{  
    Thread.Sleep(200);  
    Console.WriteLine("Client working...");  
}  
}  
}  
}  
}
```

Source Code You can find the MathClient project located under the Chapter 25 subdirectory.

Designing WCF Data Contracts

This chapter's final example shows you how to construct WCF *data contracts*. The previous WCF services defined simple methods that operate on primitive CLR data types. When you use any of the HTTP binding types (e.g., `basicHttpBinding` and `wsHttpBinding`), incoming and outgoing simple data types are automatically formatted into XML elements. On a related note, if you use a TCP-based binding (such as `netTcpBinding`), the parameters and return values of simple data types are transmitted using a compact binary format.

Note The WCF runtime will also automatically encode any type marked with the `[Serializable]` attribute; however, this is not the preferred way to define WCF contracts, and it is only included for backwards compatibility.

However, when you define service contracts that use custom classes as parameters or return values, you must define these types using a data contract. Simply put, a data contract is a type adorned with the `[DataContract]` attribute. Likewise, you must mark each field you expect to be used as part of the proposed contract with the `[DataMember]` attribute.

■ **Note** If a data contract contains fields not marked with the [DataMember] attribute, those fields will not be serialized by the WCF runtime.

Next you'll see how to construct data contracts. Begin by creating a brand-new WCF service that interacts with the AutoLot database you created in Chapter 21. Also, you will create this final WCF service using the web-based WCF Service template. Recall that this type of WCF service will automatically be placed into an IIS virtual directory, and it will function in a similar fashion to a traditional .NET XML web service. Once you understand the composition of such a WCF service, you should have little problem porting an existing WCF service into a new IIS virtual directory.

■ **Note** This example assumes you are somewhat comfortable with the structure of an IIS virtual directory (and IIS itself). If this is not the case, see Chapter 32 for details on this subject.

Using the Web-Centric WCF Service Project Template

Use the File ▶ New ▶ Web Site menu option to create a new WCF service named AutoLotWCFService, and then expose this service from the following URI: <http://localhost/AutoLotWCFService> (see Figure 25-19). Also, make sure the Location dropdown list has HTTP as the active selection.




Figure 25-19. Creating a web-centric WCF service

After you done this, set a reference to the AutoLotDAL.dll assembly you created in Chapter 21 (using the Website ▶ Add Reference menu option). You have been given some example starter code (located under the App_Code folder), which you will want to delete. Begin by renaming the initial IService.cs file to IAutoLotService.cs, and then define the initial service contract within your newly named file:

```
[ServiceContract]
public interface IAutoLotService
{
    [OperationContract]
    void InsertCar(int id, string make, string color, string petname);

    [OperationContract]
    void InsertCar(InventoryRecord car);

    [OperationContract]
    InventoryRecord[] GetInventory();
}
```

This interface defines three methods, one of which returns an array of the (yet-to-be-created) InventoryRecord type. You might recall that the GetInventory() method of InventoryDAL simply returned a DataTable object, and this might make you wonder why your service's GetInventory() method does not do the same.

While it would work to return a DataTable from a WCF service method, recall that WCF was built to honor the use of SOA principles, one of which is to program against contracts, not implementations. Therefore, you won't return the .NET-specific DataTable type to an external caller; instead you will return a custom data contract (InventoryRecord) that will be correctly expressed in the contained WSDL document in an agnostic manner.

Also note that the interface listed previously defines an overloaded method named InsertCar(). The first version takes four incoming parameters, while the second version takes an InventoryRecord type as input. You can define the InventoryRecord data contract as follows:

```
[DataContract]
public class InventoryRecord
{
    [DataMember]
    public int ID;
    [DataMember]
    public string Make;
    [DataMember]
    public string Color;
    [DataMember]
    public string PetName;
}
```

If you were to implement this interface as it now stands, and then build a host and attempt to call these methods from a client, you might be surprised to see you'll get a runtime exception. The reason: One of the requirements of a WSDL description is that each method exposed from a given endpoint must be *uniquely named*. Thus, while method overloading works just fine as far as C# is concerned, the current web service specifications do not permit two identically named InsertCar() methods.

Fortunately, the [OperationContract] attribute supports a named property (Name) that allows you to specify how the C# method will be represented within a WSDL description. Given this, you can update the second version of InsertCar() as follows:

```
public interface IAutoLotService
{
    ...
    [OperationContract(Name = "InsertCarWithDetails")]
    void InsertCar(InventoryRecord car);
}
```

Implementing the Service Contract

Now rename Service.cs to AutoLotService.cs. The AutoLotService type implements this interface as follows (be sure to import the AutoLotConnectedLayer and System.Data namespaces into this code file):

```
using AutoLotConnectedLayer;
using System.Data;

public class AutoLotService : IAutoLotService
{
    private const string ConnString =
        @"Data Source=(local)\SQLEXPRESS;Initial Catalog=AutoLot"+
        ";Integrated Security=True";

    public void InsertCar(int id, string make, string color, string petname)
    {
        InventoryDAL d = new InventoryDAL();
        d.OpenConnection(ConnString);
        d.InsertAuto(id, color, make, petname);
        d.CloseConnection();
    }

    public void InsertCar(InventoryRecord car)
    {
        InventoryDAL d = new InventoryDAL();
        d.OpenConnection(ConnString);
        d.InsertAuto(car.ID, car.Color, car.Make, car.PetName);
        d.CloseConnection();
    }

    public InventoryRecord[] GetInventory()
    {
        // First, get the DataTable from the database.
        InventoryDAL d = new InventoryDAL();
        d.OpenConnection(ConnString);
        DataTable dt = d.GetAllInventoryAsDataTable();
        d.CloseConnection();
    }
}
```

```

// Now make a List<T> to contain the records.
List<InventoryRecord> records = new List<InventoryRecord>();

// Copy the data table into List<> of custom contracts.
DataTableReader reader = dt.CreateDataReader();
while (reader.Read())
{
    InventoryRecord r = new InventoryRecord();
    r.ID = (int)reader["CarID"];
    r.Color = ((string)reader["Color"]);
    r.Make = ((string)reader["Make"]);
    r.PetName = ((string)reader["PetName"]);
    records.Add(r);
}

// Transform List<T> to array of InventoryRecord types.
return (InventoryRecord[])records.ToArray();
}
}

```

There isn't too much to say about the preceding code. For the sake of simplicity, you hard-code the connection string value (which you might need to adjust based on your machine settings), rather than store it in your `Web.config` file. Given that your data access library does all the real work of communicating with the AutoLot database, all you need to do is pass the incoming parameters to the `InsertAuto()` method of the `InventoryDAL` class type. The only other point of interest is the act of mapping the `DataTable` object's values into a generic list of `InventoryRecord` types (using a `DataTableReader`), and then transforming the `List<T>` into an array of `InventoryRecord` types.

The Role of the *.svc File

When you create a web-centric WCF service, you will find your project contains a specific file with a `*.svc` file extension. This particular file is required for any WCF service hosted by IIS; it describes the name and location of the service implementation within the install point. Because you have changed the names of your starter files and WCF types, you must now update the contents of the `Service.svc` file as follows:

```
<%@ ServiceHost Language="C#" Debug="true"
  Service="AutoLotService" CodeBehind="~/App_Code/AutoLotService.cs" %>
```

Note Under .NET 4.0, it is now possible to deploy a WCF service to an IIS virtual directory without a `*.svc` file. However, doing this means that your entire service can be nothing more than a collection of C# code files. Your service will also look highly similar to a traditional ASP.NET XML Web Service! To see more details, look up the following topic in the .NET Framework 4.0 SDK documentation: "What's new in Windows Communication Foundation."

Examining the Web.config File

The Web.config file of a WCF Service created under HTTP will use a number of the .NET 4.0 simplifications examined earlier in this chapter. As will be described in more detail during your examination of ASP.NET later in this book, the Web.config file serves a similar purpose to an executable's *.config file; however, it also controls a number of web-specific settings. For this example, notice that MEX is enabled, and you do not have to specify a custom <endpoint> manually:

```
<configuration>

  <system.web>
    <compilation debug="false" targetFramework="4.0" />
  </system.web>

  <system.serviceModel>
    <behaviors>
      <serviceBehaviors>
        <behavior>
          <!-- To avoid disclosing metadata information,
              set the value below to false and remove the
              metadata endpoint above before deployment -->
          <serviceMetadata httpGetEnabled="true"/>
          <!-- To receive exception details in faults for debugging purposes,
              set the value below to true.
              Set to false before deployment to avoid
              disclosing exception information -->
          <serviceDebug includeExceptionDetailInFaults="false"/>
        </behavior>
      </serviceBehaviors>
    </behaviors>
  </system.serviceModel>

  <system.webServer>
    <modules runAllManagedModulesForAllRequests="true"/>
  </system.webServer>

</configuration>
```

Testing the Service

Now you are free to build any sort of client to test your service, including passing in the endpoint of the *.svc file to the WcfTestClient.exe application:

```
WcfTestClient http://localhost/AutoLotWCFService/Service.svc
```

If you wish to build a custom client application, you can use the Add Service Reference dialog box, as you did for the MagicEightBallServiceClient and MathClient project examples earlier in this chapter.

■ **Source Code** You can find the AutoLotService project located under the Chapter 25 subdirectory.

That wraps up your look at the Windows Communication Foundation API. Of course, there is much more to WCF than could be covered in this introductory chapter; however if you understand the materials presented here, you are in great shape to seek out more details as you see fit. Be sure to consult the .NET Framework 4.0 SDK documentation if you want to learn more about WCF.

Summary

This chapter introduced you to the Windows Communication Foundation (WCF) API, which has been part of the base class libraries since .NET 3.0. As explained in this chapter, the major motivation behind WCF was to provide a unified object model that exposes a number of (previously unrelated) distributed computing APIs under a single umbrella. Furthermore, a WCF service is represented by specified addresses, bindings, and contracts (which you can remember easily by the friendly abbreviation, *ABC*).

You also learned that a typical WCF application involves the use of three interrelated assemblies. The first assembly defines the service contracts and service types that represent the service's functionality. This assembly is then hosted by a custom executable, an IIS virtual directory, or a Windows service. Finally, the client assembly uses a generated code file that defines a proxy type (and settings within the application configuration file) to communicate with the remote type.

The chapter also examined how to use a number of WCF programming tools, such as `SvcConfigEditor.exe` (which allows you to modify `*.config` files), the `WcfTestClient.exe` application (to test a WCF service quickly), and various Visual Studio 2010 WCF project templates. You also learned about a number of WCF 4.0 simplifications, including default endpoints and behaviors.



Introducing Windows Workflow Foundation 4.0

A few years back, Microsoft shipped an API named Windows Workflow Foundation (WF) with the release of .NET 3.0. This API allowed you to model, configure, monitor, and execute the *workflows* (which are used to model a business process) used internally by a given .NET program. The out-of-the-box functionality provided by the first release of WF was very a welcomed step in the right direction, as we were no longer required to manually develop complex infrastructure to support workflow-enabled applications.

As intriguing a technology as the first release of WF was, it was not without its warts. A number of developers felt the designer experience provided by Visual Studio 2008 was lackluster and that it was too cumbersome to navigate complex workflow during development. As well, the initial release of WF required a good deal of boilerplate code to get a workflow up and running, and even the act of building the workflow itself was a bit clunky, given the fact that your C# code base and the related workflow designer representation did not mesh together as seamlessly as hoped.

.NET 4.0 gives us a complete reboot of the entire WF API. Going forward, workflows are modeled (by default) using a declarative XML-based grammar named XAML where data used by the workflow is treated as a first class citizen. As well, the Visual Studio 2010 WF designers have been completely overhauled and rewritten using Windows Presentation Foundation (WPF) technologies. So, if you used the previous version of the WF API and were a tad dissatisfied, I encourage you to read on with a fresh set of eyes.

If you are new to the topic of WF, this chapter begins by defining the role of business processes and describes how they relate to the WF API. As well, you will be exposed to the concept of a WF activity, the two major flavors of workflows under 4.0 (flowchart and sequential), and various project templates and programming tools. Once we've covered the basics, we'll build several example programs that illustrate how to leverage the WF programming model to establish business processes that execute under the watchful eye of the WF runtime engine.

Note The entirety of WF 4.0 cannot be covered in a single introductory chapter. If you require a deeper treatment of the topic than presented here, check out *Pro WF: Windows Workflow in .NET 4.0* by Bruce Bukovics (Apress, 2010).

Defining a Business Process

Any real-world application must be able to model various *business processes*. Simply put, a business process is a conceptual grouping of tasks that logically work as a collective whole. For example, assume you are building an application that allows a user to purchase an automobile online. Once the user submits the order, a large number of activities are set in motion. You might begin by performing a credit check. If the user passes the credit verification, you might start a database transaction in order to remove the entry from an Inventory table, add a new entry to an Orders table, and update the customer account information. After the database transaction has completed, you still might need to send a confirmation e-mail to the buyer, and then invoke a remote service to place the order at the car dealership.

Collectively, all of these tasks could represent a single business process.

Historically speaking, modeling a business process was yet another detail that programmers had to account for, often by authoring custom code to ensure that a business process was not only modeled correctly but also executed correctly within the application itself. For example, you may need to author code to account for points of failure, tracing, and logging support (to see what a given business process is up to); persistence support (to save the state of long-running processes); and whatnot. As you may know firsthand, building this sort of infrastructure from scratch entails a great deal of time and manual labor.

Assuming that a development team did, in fact, build a custom business process framework for their applications, their work was not yet complete. Simply put, a raw C# code base cannot be easily explained to nonprogrammers on the team who *also* need to understand the business process. The truth of the matter is that subject matter experts (SMEs), managers, salespeople, and members of a graphical design team often do not speak the language of code. Given this, as programmers, we were required to make use of other modeling tools (such as Microsoft Visio, the office whiteboard, etc) to graphically represent our processes using skill set-neutral terms. The obvious problem here is we now have two entities to keep in sync: If we change the code, we need to update the diagrams. If we change the diagrams, we need to update the code.

Furthermore, when building a sophisticated software application using the *100% code approach*, the code base has very little trace of the internal “flow” of the application. For example, a typical .NET program might be composed of hundreds of custom types (not to mention the numerous types used within the base class libraries). While programmers may have a feel for which objects are making calls on other objects, the code itself is a far cry from a living document that explains the overall sequence of activity. While the development team may build external documentation and workflow charts, again there is the problem of multiple representations of the same process.

The Role of WF 4.0

In essence, the Windows Workflow Foundation 4.0 API allows programmers to declaratively design business processes using a prefabricated set of *activities*. Thus, rather than only using a set of custom assemblies to represent a given business activity and the necessary infrastructure, we can make use of the WF designers of Visual Studio 2010 to create our business process at design time. In this respect, WF allows us to build the skeleton of a business process, which can be fleshed out through code where required.

When programming with the WF API, a single entity can then be used to represent the overall business process as well as the code that defines it. In addition to being a friendly visual representation of the process, since a single WF document is used to represent the code driving the process, we no longer need to worry about multiple documents falling out of sync. Better yet, this WF document will clearly illustrate the process itself. With a little bit of guidance, even the most non-technical of staff members should be able to get a grip on what your WF designer is modeling.

Building a (Painfully) Simple Workflow

As you build a workflow-enabled application, you will undoubtedly notice that it “feels different” from building a typical .NET application. For example, up until this point in the text, every code example began by creating a new project workspace (most often a Console Application project) and involved authoring code to represent the program at large. A WF application also consists of custom code; however, in addition, you are building *directly into the assembly* a model of the business process itself.

Another aspect of WF which is quite different from other sorts of .NET applications is that a vast majority of your workflows will be modeled in a declarative manner, using an XML-based grammar named XAML. Much of the time, you will not need to directly author this markup, as the Visual Studio 2010 IDE will do so automatically as you work with the WF designer tools. This is a big change in direction from the previous version of the WF API, which favored using C# code as the standard way to model a workflow.

Note Be aware that the XAML dialect used within WF is not identical to the XAML dialect used for WPF. You will learn about the syntax and semantics of WPF XAML in Chapter 27, as unlike WF XAML, it is quite common to directly edit designer-generated WPF XAML.

To get you into the workflow mindset, open Visual Studio 2010. From the New Project dialog box, pick a new Workflow Console Application project named FirstWorkflowExampleApp (see Figure 26-1).




Figure 26-1. Creating a new console based workflow application

Now, consider Figure 26-2, which illustrates the initial workflow diagram generated by Visual Studio 2010. As you can see, there is not too much happening at this point, just a message telling you to drop activities on the designer.




Figure 26-2. A workflow designer is a container for activities that model your business process

For this first simple test workflow, open the Visual Studio 2010 Toolbox, and locate the `WriteLine` activity under the Primitives section (Figure 26-3).




Figure 26-3. The Toolbox will show you all the default activities of WF 4.0

Once you have located this activity, drag it onto of the designer's drop target (be sure you drag it directly onto the area which says *Drop activity here*), and enter a friendly double quoted string message into the Text edit box Figure 26-4 shows one possible workflow.




Figure 26-4. The *WriteLine* activity will display text to a *TextWriter*, the console in this case

Viewing the Underlying XAML

Now, if you close the workflow designer, you can right click on *Workflow1.xaml* using the Solution Explorer and pick the “View code” menu option. This will display the underlying XAML representation of your workflow. As you can see, the root node of this XML-based document is *<Activity>*. In the opening declaration of the root element, you will find a large number of XML namespace definitions, almost all of which have the token *clr-namespace* embedded within.

As explained in more detail in Chapter 27, when a XAML file needs to reference the definitions of .NET types contained in external assemblies (or a different namespace in the current assembly), you are required to build a .NET to XAML mapping using the *clr-namespace* token:

```
<Activity mc:Ignorable="sap" x:Class="FirstWorkflowExampleApp.Workflow1"
  xmlns="http://schemas.microsoft.com/netfx/2009/xaml/activities"
  xmlns:mc="http://schemas.openxmlformats.org/markup-compatibility/2006"
  xmlns:mv="clr-namespace:Microsoft.VisualBasic;assembly=System"
  xmlns:mva="clr-namespace:Microsoft.VisualBasic.Activities;assembly=System.Activities"
  xmlns:s="clr-namespace:System;assembly=mscorlib"
  xmlns:s1="clr-namespace:System;assembly=System"
  xmlns:s2="clr-namespace:System;assembly=System.Xml"
  xmlns:s3="clr-namespace:System;assembly=System.Core"
  xmlns:sa="clr-namespace:System.Activities;assembly=System.Activities"
  xmlns:sad="clr-namespace:System.Activities.Debugger;assembly=System.Activities"
  xmlns:sap="http://schemas.microsoft.com/netfx/2009/xaml/activities/presentation"
  xmlns:scg="clr-namespace:System.Collections.Generic;assembly=System"
  xmlns:scg1="clr-namespace:System.Collections.Generic;assembly=System.ServiceModel"
  xmlns:scg2="clr-namespace:System.Collections.Generic;assembly=System.Core"
  xmlns:scg3="clr-namespace:System.Collections.Generic;assembly=mscorlib"
```

```

xmlns:sd="clr-namespace:System.Data;assembly=System.Data"
xmlns:sl="clr-namespace:System.Linq;assembly=System.Core"
xmlns:st="clr-namespace:System.Text;assembly=mscorlib"
xmlns:x="http://schemas.microsoft.com/winfx/2006/xaml">
<x:Members>
  <x:Property Name="MessageToShow" Type="InArgument(x:String)" />
</x:Members>
<sap:VirtualizedContainerService.HintSize>
  251,240
</sap:VirtualizedContainerService.HintSize>
<mva:VisualBasic.Settings>
  Assembly references and imported namespaces for internal implementation
</mva:VisualBasic.Settings>

<WriteLine sad:XamlDebuggerXmlReader.FileName=
  "C:\My Code\ FirstWorkflowExampleApp\Workflow1.xaml"
  sap:VirtualizedContainerService.HintSize="211,200" Text="[MessageToShow]" />

</Activity>

```

The `<Activity>` element is the container of all other tasks which represent your workflow. Here, we have only one other sub-activity, `<WriteLine>`. Notice that the `Text` attribute has been set based on the data you entered in the workflow designer.

Now remember that when you are building workflows using Visual Studio 2010, you will typically not be required to manually modify this markup. Using this designer (and the various WF-centric tools integrated into Visual Studio 2010), you are able to model your process while the markup is generated by the IDE. Because of this fact, this chapter will not dive into the details of WF XAML to any great degree. However, feel free to view the markup generated by the IDE as you drag and drop activities onto the designer (this will get you in the proper mindset for your examination of WPF).

In any case, the markup found in a XAML file always maps to “real” types in a .NET assembly. For example, each element in a XAML file (such as `<Activity>`) is a declarative way to define a .NET object (such as `System.Activities.Activity`). Attributes which appear in the opening element definition map to properties or events on the related class type. At runtime, your markup will be fed into a runtime object model, where each element description will be used to set the state of the related .NET object.

Allowing us to define the structure of a workflow in a declarative manner using XAML has a number of benefits, most notably tool support. For example, it is possible to host the same Visual Studio 2010 designer tools in a custom GUI application. By doing so, you can build a simple tool which can be used by the non-programmers on your team to create the business processes they wish to have you implement in your products. Their design can be saved as a `*.xaml` file and imported into your .NET projects.

Another compelling benefit of using markup to define a workflow is that it now becomes possible to (easily) load in external XAML files into memory on the fly and thereby change how your business process operates. For example, you could author code that reads a `*.xaml` file on the fly and hydrates the related object model. Since your workflow logic is not hard-coded into your assembly, changing the functionality of the business process could be as simple as changing the markup and restarting your application.

Do understand that WF is far more than a pretty designer that allows you to model the activities of a business process. As you are building your WF diagram, your markup can always be extended using code to represent the runtime behavior of your process. In fact, if you wanted to do so, you could avoid the use of XAML all together and author the workflow using nothing but C#. If you were to this, however, you would be back to the same basic issue of having a body of code that is not readily understandable to non-technical staff.

If you were to run your application at this point, you would see your message display to the console window:

```
First Workflow!
Press any key to continue . . .
```

Fair enough; however, what started this workflow? And how were you able to ensure that the console application stayed running long enough for the workflow to complete? The answers to these questions require an understanding of the workflow runtime engine.

The WF 4.0 Runtime

The next thing to understand is that the WF API also consists of a runtime engine to load, execute, unload, and in other ways manipulate a workflow which you have defined. The WF runtime engine can be hosted within any .NET application domain; however, be aware that a single application domain can only have one running instance of the WF engine.

Recall from Chapter 16 that an AppDomain is a partition within a Windows process that plays host to a .NET application and any external code libraries. As such, the WF engine can be embedded within a simple console program, a GUI desktop application (Windows Forms or WPF), or exposed from a Windows Communication Foundation (WCF) service.

Note The WCF Workflow Service Application project template is a great starting point if you wish to build a WCF service (see Chapter 25) that makes use of workflows internally.

If you are modeling a business process that needs to be used by a wide variety of systems, you also have the option of authoring your WF within a C# Class Library project or a Workflow Activity Library project. In this way, new applications can simply reference your *.dll to reuse a predefined collection of business processes. This is obviously helpful in that you would not want to have to re-create the same workflows multiple times.

Hosting a Workflow using WorkflowInvoker

The host process of the WF runtime can interact with said runtime using a few different techniques. The simplest way to do so is to use the `WorkflowInvoker` class of the `System.Activities` namespace. This class allows you to start a workflow using a single line of code. If you were to open up the `Program.cs` file of your current Workflow Console Application project, you will see the following `Main()` method:

```
static void Main(string[] args)
{
    WorkflowInvoker.Invoke(new Workflow1());
}
```

Using the `WorkflowInvoker` is very useful when you simply want a workflow to kick off and don't care to monitor it any further. The `Invoke()` method will execute the workflow in a *synchronous blocking manner*. The calling thread is blocked until the entire workflow has finished or has been terminated abruptly. Because the `Invoke()` method is a synchronous call, you are guaranteed that the entire workflow will indeed complete before `Main()` is terminated. In fact, if you were to add any code after the call to `WorkflowInvoker.Invoke()`, it will only execute when the workflow is completed (or in a worse case situation, terminated abruptly):

```
static void Main(string[] args)
{
    WorkflowInvoker.Invoke(new Workflow1());
    Console.WriteLine("Thanks for playing");
}
```

Passing Arguments to your Workflow using `WorkflowInvoker`

When a host process kicks off a workflow, it is very common for the host to send custom startup arguments. For example, assume that you wish to let the user of your program specify which message to display in the `WriteLine` activity in place of the currently hard-coded text message. In normal C# code, you might create a custom constructor on a class to receive such arguments. However, a workflow is always created using the default constructor! Moreover, most workflows are defined only using XAML, not procedural code.

As it turns out, the `Invoke()` method has been overloaded multiple times, one version of which allows you to pass in arguments to the workflow when it starts. These arguments are represented using a `Dictionary<string, object>` variable that contains a set of name/value pairs that will be used to set identically named (and typed) argument variables in the workflow itself.

Defining Arguments using the Workflow Designer

To define the arguments that will capture the incoming dictionary data, you will make use of the workflow designer. In Solution Explorer, right-click `Workflow1.xaml` and select `View Designer`. Notice on the bottom of the designer there is a button named `Arguments`. Click this button now, and from the resulting UI, add an input argument of type `String` named `MessageToShow` (no need to assign a default value for this new argument). As well, delete your initial message from the `WriteLine` activity. Figure 26-5 shows the end result.




Figure 26-5. Workflow arguments can be used to receive host supplied arguments

Now, in the Text property of the WriteLine activity, you can simply enter MessageToShow as the evaluation expression. As you are typing in this token, you'll notice IntelliSense will kick in (Figure 26-6).




Figure 26-6. Using a custom argument as input to an activity

Now that you have the correct infrastructure in place, consider the following update to the `Main()` method of the `Program` class. Note that you will need to import the `System.Collections.Generic` namespace into your `Program.cs` file to declare the `Dictionary<>` variable.

```
static void Main(string[] args)
{
    Console.WriteLine("***** Welcome to this amazing WF application *****");

    // Get data from user, to pass to workflow.
    Console.Write("Please enter the data to pass the workflow: ");
    string wfData = Console.ReadLine();

    // Package up the data as a dictionary.
    Dictionary<string, object> wfArgs = new Dictionary<string,object>();
    wfArgs.Add("MessageToShow", wfData);

    // Pass to the workflow.
    WorkflowInvoker.Invoke(new Workflow1(), wfArgs);

    Console.WriteLine("Thanks for playing");
}
```

Again, it is important to point out that the string values for each member of your `Dictionary<>` variable will need to be identically named to the related argument variable in your workflow. In any case, you will find output similar to the following when you run the modified program:

```
***** Welcome to this amazing WF application *****
Please enter the data to pass the workflow: Hello Mr. Workflow!
Hello Mr. Workflow!
Thanks for playing
Press any key to continue . . .
```

Beyond the `Invoke()` method, the only other really interesting members of `WorkflowInvoker` would be `BeginInvoke()` and `EndInvoke()`, which allow you to start up the workflow on a secondary thread using the .NET asynchronous delegate pattern (see Chapter 19). If you require more control over how the WF runtime manipulates your workflow, you can instead make use of the `WorkflowApplication` class.

Hosting a Workflow using `WorkflowApplication`

You'll want to use `WorkflowApplication` (as opposed to `WorkflowInvoker`) if you need to save or load a long running workflow using WF persistence services, be notified of various events which fire during the lifetime of your workflow instance, work with WF "bookmarks," and other advanced features.

If you have a background in the previous version of the WF API, use of `WorkflowApplication` will look familiar to using the .NET 3.5 WF `WorkflowRuntime` class, in that you will need to call the `Run()` method to start the workflow instance.

When you do call `Run()`, a new background thread will be plucked from the CLR thread pool. Therefore, if you do not add additional support to ensure the main thread waits for the secondary thread to complete, the workflow instance may not have a chance to finish its work!

One way to make sure the calling thread waits long enough for the background thread to finish its work is to use an `AutoResetEvent` object of the `System.Threading` namespace. (In fact, this is what the .NET 3.5 workflow starter code made use of.) Here is an update to the current example, which now uses `WorkflowApplication` rather than `WorkflowInvoker`:

```
static void Main(string[] args)
{
    Console.WriteLine("***** Welcome to this amazing WF application *****");

    // Get data from user, to pass to workflow.
    Console.Write("Please enter the data to pass the workflow: ");
    string wfData = Console.ReadLine();

    // Package up the data as a dictionary.
    Dictionary<string, object> wfArgs = new Dictionary<string,object>();
    wfArgs.Add("MessageToShow", wfData);

    // Used to inform primary thread to wait!
    AutoResetEvent waitHandle = new AutoResetEvent(false);

    // Pass to the workflow.
    WorkflowApplication app = new WorkflowApplication(new Workflow1(), wfArgs);

    // Hook up an event with this app.
    // When I'm done, notify other thread I'm done,
    // and print a message.
    app.Completed = (completedArgs) => {
        waitHandle.Set();
        Console.WriteLine("The workflow is done!");
    };

    // Start the workflow!
    app.Run();

    // Wait until I am notified the workflow is done.
    waitHandle.WaitOne();

    Console.WriteLine("Thanks for playing");
}
```

The output will be similar to the previous iteration of the project:

```
***** Welcome to this amazing WF application *****
Please enter the data to pass the workflow: Hey again!
Hey again!
The workflow is done!
Thanks for playing
Press any key to continue . . .
```

The benefit of using `WorkflowApplication` is you can hook into events (as you have done indirectly using the `Completed` property here) and can also tap into more sophisticated services (persistence, bookmarks, etc).

For this introductory look at WF 4.0, we will not dive into the details of these runtime services. Be sure to check out the .NET Framework 4.0 SDK documentation for details regarding the runtime behaviors and services of the Windows Workflow Foundation 4.0 runtime environment.

Note In addition to `WorkflowInvoker` and `WorkflowApplication`, you can also start and monitor a workflow instance using `WorkflowServiceHost`. This class supports features like messaging activities, multi-instancing, and configuration. If your workflow-enabled WCF service is under IIS, `WorkflowServiceHost` is used automatically.

Recap of your First Workflow

That wraps up your first look at WF 4.0. While this example was very trivial, you did learn a few interesting (and useful) tasks. First, you learned that you can pass in a `Dictionary` object which contains name/value pairs that will be passed to identically named arguments in your workflow. This is really useful when you need to gather user input (such as a customer ID number, SSN, name of a Doctor, etc) which will be used by the workflow to process its activities.

You also learned that a .NET 4.0 workflow is defined in a declarative manner (by default) using an XML-based grammar named XAML. Using XAML, you can specify which activities your workflow contains. At runtime, this data will be used to create the correct in-memory object model. Last but not least, you looked at two different approaches to kick off a workflow using the `WorkflowInvoker` and `WorkflowApplication` classes.

Source Code The `FirstWorkflowExampleApp` project is included under the Chapter 26 subdirectory.

Examining the Workflow 4.0 Activities

Recall that the purpose of WF is to allow you to model a business process in a declarative manner, which is then executed by the WF runtime engine. In the vernacular of WF, a business process is composed of any number of *activities*. Simply put, a WF activity is an atomic “step” in the overall process. When you create a new workflow application, you will find the Toolbox contains iconic representations of the built-in activities grouped by category.

These out-of-the-box activities are used to model your business process. Each activity in the Toolbox maps to a real class within the `System.Activities.dll` assembly (most often contained within the `System.Activities.Statements` namespace). You’ll make use of several of these baked-in activities over the course of this chapter; however, here is a walkthrough of many of these default activities. As always, consult the .NET Framework 4.0 SDK documentation for full details.

Control Flow Activities

The first category of activities in the toolbox allow you to represent looping and decision tasks in a larger workflow. Their usefulness should be easy to understand, given that we do similar tasks in C# code quite often. In Table 26-1, notice that some of these control flow activities allow for parallel processing of activities using the Task Parallel Library behind the scenes (see Chapter 19).

Table 26-1. The control flow activities of WF 4.0

Activities	Meaning in Life
DoWhile	A looping activity that executes contained activities at least once, until a condition is no longer true.
ForEach<T>	Executes an activity action once for each value provided in the ForEach<T>.Values collection.
If	Models an If-Then-Else condition.
Parallel	An activity that executes all child activities simultaneously and asynchronously.
ParallelForEach<T>	Enumerates the elements of a collection and executes each element of the collection in parallel.
Pick	Provides event-based control flow modeling.
PickBranch	A potential path of execution within a parent Pick activity.
Sequence	Executes a set of child activities sequentially.
Switch<T>	Selects one choice from a number of activities to execute, based on the value of a given expression of the type specified in this object's type parameter.
While	Executes a contained workflow element while a condition evaluates to true.

Flowchart Activities

Next are the flowchart activities, which are actually quite important given that the Flowchart activity will very often be the first item you place on your WF designer. The concept of a *flow chart workflow* is new with .NET 4.0. It allows you to build a workflow using the well known flow chart model, where the

execution of the workflow is based on numerous branching paths, each of which is based on the truth or falsity of some internal condition. Table 26-2 documents each member of this activity set.

Table 26-2. The flowchart activities of WF 4.0

Activities	Meaning in Life
Flowchart	Models workflows using the familiar flowchart paradigm. This is often the very first activity you will place on a new designer.
FlowDecision	A node that provides the ability to model a conditional node with two possible outcomes.
FlowSwitch<T>	A node that allows modeling a switch construct, with one expression and one outcome for each match.

Messaging Activities

A workflow can easily invoke members of an external XML web service or WCF service, as well as be notified by an external service using *messaging activities*. Because these activities are very closely related to WCF development, they have been packaged up in a dedicated .NET assembly, `System.ServiceModel.Activities.dll`. Within this library, you will find an identically named namespace defining the core activities seen in Table 26-3.

Table 26-3. The messaging activities of WF 4.0

Activities	Meaning in Life
CorrelationScope	Used to manage child message activities.
InitializeCorrelation	Initializes correlation without sending or receiving a message.
Receive	Receives a message from a WCF service.
Send	Sends a message to a WCF service.
SendAndReceiveReply	Sends a message to a WCF service and captures the return value.
TransactedReceiveScope	An activity that enables you to flow a transaction into a workflow or dispatcher-created server side transactions.

The most common messaging activities are Send and Receive, which allow you to communicate with external XML web services or WCF services.

The Runtime and Primitives Activities

The next two categories in the toolbox, Runtime and Primitives, allow you to build a workflow which makes calls to the workflow runtime (in the case of Persist and TerminateWorkflow) and performs common operations such as push text to an output stream or invoke a method on a .NET object. Consider Table 26-4.

Table 26-4. The runtime and primitive activities of WF 4.0

Activities	Meaning in Life
Persist	Requests that a workflow instance persist its state into a database using the WF persistence service.
TerminateWorkflow	Terminates the running workflow instance, raises the <code>WorkflowApplication.Completed</code> event in the host, and reports error information. Once the workflow is terminated, it cannot be resumed.
Assign	Allows you to set properties on an activity using the assignment values you defined via the workflow designer.
Delay	Forces a workflow to stop for a fixed amount of time.
InvokeMethod	Calls a method of a specified object or type.
WriteLine	Writes a specified string to a specified <code>TextWriter</code> derived type. By default, this will be the standard output stream (a.k.a. the console); however, you can configure other streams, such as a <code>FileStream</code> .

InvokeMethod is maybe the most interesting and useful activity of this set because it allows you to call methods of .NET classes in a declarative manner. You can also configure InvokeMethod to hold onto any return value send from the method you call. TerminateWorkflow can also be helpful when you need to account for a *point of no return*. If the workflow instance hits this activity, it will raise the `Completed` event which can be caught in the host, just like you did in the first example.

The Transaction Activities

When you are building a workflow, you might need to ensure that a group of activities work in an atomic manner, meaning they must *all* succeed or *all* fail as a collective group. Even if the activities in question

are not directly working with a relational database, the core activities seen in Table 26-5 allow you to add a transactional scope into a workflow.

Table 26-5. The transaction activities of WF 4.0

Activities	Meaning in Life
CancellationScope	Associates cancellation logic within a main path of execution.
CompensableActivity	An activity that supports compensation of its child activities.
TransactionScope	An activity that demarcates a transaction boundary.

The Collection and Error Handling Activities

The final two categories to consider in this introductory chapter allow you to declaratively manipulate generic collections and respond to runtime exceptions. The collection activities are great when you need to manipulate objects which represent business data (such as purchase orders, medical information objects, or order tracking) on the fly in XAML. Error activities, on the other hand, allow you to essentially author try/catch/throw logic within a workflow. Table 26-6 documents this final set of WF 4.0 activities.

Table 26-6. The collection and error handling activities of WF 4.0

Activities	Meaning in Life
AddToCollection<T>	Adds an item to a specified collection.
ClearCollection<T>	Clears a specified collection of all items.
ExistsInCollection<T>	Indicates whether a given item is present in a given collection.
RemoveFromCollection<T>	Removes an item from a specified collection.
Rethrow	Throws a previously thrown exception from within a <code>Catch</code> activity.
Throw	Throws an exception.
TryCatch	Contains workflow elements to be executed by the workflow runtime within an exception handling block.

OK! Now that we have seen many of the default activities at a high level, we can start to build some more interesting workflows that make use of them. Along the way, you will learn about the two key activities that typically function as the root of your workflow, Flowchart and Sequence.

Building a Flowchart Workflow

In the first example, I had you drag a `WriteLine` activity directly on the workflow designer. While it is true that any activity seen in the Visual Studio 2010 Toolbox can be the first item placed on the designer, only a few of them are able to contain sub-activities (which is obviously very important!). When you are building a new workflow, the chances are very good that the first item you will place on your designer will be a `Flowchart` or `Sequence` activity.

Both of these built in activities have the ability to contain any number of internal child activities (including additional `Flowchart` or `Sequence` activities) to represent the entirety of your business process. To begin, let's create a brand new Workflow Console Application named `EnumerateMachineDataWF`. Once you have done so, rename your initial `*.xaml` file to `MachineInfoWF.xaml`.

Now, under the `Flowchart` section of your Toolbox, drag a `Flowchart` activity onto the designer. Next, using the Properties window, change the `DisplayName` property to something a tad more catchy, such as *Show Machine Data Flowchart* (as I am sure you can guess, the `DisplayName` property controls how the item is named on the designer). At this point, your workflow designer should look something like Figure 26-7.




Figure 26-7. The initial Flowchart activity

Be aware that there is a grab-handle on the lower right of the `Flowchart` activity, which can be used to increase or decrease the size of the flowchart designer space. You'll need to increase the size as you add more and more activities.

Connecting Activities in a Flowchart

The large Start icon represents the entry point to the Flowchart activity, which in this example is the first activity in our entire workflow and will be triggered when you execute the workflow using the `WorkflowInvoker` or `WorkflowApplication` classes. This icon can be positioned anywhere on your designer, and I'd suggest you move it to the upper left, just to make some more space.

Your goal is to assemble your flowchart by connecting any number of additional activities together, typically making use of the `FlowDecision` activity during the process. To start, drag a `WriteLine` activity on the designer, changing the `DisplayName` to *Greet User*. Now, if you hover your mouse over the Start icon, you will see one docking tab on each side. Click and hold the docking tab closest to the `WriteLine` activity, and drag it to the docking tab of the `WriteLine` activity. Once you have done so, you should see a connection between these first two items, signifying that the first activity which will be executed in your workflow will be *Greet User*.

Now, similar to the first example, add a workflow argument (via the Arguments button) named `UserName` of type string with no default value. This will be passed in dynamically via the custom `Dictionary<>` object in just a bit. Finally, set the `Text` property of the `WriteLine` activity to the following code statement:

```
"Hello" & UserName
```

Now, does anything strike you as odd here? If you were authoring C# code, you would encounter an error because the string concatenation symbol is `+`, not `&`! However (and this is the weird part), whenever you are entering a code condition in a workflow, you must use the syntax of Visual Basic! This is because the WF 4.0 API is making use of a helper assembly which has been coded to process VB statements rather than C# statements (strange but true).

Add a second `WriteLine` activity to your designer, which is connected to the previous. This time, define a hard coded string value of "Do you want me to list all machine drives?" for the `Text` property, and change the `DisplayName` property to *Ask User*. Figure 26-8 shows the connections between current workflow activities.




Figure 26-8. Flowchart workflows connect activities together

Working with the InvokeMethod Activity

Because the majority of a workflow is defined in a declarative manner using XAML, you are sure to make good use of the `InvokeMethod` activity, which allows you to invoke methods of real objects at various points in your workflow. Drag one of these items to your designer, change the `DisplayName` property to *Get Y or N*, and make a connection between it and the `Ask User` `WriteLine` activity.

The first property to configure for an `InvokeMethod` activity is the `TargetType` property, which represents the name of the class that defines a static member you wish to invoke. Using the dropdown list box for the `TargetType` of the `InvokeMethod` activity, pick the `Browse for Types...` option (Figure 26-9).




Figure 26-9. Specifying a target for `InvokeMethod`

From the resulting dialog box, pick the `System.Console` class of `mscorlib.dll` (if you enter the name of the type within the Type Name edit area, the dialog will automatically find the type). Once you have found the `System.Console` class, click the OK button.

Now, using the `InvokeMethod` activity on the designer, enter `ReadLine` as the value for the `MethodName` property. This will configure your `InvokeMethod` activity to invoke the `Console.ReadLine()` method when this step of the workflow is reached.

As you know, `Console.ReadLine()` will return a string value that contains the keystrokes entered on the keyboard before the Enter key is pressed; however, you need to have a way to capture the return value! You will do this next.

Defining Workflow Wide Variables

Defining a workflow variable in XAML is almost identical to defining an argument, in that you can do so directly on the designer (this time with the Variables button). The difference is that *arguments* are used to capture data passed in by the host, whereas *variables* are simply points of data in the workflow which will be used to influence its runtime behavior.

Using the Variables aspect of the designer, add a new string variable named `YesOrNo`. Notice that if you have multiple parent containers in your workflow (for example, a Flowchart containing another Sequence), you can pick the scope of the variable. Here, your only choice is the root Flowchart. Next, select the `InvokeMethod` activity on the designer, and using the Properties window of Visual Studio 2010, set the `Result` property to your new variable (Figure 26-10).




Figure 26-10. The fully configured InvokeMethod

Now that you can grab a piece of data from an external method call, you can use it to make a runtime decision in your flow chart using the FlowDecision activity.

Working with the FlowDecision Activity

A FlowDecision activity is used to take two possible courses of action, based on the truth or falsity of a Boolean variable, or a statement which resolves to a Boolean value. Drag one of these activities onto your designer, and connect it to the InvokeMethod activity (Figure 26-11).




Figure 26-11. A FlowDecision can branch two directions

Note If you need to respond to multiple branching conditions within a flowchart, make use of the FlowSwitch<T> activity. This allows you to define any number of paths, which will be entered based on the value of a defined workflow variable.

Set the Condition property (using the Properties window) of your FlowDecision activity to the following code statement, which you can type directly into the editor:

```
YesOrNo.ToUpper() = "Y"
```

Here you are testing an upper case version of your YesOrNo variable against the value “Y”. Remember, you are entering VB code here, so you don’t want to use the C# equality operator (==), but the VB equality operator (=).

Working with the TerminateWorkflow Activity

You now need to build the activities which will occur on each side of the FlowDecision activity. On the “false” side, connect a final WriteLine activity which prints out a hard coded message of your choosing, followed by a TerminateWorkflow activity (Figure 26-12).




Figure 26-12. The “false” branch

Strictly speaking, you don’t need to use the TerminateWorkflow activity, as this workflow would simply end once you reach the end of the false branch. However, by using this activity type, you can throw back an exception to the workflow host, informing them exactly why you are stopping. This exception can be configured in the Properties window.

Assuming you have selected the TerminateWorkflow activity on the designer, use the Properties window, and click on the ellipse button for the Exception property. This will open up an editor which allows you to throw back an exception, just like if you were doing so in code (VB code that is; see Figure 26-13).




Figure 26-13. Configuring an exception to throw when the TerminateWorkflow activity is encountered

Complete the configuration of this activity by setting the Reason property to “YesOrNo was false”.

Building the “True” Condition

To begin building the “true” condition of the FlowDecision, connect a WriteLine activity, which simply displays a hard coded string confirming the user has agreed to proceed. From here, connect to a new InvokeMethod activity, which will call the GetLogicalDrives() method of the System.Environment class. To do so, set the TargetType property to System.Environment and the MethodName property to GetLogicalDrives.

Next, add a new workflow level variable (using the Variables button of the workflow designer) named DriveNames of type string[]. To specify you want an array of strings, pick *Array of [T]* from the Variable Type drop down list, and pick string from the resulting dialog box. Figure 26-14 shows the first part of the “true” condition.




Figure 26-14. Configuring an exception to throw when the TerminateWorkflow activity is encountered

Now, set the Result property of this new InvokeMethod activity to your DriveNames variable.

Working with the ForEach<T> Activity

The next part of your workflow will be to print out the names of each drive to the console window, which is to say you need to loop over the data exposed by the `DriveNames` variable, which has been configured as an array of string objects. The `ForEach<T>` activity is the WF XAML equivalent of the C# `foreach` keyword, and it is configured in a very similar manner (at least conceptually).

Drag one of these activities on your designer and connect it to the previous `InvokeMethod` activity. You will configure the `ForEach<T>` activity in just a minute, but to complete the true condition branch, place one final `WriteLine` activity on your designer to close things off. Here is the final top-level look at your workflow (Figure 26-15).




Figure 26-15. The completed top-level workflow

To get rid of the current designer error, you need to finish the configuration of the `ForEach<T>` activity. First, use the Properties window to specify the type parameter to the generic, which in this example will be a `string` type. The `Values` property is where the data is coming from, which will be your `DriveNames` variable (Figure 26-16).




Figure 26-16. Setting the type of for-each enumeration

This particular activity needs to be further edited by double clicking on the designer in order to open a brand new mini designer just for this activity. Not all WF 4.0 activities can be double clicked on to yield a new designer, but you can easily tell if this is an option on the activity itself (it will literally say “Double-click to view”). Double click on your `ForEach<T>` activity, and add a single `WriteLine` activity, which will print out each string value (Figure 26-17).




Figure 26-17. The final configuration step of the `ForEach<T>` activity

Note You can add as many activities to the `ForEach<T>` mini designer as you require. The collective whole of these activities will execute with each iteration of the loop.

Once you have done so, use the links at the upper left of the designer to return to the top level workflow (you’ll use these *bread crumbs* quite a bit when drilling into a set of activities).

Completing the Application

You are just about done with this example! All you need to do is update the `Main()` method of the `Program` class to catch the exception that will be raised if the user says “NO” and thereby triggers the `Exception`

object. Update your code as so (and ensure the `System.Collections.Generic` namespace is imported in your code file):

```
static void Main(string[] args)
{
    try
    {
        Dictionary<string, object> wfArgs = new Dictionary<string, object>();
        wfArgs.Add("UserName", "Andrew");
        WorkflowInvoker.Invoke(new Workflow1(), wfArgs);
    }
    catch (Exception ex)
    {
        Console.WriteLine(ex.Message);
        Console.WriteLine(ex.Data["Reason"]);
    }
}
```

Notice that the “Reason” for the exception can be obtained using the `Data` property of `System.Exception`. So, if you run the program and enter “Y” when asked to enumerate your drives, you’ll see the following type of output:

```
Hello Andrew
Do you want me to list all machine drives?
y
Wonderful!
C:\ 
D:\ 
E:\ 
F:\ 
G:\ 
H:\ 
I:\ 
Thanks for using this workflow
```

However, if you enter “N” (or any other value other than “Y” or “y”), you will see the following:

```
Hello Andrew
Do you want me to list all machine drives?
n
K, bye...
YesOrNo was false
```

Reflecting on What We Have Done

Now, if you are new to working with a workflow environment, you might be wondering what you have gained by authoring this very simple business process using WF XAML rather than good-old C# code.

After all, you could have avoided Windows Workflow Foundation all together and simply built the following C# class:

```
class Program
{
    static void Main(string[] args)
    {
        try
        {
            ExecuteBusinessProcess();
        }
        catch (Exception ex)
        {
            Console.WriteLine(ex.Message);
            Console.WriteLine(ex.Data["Reason"]);
        }
    }

    private static void ExecuteBusinessProcess()
    {
        string UserName = "Andrew";
        Console.WriteLine("Hello {0}", UserName);
        Console.WriteLine("Do you want me to list all machine drives?");

        string YesOrNo = Console.ReadLine();
        if (YesOrNo.ToUpper() == "Y")
        {
            Console.WriteLine("Wonderful!");
            string[] DriveNames = Environment.GetLogicalDrives();
            foreach (string item in DriveNames)
            {
                Console.WriteLine(item);
            }
            Console.WriteLine("Thanks for using this workflow");
        }
        else
        {
            Console.WriteLine("K, Bye...");
            Exception ex = new Exception("User Said No!");
            ex.Data["Reason"] = "YesOrNo was false";
        }
    }
}
```

The output of the program would be absolutely identical to the previous XAML based workflow. So, why bother tinkering with all these activities in the first place? First of all, remember that not everyone is comfortable reading C# code. Be honest: If you had to explain this business process to a room full of sales people and non-technical managers, would you rather try to explain this C# code or show them the flowchart? I know my answer...

More importantly, remember that the WF API has a whole slew of additional runtime services, including persistence of long running workflows to a database, automatic tracking of workflow events, and so on (alas, I don't have time to cover them here). When you think of the amount of work you would need to do in order to replicate this functionality in a new project, the utility of WF is even clearer.

Finally, by allowing us a declarative way to generate workflows using designers and XAML, we can offload the construction of a workflow to higher level subject matter experts and managers, while we incorporate the XAML into our C# projects.

All of this being said, the WF API is not necessarily the correct tool of choice for all .NET programs. However, for most traditional business applications, the ability to define, host, execute and monitor workflows in this manner is a very good thing indeed. Like any new technology, you will need to determine if this is useful for your current project. Let's see another example of working with the WF API, this time by packaging up a workflow in a dedicated *.dll.

■ **Source Code** The EnumerateMachineInfoWF project is included under the Chapter 26 subdirectory.

Isolating Workflows into Dedicated Libraries

While making a Workflow Console Application is great for experimenting with the WF API, a production-ready workflow will certainly need to be packaged up into a custom .NET *.dll assembly. By doing so, you can reuse your workflows at a binary level across multiple projects.

While you could begin using a C# Class Library project as a starting point, the easiest way to build a workflow library is to start with the Activity Library project, under the Workflow node of the New Project dialog. The benefits of this project type are that it will set the required WF assembly references automatically and give you a *.xaml file to create your initial workflow.

This workflow will model the process of querying the AutoLot database to see if a given car of the correct make and color is in the Inventory table. If the requested car is in stock, you will build a nicely formatted response to the host via an *output parameter*. If the item is not in stock, you will generate a memo to the head of the sales division requesting that they find a car of the correct color.

Defining the Initial Project

Create a new Activity Library project named CheckInventoryWorkflowLib (Figure 26-18). Once the project is created, rename the initial Activity1.xaml file to CheckInventory.xaml.




Figure 26-18. Building an Activity Library

Now, before you continue, close down the visual workflow designer, and view the underlying XAML definition by right clicking on your XAML file and selecting the View Code menu option. Make sure that the `x:Class` attribute in the root `<Activity>` element has been updated as so (if not, replace `Activity1` with `CheckInventory`):

```
<Activity x:Class="CheckInventoryWorkflowLib.CheckInventory" ... >
```

Note It is always a good idea to check the `x:Class` value of your root activity when making a workflow library, as client programs will use this name to create an instance of the workflow.

This workflow will make use of a Sequence activity as the primary activity, rather than Flowchart. Drag a new Sequence activity onto your designer (you'll find it under the Control Flow area of your Toolbox) and change the `DisplayName` property to *Look Up Product*.

As the name suggests, a Sequence activity allows you to easily create sequential tasks, which occur one after the other. This does not necessarily mean the children activities must follow a strict linear path, however. Your sequence could contain flow charts, other sequences, parallel processing of data, if/else branches and whatever else might make good sense for the business process you are designing.

Importing Assemblies and Namespaces

Because your workflow will be communicating with the AutoLot database, the next step is to reference your AutoLot.dll assembly using the Add Reference dialog box of Visual Studio 2010. This example will make use of the disconnected layer, so I'd suggest you reference the final version of this assembly created in Chapter 22 (if you set a reference to the final version created in Chapter 23, you'll also need to set a reference to System.Data.Entity.dll, as this is required by the ADO.NET Entity Framework).

This workflow will also be making use of LINQ to DataSet to query the returned DataTable in order to discover if you have the requested item in stock. Therefore, you should also set a reference to System.Data.DataSetExtensions.dll.

Once you have referenced these assemblies, click on the Imports button located at the bottom of the workflow designer. Here you will see a listing of all of the .NET namespaces that you can make use of in your workflow designer (think of this area as a declarative version of the C# using keyword).

You can add namespaces from any referenced assembly by typing in the text box mounted on the top of the Imports editor. For convenience, import AutoLotDisconnectedLayer and System.Data.DataSetExtensions. By doing so, you can reference the contained types without needing to use fully qualified names. Figure 26-19 shows some new listings of the Imports area once you are finished.




Figure 26-19. Similar to the C# using keyword, the Imports area allows you to include .NET namespaces

Defining the Workflow Arguments

Next, define two new workflow wide input arguments, named RequestedMake and RequestedColor, both of which will be of type String. Like the previous example, the host of the workflow will create a Dictionary object that contains data that maps to these arguments, so there is no need to assign a default value to these items using the Arguments editor. As you might guess, the workflow will use these values to perform the database query.

As well, you can use this same Arguments editor to define an *output argument* named FormattedResponse of type String. When you need to return data from the workflow back to the host, you

can create any number of output arguments which can be enumerated by the host when the workflow has completed. Figure 26-20 shows the current workflow designer.

Name	Direction	Argument type	Default value
RequestedMake	In	String	Enter a VB expression
RequestedColor	In	String	Enter a VB expression
FormattedResponse	Out	String	Default value not supported
<i>Create Argument</i>			
Variables Arguments Imports		100%	Search Zoom Minimize Maximize Close

Figure 26-20. Recall that workflow arguments provide a way send data to and return data from the workflow

Defining Workflow Variables

At this point, you need to declare a member variable in your workflow which corresponds to the `InventoryDALDisLayer` class of `AutoLot.dll`. You might recall from Chapter 22 that this class allows you to get all data from the Inventory returned as a `DataTable`. Select your Sequence activity on the designer, and using the Variables button, create a variable named `AutoLotInventory`. In the Variable Type dropdown list box, pick the `Browse For Types...` menu option, and type in `InventoryDALDisLayer` (Figure 26-21).




Figure 26-21. Recall that workflow variables provide a way to declaratively define variables within a scope

Now, making sure your new variable is selected, go to the Visual Studio 2010 Properties window and click on the ellipse button of the `Default` property. This will open up a code editor which you can resize as you see fit (very helpful when entering lengthy code). This editor is much easier to use when entering complex code for a variable assignment. Enter the following (VB) code, which allocates your `InventoryDALDisLayer` variable:

```
New InventoryDALDisLayer("Data Source=(local)\SQLEXPRESS;" +
    "Initial Catalog=AutoLot;Integrated Security=True")
```

Declare a second workflow variable of type `System.Data.DataTable` named `Inventory`, again using the `Browse For Types...` menu option (set the default value of this variable to `Nothing`). You will be assigning the `Inventory` variable to the result of calling `GetAllInventory()` on the `InventoryDALDisLayer` variable in a later step.

Working with the Assign Activity

The `Assign` activity allows you to set a variable to a value, which can be the result of any sort of valid code statements. Drag an `Assign` activity (located in the `Primitives` area of your `Toolbox`) into your `Sequence` activity. In the `To` edit box, specify your `Inventory` variable. Using the `Properties` window, click on the ellipse button of the `Value` property and enter the following code:

```
AutoLotInventory.GetAllInventory()
```

Once the `Assign` activity has been encountered in your workflow, you will have a `DataTable` that contains all records of the `Inventory` table. However, you need to discover if the correct item is in stock using the values of the `RequestedMake` and `RequestedColor` arguments sent by the host. To determine if this is the case, you will make use of LINQ to `DataSet`. Once you know if you have the item in stock, you will use an `If` activity to perform the XAML equivalent of an `if/else/then` statement.

Working with the If and Switch Activities

Drag an `If` activity onto your `Sequence` node directly under the `Assign` activity. Because this activity is the XAML based way to make a simple runtime decision, you first need to configure the `If` activity to test against a Boolean expression. In the `Condition` editor, enter the following check LINQ to `DataSet` query:

```
(From car In Inventory.AsEnumerable()
  Where CType(car("Color"), String) = RequestedColor And
    CType(car("Make"), String) = RequestedMake Select car).Any()
```

This query will use the host supplied `RequestedColor` and `RequestedMake` data to fetch all records in the `DataTable` of correct make and color (note that the `CType` operator is the C# equivalent of an explicit cast operation). The call to the `Any()` extension method will return a true or false value based on if the result of the query contains any results.

Your next task is to configure the set of activities that will execute when the specified condition is true or false. Recall that your ultimate goal here is to send a formatted message to the user if you do indeed have the car in question. However, to spice things up a tad, you will return a unique message based on which make of automobile the caller has requested (BMW, Yugo, or anything else).

Drag a `Switch<T>` activity (located in the `Flow Control` area of the `Toolbox`) into the `Then` area of the `If` activity. As soon as you drop this activity, Visual Studio displays a dialog box asking for the type of the generic type parameter—specify `String` here. In the `Expression` area of your `Switch` activity, type `RequestedMake`.

You will see that a default option for the switch is already in place and is inviting you to add an activity to represent how to respond. You only need a single `Assign` activity; however, if you wanted to perform more complex actions, your default area might very well be a new `Sequence` or `Flowchart`.

Once you have added the `Assign` activity to the `Default` edit area (by clicking “Add Activity”), assign the `FormattedMessage` argument to the following code statement:

```
String.Format("Yes, we have a {0} {1} you can purchase",
    RequestedColor, RequestedMake)
```

At this point, your Switch editor will look like this (Figure 26-22).




Figure 26-22. Defining the default task for a Switch activity

Now, click on the “Add New Case” link and enter BMW (without any double quotes) for the first case, and once again for a final case of Yugo (again, no double quotes). Within each of these case areas, drop an Assign activity, both of which assign a value to the FormattedResponse variable. For the case of BMW, assign a value such as:

```
String.Format("Yes sir! We can send you {0} {1} as soon as {2}!", _
    RequestedColor, RequestedMake, DateTime.Now)
```

For the case of the Yugo, use the following expression:

```
String.Format("Please, we will pay you to get this {0} off our lot!", _
    RequestedMake)
```

The Switch activity will now look something like the following (Figure 26-23).




Figure 26-23. The final Switch activity

Building a Custom Code Activity

As expressive as the workflow designer experience is with its ability to embed complex code statements (and LINQ queries) in your XAML file, there will certainly be times when you just need to write code in a dedicated class. There are a number of ways to do so with the WF API, but the most straightforward way is to create a class extending `CodeActivity`, or if your activity needs to return a value, `CodeActivity<T>` (where `T` is the type of return value).

Here, you will make a simple custom activity which will dump out data to a text file, informing the sales staff that a request has come in for a car that is currently not in the inventory system. First, activate the `Project | Add New Item` menu option and insert a new Code Activity named `CreateSalesMemoActivity.cs` (Figure 26-24).




Figure 26-24. Inserting a new Code Activity

If your custom activity requires inputs to process, they will each be represented by a property encapsulating an `InArgument<T>` object. The `InArgument<T>` class type is a WF API specific entity, which provides a way to pass through data supplied by a workflow to the custom activity class itself. Your activity will need two such properties representing the make and color of the item not in stock.

As well, a custom code activity will need to override the virtual `Execute()` method, which will be called by the WF runtime when this activity is encountered. Typically, this method will use the `InArgument<>` properties to get the workload accomplished. To get the real underlying value, you will need to do so indirectly using the `GetValue()` method of the incoming `CodeActivityContext`.

Here then is the code for your custom activity, which generates a new *.txt file describing the situation to the sales team:

```
public sealed class CreateSalesMemoActivity : CodeActivity
{
    // Two properties for the custom activity
    public InArgument<string> Make { get; set; }
    public InArgument<string> Color { get; set; }
```

```

// If the activity returns a value, derive from CodeActivity<TResult>
// and return the value from the Execute method.
protected override void Execute(CodeActivityContext context)
{
    // Dump a message to a local text file.
    StringBuilder salesMessage = new StringBuilder();
    salesMessage.AppendLine("***** Attention sales team! *****");
    salesMessage.AppendLine("Please order the following ASAP!");
    salesMessage.AppendFormat("1 {0} {1}\n",
        context.GetValue(Color), context.GetValue(Make));
    salesMessage.AppendLine("*****");
    System.IO.File.WriteAllText("SalesMemo.txt", salesMessage.ToString());
}
}

```

Now that you have a custom code activity, how should you make use of it? Well, if you really wanted to deliver a polished activity, WF 4.0 does allow a way to build a custom designer for your custom code activities. However, doing so requires an understanding of WPF, as the custom designer uses many of the same techniques as you would use when building a WPF Window or UserControl. You'll begin learning about WPF in the next chapter, so for now I'll show you a simpler approach.

First, compile your workflow assembly. Ensuring your workflow designer is the active window within the Visual Studio 2010 IDE, examine the top area of your toolbox. You should see your custom activity is present and accounted for (Figure 26-25).




Figure 26-25. Custom code activities appear in the Visual Studio 2010 toolbox

First, drag a new Sequence activity into the Else branch of your If activity. Next, drag your custom activity into the Sequence. At this point, you can assign values to each of the exposed properties using the Properties window. Using your RequestedMake and RequestedColor variables, set the Make and Color properties of your activity as shown in Figure 26-26.




Figure 26-26. Setting the properties of your custom code activity

To complete this workflow, drag a final Assign activity into the Sequence activity of the Else branch, and set the FormattedResponse to the string value “Sorry, out of stock”. Figure 26-27 shows the final workflow design.




Figure 26-27. The completed sequential workflow

Compile your project and move onto the final part of this chapter, where you will build a client host to make use of the workflow.

■ **Source Code** The CheckInventoryWorkflowLib project is included under the Chapter 26 subdirectory.

Consuming the Workflow Library

Any sort of application can make use of a workflow library; however, here you will opt for simplicity and build a simple Console Application named WorkflowLibraryClient. Once you make the project, you will need to set a reference not only to your CheckInventoryWorkflowLib.dll and AutoLot.dll assemblies, but also the key WF 4.0 library, System.Activities.dll, which can be found in the .NET tab of the Visual Studio 2010 Add Reference dialog.

Once each assembly reference has been set, update your Program.cs file with the following logic:

```
using System;
using System.Linq;
using System.Activities;
using System.Collections.Generic;
using CheckInventoryWorkflowLib;

namespace WorkflowLibraryClient
{
    class Program
    {
        static void Main(string[] args)
        {
            Console.WriteLine("**** Inventory Look up ****");

            // Get user preferences.
            Console.Write("Enter Color: ");
            string color = Console.ReadLine();
            Console.Write("Enter Make: ");
            string make = Console.ReadLine();

            // Package up data for workflow.
            Dictionary<string, object> wfArgs = new Dictionary<string, object>()
            {
                {"RequestedColor", color},
                {"RequestedMake", make}
            };

            try
            {
                // Send data to workflow!
                WorkflowInvoker.Invoke(new CheckInventory(), wfArgs);
            }
            catch (Exception ex)
            {
                Console.WriteLine(ex.Message);
            }
        }
    }
}
```

```

        }
    }
}
```

As you have done in other examples, you are using the `WorkflowInvoker` to spin off the workflow in a synchronous manner. While this is all well and good, how are you to get back the return value of the workflow? Remember, once the workflow terminates, you should get back a formatted response!

Retrieving the Workflow Output Argument

The `WorkflowInvoker.Invoke()` method will return an object implementing the `IDictionary<string, object>` interface. Because a workflow can return back any number of output arguments, you will need to specify the name of a given output argument as a string value to the type indexer. Update your try/catch logic as so:

```

try
{
    // Send data to workflow!
    IDictionary<string, object> outputArgs =
        WorkflowInvoker.Invoke(new CheckInventory(), wfArgs);

    // Print out the output message.
    Console.WriteLine(outputArgs["FormattedResponse"]);
}
catch (Exception ex)
{
    Console.WriteLine(ex.Message);
}
```

Now, run your program and enter a make and color which is currently in your copy of the `Inventory` table of the `AutoLot` database. You'll see output such as the following:

```

**** Inventory Look up ****
Enter Color: Black
Enter Make: BMW
Yes sir! We can send you Black BMW as soon as 2/17/2010 9:23:01 PM!
Press any key to continue . . .
```

However, if you enter information for an item not currently in stock, you will not only see output such as:

```

**** Inventory Look up ****
Enter Color: Pea Soup Green
Enter Make: Viper
Sorry, out of stock
Press any key to continue . . .
```

You will also find a new *.txt file in the \bin\Debug folder of the client application. If you open this in any text editor, you'll find the "sales memo":

```
***** Attention sales team! *****
Please order the following ASAP!
1 Pea Soup Green Viper
*****
```

That wraps up your introductory look at the brand new WF 4.0 API. As mentioned at the opening of this chapter, if you have worked with the previous version of the Windows Workflow Foundation API, you can clearly see the entire programming model has been overhauled completely (for the better, in my opinion).

While this chapter has only touched on some of the key aspects of this .NET 4.0 API, I do hope you feel confident that you can dive into the topic further if you are interested.

■ Source Code The WorkflowLibraryClient project is included under the Chapter 26 subdirectory.

Summary

In essence, WF allows you to model an application's internal business processes directly within the application itself. Beyond simply modeling the overall workflow, however, WF provides a complete runtime engine and several services that round out this API's overall functionality (persistence and tracking services, etc.). While this introductory chapter did not examine these services directly, do remember that a production-level WF application will most certainly make use of these facilities.

.NET 4.0 completely changes the entire WF programming mode originally introduced in .NET 3.0. Going forward, we are able to model our workflows in a completely declarative manner using an XML-based grammar named XAML. Not only can we use XAML to define the state of each activity in our workflow, we can also embed "real code" into a XAML document indirectly when we make use of the WF designers.

In this introduction to the topic, you learned about two key top level activities, namely `Flowchart` and `Sequence`. While each of these types control the flow of logic in unique manners, they both can contain the same sort of child activities and are executed by the host in the same manner (via `WorkflowInvoker` or `WorkflowApplication`). You also learned how to pass host arguments *to* a workflow using a generic `Dictionary` object and how to retrieve output arguments *from* a workflow using a generic `IDictionary` compatible object.

PART 6

■ ■ ■

Building Desktop User Interfaces with WPF



Introducing Windows Presentation Foundation and XAML

When version 1.0 of the .NET platform was released, programmers who needed to build graphical desktop applications made use of two APIs named Windows Forms and GDI+, packaged up primarily in the `System.Windows.Forms.dll` and `System.Drawing.dll` assemblies. While Windows Forms/GDI+ are excellent APIs for building traditional desktop GUIs, Microsoft shipped an alternative GUI desktop API named Windows Presentation Foundation (WPF) beginning with the release of .NET 3.0.

This initial WPF chapter begins by examining the motivation behind this new GUI framework, which will help you see the differences between the Windows Forms/GDI+ and WPF programming models. Next, we will examine the different types of WPF applications supported by the API, and come to know the role of the several important classes including `Application`, `Window`, `ContentControl`, `Control`, `UIElement`, and `FrameworkElement`. During this time, you will learn to intercept keyboard and mouse activities, define application wide data, and other common WPF tasks using nothing but C# code.

This chapter will then introduce you to an XML-based grammar named *Extensible Application Markup Language* (XAML). Here, you will learn the syntax and semantics of XAML, including attached property syntax, the role of type converters, markup extensions, and understanding how to generate, load and parse XAML at runtime. As well, you will learn how to integrate XAML data into a C# WPF-code base (and the benefits of doing so).

This chapter wraps up by the integrated WPF designers of Visual Studio 2010. Here, you will build your own custom XAML editor/parser, which illustrates how XAML can be manipulated at runtime to build dynamic user interfaces.

Note The remaining WPF chapters of this book will introduce you to Microsoft Expression Blend, which is a WPF-centric tool dedicated to the generation of XAML on your behalf.

The Motivation Behind WPF

Over the years, Microsoft has created numerous graphical user interface toolkits (raw C/C++/Windows API development, VB6, MFC, etc.) to build desktop executables. Each of these APIs provided a code base to represent the basic aspects of a GUI application, including main windows, dialog boxes, controls, menu systems, and other basic necessities. With the initial release of the .NET platform, the Windows Forms

API quickly became the preferred model for UI development, given its simple yet very powerful object model.

While many full-featured desktop applications have been successfully created using Windows Forms, the fact of the matter is that this programming model is rather *asymmetrical*. Simply put, `System.Windows.Forms.dll` and `System.Drawing.dll` do not provide direct support for many additional technologies required to build a feature-rich desktop application. To illustrate this point, consider the ad hoc nature of GUI development before the release of WPF (e.g., .NET 2.0; see Table 27-1).

Table 27-1. .NET 2.0 Solutions to Desired Functionalities

Desired Functionality	.NET 2.0 Solution
Building windows with controls	Windows Forms
2D graphics support	GDI+ (<code>System.Drawing.dll</code>)
3D graphics support	DirectX APIs
Support for streaming video	Windows Media Player APIs
Support for flow-style documents	Programmatic manipulation of PDF files

As you can see, a Windows Forms developer must pull in types from a number of unrelated APIs and object models. While it is true that making use of these diverse APIs may look similar syntactically (it is just C# code, after all), you may also agree that each technology requires a radically different mind-set. For example, the skills required to create a 3D rendered animation using DirectX are completely different from those used to bind data to a grid. To be sure, it is very difficult for a Windows Forms programmer to master the diverse nature of each API.

■ **Note** Appendix A provides an introduction to Windows Forms and GDI+ application development.

Unifying Diverse APIs

WPF (introduced with .NET 3.0) was purposely created to merge these previously unrelated programming tasks into a single unified object model. Thus, if you need to author a 3D animation, you have no need to manually program against the DirectX API (although you could), as 3D functionality is baked directly into WPF. To see how well things have cleaned up, consider Table 27-2, which illustrates the desktop development model ushered in as of .NET 3.0.

Table 27-2. .NET 3.0 Solutions to Desired Functionalities

Desired Functionality	.NET 3.0 and Higher Solution
Building forms with controls	WPF
2D graphics support	WPF
3D graphics support	WPF
Support for streaming video	WPF
Support for flow-style documents	WPF

The obvious benefit here is that .NET programmers now have a single, symmetrical API for all common GUI programming needs. Once you become comfortable with the functionality of the key WPF assemblies and the grammar of XAML, you'll be amazed how quickly you can create very sophisticated UIs.

Providing a Separation of Concerns via XAML

Perhaps one of the most compelling benefits is that WPF provides a way to cleanly separate the look and feel of a Windows application from the programming logic that drives it. Using XAML, it is possible to define the UI of an application via XML *markup*. This markup (ideally generated using tools such as Microsoft Expression Blend) can then be connected to a managed code base to provide the guts of the program's functionality.

Note XAML is not limited to WPF applications! Any application can use XAML to describe a tree of .NET objects, even if they have nothing to do with a visible user interface. For example, the Windows Workflow Foundation API uses a XAML-based grammar to define business processes and custom activities.

As you dig into WPF, you may be surprised how much flexibility “desktop markup” provides. XAML allows you to define not only simple UI elements (buttons, grids, list boxes, etc.) in markup, but also 2D and 3D graphical data, animations, data binding logic, and multimedia functionality (such as video playback). For example, defining a circular button control that animates a company logo requires just a few lines of markup.

As shown in Chapter 31, WPF controls can be modified through styles and templates, which allow you to change the overall look and feel of an application with minimum fuss and bother. Unlike Windows Forms development, the only compelling reason to build a custom WPF control library is if you need to change the *behaviors* of a control (e.g., add custom methods, properties, or events; subclass an existing control to override virtual members). If you simply need to change the *look and feel* of a control (again, such as a circular animated button), you can do so entirely through markup.

Providing an Optimized Rendering Model

GUI toolkits such as Windows Forms, MFC or VB6 performed all graphical rendering requests (including the rendering of UI elements such as buttons and list boxes) using a low level, C-based API (GDI) which has been part of the Windows OS for years. GDI provides adequate performance for typical business applications or simple graphical programs; however, if a UI application needed to tap into high performance graphics, DirectX was required.

The WPF programming model is quite different in that GDI is *not* used when rendering graphical data. All rendering operations (e.g., 2D graphics, 3D graphics, animations, UI widget renderings buttons, list boxes) now make use of the DirectX API. The first obvious benefit is that your WPF applications will automatically take advantage of hardware and software optimizations. As well, WPF applications can tap into very rich graphical services (blur effects, anti-aliasing, transparency, etc.) without the complexity of programming directly against the DirectX API.

■ **Note** Although WPF does push all rendering requests to the DirectX layer, I don't want to suggest that a WPF application will perform as fast as building an application using unmanaged C++ and DirectX directly. If you are build a desktop application that requires the fastest possible execution speed (such as a 3D video game), unmanaged C++ and DirectX are still the best approach.

Simplifying Complex UI Programming

To recap the story thus far, Windows Presentation Foundation (WPF) is an API to build desktop applications that integrates various desktop APIs into a single object model and provides a clean separation of concerns via XAML. In addition to these major points, WPF applications also benefit from a very simple way to integrate services into your programs, which historically were quite complex to account for. Here is a quick rundown of the core WPF features:

- A number of layout managers (far more than Windows Forms) to provide extremely flexible control over placement and reposition of content.
- Use of an enhanced data-binding engine to bind content to UI elements in a variety of ways.
- A built-in style engine, which allows you to define “themes” for a WPF application.
- Use of vector graphics, which allows content to be automatically resized to fit the size and resolution of the screen hosting the application.
- Support for 2D and 3D graphics, animations, and video and audio playback.
- A rich typography API, such as support for XML Paper Specification (XPS) documents, fixed documents (WYSIWYG), flow documents, and document annotations (e.g., a Sticky Notes API).

- Support for interoperating with legacy GUI models (e.g., Windows Forms, ActiveX, and Win32 HWNDs). For example, you can incorporate custom Windows Forms controls into a WPF application, and vice versa.

Now that you have some idea of what WPF brings to the table, let's turn our attention to the various types of applications that can be created using this API.

The Various Flavors of WPF

The WPF API can be used to build a variety of GUI-centric applications that basically differ in their navigational structure and deployment models. The sections that follow present a high-level walk through each option.

Traditional Desktop Applications

The first (and most familiar) option is to use WPF to build a traditional executable assembly that runs on a local machine. For example, you could use WPF to build a text editor, painting program, or multimedia program such as a digital music player, photo viewer, and so forth. Like any other desktop applications, these *.exe files can be installed using traditional means (setup programs, Windows Installer packages, etc.) or via ClickOnce technology to allow desktop applications to be distributed and installed via a remote web server.

Programmatically speaking, this type of WPF application will make use (at a minimum) of the Window and Application types, in addition to the expected set of dialog boxes, toolbars, status bars, menu systems, and other UI elements.

Now, you can certainly use WPF to build your basic, bland business application that does not support any bells and whistles, but WPF really shines when you *do* incorporate such features. Consider Figure 27-1, which shows a WPF sample desktop application for viewing patient records in a medical environment.



Figure 27-1. This WPF desktop application makes use of several WPF APIs

Sadly, the printed page does not show the full feature set of this window. Note that the upper right of the main window is displaying a real time graph of the patient's sinus rhythm. If you click on Patient Details button on the lower right, several animations take place to flip, rotate and transform the UI to the following look and feel (Figure 27-2).



Figure 27-2. Transformations and animations are very simple under WPF

Could you build this same application without WPF? Absolutely. However, the amount of code—and the complexity of the code—would be much higher.

Note This example application can be downloaded (with source code) from the office WPF web site, <http://windowsclient.net>. Here you will find numerous WPF (and Windows Forms) sample projects, technology walkthroughs and forums.

Navigation-Based WPF Applications

WPF applications can optionally choose to make use of a navigation-based structure, which makes a traditional desktop application take on the basic behavior of a web browser application. Using this model, you can build a desktop *.exe that provides a “forward” and “back” button that allows the end user to move back and forth between various UI displays called *pages*.

The application itself maintains a list of each page and provides the necessary infrastructure to navigate between them, pass data across pages (similar to a web-based application variable), and maintain a history list. By way of a concrete example, consider Windows Explorer (see Figure 27-3), which makes use of such functionality. Notice the navigation buttons (and history list) mounted on the upper-left corner of the window.




Figure 27-3. A navigation-based desktop program

Regardless of the fact that a WPF desktop application can take on a weblike navigational structure, understand that this is simply a UI design issue. The application itself is still little more than a local executable assembly running on a desktop machine, and it has little to do with a web application beyond a slightly similar look and feel. Programmatically speaking, this type of WPF application is constructed using classes such as `Application`, `Page`, `NavigationWindow`, and `Frame`.

XBAP Applications

WPF also allows you to build applications that can be hosted *within* a web browser. This flavor of WPF application is termed an XAML browser application, or XBAP. Under this model, the end user navigates to a given URL, at which point the XBAP (which is essentially a collection of `Page` objects) is transparently downloaded and installed to the local machine. Unlike a traditional ClickOnce installation for an executable application, however, the XBAP program is hosted directly within the browser and adopts the browser’s intrinsic navigational system. Figure 27-4 illustrates an XBAP program in action (specifically, the ExpenseIt WPF sample program that ships with the .NET Framework 4.0 SDK).




Figure 27-4. XBAP programs are downloaded to a local machine and hosted within a web browser

The benefit of an XBAP is that it allows you to create sophisticated UIs which are much more expressive than a typical web page built with HTML and JavaScript. An XBAP Page object can make use of the same WPF services as a desktop WPF application, including animations, 2D and 3D graphics, themes and whatnot. In effect, the web browser is just a container for WPF Page objects, and is *not* displaying ASP.NET web pages.

However, given that these Page objects are deployed to a remote web server, XBAPs can be easily versioned and updated without the need to redeploy executables to the user's desktop. Like a traditional web program, you can simply update the Page objects in the web server, and the user will get the 'latest and greatest' when they access the URL.

One downside to this flavor of WPF is that XBAPs must be hosted within Microsoft Internet Explorer or Firefox web browsers. If you are deploying XBAPs across a company intranet, browser compatibility should not be a problem, given that system administrators can play dictator regarding which browser should be installed on users' machines. However, if you want the outside world to make use of your XBAP, it is not possible to ensure each end user is making use of Internet Explorer/Firefox, and therefore some external users may not be able to view your WPF XBAP.

Another issue to be aware of is the machine which is viewing an XBAP must have a local installation of the .NET framework, as the Page objects will be using the same .NET assemblies as an application running natively on the machine. Given this particular point, XBAPs are limited to Windows operating systems and thus cannot be viewed on a system running Mac OS X or Linux.

The WPF/Silverlight Relationship

WPF and XAML also provide the foundation for a cross-platform, cross-browser WPF-based technology termed Silverlight. From a high level, you can consider Silverlight as a competitor to Adobe Flash, with the benefit of using C# and XAML rather than a new set of tools and languages. Silverlight is a subset of WPF functionality, which is used to build highly interactive plug-ins for a larger HTML-based web page. In reality, however, Silverlight is a completely unique distribution of the .NET platform, which ships with a "mini" CLR and "mini" version of the .NET base class libraries.

Unlike an XBAP, the user's machine does not need a full installation of the .NET Framework. As long as the target machine has the Silverlight runtime installed, the browser will load the Silverlight runtime and display the Silverlight application automatically. Best of all, Silverlight plug-ins are not limited to the Windows operating systems! Microsoft has also created a Silverlight runtime for Mac OS X.

■ **Note** The Mono project (see Appendix B) provides an open source version of Silverlight for Linux based OSs named Moonlight. This API, in conjunction with Silverlight, provides the fabric for a true cross-platform model for extremely rich web pages.

With Silverlight, you are able to build extremely feature-rich (and interactive) web applications. For example, like WPF, Silverlight has a vector-based graphical system, animation support, and multimedia support. Furthermore, you are able to incorporate a subset of the .NET base class library into your applications. This subset includes a number of WPF controls, LINQ support, generic collection types, web service support, and a healthy subset of `mscorlib.dll` (file I/O, XML manipulation, etc.).

■ **Note** This edition of the text does not address Silverlight; however, a majority of your WPF knowledge will map directly to the construction of Silverlight web plug-ins. If you are interested in learning more about this API, check out <http://www.silverlight.net>.

Investigating the WPF Assemblies

Regardless of which type of WPF application you wish to build, WPF is ultimately little more than a collection of types bundled within .NET assemblies. Table 27-3 describes the core assemblies used to build WPF applications, each of which must be referenced when creating a new project (as you would hope, Visual Studio 2010 and Expression Blend WPF projects automatically reference the required assemblies).

Table 27-3. Core WPF Assemblies

Assembly	Meaning in Life
PresentationCore.dll	This assembly defines numerous types that constitute the foundation of the WPF GUI layer. For example, this assembly contains support for the WPF Ink API (for programming against stylus input for Pocket PCs and Tablet PCs), several animation primitives, and numerous graphical rendering types.
PresentationFramework.dll	This assembly contains a majority of the WPF controls, the Application and Window classes, and support for interactive 2D geometries. As well, this library provides basic functionality to read and write XAML documents at runtime.
System.Xaml.dll	This assembly provides namespaces which allow you to program against a XAML document at runtime. By and large, this library is only useful if you are authoring WPF support tools or need absolute control over XAML at runtime.
WindowsBase.dll	This assembly defines types that constitute the infrastructure of the WPF API., including those representing WPF threading types, security types, various type converters, and support for <i>dependency properties</i> and <i>routed events</i> (described in Chapter 29).

Collectively, these assemblies define a number of new namespaces and hundreds of new .NET classes, interfaces, structures, enumerations, and delegates. While you should consult the .NET Framework 4.0 SDK documentation for complete details, Table 27-4 describes the role of some (but certainly not all) of the namespaces you should be aware of.

Table 27-4. Core WPF Namespaces

Namespace	Meaning in Life
System.Windows	This is the root namespace of WPF. Here you will find core classes (such as Application and Window) that are required by any WPF desktop project.
System.Windows.Controls	Contains all of the expected WPF widgets, including types to build menu systems, tool tips, and numerous layout managers.
System.Windows.Data	Types to work with the WPF data binding engine, as well as support for data binding templates.
System.Windows.Documents	Contains types to work with the documents API, which allows you to integrate PDF style functionality into your WPF applications, via the XML Paper Specification (XPS) protocol.

Table 27-4. Core WPF Namespaces (continued)

Namespace	Meaning in Life
System.Windows.Ink	Support for the Ink API, which allows you to capture input from a stylus or mouse, respond to input gestures, and so forth. Very useful for Tablet PC program; however, any WPF can make use of this API.
System.Windows.Markup	This namespace defines a number of types that allow XAML markup (and the equivalent binary format, BAML) to be parsed and processed programmatically.
System.Windows.Media	This is the root namespace to several media-centric namespaces. Within these namespaces you will find types to work with animations, 3D rendering, text rendering, and other multimedia primitives.
System.Windows.Navigation	This namespace provides types to account for the navigation logic employed by XAML browser applications (XBAPs) as well as standard desktop applications that require a navigational page model.
System.Windows.Shapes	Defines classes which allow you to render interactive 2D graphics that automatically respond to mouse input.

To begin your journey into the WPF programming model, you'll examine two members of the System.Windows namespace that are commonplace to any traditional desktop development effort: Application and Window.

Note If you are new to the development of desktop applications using the .NET platform, be aware that the System.Windows.Forms.* and System.Drawing.* assemblies are not related to WPF! These libraries represent the original .NET GUI toolkit, Windows Forms (see Appendix A).

The Role of the Application Class

The System.Windows.Application class represents a global instance of a running WPF application. This class supplies a Run() method (to start the application), a series of events that you are able to handle in order to interact with the application's lifetime (such as Startup and Exit), and a number of events that are specific to XAML browser applications (such as events that fire as a user navigates between pages). Table 27-5 details some of the key properties to be aware of.

Table 27-5. Key Properties of the Application Type

Property	Meaning in Life
Current	This static property allows you to gain access to the running Application object from anywhere in your code. This can be very helpful when a window or dialog box needs to gain access to the Application object that created it, typically to access application wide variables and functionality.
MainWindow	This property allows you to programmatically get or set the main window of the application.
Properties	This property allows you to establish and obtain data that is accessible throughout all aspects of a WPF application (windows, dialog boxes, etc.).
StartupUri	This property gets or sets a URI that specifies a window or page to open automatically when the application starts.
Windows	This property returns a WindowCollection type, which provides access to each window created from the thread that created the Application object. This can be very helpful when you wish to iterate over each open window of an application and alter its state (such as minimizing all windows).

Constructing an Application Class

Any WPF application will need to define a class that extends `Application`. Within this class, you will define your program's entry point (the `Main()` method), which creates an instance of this subclass and typically handles the `Startup` and `Exit` events. You will build a full example project in just a moment, but here is a quick example:

```
// Define the global application object
// for this WPF program.
class MyApp : Application
{
    [STAThread]
    static void Main(string[] args)
    {
        // Create the application object.
        MyApp app = new MyApp();

        // Register the Startup / Exit events.
        app.Startup += (s, e) => { /* Start up the app */ };
        app.Exit += (s, e) => { /* Exit the app */ };
    }
}
```

Within the Startup handler, you will most often process any incoming command line arguments and launch the main window of the program. The Exit handler, as you would expect, is where you can author any necessary shut down logic for the program (e.g., save user preferences, write to the Windows registry).

Enumerating the Application.Windows collection

Another interesting property exposed by Application is Windows, which provides access to a collection representing each window loaded into memory for the current WPF application. Recall that as you create new Window objects, they are automatically added into the Application.Windows collection. Here is an example method that will minimize each window of the application (perhaps in response to a given keyboard gesture or menu option triggered by the end user):

```
static void MinimizeAllWindows()
{
    foreach (Window wnd in Application.Current.Windows)
    {
        wnd.WindowState = WindowState.Minimized;
    }
}
```

You'll build a complete Application-derived type in an upcoming example. Until then, let's check out the core functionality of the Window type and learn about a number of important WPF base classes in the process.

The Role of the Window Class

The System.Windows.Window class represents a single window owned by the Application-derived class, including any dialog boxes displayed by the main window. Not surprisingly, Window has a series of parent classes, each of which brings more functionality to the table. Consider Figure 27-5, which shows the inheritance chain (and implemented interfaces) for System.Windows.Window as seen through the Visual Studio 2010 object browser.




Figure 27-5. The hierarchy of the Window class

You'll come to understand the functionality provided by many of these base classes as you progress through this chapter and the chapters to come. However, to whet your appetite, the following sections present a breakdown of the functionality provided by each base class (consult the .NET Framework 4.0 SDK documentation for full details).

The Role of System.Windows.Controls.ContentControl

The direct parent of Window is ContentControl, which is quite possibly the most enticing of all WPF classes. This base class provides derived types with the ability to host a single piece of *content*, which, simply put, refers to the data placed within the interior of the control's surface area via the Content property. The WPF content model makes it very simple to customize the basic look and feel of a content control.

For example, when you think of a typical "button" control, you tend to assume that the content is a basic string literal (OK, Cancel, Abort, etc.). If you are using XAML to describe a WPF control, and the value you wish to assign to the Content property can be captured as a simple string, you may set the Content property within the element's opening definition as so (don't fret over the exact markup at this point):

```
<!-- Setting the Content value in the opening element -->
<Button Height="80" Width="100" Content="OK"/>
```

Note The Content property can also be set in C# code, which allows you to change the interior of a control at runtime.

However, content can be anything. For example, let's say you wish to have a "button" that has something more interesting than a simple string, perhaps a custom graphic and a blurb of text. In other UI frameworks such as Windows Forms, you would be required to build a custom control, which could entail quite a bit of code and a whole new class to maintain. With the WPF content model, there is no need to do so.

When you wish to assign to the `Content` property to a value which cannot be captured as a simple array of characters, you are unable to assign the `Content` property using an attribute in the control's opening definition. Rather, you must define the content data *implicitly*, within the element's scope. For example, this `<Button>` contains a `<StackPanel>` as content, which itself contains some unique data (an `<Ellipse>` and `<Label>`, to be exact):

```
<!-- Implicitly setting the Content property with complex data -->
<Button Height="80" Width="100">
  <StackPanel>
    <Ellipse Fill="Red" Width="25" Height="25"/>
    <Label Content ="OK!"/>
  </StackPanel>
</Button>
```

You can also make use of XAML's *property-element syntax* to set complex content. Consider the following functionally equivalent `<Button>` definition, which sets the `Content` property explicitly using property-element syntax (again, you'll find more information on XAML later in this chapter, so don't sweat the details just yet):

```
<!-- Setting the Content property using property element syntax -->
<Button Height="80" Width="100">
  <Button.Content>
    <StackPanel>
      <Ellipse Fill="Red" Width="25" Height="25"/>
      <Label Content ="OK!"/>
    </StackPanel>
  <Button.Content>
</Button>
```

Do be aware that not every WPF control derives from `ContentControl`, and therefore not all controls supports this unique content model. As well, some WPF controls add a few refinements to the basic content model you have just examined. Chapter 28 will examine the role of WPF content in much more detail.

The Role of `System.Windows.Controls.Control`

Unlike `ContentControl`, all WPF controls share the `Control` base class as a common parent. This base class provides numerous core members that account for basic UI functionality. For example, `Control` defines properties to establish the control's size, opacity, tab order logic, the display cursor, background color, and so forth. Furthermore, this parent class provides support for *templating services*. As explained in Chapter 31, WPF controls can completely change the way they render their appearance using templates and styles. Table 27-6 documents some key members of the `Control` type, grouped by related functionality.

Table 27-6. Key Members of the Control Type

Members	Meaning in Life
Background, Foreground, BorderBrush, BorderThickness, Padding, HorizontalContentAlignment, VerticalContentAlignment	These properties allow you to set basic settings regarding how the control will be rendered and positioned.
FontFamily, FontSize, FontStretch, FontWeight	These properties control various font-centric settings.
IsTabStop, TabIndex	These properties are used to establish tab order among controls on a window.
MouseDoubleClick, PreviewMouseDoubleClick	These events handle the act of double-clicking a widget.
Template	This property allows you to get and set the control's template, which can be used to change the rendering output of the widget.

The Role of System.Windows.FrameworkElement

This base class provides a number of members that are used throughout the WPF framework, such as support for storyboarding (used within animations) and support for data binding, as well as the ability to name a member (via the `Name` property), obtain any resources defined by the derived type, and establish the overall dimensions of the derived type. Table 27-7 hits the highlights.

Table 27-7. Key Members of the FrameworkElement Type

Members	Meaning in Life
ActualHeight, ActualWidth, MaxHeight, MaxWidth, MinHeight, MinWidth, Height, Width	These properties control the size of the derived type.
ContextMenu	Gets or sets the pop-up menu associated with the derived type.
Cursor	Gets or sets the mouse cursor associated with the derived type.
HorizontalAlignment, VerticalAlignment	Gets or sets how the type is positioned within a container (such as a panel or list box).
Name	Allows to you assign a name to the type, in order to access its functionality in a code file.

Table 27-7. Key Members of the *FrameworkElement* Type (continued)

Members	Meaning in Life
Resources	Provides access to any resources defined by the type (see Chapter 30 for an examination of the WPF resource system).
ToolTip	Gets or sets the tool tip associated with the derived type.

The Role of *System.Windows.UIElement*

Of all the types within a Window's inheritance chain, the *UIElement* base class provides the greatest amount of functionality. The key task of *UIElement* is to provide the derived type with numerous events to allow the derived type to receive focus and process input requests. For example, this class provides numerous events to account for drag-and-drop operations, mouse movement, keyboard input, and stylus input (for Pocket PCs and Tablet PCs).

Chapter 29 digs into the WPF event model in detail; however, many of the core events will look quite familiar (*MouseMove*, *KeyUp*, *MouseDown*, *MouseEnter*, *MouseLeave*, etc.). In addition to defining dozens of events, this parent class provides a number of properties to account for control focus, enabled state, visibility, and hit testing logic, as shown in Table 27-8.

Table 27-8. Key Members of the *UIElement* Type

Members	Meaning in Life
<i>Focusable</i> , <i>IsFocused</i>	These properties allow you to set focus on a given derived type.
<i>.IsEnabled</i>	This property allows you to control whether a given derived type is enabled or disabled.
<i>IsMouseDirectlyOver</i> , <i>IsMouseOver</i>	These properties provide a simple way to perform hit-testing logic.
<i>IsVisible</i> , <i>Visibility</i>	These properties allow you to work with the visibility setting of a derived type.
<i>RenderTransform</i>	This property allows you to establish a transformation that will be used to render the derived type.

The Role of *System.Windows.Media.Visual*

The *Visual* class type provides core rendering support in WPF, which includes hit testing of rendered data, coordinate transformation, and bounding box calculations. In fact, the *Visual* class interacts with

the underlying DirectX subsystem to actually draw data on the screen. As examined in Chapter 29, WPF provides three possible manners in which you can render graphical data, each of which differs in terms of functionality and performance. Use of the `Visual` type (and its children, such as `DrawingVisual`) provides the most lightweight way to render graphical data, but it also entails the greatest amount of manual code to account for all the required services. Again, more details to come in Chapter 29.

The Role of `System.Windows.DependencyObject`

WPF supports a particular flavor of .NET properties termed *dependency properties*. Simply put, this approach allows a type to compute the value of a property based on the value of other properties. In order for a type to participate in this new property scheme, it will need to derive from the `DependencyObject` base class. In addition, `DependencyObject` allows derived types to support *attached properties*, which are a form of dependency property very useful when programming against the WPF data-binding model as well as when laying out UI elements within various WPF panel types.

The `DependencyObject` base class provides two key methods to all derived types: `GetValue()` and `SetValue()`. Using these members, you are able to establish the property itself. Other bits of infrastructure allow you to “register” who can use the dependency/attached property in question. While dependency properties are a key aspect of WPF development, much of the time their details are hidden from view. Chapter 29 dives further into the details of the “new” property type.

The Role of `System.Windows.Threading.DispatcherObject`

The final base class of the `Window` type (beyond `System.Object`, which I assume needs no further explanation at this point in the book) is `DispatcherObject`. This type provides one property of interest, `Dispatcher`, which returns the associated `System.Windows.Threading.Dispatcher` object. The `Dispatcher` class is the entry point to the event queue of the WPF application, and it provides the basic constructs for dealing with concurrency and threading. By and large, this is a lower-level class that can be ignored by the majority of your WPF applications.

Building a WPF Application without XAML

Given all of the functionality provided by the parent classes of the `Window` type, it is possible to represent a window in your application by either directly creating a `Window` object or using this class as the parent to a strongly typed descendent. Let’s examine both approaches in the following code example. Although most WPF applications will make use of XAML, doing so is entirely optional. Anything that can be expressed in XAML can be expressed in code and (for the most part) vice versa. If you wish, it is possible to build a complete WPF project using the underlying object model and procedural code.

To illustrate, let’s create a minimal but complete application *without* the use of XAML using the `Application` and `Window` classes directly. Begin by creating a new Console Application named `WpfAppAllCode` (don’t worry, you will use the Visual Studio WPF project template later in this chapter). Next, access the `Project | Add Reference` dialog box and add a reference to `WindowsBase.dll`, `PresentationCore.dll`, `System.Xaml.dll` and `PresentationFramework.dll`.

Now, update your initial C# file with the following code, which creates a window of modest functionality:

```
// A simple WPF application, written without XAML.
using System;
```

```

using System.Windows;
using System.Windows.Controls;

namespace WpfAppAllCode
{
    // In this first example, you are defining a single class type to
    // represent the application itself and the main window.
    class Program : Application
    {
        [STAThread]
        static void Main(string[] args)
        {
            // Handle the Startup and Exit events, and then run the application.
            Program app = new Program();
            app.Startup += AppStartup;
            app.Exit += AppExit;
            app.Run(); // Fires the Startup event.
        }

        static void AppExit(object sender, ExitEventArgs e)
        {
            MessageBox.Show("App has exited");
        }

        static void AppStartup(object sender, StartupEventArgs e)
        {
            // Create a Window object and set some basic properties.
            Window mainWindow = new Window();
            mainWindow.Title = "My First WPF App!";
            mainWindow.Height = 200;
            mainWindow.Width = 300;
            mainWindow.WindowStartupLocation = WindowStartupLocation.CenterScreen;
            mainWindow.Show();
        }
    }
}

```

Note The `Main()` method of a WPF application must be attributed with the `[STAThread]` attribute, which ensures any legacy COM objects used by your application are thread-safe. If you do not annotate `Main()` in this way, you will encounter a runtime exception.

Note that the `Program` class extends the `System.Windows.Application` class. Within the `Main()` method, you create an instance of the `application` object and handle the `Startup` and `Exit` events using method group conversion syntax. Recall from Chapter 11 that this shorthand notation removes the need to manually specify the underlying delegates used by a particular event.

Of course, if you wish, you can specify the underlying delegates directly by name. In the following modified Main() method, notice that the Startup event works in conjunction with the StartupEventHandler delegate, which can only point to methods taking an Object as the first parameter and a StartupEventArgs as the second. The Exit event, on the other hand, works with the ExitEventHandler delegate, which demands that the method pointed to take an ExitEventArgs type as the second parameter:

```
[STAThread]
static void Main(string[] args)
{
    // This time, specify the underlying delegates.
    MyWPFApp app = new MyWPFApp();
    app.Startup += new StartupEventHandler(AppStartUp);
    app.Exit += new ExitEventHandler(AppExit);
    app.Run(); // Fires the Startup event.
}
```

In any case, the AppStartUp() method has been configured to create a Window object, establish some very basic property settings, and call Show() to display the window on the screen in a modeless fashion (the ShowDialog() method can be used to launch a modal dialog). The AppExit() method simply makes use of the WPF MessageBox class to display a diagnostic message when the application is being terminated.

Once you compile and run the project, you will find a very simple main window that can be minimized, maximized, and closed. To spice things up a bit, you need to add some user interface elements. Before you do, however, you should refactor your code base to account for a strongly typed and well-encapsulated Window-derived class.

Creating a Strongly Typed Window

Currently, the Application-derived class directly creates an instance of the Window type upon application startup. Ideally, you would create a class deriving from Window in order to encapsulate its appearance and functionality. Assume that you have created the following class definition within your current WpfAppAllCode namespace (if you place this class in a new C# file, be sure to import the System.Windows namespace):

```
class MainWindow : Window
{
    public MainWindow(string windowTitle, int height, int width)
    {
        this.Title = windowTitle;
        this.WindowStartupLocation = WindowStartupLocation.CenterScreen;
        this.Height = height;
        this.Width = width;
    }
}
```

You can now update your Startup event handler to simply directly create an instance of MainWindow:

```
static void AppStartUp(object sender, StartupEventArgs e)
{
```

```
// Create a MainWindow object.
MainWindow wnd = new MainWindow("My better WPF App!", 200, 300);
wnd.Show();
}
```

Once the program is recompiled and executed, the output is identical. The obvious benefit is that you now have a strongly typed window class to build upon.

Note When you create a Window (or Window-derived) object, it will automatically be added to the windows collection of the Application class (via some constructor logic found in the Window class itself). You can use the Application.Windows property to iterate over the list of Window objects currently in memory.

Creating a Simple User Interface

Adding a UI element to a Window in C# code will involve the following basic steps:

1. Define a member variable to represent the control.
2. Configure the control's look and feel upon Window construction.
3. Assign the control to the inherited Content property, or alternatively, as a parameter to the inherited AddChild() method.

Recall that the WPF control content model demands that the Content property is set only once. Of course, a Window that only contained a single UI control would be quite useless. Therefore, in almost every case, the "single piece of content" that is assigned to the Content property is, in reality, a layout manager, such as DockPanel, Grid, Canvas, or StackPanel. Within the layout manager, you can have any combination of internal controls, including other nested layout managers. (Read more on this aspect of WPF development in Chapter 28.)

For now, you will add a single Button control to your Window derived class. When you click the button, you will close the current window, which will indirectly terminate the application, as you have no other windows in memory. Ponder the following update to the MainWindow class (be sure you have imported System.Windows.Controls to gain access to the Button class):

```
class MainWindow : Window
{
    // Our UI element.
    private Button btnExitApp = new Button();

    public MainWindow(string windowTitle, int height, int width)
    {
        // Configure button and set the child control.
        btnExitApp.Click += new RoutedEventHandler(btnExitApp_Clicked);
        btnExitApp.Content = "Exit Application";
        btnExitApp.Height = 25;
        btnExitApp.Width = 100;
```

```

// Set the content of this window to a single button.
this.Content = btnExitApp;

// Configure the window.
this.Title = windowTitle;
this.WindowStartupLocation = WindowStartupLocation.CenterScreen;
this.Height = height;
this.Width = width;
this.Show();
}

private void btnExitApp_Clicked(object sender, RoutedEventArgs e)
{
    // Close the window.
    this.Close();
}
}

```

Notice that the `Click` event of the WPF Button works in conjunction with a delegate named `RoutedEventHandler`, which begs the question, what is a routed event? You'll examine the details of the WPF event model in the next chapter; for the time being, simply understand that targets of the `RoutedEventHandler` delegate must supply an `object` as the first parameter and a `RoutedEventArgs` as the second.

In any case, once you recompile and run this application, you will find the customized window shown in Figure 27-6. Notice that your button is automatically placed in the dead center of the window's client area; this is the default behavior when content is not placed within a WPF panel type.




Figure 27-6. A Simple WPF application written in 100% C# code

Interacting with Application Level Data

Recall that the `Application` class defines a property named `Properties`, which allows you to define a collection of name/value pairs via a type indexer. Because this indexer has been defined to operate on type `System.Object`, you are able to store any sort of item within this collection (including your custom classes), to be retrieved at a later time using a friendly moniker. Using this approach, it is simple to share data across all windows in a WPF application.

To illustrate, you will update the current `Startup` event handler to check the incoming command-line arguments for a value named `/GODMODE` (a common cheat code for many PC video games). If you find

this token, you will establish a bool value set to true within the properties collection of the same name (otherwise you will set the value to false).

Sounds simple enough, but how are you going to pass the incoming command-line arguments (typically obtained from the `Main()` method) to your `Startup` event handler? One approach is to call the static `Environment.GetCommandLineArgs()` method. However, these same arguments are automatically added to the incoming `StartupEventArgs` parameter and can be accessed via the `Args` property. That being said, here is the first update to the current code base:

```
private static void AppStartUp(object sender, StartupEventArgs e)
{
    // Check the incoming command-line arguments and see if they
    // specified a flag for /GODMODE.
    Application.Current.Properties["GodMode"] = false;
    foreach(string arg in e.Args)
    {
        if (arg.ToLower() == "/godmode")
        {
            Application.Current.Properties["GodMode"] = true;
            break;
        }
    }

    // Create a MainWindow object.
    MainWindow wnd = new MainWindow("My better WPF App!", 200, 300);
}
```

Application-wide data can be accessed from anywhere within the WPF application. All you are required to do is obtain an access point to the global application object (via `Application.Current`) and investigate the collection. For example, you could update the `Click` event handler of the `Button` as so:

```
private void btnExitApp_Clicked(object sender, RoutedEventArgs e)
{
    // Did user enable /godmode?
    if((bool)Application.Current.Properties["GodMode"])
        MessageBox.Show("Cheater!");

    this.Close();
}
```

With this, if the end user launches our program as follows:

```
WpfAppAllCode.exe /godmode
```

he or she will see our shameful message box displayed when terminating the application.

■ **Note** Recall that you can supply command line arguments within Visual Studio. Simply double click on the Properties icon within Solution Explorer, click the Debug tab from the resulting editor, and enter /godmode within the "Command line arguments" editor.

Handling the Closing of a Window Object

End users can shut down a window using numerous built-in system-level techniques (e.g., clicking the "X" close button on the window's frame) or by indirectly calling the `Close()` method in response to some user interaction element (e.g., File ▶ Exit). In either case, WPF provides two events that you can intercept to determine if the user is *truly* ready to shut down the window and remove it from memory. The first event to fire is `Closing`, which works in conjunction with the `CancelEventHandler` delegate.

This delegate expects target methods to take `System.ComponentModel.CancelEventArgs` as the second parameter. `CancelEventArgs` provides the `Cancel` property, which when set to true will prevent the window from actually closing (this is handy when you have asked the user if he really wants to close the window or if perhaps he would like to save his work first).

If the user did indeed wish to close the window, `CancelEventArgs.Cancel` can be set to false. This will then cause the `Closed` event to fire (which works with the `System.EventHandler` delegate), making it the point at which the window is about to be closed for good.

Update the `MainWindow` class to handle these two events by adding these code statements to the current constructor:

```
public MainWindow(string windowTitle, int height, int width)
{
    ...
    this.Closing += MainWindow_Closing;
    this.Closed += MainWindow_Closed;
}
```

Now, implement the corresponding event handlers as so:

```
private void MainWindow_Closing(object sender,
    System.ComponentModel.CancelEventArgs e)
{
    // See if the user really wants to shut down this window.
    string msg = "Do you want to close without saving?";
    MessageBoxResult result = MessageBox.Show(msg,
        "My App", MessageBoxButton.YesNo, MessageBoxIcon.Warning);

    if (result == MessageBoxResult.No)
    {
        // If user doesn't want to close, cancel closure.
        e.Cancel = true;
    }
}

private void MainWindow_Closed(object sender, EventArgs e)
```

```
{
    MessageBox.Show("See ya!");
}
```

Now, run your program and attempt to close the window, either by clicking the "X" icon on the upper right of the window or by clicking the button control. You should see the following confirmation dialog (Figure 27-7).




Figure 27-7. Trapping the Closing event of a Window

If you click the Yes button, the application will terminate; however, clicking the No button will keep the window in memory.

Intercepting Mouse Events

The WPF API provides a number of events you can capture in order to interact with the mouse. Specifically, the `UIElement` base class defines a number of mouse-centric events such as `MouseMove`, `MouseUp`, `MouseDown`, `MouseEnter`, `MouseLeave`, and so forth.

Consider, for example, the act of handling the `MouseMove` event. This event works in conjunction with the `System.Windows.Input.MouseEventHandler` delegate, which expects its target to take a `System.Windows.Input.MouseEventArgs` type as the second parameter. Using `MouseEventArgs` (like a Windows Forms application), you are able to extract out the (x, y) position of the mouse and other relevant details. Consider the following partial definition:

```
public class MouseEventArgs : InputEventArgs
{
    ...
    public Point GetPosition(IInputElement relativeTo);
    public MouseButtonState LeftButton { get; }
    public MouseButtonState MiddleButton { get; }
    public MouseDevice MouseDevice { get; }
    public MouseButtonState RightButton { get; }
    public StylusDevice StylusDevice { get; }
    public MouseButtonState XButton1 { get; }
    public MouseButtonState XButton2 { get; }
}
```

■ **Note** The XButton1 and XButton2 properties allow you to interact with "extended mouse buttons" (such as the "next" and "previous" buttons found on some mouse controls). These are often used to interact with a browser's history list to navigate between visited pages.

The GetPosition() method allows you to get the (x, y) value relative to a UI element on the window. If you are interested in capturing the position relative to the activated window, simply pass in this. Handle the MouseMove event in the constructor of your MainWindow class like so:

```
public MainWindow(string windowTitle, int height, int width)
{
...
    this.MouseEventHandler += MainWindow_MouseMove;
}
```

Here is an event handler for MouseMove that will display the location of the mouse in the window's title area (notice you are translating the returned Point type into a text value via ToString()):

```
private void MainWindow_MouseMove(object sender,
    System.Windows.Input.MouseEventArgs e)
{
    // Set the title of the window to the current X,Y of the mouse.
    this.Title = e.GetPosition(this).ToString();
}
```

Intercepting Keyboard Events

Processing keyboard input is also very straightforward. UIElement defines a number of events that you can capture to intercept keypresses from the keyboard on the active element (e.g., KeyUp, KeyDown). The KeyUp and KeyDown events both work with the System.Windows.Input.KeyEventHandler delegate, which expects the target's second event handler to be of type KeyEventArgs, which defines several public properties of interest:

```
public class KeyEventArgs : KeyboardEventArgs
{
...
    public bool IsDown { get; }
    public bool IsRepeat { get; }
    public bool IsToggled { get; }
    public bool IsUp { get; }
    public Key Key { get; }
    public KeyStates KeyStates { get; }
    public Key SystemKey { get; }
}
```

To illustrate handling the `KeyDown` event in the constructor of `MainWindow` (just like you did for the previous events) and implement the following event handler that changes the content of the button with the currently pressed key, use this code:

```
private void MainWindow_KeyDown(object sender, System.Windows.Input.KeyEventArgs e)
{
    // Display key press on the button.
    btnExitApp.Content = e.Key.ToString();
}
```

As a finishing touch, double click on the Properties icon of the Solution Explorer, and under the Application tab, set the Output Type setting to Windows Application. This will prevent the console window from launching in the background of your WPF application. Figure 27-8 shows the final product of your first WPF program.



Figure 27-8. Your first WPF program, 100% XAML free

At this point in the chapter, WPF might look like nothing more than yet another GUI framework that is providing (more or less) the same services as Windows Forms, MFC or VB6. If this were in fact the case, you might question the need for yet another UI toolkit. To truly see what makes WPF so unique requires an understanding of the XML-based grammar, XAML.

■ **Source Code** The `WpfAppAllCode` project is included under the Chapter 27 subdirectory.

Building a WPF Application using Only XAML

A typical WPF application will *not* be composed exclusively of code, as you did in this first example. Rather, your C# code files will be paired with a related XAML source file, and together they represent the entirety of a given Window or Application, as well as other class types we have not yet examined such as `UserControl` and `Page`.

This approach is termed the *code file* approach to building a WPF application, and you will make use of this technique extensively throughout the remainder of the books WPF coverage. However, before you do, the next example will illustrate how to build a WPF application using nothing but XAML files. While

this "100% XAML" approach is not recommended, it will help you clearly understand how blobs of markup are transformed into a corresponding C# code base, and ultimately, a .NET assembly.

Note This next example will make use of a number of XAML techniques we have not yet formally examined, so don't sweat the details. You may wish to simply load the solution files into a text editor and follow along; however, don't use Visual Studio 2010 to do so! Some of the markup in this sample contains markup that cannot be displayed in the Visual Studio XAML designers.

In general, XAML files will contain markup that describes the look and feel of the window , while the related C# code files contain the implementation logic. For example, the XAML file for a Window might describe the overall layout system, the controls within that layout system, and specify the names of various event handlers. The related C# file would contain the implementation logic of these event handlers and any custom code required by the application.

Extensible Application Markup Language, or XAML, is an XML-based grammar that allows you to define the state (and, to some extent, the functionality) of a tree of .NET objects through markup. While XAML is frequently used when building UIs with WPF, in reality it can be used to describe any tree of *nonabstract* .NET types (including your own custom types defined in a custom .NET assembly), provided each supports a default constructor. As you will see, the markup within a *.xaml file is transformed into a full-blown object model.

Because XAML is an XML-based grammar, we gain all the benefits and drawbacks XML affords us. On the plus side, XAML files are very self-describing (as any XML document should be). By and large, each element in an XAML file represents a type name (such as Button, Window, or Application) within a given .NET namespace. Attributes within the scope of an opening element map to properties (Height, Width, etc.) and events (Startup, Click, etc.) of the specified type.

Given the fact that XAML is simply a declarative way to define the state of an object, it is possible to define a WPF widget via markup or procedural code. For example, the following XAML

```
<!-- Defining a WPF Button in XAML -->
<Button Name = "btnClickMe" Height = "40" Width = "100" Content = "Click Me" />
```

can be represented programmatically as follows:

```
// Defining the same WPF Button in C# code.
Button btnClickMe = new Button();
btnClickMe.Height = 40;
btnClickMe.Width = 100;
btnClickMe.Content = "Click Me";
```

On the downside, XAML can be verbose and is (like any XML document) case sensitive, thus complex XAML definitions can result in a good deal of markup. Most developers will not need to manually author a complete XAML description of their WPF applications. Rather, the majority of this task will (thankfully) be relegated to development tools such as Visual Studio 2010, Microsoft Expression Blend, or any number of third-party products. Once the tools generate the basic markup, you can go in and fine-tune the XAML definitions by hand if necessary.

Defining MainWindow in XAML

While tools can generate a good deal of XAML on your behalf, it is important for you to understand the basic workings of XAML syntax and how this markup is eventually transformed into a valid .NET assembly. To illustrate XAML in action, in the next example you'll build a WPF application using nothing more than a pair of *.xaml files.

The first Window-derived class (`MainWindow`) was defined in C# as a class type that extends the `System.Windows.Window` base class. This class contains a single `Button` object that calls a registered event handler when clicked. Defining this same `Window` type in the grammar of XAML can be achieved as so (assume this markup has been defined in a file named `MainWindow.xaml`):

```
<!-- Here is your Window definition -->
<Window x:Class="SimpleXamlApp.MainWindow"
    xmlns="http://schemas.microsoft.com/winfx/2006/xaml/presentation"
    xmlns:x="http://schemas.microsoft.com/winfx/2006/xaml"
    Title="A Window built using 100% XAML"
    Height="200" Width="300"
    WindowStartupLocation ="CenterScreen">

    <!--This window has a single button as content -->
    <Button x:Name="btnExitApp" Width="133" Height="24"
        Content = "Close Window" Click ="btnExitApp_Clicked"/>

    <!--The implementation of your button's Click event handler! -->
    <x:Code>
        <![CDATA[
            private void btnExitApp_Clicked(object sender, RoutedEventArgs e)
            {
                this.Close();
            }
        ]]>
    </x:Code>
</Window>
```

First of all, notice that the root element `<Window>` makes use of the `Class` attribute, which is used to specify the name of the C# class that will be generated when this XAML file is processed. Also notice that the `Class` attribute is prefixed with the `x:` tag prefix. If you look within the opening `<Window>` element, you'll see that this XML tag prefix is assigned to the string `"http://schemas.microsoft.com/winfx/2006/xaml"` to build an XML namespace declaration. You will understand the details of these XML namespace definitions a bit later in the chapter, but for now, just be aware that any time you want to make reference to an item defined by the `"http://schemas.microsoft.com/winfx/2006/xaml"` XAML namespace, you must prefix the `x:` token.

Within the scope of the `<Window>` start tag, you have specified values for the `Title`, `Height`, `Width`, and `WindowsStartupLocation` attributes, which are a direct mapping to properties of the same name supported by the `System.Windows.Window` class in the `PresentationFramework.dll` assembly.

Next up, notice that within the scope of the window's definition, you have authored markup to describe the look and feel of a `Button` object that will be used to implicitly set the `Content` property of the window. Beyond setting up the variable name (using the `x:Name` XAML token) and its overall dimensions, you have also handled the `Click` event of the `Button` type by assigning the method to delegate to when the `Click` event occurs.

The final aspect of this XAML file is the `<x:Code>` element, which allows you to author event handlers and other methods of this class directly within an `*.xaml` file. As a safety measure, the code itself is wrapped within a CDATA scope to prevent XML parsers from attempting to directly interpret the data (although this is not strictly required for the current example).

It is important to point out that authoring functionality within a `<Code>` element is not recommended. Although this “single-file approach” isolates all the action to one location, inline code does not provide a clear separation of concerns between UI markup and programming logic. In most WPF applications, implementation code will be found within a related C# file (which you will do eventually).

Defining the Application Object in XAML

Remember that XAML can be used to define in markup any nonabstract .NET class that supports a default constructor. Given this, you could most certainly define your application object in markup as well. Consider the following content within a new file, `MyApp.xaml`:

```
<!-- The Main() method seems to be missing!
     However, the StartupUri attribute is the
     functional equivalent -->
<Application x:Class="SimpleXamlApp.MyApp"
    xmlns="http://schemas.microsoft.com/winfx/2006/xaml/presentation"
    xmlns:x="http://schemas.microsoft.com/winfx/2006/xaml"
    StartupUri="MainWindow.xaml">
</Application>
```

Here, you might agree, the mapping between the `Application`-derived C# class type and its XAML description is not as clear-cut as was the case for our `MainWindow`'s XAML definition. Specifically, there does not seem to be any trace of a `Main()` method. Given that any .NET executable must have a program entry point, you are correct to assume it is generated at compile time, based in part on the `StartupUri` property. The value assigned to `StartupUri` represents which XAML resource to display when the application starts up.

Although the `Main()` method is automatically created at compile time, you are free to use the `<x:Code>` element to capture other C# code blocks. For example, if you wanted to display a message when your program shuts down, you could handle the `Exit` event and implement it as so:

```
<Application x:Class="SimpleXamlApp.MyApp"
    xmlns="http://schemas.microsoft.com/winfx/2006/xaml/presentation"
    xmlns:x="http://schemas.microsoft.com/winfx/2006/xaml"
    StartupUri="MainWindow.xaml" Exit ="AppExit">
<x:Code>
  <![CDATA[
    private void AppExit(object sender, ExitEventArgs e)
    {
      MessageBox.Show("App has exited");
    }
  ]]>
</x:Code>
</Application>
```

Processing the XAML Files using msbuild.exe

At this point, you are ready to transform our markup into a valid .NET assembly. However, you cannot directly use the C# compiler to do so! To date, the C# compiler does not have a native understanding of XAML markup. However, the `msbuild.exe` command-line utility does understand how to transform XAML into C# code and compile this code on the fly when it is informed of the correct `*.targets` files.

`Msbuild.exe` is a tool that will compile .NET code based on the instructions contained within an XML based build script. As it turns out, these build script files contain the exact same sort of data that is found in the `*.csproj` file generated by Visual Studio! Therefore, it is possible to compile a .NET program at the command-line using `msbuild.exe` or using Visual Studio 2010 itself.

Note A full examination of the `msbuild.exe` utility is beyond the scope of this chapter. If you'd like to learn more, perform a search for the topic "MSBuild" in the .NET Framework 4.0 SDK documentation.

Here is a very simple build script, `SimpleXamlApp.csproj`, which contains just enough information to inform `msbuild.exe` how to transform your XAML files into a related C# code base:

```
<Project DefaultTargets="Build"
  xmlns="http://schemas.microsoft.com/developer/msbuild/2003">
  <PropertyGroup>
    <RootNamespace>SimpleXamlApp</RootNamespace>
    <AssemblyName>SimpleXamlApp</AssemblyName>
    <OutputType>winexe</OutputType>
  </PropertyGroup>
  <ItemGroup>
    <Reference Include="System" />
    <Reference Include="WindowsBase" />
    <Reference Include="PresentationCore" />
    <Reference Include="PresentationFramework" />
  </ItemGroup>
  <ItemGroup>
    <ApplicationDefinition Include="MyApp.xaml" />
    <Page Include="MainWindow.xaml" />
  </ItemGroup>
  <Import Project="$(MSBuildBinPath)\Microsoft.CSharp.targets" />
  <Import Project="$(MSBuildBinPath)\Microsoft.WinFX.targets" />
</Project>
```

Note This `*.csproj` file cannot be loaded directly into Visual Studio 2010, as it only contains the minimal instructions necessary to build our application at the command line.

The `<PropertyGroup>` element is used to specify some basic aspects of the build, such as the root namespace, the name of the resulting assembly, and the output type (the equivalent of the `/target:winexe` option of `csc.exe`).

The first `<ItemGroup>` specifies the set of external assemblies to reference with the current build, which, as you can see, are the core WPF assemblies examined earlier in this chapter.

The second `<ItemGroup>` is much more interesting. Notice that the `<ApplicationDefinition>` element's `Include` attribute is assigned to the `*.xaml` file that defines our application object. The `<Page>`'s `Include` attribute can be used to list each of the remaining `*.xaml` files that define the windows (and pages, which are often used when building XAML browser applications) processed by the application object.

However, the "magic" of this build script is the final `<Import>` elements. Here, you are referencing two `*.targets` files, each of which contains numerous other instructions used during the build process. The `Microsoft.WinFX.targets` file contains the necessary build settings to transform the XAML definitions into equivalent C# code files, while `Microsoft.CSharp.Targets` contains data to interact with the C# compiler itself.

In any case, at this point you can use a Visual Studio 2010 Command Prompt to process your XAML data with `msbuild.exe`. To do so, change to the directory containing your `MainWindow.xaml`, `MyApp.xaml` and `SimpleXamlApp.csproj` files, and enter the following command:

```
msbuild SimpleXamlApp.csproj
```

Once the build process has completed, you will find that your working directory now contains a `\bin` and `\obj` subdirectory (just like a Visual Studio project). If you were to open the `\bin\Debug` folder, sure enough, you will find a new .NET assembly named `SimpleXamlApp.exe`. If you open this assembly into `ildasm.exe`, you can see that (somehow) your XAML has been transformed into a valid executable application (see Figure 27-9).




Figure 27-9. Transforming XAML markup into a .NET assembly? Interesting . . .

And if you run your program by double clicking on the executable, you will see your main window launch on the screen.

Transforming Markup into a .NET Assembly

To understand exactly *how* your markup was transformed into a .NET assembly, you need to dig a bit deeper into the msbuild.exe process and examine a number of compiler-generated files, including a particular binary resource embedded within the assembly at compile time. The first task is to learn how your *.xaml files are transformed into a corresponding C# code base.

Mapping the Window XAML Data to C# Code

The *.targets files specified in a msbuild script contain numerous instructions to translate XAML elements into C# code. When msbuild.exe processed your *.csproj file, it produced two files with the form *.g.cs (where g denotes *autogenerated*) that were saved into the \obj\Debug directory. Based on the names of your *.xaml file names, the C# files in question are MainWindow.g.cs and MyApp.g.cs.

If you open the MainWindow.g.cs file into a text editor, you will find a class named MainWindow, which extends the Window base class. The name of this class is a direct result of the x:Class attribute in the <Window> start tag. This class also contains a member variable of type System.Windows.Controls.Button, named btnExitApp. In this case, the name of the control is based on the x:Name attribute value within the opening <Button> declaration. This class also contains the handler for the button's Click event, btnExitApp_Clicked(). Here is a partial listing of this compiler generated file:

```
public partial class MainWindow :  
    System.Windows.Window, System.Windows.Markup.IComponentConnector  
{  
    internal System.Windows.Controls.Button btnExitApp;  
  
    private void btnExitApp_Clicked(object sender, RoutedEventArgs e)  
    {  
        this.Close();  
    }  
...  
}
```

This class defines a private member variable of type bool (named _contentLoaded), which was not directly accounted for in the XAML markup. This data member is used to determine (and ensure) the content of the window is assigned only once:

```
public partial class MainWindow :  
    System.Windows.Window, System.Windows.Markup.IComponentConnector  
{  
    // This member variable will be explained soon enough.  
    private bool _contentLoaded;  
...  
}
```

Notice that the compiler generated class also explicitly implements the WPF `IComponentConnector` interface defined in the `System.Windows.Markup` namespace. This interface defines a single method called `Connect()`, which has been implemented to prep each control defined in the markup and rig up the event logic as specified within the original `MainWindow.xaml` file. Before the method completes, the `_contentLoaded` member variable is set to true. Here is the crux of the method:

```
void System.Windows.Markup.IComponentConnector.Connect(int connectionId, object target)
{
    switch (connectionId)
    {
        case 1:
            this.btnExitApp = ((System.Windows.Controls.Button)(target));
            this.btnExitApp.Click += new
                System.Windows.RoutedEventHandler(this.btnExitApp_Clicked);
            return;
    }
    this._contentLoaded = true;
}
```

Last but not least, the `MainWindow` class also defines and implements a method named `InitializeComponent()`. You might expect that this method contains code that sets up the look and feel of each control by setting various properties (Height, Width, Content, etc). However, this is not the case! How then do the controls take on the correct UI? The logic with `InitializeComponent()` resolves the location of an embedded assembly resource that is named identical to the original `*.xaml` file:

```
public void InitializeComponent()
{
    if (_contentLoaded)
    {
        return;
    }
    _contentLoaded = true;
    System.Uri resourceLocater = new
        System.Uri("/SimpleXamlApp;component/mainwindow.xaml",
                  System.UriKind.Relative);
    System.Windows.Application.LoadComponent(this, resourceLocater);
}
```

At this point, the question becomes, *what exactly is this embedded resource?*

The Role of BAML

When `msbuild.exe` processed our `*.csproj` file, it generated a file taking a `*.bam` file extension. The full name of this file is named based on the initial `MainWindow.xaml` file, therefore you should see a file called `MainWindow.bam` in the `\obj\Debug` folder. As you might have guessed from the name, Binary Application Markup Language (BAML) is a compact, binary representation of the original XAML data.

This `*.bam` file is embedded as a resource (via a generated `*.g.resources` file) into the compiled assembly. You can verify this for yourself by opening your assembly using `reflector.exe`, as shown in Figure 27-10.




Figure 27-10. Viewing the embedded *.baml resource using Reflector

This BAML resource contains all of the data needed to establish the look and feel of the UI widgets (again, such as the Height and Width properties). In fact, if you open the *.baml file into Visual Studio 2010, you can see traces of the initial XAML attributes (see Figure 27-11).

MainWindow.xaml x Object Browser

000000160	36	61	64	33	36	34	65	33	35	14	44	00	39	68	74	74	6ad364e35.D.9htt
000000170	70	3A	2F	73	63	68	65	6D	61	73	2E	6D	69	63	72	p://schemas.micr	
000000180	6F	73	6F	66	74	2E	63	6F	6D	2F	77	69	6E	66	78	2F	
000000190	32	30	30	36	2F	78	61	6D	6C	2F	70	72	65	73	65	6E	
0000001a0	74	61	74	69	6F	68	03	00	01	00	02	00	03	00	35	03	
0000001b0	00	00	00	03	00	00	00	00	14	38	01	78	2C	68	74	74	
0000001c0	3A	2F	2F	73	63	68	65	6D	61	73	2E	6D	69	63	72		
0000001d0	73	6F	66	74	2E	63	6F	6D	2F	77	69	6E	66	78	2F		
0000001e0	30	30	36	2F	78	61	6D	6C	03	00	01	00	02	00	03		
0000001f0	35	04	00	00	03	00	00	00	01	0C	00	00	01	FD	00		
000000200	05	54	69	74	6C	65	24	24	00	00	1E	41	20	57	69		
000000210	64	6F	77	20	62	75	69	6C	74	20	25	73	69	6E	67		
000000220	31	30	30	25	20	58	41	4D	4C	99	3D	35	05	00	00		
000000230	03	00	00	00	24	09	D1	FF	03	32	30	30	A4	FE	35		
000000240	00	00	00	03	00	00	00	24	09	C7	FF	03	33	30	A4		
000000250	FE	36	10	00	00	00	1F	1C	01	00	01	FD	00	15	57		
000000260	6E	64	6F	77	53	74	61	72	74	75	70	4C	6F	63	61		
000000270	69	6F	6E	24	12	01	00	0C	43	65	6E	74	65	72	53		

Figure 27-11. BAML is a compact, binary version of the initial XAML markup

The important take-away here is to understand that a WPF application contains within itself a binary representation (the BAML) of the markup. At runtime, this BAML will be plucked out of the resource container and used to make sure all windows and controls are initialized to the correct look and feel.

Also, remember that the name of these binary resources are *identical* to the name of the standalone *.xaml files you authored. However, this does not imply in any way that you must distribute the loose *.xaml files with your compiled WPF program! Unless you build a WPF application that will dynamically load and parse *.xaml files at runtime, you will never need to ship the original markup.

Mapping the Application XAML Data to C# Code

The final piece of the autogenerated code to examine is the `MyApp.g.cs` file. Here, you see your Application-derived class with a proper `Main()` entry point method. The implementation of this method calls `InitializeComponent()` on the Application-derived type, which, in turn, sets the `StartupUri` property, allowing each of the objects to establish its correct property settings based on the binary XAML definition.

```
namespace SimpleXamlApp
{
    public partial class MyApp : System.Windows.Application
    {
        void AppExit(object sender, ExitEventArgs e)
        {
            MessageBox.Show("App has exited");
        }

        [System.Diagnostics.DebuggerNonUserCodeAttribute()]
        public void InitializeComponent()
        {
            this.Exit += new System.Windows.ExitEventHandler(this.AppExit);
            this.StartupUri = new System.Uri("MainWindow.xaml", System.UriKind.Relative);
        }

        [System.STAThreadAttribute()]
        [System.Diagnostics.DebuggerNonUserCodeAttribute()]
        public static void Main()
        {
            SimpleXamlApp.MyApp app = new SimpleXamlApp.MyApp();
            app.InitializeComponent();
            app.Run();
        }
    }
}
```

XAML-to-Assembly Process Summary

So far, you have created a full-blown .NET assembly using nothing but two XAML files and a related build script. As you have seen, `msbuild.exe` leverages auxiliary settings defined within the `*.targets` file to process the XAML files (and generate the `*.baml`) for the build process. While these gory details happen behind the scenes, Figure 27-12 illustrates the overall picture regarding the compile-time processing of `*.xaml` files.




Figure 27-12. The XAML-to-assembly compile-time process

Hopefully you now have a much better idea how XAML data is used to build a .NET application. At this point, you are ready to take a look at the syntax and semantics of XAML itself.

■ **Source Code** The WpfAppAllXaml project can be found under the Chapter 27 subdirectory.

Understanding The Syntax of WPF XAML

Production level WPF applications will typically make use of dedicated tools to generate the necessary XAML. As helpful as these tools are, it is a very good idea to have an understanding of the overall structure of XAML markup.

Introducing Kaxaml

When you are first learning the grammar of XAML, it can be very helpful to use a free tool named *kaxaml*. You can obtain this popular WPF XAML editor/parser from the following web site:

<http://www.kaxaml.com>

Kaxaml is helpful in that it has no clue about C# source code, event handlers or implementation logic and is a much more straightforward way to test XAML snippets than using a full-blown Visual Studio 2010 WPF project template. As well, kaxaml has a number of integrated tools, such as a color chooser, XAML snippet manager, and even a "XAML scrubber" option that will format your XAML based on your settings.

When you first open kaxaml, you will find simple markup for a <Page> control:

```
<Page
  xmlns="http://schemas.microsoft.com/winfx/2006/xaml/presentation"
  xmlns:x="http://schemas.microsoft.com/winfx/2006/xaml">
  <Grid>
    <!-- Add your XAML here! -->
  </Grid>
</Page>
```

Like a Window, a Page contains various layout managers and controls. However, unlike a Window, Page objects cannot run as standalone entities. Rather, they must be placed inside of a suitable host such as a NavigationWindow, Frame or a web browser (and in that case, you have just made an XBAP!). The good news is that you can type identical markup within a <Page> or <Window> scope.

Note If you change the <Page> and </Page> elements in the kaxaml markup window to <Window> and </Window>, you can press the F5 key to load a new window onto the screen.

As an initial test, enter the following markup into the XAML pane at the bottom of the tool:

```
<Page
  xmlns="http://schemas.microsoft.com/winfx/2006/xaml/presentation"
  xmlns:x="http://schemas.microsoft.com/winfx/2006/xaml">
  <Grid>
    <!-- A button with custom content -->
    <Button Height="100" Width="100">
      <Ellipse Fill="Green" Height="50" Width="50"/>
    </Button>
  </Grid>
</Page>
```

You should now see your page render at the upper part of the kaxaml editor (Figure 27-13).




Figure 27-13. Kaxaml is a very helpful (and free) tool used to learn the grammar of XAML

As you work with kaxaml, remember that this tool does not allow you to author any markup that entails code compilation (however, using `x:Name` is allowed). This includes defining a `x:Class` attribute (for specifying a code file), entering event handler names in markup, or using any XAML keywords that also entail code compilation (such as `FieldModifier` or `ClassModifier`). Any attempt to do so will result in a markup error.

XAML XML Namespaces and XAML "Keywords"

The root element of a WPF XAML document (such as a `<Window>`, `<Page>`, `<UserControl>` or `<Application>` definition) will almost always make reference to two predefined XML namespaces:

```

<Page
    xmlns="http://schemas.microsoft.com/winfx/2006/xaml/presentation"
    xmlns:x="http://schemas.microsoft.com/winfx/2006/xaml">
    <Grid>
    </Grid>
</Page>

```

The first XML namespace, `http://schemas.microsoft.com/winfx/2006/xaml/presentation`, maps a slew of WPF .NET namespaces for use by the current `*.xaml` file (`System.Windows`,

`System.Windows.Controls`, `System.Windows.Data`, `System.Windows.Ink`, `System.Windows.Media`, `System.Windows.Navigation`, etc.).

This one-to-many mapping is actually hard-coded within the WPF assemblies (`WindowsBase.dll`, `PresentationCore.dll`, and `PresentationFramework.dll`) using the assembly-level [`XmlnsDefinition`] attribute. Here is one such listing, which essentially imports `System.Windows`:

```
[assembly: XmlnsDefinition("http://schemas.microsoft.com/winfx/2006/xaml/presentation",
    "System.Windows")]
```

If you load these WPF assemblies into `reflector.exe`, you can view these mappings firsthand. For example, if you select the `PresentationCore.dll` assembly (see Figure 27-14), and press the Space key, you will see numerous instances of the [`XmlnsDefinition`] attribute.




Figure 27-14. The `http://schemas.microsoft.com/winfx/2006/xaml/presentation` namespace maps to the core WPF namespaces

The second XML namespace, `http://schemas.microsoft.com/winfx/2006/xaml`, is used to include XAML-specific "keywords" (for lack of a better term) as well as the inclusion of the `System.Windows.Markup` namespace:

```
[assembly: XmlnsDefinition("http://schemas.microsoft.com/winfx/2006/xaml",
    "System.Windows.Markup")]
```

One rule of any well-formed XML document (remember, XAML is an XML-based grammar) is that the opening root element designates one XML namespace as the *primary namespace*, which typically is the namespace that contains the most commonly used items. If a root element requires the inclusion of additional secondary namespaces (as seen here), they must be defined using a unique tag prefix (to resolve any possible name clashes). As a convention, the prefix is simply `x`; however, this can be any unique token you require, such as `XamlSpecificStuff`:

```
<Page
  xmlns="http://schemas.microsoft.com/winfx/2006/xaml/presentation"
```

```

xmlns:XamlSpecificStuff="http://schemas.microsoft.com/winfx/2006/xaml">
<Grid>
  <!-- A button with custom content -->
  <Button XamlSpecificStuff:Name="button1" Height="100" Width="100">
    <Ellipse Fill="Green" Height="50" Width="50"/>
  </Button>
</Grid>
</Page>

```

The obvious downside of defining wordy XML namespace prefixes is you would be required to type `XamlSpecificStuff` each time your XAML file needs to refer to one of the items defined within this XAML-centric XML namespace. Given that `XamlSpecificStuff` requires many additional keystrokes, just stick with `x`.

In any case, beyond the `x:Name`, `x:Class` and `x:Code` keywords, the <http://schemas.microsoft.com/winfx/2006/xaml> XML namespace also provides access to additional XAML keywords, the most common of which are shown in Table 27-9.

Table 27-9. XAML Keywords

XAML Keyword	Meaning in Life
<code>x:Array</code>	Represents a .NET array type in XAML.
<code>x:ClassModifier</code>	Allows you to define the visibility of the C# class (internal or public) denoted by the <code>Class</code> keyword.
<code>x:FieldModifier</code>	Allows you to define the visibility of a type member (internal, public, private, or protected) for any named subelement of the root (e.g., a <code><Button></code> within a <code><Window></code> element). A <i>named element</i> is defined using the <code>Name</code> XAML keyword.
<code>x:Key</code>	Allows you to establish a key value for an XAML item that will be placed into a dictionary element.
<code>x:Name</code>	Allows you to specify the generated C# name of a given XAML element.
<code>x:Null</code>	Represents a <code>null</code> reference.
<code>x:Static</code>	Allows you to make reference to a static member of a type.
<code>x>Type</code>	The XAML equivalent of the C# <code>typeof</code> operator (it will yield a <code>System.Type</code> based on the supplied name).
<code>x:TypeArguments</code>	Allows you to establish an element as a generic type with a specific type parameter (e.g., <code>List<int></code> vs. <code>List<bool></code>).

In addition to these two necessary XML namespace declarations, it is possible, and sometimes necessary, to define additional tag prefixes in the opening element of a XAML document. You will

typically do so whenever you need to describe in XAML a .NET class defined in an external assembly. For example, say you have built a few custom WPF controls and packaged them in a library named `MyControls.dll`.

Now, if you wish to create a new Window that uses these controls, you can establish a custom XML namespace that maps to your library using the `clr-namespace` and `assembly` tokens. Here is some example markup that creates a tag prefix named `myCtrls`, which can be used to access members in your library:

```
<Window x:Class="WpfApplication1.MainWindow"
    xmlns="http://schemas.microsoft.com/winfx/2006/xaml/presentation"
    xmlns:x="http://schemas.microsoft.com/winfx/2006/xaml"
    xmlns:myCtrls="clr-namespace:MyControls;assembly=MyControls"
    Title="MainWindow" Height="350" Width="525">
    <Grid>
        <myCtrls:MyCustomControl />
    </Grid>
</Window>
```

The `clr-namespace` token is assigned to the name of the .NET namespace in the assembly, while the `assembly` token is set to the friendly name of the external *.dll assembly. You can use this syntax for any external .NET library you wish to manipulate in markup.

Controlling Class and Member Variable Declarations

You will see many of these keywords in action where required in the chapters to come; however, by way of a simple example, consider the following XAML `<Window>` definition that makes use of the `ClassModifier` and `FieldModifier` keywords as well as `x:Name` and `x:Class` (remember that `kaxaml.exe` will not allow you to make use of any XAML keyword that entails code compilation, such as `x:Code`, `x:FieldModifier`, or `x:ClassModifier`):

```
<!-- This class will now be declared internal in the *.g.cs file -->
<Window x:Class="MyWPFApp.MainWindow" x:ClassModifier ="internal"
    xmlns="http://schemas.microsoft.com/winfx/2006/xaml/presentation"
    xmlns:x="http://schemas.microsoft.com/winfx/2006/xaml">

    <!-- This button will be public in the *.g.cs file -->
    <Button x:Name ="myButton" x:FieldModifier ="public" Content = "OK"/>
</Window>
```

By default, all C#/XAML type definitions are public, while members default to internal. However, based on your XAML definition, the resulting autogenerated file contains an internal class type with a public `Button` `tButton` type:

```
internal partial class MainWindow : System.Windows.Window,
    System.Windows.Markup.IComponentConnector
{
    public System.Windows.Controls.Button myButton;
    ...
}
```

XAML Elements, XAML Attributes and Type Converters

Once you have established your root element and any required XML namespaces, your next task is to populate the root with a *child element*. In a real-world WPF application, the child will be a layout manager (such as a *Grid* or *StackPanel*) which contains, in turn, any number of additional UI elements that describe the user interface. The next chapter examines these layout managers in detail, so for now just assume that your *<Window>* type will contain a single *Button* element.

As you have already seen over the course of this chapter, XAML *elements* map to a class or structure type within a given .NET namespace, while the *attributes* within the opening element tag map to properties or events of the type.

To illustrate, enter the following *<Button>* definition into kaxaml:

```
<Page
  xmlns="http://schemas.microsoft.com/winfx/2006/xaml/presentation"
  xmlns:x="http://schemas.microsoft.com/winfx/2006/xaml">
  <Grid>
    <!-- Configure the look and feel of a Button -->
    <Button Height="50" Width="100" Content="OK!" 
            FontSize="20" Background="Green" Foreground="Yellow"/>
  </Grid>
</Page>
```

Notice that the values assigned to each property have been captured as a simple text value. This may seem like a complete mismatch of data types because if you were to make this *Button* in C# code, you would *not* assign string objects to these properties but would make use of specific data types. For example, here is the same button authored in code:

```
public void MakeAButton()
{
    Button myBtn = new Button();
    myBtn.Height = 50;
    myBtn.Width = 100;
    myBtn.FontSize = 20;
    myBtn.Content = "OK!";
    myBtn.Background = new SolidColorBrush(Colors.Green);
    myBtn.Foreground = new SolidColorBrush(Colors.Yellow);
}
```

As it turns out, WPF ships with a number of *type converter* classes, which will be used to transform simple text values into the correct underlying data type. This process happens transparently (and automatically).

While this is all well and good, there will be many times when you need to assign a much more complex value to a XAML attribute, which cannot be captured as a simple string. For example, let's say you want to build a custom brush to set the *Background* property of the *Button*. If you are building the brush in code, it is quite straightforward:

```
public void MakeAButton()
{
    ...
    // A fancy brush for the background.
    LinearGradientBrush fancyBruch =
```

```

        new LinearGradientBrush(Colors.DarkGreen, Colors.LightGreen, 45);
myBtn.Background = fancyBruch;
myBtn.Foreground = new SolidColorBrush(Colors.Yellow);
}

```

How, however, can you represent your complex brush as a string? Well, you can't! Thankfully XAML provides a special syntax that can be used whenever you need to assign a property value to a complex object, termed property-element syntax.

Understanding XAML Property-Element Syntax

Property-element syntax allows you to assign complex objects to a property. Here is an XAML description for a Button that makes use of a `LinearGradientBrush` to set its `Background` property:

```

<Button Height="50" Width="100" Content="OK!"  

    FontSize="20" Foreground="Yellow">  

    <Button.Background>  

        <LinearGradientBrush>  

            <GradientStop Color="DarkGreen" Offset="0"/>  

            <GradientStop Color="LightGreen" Offset="1"/>  

        </LinearGradientBrush>  

    </Button.Background>  

</Button>

```

Notice that within the scope of the `<Button>` and `</Button>` tags, you have defined a sub-scope named `<Button.Background>`. Within this scope, you have defined a custom `<LinearGradientBrush>`. (Don't worry about the exact code for the brush; you'll learn about WPF graphics in Chapter 30.)

Generally speaking, any property can be set using property-element syntax, that always breaks down to the following pattern:

```

<DefiningClass>  

    <DefiningClass.PropertyOnDefiningClass>  

        <!-- Value for Property here! -->  

    </DefiningClass.PropertyOnDefiningClass>  

</DefiningClass>

```

While any property *could* be set using this syntax, if you can capture a value as a simple string, you will save yourself typing time. For example, here would be a much more verbose way to set the `Width` of your `Button`:

```

<Button Height="50" Content="OK!"  

    FontSize="20" Foreground="Yellow">  

    ...  

    <Button.Width>  

        100  

    </Button.Width>  

</Button>

```

Understanding XAML Attached Properties

In addition to property-element syntax, XAML defines a special syntax used to set a value to an *attached property*. Essentially, an attached property allows a child element to set the value for a property that is actually defined in a parent element. The general template to follow looks like this:

```
<ParentElement>
  <ChildElement ParentElement.PropertyOnParent = "Value">
</ParentElement>
```

The most common use of attached property syntax is to position UI elements within one of the WPF layout managers classes (Grid, DockPanel, etc.). The next chapter dives into these panels in some detail; for now, enter the following in kaxaml:

```
<Page
  xmlns="http://schemas.microsoft.com/winfx/2006/xaml/presentation"
  xmlns:x="http://schemas.microsoft.com/winfx/2006/xaml">
  <Canvas Height="200" Width="200" Background="LightBlue">
    <Ellipse Canvas.Top="40" Canvas.Left="40" Height="20" Width="20" Fill="DarkBlue"/>
  </Canvas>
</Page>
```

Here, you have defined a Canvas layout manager that contains an Ellipse. Notice that the Ellipse is able to inform its parent (the Canvas) where to position its top/left position using attached property syntax.

There are a few items to be aware of regarding attached properties. First and foremost, this is not an all-purpose syntax that can be applied to *any* property of *any* parent. For example, the following XAML cannot be parsed without error:

```
<!-- Error! Set Background property on Canvas via attached property? -->
<Canvas Height="200" Width="200">
  <Ellipse Canvas.Background="LightBlue"
    Canvas.Top="40" Canvas.Left="90"
    Height="20" Width="20" Fill="DarkBlue"/>
</Canvas>
```

In reality, attached properties are a specialized form of a WPF-specific concept termed a *dependency property*. Unless a property was implemented in a very specific manner, you cannot set its value using attached property syntax. You will explore dependency properties in a detail in Chapter 31.

Note Kaxaml, Visual Studio 2010, and Expression Blend all have IntelliSense, which will show you valid attached properties that can be set by a given element.

Understanding XAML Markup Extensions

As explained, property values are most often represented using a simple string or via property-element syntax. There is, however, another way to specify the value of a XAML attribute, using *markup extensions*. Markup extensions allow a XAML parser to obtain the value for a property from a dedicated, external class. This can be very beneficial, given that some property values require a number of code statements to execute to figure out the value.

Markup extensions provide a way to cleanly extend the grammar of XAML with new functionality. A markup extension is represented internally as a class that derives from `MarkupExtension`. Note that the chances of your ever needing to build a custom markup extension will be slim to none. However, a subset of XAML keywords (such as `x:Array`, `x:Null`, `x:Static`, and `x:Type`) are markup extensions in disguise!

A markup extension is sandwiched between curly brackets, like so:

```
<Element PropertyToSet = "{MarkUpExtension}" />
```

To see a markup extensions in action, author the following into kaxaml:

```
<Page
  xmlns="http://schemas.microsoft.com/winfx/2006/xaml/presentation"
  xmlns:x="http://schemas.microsoft.com/winfx/2006/xaml"
  xmlns:CorLib="clr-namespace:System;assembly=mscorlib">

  <StackPanel>
    <!-- The Static markup extension lets us obtain a value
        from a static member of a class -->
    <Label Content ="{x:Static CorLib:Environment.OSVersion}" />
    <Label Content ="{x:Static CorLib:Environment.ProcessorCount}" />

    <!-- The Type markup extension is a XAML verion of
        the C# typeof operator -->
    <Label Content ="{x:Type Button}" />
    <Label Content ="{x:Type CorLib:Boolean}" />

    <!-- Fill a ListBox with an array of strings! -->
    <ListBox Width="200" Height="50">
      <ListBox.ItemsSource>
        <x:Array Type="CorLib:String">
          <CorLib:String>Sun Kil Moon</CorLib:String>
          <CorLib:String>Red House Painters</CorLib:String>
          <CorLib:String>Besnard Lakes</CorLib:String>
        </x:Array>
      </ListBox.ItemsSource>
    </ListBox>
  </StackPanel>
</Page>
```

First of all, notice that the `<Page>` definition has a new XML namespace declaration, which allows you to gain access to the `System` namespace of `mscorlib.dll`. With this XML namespace established, you first make use of the `x:Static` markup extension and grab values from `OSVersion` and `ProcessorCount` of the `System.Environment` class.

The `x:Type` markup extension allows you to gain access to the metadata description of the specified item. Here, you are simply assigning the fully qualified names of the WPF Button and `System.Boolean` types.

The most interesting part of this markup is the `ListBox`. Here, you are setting the `ItemsSource` property to an array of strings declared entirely in markup! Notice how the `x:Array` markup extension allows you to specify a set of sub-items within its scope:

```
<x:Array Type="CorLib:String">
  <CorLib:String>Sun Kil Moon</CorLib:String>
  <CorLib:String>Red House Painters</CorLib:String>
  <CorLib:String>Besnard Lakes</CorLib:String>
</x:Array>
```

Note The previous XAML example is only used to illustrate a markup extension in action. As you will see in Chapter 28, there are much easier ways to populate `ListBox` controls!

Figure 27-15 shows the mark up of this `<Page>` in kaxaml.




Figure 27-15. Markup extensions allow you to set values via the functionality of a dedicated class

So! At this point, you have seen numerous examples that showcase each of the core aspects of XAML syntax. As you might agree, XAML is very interesting in that it allows you to describe a tree of .NET objects in a declarative manner. While this is extremely helpful when configuring graphical user

interfaces, do remember that XAML can describe *any* type from *any* assembly provided it is a nonabstract type containing a default constructor.

Building a WPF Application using Code-Behind Files

The first two examples of this chapter illustrated the extreme ends of building a WPF application, using all code or using all XAML. The recommended way to build any WPF application, however, is to use the *code file* approach. Under this model, the XAML files of your project contain nothing but the markup that describes the general state of your classes, while the code file contains the implementation details.

Adding a Code File for the MainWindow Class

To illustrate, you will update the WpfAppAllXaml example to use code files. If you are following along, copy this entire folder and give it the name WpfAppCodeFiles. Now, create a new C# code file in this folder named `MainWindow.xaml.cs` (by convention, the name of a C# code-behind file takes the form `*.xaml.cs`). Add the following code to this new file:

```
// MainWindow.xaml.cs
using System;
using System.Windows;
using System.Windows.Controls;

namespace Simple.XamlApp
{
    public partial class MainWindow : Window
    {
        public MainWindow()
        {
            // Remember! This method is defined
            // within the generated MainWindow.g.cs file.
            InitializeComponent();
        }

        private void btnExitApp_Clicked(object sender, RoutedEventArgs e)
        {
            this.Close();
        }
    }
}
```

Here, you have defined a partial class to contain the event handling logic that will be merged with the partial class definition of the same type in the `*.g.cs` file. Given that `InitializeComponent()` is defined within the `MainWindow.g.cs` file, your window's constructor makes a call in order to load and process the embedded BAML resource.

The `MainWindow.xaml` file will also need to be updated; this simply involves gutting all traces of the previous C# code:

```
<Window x:Class="Simple.XamlApp.MainWindow"
       xmlns="http://schemas.microsoft.com/winfx/2006/xaml/presentation"
```

```

xmlns:x="http://schemas.microsoft.com/winfx/2006/xaml"
Title="A Window built using Code Files!"
Height="200" Width="300"
WindowStartupLocation ="CenterScreen">

<!--The event handler is now in your code file -->
<Button x:Name="btnExitApp" Width="133" Height="24"
        Content = "Close Window" Click ="btnExitApp_Clicked"/>
</Window>

```

Adding a Code File for the MyApp Class

If desired, you could also build a code-behind file for your Application-derived type. Because most of the action takes place in the `MyApp.g.cs` file, the code within `MyApp.xaml.cs` is little more than the following:

```

// MyApp.xaml.cs
using System;
using System.Windows;
using System.Windows.Controls;

namespace SimpleXamlApp
{
    public partial class MyApp : Application
    {
        private void AppExit(object sender, ExitEventArgs e)
        {
            MessageBox.Show("App has exited");
        }
    }
}

```

The `MyApp.xaml` file now looks like so:

```

<Application x:Class="SimpleXamlApp.MyApp"
    xmlns="http://schemas.microsoft.com/winfx/2006/xaml/presentation"
    xmlns:x="http://schemas.microsoft.com/winfx/2006/xaml"
    StartupUri="MainWindow.xaml"
    Exit ="AppExit">
</Application>

```

Processing the Code Files with msbuild.exe

Before you recompile your files using `msbuild.exe`, you need to update our `*.csproj` file to account for the new C# files to include in the compilation process, via the `<Compile>` elements (shown in bold):

```

<Project DefaultTargets="Build" xmlns=
    "http://schemas.microsoft.com/developer/msbuild/2003">

```

```

<PropertyGroup>
  <RootNamespace>SimpleXamlApp</RootNamespace>
  <AssemblyName>SimpleXamlApp</AssemblyName>
  <OutputType>winexe</OutputType>
</PropertyGroup>
<ItemGroup>
  <Reference Include="System" />
  <Reference Include="WindowsBase" />
  <Reference Include="PresentationCore" />
  <Reference Include="PresentationFramework" />
</ItemGroup>
<ItemGroup>
  <ApplicationDefinition Include="MyApp.xaml" />
  <Compile Include = "MainWindow.xaml.cs" />
  <Compile Include = "MyApp.xaml.cs" />
  <Page Include="MainWindow.xaml" />
</ItemGroup>
<Import Project="$(MSBuildBinPath)\Microsoft.CSharp.targets" />
<Import Project="$(MSBuildBinPath)\Microsoft.WinFX.targets" />
</Project>

```

Once you pass our build script into `msbuild.exe`, you find once again the same executable assembly as the `WpfAppAllXaml` application. However, as far as development is concerned, you now have a clean partition of presentation (XAML) from programming logic (C#).

Given that this is the preferred method for WPF development, you'll be happy to know that WPF applications created using Visual Studio 2010 always make use of the code-behind model just presented.

■ Source Code The `WpfAppCodeFiles` project can be found under the Chapter 27 subdirectory.

Building WPF Applications Using Visual Studio 2010

Over the course of this chapter you created examples using no-frills text editors, the command-line compiler, and `kaxaml.exe`. The reason for doing so, of course, was to focus on the core syntax of WPF applications without getting distracted by the bells and whistles of a graphical designer. Now that you have seen how to build WPF applications in the raw, let's examine how Visual Studio 2010 can simplify the construction of WPF applications.

■ Note While Visual Studio 2010 does have some support for authoring complex XAML using the integrated designers, Expression Blend is a far better alternative to build the UI of your WPF applications. You will begin to examine Expression Blend in Chapter 28.

The WPF Project Templates

The New Project dialog box of Visual Studio 2010 defines a set of WPF project workspaces, all of which are contained under the Window node of the Visual C# root. Here, you can choose from a WPF Application, WPF User Control Library, WPF Custom Control Library, and WPF Browser Application (i.e., XBAP). To begin, create a new WPF Application named MyXamlPad (Figure 27-16).




Figure 27-16. The WPF project templates of Visual Studio 2010

Beyond setting references to each of the WPF assemblies (`PresentationCore.dll`, `PresentationFramework.dll`, and `WindowsBase.dll`), you will also be provided with initial `Window` and `Application` derived classes, making use of code files and a related XAML file. Consider Figure 27-17, which shows the Solution Explorer for this new WPF project.




Figure 27-17. The initial files of a WPF Application project

Exploring the WPF Designer Tools

Visual Studio 2010 provides a Toolbox (which you can open via the View menu) that contains numerous WPF controls (Figure 27-18).




Figure 27-18. The Toolbox contains the WPF controls that can be placed on the designer surface

Using a standard mouse drag and drop, you can place any of these controls onto the Window's designer surface. As you do, the underlying XAML will be authored on your behalf. However, you can

also manually type in your markup using the integrated XAML editor. As you can see in Figure 29-19, you do get IntelliSense support, which can help simplify the authoring of the markup.




Figure 27-19. The WPF Window designer

Note You can reposition the display panes of the visual designer using the buttons embedded within the splitter window, such as the Swap Panes button (indicated by the up/down arrows), the Horizontal and Vertical split buttons, and so on. Take a moment to find a configuration you are comfortable with.

Once you have placed controls onto your designer (which you will do in a moment), you can then make use of the Properties window to set property values for the selected control, as well as rig up event handlers for the selected control. By way of a simple test, drag a button control anywhere on your visual designer. Once you do, you will see that Visual Studio authored XAML similar to the following:

```
<Button Content="Button" Height="23" HorizontalAlignment="Left"
    Margin="12,12,0,0" Name="button1" VerticalAlignment="Top" Width="75" />
```

Now, use the Properties window to change the Background color of the Button using the integrated brush editor (Figure 27-20).

Note The Brush Editor of Expression Blend is very similar to the Visual Studio brush editor and will be examined in detail in Chapter 29.




Figure 27-20. The Properties window can be used to configure the UI of a WPF control

Once you have finished tinkering with the brush editor, check out the generated markup. It might look something like this:

```
<Button Content="Button" Height="23" HorizontalAlignment="Left" Margin="12,12,0,0"
    Name="button1" VerticalAlignment="Top" Width="75">
    <Button.Background>
        <LinearGradientBrush EndPoint="1,0.5" StartPoint="0,0.5">
            <GradientStop Color="#FF7488CE" Offset="0" />
            <GradientStop Color="#FFC11E1E" Offset="0.837" />
        </LinearGradientBrush>
    </Button.Background>
</Button>
```

If you wish to handle events for a given control, you can also make use of the Properties window, but this time you need to click on the Events tab. Ensure that the button is selected on your designer, click on the Events tab, and locate the Click event. Once you do, double click directly on the Click event entry. This will cause Visual Studio 2010 to automatically build an event handler that takes the form:

NameOfControl_NameOfEvent

Since you did not rename your button, the Properties window shows it generated an event handler named `button1_Click` (see Figure 27-21).




Figure 27-20. Handling events using the visual designer

As well, Visual Studio 2010 generated the corresponding C# code in your window's code file. Here, you can add any sort of code that must execute when the button is clicked:

```
public partial class MainWindow : Window
{
    public MainWindow()
    {
        InitializeComponent();
    }

    private void button1_Click(object sender, RoutedEventArgs e)
    {
    }
}
```

You can also handle events directly in the XAML editor. By way of an example, place your mouse within the `<Button>` element and type in the `MouseEnter` event, followed by the equals sign. Once you do, you will see Visual Studio displays any compatible handlers in your code file, as well as the `<New Event Handler>` option. If you double click `<New Event Handler>`, the IDE will generate a fitting handler in your C# code file.

Now that you have seen the basic tools used within Visual Studio 2010 to create WPF applications, let's leverage this IDE to build an example program that illustrates the process of parsing XAML at runtime.

Before you start, completely delete the markup describing the Button you just created and also delete the C# event handler code.

Designing the GUI of our Window

The WPF API supports the ability to load, parse, and save XAML descriptions programmatically. Doing so can be quite useful in a variety of situations. For example, assume you have five different XAML files that describe the look and feel of a `Window` type. As long as the names of each control (and any necessary event handlers) are identical within each file, it would be possible to dynamically apply “skins” to the window (perhaps based on a startup argument passed into the application).

Interacting with XAML at runtime revolves around the `XamlReader` and `XamlWriter` types, both of which are defined within the `System.Windows.Markup` namespace. To illustrate how to programmatically hydrate a `Window` object from an external *.xaml file, you will build an application that mimics the basic functionality of the `kaxaml`.

While your application will certainly not be as feature-rich as `kaxaml.exe`, it will provide the ability to enter XAML markup, view the results, and save the XAML to an external file. To begin, update the initial XAML definition of your `<Window>` as:

Note The next chapter will dive into the details of working with controls and panels, so don't fret over the details of the control declarations.

```
<Window x:Class="MyXamlPad.MainWindow"
    xmlns="http://schemas.microsoft.com/winfx/2006/xaml/presentation"
    xmlns:x="http://schemas.microsoft.com/winfx/2006/xaml"
    Title="My Custom XAML Editor"
    Height="338" Width="1041"
    Loaded="Window_Loaded" Closed="Window_Closed"
    WindowStartupLocation="CenterScreen">

    <!-- You will use a DockPanel, not a Grid -->
    <DockPanel LastChildFill="True" >

        <!-- This button will launch a window with defined XAML -->
        <Button DockPanel.Dock="Top" Name = "btnViewXaml" Width="100" Height="40"
            Content ="View Xaml" Click="btnViewXaml_Click" />

        <!-- This will be the area to type within -->
        <TextBox AcceptsReturn ="True" Name ="txtXamlData"
            FontSize ="14" Background="Black" Foreground="Yellow"
            BorderBrush ="Blue" VerticalScrollBarVisibility="Auto"
            AcceptsTab="True" />

    </DockPanel>
</Window>
```

First of all, notice that you have replaced the initial `<Grid>` with a `<DockPanel>` type that contains a `Button` (named `btnViewXaml`) and a `TextBox` (named `txtXamlData`), and that the `Click` event of the `Button` type has been handled. Also notice that the `Loaded` and `Closed` events of the `Window` itself have been handled within the opening `<Window>` element. If you have used the designer to handle your events, you should find the following code in your `MainWindow.xaml.cs` file:

```

public partial class MainWindow : Window
{
    public MainWindow()
    {
        InitializeComponent();
    }

    private void btnViewXaml_Click(object sender, RoutedEventArgs e)
    {}

    private void Window_Closed(object sender, EventArgs e)
    {}

    private void Window_Loaded(object sender, RoutedEventArgs e)
    {}
}

```

Before continuing, be sure to import the following namespaces into your `MainWindow.xaml.cs` file:

```

using System.IO;
using System.Windows.Markup;

```

Implementing the Loaded Event

The `Loaded` event of your main window is in charge of determining if there is currently a file named `YourXaml.xaml` in the folder containing the application. If this file does exist, you will read in the data and place it into the `TextBox` on the main window. If not, you will fill the `TextBox` with an initial default XAML description of an empty window (this description is the exact same markup as an initial window definition, except that you are using a `<StackPanel>` rather than a `<Grid>`).

Note The string you are building to represent the key XML namespaces is a bit cumbersome to type, given the escape characters required for the embedded quotations, so type carefully.

```

private void Window_Loaded(object sender, RoutedEventArgs e)
{
    // When the main window of the app loads,
    // place some basic XAML text into the text block.
    if (File.Exists(System.Environment.CurrentDirectory + "\\YourXaml.xaml"))
    {
        txtXamlData.Text = File.ReadAllText("YourXaml.xaml");
    }
}

```

```

else
{
    txtXamlData.Text =
        "<Window xmlns=\"http://schemas.microsoft.com/winfx/2006/xaml/presentation\"\n"
        +"xmlns:x=\"http://schemas.microsoft.com/winfx/2006/xaml\"\n"
        +"Height =\"400\" Width =\"500\" WindowStartupLocation=\"CenterScreen\">\n"
        +"<StackPanel>\n"
        +"</StackPanel>\n"
        +"</Window>";
}
}

```

Using this approach, your application will be able to load the XAML entered in a previous session or supply a default block of markup if necessary. At this point, you should be able to run your program and find the display shown in Figure 27-22 within the TextBox type.




Figure 27-22. The first run of MyXamlPad.exe

Implementing the Button's Click Event

When you click the Button, you will first save the current data in the TextBox into the `YourXaml.xaml` file. At this point, you will read in the persisted data via `File.Open()` to obtain a Stream-derived type. This is necessary, as the `XamlReader.Load()` method requires a Stream-derived type (rather than a simple `System.String`) to represent the XAML to be parsed.

Once you have loaded the XAML description of the `<Window>` you wish to construct, create an instance of `System.Windows.Window` based on the in-memory XAML and display the Window as a modal dialog:

```

private void btnViewXaml_Click(object sender, RoutedEventArgs e)
{
    // Write out the data in the text block to a local *.xaml file.
    File.WriteAllText("YourXaml.xaml", txtXamlData.Text);

    // This is the window that will be dynamically XAML-ed.
    Window myWindow = null;
}

```

```
// Open local *.xaml file.  
try  
{  
    using (Stream sr = File.Open("YourXaml.xaml", FileMode.Open))  
    {  
        // Connect the XAML to the Window object.  
        myWindow = (Window)XamlReader.Load(sr);  
  
        // Show window as a dialog and clean up.  
        myWindow.ShowDialog();  
        myWindow.Close();  
        myWindow = null;  
  
    }  
}  
catch (Exception ex)  
{  
    MessageBox.Show(ex.Message);  
}  
}
```

Note that you are wrapping much of our logic within a try/catch block. In this way, if the YourXaml.xaml file contains ill-formed markup, you can see the error of your ways within the resulting message box. For example, run your program, and purposely misspell <StackPanel> by adding an extra letter P in the opening element or whatnot. If you click the button, you will see an error similar to Figure 27-23:




Figure 27-23. Catching markup errors

Implementing the Closed Event

Finally, the `Closed` event of your `Window` type will ensure that the latest and greatest data in the `TextBox` is persisted to the `YourXaml.xaml` file:

```
private void Window_Closed(object sender, EventArgs e)
{
    // Write out the data in the text block to a local *.xaml file.
    File.WriteAllText("YourXaml.xaml", txtXamlData.Text);
}
```

Testing the Application

Now fire up your program and enter some XAML into your text area. Do be aware that (like `kaxaml.exe`) this program does not allow you to specify any code generation–centric XAML attributes (such as `Class` or any event handlers). As a test, enter the following XAML within your `<Window>` scope:

```
<StackPanel>
<Rectangle Fill = "Green" Height = "40" Width = "200" />
<Button Content = "OK!" Height = "40" Width = "100" />
<Label Content = "{x:Type Label}" />
</StackPanel>
```

Once you click the button, you will see a window appear that renders your XAML definitions (or possibly you'll see a parsing error in the message box—watch your typing!). Figure 27-24 shows possible output.




Figure 27-24. *MyXamlPad.exe* in action

Great! I am sure you can think of many possible enhancements to this application, but to do so you need to be aware of how to work with WPF controls and the panels that contain them. You will do so starting in the next chapter.

■ **Source Code** The MyXamlPad project can be found under the Chapter 27 subdirectory.

Summary

Windows Presentation Foundation (WPF) is a user interface toolkit introduced since the release of .NET 3.0. The major goal of WPF is to integrate and unify a number of previously unrelated desktop technologies (2D graphics, 3D graphics, window and control development, etc.) into a single unified programming model. Beyond this point, WPF programs typically make use of Extendable Application Markup Language (XAML), which allows you to declare the look and feel of your WPF elements via markup.

Recall that XAML allows you to describe trees of .NET objects using a declarative syntax. During this chapter's investigation of XAML, you were exposed to several new bits of syntax including property-element syntax and attached properties, as well as the role of type converters and XAML markup extensions.

While XAML is a key aspect for any production level WPF application, your first example of this chapter illustrated how you can build a WPF program using nothing but C# code. Next, you discovered how you could build a WPF program using nothing but XAML (this is not recommended; however, it was a useful learning exercise!). Finally, you learned about the use of "code files" which allow you to partition look-and-feel from functionality.

The final example of this chapter gave you a chance to build a WPF application that allowed you to programmatically interact with XAML definitions using the `XamlReader` and `XamlWriter` classes. Along the way, you took a tour of the WPF designers of Visual Studio 2010.



Programming with WPF Controls

The previous chapter provided a foundation for the WPF programming model, including an examination of the `Window` and `Application` classes, the grammar of XAML, and the use of code files. Chapter 27 also introduced you to the process of building WPF applications using the designers of Visual Studio 2010. In this chapter you will dig into the construction of more sophisticated graphical user interfaces using several new controls and layout managers.

This chapter will also examine some related WPF control topics such as the data binding programming model and the use of control commands. You will also learn how to use the Ink and Documents APIs, which allow you to capture stylus (or mouse) input and build rich text documents using the XML Paper Specification, respectively.

Finally, this chapter will show you how to use Expression Blend to build the UI of a WPF application. Using Blend in a WPF project is technically optional, but this IDE can greatly simplify your development because it can generate the necessary XAML using a number of integrated designers, editors, and wizards.

A Survey of the Core WPF Controls

Unless you are new to the concept of building graphical user interfaces (which is fine), the general role of the WPF controls should not raise too many issues. Regardless of which GUI toolkit you might have used in the past (e.g., MFC, Java AWT/Swing, Windows Forms, VB 6.0, Mac OS X [Cocoa], or GTK+/GTK#), the core WPF controls listed in Table 28-1 are likely to look familiar.


Table 28-1. The Core WPF Controls

WPF Control Category	Example Members	Meaning in Life
Core user input controls	Button, RadioButton, ComboBox, CheckBox, Calendar, DatePicker, Expander, DataGrid, ListBox, ListView, Slider, ToggleButton, TreeView, ContextMenu, ScrollBar, Slider, TabControl, TextBlock, TextBox, RepeatButton, RichTextBox, Label	WPF provides an entire family of controls you can use to build the crux of a user interface.

Table 28-1. The Core WPF Controls (continued)

WPF Control Category	Example Members	Meaning in Life
Window and control adornments	Menu,ToolBar,StatusBar,ToolTip,ProgressBar	You use these UI elements to decorate the frame of a Window object with input devices (such as the Menu) and user informational elements (e.g., StatusBar and ToolTip).
Media controls	Image, MediaElement, SoundPlayerAction	These controls provide support for audio/video playback and image display.
Layout controls	Border, Canvas, DockPanel, Grid, GridView, GridSplitter, GroupBox, Panel, TabControl, StackPanel, Viewbox, WrapPanel	WPF provides numerous controls that allow you to group and organize other controls for the purpose of layout management.

A majority of these standard WPF controls have been packaged up in the `System.Windows.Controls` namespace of the `PresentationFramework.dll` assembly. When you build a WPF application using Visual Studio 2010, you will find most of these common controls contained in the Toolbox, provided you have a WPF designer open as the active window (see Figure 28-1).

**Figure 28-1.** The Visual Studio 2010 Toolbox exposes the intrinsic WPF controls

Much as you can with a Windows Forms application, you can drag these controls onto the WPF window designer and configure them using the Properties window (which you learned about in the previous chapter). While Visual Studio 2010 will generate a good amount of the XAML on your behalf, it is not uncommon to edit the markup yourself manually. Let's review the basics.

Working with WPF Controls Using Visual Studio 2010

You might recall from Chapter 27 that when you place a WPF control onto the Visual Studio 2010 designer, you want to set the `x:Name` property through the Properties window because this allows you to access the object in your related C# code file. You might also recall that you can use the Events tab of the Properties window to generate event handlers for a selected control. Thus, you could use Visual Studio to generate the following markup for a simple Button control:

```
<Button x:Name="btnMyButton" Content="Click Me!" Height="23" Width="140"
    Click="btnMyButton_Click" />
```

Here, you set the `Content` property of the Button to a simple string. However, thanks to the WPF control content model, you could fashion a Button that contains the following complex content:

```
<Button x:Name="btnMyButton" Height="121" Width="156" Click="btnShowDlg_Click">
    <Button.Content>
        <StackPanel Height="95" Width="128" Orientation="Vertical">
            <Ellipse Fill="Red" Width="52" Height="45" Margin="5"/>
            <Label Width="59" FontSize="20" Content="Click!" Height="36" />
        </StackPanel>
    </Button.Content>
</Button>
```

You might also recall that the immediate child element of a `ContentControl`-derived class is the implied content; therefore, you do not need to define a `<Button.Content>` scope explicitly when specifying complex content. You could simply author the following:

```
<Button x:Name="btnMyButton" Height="121" Width="156" Click="btnShowDlg_Click">
    <StackPanel Height="95" Width="128" Orientation="Vertical">
        <Ellipse Fill="Red" Width="52" Height="45" Margin="5"/>
        <Label Width="59" FontSize="20" Content="Click!" Height="36" />
    </StackPanel>
</Button>
```

In either case, you set the button's `Content` property to a `<StackPanel>` of related items. You can author this sort of complex content using the Visual Studio 2010 designer, as well. Once you define the layout manager, you can select it on the design to serve as a drop target for the internal controls. At this point, you can edit each using the Properties window.

You should also be aware that the Document Outline window of Visual Studio 2010 (which you can open using the `View ▶ Other Windows` menu) is useful when designing a WPF control that has complex content. Notice in Figure 28-2 how the logical tree of XAML is displayed for the Window you are building. If you click any of these nodes, you can get a preview of the selected item.



Figure 28-2. The Visual Studio 2010 Document Outline window can help you navigate complex content

In any case, once you define the initial markup, you are free to open the related C# code file to add your implementation logic:

```
private void btnShowDlg_Click(object sender, RoutedEventArgs e)
{
    MessageBox.Show("You clicked the button!");
}
```

The first part of this chapter uses Visual Studio 2010 to build the UIs of the example projects. The chapter will point out additional features as necessary, but make sure you take some time to explore the options of the Properties window and designer functionality. Later in this chapter, you will use Expression Blend to build your UIs. As you will see, Blend has many integrated tools that generate a majority of the required XAML automatically.

The WPF Ink Controls

In addition to the common WPF controls listed in Table 28-1, WPF defines additional controls for working with the digital Ink API. This aspect of WPF development is useful during tablet PC development because it lets you capture input from the stylus. However, this is not to say a standard desktop application cannot leverage the Ink API because the same controls can capture input using the mouse.

The `System.Windows.Ink` namespace of `PresentationCore.dll` contains various Ink API support types (e.g., `Stroke` and `StrokeCollection`); however, a majority of the Ink API controls (e.g., `InkCanvas` and `InkPresenter`) are packaged up with the common WPF controls under the `System.Windows.Controls` namespace in the `PresentationFramework.dll` assembly. You'll work with the Ink API later in this chapter.

The WPF Document Controls

WPF also provides controls for advanced document processing, allowing you to build applications that incorporate Adobe PDF-style functionality. Using the types within the `System.Windows.Documents` namespace (also in the `PresentationFramework.dll` assembly), you can create print-ready documents that support zooming, searching, user annotations (sticky notes), and other rich text services.

Under the covers, however, the document controls do not use Adobe PDF APIs; rather, they use the XML Paper Specification (XPS) API. To the end user, there will really appear to be no difference because PDF documents and XPS documents have an almost identical look-and-feel. In fact, you can find many free utilities that allow you to convert between the two file formats on the fly. You'll work with some aspects of the document controls in an upcoming example.

WPF Common Dialog Boxes

WPF also provides you with a few common dialog boxes such as `OpenFileDialog` and `SaveFileDialog`. These dialog boxes are defined within the `Microsoft.Win32` namespace of the `PresentationFramework.dll` assembly. Working with either of these dialog boxes is a matter of creating an object and invoking the `ShowDialog()` method:

```
using Microsoft.Win32;

namespace WpfControls
{
    public partial class MainWindow : Window
    {
        public MainWindow()
        {
            InitializeComponent();
        }

        private void btnShowDlg_Click(object sender, RoutedEventArgs e)
        {
            // Show a file save dialog.
            SaveFileDialog saveDlg = new SaveFileDialog();
            saveDlg.ShowDialog();
        }
    }
}
```

As you would hope, these classes support various members that allow you to establish file filters and directory paths, and gain access to user-selected files. You will put these file dialogs to use in later examples; you will also learn how to build custom dialog boxes to gather user input.

The Details Are in the Documentation

Despite what you might be thinking, the intent of this chapter is *not* to walk through each and every member of each and every WPF control. Rather, you will receive an overview of the various controls with an emphasis on the underlying programming model and key services common to most WPF controls. You will also learn how to build UIs with Expression Blend and Visual Studio 2010.

To round out your understanding of the particular functionality of a given control, be sure to consult the .NET Framework 4.0 SDK documentation—specifically, the Control Library section of the help system, which you can find under Windows Presentation Foundation ➤ Controls (see Figure 28-3).




Figure 28-3. The full details of each WPF control are just a keypress away (F1)

Here you will find full details of each control, various code samples (in XAML, as well as C#), and information regarding a control's inheritance chain, implemented interfaces, and applied attributes.

Controlling Content Layout Using Panels

A WPF application invariably contains a good number of UI elements (e.g., user input controls, graphical content, menu systems, and status bars) that need to be well organized within various windows. Once you place the UI elements, you need to make sure they behave as intended when the end user resizes the window or possibly a portion of the window (as in the case of a splitter window). To ensure your WPF controls retain their position within the hosting window, you can take advantage of a good number of *panel* types.

When you declare a control directly inside a window that doesn't use panels, the control is positioned dead-center in the container. Consider the following simple window declaration, which

contains a single Button control. Regardless of how you resize the window, the UI widget is always equidistant from all four sides of the client area:

```
<!-- This button is in the center of the window at all times-->
<Window x:Class="MyWPFApp.MainWindow"
    xmlns="http://schemas.microsoft.com/winfx/2006/xaml/presentation"
    xmlns:x="http://schemas.microsoft.com/winfx/2006/xaml"
    Title="Fun with Panels!" Height="285" Width="325">

    <Button x:Name="btnOK" Height = "100"
        Width="80" Content="OK"/>
</Window>
```

You might also recall that if you attempt to place multiple elements directly within the scope of a `<Window>`, you will receive markup and compile-time errors. The reason for these errors is that a window (or any descendant of `ContentControl` for that matter) can assign only a single object to its `Content` property:

```
<!-- Error! Content property is implicitly set more than once!-->
<Window x:Class="MyWPFApp.MainWindow"
    xmlns="http://schemas.microsoft.com/winfx/2006/xaml/presentation"
    xmlns:x="http://schemas.microsoft.com/winfx/2006/xaml"
    Title="Fun with Panels!" Height="285" Width="325">

    <!-- Error! Two direct child elements of the <Window>! -->
    <Label x:Name="lblInstructions" Width="328" Height="27"
        FontSize="15" Content="Enter Information"/>
    <Button x:Name="btnOK" Height = "100" Width="80" Content="OK"/>
</Window>
```

Obviously a window that can only contain a single control is of little use. When a window needs to contain multiple elements, those elements must be arranged within any number of panels. The panel will contain all of the UI elements that represent the window, after which the panel itself is used as the single object assigned to the `Content` property.

The `System.Windows.Controls` namespace provides numerous panels, each of which controls how sub-elements are maintained. You can use panels to establish how the controls behave if the end user resizes the window, if the controls remain exactly where they were placed at design time, if the controls reflow horizontally from left-to-right or vertically from top-to-bottom, and so forth.

You can also intermix panel controls within other panels (e.g., a `DockPanel` that contains a `StackPanel` of other items) to provide a great deal of flexibility and control. Table 28-2 documents the role of some commonly used WPF panel controls.

Table 28-2. Core WPF Panel Controls

Panel Control	Meaning in Life
Canvas	Provides a classic mode of content placement. Items stay exactly where you put them at design time.
DockPanel	Locks content to a specified side of the panel (Top, Bottom, Left, or Right).

Table 28-2. Core WPF Panel Controls (continued)

Panel Control	Meaning in Life
Grid	Arranges content within a series of cells, maintained within a tabular grid.
StackPanel	Stacks content in a vertical or horizontal manner, as dictated by the Orientation property.
WrapPanel	Positions content from left-to-right, breaking the content to the next line at the edge of the containing box. Subsequent ordering happens sequentially from top-to-bottom or from right-to-left, depending on the value of the Orientation property.

In the next few sections, you will learn how to use these commonly used panel types by copying some predefined XAML data into the `MyXamlPad.exe` application you created in Chapter 27 (you could also load this data into `kaxaml.exe`, if you wish). You can find all these loose XAML files contained inside the `PanelMarkup` subfolder of your Chapter 28 code download folder (Figure 28-4).




Figure 28-4. You will be loading the supplied XAML data into your `MyXamlPad.exe` application to test various layouts

Positioning Content Within Canvas Panels

You will probably feel most at home with the `Canvas` panel because it allows for absolute positioning of UI content. If the end user resizes the window to an area that is smaller than the layout maintained by the `Canvas` panel, the internal content will not be visible until the container is stretched to a size equal to or larger than the `Canvas` area.

To add content to a `Canvas`, you begin by defining the required controls within the scope of the opening `<Canvas>` and closing `</Canvas>` tags. Next, specify the upper-left corner for each control; this is

where the rendering should begin using the `Canvas.Top` and `Canvas.Left` properties. You can specify the bottom-right area indirectly in each control by setting its `Height` and `Width` properties, or directly by using the `Canvas.Right` and `Canvas.Bottom` properties.

To see `Canvas` in action, open the provided `SimpleCanvas.xaml` file using a text editor and copy the content into `MyXamlPad.exe` (or `kaxaml.exe`). You should see the following `Canvas` definition:

```
<Window
    xmlns="http://schemas.microsoft.com/winfx/2006/xaml/presentation"
    xmlns:x="http://schemas.microsoft.com/winfx/2006/xaml"
    Title="Fun with Panels!" Height="285" Width="325">
    <Canvas Background="LightSteelBlue">
        <Button x:Name="btnOK" Canvas.Left="212" Canvas.Top="203"
            Width="80" Content="OK"/>
        <Label x:Name="lblInstructions" Canvas.Left="17" Canvas.Top="14"
            Width="328" Height="27" FontSize="15"
            Content="Enter Car Information"/>
        <Label x:Name="lblMake" Canvas.Left="17" Canvas.Top="60"
            Content="Make"/>
        <TextBox x:Name="txtMake" Canvas.Left="94" Canvas.Top="60"
            Width="193" Height="25"/>
        <Label x:Name="lblColor" Canvas.Left="17" Canvas.Top="109"
            Content="Color"/>
        <TextBox x:Name="txtColor" Canvas.Left="94" Canvas.Top="107"
            Width="193" Height="25"/>
        <Label x:Name="lblPetName" Canvas.Left="17" Canvas.Top="155"
            Content="Pet Name"/>
        <TextBox x:Name="txtPetName" Canvas.Left="94" Canvas.Top="153"
            Width="193" Height="25"/>
    </Canvas>
</Window>
```

Clicking your View Xaml button causes the following window display on the screen (Figure 28-5).




Figure 28-5. The `Canvas` layout manager allows for absolute positioning of content

Note that the order you declare content within a `Canvas` is not used to calculate placement; instead, placement is based on the control's size and the `Canvas.Top`, `Canvas.Bottom`, `Canvas.Left`, and `Canvas.Right` properties.

Note If sub-elements within a `Canvas` do not define a specific location using attached property syntax (e.g. `Canvas.Left` and `Canvas.Top`), they automatically attach to the extreme upper-left corner of `Canvas`.

Using the `Canvas` type might seem like the preferred way to arrange content (because it feels so familiar), but this approach does suffer from some limitations. First, items within a `Canvas` do not dynamically resize themselves when applying styles or templates (e.g., their font sizes are unaffected). Second, the `Canvas` will not attempt to keep elements visible when the end user resizes the window to a smaller surface.

Perhaps the best use of the `Canvas` type is for positioning *graphical content*. For example, if you were building a custom image using XAML, you certainly would want the lines, shapes, and text to remain in the same location, rather than see them dynamically repositioned as the user resizes the window! You'll revisit `Canvas` in the next chapter when you examine WPF's graphical rendering services.

Positioning Content Within `WrapPanel` Panels

A `WrapPanel` allows you to define content that will flow across the panel as the window is resized. When positioning elements in a `WrapPanel`, you do not specify top, bottom, left, and right docking values as you typically do with `Canvas`. However, each sub-element is free to define a `Height` and `Width` value (among other property values) to control its overall size in the container.

Because content within a `WrapPanel` does not dock to a given side of the panel, the order in which you declare the elements is important (content is rendered from the first element to the last). If you were to load the XAML data found within the `SimpleWrapPanel.xaml` file, you would find it contains the following markup (enclosed within a `<Window>` definition):

```
<WrapPanel Background="LightSteelBlue">
    <Label x:Name="lblInstruction" Width="328"
        Height="27" FontSize="15" Content="Enter Car Information"/>
    <Label x:Name="lblMake" Content="Make"/>
    <TextBox x:Name="txtMake" Width="193" Height="25"/>
    <Label x:Name="lblColor" Content="Color"/>
    <TextBox x:Name="txtColor" Width="193" Height="25"/>
    <Label x:Name="lblPetName" Content="Pet Name"/>
    <TextBox x:Name="txtPetName" Width="193" Height="25"/>
    <Button x:Name="btnOK" Width="80" Content="OK"/>
</WrapPanel>
```

When you load this markup, the content looks out of sorts as you resize the width because it flows from left-to-right across the window (see Figure 28-6).




Figure 28-6. Content in a WrapPanel behaves much like a traditional HTML page

By default, content within a WrapPanel flows from left-to-right. However, if you change the value of the Orientation property to Vertical, you can have content wrap in a top-to-bottom manner:

```
<WrapPanel Orientation = "Vertical">
```

You can declare a WrapPanel (as well as some other panel types) by specifying ItemWidth and ItemHeight values, which control the default size of each item. If a sub-element does provide its own Height and/or Width value, it will be positioned relative to the size established by the panel. Consider the following markup:

```
<WrapPanel ItemWidth ="200" ItemHeight ="30">
    <Label x:Name="lblInstruction"
        FontSize="15" Content="Enter Car Information"/>
    <Label x:Name="lblMake" Content="Make"/>
    <TextBox x:Name="txtMake"/>
    <Label x:Name="lblColor" Content="Color"/>
    <TextBox x:Name="txtColor"/>
    <Label x:Name="lblPetName" Content="Pet Name"/>
    <TextBox x:Name="txtPetName"/>
    <Button x:Name="btnOK" Width ="80" Content="OK"/>
</WrapPanel>
```

When you see this code rendered, you find the output shown in Figure 28-7 (notice the size and position of the Button control, which has specified a unique Width value).



Figure 28-7. A WrapPanel can establish the width and height of a given item

As you might agree after looking at Figure 28-7, a WrapPanel is not typically the best choice for arranging content directly in a window because its elements can become scrambled as the user resizes

the window. In most cases, a `WrapPanel` will be a sub-element to another panel type, allowing a small area of the window to wrap its content when resized (e.g., a Toolbar control).

Positioning Content Within StackPanel Panels

Like a `WrapPanel`, a `StackPanel` control arranges content into a single line that can be oriented horizontally or vertically (the default), based on the value assigned to the `Orientation` property. The difference, however, is that the `StackPanel` will *not* attempt to wrap the content as the user resizes the window. Rather, the items in the `StackPanel` will simply stretch (based on their orientation) to accommodate the size of the `StackPanel` itself. For example, the `SimpleStackPanel.xaml` file contains markup that results in the output shown in Figure 28-8:

```
<StackPanel Background="LightSteelBlue">
    <Label x:Name="lblInstruction"
        FontSize="15" Content="Enter Car Information"/>
    <Label x:Name="lblMake" Content="Make"/>
    <TextBox Name="txtMake"/>
    <Label x:Name="lblColor" Content="Color"/>
    <TextBox x:Name="txtColor"/>
    <Label x:Name="lblPetName" Content="Pet Name"/>
    <TextBox x:Name="txtPetName"/>
    <Button x:Name="btnOK" Width ="80" Content="OK"/>
</StackPanel>
```




Figure 28-8. Vertical stacking of content

If you assign the `Orientation` property to `Horizontal` as follows, the rendered output will match that shown in Figure 28-9:

```
<StackPanel Orientation ="Horizontal">
```




Figure 28-9. Horizontal stacking of content

Again, as is the case with the `WrapPanel`, you will seldom want to use a `StackPanel` to arrange content directly within a window. Instead, you'll be better off using `StackPanel` as a subpanel to a master panel.

Positioning Content Within Grid Panels

Of all the panels provided with the WPF APIs, `Grid` is far and away the most flexible. Like an HTML table, the `Grid` can be carved up into a set of cells, each one of which provides content. When defining a `Grid`, you perform three steps:

1. Define and configure each column.
2. Define and configure each row.
3. Assign content to each cell of the grid using attached property syntax.

Note If you do not define any rows or columns, the `<Grid>` defaults to a single cell that fills the entire surface of the window. Furthermore, if you do not assign a cell value for a sub-element within a `<Grid>`, it automatically attaches to column 0, row 0.

You achieve the first two steps (defining the columns and rows) by using the `<Grid.ColumnDefinitions>` and `<Grid.RowDefinitions>` elements, which contain a collection of `<ColumnDefinition>` and `<RowDefinition>` elements, respectively. Each cell within a grid is indeed a true .NET object, so you can configure the look-and-feel and behavior of each cell as you see fit.

Here is a `<Grid>` definition (that you can find in the `SimpleGrid.xaml` file) that arranges your UI content as shown in Figure 28-10:

```
<Grid ShowGridLines = "True" Background = "AliceBlue">
    <!-- Define the rows/columns -->
    <Grid.ColumnDefinitions>
        <ColumnDefinition/>
        <ColumnDefinition/>
    </Grid.ColumnDefinitions>
    <Grid.RowDefinitions>
        <RowDefinition/>
        <RowDefinition/>
    </Grid.RowDefinitions>
```

```

<!-- Now add the elements to the grid's cells-->
<Label x:Name="lblInstruction" Grid.Column ="0" Grid.Row = "0"
    FontSize="15" Content="Enter Car Information"/>
<Button x:Name="btnOK" Height ="30" Grid.Column ="0"
    Grid.Row = "0" Content="OK"/>
<Label x:Name="lblMake" Grid.Column ="1"
    Grid.Row = "0" Content="Make"/>
<TextBox x:Name="txtMake" Grid.Column ="1"
    Grid.Row = "0" Width="193" Height="25"/>
<Label x:Name="lblColor" Grid.Column ="0"
    Grid.Row = "1" Content="Color"/>
<TextBox x:Name="txtColor" Width="193" Height="25"
    Grid.Column ="0" Grid.Row = "1" />

<!-- Just to keep things interesting, add some color to the pet name cell -->
<Rectangle Fill ="LightGreen" Grid.Column ="1" Grid.Row = "1" />
<Label x:Name="lblPetName" Grid.Column ="1" Grid.Row = "1" Content="Pet Name"/>
<TextBox x:Name="txtPetName" Grid.Column ="1" Grid.Row = "1"
    Width="193" Height="25"/>
</Grid>

```

Notice that each element (including a light green Rectangle element thrown in for good measure) connects itself to a cell in the grid using the `Grid.Row` and `Grid.Column` attached properties. By default, the ordering of cells in a grid begins at the upper left, which you specify using `Grid.Column="0"` `Grid.Row="0"`. Given that your grid defines a total of four cells, you can identify the bottom-right cell using `Grid.Column="1"` `Grid.Row="1"`.




Figure 28-10. The Grid panel in action

Grids with GridSplitter Types

Grid objects can also support *splitters*. As you might know, splitters allow the end user to resize rows or columns of a grid type. As this is done, the content within each resizable cell will reshape itself based on how the items have been contained. Adding splitters to a Grid is easy to do; you simply define the `<GridSplitter>` control, using attached property syntax to establish which row or column it affects.

Be aware that you must assign a `Width` or `Height` value (depending on vertical or horizontal splitting) for the splitter to be visible on the screen. Consider the following simple `Grid` type with a splitter on the first column (`Grid.Column = "0"`). The contents of the provided `GridWithSplitter.xaml` file look like this:

```
<Grid Background ="AliceBlue">
    <!-- Define columns -->
    <Grid.ColumnDefinitions>
        <ColumnDefinition Width ="Auto"/>
        <ColumnDefinition/>
    </Grid.ColumnDefinitions>

    <!-- Add this label to cell 0 -->
    <Label x:Name="lblLeft" Background ="GreenYellow"
        Grid.Column="0" Content ="Left!"/>

    <!-- Define the splitter -->
    <GridSplitter Grid.Column ="0" Width ="5"/>

    <!-- Add this label to cell 1 -->
    <Label x:Name="lblRight" Grid.Column ="1" Content ="Right!"/>
</Grid>
```

First and foremost, notice that the column that will support the splitter has a `Width` property of `Auto`. Next, notice that the `<GridSplitter>` uses attached property syntax to establish which column it is working with. If you were to view this output, you would find a five-pixel splitter that allows you to resize each `Label`. Note that the content fills up the entire cell because you have not specified `Height` or `Width` properties for either `Label` (see Figure 28-11).



Figure 28-11. Grid types containing splitters

Positioning Content Within DockPanel Panels

`DockPanel` is typically used as a master panel that contains any number of additional panels for grouping related content. `DockPanels` use attached property syntax (as seen with the `Canvas` or `Grid` types) to control where each item docks itself within the `DockPanel`.

The `SimpleDockPanel.xaml` file defines a simple `DockPanel` definition that results in the output shown in Figure 28-12:

```
<DockPanel LastChildFill ="True">
    <!-- Dock items to the panel -->
```

```

<Label x:Name="lblInstruction" DockPanel.Dock ="Top"
    FontSize="15" Content="Enter Car Information"/>
<Label x:Name="lblMake" DockPanel.Dock ="Left" Content="Make"/>
<Label x:Name="lblColor" DockPanel.Dock ="Right" Content="Color"/>
<Label x:Name="lblPetName" DockPanel.Dock ="Bottom" Content="Pet Name"/>
<Button x:Name="btnOK" Content="OK"/>
</DockPanel>

```




Figure 28-12. A simple DockPanel

Note If you add multiple elements to the same side of a DockPanel, they will stack along the specified edge in the order that they are declared.

The benefit of using DockPanel types is that, as the user resizes the window, each element remains connected to the specified side of the panel (through DockPanel.Dock). Also notice that the opening <DockPanel> tag sets the LastChildFill attribute to true. Given that the Button control has not specified any DockPanel.Dock value, it will therefore be stretched within the remaining space.

Enabling Scrolling for Panel Types

It is worth pointing out the WPF supplies a ScrollViewer class, which provides automatic scrolling behaviors for data within panel objects. The ScrollViewer.xaml file defines the following:

```

<ScrollViewer>
    <StackPanel>
        <Button Content ="First" Background = "Green" Height ="40"/>
        <Button Content ="Second" Background = "Red" Height ="40"/>
        <Button Content ="Third" Background = "Pink" Height ="40"/>
        <Button Content ="Fourth" Background = "Yellow" Height ="40"/>
        <Button Content ="Fifth" Background = "Blue" Height ="40"/>
    </StackPanel>
</ScrollViewer>

```

You can see the result of the previous XAML definition in Figure 28-13.



Figure 28-13. Working with the *ScrollViewer* type

As you would expect, each panel provides numerous members that allow you to fine-tune content placement. On a related note, many WPF controls support two properties of interest (*Padding* and *Margin*) that allow the control itself to inform the panel how it wishes to be treated. Specifically, the *Padding* property controls how much extra space should surround the interior control, while *Margin* controls the extra space around the exterior of a control.

This wraps up this chapter's look at the major panel types of WPF, as well as the various ways they position their content. Next, you will see an example that uses nested panels to create a layout system for a main window.

Building a Window's Frame Using Nested Panels

As mentioned previously, a typical WPF window will not use a single panel control, but instead will nest panels within other panels to gain the desired layout system. The next step is to learn how to nest panels, as well as how to use a number of new WPF controls. You will learn this by building a simple WPF word processor application. Begin by opening Visual Studio 2010 and creating a new WPF Application named *MyWordPad*.

Your goal is to construct a layout where the main window has a topmost menu system, a toolbar under the menu system, and a status bar mounted on the bottom of the window. The status bar will contain a pane to hold text prompts that are displayed when the user selects a menu item (or toolbar button), while the menu system and toolbar will offer UI triggers to close the application and display spelling suggestions in an *Expander* widget. Figure 28-14 shows the initial layout you are shooting for; it also displays spelling suggestions for *XAML*.




Figure 28-14. Using nested panels to establish a window's UI

Notice that the two toolbar buttons are not supporting an expected image, but a simple text value. This would not be sufficient for a production-level application, but assigning images to toolbar buttons typically involves using embedded resources, a topic that you will examine in Chapter 30 (so text data will do for now). Also note that, as the mouse button is placed over the Check button, the mouse cursor changes and the single pane of the status bar displays a useful UI message.

To begin building this UI, update the initial XAML definition for your `Window` type so it uses a `<DockPanel>` child element, rather than the default `<Grid>`:

```
<Window x:Class="MyWordPad.MainWindow"
    xmlns="http://schemas.microsoft.com/winfx/2006/xaml/presentation"
    xmlns:x="http://schemas.microsoft.com/winfx/2006/xaml"
    Title="MySpellChecker" Height="331" Width="508"
    WindowStartupLocation ="CenterScreen" >

    <!-- This panel establishes the content for the window -->
    <DockPanel>
    </DockPanel>

</Window>
```

Building the Menu System

Menu systems in WPF are represented by the `Menu` class, which maintains a collection of `MenuItem` objects. When building a menu system in XAML, you can have each `MenuItem` handle various events. The most notable of these events is `Click`, which occurs when the end user selects a sub-item. In this example, you begin by building the two topmost menu items (`File` and `Tools`; you will build the `Edit` menu later in this example), which expose `Exit` and `Spelling Hints` sub-items, respectively.

In addition to handling the `Click` event for each sub-item, you also need to handle the `MouseEnter` and `MouseLeave` events, which you will use to set the status bar text in a later step. Add the following markup within your `<DockPanel>` scope (feel free to use Properties window of Visual Studio 2010 to help minimize the amount of markup you need to type by hand):

```
<!--Dock menu system on the top-->
<Menu DockPanel.Dock ="Top"
    HorizontalAlignment="Left" Background="White" BorderBrush ="Black">
    <MenuItem Header="_File">
        <Separator/>
        <MenuItem Header ="_Exit" MouseEnter ="MouseEnterExitArea"
            MouseLeave ="MouseLeaveArea" Click ="FileExit_Click"/>
    </MenuItem>
    <MenuItem Header=_Tools>
        <MenuItem Header ="_Spelling Hints"
            MouseEnter ="MouseEnterToolsHintsArea"
            MouseLeave ="MouseLeaveArea" Click ="ToolsSpellingHints_Click"/>
    </MenuItem>
</Menu>
```

Notice that you dock the menu system to the top of the `DockPanel`. Also, you use the `<Separator>` element to insert a thin horizontal line in the menu system, directly before the `Exit` option. Also notice that the `Header` values for each `MenuItem` contain an embedded underbar token (e.g., `_Exit`). You use this

token to establish which letter will be underlined when the end user presses the Alt key (for keyboard shortcuts).

So far you've implemented the complete the menu system definition; next, you need to implement the various event handlers. First, you have the File ► Exit handler, `FileExit_Click()`, which simply closes the window, which in turn terminates the application because this is your topmost window. The `MouseEnter` and `MouseExit` event handlers for each sub-item will eventually update your status bar; however, for now, you will simply provide shells. Finally, the `ToolsSpellingHints_Click()` handler for the Tools ► Spelling Hints menu item will also remain a shell for the time being. Here are the current updates to your code-behind file:

```
public partial class MainWindow : System.Windows.Window
{
    public MainWindow()
    {
        InitializeComponent();
    }

    protected void FileExit_Click(object sender, RoutedEventArgs args)
    {
        // Close this window.
        this.Close();
    }

    protected void ToolsSpellingHints_Click(object sender, RoutedEventArgs args)
    {
    }
    protected void MouseEnterExitArea(object sender, RoutedEventArgs args)
    {
    }
    protected void MouseEnterToolsHintsArea(object sender, RoutedEventArgs args)
    {
    }
    protected void MouseLeaveArea(object sender, RoutedEventArgs args)
    {
    }
}
```

Building the ToolBar

Toolbars (represented by the `ToolBar` class in WPF) typically provide an alternative manner for activating a menu option. Add the following markup directly after the closing scope of your `<Menu>` definition:

```
<!-- Put Toolbar under the Menu -->
<ToolBar DockPanel.Dock ="Top" >
    <Button Content ="Exit" MouseEnter ="MouseEnterExitArea"
           MouseLeave ="MouseLeaveArea" Click ="FileExit_Click"/>
    <Separator/>
    <Button Content ="Check" MouseEnter ="MouseEnterToolsHintsArea"
           MouseLeave ="MouseLeaveArea" Click ="ToolsSpellingHints_Click"
```

```

        Cursor="Help" />
</ToolBar>
```

Your ToolBar control consists of two Button controls, which just so happen to handle the same events and are handled by the same methods in your code file. Using this technique, you can double-up your handlers to serve both menu items and toolbar buttons. Although this toolbar uses the typical push buttons, you should appreciate that the ToolBar type “is-a” ContentControl; therefore, you are free to embed any types into its surface (e.g., drop-down lists, images, and graphics). The only other point of interest here is that the Check button supports a custom mouse cursor through the Cursor property.

Note You can optionally wrap the ToolBar element within a <ToolBarTray> element, which controls layout, docking, and drag-and-drop operations for a set of ToolBar objects. Consult the .NET Framework 4.0 SDK documentation for details.

Building the StatusBar

A StatusBar control will be docked to the lower portion of the <DockPanel> and contain a single <TextBlock> control, which you have not used prior to this point in the chapter. You can use a TextBlock to hold text that supports numerous textual annotations, such as bold text, underlined text, line breaks, and so forth. Add the following markup directly after the previous ToolBar definition:

```

<!-- Put a StatusBar at the bottom --&gt;
&lt;StatusBar DockPanel.Dock ="Bottom" Background="Beige" &gt;
    &lt;StatusBarItem&gt;
        &lt;TextBlock Name="statBarText" Text="Ready"/&gt;
    &lt;/StatusBarItem&gt;
&lt;/StatusBar&gt;</pre>

```

Finalizing the UI Design

The final aspect of your UI design is to define a splittable Grid that defines two columns. On the left you place an Expander control that will display a list of spelling suggestions, wrapped within a <StackPanel>. On the right, you place a TextBox control that supports multiple lines and scrollbars, and includes enabled spell checking. You mount the entire <Grid> to the left of the parent <DockPanel>. Add the following XAML markup directly under the markup describing the StatusBar to complete the definition of our Window’s UI:

```

<Grid DockPanel.Dock ="Left" Background ="AliceBlue">
    <!-- Define the rows and columns -->
    <Grid.ColumnDefinitions>
        <ColumnDefinition />
        <ColumnDefinition />
    </Grid.ColumnDefinitions>

    <GridSplitter Grid.Column ="0" Width ="5" Background ="Gray" />
```

```

<StackPanel Grid.Column="0" VerticalAlignment = "Stretch" >
    <Label Name="lblSpellingInstructions" FontSize="14" Margin="10,10,0,0">
        Spelling Hints
    </Label>

    <Expander Name="expanderSpelling" Header = "Try these!" 
        Margin="10,10,10,10">
        <!-- This will be filled programmatically -->
        <Label Name = "lblSpellingHints" FontSize ="12"/>
    </Expander>
</StackPanel>

<!-- This will be the area to type within -->
<TextBox Grid.Column ="1"
    SpellCheck.IsEnabled ="True"
    AcceptsReturn ="True"
    Name ="txtData"   FontSize ="14"
    BorderBrush ="Blue"
    VerticalScrollBarVisibility="Auto"
    HorizontalScrollBarVisibility="Auto">
</TextBox>
</Grid>

```

Implementing the MouseEnter/MouseLeave Event Handlers

At this point, the UI of your window is complete. The only remaining tasks are to provide an implementation for the remaining event handlers. Begin by updating your C# code file so that each of the MouseEnter and MouseLeave handlers set the text pane of the status bar with a fitting message to help the end user:

```

public partial class MainWindow : System.Windows.Window
{
    ...
    protected void MouseEnterExitArea(object sender, RoutedEventArgs args)
    {
        statBarText.Text = "Exit the Application";
    }
    protected void MouseEnterToolsHintsArea(object sender, RoutedEventArgs args)
    {
        statBarText.Text = "Show Spelling Suggestions";
    }
    protected void MouseLeaveArea(object sender, RoutedEventArgs args)
    {
        statBarText.Text = "Ready";
    }
}

```

At this point, you can run your application. You should see your status bar change its text, based on which menu item/toolbar button you have selected.

Implementing the Spell Checking Logic

The WPF API ships with built-in spell checker support, which is independent of Microsoft Office products. This means you don't need to use the COM interop layer to use the spell checker of Microsoft Word; instead, you can easily add the same type of support with only a few lines of code.

You might recall that when you defined the `<TextBox>` control, you set the `SpellCheck.IsEnabled` property to true. When you do this, misspelled words are underlined in a red squiggle, just as they are in Microsoft Office. Even better, the underlying programming model gives you access to the spell-checker engine, which allows you to get a list of suggestions for misspelled words. Add the following code to your `ToolsSpellingHints_Click()` method:

```
protected void ToolsSpellingHints_Click(object sender, RoutedEventArgs args)
{
    string spellingHints = string.Empty;

    // Try to get a spelling error at the current caret location.
    SpellingError error = txtData.GetSpellingError(txtData.CaretIndex);
    if (error != null)
    {
        // Build a string of spelling suggestions.
        foreach (string s in error.Suggestions)
        {
            spellingHints += string.Format("{0}\n", s);
        }

        // Show suggestions and expand the expander.
        lblSpellingHints.Content = spellingHints;
        expanderSpelling.IsExpanded = true;
    }
}
```

The preceding code is quite simple. You simply figure out the current location of the caret in the text box by using the `CaretIndex` property to extract a `SpellingError` object. If there is an error at said location (meaning the value is not null), you loop over the list of suggestions using the aptly named `Suggestions` property. Once you have all of the suggestions for the misspelled word, you connect the data to the `Label` in the `Expander`.

So there you have it! With only a few lines of procedural code (and a healthy dose of XAML), you have the beginnings of a functioning word processor. An understanding of *control commands* can help you add a bit more pizzazz.

Understanding WPF Control Commands

Windows Presentation Foundation provides support for what might be considered *control-agnostic events* with *control commands*. A typical .NET event is defined within a specific base class and can only be used by that class or a derivative thereof. Therefore, normal .NET events are tightly coupled to the class in which they are defined.

In contrast, WPF control commands are event-like entities that are independent from a specific control and, in many cases, can be successfully applied to numerous (and seemingly unrelated) control types. By way of a few examples, WPF supports Copy, Paste, and Cut commands, which you can apply to

a wide variety of UI elements (e.g., menu items, toolbar buttons, and custom buttons), as well as keyboard shortcuts (e.g., Ctrl+C, and Ctrl+V).

While other UI toolkits (such as Windows Forms) provided standard events for such purposes, using them typically left you with redundant and hard to maintain code. Under the WPF model, you can use commands as an alternative. The end result typically yields a smaller and more flexible code base.

The Intrinsic Control Command Objects

WPF ships with numerous built-in control commands, all of which you can configure with associated keyboard shortcuts (or other input gestures). Programmatically speaking, a WPF control command is any object that supports a property (often called *Command*) that returns an object implementing the *ICommand* interface, as shown here:

```
public interface ICommand
{
    // Occurs when changes occur that affect whether
    // or not the command should execute.
    event EventHandler CanExecuteChanged;

    // Defines the method that determines whether the command
    // can execute in its current state.
    bool CanExecute(object parameter);

    // Defines the method to be called when the command is invoked.
    void Execute(object parameter);
}
```

While you could provide your own implementation of this interface to account for a control command, the chances that you will need to do so are slim, given that the functionality provided by the five WPF classes contains close to 100 command objects out-of-the-box. These classes define numerous properties that expose specific command objects, each of which implements *ICommand*.

Table 28-3 documents some of the standard command objects available (be sure to consult the .NET Framework 4.0 SDK documentation for complete details).

Table 28-3. The Intrinsic WPF Control Command Objects

WPF Class	Command Objects	Meaning in Life
ApplicationCommands	Close, Copy, Cut, Delete, Find, Open, Paste, Save, SaveAs, Redo, Undo	Various application-level commands
ComponentCommands	MoveDown, MoveFocusBack, MoveLeft, MoveRight, ScrollToEnd, ScrollToHome	Various commands common to UI components
MediaCommands	BoostBase, ChannelUp, ChannelDown, FastForward, NextTrack, Play, Rewind, Select, Stop	Various media-centric commands

Table 28-3. The Intrinsic WPF Control Command Objects (continued)

WPF Class	Command Objects	Meaning in Life
NavigationCommands	BrowseBack, BrowseForward, Favorites, LastPage, NextPage, Zoom	Various commands relating to the WPF navigation model
EditingCommands	AlignCenter, CorrectSpellingError, DecreaseFontSize, EnterLineBreak, EnterParagraphBreak, MoveDownByLine, MoveRightByWord	Various commands relating to the WPF document API

Connecting Commands to the Command Property

If you wish to connect any of these command properties to a UI element that supports the `Command` property (such as a `Button` or `MenuItem`), you have little work to do. You can see how to do this by updating the current menu system so it supports a new topmost menu item named `Edit` and three sub-items to account for copying, pasting, and cutting of textual data:

```
<Menu DockPanel.Dock ="Top"
      HorizontalAlignment="Left"
      Background="White" BorderBrush ="Black">
  <MenuItem Header="_File" Click ="FileExit_Click" >
    <Separator/>
    <MenuItem Header ="_Exit" MouseEnter ="MouseEnterExitArea"
              MouseLeave ="MouseLeaveArea" Click ="FileExit_Click"/>
  </MenuItem>

  <!-- New menu item with commands! -->
  <MenuItem Header=_Edit">
    <MenuItem Command ="ApplicationCommands.Copy"/>
    <MenuItem Command ="ApplicationCommands.Cut"/>
    <MenuItem Command ="ApplicationCommands.Paste"/>
  </MenuItem>

  <MenuItem Header=_Tools">
    <MenuItem Header ="_Spelling Hints"
              MouseEnter ="MouseEnterToolsHintsArea"
              MouseLeave ="MouseLeaveArea"
              Click ="ToolsSpellingHints_Click"/>
  </MenuItem>
</Menu>
```

Notice that each of the sub-items on the `Edit` menu has a value assigned to the `Command` property. Doing this means that the menu items automatically receive the correct name and shortcut key (e.g., `Ctrl+C` for a cut operation) in the menu item UI; it also means that the application is now *copy, cut, and paste* aware with no procedural code!

If you were to run the application and select some of your text, you would be able to use your new menu items out-of-the-box. As a bonus, your application is also equipped to respond to a standard *right-click* operation to present the user with the same options (Figure 28-15).




Figure 28-15. Command objects provide a good deal of built-in functionality for free

Connecting Commands to Arbitrary Actions

If you wish to connect a command object to an arbitrary (application-specific) event, you will need to drop down to procedural code. Doing so is not complex, but it does involve a bit more logic than you see in XAML. For example, assume that want to have the entire window respond to the F1 key, so that when the end user presses this key, he will activate an associated help system.

Also, assume your code file for the main window defines a new method named `SetF1CommandBinding()`, which you call within the constructor after the call to `InitializeComponent()`:

```
public MainWindow()
{
    InitializeComponent();
    SetF1CommandBinding();
}
```

This new method will programmatically create a new `CommandBinding` object, which you can use whenever you wish to bind a command object to a given event handler in your application. Here, you configure your `CommandBinding` object to operate with the `ApplicationCommands.Help` command, which is automatically F1-aware:

```
private void SetF1CommandBinding()
{
    CommandBinding helpBinding = new CommandBinding(ApplicationCommands.Help);
    helpBinding.CanExecute += CanHelpExecute;
    helpBinding.Executed += HelpExecuted;
    CommandBindings.Add(helpBinding);
}
```

Most `CommandBinding` objects will want to handle the `CanExecute` event (which allows you to specify whether the command occurs based on the operation of your program) and the `Executed` event (which is

where you can author the content that should occur once the command occurs). Add the following event handlers to your Window-derived type (note the format of each method, as required by the associated delegates):

```
private void CanHelpExecute(object sender, CanExecuteRoutedEventArgs e)
{
    // Here, you can set CanExecute to false if you wish to prevent the
    // command from executing.
    e.CanExecute = true;
}

private void HelpExecuted(object sender, ExecutedRoutedEventArgs e)
{
    MessageBox.Show("Look, it is not that difficult. Just type something!",
        "Help!");
}
```

In the preceding snippet, you implemented `CanHelpExecute()` so it always allows F1 help to launch; you do this by simply returning true. However, if you have certain situations where the help system should not display, you can account for this and return false when necessary. Your “help system” displayed within `HelpExecuted()` is little more than a message box. At this point, you can run your application. When you press the F1 key on your keyboard, you will see your (less than helpful, if not a bit insulting) user-guidance system (see Figure 28-16).



Figure 28-16. Your custom help system (which is not quite as helpful as the user would hope)

Working with the Open and Save Commands

To complete the current example, you will add functionality to save your text data to an external file and open up *.txt files for editing. If you want to take the long road, you can manually add programming logic that enables or disables new menu items based on whether your TextBox has data inside it. Once again, however, you can use commands to decrease your burden.

Begin by updating the `<MenuItem>` element that represents your topmost File menu by adding two new submenus that use the `Save` and `Open ApplicationCommands` objects:

```
<MenuItem Header="_File">
  <MenuItem Command = "ApplicationCommands.Open"/>
  <MenuItem Command = "ApplicationCommands.Save"/>
  <Separator/>
  <MenuItem Header ="_Exit"
    MouseEnter = "MouseEnterExitArea"
    MouseLeave = "MouseLeaveArea" Click ="FileExit_Click"/>

</MenuItem>
```

Again, remember that all command objects implement the `ICommand` interface, which defines two events (`CanExecute` and `Executed`). Now you need to enable the entire window, so it can check whether it is currently OK to fire these commands; if so, you can define an event handler to execute the custom code.

You do this by populating the `CommandBindings` collection maintained by the window. To do so in XAML requires that you use property element syntax to define a `<Window.CommandBindings>` scope in which you place two `<CommandBinding>` definitions. Update your `<Window>` like this:

```
<Window x:Class="MyWordPad.MainWindow"
  xmlns="http://schemas.microsoft.com/winfx/2006/xaml/presentation"
  xmlns:x="http://schemas.microsoft.com/winfx/2006/xaml"
  Title="MySpellChecker" Height="331" Width="508"
  WindowStartupLocation ="CenterScreen" >

  <!-- This will inform the Window which handlers to call,
       when testing for the Open and Save commands. -->
  <Window.CommandBindings>
    <CommandBinding Command="ApplicationCommands.Open"
      Executed="OpenCmdExecuted"
      CanExecute="OpenCmdCanExecute"/>
    <CommandBinding Command="ApplicationCommands.Save"
      Executed="SaveCmdExecuted"
      CanExecute="SaveCmdCanExecute"/>
  </Window.CommandBindings>

  <!-- This panel establishes the content for the window -->
  <DockPanel>
    ...
  </DockPanel>
</Window>
```

Now right-click each of the `Executed` and `CanExecute` attributes in your XAML editor and pick the `Navigate to Event Handler` menu option. As you might recall from Chapter 27, this will automatically generate stub code for the event itself. At this point, you should have four empty handlers in the C# code file for the window.

The implementation of `CanExecute` event handlers will tell the window that it is OK to fire the corresponding `Executed` events at any time by setting the `CanExecute` property of the incoming `CanExecuteRoutedEventArgs` object:

```

private void OpenCmdCanExecute(object sender, CanExecuteRoutedEventArgs e)
{
    e.CanExecute = true;
}

private void SaveCmdCanExecute(object sender, CanExecuteRoutedEventArgs e)
{
    e.CanExecute = true;
}

```

The corresponding Executed handlers perform the actual work of displaying the open and save dialog boxes; they also send the data in your TextBox to a file. Begin by making sure that you import the System.IO and Microsoft.Win32 namespaces into your code file. The completed code is straightforward:

```

private void OpenCmdExecuted(object sender, ExecutedRoutedEventArgs e)
{
    // Create an open file dialog box and only show XAML files.
    OpenFileDialog openDlg = new OpenFileDialog();
    openDlg.Filter = "Text Files (*.txt)";

    // Did they click on the OK button?
    if (true == openDlg.ShowDialog())
    {
        // Load all text of selected file.
        string dataFromFile = File.ReadAllText(openDlg.FileName);

        // Show string in TextBox.
        txtData.Text = dataFromFile;
    }
}

private void SaveCmdExecuted(object sender, ExecutedRoutedEventArgs e)
{
    SaveFileDialog saveDlg = new SaveFileDialog();
    saveDlg.Filter = "Text Files (*.txt)";

    // Did they click on the OK button?
    if (true == saveDlg.ShowDialog())
    {
        // Save data in the TextBox to the named file.
        File.WriteAllText(saveDlg.FileName, txtData.Text);
    }
}

```

That wraps up this example and your initial look at working with WPF controls. Here, you learned how to work with menu systems, status bars, tool bars, nested panels, and a few basic UI controls, such as TextBox and Expander. The next example will work with some more exotic controls, while examining several important WPF services at the same time. As an added bonus, you will build the interface using Expression Blend.

■ **Source Code** You can find the MyWordPad project under the Chapter 28 subdirectory.

Building a WPF User Interface with Expression Blend

Visual Studio 2010 provides a solid WPF-editing experience; and, if you so choose, you can use the IDE for all of your XAML editing. However, for complex applications, your work load will often decrease considerably if you use Blend to generate the markup, and then open the same project in Visual Studio to tweak the markup (if needed) and author code.

On a related note, Blend 3.0 ships with a simple code editor; while it is not anywhere near as powerful as Visual Studio, you can use this built-in C# editor to add code quickly to the UI event handlers during development.

Getting to know the Key Aspects of the Blend IDE

To begin learning about Blend, load the product and click the New Project button from the Welcome dialog (if you don't see the dialog, you can activate it from the File ▶ New project menu command). In the New Project dialog (see Figure 28-17), create a new WPF Application named `WpfControlsAndAPIs`.




Figure 28-17. Creating a new WPF Application with Expression Blend

Once you open the project, activate the Projects tab mounted on the upper-left area of the IDE (if you don't see it, activate the Window ▶ Projects menu option). As you can see in Figure 28-18, a WPF Application generated with Blend is identical to a WPF project generated with Visual Studio.




Figure 28-18. An Expression Blend WPF project is identical to a Visual Studio WPF project

Now locate the Properties tab on the right-hand side of the Blend IDE. Similar to Visual Studio 2010, this aspect of the tool allows you to assign property values to an item selected on the designer. However, it looks quite different from its Visual Studio 2010 counterpart. For example, notice that similar properties are grouped together in collapsible panes (see Figure 28-19).




Figure 28-19. The Blend Properties editor

Perhaps the most obvious part of the Blend IDE is its window designer, which takes up a majority of the real estate. Notice that you can see three small buttons in the upper-right area of the window designer; these buttons allow you to open the designer itself, the underlying XAML, or a split view. Figure 28-20 shows the designer in split view.




Figure 28-20. The Blend Designer allows you to view the underlying XAML

The XAML editor is quite feature-rich. For example, as you start typing, you will activate IntelliSense and find support for auto completion, as well as a useful help system. You won't have to enter much XAML manually in this example, but you can see the editor at work in Figure 28-21.




Figure 28-21. The Blend XAML editor is as rich as the editor in Visual Studio

Another key aspect of Blend to be aware of is the Objects and Timeline area (located in the bottom-left area of the Blend window). As you will learn in Chapter 30, the timeline aspect of this tool allows you to capture animation sequences. For now, suffice it to say that this aspect of the IDE allows you to view the logical tree of markup, much as the Document Viewer in Visual Studio 2010 does. Currently, your Objects and Timeline window should look like what you see in Figure 28-22.




Figure 28-22. You can view the tree of XAML using the Objects and Timeline editor

Here, you can see that your top-most node is the Window itself, which has an item named LayoutRoot as content. If you view the XAML of your initial window, you see this is the name given to the default <Grid> layout manager:

```
<Window
  xmlns="http://schemas.microsoft.com/winfx/2006/xaml/presentation"
  xmlns:x="http://schemas.microsoft.com/winfx/2006/xaml"
  x:Class="WpfControlsAndAPIs.MainWindow"
  x:Name="Window"
  Title="MainWindow"
  Width="559" Height="288" >
  <Grid x:Name="LayoutRoot"/>
</Window>
```

If you do not want to use a Grid as your default layout manager, you can edit the XAML file directly. Or, if you prefer, you can right-click the LayoutRoot icon in the Objects and Timeline window and select the Change Layout Type menu option.

Note When you wish to use the Properties editor to change the look-and-feel of a UI item, select it from the Objects and Timeline tree first. This will automatically select the correct item on the designer.

One final key aspect of Blend you should know about for now is the Tools editor, mounted on the far-left side of the IDE. Here you will find an assortment of WPF controls to select and place on your designer. Figure 28-23 shows that some of these buttons have a small triangle in the bottom-right area. If you click and hold such buttons, you will find a selection of related choices.

Note I have my Tools window mounted at the top of the Blend IDE, so my controls appear in a horizontal, rather than vertical strip. You can dock almost any Blend window using a standard mouse drag-and-drop command. Also, the Window > Reset Current Workspace menu option automatically restores the default location of each Blend window.




Figure 28-23. The Tools editor allows you to select a WPF control to place on the designer

Also notice that one of the buttons on the Tools window looks like a double greater-than sign (>>). Clicking this button opens up the Assets Library (see Figure 28-24). Here you will find many additional WPF controls that don't appear on the Tools window by default. Selecting items from the Assets Library moves them into the Tools area for use.




Figure 28-24. The Assets Library gives you access to additional WPF controls

Another important topic related to the Tools window is a common point of confusion for people who work with Blend for the first time; specifically, people are often confused about the difference between the Selection and Direct Selection buttons.

When you want to select an item on the designer (such as a Button) to change its size or relocate it in the container, you do so using the Selection button, which is the black arrow button (see Figure 28-25).



Figure 28-25. A Selection allows you to resize and reposition content on the designer

You use the Direct Selection arrow button (white in color) to drill into the content of a content control. Thus, if you direct select a Button, you can drill into its interior to build complex content visually (e.g., add a StackPanel and graphical items). You will revisit direct selection in Chapter 31 when you look at building custom controls. For this chapter, make sure you choose Select items, rather than Direct Select, when you build your GUIs.

Using the TabControl

Your window will contain a TabControl with four different tabs, each of which shows off a set of related controls and/or WPF APIs. Begin by ensuring that LayoutRoot is the selected node in your Objects and Timeline editor; this ensures that the control will be added to the panel. Next, use the Assets Library (the >> button) to locate the TabControl control. Now select the new item on your Tools window and draw the control onto the window designer so it takes up the majority of the surface. You should now see a tab system on your window with two default tabs.

Select your new TabControl in the Objects and Timeline editor, and then use the Properties window to name your new control `myTabSystem` using the Name edit area at the top of the property editor. Next, right-click the TabControl in the Objects and Timeline editor and select Add TabItem (see Figure 28-26).




Figure 28-26. Visually adding TabItems

Add another tab to your control and use the Properties editor to locate the Common Properties area of the Properties window. Next, change the Header property for each tab, naming them Ink API, Documents, Data Binding, and DataGrid (see Figure 28-27).




Figure 28-27. Visually editing the TabItem controls

At this point, your window designer should look like what you see in Figure 28-28.




Figure 28-28. The initial layout of the tab system

Now click each tab again and use the Properties window to give each tab a unique, proper name (you can also select each tab item using the Objects and Timeline editor). Be aware that when you click a tab using either approach, that tab becomes the active tab, and you can design that tab by dragging controls from the Tools area. Before you begin to design each tab, take a peek at the XAML that the IDE generates on your behalf by clicking the XAML button. You should see markup similar to the following (your markup might differ based on the properties you set):

```
<Window
    xmlns="http://schemas.microsoft.com/winfx/2006/xaml/presentation"
    xmlns:x="http://schemas.microsoft.com/winfx/2006/xaml"
    x:Class="WpfControlsAndAPIs.MainWindow"
    x:Name="Window"
    Title="MainWindow"
    Width="628" Height="383" >

    <Grid x:Name="LayoutRoot">
        <TabControl x:Name="myTabSystem" Margin="8">
            <TabItem x:Name="tabInk" Header="Ink API">
                <Grid/>
            </TabItem>
            <TabItem x:Name="tabDocuments" Header="Documents">
                <Grid/>
            </TabItem>
        </TabControl>
    </Grid>

```

```

</TabItem>
<TabItem x:Name="tabDataBinding" Header="Data Binding">
    <Grid/>
</TabItem>
<TabItem x:Name="tabDataGrid" Header="DataGrid">
    <Grid/>
</TabItem>
</TabControl>
</Grid>
</Window>

```

Building the Ink API Tab

The first tab shows the overall role of WPF's digital ink API, which allows you to incorporate painting functionality into a program easily. Of course, the application does not literally need to be a paining application; you can use this API for a wide variety of purposes, including capturing hand-writing input with a stylus for a TabletPC.

Begin by locating the node that represents the Ink API tab in your Objects and Timeline area and expand it. You should see that the default layout manager for this `TabItem` is a `<Grid>`. Right-click this and change it to a `StackPanel` (see Figure 28-29).




Figure 28-29. Changing the layout manager

Designing the ToolBar

You can ensure that the StackPanel is the currently selected node in the Objects and Timeline editor by using the Assets Library to insert a newToolBar control named inkToolbar. Next, select the inkToolbar node in the Objects and Timeline editor, locate the Layout section of the Properties window, and set the Height of the Toolbar control to 60 (leave the Width set to Auto).

Now find the Common Properties section of your Properties window and click the ellipse button for the Items (Collection) property (see Figure 28-30).




Figure 28-30. The first step in adding controls to a ToolBar with the Blend Properties window

After you click this button, you are presented with a dialog box that allows you to select the controls you want to add to the ToolBar. Click the dropdown area of the Add another item button, then add three RadioButton controls (Figure 28-31).




Figure 28-31. Adding three RadioButtons to the ToolBar

You can use the embedded Properties editor of this dialog to give each RadioButton a Height of 50 and a Width of 100 (again, you can find these properties in the Layout area). Also, set the Content property (located in the Common Properties area) of each RadioButton to the values Ink Mode!, Erase Mode!, and Select Mode! (see Figure 28-32).




Figure 28-32. Configuring each RadioButton

Once you add your three RadioButton controls, add a Separator control using the Add another item dropdown list. Now you need to add the final ComboBox (not ComboBoxItem) control; however, you will *not* see this control listed in the Add another item dropdown. When you need to insert non-standard controls using the Items (Collection) dialog, just click the Add another item area as if it were a push button. This opens the Select Object editor, where you can type in the name of the control you want (see Figure 28-33).




Figure 28-33. Using the Select Object editor to add unique items to the Toolbar

Set the Width property of the ComboBox to 100 and add three ComboBoxItem objects to the ComboBox using the Items (Collection) property (again) in the Common Properties section of the property editor. Set the Content property of each ComboBoxItem to the strings Red, Green, and Blue.

Once you do this, close the editor to return to the window designer. The last task for this section is to use the Name property to assign variable names to your new items. Name your three RadioButton controls inkRadio, selectRadio, and eraseRadio. Also, name your ComboBox control comboColors.

Note As you built your toolbar using Blend, you might have thought to yourself how much quicker your task would be if you could simply edit the XAML by hand... and you're right! You might remember that Expression Blend is targeted at graphical artists who might not feel comfortable manually entering markup or code. As a C# programmer, you can always use the integrated XAML editor of Blend as you work through these chapters; however, it is useful to know how to work within the IDE, especially when you need to explain how to use the tool to designers!

The RadioButton Control

In this example, you want these three RadioButton controls to be mutually exclusive. In other GUI frameworks, ensuring that a group of related controls (such as radio buttons) were mutually exclusive required that you place them in the same group box. You don't need to do this under WPF. Instead, you can simply assign them all to the same *group name*. This is helpful because the related items do not need to be physically collected in the same area, but can be anywhere in the window.

Do this by selecting each RadioButton on the designer (you can select all three using a Shift-Click operation), and then setting the *GroupName* property (located in the Common Properties area of the Properties window) to *InkMode*.

When a RadioButton control is not placed inside of a parent panel control, it will take on a UI identical to a Button control! However, unlike a Button, the RadioButton class includes an *IsChecked* property, which toggles between true and false when the end user clicks the UI element. Furthermore, RadioButton provides two events (*Checked* and *Unchecked*) that you can use to intercept this state change.

To configure your RadioButton controls to look like typical radio buttons, select each control on the designer using a Shift+Click operation, then right-click the selection and pick the *Group Into* ► *Border* menu option (see Figure 28-34).




Figure 28-34. Grouping items in a Border control

At this point, you're ready to test the program, which you can do by pressing the F5 key. You should now see three mutually exclusive radio buttons and a combo box with three selections (see Figure 28-35).




Figure 28-35. The completed toolbar system

Before you finish the UI of your Ink API tab, you need to handle the Click event for each RadioButton control. Similar to Visual Studio, the Blend Properties window has a Lightning Bolt button to enter the names of event handlers (you can see it mounted next to the Name property). Use this tool to route the Click event for each button to the same handler, named RadioButtonClicked (see Figure 28-36).




Figure 28-36. Handling the Click event for each RadioButton

Doing this brings up the Blend code editor. Once you handle all three Click events, handle the SelectionChanged event of the ComboBox using a handler named ColorChanged. When you finish, you should have the following C# code:

```
public partial class MainWindow : Window
{
    public MainWindow()
    {
        this.InitializeComponent();

        // Insert code required on object creation below this point.
    }
```

```

private void RadioButtonClicked(object sender, System.Windows.RoutedEventArgs e)
{
    // TODO: Add event handler implementation here.
}

private void ColorChanged(object sender,
    System.Windows.Controls.SelectionChangedEventArgs e)
{
    // TODO: Add event handler implementation here.
}
}

```

You will implement these handlers in a later step, so leave them empty for the time being.

The InkCanvas Control

To finish the UI of this tab, you need to place an `InkCanvas` control into the `StackPanel1`, so it appears below the `Toolbar` you have just created. Select the `StackPanel1` for the `tabInk` object in the Objects and Timeline editor, and then use the Assets Library to add an `InkCanvas` named `myInkCanvas`. Next, click the Selection tool on your Tools window (you can also press the `V` key on your keyboard as a shortcut) and stretch the ink canvas so it takes up a majority of the tab area.

Also, you might wish to use the Brushes editor to give your `InkCanvas` a unique background color (you'll learn much more about the brush editor in the next chapter). Once you do this, run your program by pressing the `F5` key. You will see the canvas is already able to draw data when you click-and-drag the left-mouse button (see Figure 28-37).




Figure 28-37. The `InkCanvas` in action

The `InkCanvas` does more than draw mouse (or stylus) strokes; it also supports a number of unique editing modes, controlled by the `EditingMode` property. You can assign this property any value from the

related `InkCanvasEditingStyle` enumeration. For this example, you are interested in `Ink` mode, which is the default option you just witnessed; `Select` mode, which allows the user to select a region with the mouse to move or resize; and `EraseByStroke`, which will delete the previous mouse stroke.

Note A *stroke* is the rendering that takes place during a single mouse down/mouse up operation. The `InkCanvas` stores all strokes in a `StrokeCollection` object, which you can access using the `Strokes` property.

Update your `RadioButtonClicked()` handler with the following logic, which places the `InkCanvas` in the correct mode, based on the selected `RadioButton`:

```
private void RadioButtonClicked(object sender,
    System.Windows.RoutedEventArgs e)
{
    // Based on which button sent the event, place the InkCanvas in a unique
    // mode of operation.
    switch((sender as RadioButton).Content.ToString())
    {
        // These strings must be the same as the Content values for each
        // RadioButton.
        case "Ink Mode!":
            this.myInkCanvas.EditingMode = InkCanvasEditingStyle.Ink;
            break;

        case "Erase Mode!":
            this.myInkCanvas.EditingMode = InkCanvasEditingStyle.EraseByStroke;
            break;

        case "Select Mode!":
            this.myInkCanvas.EditingMode = InkCanvasEditingStyle.Select;
            break;
    }
}
```

Also, set the mode to `Ink` by default in the window's constructor. And while you are at it, set a default selection for the `ComboBox` (more details on this control in the next section):

```
public MainWindow()
{
    this.InitializeComponent();

    // Be in Ink mode by default.
    this.myInkCanvas.EditingMode = InkCanvasEditingStyle.Ink;
    this.inkRadio.IsChecked = true;
    this.comboColors.SelectedIndex=0;
}
```

Now run your program again by pressing F5. Enter `Ink` mode and draw some data. Next, enter `Erase` mode and remove the previous mouse stroke you entered (you'll notice the mouse icon automatically

looks like an erasure). Finally, enter Select mode and select some strokes by using the mouse as a lasso. After you circle the item, you can move it around the canvas and resize its dimensions. Figure 28-38 shows your edit modes at work.




Figure 28-38. The InkCanvas in action, with edit modes!

The ComboBox Control

Once you populate a ComboBox control (or a ListBox), you have three ways to determine the selected item. First, if you wish to find the numerical index of the item selected, you can use the `SelectedIndex` property (which is zero-based; a value of -1 represents no selection). Second, if you wish to obtain the object within the list that has been selected, the `SelectedItem` property fits the bill. Third, the `SelectedValue` allows you to obtain the value of the selected object (typically obtained using a call to `ToString()`).

You need to add the last bit of code for this tab to change the color of the strokes entered on the InkCanvas. The `DefaultDrawingAttributes` property of `InkCanvas` returns a `DrawingAttributes` object that allows you to configure numerous aspects of the pen nib, including its size and color (among other settings). Update your C# code with this implementation of the `ColorChanged()` method:

```
private void ColorChanged(object sender,
    System.Windows.Controls.SelectionChangedEventArgs e)
{
    // Get the selected value in the combo box.
    string colorToUse =
        (this.comboBoxColors.SelectedItem as ComboBoxItem).Content.ToString();

    // Change the color used to render the strokes.
    this.myInkCanvas.DefaultDrawingAttributes.Color =
        (Color)ColorConverter.ConvertFromString(colorToUse);
}
```

Now recall that the `ComboBox` has a collection of `ComboBoxItems`. If you were to view the generated XAML, you'd see the following definition:

```
<ComboBox x:Name="comboColors" Width="100" SelectionChanged="ColorChanged">
    <ComboBoxItem Content="Red"/>
    <ComboBoxItem Content="Green"/>
    <ComboBoxItem Content="Blue"/>
</ComboBox>
```

When you call `SelectedItem`, you grab the selected `ComboBoxItem`, which is stored as a general `Object`. Once you cast the `Object` as a `ComboBoxItem`, you pluck out the value of the `Content`, which will be the string Red, Green, or Blue. This string is then converted to a `Color` object using the handy `ColorConverter` utility class. Now run your program again. You should be able to change between colors as you render your image.

Note that the `ComboBox` and `ListBox` controls can contain complex content as well, rather than a list of text data. You can get a sense of some of the things that are possible by opening the XAML editor for your window and changing the definition of your `ComboBox` so it contains a set of `<StackPanel>` elements, each of which contains an `<Ellipse>` and a `<Label>` (notice that the `Width` of the `ComboBox` is 200):

```
<ComboBox x:Name="comboColors" Width="200" SelectionChanged="ColorChanged">
    <StackPanel Orientation ="Horizontal" Tag="Red">
        <Ellipse Fill ="Red" Height ="50" Width ="50"/>
        <Label FontSize ="20" HorizontalAlignment="Center"
            VerticalAlignment="Center" Content="Red"/>
    </StackPanel>

    <StackPanel Orientation ="Horizontal" Tag="Green">
        <Ellipse Fill ="Green" Height ="50" Width ="50"/>
        <Label FontSize ="20" HorizontalAlignment="Center"
            VerticalAlignment="Center" Content="Green"/>
    </StackPanel>

    <StackPanel Orientation ="Horizontal" Tag="Blue">
        <Ellipse Fill ="Blue" Height ="50" Width ="50"/>
        <Label FontSize ="20" HorizontalAlignment="Center"
            VerticalAlignment="Center" Content="Blue"/>
    </StackPanel>
</ComboBox>
```

Notice that each `StackPanel` assigns a value to its `Tag` property, which is a simple, fast, and convenient way to discover which stack of items has been selected by the user (there are better ways to do this, but this will do for now). With this adjustment, you need to change the implementation of your `ColorChanged()` method, like this:

```
private void ColorChanged(object sender,
    System.Windows.Controls.SelectionChangedEventArgs e)
{
    // Get the Tag of the selected StackPanel.
    string colorToUse = (this.comboColors.SelectedItem
        as StackPanel).Tag.ToString();

    ...
}
```

Now run your program again and take note of your unique ComboBox (see Figure 28-39).




Figure 28-39. A custom ComboBox, thanks to the WPF content model

Saving, Loading, and Clearing InkCanvas Data

The last part of this tab will enable you to save and load your canvas data, as well as clear it of all content. At this point in the chapter, you might feel a bit more comfortable designing a UI with Blend, so the instructions will be short and sweet.

Begin by importing the `System.IO` and `System.Windows.Ink` namespaces to your code file. Now add three more Button controls to yourToolBar named `btnSave`, `btnLoad`, and `btnClear`. Next, handle the Click event for each control, then Implement the handlers, like this:

```
private void SaveData(object sender, System.Windows.RoutedEventArgs e)
{
    // Save all data on the InkCanvas to a local file.
    using (FileStream fs = new FileStream("StrokeData.bin", FileMode.Create))
    {
        this.myInkCanvas-strokes.Save(fs);
        fs.Close();
    }
}

private void LoadData(object sender, System.Windows.RoutedEventArgs e)
{
    // Fill StrokeCollection from file.
    using(FileStream fs = new FileStream("StrokeData.bin",
        FileMode.Open, FileAccess.Read))
    {
        StrokeCollection strokes = new StrokeCollection(fs);
```

```

        this.myInkCanvas.Strokes = strokes;
    }

private void Clear(object sender, System.Windows.RoutedEventArgs e)
{
    // Clear all strokes.
    this.myInkCanvas.Strokes.Clear();
}

```

You should now be able to save your data to a file, load it from the file, and clear the InkCanvas of all data. That wraps up the first tab of the TabControl1, as well as your examination of the WPF digital Ink API. To be sure, there is more to say about this technology; however, you should be in a good position to dig into the topic further if that interests you. Next, you will learn how to use the WPF Documents API.

Introducing the Documents API

WPF ships with many controls that allow you to capture or display simple blurbs of textual data, including Label, TextBox, TextBlock, and PasswordBox. These controls are useful, but some WPF applications require the use of sophisticated, highly formatted text data, similar to what you might find in an Adobe PDF file. The Documents API of WPF provides such functionality; however, it uses the XML Paper Specification (XPS) format rather than the PDF file format.

You can use the Documents API to construct a print-ready document by leveraging several classes from the `System.Windows.Documents` namespace. Here you will find a number of types that represent pieces of a rich XPS document, such as List, Paragraph, Section, Table, LineBreak, Figure, Floater, and Span.

Block Elements and Inline Elements

Formally speaking, the items you add to a XPS document belong to one of two broad categories: *block elements* and *inline elements*. This first category, *block elements*, consists of classes that extend the `System.Windows.Documents.Block` base class. Examples of block elements include List, Paragraph, BlockUIContainer, Section, and Table. You use classes from this category to group together other content (e.g., a list containing paragraph data, and a paragraph containing sub paragraphs for different text formatting).

The second category, *inline elements*, consists of classes that extend the `System.Windows.Documents.Inline` base class. You nest inline elements within another block item (or possibly within another inline element inside a block element). Some common inline elements include Run, Span, LineBreak, Figure, and Floater.

These classes possess names that you might encounter when building a rich document with a professional editor. As with any other WPF control, you can configure these classes in XAML or through code. Therefore, you can declare an empty `<Paragraph>` element that is populated at runtime (you'll see how to do such tasks in this example).

Document Layout Managers

You might think you can simply place inline and block elements directly into a panel container such as a `Grid`; however, you need to wrap them in a `<FlowDocument>` element or a `<FixedDocument>` element.

It is ideal to place items in a `FlowDocument` when you wish to let your end user change the way the data is presented on the computer screen. The user can do this by zooming text or changing how the data is presented (e.g., a single long page or a pair of columns). You're better off using `FixedDocument` for true print-ready (WYSIWYG), unchangeable document data.

For this example, you will only concern yourself with the `FlowDocument` container. Once you insert inline and block items to your `FlowDocument`, the `FlowDocument` object is placed in one of four specialized XPS-aware layout managers, listed in Table 28-4.

Table 28-4. XPS Control Layout Managers

Panel Control	Meaning in Life
<code>FlowDocumentReader</code>	Displays data in a <code>FlowDocument</code> and adds support for zooming, searching, and content layout in various forms.
<code>FlowDocumentScrollView</code>	Displays data in a <code>FlowDocument</code> ; however, the data is presented as a single document viewed with scrollbars. This container does not support zooming, searching, or alternative layout modes.
<code>RichTextBox</code>	Displays data in a <code>FlowDocument</code> and adds support for user editing.
<code>FlowDocumentPageViewer</code>	Displays the document page-by-page, one page at a time. Data can also be zoomed, but not searched.

The most feature-rich way to display a `FlowDocument` is to wrap it within a `FlowDocumentReader` manager. When you do this, the user can alter the layout, search for words in the document, and zoom in on the data using the provided UI. The one limitation of this container (as well as of `FlowDocumentScrollView` and `FlowDocumentPageViewer`) is that the content you display with it is read only. However, if you do want to allow the end user to enter new information to the `FlowDocument`, you can wrap it in a `RichTextBox` control.

Building the Documents Tab

Click on the Documents tab of your `TabItem` and use the Blend editor to open this control for editing. You should already have a default `<Grid>` control as the direct child of the `TabItem` control; however, change it to a `StackPanel` here using the Objects and Timeline window. This tab will display a `FlowDocument` that allows the user to highlight selected text, as well as add annotations using the Sticky Notes API.

Begin by defining the following `ToolBar` control, which has three simple (and unnamed!) `Button` controls. You will be rigging up a few new commands to these controls later on, so you do not need to refer to them in code:

```

<TabItem x:Name="tabDocuments" Header="Documents" VerticalAlignment="Bottom"
         Height="20">
    <StackPanel>
        <ToolBar>
            <Button BorderBrush="Green" Content="Add Sticky Note"/>
            <Button BorderBrush="Green" Content="Delete Sticky Notes"/>
            <Button BorderBrush="Green" Content="Highlight Text"/>
        </ToolBar>
    </StackPanel>
</TabItem>

```

Next, open the Assets Library and locate the FlowDocumentReader control from the All category of the Controls node. Place this control into your StackPanel, rename it to myDocumentReader, and stretch it out over the surface of your StackPanel (make sure you have clicked the Selection tool). At this point, your layout should look similar to what you see in Figure 28-40.




Figure 28-40. The layout of the Documents tab

Now select your FlowDocumentReader control in the Objects and Timeline editor and locate the Miscellaneous category of the Properties window. Next, click the New button next to the Document property. Doing this updates your XAML with an empty <FlowDocument>:

```

<FlowDocumentReader x:Name="myDocumentReader" Height="269.4">
    <FlowDocument/>
</FlowDocumentReader>

```

At this point, you can add document classes (e.g., List, Paragraph, Section, Table, LineBreak, Figure, Floater, and Span) to the element.

Populating a FlowDocument using Blend

As soon as you add a new document to a document container, the Document property in the Properties window becomes expandable, displaying a *ton* of new properties that allow you to build the design of your document. For this example, the only property you care about is the Blocks (Collection) property (see Figure 28-41).




Figure 28-41. You can populate a FlowDocument using the Blocks (Collection) property

Click the ellipse button (...) to the right of Blocks (Collection), and then use the Add another item button of the resulting dialog box to insert a Section, List, and Paragraph. You can edit each one of these further using the Blocks editor; furthermore, a given block can contain related sub-blocks. For example, if you select your Section, you can add a Paragraph sub-block. In my case, I configured my Section with a specific background color, foreground color, and font size. I also inserted a sub-Paragraph.

Go ahead and configure your Section as you wish; however, leave the List and original Paragraph empty because you will drive these through code. Here is one possible way to configure the FlowDocument:

```
<FlowDocumentReader x:Name="myDocumentReader" Height="269.4">
  <FlowDocument>
    <Section Foreground = "Yellow" Background = "Black">
      <Paragraph FontSize = "20">
        Here are some fun facts about the WPF Document API!
      </Paragraph>
    </Section>
    <List/>
    <Paragraph/>
  </FlowDocument>
</FlowDocumentReader>
```

If you run your program now (hit the F5 key), you should already be able to zoom your document (using the lower-right slider bar), search for a keyword (using the lower-left search editor) and display the data in one of three manners (using the layout buttons). Figure 28-42 shows a search for the text *WPF*; note too that the content shown in this figure has been zoomed in on.



Figure 28-42. Manipulating the *FlowDocument* with the *FlowDocumentReader*

Before moving to the next step, you might want to edit your XAML to use a different *FlowDocument* container, such as the *FlowDocumentScrollView* or a *RichTextBox*, rather than the *FlowDocumentReader*. Once you done this, run the application again and notice the different ways the document data is handled. Be sure to roll back to the *FlowDocumentReader* type when you finish this task.

Populating a *FlowDocument* Using Code

Now, let's build the *List* block and the remaining *Paragraph* block in code. This is important because you might need to populate a *FlowDocument* based on user input, external files, database information, or what have you. Before you do so, use the XAML editor of Blend to give the *List* and *Paragraph* elements proper names, so you can access them in code:

```
<List x:Name="listOfFunFacts"/>
<Paragraph x:Name="paraBodyText"/>
```

In your code file, define a new private method named *PopulateDocument()*. This method first adds a set of new *ListItems* to the *List*, each of which has a *Paragraph* with a single *Run*. Also, your helper method dynamically builds a formatted paragraph using three separate *Run* objects, as in the following example:

```
private void PopulateDocument()
{
    // Add some data to the List item.
```

```

this.listOfFunFacts.FontSize = 14;
this.listOfFunFacts.MarkerStyle = TextMarkerStyle.Circle;
this.listOfFunFacts.ListItems.Add(new ListItem(
    new Paragraph(new Run("Fixed documents are for WYSIWYG print ready docs!"))));
this.listOfFunFacts.ListItems.Add(new ListItem(
    new Paragraph(new Run("The API supports tables and embedded figures!"))));
this.listOfFunFacts.ListItems.Add(new ListItem(
    new Paragraph(new Run("Flow documents are read only!"))));
this.listOfFunFacts.ListItems.Add(new ListItem(new Paragraph(new Run(
        ("BlockUIContainer allows you to embed WPF controls in the document!")
    ))));

// Now add some data to the Paragraph.
// First part of sentence.
Run prefix = new Run("This paragraph was generated ");

// Middle of paragraph.
Bold b = new Bold();
Run infix = new Run("dynamically");
infix.Foreground = Brushes.Red;
infix.FontSize = 30;
b.Inlines.Add(infix);

// Last part of paragraph.
Run suffix = new Run(" at runtime!");

// Now add each piece to the collection of inline elements
// of the Paragraph.
this.paraBodyText.Inlines.Add(prefix);
this.paraBodyText.Inlines.Add(infix);
this.paraBodyText.Inlines.Add(suffix);
}

```

Make sure you call this method from your window's constructor. Once you do this, you can run the application and see your new, dynamically generated document content.

Enabling Annotations and Sticky Notes

So far, so good. You can now build a document with interesting data using XAML and C# code; however, you still need to address the three buttons on your toolbar for the Documents tab. WPF ships with a set of commands that are used specifically with the Documents API. You can use these commands to allow the user to select a part of a document for highlighting or to add sticky note annotations. Best of all, you can add all of this with a few lines of code (and a tad of markup).

You can find the command objects for the Documents API bundled in the `System.Windows.Annotations` namespace of `PresentationFramework.dll`. Thus, you need to define a custom XML namespace in the opening element of the `<Window>` to use such objects in XAML (notice that the tag prefix is *a*):

```

<Window
...

```

```

xmlns:a=
"clr-namespace:System.Windows.Annotations;assembly=PresentationFramework"
x:Class="WpfControlsAndAPIs.MainWindow"
x:Name="Window"
Title="MainWindow"
Width="856" Height="383" mc:Ignorable="d"
WindowStartupLocation="CenterScreen" >
...
</Window>

```

Now update your three <Button> definitions to set the Command property to three of the supplied annotation commands:

```

<ToolBar>
  <Button BorderBrush="Green" Content="Add Sticky Note"
    Command="a:AnnotationService.CreateTextStickyNoteCommand"/>
  <Button BorderBrush="Green" Content="Delete Sticky Notes"
    Command="a:AnnotationService.DeleteStickyNotesCommand"/>
  <Button BorderBrush="Green" Content="Highlight Text"
    Command="a:AnnotationService.CreateHighlightCommand"/>
</ToolBar>

```

The last thing you need to do is to enable annotation services for the FlowDocumentReader object, which you named myDocumentReader. Add another private method in your class named EnableAnnotations(), which is called from the constructor of the window. Now import the following namespaces:

```

using System.Windows.Annotations;
using System.Windows.Annotations.Storage;

```

Next, implement this method:

```

private void EnableAnnotations()
{
  // Create the AnnotationService object that works
  // with our FlowDocumentReader.
  AnnotationService anoService = new AnnotationService(myDocumentReader);

  // Create a MemoryStream which will hold the annotations.
  MemoryStream anoStream = new MemoryStream();

  // Now, create a XML-based store based on the MemoryStream.
  // You could use this object to programmatically add, delete
  // or find annotations.
  AnnotationStore store = new XmlStreamStore(anoStream);

  // Enable the annotation services.
  anoService.Enable(store);
}

```

The `AnnotationService` class allows a given document layout manager to opt in to annotation support. Before you call the `Enable()` method of this object, you need to provide a location for the object to store annotation data, which in this example is a chunk of memory represented by a `MemoryStream` object. Notice that you connect the `AnnotationService` object with the `Stream` using the `AnnotationStore`.

Now, run your application. When you select some text, you can click the Add Sticky Note button and type in some information. Also, when you select some text, you can highlight data (the color is yellow by default). Finally, you can delete created notes once you select them and click the Delete Sticky Note button. Figure 28-43 shows a test run.




Figure 28-43. Sticky notes!

Saving and Loading a Flow Document

Let's wrap up this look at the Documents API by looking at how simple it is to save a document out to a file, as well as read a document in from a file. Recall that, unless you wrap your `FlowDocument` object in a `RichTextBox`, the end user cannot edit the document; however, part of the document was created dynamically at runtime, so you might like to save it for later use. The ability to load an XPS style document could also be useful in many WPF applications because you might wish to define a blank document and load it all on the fly.

This next snippet assumes you will add two new Buttons to the Toolbar of the Documents tab, which you declare like this (note that you did not handle any events in your markup):

```
<Button x:Name="btnSaveDoc" HorizontalAlignment="Stretch"
    VerticalAlignment="Stretch" Width="75" Content="Save Doc"/>
<Button x:Name="btnLoadDoc" HorizontalAlignment="Stretch"
    VerticalAlignment="Stretch" Width="75" Content="Load Doc"/>
```

Now, in the constructor of your window, author the following lambda expressions to save and load the FlowDocument data (you'll need to import the `System.Windows.Markup` namespace to gain access to the `XamlReader` and `XamlWriter` classes):

```
public MainWindow()
{
...
    // Rig up some Click handlers for the save / load of the flow doc.
    btnSaveDoc.Click += (o, s) =>
    {
        using(FileStream fStream = File.Open(
            "documentData.xaml", FileMode.Create))
        {
            XamlWriter.Save(this.myDocumentReader.Document, fStream);
        }
    };

    btnLoadDoc.Click += (o, s) =>
    {
        using(FileStream fStream = File.Open("documentData.xaml", FileMode.Open))
        {
            try
            {
                FlowDocument doc = XamlReader.Load(fStream) as FlowDocument;
                this.myDocumentReader.Document = doc;
            }
            catch(Exception ex) {MessageBox.Show(ex.Message, "Error Loading Doc!");}
        }
    };
}
```

That is all you need to do to save the document (note that you did not save any annotations; however, you can also accomplish that using annotation services). If you click your Save button, you will see a new *.xaml file in your \bin\Debug folder. This file contains the current document data.

That wraps up your look at the WPF Documents API. To be sure, there is more to this API than you have seen here; but at this point, you know a good deal about the basics. To wrap up this chapter, you will look at a handful of data-binding topics and complete the current application.

Introducing the WPF Data-Binding Model

Controls are often the target of various data-binding operations. Simply put, *data binding* is the act of connecting control properties to data values that might change over the course of your application's lifetime. Doing so lets a user interface element display the state of a variable in your code. For example, you might use data binding to accomplish the following:

- Check a CheckBox control based on a Boolean property of a given object.
- Display data in DataGrid objects from a relational database table.
- Connect a Label to an integer that represents the number of files in a folder.

When you use the intrinsic WPF data-binding engine, you must be aware of the distinction between the *source* and the *destination* of the binding operation. As you might expect, the source of a data-binding operation is the data itself (e.g., a Boolean property or relational data), while the destination (target) is the UI control property that uses the data content (e.g., a CheckBox or TextBox).

Truth be told, using the WPF data-binding infrastructure is always optional. If you were to roll your own data-binding logic, the connection between a source and destination typically would involve handling various events and authoring procedural code to connect the source and destination. For example, if you had a ScrollBar on a window that needed to display its value on a Label type, you might handle the ScrollBar's ValueChanged event and update the Label's content accordingly.

However, you can use WPF data binding to connect the source and destination directly in XAML (or use C# code in your code file) without the need to handle various events or hard-code the connections between the source and destination. Also, based on how you set up your data-binding logic, you can ensure that the source and destination stay in sync if either of their values changes.

Building the Data Binding Tab

Using the Objects and Timeline editor, change the Grid of your third tab to a StackPanel. Now, use the Assets Library and the Properties editor of Blend to build the following initial layout:

```
<TabItem x:Name="tabDataBinding" Header="Data Binding">
    <StackPanel Width="250">
        <Label Content="Move the scroll bar to see the current value"/>

        <!-- The scrollbar's value is the source of this data bind -->
        <ScrollBar x:Name="mySB" Orientation="Horizontal" Height="30"
            Minimum = "1" Maximum = "100" LargeChange="1" SmallChange="1"/>

        <!-- The label's content will be bound to the scroll bar! -->
        <Label x:Name="labelSBThumb" Height="30" BorderBrush="Blue"
            BorderThickness="2" Content = "0"/>
    </StackPanel>
</TabItem>
```

Notice that the `<ScrollBar>` object (named `mySB` here) has been configured with a range between 1 and 100. The goal is to ensure that, as you reposition the thumb of the scrollbar (or click the left or right arrow), the Label will automatically update with the current value.

Establishing Data Bindings using Blend

The glue that makes it possible to define a binding in XAML is the `{Binding}` markup extension. If you wish to establish a binding between controls using Blend, you can do so easily. For this example, locate the Content property of the Label object (in the Common Properties area of the Properties window) and click the (very) small white square next to the property to open the Advanced Property options. From here, select Data Binding (see Figure 28-44).




Figure 28-44. Configuring a data binding operation with Blend

You are interested in the Element Property tab here because this will give you a list of all items in your XAML file, which you can select as the source of the data-binding operation. Select this tab, and in the Scene elements list box, find your ScrollBar object (named mySB). In the Properties list box, find the Value property (see Figure 28-45). Click the OK button once you do this.




Figure 28-45. Selecting the source object and the property on the object

If you run your program again, you will find that the content of the label updates as you move the thumb! Now look at the XAML the data binding tool generated on your behalf:

```
<Label x:Name="labelSBThumb" Height="30" BorderBrush="Blue" BorderThickness="2"
Content = "{Binding Value, ElementName=mySB, Mode=Default}" />
```

Note the value assigned to the Label's Content property. Here, the ElementName value represents the source of the data-binding operation (the ScrollBar object), while the first item after the Binding keyword (Value) represents (in this case) the property of the element to obtain.

If you have worked with WPF data binding previously, you might expect to see the use of the Path token to set the property to observe on the object. For example, the following markup would also update the Label correctly:

```
<Label x:Name="labelSBThumb" Height="30" BorderBrush="Blue"
BorderThickness="2" Content = "{Binding Path=Value,
ElementName=mySB, Mode=Default}" />
```

By default, Blend omits the Path= aspect of the data-binding operation unless the property is a sub-property of another object (e.g., myObject.MyProperty.Object2.Property2).

The DataContext Property

You can define a data-binding operation in XAML using an alternative format, where it is possible to break out the values specified by the {Binding} markup extension by explicitly setting the `DataContext` property to the source of the binding operation, as follows:

```
<!-- Breaking object/value apart via DataContext -->
<Label x:Name="labelSBThumb" Height="30" BorderBrush="Blue"
    BorderThickness="2"
    DataContext = "{Binding ElementName=mySB}"
    Content = "{Binding Path=Value}" />
```

In the current example, the output would be identical if you were to modify the markup in this way. Given this, you might wonder when you would want to set the `DataContext` property explicitly. Doing so can be helpful because sub-elements can inherit its value in a tree of markup.

In this way, you can easily set the same data source to a family of controls, rather than having to repeat a bunch of redundant "`{Binding ElementName=X, Path=Y}`" XAML values to multiple controls. For example, assume you have added a new Button to the `<StackPanel>` of this tab (you'll see why it is so large in just a moment):

```
<Button Content="Click" Height="140"/>
```

You could use Blend to generate data bindings for multiple controls, but instead try entering the modified markup manually using the XAML editor:

```
<!-- Note the StackPanel sets the DataContext property -->
<StackPanel Width="250" DataContext = "{Binding ElementName=mySB}">
    <Label Content="Move the scroll bar to see the current value"/>

    <ScrollBar Orientation="Horizontal" Height="30" Name="mySB"
        Maximum = "100" LargeChange="1" SmallChange="1"/>

    <!-- Now both UI elements use the scrollbar's value in unique ways. -->
    <Label x:Name="labelSBThumb" Height="30" BorderBrush="Blue" BorderThickness="2"
        Content = "{Binding Path=Value}" />

    <Button Content="Click" Height="200"
        FontSize = "{Binding Path=Value}" />
</StackPanel>
```

Here, you set the `DataContext` property on the `<StackPanel>` directly. Therefore, as you move the thumb, you see not only the current value on the Label, but also see the font size of the Button grow and shrink accordingly, based on the same value (see Figure 28-46 shows for one possible output).



Figure 28-46. Binding the ScrollBar value to a Label and a Button

Data Conversion Using IValueConverter

The ScrollBar type uses a double to represent the value of the thumb, rather than an expected whole number (e.g., an integer). Therefore, as you drag the thumb, you will find various floating-point numbers displayed within the Label (e.g., 61.0576923076923). The end user would find this rather unintuitive because he is most likely expecting to see whole numbers (e.g., 61, 62, and 63).

If you wish to convert the value of a data-binding operation into an alternative format, you could create a custom class that implements the `IValueConverter` interface of the `System.Windows.Data` namespace. This interface defines two members that allow you to perform the conversion to and from the target and destination (in the case of a two-way data binding). Once you define this class, you can use it to qualify further the processing of your data-binding operation.

Assuming that you wish to display whole numbers within the Label control, you can build the following class using Expression Blend. Activate the Project ▶ Add New Item menu and insert a class named `MyDoubleConverter`. Next, add the following:

```
class MyDoubleConverter : IValueConverter
{
    public object Convert(object value, Type targetType, object parameter,
                         System.Globalization.CultureInfo culture)
    {
        // Convert the double to an int.
        double v = (double)value;
        return (int)v;
    }

    public object ConvertBack(object value, Type targetType, object parameter,
                            System.Globalization.CultureInfo culture)
    {
```

```

    // You won't worry about "two way" bindings
    // here, so just return the value.
    return value;
}
}

```

The `Convert()` method is called when the value is transferred from the source (the `ScrollBar`) to the destination (the `Text` property of the `TextBox`). You receive many of incoming arguments, but you only need to manipulate the incoming object for this conversion, which is the value of the current double. You can use this type to cast the type into an integer and return the new number.

The `ConvertBack()` method will be called when the value is passed from the destination to the source (if you have enabled a two-way binding mode). Here, you simply return the value straightforward. Doing so lets you type a floating-point value into the `TextBox` (e.g., 99.9) and have it automatically convert to a whole number value (e.g., 99) when the user tabs off the control. This “free” conversion happens due to the fact that the `Convert()` method is called again, after a call to `ConvertBack()`. If you were simply to return `null` from `ConvertBack()`, your binding would appear to be out of sync because the text box would still be displaying a floating-point number!

Establishing Data Bindings in Code

With this class in place, you are ready to register your custom converter with any control that wishes to use it. You could accomplish this exclusively in XAML; however, to do so, you would need to define some custom object resources, which you will not learn how to do until the next chapter. For now, you can register your data conversion class in code. Begin by cleaning up the current definition of the `<Label>` control in your data binding tab, so that it no longer uses the `{Binding}` markup extension:

```
<Label x:Name="labelSBThumb" Height="30" BorderBrush="Blue"
       BorderThickness="2" Content = "0"/>
```

In your window’s constructor, call a new private helper function called `SetBindings()`. In this method, add the following code:

```

private void SetBindings()
{
    // Create a Binding object.
    Binding b = new Binding();

    // Register the converter, source and path.
    b.Converter = new MyDoubleConverter();
    b.Source = this.mySB;
    b.Path = new PropertyPath("Value");

    // Call the SetBinding method on the Label.
    this.labelSBThumb.SetBinding(Label.ContentProperty, b);
}

```

The only part of this function that probably looks a bit off is the call to `SetBinding()`. Notice that the first parameter calls a static, read-only field of the `Label` class named `ContentProperty`.

As you will learn about in Chapter 31, you are specifying what is known as a *dependency property*. For the time being, just know that when you set bindings in code, the first argument will nearly always

require you to specify the name of the class that wants the binding (the `Label`, in this case), followed by a call to the underlying property with the `-Property` suffix (again, you'll learn more about this in Chapter 31). In any case, running the application illustrates that the `Label` only prints out whole numbers.

Building the DataGrid Tab

You have built an interesting example so far using nothing but Expression Blend. For the remainder of this project, however, you will use Visual Studio 2010, which will give you some firsthand experience regarding how Blend and Visual Studio can work hand-in-hand. So, save your project and close down Blend. Next, open the same project in Visual Studio 2010 using the `File > Open > Project/Solution...` menu option.

The previous data-binding example illustrated how to configure two (or more) controls to participate in a data-binding operation. While this is helpful, it is also possible to bind data from XML files, database data, and in-memory objects. To complete this example, you will design the final tab of your tab control, so it displays data obtained from the `Inventory` table of the AutoLot database.

As with the other tabs, you begin by changing the current `Grid` to a `StackPanel`. Do this by directly updating the XAML using Visual Studio. Now define a `DataGrid` control in your new `StackPanel` named `gridInventory`:

```
<TabItem x:Name="tabDataGrid" Header="DataGrid">
  <StackPanel>
    <DataGrid x:Name="gridInventory" Height="288"/>
  </StackPanel>
</TabItem>
```

Next, reference the `AutoLotDAL.dll` assembly you created in Chapter 23 (where you used the Entity Framework), as well as `System.Data.Entity.dll`. You will use the Entity Framework, so you need to ensure that your project has the required connection string data in an `App.config` file. You should probably begin by copying the `App.config` file from your `AutoLotEDM_GUI` project from Chapter 23 into this project using the `Project > Add Existing Item` menu option.

Open the code file for your window and add a final helper function called `ConfigureGrid()`; make sure you call this from your constructor. Assuming that you did import the `AutoLotDAL` namespace, all you need to do is add a few lines of code:

```
private void ConfigureGrid()
{
  using (AutoLotEntities context = new AutoLotEntities())
  {
    // Build a LINQ query that gets back some data from the Inventory table.
    var dataToShow = from c in context.Inventories
                    select new { c.CarID, c.Make, c.Color, c.PetName };
    this.gridInventory.ItemsSource = dataToShow;
  }
}
```

Notice that you do not directly bind `context.Inventories` to the grid's `ItemsSource` collection; instead, you build a LINQ query that appears to ask for the same data in the entities. The reason for this approach: The `Inventory` object set *also* contains additional EF properties that would appear on the grid, but which don't map to the physical database.

If we were to run the project as-is, you would see an extremely plain grid. To make the grid a bit less of an eye sore, use the Visual Studio 2010 Properties window to edit the Rows category of the DataGrid. At a minimum, set the AlternationCount property to 2 and pick a custom brush using the integrated editor for the AlternatingRowBackground and RowBackground properties (see Figure 28-47 for some possible values).




Figure 28-47. Applying some eye candy to the grid

You can see the final tab for this example in Figure 28-48.




Figure 28-48. The final tab of your project

To be sure, you can configure the WPF `DataGridView` in a huge number of ways, so you'll want to consult the .NET Framework 4.0 SDK for details. For example, you can build custom *data templates* for the `DataGridView` using WPF graphical types; this enables you to provide an extremely rich UI.

That wraps up the current example. You'll use some other controls in later chapters; at this point, however, you should feel comfortable with the process of building UIs with Blend, Visual Studio 2010, and manually using XAML and C# code.

Source Code You can find the `WpfControlsAndAPIs` project under the Chapter 28 subdirectory.

Summary

This chapter examined several aspects of WPF controls, beginning with an overview of the control toolkit and the role of layout managers (panels). The first example gave you a chance to build a simple word processor application that illustrated the integrated spell-checking functionality of WPF, as well as how to build a main window with menu systems, status bars, and tool bars.

More importantly, you examined how to use WPF commands. Recall that you can attach these control-agnostic events to a UI element or an input gesture to inherit out-of-the-box services automatically (e.g., clipboard operations).

You also learned quite a bit about Microsoft Expression Blend. Specifically, you built a complex user interface using numerous aspects of the tool, and you learned about the WPF Ink and Document APIs at the same time. You also received an introduction to WPF data binding operations, including how to use the .NET 4.0 `DataGridView` class to display data from your custom AutoLot database.



WPF Graphics Rendering Services

In this chapter we'll examine the graphical rendering capabilities of Windows Presentation Foundation (WPF). As you'll see, WPF provides three separate ways to render graphical data—shapes, drawings and visuals. Once you understand the pros and cons of each approach, you will start learning about the world of interactive 2D graphics using the classes within `System.Windows.Shapes`. After this, you'll see how drawings and geometries allow you to render 2D data in a more lightweight manner. And last but not least, you'll learn how the visual layer gives you the greatest level of power and performance.

Along the way, you will explore a number of related topics, such as the creation of custom brushes and pens, how to apply graphical transformations to your renderings, and how to perform hit-test operations. In particular, you'll see how the integrated tools of Visual Studio 2010, Expression Blend and Expression Design, can help simplify your graphical coding endeavors.

Note Graphics are a key aspect of WPF development. Even if you are not building a graphics-heavy application (such as a video game or multimedia application), the topics in this chapter are critical when you work with services such as control templates, animations, and data binding customization.

Understanding WPF's Graphical Rendering Services

WPF uses a particular flavor of graphical rendering that goes by the term *retained-mode graphics*. Simply put, this means that as you are using XAML or procedural code to generate graphical renderings, it is the responsibility of WPF to persist these visual items and ensure they are correctly redrawn and refreshed in an optimal manner. Thus, when you render graphical data, it is always present, even when the end user hides the image by resizing or minimizing the window, by covering the window with another, and so forth.

In stark contrast, previous Microsoft graphical rendering APIs (including Windows Form's GDI+) were *immediate-mode* graphical systems. In this model, it was up to the programmer to ensure that rendered visuals were correctly “remembered” and updated during the life of the application. For example, in a Windows Forms application, rendering a shape such as a rectangle involves handling the `Paint` event (or overriding the virtual `OnPaint()` method), obtaining a `Graphics` object to draw the rectangle and, most important, adding the infrastructure to ensure that the image was persisted when

the user resized the window (for example, creating member variables to represent the position of the rectangle and calling `Invalidate()` throughout your program).

The shift from immediate-mode to retained-mode graphics is indeed a good thing, as programmers have far less grungy graphics code to author and maintain. However, I'm not suggesting that the WPF graphics API is *completely* different from earlier rendering toolkits. For example, like GDI+, WPF supports various brush types and pen objects, techniques for hit-testing, clipping regions, graphical transformations, and so on. So, if you currently have a background in GDI+ (or C/C++-based GDI), you already know a good deal about how to perform basic renderings under WPF.

WPF Graphical Rendering Options

As with other aspects of WPF development, you have a number of choices regarding how to perform your graphical rendering, beyond the decision to do so via XAML or procedural C# code (or perhaps a combination of both). Specifically, WPF provides three distinct ways to render graphical data:

- **Shapes:** WPF provides the `System.Windows.Shapes` namespace, which defines a small number of classes for rendering 2D geometric objects (rectangles, ellipses, polygons, etc.). While these types are very simple to use, and very powerful, they do come with a fair amount of memory overhead if used with reckless abandon.
- **Drawings and Geometries:** The WPF API provides a second way to render graphical data, using descendants from the `System.Windows.Media.Drawing` abstract class. Using classes such as `GeometryDrawing` or `ImageDrawing` (in addition to various *geometry objects*) you can render graphical data in a more lightweight (but less feature-rich) manner.
- **Visuals:** The fastest and most lightweight way to render graphical data under WPF is using the visual layer, which is accessible only through C# code. Using descendants of `System.Windows.Media.Visual`, you can speak directly to the WPF graphical subsystem.

The reason for offering different ways to do the exact same thing (i.e., render graphical data) has to do with memory use and ultimately application performance. Because WPF is such a graphically intensive system, it is not unreasonable for an application to render hundreds or even thousands of different images on a window's surface, and the choice of implementation (shapes, drawings, or visuals) could have a huge impact.

Do understand that when you build a WPF application, chances are good you'll use all three options. As a rule of thumb, if you need a modest amount of *interactive* graphical data that can be manipulated by the user (receive mouse input, display tooltips, etc), you'll want to use members in the `System.Windows.Shapes` namespace.

In contrast, drawings and geometries are more appropriate when you need to model complex, generally non-interactive, vector-based graphical data using XAML or C#. While drawings and geometries can still respond to mouse events, hit-testing, and drag-and-drop operations, you will typically need to author more code to do so.

Last but not least, if you require the fastest possible way to render massive amounts of graphical data, the visual layer is the way to go. For example, let's say you are using WPF to build a scientific application that can plot out thousands of points of data. Using the visual layer, you can render the plot points in the most optimal way possible. As you will see later in this chapter, the visual layer is only accessible via C# code, and is not XAML-friendly.

No matter which approach you take (shapes, drawings and geometries, or visuals) you will make use of common graphical primitives such as brushes (which fill interiors), pens (which draw exteriors) and transformation objects (which, well, transform the data). To begin the journey, we will begin working with the classes of `System.Windows.Shapes`.

Note WPF also ships with a full-blown API that can be used to render and manipulate 3D graphics, which is not addressed in this edition of the text. Please consult the .NET Framework 4.0 SDK documentation if you are interested in incorporating 3D graphics in your applications.

Rendering Graphical Data Using Shapes

Members of the `System.Windows.Shapes` namespace provide the most straightforward, most interactive, yet most memory-intensive way to render a two-dimensional image. This namespace (defined in the `PresentationFramework.dll` assembly) is quite small and consists of only six sealed classes that extend the abstract `Shape` base class: `Ellipse`, `Rectangle`, `Line`, `Polygon`, `Polyline`, and `Path`.

Create a new WPF Application named `RenderingWithShapes`. Now, if you locate the abstract `Shape` class in the Visual Studio 2010 object browser (see Figure 29-1) and expand each of the parent nodes, you can see that each descendent of `Shape` receives a great deal of functionality up the inheritance chain.




Figure 29-1. The `Shape` base class receives a good deal of functionality from its parent classes

Now, given your work in the previous two chapters, some of these parent classes may ring a bell. Recall, for example, that `UIElement` defines numerous methods to receive mouse input and deal with drag-and-drop events, while `FrameworkElement` defines members to deal with sizing, tooltips, mouse cursors, and whatnot. Given this inheritance chain, be aware that when you render graphical data using `Shape` derived classes, the objects are just about as functional (as far as user interactivity is concerned) as a WPF control!

For example, determining if the user has clicked on your rendered image is no more complicated than handling the `MouseDown` event. By way of a simple example, if you authored the following XAML of a `Rectangle` object:

```
<Rectangle x:Name="myRect" Height="30" Width="30"
           Fill="Green" MouseDown="myRect_MouseDown"/>
```

you could implement a C# event handler for the `MouseDown` event that changes the rectangle's background color when clicked:

```
private void myRect_MouseDown(object sender, MouseButtonEventArgs e)
{
    // Change color of Rectangle when clicked.
    myRect.Fill = Brushes.Pink;
}
```

Unlike with other graphical toolkits you may have used, you do *not* need to author a ton of infrastructure code that manually maps mouse coordinates to the geometry, manually calculates hit-testing, renders to an off-screen buffer, and so forth. The members of `System.Windows.Shapes` simply respond to the events you register with, just like a typical WPF control (`Button`, etc).

The downside of all this out-of-the-box functionality is that the shapes do take up a fair amount of memory. Again, if you're building a scientific application that plots thousands of points on the screen, using shapes would be a poor choice (essentially, it would be about as memory-intensive as rendering thousands of `Button` objects!). However, when you need to generate an interactive 2D vector image, shapes are a wonderful choice.

Beyond the functionality inherited from the `UIElement` and `FrameworkElement` parent classes, `Shape` defines a number of members for each of the children; some of the more useful ones are shown in Table 29-1.

Table 29-1. Key Properties of the `Shape` Base Class

Properties	Meaning in Life
<code>DefiningGeometry</code>	Returns a <code>Geometry</code> object that represents the overall dimensions of the current shape. This object <i>only</i> contains the plot points that are used to render the data, and has no trace of the functionality from <code>UIElement</code> or <code>FrameworkElement</code> .
<code>Fill</code>	Allows you to specify a “brush object” to render the interior portion of a shape.
<code>GeometryTransform</code>	Allows you to apply transformations to a shape, <i>before</i> it is rendered on the screen. The inherited <code>RenderTransform</code> property (from <code>UIElement</code>) applies the transformation <i>after</i> it has been rendered on the screen.

Table 29-1. Key Properties of the Shape Base Class (continued)

Properties	Meaning in Life
Stretch	Describes how to fill a shape within its allocated space, such as its position within a layout manager. This is controlled using the corresponding System.Windows.Media.Stretch enumeration.
Stroke	Defines a brush object, or in some cases, a pen object (which is really a brush in disguise) that is used to paint the border of a shape.
StrokeDashArray, StrokeEndLineCap, StrokeStartLineCap StrokeThickness	These (and other) stroke-related properties control how lines are configured when drawing the border of a shape. In a majority of cases, these properties will configure the brush used to draw a border or line.

■ **Note** If you forget to set the Fill and Stroke properties, WPF will give you “invisible” brushes and therefore the shape will not be visible on the screen!

Adding Rectangles, Ellipses, and Lines to a Canvas

Later in this chapter, you will learn to use Expression Blend and Expression Design to generate XAML descriptions of graphical data. For now, we will build a WPF application that can render shapes using XAML and C#, and while doing so, learn a bit about the process of hit-testing. First of all, update the initial XAML of the <Window> to define a <DockPanel>, containing a (now empty) <ToolBar> and a <Canvas>. Note that we have given each contained item a fitting name via the Name property.

```
<DockPanel LastChildFill="True">
  <ToolBar DockPanel.Dock="Top" Name="mainToolBar" Height="50">
    </ToolBar>
    <Canvas Background="LightBlue" Name="canvasDrawingArea"/>
</DockPanel>
```

Now, populate the <ToolBar> with a set of <RadioButton> objects, each of which contains a specific Shape derived class as content. Notice that each <RadioButton> is assigned to the same GroupName (to ensure mutual exclusivity) and is also given a fitting name:

```
<ToolBar DockPanel.Dock="Top" Name="mainToolBar" Height="50">
  <RadioButton Name="circleOption" GroupName="shapeSelection">
    <Ellipse Fill="Green" Height="35" Width="35" />
  </RadioButton>

  <RadioButton Name="rectOption" GroupName="shapeSelection">
    <Rectangle Fill="Red" Height="35"
      Width="35" RadiusY="10" RadiusX="10" />
  </RadioButton>
```

```

</RadioButton>

<RadioButton Name="lineOption" GroupName="shapeSelection">
    <Line Height="35" Width="35"
        StrokeThickness="10" Stroke="Blue"
        X1="10" Y1="10" Y2="25" X2="25"
        StrokeStartLineCap="Triangle" StrokeEndLineCap="Round" />
</RadioButton>
</ToolBar>

```

As you can see, declaring Rectangle, Ellipse, and Line objects in XAML is quite straightforward and requires little comment. Recall that the *Fill* property is used to specify a *brush* to paint the interior of a shape. When you require a solid-colored brush, you can simply specify a hard-coded string of known values and the underlying type converter (see Chapter 28) will generate the correct object. One interesting feature of the Rectangle type is that it defines RadiusX and RadiusY properties to allow you to render curved corners if you require.

Line represents its starting and end points using the X1, X2, Y1, and Y2 properties (given that *height* and *width* make little sense when describing a line). Here we are setting up a few additional properties that control how to render the starting and ending points of the Line, as well as how to configure the stroke settings. Figure 29-2 shows the rendered toolbar, as seen through the Visual Studio 2010 WPF designer:



Figure 29-2. Using Shapes as content for a set of RadioButtons

Now, using the Properties window of Visual Studio 2010, handle the *MouseLeftButtonDown* event for the Canvas, and the *Click* event for each RadioButton. In your C# file, your goal is to render the selected shape (a circle, square, or line) when the user clicks within the Canvas. First, define the following nested enum (and corresponding member variable) within your Window derived class:

```

public partial class MainWindow : Window
{
    private enum SelectedShape
    { Circle, Rectangle, Line }

    private SelectedShape currentShape;
    ...
}

```

Within each Click event handler, set the currentShape member variable to the correct SelectedShape value. For example, here is the implementation code for the Click event of the circleOption RadioButton. Implement the remaining two Click handlers in a similar manner:

```
private void circleOption_Click(object sender, RoutedEventArgs e)
{
    currentShape = SelectedShape.Circle;
}
```

With the MouseLeftButtonDown event handler of the Canvas, you will render out the correct shape (of a predefined size), using the X,Y position of the mouse cursor as a starting point. Here is the complete implementation, with analysis to follow:

```
private void canvasDrawingArea_MouseLeftButtonDown(object sender, MouseButtonEventArgs e)
{
    Shape shapeToRender = null;

    // configure the correct shape to draw.
    switch (currentShape)
    {
        case SelectedShape.Circle:
            shapeToRender = new Ellipse() { Fill = Brushes.Green, Height = 35, Width = 35 };
            break;
        case SelectedShape.Rectangle:
            shapeToRender = new Rectangle()
            { Fill = Brushes.Red, Height = 35, Width = 35, RadiusX = 10, RadiusY = 10 };
            break;
        case SelectedShape.Line:
            shapeToRender = new Line()
            {
                Stroke = Brushes.Blue,
                StrokeThickness = 10,
                X1 = 0, X2 = 50, Y1 = 0, Y2 = 50,
                StrokeStartLineCap= PenLineCap.Triangle,
                StrokeEndLineCap = PenLineCap.Round
            };
            break;
        default:
            return;
    }

    // Set top / left position to draw in the canvas.
    Canvas.SetLeft(shapeToRender, e.GetPosition(canvasDrawingArea).X);
    Canvas.SetTop(shapeToRender, e.GetPosition(canvasDrawingArea).Y);

    // Draw shape!
    canvasDrawingArea.Children.Add(shapeToRender);
}
```

■ **Note** You may notice that the Ellipse, Rectangle, and Line objects being created in this method have the same property settings as the corresponding XAML definitions! As you might hope, we can streamline this code—but that requires an understanding of the WPF object resources, which we will examine in Chapter 30.

As you can see, we are testing the currentShape member variable to create the correct Shape derived object. After this point, we set the top-left value within the Canvas using the incoming MouseButtonEventArgs. Last but not least, we add the new Shape derived type to the collection of UIElement objects maintained by the Canvas. If you run your program now, you should be able to click anywhere in the canvas and see the selected shape rendered at the location of the left mouse-click.

Removing Rectangles, Ellipses, and Lines from a Canvas

With the Canvas maintaining a collection of objects, you may wonder how you can dynamically remove an item, perhaps in response to the user right-clicking on a shape. You can certainly do this, using a class in the System.Windows.Media namespace called the VisualTreeHelper. In Chapter 31, you will come to know the role of “visual trees” and “logical trees” in some detail. Until then, handle the MouseRightButtonDown event on your Canvas object, and implement the corresponding event handler like so:

```
private void canvasDrawingArea_MouseRightButtonDown(object sender, MouseButtonEventArgs e)
{
    // First, get the X,Y location of where the user clicked.
    Point pt = e.GetPosition((Canvas)sender);

    // Use the HitTest() method of VisualTreeHelper to see if the user clicked
    // on an item in the canvas.
    HitTestResult result = VisualTreeHelper.HitTest(canvasDrawingArea, pt);

    // If the result is not null, they DID click on a shape!
    if (result != null)
    {
        // Get the underlying shape clicked on, and remove it from
        // the canvas.
        canvasDrawingArea.Children.Remove(result.VisualHit as Shape);
    }
}
```

This method begins by obtaining the exact X,Y location the user clicked in the Canvas, and performs a hit-test operation via the static VisualTreeHelper.HitTest() method. The return value, a HitTestResult object, will be set to null if the user does not click on a UIElement within the Canvas. If HitTestResult is *not* null, we can obtain the underlying UIElement that was clicked via the VisualHit property, which we are casting into a Shape derived object (remember, a Canvas can hold any UIElement, not just shapes!) Again, you’ll get more details on exactly what a “visual tree” is in the next chapter.

Note By default, `VisualTreeHelper.HitTest()` returns the top-most `UIElement` clicked on, and does not provide information on other objects below that item (e.g., objects overlapping by Z-order).

With this modification, you should be able to add a shape to the canvas with a left mouse-click, and delete an item from the canvas with a right mouse-click! Figure 29-3 shows the functionality of the current example:




Figure 29-3. Fun with shapes

So far so good. At this point, you have used `Shape` derived objects to render content on `RadioButtons` using XAML and populate a `Canvas` using C#. We will add a bit more functionality to this example when we examine the role of brushes and graphical transformations. On a related note, a different example in this chapter will illustrate drag-and-drop techniques on `UIElement` objects. Until then, we will examine the remaining members of `System.Windows.Shapes`.

Working with Polylines and Polygons

The current example used only three of the `Shape` derived classes. The remaining child classes (`Polyline`, `Polygon`, and `Path`) are extremely tedious to render correctly without the use of a tool like Expression Blend, simply because they require a large number of plot points to represent their output. You'll use Blend in just a moment, but until then, here is an overview of the remaining `Shapes` types.

The `Polyline` type lets you define a collection of (x, y) coordinates (via the `Points` property) to draw a series of line segments that do not require connecting ends. The `Polygon` type is similar; however, it is programmed so that it will always close the starting and ending points and fill the interior with the specified brush. Assume you have authored the following `<StackPanel>` in the kaxaml editor, or better yet, in the custom XAML editor you created in Chapter 27:

```
<!-- Polylines do not automatically connect the ends -->
```

```
<Polyline Stroke ="Red" StrokeThickness ="20" StrokeLineJoin ="Round"
    Points ="10,10  40,40  10,90  300,50"/>
<!-- A Polygon always closes the end points-->
<Polygon Fill ="AliceBlue" StrokeThickness ="5" Stroke ="Green"
    Points ="40,10 70,80 10,50" />
```

Figure 29-4 shows the rendered output.



Figure 29-4. Polygons and polylines

Working with Paths

Using the Rectangle, Ellipse, Polygon, Polyline, and Line types alone to draw a detailed 2Dvector image would be extremely complex, as these primitives do not allow you to easily capture graphical data such as curves, unions of overlapping data, and so forth. The final Shape derived class, Path, provides the ability to define complex 2D graphical data represented as a collection of independent *geometries*. Once you have defined a collection of such geometries, you can assign them to the Data property of the Path class, where this information will be used to render your complex 2D image.

The Data property takes a System.Windows.Media.Geometry derived class, which contains the key members described in Table 29-2.

Table 29-2. Select Members of the System.Windows.Media.Geometry Type

Member	Meaning in Life
Bounds	Establishes the current bounding rectangle containing the geometry.
FillContains()	Determines if a given Point (or other Geometry object) is within the bounds of a particular Geometry-derived class. This is useful for hit-testing calculations.
GetArea()	Returns the entire area a Geometry-derived type occupies.
GetRenderBounds()	Returns a Rect that contains the smallest possible rectangle that could be used to render the Geometry-derived class.
Transform	Assigns a Transform object to the geometry to alter the rendering.

The classes that extend `Geometry` (see Table 29-3) look very much like their `Shape`-derived counterparts. For example, `EllipseGeometry` has similar members to `Ellipse`. The big distinction is that `Geometry` derived classes *do not know* how to render themselves directly, as they are not `UIElements`. Rather, `Geometry` derived classes represent little more than a collection of plot-point data, which say in effect “If a `Path` uses my data, this is how I would render myself.”

Note `Path` is not the only class in WPF that can use a collection of geometries. For example, `DoubleAnimationUsingPath`, `DrawingGroup`, `GeometryDrawing` and even `UIElement` can all use geometries for rendering, using the `PathGeometry`, `ClipGeometry`, `Geometry`, and `Clip` properties, respectively.

Table 29-3. Geometry Derived Classes

Geometry Class	Meaning in Life
<code>LineGeometry</code>	Represents a straight line.
<code>RectangleGeometry</code>	Represents a rectangle.
<code>EllipseGeometry</code>	Represents an ellipse.
<code>GeometryGroup</code>	Allows you to group together several <code>Geometry</code> objects.
<code>CombinedGeometry</code>	Allows you to merge two different <code>Geometry</code> objects into a single shape.
<code>PathGeometry</code>	Represents a figure composed of lines and curves.

Here is a `Path` defined in kaxaml that makes use of a few `Geometry`-derived types. Notice that we are setting the `Data` property of `Path` to a `GeometryGroup` object that contains other `Geometry`-derived objects such as `EllipseGeometry`, `RectangleGeometry`, and `LineGeometry`. Figure 29-5 shows the output.

```
<!--A Path contains a set of geometry objects,
set with the Data property -->
<Path Fill = "Orange" Stroke = "Blue" StrokeThickness = "3">
  <Path.Data>
    <GeometryGroup>
      <EllipseGeometry Center = "75,70"
        RadiusX = "30" RadiusY = "30" />
      <RectangleGeometry Rect = "25,55 100 30" />
      <LineGeometry StartPoint="0,0" EndPoint="70,30" />
      <LineGeometry StartPoint="70,30" EndPoint="0,30" />
    </GeometryGroup>
  </Path.Data>
</Path>
```




Figure 29-5. A Path containing various Geometries objects

The image in Figure 29-5 could have been rendered using the Line, Ellipse, and Rectangle classes shown earlier. However, this would have put various UIElement objects in memory. When you use geometries to model the plot points of what to draw, and then place the geometry collection into a container that can render the data (Path, in this case), you reduce the memory overhead.

Now recall that Path has the same inheritance chain as any other member of System.Windows.Shapes, and therefore has the ability to send the same event notifications as other UIElements. Thus, if you were to define this same <Path> element in a Visual Studio 2010 project, you could determine if the user clicked anywhere in the sweeping line simply by handling a mouse event (remember, kaxaml does not allow you to handle events for the markup you have authored).

The Path "Modeling Mini Language"

Of all the classes listed in Table 29-2, PathGeometry is the most complex to configure in terms of XAML or code. This has to do with the fact that each *segment* of the PathGeometry is composed of objects that contain various segments and figures (for example, ArcSegment, BezierSegment, LineSegment, PolyBezierSegment, PolyLineSegment, PolyQuadraticBezierSegment, etc). Here is an example of a Path object whose Data property has been set to a <PathGeometry> composed of various figures and segments.

```
<Path Stroke="Black" StrokeThickness="1" >
  <Path.Data>
    <PathGeometry>
      <PathGeometry.Figures>
        <PathFigure StartPoint="10,50">
          <PathFigure.Segments>
            <BezierSegment
              Point1="100,0"
              Point2="200,200"
              Point3="300,100"/>
            <LineSegment Point="400,100" />
            <ArcSegment
              Size="50,50" RotationAngle="45"
              IsLargeArc="True" SweepDirection="Clockwise"
              Point="200,100"/>
          </PathFigure.Segments>
        </PathFigure>
      </PathGeometry.Figures>
    </PathGeometry>
  </Path.Data>
</Path>
```

Now, to be perfectly honest, very few programmers will ever need to manually build complex 2D images by directly describing Geometry or PathSegment derived classes. In reality, complex paths will be composed on your behalf when you are working with Expression Blend or Expression Design.

Even with the assistance of these tools, the amount of XAML required to define a complex Path object would be ghastly, as the data consists of full descriptions of various Geometry or PathSegment derived classes. In order to produce more concise and compact markup, the Path class has been designed to understand a specialized “mini-language.”

For example, rather than setting the Data property of Path to a collection of Geometry and PathSegment derived types, you can set the Data property to a single string literal containing a number of known symbols and various values that define the shape to be rendered. In fact, when you use the Expression tools to build a Path object, the mini-language is used automatically. Here is a simple example, and the resulting output (see Figure 29-6).

```
<Path Stroke="Black" StrokeThickness="3"
      Data="M 10,75 C 70,15 250,270 300,175 H 240" />
```




Figure 29-6. The path mini-language allows you to compactly describe a Geometry/PathSegment object model

The M command (short for *move*) takes an X,Y position that represents the starting point of the drawing. The C command takes a series of plot points to render a curve (a cubic Bézier curve to be exact) while H draws a horizontal line.

Now, to be perfectly honest, the chances that you will ever need to manually build or parse a string literal containing path mini-language instructions are slim to none. However, at the very least, you will no longer be surprised when you view XAML generated by Expression Blend. If you are interested in examining the details of this particular grammar, look up “Path Markup Syntax” in the .NET Framework 4.0 SDK documentation.

WPF Brushes and Pens

Each of the WPF graphical rendering options (shape, drawing and geometries, and visuals) makes extensive use of *brushes*, which allow you to control how the interior of a 2D surface is filled. WPF provides six different brush types, all of which extend `System.Windows.Media.Brush`. While `Brush` is abstract, the descendants described in Table 29-4 can be used to fill a region with just about any conceivable option.

Table 29-4. WPF Brush-Derived Types

Brush Type	Meaning in Life
DrawingBrush	Paints an area with a Drawing derived object (GeometryDrawing, ImageDrawing, or VideoDrawing)
ImageBrush	Paints an area with an image (represented by an ImageSource object)
LinearGradientBrush	Paints an area with a linear gradient
RadialGradientBrush	Paints an area with a radial gradient
SolidColorBrush	Paints a single color, set with the Color property
VisualBrush	Paints an area with a Visual derived object (DrawingVisual, Viewport3DVisual, and ContainerVisual)

The `DrawingBrush` and `VisualBrush` classes allow you to build a brush based on an existing `Drawing` or `Visual` derived class. These brush classes are used when you are working with the other two graphical options of WPF (drawings or visuals) and will be examined later in this chapter.

`ImageBrush`, as the name suggests, lets you build a brush that displays image data from an external file or embedded application resource, by setting the `ImageSource` property. The remaining brush types (`LinearGradientBrush` and `RadialGradientBrush`) are quite straightforward to use, though typing in the required XAML can be a tad verbose. Thankfully, Visual Studio 2010 supports integrated brush editors that make it simple to generate stylized brushes.

Configuring Brushes Using Visual Studio 2010

Let's update our WPF drawing program, `RenderingWithShapes` to use some more interesting brushes. The three shapes we've employed so far to render data on our toolbar use simple, solid colors, so we can capture their values using simple string literals. To spice things up a tad, we will now use the integrated brush editor. Ensure that the XAML editor of your initial window is the open window within the IDE, and select the `Ellipse` element. Now, locate the `Fill` property in the Properties window, and click the drop-down list. You should now see the following brush editor (Figure 29-7).




Figure 29-7. Any property that requires a brush can be configured with the integrated brush editor

As you can see, this editor contains four slider controls, which allow you to set the ARGB (alpha, red, green and blue, where “alpha” controls transparency) of the current brush. Using these sliders and the related color selection area, you can create any sort of solid color. Go ahead and use these tools to change the color of your Ellipse, and view the resulting XAML. You’ll notice the color is stored as a hexadecimal value, for example:

```
<Ellipse Fill="#FF47CE47" Height="35" Width="35" />
```

More interestingly, this same editor allows you to configure gradient brushes, which are used to define a series of colors and transition points. On the upper-left of the brush editor, you will see four small buttons, the first of which lets you set a *null brush* for no rendered output. The other three allow you to set up a solid color brush (what we just examined), gradient brush, or image brush.

Click the gradient brush button and the editor will display a few new options (see Figure 29-8). The three buttons on the lower left allow you to pick a vertical, horizontal, or radial gradient. The bottom-most strip will show you the current color of each gradient stop, each of which is marked by a “thumb” on the strip. As you drag these thumbs around the gradient strip, you can control the gradient offset. Furthermore, when you click on a given thumb, you can change the color for that particular gradient stop via the color selector. Finally, if you click directly on the gradient strip, you can add additional gradient stops.

Take a few minutes to play around this editor to build a radial gradient brush containing three gradient stops, set to your colors of choice. Figure 29-8 shows the brush I just constructed, using three different shades of green.




Figure 29-8. The Visual Studio brush editor allows you to build basic gradient brushes

Once you are done, the IDE will update your XAML with a custom brush set to a brush-compatible property (the Fill property of the Ellipse in our example) using property-element syntax. For example:

```
<Ellipse Height="35" Width="35">
  <Ellipse.Fill>
    <RadialGradientBrush>
      <GradientStop Color="#FF87E71B" Offset="0.589" />
      <GradientStop Color="#FF2BA92B" Offset="0.013" />
      <GradientStop Color="#FF34B71B" Offset="1" />
    </RadialGradientBrush>
  </Ellipse.Fill>
</Ellipse>
```

Configuring Brushes in Code

Now that we have built a custom brush for the XAML definition of our Ellipse, the corresponding C# code is out of date, in that it will still render a solid green circle. To sync things back up, update the correct case statement to use the same brush you just created. Here is the necessary update, which looks more complex than you might expect, just because we are converting the hexadecimal value to a proper Color object via the System.Windows.Media.ColorConverter class (see Figure 29-9 for the modified output):

```
case SelectedShape.Circle:
  shapeToRender = new Ellipse() { Height = 35, Width = 35 };

  // Make a RadialGradientBrush in code!
  RadialGradientBrush brush = new RadialGradientBrush();
  brush.GradientStops.Add(new GradientStop(
```

```

        (Color)ColorConverter.ConvertFromString("#FF87E71B"), 0.589));
brush.GradientStops.Add(new GradientStop(
    (Color)ColorConverter.ConvertFromString("#FF2BA92B"), 0.013));
brush.GradientStops.Add(new GradientStop(
    (Color)ColorConverter.ConvertFromString("#FF34B71B"), 1));

shapeToRender.Fill = brush;
break;

```




Figure 29-9. Drawing circles with a bit more pizzazz!

By the way, you can build `GradientStop` objects by specifying a simple color as the first constructor parameter using the `Colors` enumeration, which returns a configured `Color` object:

```
GradientStop g = new GradientStop(Colors.Aquamarine, 1);
```

Or, if you require even finer control, you can pass in a configured `Color` object. For example:

```
Color myColor = new Color() { R = 200, G = 100, B = 20, A = 40 };
GradientStop g = new GradientStop(myColor, 34);
```

Of course, the `Colors` enum and `Color` class are not limited to gradient brushes. You can use them anytime you need to represent a color value in code.

Configuring Pens

In comparison with brushes, a *pen* is an object for drawing borders of geometries, or in the case of the `Line` or `PolyLine` class, the line geometry itself. Specifically, the `Pen` class allows you to draw a specified thickness, represented by a `double` value. In addition, a `Pen` can be configured with the same sort of properties seen in the `Shape` class, such as starting and stopping pen caps, dot-dash patterns, and so forth. For example:

```
<Pen Thickness="10" LineJoin="Round" EndLineCap="Triangle" StartLineCap="Round" />
```

In many cases, you won't need to directly create a Pen object, as this will be done indirectly when you assign a value to properties, such as `StrokeThickness` to a `Shape` derived type (as well as other `UIElements`). However, building a custom Pen object is very handy when working with `Drawing` derived types (described later in the chapter). Visual Studio 2010 does not have a pen editor, *per se*, but it does allow you to configure all of the stroke-centric properties of a selected item using the Properties Window.

Applying Graphical Transformations

To wrap up our discussion of using shapes, let's address the topic of *transformations*. WPF ships with numerous classes that extend the `System.Windows.Media.Transform` abstract base class. Table 29-5 documents many of the key out-of-the-box `Transform` derived classes.

Table 29-5. Key Descendents of the `System.Windows.Media.Transform` Type

Type	Meaning in Life
<code>MatrixTransform</code>	Creates an arbitrary matrix transformation that is used to manipulate objects or coordinate systems in a 2D plane
<code>RotateTransform</code>	Rotates an object clockwise about a specified point in a 2D (x, y) coordinate system
<code>ScaleTransform</code>	Scales an object in the 2D (x, y) coordinate system
<code>SkewTransform</code>	Skews an object in the 2D (x, y) coordinate system
<code>TranslateTransform</code>	Translates (moves) an object in the 2-D x-y coordinate system.
<code>TransformGroup</code>	Represents a composite <code>Transform</code> composed of other <code>Transform</code> objects

Transformations can be applied to any `UIElement` (e.g., descendents of `Shape` as well as controls such as `Buttons`, `TextBoxes`, and the like). Using these transformation classes, you can render graphical data at a given angle, skew the image across a surface, and expand, shrink, or flip the target item in a variety of ways.

■ **Note** While transformation objects can be used anywhere, you will find them most useful when working with WPF animations and custom control templates. As you will see later in the text, you can use WPF animations to incorporate visual cues to the end user for a custom control.

Transformation objects (or a whole set of them) can be assigned to a target object (`Button`, `Path`, etc.) using two common properties. The `LayoutTransform` property is helpful in that the transformation

occurs *before* elements are rendered into a layout manager, and therefore the transformation will not affect z-ordering operations (in other words, the transformed image data will not overlap).

The `RenderTransform` property, on the other hand, occurs after the items are in their container, and therefore it is quite possible that elements can be transformed in such a way that they could overlap each other, based on how they were arranged in the container.

A First Look at Transformations

We will add some transformational logic to our `RenderingWithShapes` project in just a moment. However, to see transformation objects in action, open `kaxaml` (or your custom XAML editor) and define a simple `<StackPanel>` in the root `<Page>` or `<Window>`, and set the `Orientation` property to `Horizontal`. Now, add the following `<Rectangle>`, which will be drawn at a 45-degree angle using a `RotateTransform` object.

```
<!-- A Rectangle with a rotate transformation -->
<Rectangle Height = "100" Width = "40" Fill = "Red">
    <Rectangle.LayoutTransform>
        <RotateTransform Angle = "45"/>
    </Rectangle.LayoutTransform>
</Rectangle>
```

Here is a `<Button>` that is skewed across the surface by 20 percent, using a `<SkewTransform>`:

```
<!-- A Button with a skew transformation -->
<Button Content = "Click Me!" Width="95" Height="40">
    <Button.LayoutTransform>
        <SkewTransform AngleX = "20" AngleY = "20"/>
    </Button.LayoutTransform>
</Button>
```

And for good measure, here is an `<Ellipse>` that is scaled by 20 percent with a `ScaleTransform`, (note the values set to the initial `Height` and `Width`), as well as a `<TextBox>` that has a group of transformation objects applied to it.

```
<!-- An Ellipse that has been scaled by 20% -->
<Ellipse Fill = "Blue" Width="5" Height="5">
    <Ellipse.LayoutTransform>
        <ScaleTransform ScaleX = "20" ScaleY = "20"/>
    </Ellipse.LayoutTransform>
</Ellipse>

<!-- A textbox that has been rotated and skewed -->
<TextBox Text = "Me Too!" Width="50" Height="40">
    <TextBox.LayoutTransform>
        <TransformGroup>
            <RotateTransform Angle = "45"/>
            <SkewTransform AngleX = "5" AngleY = "20"/>
        </TransformGroup>
    </TextBox.LayoutTransform>
</TextBox>
```

Note that when a transformation is applied, you are not required to perform any manual calculations to correctly respond to hit-testing, input focus, or whatnot. The WPF graphics engine handles such tasks on your behalf. For example, in Figure 29-10, you can see that the TextBox is still responsive to keyboard input.




Figure 29-10. The results of graphical transformation objects

Transforming our Canvas Data

Now, let's see how we can incorporate some transformational logic into our `RenderingWithShapes` example. In addition to applying a transformation object to a single item (Rectangle, TextBox, etc.), you can also apply transformation objects to a layout manager, to transform all of the internal data. You could, for example, render the entire `<DockPanel>` of the main window at an angle like so:

```
<DockPanel LastChildFill="True">
    <DockPanel.LayoutTransform>
        <RotateTransform Angle="45"/>
    </DockPanel.LayoutTransform>
    ...
</DockPanel>
```

This is a bit extreme for this example, so let's add a final (less aggressive) feature that allows the user to flip the entire Canvas and all contained graphics. Begin by adding a final `<ToggleButton>` to your `<ToolBar>`, defined as:

```
<ToggleButton Name="flipCanvas" Click="flipCanvas_Click" Content="Flip Canvas!"/>
```

Within the `Click` event handler, you create a `RotateTransform` object and connect it to the `Canvas` object via the `LayoutTransform` property if this new `ToggleButton` is clicked. If the `ToggleButton` is not clicked, you remove the transformation by setting the same property to `null`:

```
private void flipCanvas_Click(object sender, RoutedEventArgs e)
{
    if (flipCanvas.IsChecked == true)
    {
        RotateTransform rotate = new RotateTransform(-180);
        canvasDrawingArea.LayoutTransform = rotate;
    }
    else
    {
```

```

        canvasDrawingArea.LayoutTransform = null;
    }
}

```

Run your application and add a bunch of graphics throughout the canvas area. If you click your new button, you will find that the shape data flows outside of the boundaries of the canvas! This is because we have not defined a clipping region (see Figure 29-11).




Figure 29-11. Oops! Our data is flowing outside of the canvas after the transformation!

Fixing this is trivial. Rather than manually authoring complex clipping-logic code, simply set the `ClipToBounds` property of the `<Canvas>` to true, which prevents child elements from being rendered outside the parent's boundaries. If you run your program again, you'll find the data will not bleed off the canvas boundary.

```
<Canvas ClipToBounds = "True" ... >
```

The last tiny modification to make has to do with the fact that when you flip the canvas by pressing your toggle button, and then click on the canvas to draw a new shape, the point at which you click is *not* the point where the graphical data is applied. Rather the data is rendered above the mouse cursor.

To resolve this issue, check out the solution code for this example where I have added one final Boolean member variable (`isFlipped`), which will apply the same transformation object to the shape being drawn before the rendering occurs (via `RenderTransform`). Here is the crux of the code:

```

private void canvasDrawingArea_MouseLeftButtonDown(object sender, MouseButtonEventArgs e)
{
    Shape shapeToRender = null;
    ...

    // isFlipped is a private boolean field. This is toggled when the
    // toggle button is clicked.
    if (isFlipped)
    {
        RotateTransform rotate = new RotateTransform(-180);
        shapeToRender.RenderTransform = rotate;
    }
}

```

```

}

// Set top / left to draw in the canvas.
Canvas.SetLeft(shapeToRender, e.GetPosition(canvasDrawingArea).X);
Canvas.SetTop(shapeToRender, e.GetPosition(canvasDrawingArea).Y);

// Draw shape!
canvasDrawingArea.Children.Add(shapeToRender);
}

```

This wraps up our examination of `System.Windows.Shapes`, brushes, and transformations. Before turning our attention to the role of rendering graphics using drawings and geometries, let's see how Expression Blend can be used to simplify how we work with primitive graphics.

Source Code The `RenderingWithShapes` project can be found under the Chapter 29 subdirectory.

Working with Shapes using Expression Blend

Although Visual Studio 2010 does give you a few IDE tools that let you work with shapes, Expression Blend provides many more features, including a graphical transformation editor. If you'd like to try things out first hand, launch Expression Blend and create a new WPF application. (We are not going to do much beyond trying out a few features of the IDE, so you can name this project whatever you wish.)

Selecting a Shape to Render from the Tool Palette

Look at your tool palette and you'll see an area that lets you select an Ellipse, Rectangle, or Line (recall, you click-and-hold on buttons that have a small triangle on the lower-right to pop-up any available choices; see Figure 29-12).




Figure 29-12. Rendering basic shapes with Blend

Go ahead and draw a few overlapping shapes—you'll see why in just a moment. Now, locate the area of the Blend tool palette where you can select the Pen and Pencil tools, as shown in Figure 29-13.



Figure 29-13. Working with pens and pencils

The Pencil tool allows you to render completely free-form polygons, similar to a scribble program. The Pen tool is better suited for rendering swooping arcs or straight lines. To draw lines with the Pen, simply click at the desired starting point, then click at the desired ending point on the designer. Be aware that both of these tools will generate a Path definition, with the Data property set using the path mini language mentioned earlier.

Play around with these tools and render some new graphics on the designer. Note that if you perform a Direct Select on any Path (such as the Path created by the Pencil tool) you can tweak the overall connecting segments, as seen in Figure 29-14.




Figure 29-14. Editing a Path

Converting Shapes to Paths

When you use the Ellipse, Rectangle, or Line tools, the XAML will indeed use the `<Ellipse>`, `<Rectangle>` and `<Line>` elements. For example:

```
<Rectangle Stroke="Black" StrokeThickness="1" HorizontalAlignment="Left"
Margin="44,42,0,0" VerticalAlignment="Top" Width="137" Height="35"/>
```

If you right-click on one of these primitive types on your designer, you can select the Path-> Convert to Path menu option. When you select this operation, the original shape declaration is transformed into a Path containing a set of geometries, via the path mini language. Here is the previous <Rectangle> after conversion:

```
<Path Stretch="Fill" Stroke="Black" StrokeThickness="1" HorizontalAlignment="Left"
Margin="44,42,0,0" VerticalAlignment="Top" Width="137"
Height="35" Data="M0.5,0.5 L136.5,0.5 L136.5,34.5 L0.5,34.5 z"/>
```

While you might not need to convert a single shape into a Path containing geometries, it is common to combine multiple shapes into new paths.

Combining Shapes

Now try this. Select two or more shapes on the designer (via a mouse click-and-drag operation) and then right-click on the set of selected items. You'll see that you have a number of options under the Combine menu that allow you to generate new Path objects based on a set of selections and a combine operation (Figure 29-15).




Figure 29-15. Combining Paths to generate new Paths

Essentially, the options under the Combine menu are basic Venn diagramming operations. Try a few and then view the generated XAML (and remember, just as in Visual Studio 2010, Ctrl + z will undo the previous operation!)

The Brush and Transformation Editors

Like Visual Studio 2010, Blend supports a brush editor. When you select an item on the designer (such as one of your shapes), you can then go to the Brushes area of the Properties window. At the very top of the Brushes editor, you'll find all properties on the selected object that can be assigned a Brush type. Below, you'll find the same basic editing features you saw earlier in this chapter. Figure 29-16 shows one possible brush configuration.



Figure 29-16. The Blend brush editor

The only major difference between the Blend and Visual Studio 2010 brush editors is that with Blend you can remove a gradient stop by clicking on the offending thumb marker and dragging it off the gradient slider (literally anywhere off the gradient slider will do; right-clicking won't work!).

Another nice feature of the Blend brush editor is that when you have selected an item that makes use of a gradient brush, you can press the G key on your keyboard or click the Gradient Tool icon on the tool palette to change the origin of the gradient (Figure 29-17).




Figure 29-17. Changing the origin of a gradient

Finally, Blend also supports an integrated transformation editor. First, select a shape on your designer (of course, the transformation editor works for any item selected in the Objects and Timeline window). Now, on your Properties window, locate the Transform pane (Figure 29-18).




Figure 29-18. The Blend transformation editor

As you experiment with the transformation editor, be sure to take some time to examine the resulting XAML. Also note that many transformations can be applied directly on the designer, by hovering the mouse over a resizing node of the selected object. For example, if you place the mouse next to a node on the side of a selected item, you can apply a skew. (Personally speaking, however, I tend to use the transformation editor, rather than trying to get the mouse positioned just so.)

Note Recall that members of the `System.Windows.Shapes` namespace are `UIElements` and have numerous events you can respond to. Given this, you can handle events on your drawings using Blend, just as you would when handling an event for a typical control (see Chapter 29).

That wraps up our first look at the graphical rendering services of WPF and our whirlwind tour of using Blend to generate simple graphical data. While you could use this information to build a number of graphical applications, our next step is to examine the second way to render out graphical data, using drawings and geometries.

Rendering Graphical Data Using Drawings and Geometries

While the Shape types allow you to generate any sort of interactive two-dimensional surface, they entail quite a bit of memory overhead due to their rich inheritance chain. And though the Path class can help remove some of this overhead using contained geometries (rather than a large collection of other shapes), WPF provides a sophisticated drawing and geometry programming interface that renders even more lightweight 2D vector images.

The entry point into this API is the abstract `System.Windows.Media.Drawing` class (in `PresentationCore.dll`), which on its own does little more than define a bounding rectangle to hold the rendering. Notice in Figure 29-19, the inheritance chain of the Drawing class is significantly more lightweight than Shape, given that neither `UIElement` nor `FrameworkElement` is in the inheritance chain.




Figure 29-19. The Drawing class is more lightweight than Shape

WPF provides various classes that extend Drawing, each of which represents a particular way of drawing the content, as described in Table 29-5.

Table 29-5. WPF Drawing Derived Types

Type	Meaning in Life
<code>DrawingGroup</code>	Used to combine a collection of separate Drawing derived objects into a single composite rendering.
<code>GeometryDrawing</code>	Used to render 2D shapes in a very lightweight manner.
<code>GlyphRunDrawing</code>	Used to render textual data using WPF graphical rendering services.
<code>ImageDrawing</code>	Used to render an image file, or geometry set, into a bounding rectangle.

Table 29-5. WPF Drawing Derived Types (continued)

Type	Meaning in Life
VideoDrawing	Used to play an audio file or video file. This type can only be fully exploited using procedural code. If you wish to play videos via XAML, the MediaPlayer type is a better choice.

Because they are more lightweight, Drawing derived types do not have intrinsic support for handling input events as they are not UIElements or FrameworkElements (although it is possible to programmatically perform hit-testing logic); however, they can be animated due to the fact that they extend Animatable (Chapter 30 will examine the animation features of WPF).

Another key difference between Drawing derived types and Shape derived types is that Drawing derived types have no ability to render themselves, as they do not derive from UIElement! Rather, derived types must be placed within a hosting object (specifically, DrawingImage, DrawingBrush, or DrawingVisual) to display their content.

DrawingImage allows you to place drawing and geometries inside of a WPF Image control, which typically is used to display data from an external file. DrawingBrush allows you to build a brush based on a drawing and its geometries, in order to set a property that requires a brush. Finally, DrawingVisual is used only in the “visual” layer of graphical rendering, which is driven completely via C# code.

Although using drawings is a bit more complex than using simple shapes, this decoupling of graphical composition from graphical rendering makes the Drawing derived types much more lightweight than the Shape derived types, while still retaining key services.

Building a DrawingBrush using Geometries

Earlier in this chapter, we filled a Path with a group of geometries like so:

```
<Path Fill = "Orange" Stroke = "Blue" StrokeThickness = "3">
  <Path.Data>
    <GeometryGroup>
      <EllipseGeometry Center = "75,70"
        RadiusX = "30" RadiusY = "30" />
      <RectangleGeometry Rect = "25,55 100 30" />
      <LineGeometry StartPoint="0,0" EndPoint="70,30" />
      <LineGeometry StartPoint="70,30" EndPoint="0,30" />
    </GeometryGroup>
  </Path.Data>
</Path>
```

By doing this, we gain interactivity from Path but are still fairly lightweight given our geometries. However, if you want to render the same output and have no need for any (out-of-the-box) interactivity, you can place the same <GeometryGroup> inside a DrawingBrush, like this:

```
<DrawingBrush>
  <DrawingBrush.Drawing>
    <GeometryDrawing>
      <GeometryDrawing.Geometry>
        <GeometryGroup>
```

```

<EllipseGeometry Center = "75,70"
    RadiusX = "30" RadiusY = "30" />
<RectangleGeometry Rect = "25,55 100 30" />
<LineGeometry StartPoint="0,0" EndPoint="70,30" />
<LineGeometry StartPoint="70,30" EndPoint="0,30" />
</GeometryGroup>
</GeometryDrawing.Geometry>
<!-- A custom pen to draw the borders -->
<GeometryDrawing.Pen>
    <Pen Brush="Blue" Thickness="3"/>
</GeometryDrawing.Pen>
<!-- A custom brush to fill the interior -->
<GeometryDrawing.Brush>
    <SolidColorBrush Color="Orange"/>
</GeometryDrawing.Brush>
</GeometryDrawing>
</DrawingBrush.Drawing>
</DrawingBrush>

```

When you place a group of geometries into a `DrawingBrush`, you also need to establish the `Pen` object used to draw the boundaries, as we no longer inherit a `Stroke` property from the `Shape` base class. Here, I created a `<Pen>` with the same settings used in the `Stroke` and `StrokeThickness` values of the previous `Path` example.

Furthermore, since we no longer inherit a `Fill` property from `Shape`, we also need to use property element syntax to define a brush object to use for the `<DrawingGeometry>`, which here is a solid colored orange brush, just like the previous `Path` settings.

Painting with the DrawingBrush

Now that you have a `DrawingBrush`, you can use it to set the value of any property requiring a brush object. For example, if you are authoring this markup in kaxaml, you could use property-element syntax to paint your drawing over the entire surface of a `Page`:

```

<Page
    xmlns="http://schemas.microsoft.com/winfx/2006/xaml/presentation"
    xmlns:x="http://schemas.microsoft.com/winfx/2006/xaml">

    <Page.Background>
        <!-- Same DrawingBrush as seen above -->
        <DrawingBrush>
            ...
            </DrawingBrush>
        </Page.Background>
    </Page>

```

Or, you can use this `<DrawingBrush>` to set a different brush-compatible property, such as the `Background` property of a `Button`:

```

<Page
  xmlns="http://schemas.microsoft.com/winfx/2006/xaml/presentation"
  xmlns:x="http://schemas.microsoft.com/winfx/2006/xaml">

  <Button Height="100" Width="100">
    <Button.Background>
      <!-- Same DrawingBrush as seen above -->
      <DrawingBrush>
        ...
      </DrawingBrush>
    </Button.Background>
  </Button>

</Page>

```

No matter which brush-compatible property you set with your custom `<DrawingBrush>`, the bottom line is you are rendering a 2D vector image with much less overhead than the same 2D image rendered with shapes.

Containing Drawing Types in a DrawingImage

The `DrawingImage` type allows you to plug your drawing geometry into a WPF `<Image>` control. Consider the following:

```

<Page
  xmlns="http://schemas.microsoft.com/winfx/2006/xaml/presentation"
  xmlns:x="http://schemas.microsoft.com/winfx/2006/xaml">
  <Image Height="100" Width="100">
    <Image.Source>
      <DrawingImage>
        <DrawingImage.Drawing>
          <GeometryDrawing>
            <GeometryDrawing.Geometry>
              <GeometryGroup>
                <EllipseGeometry Center = "75,70"
                                  RadiusX = "30" RadiusY = "30" />
                <RectangleGeometry Rect = "25,55 100 30" />
                <LineGeometry StartPoint="0,0" EndPoint="70,30" />
                <LineGeometry StartPoint="70,30" EndPoint="0,30" />
              </GeometryGroup>
            </GeometryDrawing.Geometry>
          </GeometryDrawing>
        <!-- A custom pen to draw the borders -->
        <GeometryDrawing.Pen>
          <Pen Brush="Blue" Thickness="3"/>
        </GeometryDrawing.Pen>
        <!-- A custom brush to fill the interior -->
        <GeometryDrawing.Brush>

```

```

        <SolidColorBrush Color="Orange" />
    </GeometryDrawing.Brush>
    </GeometryDrawing>
    </DrawingImage.Drawing>
    </DrawingImage>
    </Image.Source>
</Image>
</Page>
```

In this case, our `<GeometryDrawing>` has been placed into a `<DrawingImage>`, rather than a `<DrawingBrush>`. Using this `<DrawingImage>`, we can set the `Source` property of the `Image` control.

Generating Complex Vector Graphics using Expression Design

To be sure, manually authoring XAML that represents a complex set of geometries, segments, figures, and paths would be a nightmare, and nobody would expect us to do so. As we have already seen, Expression Blend does contain a few IDE features that allow us to work with basic graphics; however when you need to generate professional, compelling vector graphics, Expression Design is the tool of champions.

Note If you do not have a copy of Expression Design, you can download a trial edition of the product from the official web site: <http://www.microsoft.com/expression>.

Expression Design has features similar to those you might find in a professional graphical design tool such as Adobe Photoshop or Adobe Illustrator. In the hands of a talented graphical artist, Design can be used to create very sophisticated 2D and 3D images, which can be exported in a variety of file formats—including XAML!

The ability to export a graphical image as XAML is very compelling, in that we (as programmers) can incorporate the markup into our applications, name objects, and manipulate them in code. For example, a graphical artist could use Design to create a 3D cube image. Once the image is exported to XAML, we could add the `x:Name` attribute to the items we wish to interact with, and gain access to the generated object in our C# codebase.

Exporting a Design Document to XAML

Now, in the spirit of full disclosure, I must admit that I am in no way, shape, or form, a graphical artist. Therefore, I am not going to walk through using Expression Design to render complex graphical data; rather we will view and manipulate some standard sample documents that ship with the product.

To begin, launch Expression Design and activate the Help ► Samples menu selection. In the resulting dialog box, double-click one of the sample drawings. For this example, I'll assume you clicked the `bear_paper.design` file that ships with Expression Design 3.0.

Now, select the File ► Export menu option. Here you will find a dialog box that allows you to save the selected image data to a variety of common file formats, including .png, .jpeg, .gif, .tif, .bmp and .wdp (for HD photos). If you use Design simply to make professional static images, these file formats should fit the bill. However, if you want to add interactivity to your vector art, you can save the file in a XAML description.

Select XAML WPF Canvas from the Format drop-down list in the Export dialog box. Notice the other options in Figure 29-20, including the ability to give each item a default name (via the `x:Name` attribute) and to save any text data as a Path object. You can leave the default settings, but be sure to save the XAML file to an easily found location and then click the Export All button.




Figure 29-20. Expression Design files can be exported as XAML

At this point, you can copy the generated XAML Canvas object into any Visual Studio 2010 or Expression Blend WPF application. Or, for an even easier test, you could copy the generated markup into a `<Page>` or `<Window>` scope within the kaxaml editor (or the custom XAML editor you created in Chapter 27).

In any case, if you view the generated XAML, you'll see that Path objects are the default format. At this point, you can handle events on the parts of the image you wish to manipulate, and author the related C# code. While I won't walk you through the process (you should already be in pretty good shape by this point in the chapter), you might want to import the "teddy bear" data into a new WPF application and see if you can handle the `MouseDown` event for one of eyeball objects. In the event handler, try to apply a transformation object or change the color (I have to admit I did make my bear's eye blood-red when clicked upon...).

Note We will not use Expression Design anymore in this book. If you're interested in the product, however, Design ships with its own dedicated help system, which can be activated via the F1 key.

Rendering Graphical Data Using the Visual Layer

The final option for rendering graphical data with WPF is termed the *visual layer*. As mentioned, you can only gain access to this layer through code (it is not XAML-friendly). While a vast majority of your WPF applications will work just fine using shapes, drawings, and geometries, the visual layer does provide the fastest possible way to render huge amounts of graphical data. Oddly, this very low-level graphical layer can also be useful when you need render to single image over a very large area. For example, if you need to fill the background of a window with a plain static image, the visual layer will be the fastest way to do so, and it may be useful if you need to change between window backgrounds very quickly, based on user input or whatnot.

While we won't spend too much time delving into the details of this aspect of WPF programming, let's build a small sample program that illustrates the basics.

The Visual Base Class and Derived Child Classes

The abstract `System.Windows.Media.Visual` class type supplies a minimal set of services (rendering, hit testing, transformations) to render graphics, but it does not provide support for additional non-visual services, which can lead to code bloat (input events, layout services, styles, and data binding). Notice the simple inheritance chain of the `Visual` type, as shown in Figure 29-21.




Figure 29-21. The `Visual` type provides basic hit testing, coordinate transformation, and bounding box calculations

Given that `Visual` is an abstract base class, we need to use one of the derived types to perform actual rendering operations. WPF provides a handful of subclasses, including `DrawingVisual`, `Viewport3DVisual`, and `ContainerVisual`.

In this example, we will focus only on `DrawingVisual`, a lightweight drawing class that is used to render shapes, images, or text.

A First Look at using the DrawingVisual Class

To render data onto a surface using a `DrawingVisual`, you need to take the following basic steps:

- Obtain a `DrawingContext` object from the `DrawingVisual`.
- Use the `DrawingContext` to render the graphical data.

These two steps represent the bare minimum necessary for rendering some data to a surface. However, if you want the graphical data you've rendered to be responsive to hit-testing calculations (which would be important for adding user interactivity), you will also need to perform these additional steps:

- Update the logical and visual trees maintained by the container you are rendering on top of.
- Override two virtual methods from the `FrameworkElement` class, allowing the container to obtain the visual data you have created.

We will examine these final two steps in a bit. First, to illustrate how you can use the `DrawingVisual` class to render 2D data, create a new WPF application with Visual Studio named `RenderingWithVisuals`. Our first goal is to use a `DrawingVisual` to dynamically assign data to a WPF `Image` control. Begin by updating the XAML of your window like so:

```
<Window x:Class="RenderingWithVisuals.MainWindow"
    xmlns="http://schemas.microsoft.com/winfx/2006/xaml/presentation"
    xmlns:x="http://schemas.microsoft.com/winfx/2006/xaml"
    Title=" Fun with the Visual Layer" Height="350" Width="525"
    Loaded="Window_Loaded" WindowStartupLocation="CenterScreen">
    <StackPanel Background="AliceBlue" Name="myStackPanel">
        <Image Name="myImage" Height="80"/>
    </StackPanel>
</Window>
```

Notice that our `<Image>` control does not yet have a `Source` value, as that will happen at runtime. Also notice that we are handling the `Loaded` event of the window, which will do the work of building the in-memory graphical data, using a `DrawingBrush` object. Here is the implementation of the `Loaded` event handler:

```
private void Window_Loaded(object sender, RoutedEventArgs e)
{
    const int TextFontSize = 30;

    // Make a System.Windows.Media.FormattedText object.
    FormattedText text = new FormattedText("Hello Visual Layer!",
        new System.Globalization.CultureInfo("en-us"),
        FlowDirection.LeftToRight,
        new Typeface(this.FontFamily, FontStyles.Italic,
            FontWeights.DemiBold, FontStretches.UltraExpanded),
        TextFontSize,
        Brushes.Green);
```

```

// Create a DrawingVisual, and obtain the DrawingContext.
DrawingVisual drawingVisual = new DrawingVisual();
using(DrawingContext drawingContext = drawingVisual.RenderOpen())
{
    // Now, call any of the methods of DrawingContext to render data.
    drawingContext.DrawRoundedRectangle(Brushes.Yellow, new Pen(Brushes.Black, 5),
        new Rect(5, 5, 450, 100), 20, 20);
    drawingContext.DrawText(text, new Point(20, 20));
}

// Dynamically make a bitmap, using the data in the DrawingVisual.
RenderTargetBitmap bmp = new RenderTargetBitmap(500, 100, 100, 90,
    PixelFormats.Pbgra32);
bmp.Render(drawingVisual);

// Set the source of the Image control!
myImage.Source = bmp;
}

```

This code introduces a number of new WPF classes, which I will briefly comment on here (be sure to check the .NET Framework 4.0 SDK documentation for full details if you are interested). The method begins by creating a new `FormattedText` object that represents the textual portion of the in-memory image we are constructing. As you can see, the constructor allows us to specify numerous attributes such as font size, font family, foreground color, and the text itself.

Next, we obtain the necessary `DrawingContext` object via a call to `RenderOpen()` on the `DrawingVisual` instance. Here, we are rendering a colored, rounded rectangle into the `DrawingVisual`, followed by our formatted text. In both cases, we are placing the graphical data into the `DrawingVisual` using hard-coded values, which is not necessarily a great idea for production, but fine for our simple test.

Note Be sure to look up the `DrawingContext` class within the .NET Framework 4.0 SDK documentation to view all rendering members. If you have worked with the Windows Forms `Graphics` object in the past, `DrawingContext` should look very similar.

The last few statements map the `DrawingVisual` into a `RenderTargetBitmap` object, which is a member of the `System.Windows.Media.Imaging` namespace. This class will take a visual object, and transform it into an in-memory bitmap image. After this point, we set the `Source` property of the `Image` control, and sure enough, we see the output in Figure 29-22.




Figure 29-22. Using the visual layer to render an in-memory bitmap

Note The System.Windows.Media.Imaging namespace contains a number of additional encoding classes that let you save the in-memory RenderTargetBitmap object to a physical file in a variety of formats. Check out the JpegBitmapEncoder class (and friends) for more information.

Rendering Visual Data to a Custom Layout Manager

While it is interesting to use DrawingVisual to paint onto the background of a WPF control, it is perhaps more common to build a custom layout manager (Grid, StackPanel, Canvas, etc) that uses the visual layer internally to render its content. Once you have created such a custom layout manager, you can plug it into a normal Window (or Page, or UserControl) and have a part of the UI using a highly optimized rendering agent, while the non-critical aspects of the hosting Window use shapes and drawings for the remainder of the graphical data.

If you don't require the extra functionality provided by a dedicated layout manager, you could opt to simply extend FrameworkElement, which does have the necessary infrastructure to also contain visual items. To illustrate how this could be done, insert a new class to your project named CustomVisualFrameworkElement. Extend this class from FrameworkElement and import the System.Windows, System.Windows.Input and System.Windows.Media namespaces.

This class will maintain a member variable of type VisualCollection, which contains two fixed DrawingVisual objects (of course, you could add new members to this collection via a mouse operation, but this example will keep it simple). Update your class with the following new functionality:

```
class CustomVisualFrameworkElement : FrameworkElement
{
    // A collection of all the visuals we are building.
    VisualCollection theVisuals;

    public CustomVisualFrameworkElement()
    {
        // Fill the VisualCollection with a few DrawingVisual objects.
        // The ctor arg represents the owner of the visuals.
        theVisuals = new VisualCollection(this);
        theVisuals.Add(AddRect());
        theVisuals.Add(AddCircle());
    }
}
```

```

private Visual AddCircle()
{
    DrawingVisual drawingVisual = new DrawingVisual();

    // Retrieve the DrawingContext in order to create new drawing content.
    using (DrawingContext drawingContext = drawingVisual.RenderOpen())
    {
        // Create a circle and draw it in the DrawingContext.
        Rect rect = new Rect(new Point(160, 100), new Size(320, 80));
        drawingContext.DrawEllipse(Brushes.DarkBlue, null, new Point(70, 90), 40, 50);
    }
    return drawingVisual;
}

private Visual AddRect()
{
    DrawingVisual drawingVisual = new DrawingVisual();
    using (DrawingContext drawingContext = drawingVisual.RenderOpen())
    {
        Rect rect = new Rect(new Point(160, 100), new Size(320, 80));
        drawingContext.DrawRectangle(Brushes.Tomato, null, rect);
    }
    return drawingVisual;
}
}

```

Now, before we can use this custom `FrameworkElement` in our `Window`, we must override two key virtual methods mentioned previously, both of which are called internally by WPF during the rendering process. The `GetVisualChild()` method returns a child at the specified index from the collection of child elements. The read-only `VisualChildrenCount` property returns the number of visual child elements within this visual collection. Both methods are easy to implement, as we can delegate the real work to the `VisualCollection` member variable:

```

protected override int VisualChildrenCount
{
    get { return theVisuals.Count; }
}

protected override Visual GetVisualChild(int index)
{
    // Value must be greater than zero, so do a sanity check.
    if (index < 0 || index >= theVisuals.Count)
    {
        throw new ArgumentOutOfRangeException();
    }

    return theVisuals[index];
}

```

We now have just enough functionality to test our custom class. Update the XAML description of the `Window` to add one of your `CustomVisualFrameworkElement` objects to the existing `StackPanel`. Doing so

will require you to build a custom XML namespace that maps to your .NET namespace (see Chapter 28):

```
<Window x:Class="RenderingWithVisuals.MainWindow"
    xmlns="http://schemas.microsoft.com/winfx/2006/xaml/presentation"
    xmlns:x="http://schemas.microsoft.com/winfx/2006/xaml"
    xmlns:custom="clr-namespace:RenderingWithVisuals"
    Title="Fun with the Visual Layer" Height="350" Width="525"
    Loaded="Window_Loaded" WindowStartupLocation="CenterScreen">
    <StackPanel Background="AliceBlue" Name="myStackPanel">
        <Image Name="myImage" Height="80"/>
        <custom:CustomVisualFrameworkElement/>
    </StackPanel>
</Window>
```

If all is well, you should see something similar to Figure 29-23 when you run your program.




Figure 29-23. Using the visual layer to render data to a custom FrameworkElement

Responding to Hit Test Operations

Because DrawingVisual does not have any of the infrastructure of UIElement or FrameworkElement, you will need to programmatically add in the ability to calculate hit-test operations. Thankfully, this is fairly easy to do in the visual layer because of the concept of *logical* and *visual* trees. As it turns out, when you author a blob of XAML, you are essentially building a logical tree of elements. However, behind every logical tree is a much richer description known as the visual tree, which contains lower-level rendering instructions.

Chapter 32 will delve into these trees in more detail but for now, just understand that until you register your custom visuals with these data structures, you will not be able to perform hit-testing operations. Luckily, the VisualCollection container does this on your behalf (which explains why we needed to pass in a reference to the custom FrameworkElement as a constructor argument).

First, update the `CustomVisualFrameworkElement` class to handle the `MouseDown` event in the class constructor using standard C# syntax:

```
this.MouseDown += MyVisualHost_MouseDown;
```

The implementation of this handler will call the `VisualTreeHelper.HitTest()` method to see if the mouse is within the boundaries of one of the rendered visuals. To do this, we specify as a parameter to `HitTest()`, a `HitTestResultCallback` delegate that will perform the calculations. If we did click on a visual, we will toggle between a skewed rendering of the visual and the original rendering. Add the following methods to your `CustomVisualFrameworkElement` class:

```
void MyVisualHost_MouseDown(object sender, MouseButtonEventArgs e)
{
    // Figure out where the user clicked.
    Point pt = e.GetPosition((UIElement)sender);

    // Call helper function via delegate to see if we clicked on a visual.
    VisualTreeHelper.HitTest(this, null,
        new HitTestResultCallback(myCallback), new PointHitTestParameters(pt));
}

public HitTestResultBehavior myCallback(HitTestResult result)
{
    // Toggle between a skewed rendering and normal rendering,
    // if a visual was clicked.
    if (result.VisualHit.GetType() == typeof(DrawingVisual))
    {
        if (((DrawingVisual)result.VisualHit).Transform == null)
        {
            ((DrawingVisual)result.VisualHit).Transform = new SkewTransform(7, 7);
        }
        else
        {
            ((DrawingVisual)result.VisualHit).Transform = null;
        }
    }

    // Tell HitTest() to stop drilling into the visual tree.
    return HitTestResultBehavior.Stop;
}
```

Now, run your program once again. You should now be able to click on either rendered visual and see the transformation in action! While this is just a very simple example of working with the visual layer of WPF, remember that you make use of the same brushes, transformations, pens, and layout managers as you would when working with XAML. As a result, you already know quite a bit about working this `Visual` derived classes.

■ Source Code The `RenderingWithVisuals` project can be found under the Chapter 29 subdirectory.

That wraps up our investigation of the graphical rendering services of Windows Presentation Foundation. While we covered a number of interesting topics, the reality is that we have only scratched the surface of WPF's graphical capabilities. I will leave it in your hands to dig deeper into the topics of shapes, drawings, brushes, transformations, and visuals (and, to be sure, you will see some additional details of these topics in the remaining WPF chapters).

Summary

Since Windows Presentation Foundation is such a graphically intensive GUI API, it comes as no surprise that we are given a number of ways to render graphical output. This chapter began by examining each of three ways a WPF application can do so (shapes, drawings, and visuals), and along the way discussed various rendering primitives such as brushes, pens, and transformations.

Remember that when you need to build interactive 2D renderings, shapes make the process very simple. However, static, non-interactive renderings can be rendered in a more optimal manner by using drawings and geometries, while the visual layer (accessible only in code) gives you maximum control and performance.



WPF Resources, Animations, and Styles

This chapter introduces you to three important (and interrelated) topics that will deepen your understanding of the Windows Presentation Foundation (WPF) API. The first order of business is to learn the role of *logical resources*. As you will see, the logical resource (also known as an *object resource*) system is a way to name and refer to commonly used objects within a WPF application. While logical resources are often authored in XAML, they can also be defined in procedural code.

Next, you will learn how to define, execute, and control an animation sequence. Despite what you may think, WPF animations are not limited to video game or multimedia applications. Under the WPF API, animations can be as subtle as making a button appear to glow when it receives focus, or expanding the size of a selected row in a `DataGridView`. Understanding animations is a key aspect of building custom control templates (as you'll see in Chapter 31).

We wrap up by exploring the role of WPF styles. Much like a web page that uses CSS or the ASP.NET theme engine, a WPF application can define a common look and feel for a set of controls. You can define these styles in markup and store them as object resources for later use, and you can also apply them dynamically at runtime.

Understanding the WPF Resource System

Our first task is to examine the topic of embedding and accessing application resources. WPF supports two flavors of resources. The first is a *binary resource*, and this category typically includes items most programmers consider a resource in the traditional sense (embedded image files or sound clips, icons used by the application, and so on).

The second flavor, termed *object resources* or *logical resources*, represents a named .NET object that can be packaged and reused throughout the application. While any .NET object can be packaged as an object resource, logical resources are particularly helpful when working with graphical data of any sort, given that you can define commonly used graphic primitives (brushes, pens, animations, etc.) and refer to them when required.

Working with Binary Resources

Before we get to the topic of object resources, let's quickly examine how to package up *binary resources* such as icons or image files (e.g., company logos and images for an animation) into your applications. If you'd like to follow along, create a new WPF application named `BinaryResourcesApp` using Visual Studio 2010. Update the markup for your initial window to use a `DockPanel` as the layout root:

```
<Window x:Class="BinaryResourcesApp.MainWindow"
    xmlns="http://schemas.microsoft.com/winfx/2006/xaml/presentation"
    xmlns:x="http://schemas.microsoft.com/winfx/2006/xaml"
    Title="Fun with Binary Resources" Height="500" Width="649">

    <DockPanel LastChildFill="True">
        </DockPanel>

</Window>
```

Now, let's say your application needs to display one of three image files inside part of the window, based on user input. The WPF Image control can be used to not only display a typical image file (*.bmp, *.gif, *.ico, *.jpg, *.png, *.wdp, and *.tiff) but also data in a DrawingImage (as you saw in Chapter 29). You might build a UI for your window that supports a DockPanel containing a simple toolbar with Next and Previous buttons. Below this toolbar you can place an Image control, which currently does not have a value set to the Source property, as we will do this in code:

```
<Window x:Class="BinaryResourcesApp.MainWindow"
    xmlns="http://schemas.microsoft.com/winfx/2006/xaml/presentation"
    xmlns:x="http://schemas.microsoft.com/winfx/2006/xaml"
    Title="Fun with Binary Resources" Height="500" Width="649">

    <DockPanel LastChildFill="True">
        <ToolBar Height="60" Name="picturePickerToolbar" DockPanel.Dock="Top">
            <Button x:Name="btnPreviousImage" Height="40" Width="100" BorderBrush="Black"
                Margin="5" Content="Previous" Click="btnPreviousImage_Click"/>
            <Button x:Name="btnNextImage" Height="40" Width="100" BorderBrush="Black"
                Margin="5" Content="Next" Click="btnNextImage_Click"/>
        </ToolBar>

        <!-- We will fill this Image in code -->
        <Border BorderThickness="2" BorderBrush="Green">
            <Image x:Name="imageHolder" Stretch="Fill" />
        </Border>
    </DockPanel>

</Window>
```

Please note that the Click event has been handled for each Button objects. Assuming you have used the IDE to handle these events, you will have two empty methods in your C# code file. So, how can we code the Click event handlers to cycle through the image data? More importantly, do we want to have the image data located on the user's hard drive or embedded in our compiled assembly? Let's examine our options.

Including Loose Resource Files in a Project

Let's assume you wish to ship your image files as a set of loose files in a subdirectory of the application install path. Using the Solution Explorer window of Visual Studio, you can right-click on your project node and select the Add ➤ New Folder menu option to create such a subdirectory, which I have called Images.

Now, when you right-click on this folder, you can select the Add ► Existing Item menu option, to copy the image files into the new subdirectory. In the downloadable source code for this project, you will find three image files named `Welcome.jpg`, `Dogs.jpg` and `Deer.jpg` that you can include in this project, or simply add three image files of your choice. Figure 30-1 shows the current setup.




Figure 30-1. A new subdirectory in our WPF project containing image data

Configuring the Loose Resources

When you want Visual Studio 2010 to copy project content to your output directory, you need to adjust a few settings using the Properties window. To ensure that the content of your \Images folder is copied to the \bin\Debug folder, begin by selecting each image in the Solution Explorer. Now, with these images still selected, use the Properties window to set the Build Action property to Content, and the Copy to Output Directory property to Copy always (see Figure 30-2).




Figure 30-2. Configuring the image data to be copied to our output directory

If you recompile your program, you can now click on the Show all Files button of the Solution Explorer and view the copied Image folder under your \bin\Debug directory (you might need to click the refresh button). See Figure 30-3.




Figure 30-3. The copied data

Programmatically Loading an Image

WPF provides a class named `BitmapImage`, which is part of the `System.Windows.Media.Imaging` namespace. This class allows you to load data from an image file whose location is represented by a `System.Uri` object. If you handle the `Loaded` event of your window, you might fill a `List<T>` of `BitmapImages` like so:

```
public partial class MainWindow : Window
{
    // A List of BitmapImage files.
    List<BitmapImage> images = new List<BitmapImage>();

    // Current position in the list.
    private int currImage = 0;
    private const int MAX_IMAGES = 2;

    private void Window_Loaded(object sender, RoutedEventArgs e)
    {
        try
        {
            string path = Environment.CurrentDirectory;

            // Load these images when the window loads.
            images.Add(new BitmapImage(new Uri(string.Format("{0}\Images\Deer.jpg", path)))); 
            images.Add(new BitmapImage(new Uri(string.Format("{0}\Images\Dog.jpg", path))));
```

```

        images.Add(new BitmapImage(new Uri(string.Format(@"{0}\Images\Welcome.jpg", path))));

    // Show first image in the List<>.
    imageHolder.Source = images[currImage];
}
catch (Exception ex)
{
    MessageBox.Show(ex.Message);
}
}
...
}
}

```

Notice that this class also defines an int member variable (`currImage`) that will allow the Click event handlers to loop through each item in the `List<T>` and display it in the `Image` control by setting the `Source` property. (Here, our `Loaded` event handler sets the `Source` property to the first image in the `List<T>`.) In addition, our `MAX_IMAGES` constant will let us test for upper and lower limits as we iterate over the list. Here are the Click handlers that do exactly this:

```

private void btnPreviousImage_Click(object sender, RoutedEventArgs e)
{
    if (--currImage < 0)
        currImage = MAX_IMAGES;
    imageHolder.Source = images[currImage];
}

private void btnNextImage_Click(object sender, RoutedEventArgs e)
{
    if (++currImage > MAX_IMAGES)
        currImage = 0;
    imageHolder.Source = images[currImage];
}

```

At this point, you can run your program and flip through each picture.

Embedding Application Resources

If you'd rather configure your image files to be compiled directly into your .NET assembly as binary resources, select the image files in Solution Explorer (in the `\Images` folder, not in the `\bin\Debug\Images` folder). Then change the Build Action property to Resource and the Copy to Output Directory property to Do not copy (Figure 30-4).




Figure 30-4. Configuring the images to be embedded resources

Now, using Visual Studio 2010's Build menu, select the Clean Solution option to wipe out the current contents of \bin\Debug\Images, then rebuild your project. Refresh the Solution Explorer, and observe the absence of \bin\Debug\Images in your \bin\Debug directory.

With the current build options, your graphical data is no longer copied to the output folder and is now embedded within the assembly itself. Assuming you have recompiled your project, you can open the assembly into reflector.exe, and see the embedded image data (Figure 30-5).




Figure 30-5. The embedded image data

With this adjustment, we will now need to modify our code to load these images by extracting them from the compiled assembly:

```
private void Window_Loaded(object sender, RoutedEventArgs e)
{
    try
    {
        images.Add(new BitmapImage(new Uri(@"/Images/Deer.jpg", UriKind.Relative)));
        images.Add(new BitmapImage(new Uri(@"/Images/Dogs.jpg", UriKind.Relative)));
        images.Add(new BitmapImage(new Uri(@"/Images/Welcome.jpg", UriKind.Relative)));
    }
}
```

```
    imageHolder.Source = images[currImage];
}
catch (Exception ex)
{
    MessageBox.Show(ex.Message);
}
}
```

Notice in this case, we no longer need to determine the installation path and can simply list the resources by name, which takes into account the name of the original subdirectory. Also notice, when we create our Uri objects, we specify a UriKind value of Relative. In any case, at this point our executable is a standalone entity that can be run from any location on the machine, as all compiled data is within the binary. Figure 30-6 shows the completed application.




Figure 30-6. Our simple picture viewer

■ **Source Code** The BinaryResourcesApp can be found under the Chapter 30 subdirectory.

Working with Object (Logical) Resources

When you are building a WPF application, it is very common to define a blurb of XAML to use in multiple locations within a window, or perhaps across multiple windows or projects. For example, say you are using Expression Blend to build the *perfect* linear gradient brush, which consists of 10 lines of markup. Now, you want to use that brush as the background color for every Button control in the project...which consists of 8 windows...for a total of 16 Buttons.

The worst thing you could do is to copy and paste the XAML to each and every control. Clearly, this would be a nightmare to maintain, as you would need to make numerous changes anytime you wanted to tweak the look and feel of the brush.

Thankfully, *object resources* allow us to define a blob of XAML, give it a name, and store it in a fitting dictionary for later use. Like a binary resource, object resources are often compiled into the assembly that requires them. However, you don't need to tinker with the Build Action property to do so. As long as you place your XAML into the correct location, the compiler will take care of the rest.

Working with object resources is a big part of WPF development. As you will see, object resources can be far more complex than a custom brush. You could define a XAML-based animation, a 3D rendering, a custom control style, data template, control template, and more, and package each one as a reusable resource.

The Role of the Resources Property

As mentioned, object resources must be placed in a fitting dictionary object in order to be used across an application. As it stands, every descendent of `FrameworkElement` supports a `Resources` property. This property encapsulates a `ResourceDictionary` object that contains the defined object resources. The `ResourceDictionary` can hold any type of item as it operates on `System.Object` types and may be manipulated via XAML or procedural code.

In WPF, all controls, Windows, Pages (used when building navigation applications or XBAP programs) and `UserControls` extend `FrameworkElement`, so just about all widgets provide access to a `ResourceDictionary`. Furthermore, the `Application` class, while not extending `FrameworkElement`, supports an identically named `Resources` property for the same purpose.

Defining Window-Wide Resources

To begin exploring the role of object resources, create a new WPF application named `ObjectResourcesApp` using Visual Studio 2010 and change the initial `Grid` to a horizontally aligned `StackPanel` layout manager. Into this `StackPanel`, define two `Button` controls (we really don't need much to illustrate the role of object resources, so this will do):

```
<Window x:Class="ObjectResourcesApp.MainWindow"
    xmlns="http://schemas.microsoft.com/winfx/2006/xaml/presentation"
    xmlns:x="http://schemas.microsoft.com/winfx/2006/xaml"
    Title="Fun with Object Resources" Height="350" Width="525">

    <StackPanel Orientation="Horizontal">
        <Button Margin="25" Height="200" Width="200" Content="OK" FontSize="20"/>
        <Button Margin="25" Height="200" Width="200" Content="Cancel" FontSize="20"/>
    </StackPanel>

</Window>
```

Now, select the OK button and set the Background color property to a custom brush type using the integrated brush editor (discussed in Chapter 29). Once you've done so, notice how the brush is embedded within the scope of the `<Button>` and `</Button>` tags:

```
<Button Margin="25" Height="200" Width="200" Content="OK" FontSize="20">
    <Button.Background>
        <RadialGradientBrush>
            <GradientStop Color="#FFC44EC4" Offset="0" />
            <GradientStop Color="#FF829CEB" Offset="1" />
            <GradientStop Color="#FF793879" Offset="0.669" />
        </RadialGradientBrush>
    </Button.Background>
</Button>
```

To allow the Cancel button to use this brush as well, we should promote the scope of our `<RadialGradientBrush>` to a parent element's resource dictionary. For example, if we move it to the `<StackPanel>`, both buttons can use the same brush, as they are child elements of the layout manager. Even better, we could package the brush into the resource dictionary of the window itself, so all aspects of the window's content (nested panels, etc.) can freely make use of it.

When you need to define a resource, you use property element syntax to set the `Resources` property of the owner. You also give the resource item an `x:Key` value, which will be used by other parts of the window when they want to refer to the object resource. Be aware that `x:Key` and `x:Name` are not the same! The `x:Name` attribute allows you to gain access to the object as a member variable in your code file, while the `x:Key` attribute allows you to refer to an item in a resource dictionary.

Visual Studio 2010 and Expression Blend both allow you to promote a resource to a higher scope using their respective Properties windows. In Visual Studio 2010, first identify the property that has the complex object you wish to package as a resource (the `Background` property in our example). Next to the property, you'll see a small diamond button that, when clicked, will open a pop-up menu. From here, select the "Extract value to Resource..." option (Figure 30-7).




Figure 30-7. Moving a complex object into a resource container

You are now asked to name your resource (`myBrush`), and specify where to place it. For this example, leave the default selection of `MainWindow.xaml` (Figure 30-8).




Figure 30-8. Naming the object resource

When you're done, the markup will be restructured like this:

```
<Window x:Class="ObjectResourcesApp.MainWindow"
    xmlns="http://schemas.microsoft.com/winfx/2006/xaml/presentation"
    xmlns:x="http://schemas.microsoft.com/winfx/2006/xaml"
    Title="Fun with Object Resources" Height="350" Width="525">

    <Window.Resources>
        <RadialGradientBrush x:Key="myBrush">
            <GradientStop Color="#FFC44EC4" Offset="0" />
            <GradientStop Color="#FF829CEB" Offset="1" />
            <GradientStop Color="#FF793879" Offset="0.669" />
        </RadialGradientBrush>
    </Window.Resources>

    <StackPanel Orientation="Horizontal">
        <Button Margin="25" Height="200" Width="200" Content="OK"
            FontSize="20" Background="{StaticResource myBrush}"></Button>
        <Button Margin="25" Height="200" Width="200" Content="Cancel" FontSize="20"/>
    </StackPanel>

</Window>
```

Notice the new `<Window.Resources>` scope, which now contains the `RadialGradientBrush` object, which has a key value of `myBrush`.

The `{StaticResource}` Markup Extension

The other change that took place when we extracted our object resource was that the property that was the target of the extraction (again, `Background`) now makes use of the `{StaticResource}` markup extension. As you can see, the key name is specified as an argument. Now, if the `Cancel` button wishes to use the same brush to paint its background, it is free to do so. Or, if the `Cancel` button had some complex content, any sub-element of that `Button` could also use the window-level resource—for example, the `Fill` property of an `Ellipse`:

```
<StackPanel Orientation="Horizontal">
    <Button Margin="25" Height="200" Width="200" Content="OK" FontSize="20"
```

```

        Background="{StaticResource myBrush}">
    </Button>

    <Button Margin="25" Height="200" Width="200" FontSize="20">
        <StackPanel>
            <Label HorizontalAlignment="Center" Content= "No Way!"/>
            <Ellipse Height="100" Width="100" Fill="{StaticResource myBrush}"/>
        </StackPanel>
    </Button>
</StackPanel>
```

Changing a Resource after Extraction

After you have extracted a resource to the scope of a window, you can locate it in your Document Outline window, which can be opened via the View ▶ Other Windows ▶ Document Outline menu (Figure 30-9).




Figure 30-9. Viewing our resource in the Document Outline

If you select any aspect of the object resource in the Document Outline window, you can change values using the Properties window. Thus, you could change the individual gradient stops, the origin offset, and other aspects of the brush.

The {DynamicResource} Markup Extension

It is also possible for a property to use the {DynamicResource} markup extension when connecting to a keyed resource. To understand the difference, name your OK button btnOK and handle the Click event. In this event handler, use the Resources property to obtain the custom brush, and then change some aspect of it:

```

private void btnOK_Click(object sender, RoutedEventArgs e)
{
    // Get the brush and make a change.
    RadialGradientBrush b = (RadialGradientBrush)Resources["myBrush"];
    b.GradientStops[1] = new GradientStop(Colors.Black, 0.0);
}
```

Note We are using the Resources indexer to locate a resource by name here. Be aware, however, that this will throw a runtime exception if the resource can't be found. You could also use the TryFindResource() method, which will not throw a runtime error but simply return null if the specified resource can't be located.

If you run this application and click the OK button, you will see the brush's change is accounted for and each button updates to render the modified brush. However, what if you completely changed the type of brush specified by the myBrush key? For example:

```
private void btnOK_Click(object sender, RoutedEventArgs e)
{
    // Put a totally new brush into the myBrush slot.
    Resources["myBrush"] = new SolidColorBrush(Colors.Red);
}
```

This time, when you click the button, neither updates as expected. This is because the {StaticResource} markup extension applies the resource only once and stays “connected” to the original object during the life of the application. However, if we change each occurrence of {StaticResource} to {DynamicResource} in our markup, we find our custom brush has been replaced with the expected solid red brush.

Essentially, the {DynamicResource} markup extension is able to detect whether the underlying keyed object has been replaced with a new object. As you might guess, this requires some extra runtime infrastructure, so you should typically stick to using {StaticResource} unless you know you have an object resource that will be swapped with a different object at runtime, and you want all items using that resource to be informed.

Application-Level Resources

When you have object resources in a window's resource dictionary, all items in the window are free to make use of it, but other windows in the application cannot. Give your Cancel button a name of btnCancel and handle the Click event. Insert a new window into your current project (named TestWindow.xaml) that contains a single Button, which, when clicked, will close the window:

```
public partial class TestWindow : Window
{
    public TestWindow()
    {
        InitializeComponent();
    }

    private void btnClose_Click(object sender, RoutedEventArgs e)
    {
        this.Close();
    }
}
```

Now, in the Click handler of the Cancel button on your first window, just load and display this new window, like so:

```
private void btnCancel_Click(object sender, RoutedEventArgs e)
{
    TestWindow w = new TestWindow();
    w.Owner = this;
    w.WindowStartupLocation = WindowStartupLocation.CenterOwner;
    w.ShowDialog();
}
```

So, if the new window wants to use myBrush, it currently won't be able to as it is not within the correct "scope." The solution is to define the object resource at the application level, rather than at the level of a specific window. There is no way to automate this within Visual Studio 2010, so simply cut the current brush object out of the <Windows.Resources> scope, and place it in the <Application.Resources> scope in your App.xaml file:

```
<Application x:Class="ObjectResourcesApp.App"
    xmlns="http://schemas.microsoft.com/winfx/2006/xaml/presentation"
    xmlns:x="http://schemas.microsoft.com/winfx/2006/xaml"
    StartupUri="MainWindow.xaml">

    <Application.Resources>
        <RadialGradientBrush x:Key="myBrush">
            <GradientStop Color="#FFC44EC4" Offset="0" />
            <GradientStop Color="#FF829CEB" Offset="1" />
            <GradientStop Color="#FF793879" Offset="0.669" />
        </RadialGradientBrush>
    </Application.Resources>

</Application>
```

Now your TestWindow is free to use this same brush to paint its background. If you find the Background property for this new Window, click the "Advanced properties" square and you can activate the Apply Resource... menu option. You can then search for your application-level brush by typing its name into the Search box. (Figure 30-10)




Figure 30-10. Applying application-level resources

Defining Merged Resource Dictionaries

Application-level resources are a good starting point, but what if you need to define a set of complex (or not so complex) resources that need to be reused across multiple WPF projects? In this case, you want to define what is known as a “merged resource dictionary.” This is nothing more than a .xaml file that contains nothing but a collection of object resources. A single project can have as many of these files as required (one for brushes, one for animations, and so forth), each of which can be inserted using the Add New Item dialog box activated via the Project menu (Figure 30-11).




Figure 30-11. Inserting a new merged resource dictionary

In the new MyBrushes.xaml file, we will want to cut the current resources in the Application.Resources scope and move them into our dictionary, like so:

```
<ResourceDictionary xmlns="http://schemas.microsoft.com/winfx/2006/xaml/presentation"
    xmlns:x="http://schemas.microsoft.com/winfx/2006/xaml">

    <RadialGradientBrush x:Key="myBrush">
        <GradientStop Color="#FFC44EC4" Offset="0" />
        <GradientStop Color="#FF829CEB" Offset="1" />
        <GradientStop Color="#FF793879" Offset="0.669" />
    </RadialGradientBrush>

</ResourceDictionary>
```

Now, even though this resource dictionary is part of our project, we will get runtime errors. The reason is that all resource dictionaries must be merged (typically at the application level) into an existing resource dictionary. To do this, use the following format (note that multiple resource dictionaries can be merged by adding multiple `<ResourceDictionary>` elements within the `<ResourceDictionary.MergedDictionaries>` scope).

```
<Application x:Class="ObjectResourcesApp.App"
    xmlns="http://schemas.microsoft.com/winfx/2006/xaml/presentation"
    xmlns:x="http://schemas.microsoft.com/winfx/2006/xaml"
    StartupUri="MainWindow.xaml">

    <!-- Bring in the logical resources
        from the MyBrushes.xaml file. -->
```

```

<Application.Resources>
  <ResourceDictionary>
    <ResourceDictionary.MergedDictionaries>
      <ResourceDictionary Source = "MyBrushes.xaml"/>
    </ResourceDictionary.MergedDictionaries>
  </ResourceDictionary>
</Application.Resources>

</Application>

```

Defining a Resource-Only Assembly

Last but not least, it is possible to create .NET class libraries that contain nothing but dictionaries of object resources. This can be useful if you have defined a set of themes that need to be used on a machine-wide level. You could package up the object resource into a dedicated assembly, and then applications that wish to make use of them could load them into memory.

The easiest way to build a resource-only assembly is to actually begin with a WPF User Control Library project. Add such a project (named MyBrushesLibrary) to your current solution, using the Add ➤ New Project menu option of Visual Studio 2010 (Figure 30-12).




Figure 30-12. Adding a User Control library as a starting point for a resource-only library

Now, completely delete the `UserControl1.xaml` file from the project (the only items we really want are the referenced WPF assemblies). Next, drag and drop the `MyBrushes.xaml` file into your `MyBrushesLibrary` project and delete it from the `ObjectResourcesApp` project. Your Solution Explorer should now look like Figure 30-13.




Figure 30-13. Moving the *MyBrushes.xaml* file into our new library project

Compile your code library project. Next, reference this library from the ObjectResourcesApp project using the Add Reference dialog box. Now, you will want to merge these binary resources into the application-level resource dictionary of the ObjectResourcesApp project. Doing so, however, requires some rather funky syntax, shown here:

```
<Application.Resources>
  <ResourceDictionary>
    <ResourceDictionary.MergedDictionaries>
      <!--The syntax is /NameOfAssembly;Component/NameOfXamlFileInAssembly.xaml -->
      <ResourceDictionary Source = "/MyBrushesLibrary;Component/MyBrushes.xaml"/>
    </ResourceDictionary.MergedDictionaries>
  </ResourceDictionary>
</Application.Resources>
```

First, be aware that this string is space-sensitive. If you have extra white space around your semicolon or forward slashes, you will generate runtime errors. The first part of the string is the friendly name of the external library (no file extension). After the semicolon, you type in the word *Component* followed by the name of the compiled binary resource, which will be identical to the original XAML resource dictionary.

Extracting Resources in Expression Blend

As mentioned, Expression Blend has similar ways to promote local resources to window-level, application-level, and even resource-dictionary-level. Assume you have defined a custom brush for the Background property of the main window and wish to package it as a new resource. Using the Brush editor, click on the (ever so tiny) Advanced Properties button (the small white dot) of the Background property to access the Convert to New Resource option (Figure 30-14).



Figure 30-14. Extracting a new resource using Blend

From the resulting dialog box, you can give your object resource a name and specify where Blend should store it (the current window, the application, or a new merged resource dictionary). Here I have placed myNewBrush at the application level (Figure 30-15).




Figure 30-15. Defining a new application-level resource with Blend

Once you've done this, you will see that your App.xaml file has been updated as expected. Also, using the Resources tab (opened via the Window menu) you can modify existing resources using the appropriate editor (Figure 30-16).




Figure 30-16. Modifying existing resources with Blend

That wraps up our examination of WPF's resource management system. You will make good use of these techniques for most of your applications, as well as during the remainder of the WPF chapters of this text. Next up, let's investigate the integrated animation API of Windows Presentation Foundation.

Source Code The ObjectResourcesApp project can be found under the Chapter 30 subdirectory.

Understanding WPF's Animation Services

In addition to the graphical rendering services you examined in Chapter 29, WPF supplies a programming interface to support animation services. The term *animation* may bring to mind visions of spinning company logos, a sequence of rotating image resources (to provide the illusion of movement), text bouncing across the screen, or specific types of programs such as video games or multimedia applications.

While WPF's animation APIs could certainly be used for such purposes, animation can be used any time you wish to give an application additional flair. For example, you could build an animation for a button on a screen that magnifies slightly when the mouse cursor hovers within its boundaries (and shrinks back once the mouse cursor moves beyond the boundaries). Or you could animate a window so that it closes using a particular visual appearance, such as slowly fading into transparency. In fact, WPF's

animation support can be used within any sort of application (a business application, multimedia programs, video games, etc.) whenever you wish to provide a more engaging user experience.

As with many other aspects of WPF, the notion of building animations is nothing new. What is new is that, unlike other APIs you may have used in the past (including Windows Forms), developers are not required to author the necessary infrastructure by hand. Under WPF, there's no need to create the background threads or timers used to advance the animation sequence, define custom types to represent the animation, erase and redraw images, or bother with tedious mathematical calculations.

Like other aspects of WPF, we can build an animation entirely using XAML, entirely using C# code, or using a combination of the two. Furthermore, we can use Microsoft Expression Blend to design an animation using integrated tools and wizards—without seeing a bit of C# or XAML in the foreground. You will see how to use Blend to author animations in the next chapter during our discussion of control templates. For now, let's get to know the overall role of the animation API.

Note Visual Studio 2010 has no support for authoring animations using GUI animation tools. If you author an animation with Visual Studio, you will do so by typing in the XAML directly.

The Role of the Animation Class Types

To understand WPF's animation support, we must begin by examining the animation classes within the `System.Windows.Media.Animation` namespace of `PresentationCore.dll`. Here you will find over 100 different class types that are named using the `Animation` token.

All of these classes can be placed into one of three broad categories. First of all, any class that follows the name convention `DataTypeAnimation` (`ByteAnimation`, `ColorAnimation`, `DoubleAnimation`, `Int32Animation`, etc.) allows you to work with linear interpolation animations. This enables you to change a value smoothly over time from a start value to a final value.

Next, the classes that follow the naming convention `DataTypeAnimationUsingKeyFrames` (`StringAnimationUsingKeyFrames`, `DoubleAnimationUsingKeyFrames`, `PointAnimationUsingKeyFrames`, etc.) represent “key frame animations,” which allow you to cycle through a set of defined values over a period of time. For example, you could use keyframes to change the caption of a button by cycling through a series of individual characters.

Finally, classes that follow the `DataTypeAnimationUsingPath` naming convention (`DoubleAnimationUsingPath`, `PointAnimationUsingPath`, among others) are path-based animations that allow you to animate objects to move along a path you define. By way of an example, if you were building a GPS application, you could use a path-based animation to move an item along the quickest travel route to the user's destination.

Now, obviously, these classes are *not* used to somehow provide an animation sequence directly to a variable of a particular data type (after all, how exactly could we animate the value “9” using an `Int32Animation`?).

For example, consider the `Label` type's `Height` and `Width` properties, both of which are dependency properties wrapping a double. If you wish to define an animation that would increase the height of a label over a time span, you could connect a `DoubleAnimation` object to the `Height` property and allow WPF to take care of the details of performing the actual animation itself. By way of another example, if you wish to transition the color of a brush type from green to yellow over a period of 5 seconds, you could do so using the `ColorAnimation` type.

To be very clear, these `Animation` classes can be connected to any *dependency property* of a given object that matches the underlying types. As explained in Chapter 31, dependency properties are a

specialized form of property required by many WPF services including animation, data binding, and styles.

By convention, a dependency property is defined as a static read-only field of the class, and is named by suffixing the word `Property` to the normal property name. For example, the dependency property for the `Height` property of a `Button` would be accessed in code using `Button.HeightProperty`.

The To, From, and By Properties

All `Animation` classes define a handful of key properties that control the starting and ending values used to perform the animation:

- `To`: This property represents the animation's ending value.
- `From`: This property represents the animation's starting value.
- `By`: This property represents the total amount by which the animation changes its starting value.

Despite the fact that all `Animation` classes support the `To`, `From`, and `By` properties, they do not receive them via virtual members of a base class. The reason for this is that the underlying types wrapped by these properties vary greatly (integers, colors, `Thickness` objects, etc.), and representing all possibilities using a single base class would result in very complex coding constructs.

On a related note, you might also wonder why .NET generics were not used to define a single generic animation class with a single type parameter (e.g., `Animate<T>`). Again, given that there are so many underlying data types (colors, vectors, ints, strings, etc.) used to animated dependency properties, it would not be as clean a solution as you might expect (not to mention XAML has only limited support for generic types).

The Role of the Timeline Base Class

Although a single base class was not used to define virtual `To`, `From`, and `By` properties, the `Animation` classes do share a common base class: `System.Windows.Media.Animation.Timeline`. This type provides a number of additional properties that control the pacing of the animation, as described in Table 30-1.

Table 30-1. Key Members of the Timeline Base Class

Properties	Meaning in Life
<code>AccelerationRatio</code> , <code>DecelerationRatio</code> , <code>SpeedRatio</code>	These properties can be used to control the overall pacing of the animation sequence.
<code>AutoReverse</code>	This property gets or sets a value that indicates whether the timeline plays in reverse after it completes a forward iteration (the default value is <code>false</code>).
<code>BeginTime</code>	This property gets or sets the time at which this timeline should begin. The default value is 0, which begins the animation immediately.

Table 30-1. Key Members of the Timeline Base Class (continued)

Properties	Meaning in Life
Duration	This property allows you to set a duration of time to play the timeline.
FillBehavior, RepeatBehavior	These properties are used to control what should happen once the timeline has completed (repeat the animation, do nothing, etc.).

Authoring an Animation in C# Code

The chances are quite good that a majority of your WPF animation projects will be authored using the Expression Blend animation editor, and will therefore be represented as markup. However, our first look at WPF's animation services will use nothing but C# code, as I feel it is a tad more straightforward.

Specifically, we will build a Window that contains a Button, which has the odd behavior of spinning in a circle (based on the upper left corner) whenever the mouse enters its surface area. Begin by creating a new WPF application named SpinningButtonAnimationApp, using Visual Studio 2010. Update the initial markup like the following (note we are handling the button's MouseEnter event):

```
<Window x:Class="SpinningButtonAnimationApp.MainWindow"
    xmlns="http://schemas.microsoft.com/winfx/2006/xaml/presentation"
    xmlns:x="http://schemas.microsoft.com/winfx/2006/xaml"
    Title="Animations in C# code" Height="350"
    Width="525" WindowStartupLocation="CenterScreen">
    <Grid>
        <Button x:Name="btnSpinner" Height="50" Width="100" Content="I Spin!"
            MouseEnter="btnSpinner_MouseEnter"/>
    </Grid>
</Window>
```

Now, import the `System.Windows.Media.Animation` namespace and add the following code in the window's C# code file:

```
public partial class MainWindow : Window
{
    private bool isSpinning = false;

    private void btnSpinner_MouseEnter(object sender, MouseEventArgs e)
    {
        if (!isSpinning)
        {
            isSpinning = true;

            // Make a double animation object, and register
            // with the Completed event.
            DoubleAnimation dblAnim = new DoubleAnimation();
            dblAnim.Completed += (o, s) => { isSpinning = false; };
        }
    }
}
```

```

// Set the start value and end value.
dblAnim.From = 0;
dblAnim.To = 360;

// Now, create a RotateTransform object, and set
// it to the RenderTransform property of our
// button.
RotateTransform rt = new RotateTransform();
btnSpinner.RenderTransform = rt;

// Now, animation the RotateTransform object.
rt.BeginAnimation(RotateTransform.AngleProperty, dblAnim);
}

}
}

```

The first major task of this method is to configure a `DoubleAnimation` object, which will start at the value 0 and end at the value 360. Notice that we are handling the `Completed` event on this object as well, to toggle a class-level `bool` variable that is used to ensure that if an animation is currently being performed, we don't "reset" it to start again.

Next, we create a `RotateTransform` object that is connected to the `RenderTransform` property of our `Button` control (`btnSpinner`). Last but not least, we inform the `RenderTransform` object to begin animating its `Angle` property using our `DoubleAnimation` object. When you are authoring animations in code, you typically do so by calling `BeginAnimation()`, and pass in the underlying *dependency property* you wish to animate (remember, by convention, this is a static field on the class), followed by a related animation object.

Let's add another animation to the program, which will cause the button to fade into invisibility when clicked. First, handle the `Click` event of the `btnSpinner` object, then add the following code in the resulting event handler:

```

private void btnSpinner_Click(object sender, RoutedEventArgs e)
{
    DoubleAnimation dblAnim = new DoubleAnimation();
    dblAnim.From = 1.0;
    dblAnim.To = 0.0;
    btnSpinner.BeginAnimation(Button.OpacityProperty, dblAnim);
}

```

Here, we are changing the `Opacity` property value to fade the button out of view. Currently, however, this is hard to do, as the button is spinning very fast! How, then, can we control the pace of an animation? Glad you asked.

Controlling the Pacing of an Animation

By default, an animation will take approximately one second to transition between the values assigned to the `From` and `To` properties. Therefore, our button has one second to spin around a full 360 degree angle, while the button will fade away to invisibility (when clicked) over the course of one second.

If you wish to define a custom amount of time for an animation's transition, you may do so via the animation object's `Duration` property, which can be set to an instance of a `Duration` object. Typically, the

time span is established by passing a `TimeSpan` object to the `Duration`'s constructor. Consider the following update that will give the button a full 4 seconds to rotate:

```
private void btnSpinner_MouseEnter(object sender, MouseEventArgs e)
{
    if (!isSpinning)
    {
        isSpinning = true;

        // Make a double animation object, and register
        // with the Completed event.
        DoubleAnimation dblAnim = new DoubleAnimation();
        dblAnim.Completed += (o, s) => { isSpinning = false; };

        // Button has 4 seconds to finish the spin!
        dblAnim.Duration = new Duration(TimeSpan.FromSeconds(4));

        ...
    }
}
```

With this adjustment, you should have a fighting chance to click the button while it is spinning, at which point it will fade away.

Note The `BeginTime` property of an `Animation` class also takes a `TimeSpan` object. Recall that this property can be set to establish a wait time before starting an animation sequence.

Reversing and Looping an Animation

You can also tell `Animation` objects to play an animation in reverse at the completion of the animation sequence by setting the `AutoReverse` property to `true`. For example, if you wish to have the button come back into view after it has faded away, you could author the following:

```
private void btnSpinner_Click(object sender, RoutedEventArgs e)
{
    DoubleAnimation dblAnim = new DoubleAnimation();
    dblAnim.From = 1.0;
    dblAnim.To = 0.0;

    // Reverse when done.
    dblAnim.AutoReverse = true;
    btnSpinner.BeginAnimation(Button.OpacityProperty, dblAnim);
}
```

If you'd like to have an animation repeat some number of times (or to never stop once activated), you can do so using the `RepeatBehavior` property, which is common to all `Animation` classes. If you pass in a simple numerical value to the constructor, you can specify a hard-coded number of times to repeat.

On the other hand, if you pass in a `TimeSpan` object to the constructor, you can establish an amount of time the animation should repeat. Finally, if you wish an animation to loop ad infinitum, you can simply specify `RepeatBehavior.Forever`. Consider the following ways we could change the repeat behaviors of either of the `DoubleAnimation` objects used in this example:

```
// Loop forever.
dblAnim.RepeatBehavior = RepeatBehavior.Forever;

// Loop three times.
dblAnim.RepeatBehavior = new RepeatBehavior(3);

// Loop for 30 seconds.
dblAnim.RepeatBehavior = new RepeatBehavior(TimeSpan.FromSeconds(30));
```

That wraps up our investigation about how to animate aspects of an object using C# code and the WPF animation API. Next, we will learn how to do the same using XAML.

■ Source Code The SpinningButtonAnimationApp project can be found under the Chapter 30 subdirectory.

Authoring Animations in XAML

Authoring animations in markup is similar to authoring them in code, at least for simple, straightforward animation sequences. When you need to capture more complex animations, which may involve changing the values of numerous properties at once, the amount of markup can grow considerably. Thankfully, the Expression Blend animation editors can take care of the details for us. Even so, it is important to know the basics of how an animation is represented in XAML, as this will make it easier for you to modify and tweak tool-generated content.

■ Note You will find a number of XAML files in the `XamlAnimations` folder of the downloadable source code. As you go through the next several pages, copy these markup files into your custom XAML editor, or into the `kaxaml` editor, to see the results.

For the most part, creating an animation is similar to what you have already seen. You still configure an `Animation` object and associate it to an object's property. One big difference, however, is that WPF is not function-call-friendly. As a result, instead of calling `BeginAnimation()`, you use a *Storyboard* as a layer of indirection.

Let's walk through a complete example of an animation defined in terms of XAML, followed by a detailed breakdown. The following XAML definition will display a window that contains a single label. As soon as the `Label` object loads into memory, it begins an animation sequence in which the font size increases from 12 points to 100 over a period of four seconds. The animation will repeat for as long as the `Window` object is loaded in memory. You can find this markup in the `GrowLabelFont.xaml` file, so copy it into your `MyXamlPad.exe` application and observe the behavior.

```

<Window
    xmlns="http://schemas.microsoft.com/winfx/2006/xaml/presentation"
    xmlns:x="http://schemas.microsoft.com/winfx/2006/xaml"
    Height="200" Width="600" WindowStartupLocation="CenterScreen" Title="Growing Label Font!">
    <StackPanel>
        <Label Content = "Interesting...">
            <Label.Triggers>
                <EventTrigger RoutedEvent = "Label.Loaded">
                    <EventTrigger.Actions>
                        <BeginStoryboard>
                            <Storyboard TargetProperty = "FontSize">
                                <DoubleAnimation From = "12" To = "100" Duration = "0:0:4"
                                    RepeatBehavior = "Forever"/>
                            </Storyboard>
                        </BeginStoryboard>
                    </EventTrigger.Actions>
                </EventTrigger>
            </Label.Triggers>
        </Label>
    </StackPanel>
</Window>

```

Now, lets break this example down bit-by-bit.

The Role of Storyboards

Working from the innermost element outward, we first encounter the `<DoubleAnimation>` element, which makes use of the same properties we set in procedural code (`To`, `From`, `Duration`, and `RepeatBehavior`):

```

<DoubleAnimation From = "12" To = "100" Duration = "0:0:4"
    RepeatBehavior = "Forever"/>

```

As mentioned, Animation elements are placed within a `<Storyboard>` element, which is used to map the animation object to a given property on the parent type via the `TargetProperty` property—which in this case is `FontSize`. A `<Storyboard>` is always wrapped in a parent element named `<BeginStoryboard>`, which is little more than a way to denote a storyboard's location:

```

<BeginStoryboard>
    <Storyboard TargetProperty = "FontSize">
        <DoubleAnimation From = "12" To = "100" Duration = "0:0:4"
            RepeatBehavior = "Forever"/>
    </Storyboard>
</BeginStoryboard>

```

The Role of Event Triggers

Once the `<BeginStoryboard>` element has been defined, we need to specify some sort of action that will cause the animation to begin executing. WPF has a few different ways to respond to runtime conditions

in markup, one of which is termed a *trigger*. From a high level, you can consider a trigger a way of responding to an event condition in XAML, without the need for procedural code.

Typically, when you respond to an event in C#, you author custom code that will execute when the event occurs. A trigger, however, is just a way to be notified that some event condition has happened (“I’m loaded into memory”, “The mouse is over me!”, “I have focus!”).

Once you’ve been notified that an event condition has occurred, you can start the storyboard. In this example, we are responding to the Label being loaded into memory. Because it is the Label’s Loaded event we are interested in, the <EventTrigger> is placed in the Label’s trigger collection:

```
<Label Content = "Interesting...">
  <Label.Triggers>
    <EventTrigger RoutedEvent = "Label.Loaded">
      <EventTrigger.Actions>
        <BeginStoryboard>
          <Storyboard TargetProperty = "FontSize">
            <DoubleAnimation From = "12" To = "100" Duration = "0:0:4"
                           RepeatBehavior = "Forever"/>
          </Storyboard>
        </BeginStoryboard>
      </EventTrigger.Actions>
    </EventTrigger>
  </Label.Triggers>
</Label>
```

Let’s see another example of defining an animation in XAML, this time using a *key frame* animation.

Animation Using Discrete Key Frames

Unlike the linear interpolation animation objects, which can only move between a starting point and an ending point, the *key frame* counterparts allow us to create a collection of specific values for an animation that should take place at specific times.

To illustrate the use of a discrete key frame type, assume you wish to build a Button control that animates its content so that over the course of three seconds, the value “OK!” appears, one character at a time. You’ll find the following markup in the StringAnimation.xaml file. Copy this markup into your MyXamlPad.exe program and view the results:

```
<Window xmlns="http://schemas.microsoft.com/winfx/2006/xaml/presentation"
        xmlns:x="http://schemas.microsoft.com/winfx/2006/xaml"
        Height="100" Width="300"
        WindowStartupLocation="CenterScreen" Title="Animate String Data!">
  <StackPanel>
    <Button Name="myButton" Height="40"
           FontSize="16pt" FontFamily="Verdana" Width = "100">
      <Button.Triggers>
        <EventTrigger RoutedEvent="Button.Loaded">
          <BeginStoryboard>
            <Storyboard>
              <StringAnimationUsingKeyFrames RepeatBehavior = "Forever">
                <Storyboard.TargetName="myButton" />
                <Storyboard.TargetProperty="Content" />
              </StringAnimationUsingKeyFrames>
            </Storyboard>
          </BeginStoryboard>
        </EventTrigger>
      </Button.Triggers>
    </Button>
  </StackPanel>
</Window>
```

```

        Duration="0:0:3">
        <DiscreteStringKeyFrame Value="" KeyTime="0:0:0" />
        <DiscreteStringKeyFrame Value="O" KeyTime="0:0:1" />
        <DiscreteStringKeyFrame Value="OK" KeyTime="0:0:1.5" />
        <DiscreteStringKeyFrame Value="OK!" KeyTime="0:0:2" />
    </StringAnimationUsingKeyFrames>
</Storyboard>
</BeginStoryboard>
</EventTrigger>
</Button.Triggers>
</Button>
</StackPanel>
</Window>

```

Notice first of all that we have defined an event trigger for our button to ensure that our storyboard executes when the button has loaded into memory. The `StringAnimationUsingKeyFrames` class is in charge of changing the content of the button, via the `Storyboard.TargetName` and `Storyboard.TargetProperty` values.

Within the scope of the `<StringAnimationUsingKeyFrames>` element, we defined four `DiscreteStringKeyFrame` elements, which change the button's `Content` property over the course of two seconds (note that the duration established by `StringAnimationUsingKeyFrames` is a total of three seconds, so we will see a slight pause between the final "!" and looping "O").

Now that you have a better feel for how to build animations in C# code and XAML, let's turn our attention of the role of WPF styles, which make heavy use of graphics, object resources, and animations.

Source Code These loose XAML files can be found under the `XamlAnimations` subdirectory of Chapter 30.

Understanding the Role of WPF Styles

When you are building the UI of a WPF application, it is not uncommon for a family of controls to require a shared look and feel. For example, you may want all button types have the same height, width, background color, and font size for their string content. Though you could handle this by setting each button's individual properties to identical values, such an approach makes it difficult to implement changes down the road, as you'd need to reset the same set of properties on multiple objects for every change.

Thankfully, WPF offers a simple way to constrain the look and feel of related controls using *styles*. Simply put, a WPF style is an object that maintains a collection of property/value pairs. Programmatically speaking, an individual style is represented using the `System.Windows.Style` class. This class has a property named `Setters`, which exposes a strongly typed collection of `Setter` objects. It is the `Setter` object that allows you to define the property/value pairs.

In addition to the `Setters` collection, the `Style` class also defines a few other important members that allow you to incorporate triggers, restrict where a style can be applied, and even create a new style based on an existing style (think of it as "style inheritance"). In particular, be aware of the following members of the `Style` class:

- **Triggers:** Exposes a collection of trigger objects, which allow you to capture various event conditions within a style.
- **BasedOn:** Allows you to build a new style based on an existing style.
- **TargetType:** Allows you to constrain where a style can be applied.

Defining and Applying a Style

In almost every case, a **Style** object will be packaged as an object resource. Like any object resource, you can package it at the window or application level, as well as within a dedicated resource dictionary (this is great, because it makes the **Style** object easily accessible throughout your application). Now recall that the goal is to define a **Style** object that fills (at minimum) the **Setters** collection with a set of property/value pairs.

Create a new WPF application named **WpfStyles** using Visual Studio 2010. Let's build a style that captures the basic font characteristics of a control in our application. Open your **App.xaml** file and define the following named style:

```
<Application x:Class="WpfStyles.App"
  xmlns="http://schemas.microsoft.com/winfx/2006/xaml/presentation"
  xmlns:x="http://schemas.microsoft.com/winfx/2006/xaml"
  StartupUri="MainWindow.xaml">

  <Application.Resources>
    <Style x:Key ="BasicControlStyle">
      <Setter Property = "Control.FontSize" Value = "14"/>
      <Setter Property = "Control.Height" Value = "40"/>
      <Setter Property = "Control.Cursor" Value = "Hand"/>
    </Style>
  </Application.Resources>

</Application>
```

Notice that our “**BasicControlStyle**” adds three **Setter** objects to the internal collection. Now, let's apply this style to a few controls in our main window. Because this style is an object resource, the controls that wish to use it still need to use the **{StaticResource}** or **{DynamicResource}** markup extension to locate the style. When they find the style, they will set the resource item to the identically named **Style** property. Consider the following **<Window>** definition:

```
<Window x:Class="WpfStyles.MainWindow"
  xmlns="http://schemas.microsoft.com/winfx/2006/xaml/presentation"
  xmlns:x="http://schemas.microsoft.com/winfx/2006/xaml"
  Title="A Window with Style!" Height="229"
  Width="525" WindowStartupLocation="CenterScreen">

  <StackPanel>
    <Label x:Name="lblInfo" Content="This style is boring..." 
      Style="{StaticResource BasicControlStyle}" Width="150"/>
    <Button x:Name="btnTestButton" Content="Yes, but we are reusing settings!" 
      Style="{StaticResource BasicControlStyle}" Width="250"/>
  </StackPanel>
```

```
</StackPanel>
</Window>
```

If you run this application, you'll find that both controls support the same cursor, height, and font size.

Overriding Style Settings

Here we have a `Button` and `Label` that have both opted in to the constraints enforced by our style. Of course, if a control wishes to apply a style and then change some of the defined settings, that's fine. For example, the `Button` will now use the `Help` cursor (rather than the `Hand` cursor defined in the style):

```
<Button x:Name="btnTestButton" Content="Yes, but we are reusing settings!"  
        Cursor="Help" Style="{StaticResource BasicControlStyle}" Width="250" />
```

Styles are processed before the individual property settings of the control using the style; therefore controls can "override" settings on a case-by-case basis.

Automatically Applying a Style with TargetType

Currently, our style is defined in such a way that any control can adopt it (and has to do so explicitly by setting the control's `Style` property), given that each property is qualified by the `Control` class. For a program that defines dozens of settings, this would entail a good amount of repeated code. One way to clean this style up a bit is to use the `TargetType` attribute. When you add this attribute to a `Style`'s opening element, you can mark exactly once where it can be applied:

```
<Style x:Key ="BasicControlStyle" TargetType="Control">  
    <Setter Property = "FontSize" Value = "14"/>  
    <Setter Property = "Height" Value = "40"/>  
    <Setter Property = "Cursor" Value = "Hand"/>  
</Style>
```

Note When you are building a style that is using a base class type, you needn't be concerned if you assign a value to a dependency property not supported by derived types. If the derived type does not support a given dependency property, it is ignored.

This is somewhat helpful, but we still have a style that can apply to any control. The `TargetType` attribute is more useful when you wish to define a style that can only be applied to a particular type of control. Add the following new style to the application's resource dictionary:

```
<Style x:Key ="BigGreenButton" TargetType="Button">  
    <Setter Property = "FontSize" Value = "20"/>  
    <Setter Property = "Height" Value = "100"/>
```

```

<Setter Property = "Width" Value = "100"/>
<Setter Property = "Background" Value = "DarkGreen"/>
<Setter Property = "Foreground" Value = "Yellow"/>
</Style>

```

This style will work only on Button controls (or a sub-class of Button) and if you apply it on an incompatible element, you will get markup and compiler errors. If the Button uses this new style like so:

```

<Button x:Name="btnTestButton" Content="This Style ROCKS!"
        Cursor="Help" Style="{StaticResource BigGreenButton}" Width="250" />

```

you'd see the output like that shown in Figure 30-17.



Figure 30-17. Controls with different styles

Subclassing Existing Styles

You can also build new styles using an existing style, via the `BasedOn` property. The style you are extending must have been given a proper `x:Key` in the dictionary, as the derived style will reference it by name using the `{StaticResource}` markup extension. Here is a new style based on “BigGreenButton”, which rotates the button element by 20 degrees:

```

<!-- This style is based on BigGreenButton -->
<Style x:Key ="TiltButton" TargetType="Button" BasedOn = "{StaticResource BigGreenButton}">
    <Setter Property = "Foreground" Value = "White"/>
    <Setter Property = "RenderTransform">
        <Setter.Value>
            <RotateTransform Angle = "20"/>
        </Setter.Value>
    </Setter>
</Style>

```

This time, the output appears as in Figure 30-18.




Figure 30-18. Using a derived style

The Role of Unnamed Styles

Assume you need to ensure that all TextBox controls have the same look and feel. Now assume you have defined a style as an application-level resource, so all windows in the program have access to it. While this is a step in the right direction, if you have numerous windows with numerous TextBox controls, you'll need to set the Style property numerous times!

WPF styles can be implicitly applied to all controls within a given XAML scope. To create such a style, you use the TargetType property but you don't assign the Style resource an x:Key value. This "unnamed style" now applies to all controls of the correct type. Here is another application-level style that will apply automatically to all TextBox controls in the current application.

```
<!-- The default style for all text boxes -->
<Style TargetType="TextBox">
    <Setter Property = "FontSize" Value = "14"/>
    <Setter Property = "Width" Value = "100"/>
    <Setter Property = "Height" Value = "30"/>
    <Setter Property = "BorderThickness" Value = "5"/>
    <Setter Property = "BorderBrush" Value = "Red"/>
    <Setter Property = "FontStyle" Value = "Italic"/>
</Style>
```

We can now define any number of TextBox controls and they will automatically get the defined look. If a given TextBox does not want this default look and feel, it can opt out by setting the Style property to {x:Null}. For example, txtTest will get the default unnamed style, while txtTest2 is doing things its own way:

```
<TextBox x:Name="txtTest"/>
<TextBox x:Name="txtTest2" Style="{x:Null}" BorderBrush="Black"
        BorderThickness="5" Height="60" Width="100" Text="Ha!"/>
```

Defining Styles with Triggers

WPF styles can also contain triggers, by packaging up `Trigger` objects within the `Triggers` collection of the `Style` object. Using triggers in a style allows you to define certain `<Setter>` elements in such a way that they will be applied only if a given trigger condition is true. For example, perhaps you want to increase the size of a font when the mouse is over a button. Or maybe you want to make sure that the text box with the current focus is highlighted with a given color. Triggers are very useful for these sorts of situations, in that they allow you to take specific actions when a property changes without the need to author explicit C# code in a code-behind file.

Here is an update to the `TextBox` style that ensures that when a `TextBox` has the input focus, it will receive a yellow background:

```
<!-- The default style for all text boxes -->
<Style TargetType="TextBox">
    <Setter Property = "FontSize" Value = "14"/>
    <Setter Property = "Width" Value = "100"/>
    <Setter Property = "Height" Value = "30"/>
    <Setter Property = "BorderThickness" Value = "5"/>
    <Setter Property = "BorderBrush" Value = "Red"/>
    <Setter Property = "FontStyle" Value = "Italic"/>
    <!-- The following setter will only be applied when the text box is
        in focus. -->
    <Style.Triggers>
        <Trigger Property = "IsFocused" Value = "True">
            <Setter Property = "Background" Value = "Yellow"/>
        </Trigger>
    </Style.Triggers>
</Style>
```

If you test this style, you'll find that as you tab between various `TextBox` objects, the currently selected `TextBox` has a bright yellow background (provided it has not opted out by assigning `{x:Null}` to the `Style` property).

Property triggers are also very smart, in that when the trigger's condition is *not true*, the property automatically receives the default assigned value. Therefore, as soon as a `TextBox` loses focus, it also automatically becomes the default color without any work on your part. In contrast, event triggers (examined when we looked at WPF animations) do not automatically revert to a previous condition.

Defining Styles with Multiple Triggers

Triggers can also be designed in such a way that the defined `<Setter>` elements will be applied when *multiple conditions* are true (similar to building an `if` statement for multiple conditions). Let's say we want to set the background of a `TextBox` to Yellow only if it has the active focus and the mouse is hovering within its boundaries. To do so, we can make use of the `<MultiTrigger>` element to define each condition:

```
<!-- The default style for all text boxes -->
<Style TargetType="TextBox">
    <Setter Property = "FontSize" Value = "14"/>
    <Setter Property = "Width" Value = "100"/>
    <Setter Property = "Height" Value = "30"/>
```

```

<Setter Property = "BorderThickness" Value = "5"/>
<Setter Property = "BorderBrush" Value = "Red"/>
<Setter Property = "FontStyle" Value = "Italic"/>
<!-- The following setter will only be applied when the text box is
in focus AND the mouse is over the text box. --&gt;
&lt;Style.Triggers&gt;
  &lt;MultiTrigger&gt;
    &lt;MultiTrigger.Conditions&gt;
      &lt;Condition Property = "IsFocused" Value = "True"/&gt;
      &lt;Condition Property = "IsMouseOver" Value = "True"/&gt;
    &lt;/MultiTrigger.Conditions&gt;
    &lt;Setter Property = "Background" Value = "Yellow"/&gt;
  &lt;/MultiTrigger&gt;
&lt;/Style.Triggers&gt;
&lt;/Style&gt;
</pre>

```

Animated Styles

Styles can also incorporate triggers that kick off an animation sequence. Here is one final style that, when applied to Button controls, will cause the control to grow and shrink in size when the mouse is inside the button's surface area:

```

<!-- The growing button style! -->
<Style x:Key = "GrowingButtonStyle" TargetType="Button">
  <Setter Property = "Height" Value = "40"/>
  <Setter Property = "Width" Value = "100"/>
  <Style.Triggers>
    <Trigger Property = "IsMouseOver" Value = "True">
      <Trigger.EnterActions>
        <BeginStoryboard>
          <Storyboard TargetProperty = "Height">
            <DoubleAnimation From = "40" To = "200"
                            Duration = "0:0:2" AutoReverse="True"/>
          </Storyboard>
        </BeginStoryboard>
      </Trigger.EnterActions>
    </Trigger>
  </Style.Triggers>
</Style>

```

Here, our triggers collection is on the lookout for the IsMouseOver property to return true. When this occurs, we define a `<Trigger.EnterActions>` element to execute a simple storyboard that forces the button to grow to a Height value of 200 (and then return to a Height of 40) over 2 seconds. If you wish to perform other property changes, you could also define a `<Trigger.ExitActions>` scope to define any custom actions to take when IsMouseOver is false.

Assigning Styles Programmatically

Recall that a style can be applied at runtime as well. This can be helpful if you want to let end users choose how their UI looks and feels, or if you need to enforce a look and feel based on security settings (e.g., the “DisableAllButton” style) or what have you.

During this project, you have defined a number of styles, many of which can apply to `Button` controls. So, let’s retool the UI of our main window to allow the user to pick from some of these styles by selecting names in a `ListBox`. Based on the user’s selection, we will apply the appropriate style. Here is the new (and final) markup for the `<Window>` element:

```
<Window x:Class="WpfStyles.MainWindow"
    xmlns="http://schemas.microsoft.com/winfx/2006/xaml/presentation"
    xmlns:x="http://schemas.microsoft.com/winfx/2006/xaml"
    Height="350" Title="A Window with Style!"'
    Width="525" WindowStartupLocation="CenterScreen">

    <DockPanel>
        <StackPanel Orientation="Horizontal" DockPanel.Dock="Top">
            <Label Content="Please Pick a Style for this Button" Height="50"/>
            <ListBox x:Name="lstStyles" Height="80" Width="150" Background="LightBlue"
                SelectionChanged="comboStyles_Changed" />
        </StackPanel>
        <Button x:Name="btnStyle" Height="40" Width="100" Content="OK!"/>
    </DockPanel>

</Window>
```

The `ListBox` control (named `lstStyles`) will be filled dynamically within the window’s constructor like so:

```
public MainWindow()
{
    InitializeComponent();

    // Fill the list box with all the Button
    // styles.
    lstStyles.Items.Add("GrowingButtonStyle");
    lstStyles.Items.Add("TiltButton");
    lstStyles.Items.Add("BigGreenButton");
    lstStyles.Items.Add("BasicControlStyle");
}
```

The final task is to handle the `SelectionChanged` event in the related code file. Notice in the following code how we are able to extract the current resource by name, using the inherited `TryFindResource()` method:

```
private void comboStyles_Changed(object sender, SelectionChangedEventArgs e)
{
    // Get the selected style name from the list box.
    Style currStyle = (Style)
        TryFindResource(lstStyles.SelectedValue);
```

```

if (currStyle != null)
{
    // Set the style of the button type.
    this.btnAdd.Style = currStyle;
}
}

```

When you run this application, you can pick from one of these four button styles on the fly. Figure 30-19 shows our completed application.




Figure 30-19. Controls with different styles

■ **Source Code** The WpfStyles project can be found under the Chapter 30 subdirectory.

Generating Styles with Expression Blend

To wrap up our examination of WPF styles, let's take a quick tour of how Blend can help automate the process of style construction. Again, however, I'll hold off discussing the animation editor (and related topics, such as triggers and control templates) until the next chapter. Here I want to point out the default "Simple Styles" of the Assets Library.

Working with Default Visual Styles

Blend ships with a number of default styles for common controls, referred to as the *Simple Styles*. If you open the Assets Library, you can locate the Styles in the tree view on the left-hand side (Figure 30-20).




Figure 30-20. Blend's default styles

When you select one of these simple styles, a few things happen. First, the control is declared with the {DynamicResource} markup extension. For example, if you place a Simple Button Style on your designer, you'll find XAML similar to:

```
<Button Margin="116,49,220,0" Style="{DynamicResource SimpleButton}"
    VerticalAlignment="Top" Height="63" Content="Button"/>
```

Strangely enough, the control will look identical to a normal Button. However, if you take a look in your Project window, you will see Blend has added a new file named Simple Styles.xaml (Figure 30-21).




Figure 30-21. This is a resource dictionary!

If you double-click on this item and open the XAML editor, you will see it is a very large <ResourceDictionary> of default control styles. Furthermore, if you open the Blend Resources window, you'll see each item is listed and can be edited by clicking a given entry (Figure 30-22).




Figure 30-22. Selecting a default style for editing

If you click on the `SimpleButton` icon in the Resources view, a new designer will open that you can use to change the style to your heart's content using Blend's standard editing tools (the Properties window, animation editor, etc). Consider Figure 30-23




Figure 30-23. Editing a default style

The beauty of this approach is that the `Simple Styles.xaml` file is merged with your application resources and, therefore, all of your local edits will automatically be compiled into your application. Taking advantage of default simple styles essentially allows you to use starter markup for a control's normal look and feel, and customize it on a per-project basis. Here's the markup that would be in your `App.xaml` file:

```
<Application
  xmlns="http://schemas.microsoft.com/winfx/2006/xaml/presentation"
  xmlns:x="http://schemas.microsoft.com/winfx/2006/xaml"
  x:Class="WpfApplication6.App"
  StartupUri="MainWindow.xaml">
  <Application.Resources>
    <!-- Resources scoped at the Application level should be defined here. -->
    <ResourceDictionary>
      <ResourceDictionary.MergedDictionaries>
        <ResourceDictionary Source="Simple Styles.xaml"/>
      </ResourceDictionary.MergedDictionaries>
    </ResourceDictionary>
  </Application.Resources>
</Application>
```

Well, that wraps up this chapter. The next chapter will complete our examination of WPF by looking at the role of control templates and custom `UserControl` classes. Along the way, I'll also illustrate several new aspects of working with Expression Blend.

Summary

The first part of this chapter examined the resource management system of WPF. We began by looking at how to work with binary resources, then quickly turned our attention of the role of object resources. As you learned, object resources are named blobs of XAML that can be stored at various locations, in order to reuse content.

Next, you learned about WPF's animation framework. Here you had a chance to create some animations using C# code, as well as with XAML. You learned that if you define an animation in markup, you use Storyboard elements and triggers to control execution.

We wrapped up by looking at the WPF style mechanism, which makes heavy use of graphics, object resources, and animations. Along the way, you learned about how you can use Blend to simplify the creation of styles using default simple styles as a starting point.



WPF Control Templates and UserControls

This chapter concludes your investigation of the Windows Presentation Foundation (WPF) programming model by introducing you to the process of building customized controls. While it is true that the content model and style mechanism do allow you to add unique bits to a standard WPF control, the process of building custom templates and `UserControls` allows you to fully define how a control should render its output, respond to state transitions, and integrate into the WPF APIs.

This chapter begins by examining two topics that are important when creating a custom control, specifically *dependency properties* and *routed events*. Once you understand these topics, you will then learn about the role of a *default template* and how to view them programmatically at runtime.

Once this foundation has been laid, the remainder of this chapter will examine how to build custom `UserControl` classes using Visual Studio 2010 and Expression Blend. Along the way, you will learn more about the WPF trigger framework (first introduced in Chapter 30), as well as the new .NET 4.0 Visual State Manager (VSM). Finally, you will learn how to use the animation editor of Expression Blend to define state transitions and see how to incorporate your custom controls into larger WPF applications.

Understanding the Role of Dependency Properties

Like any .NET API, WPF makes use of each member of the .NET type system (classes, structures, interfaces, delegates, enumerations) and each type member (properties, methods, events, constant data, read-only fields, etc.) within its implementation. However, WPF also supports a unique programming concept termed a *dependency property*.

Note Dependency properties are also part of the Windows Workflow Foundation (WF) API. While a WF dependency property is constructed in a similar manner as a WPF dependency property, WF uses a different technology stack to implement them.

Like a “normal” .NET property (often termed a *CLR property* in the WPF literature), dependency properties can be set declaratively using XAML or programmatically within a code file. Furthermore, dependency properties (like CLR properties) ultimately exist to encapsulate data fields of a class and can be configured as read-only, write-only or read-write.

To make matters more interesting, in almost every case you will be blissfully unaware that you have actually set (or accessed) a dependency property as opposed to a CLR property! For example, the Height and Width properties that WPF controls inherit from FrameworkElement, as well as the Content member inherited from ControlContent, are all, in fact, dependency properties:

```
<!-- Set three dependency properties! -->
<Button x:Name = "btnMyButton" Height = "50" Width = "100" Content = "OK"/>
```

Given all of these similarities, why does WPF defines a new term for such a familiar concept? The answer lies in how a dependency property is implemented within the class. You'll see a coding example in just a little bit; however, from a high level, all dependency properties are created in the following manner:

- First, the class that defined a dependency property must have DependencyObject in its inheritance chain.
- A single dependency property is represented as a public, static, read-only field in the class of type DependencyProperty. By convention, this field is named by suffixing the word Property to the name of the CLR wrapper (see final bullet point).
- The DependencyProperty variable is registered via a static call to DependencyProperty.Register(), which typically occurs in a static constructor or inline when the variable is declared.
- Finally, the class will define a XAML-friendly CLR property, which makes calls to methods provided by DependencyObject to get and set the value.

Once implemented, dependency properties provide a number of powerful features that are used by various WPF technologies including data binding, animation services, styles, and so forth. In a nutshell, the motivation of dependency properties is to provide a way to compute the value of a property based on the value of other inputs. Here is a list of some of these key benefits, which go well beyond those of the simple data encapsulation found with a CLR property:

- Dependency properties can inherit their values from a parent element's XAML definition. For example, if you defined a value for the FontSize attribute in the opening tag of a <Window>, all controls in that Window would have the same font size by default.
- Dependency properties support the ability to have values set by elements contained within their XAML scope, such as a Button setting the Dock property of a DockPanel parent. (Recall from Chapter 28 that *attached properties* do this very thing, as attached properties are a form of dependency properties.)
- Dependency properties allow WPF to compute a value based on multiple external values, which can be very important for animation and data binding services.
- Dependency properties provide infrastructure support for WPF triggers (also used quite often when working with animation and data binding).

Now remember, in many cases you will interact with an existing dependency property in a manner identical to a normal CLR property (thanks to the XAML wrapper). However, when I covered data binding in Chapter 28, you learned that if you need to establish a data binding in code, you must call the `SetBinding()` method on the object that is the destination of the operation and specify the *dependency property* it will operate on:

```
private void SetBindings()
{
    Binding b = new Binding();
    b.Converter = new MyDoubleConverter();
    b.Source = this.mySB;
    b.Path = new PropertyPath("Value");

    // Specify the dependency property!
    this.labelSBThumb.SetBinding(Label.ContentProperty, b);
}
```

You also saw similar code when you examined how to start an animation in code, back in the previous chapter:

```
// Specify the dependency property!
rt.BeginAnimation(RotateTransform.AngleProperty, dblAnim);
```

The only time when you would need to build your own custom dependency property is when you are authoring a custom WPF control. For example, if you are building a `UserControl` which defines four custom properties and you want these properties to integrate well within the WPF API, you should author them using dependency property logic.

Specifically, if your properties need to be the target of a data binding or animation operation, if the property must broadcast when it has changed, if it must be able to work as a Setter in a WPF style, or if it must be able to receive their values from a parent element, a normal CLR property will *not* be enough. If you were to use a normal CLR property, other programmers may indeed be able to get and set a value; however, if they attempt to use your properties within the context of a WPF service, things will not work as expected. Because you can never know how others might want to interact with the properties of your custom `UserControl` classes, you should get in the habit of *always* defining dependency properties when building custom controls.

Examining an Existing Dependency Property

Before you learn how to build a custom dependency property, let's take a look at how the `Height` property of the `FrameworkElement` class has been implemented internally. The relevant code is shown here (with my included comments); however, you can view the same code yourself if you make use of `reflector.exe` (just use the `View | Search` option).

```
// FrameworkElement is-a DependencyObject.
public class FrameworkElement : UIElement, IFrameworkInputElement,
    IInputElement, ISupportInitialize, IHaveResources, IQueryAmbient
{
    ...
    // A static readonly field of type DependencyProperty.
```

```

public static readonly DependencyProperty HeightProperty;

// The DependencyProperty field is often registered
// in the static constructor of the class.
static FrameworkElement()
{
    ...
    HeightProperty = DependencyProperty.Register(
        "Height",
        typeof(double),
        typeof(FrameworkElement),
        new FrameworkPropertyMetadata((double) 1.0 / (double) 0.0,
            FrameworkPropertyMetadataOptions.AffectsMeasure,
            new PropertyChangedCallback(FrameworkElement.OnTransformDirty)),
            new ValidateValueCallback(FrameworkElement.IsWidthHeightValid));
}

// The CLR wrapper, which is implemented using
// the inherited GetValue()/SetValue() methods.
public double Height
{
    get { return (double) base.GetValue(HeightProperty); }
    set { base.SetValue(HeightProperty, value); }
}
}

```

As you can see, dependency properties require quite a bit of additional code from a normal CLR property! And in reality, a dependency can be even more complex than what you see here (thankfully, many implementations are simpler than Height).

First and foremost, remember that if a class wants to define a dependency property, it must have `DependencyObject` in the inheritance chain, as this is the class which defines the `GetValue()` and `SetValue()` methods used in the CLR wrapper. Since `FrameworkElement` is-a `DependencyObject`, this requirement is satisfied.

Next, recall that the entity which will hold the actual value of the property (a `double` in the case of Height) is represented as a public, static read-only field of type `DependencyProperty`. The name of this field should, by convention, always be named by suffixing the word `Property` to the name of the related CLR wrapper, like so:

```
public static readonly DependencyProperty HeightProperty;
```

Given that dependency properties are declared as static fields, they are typically created (and registered) within the static constructor of the class. The `DependencyProperty` object is created via a call to the static `DependencyProperty.Register()` method. This method has been overloaded many times; however, in the case of Height, `DependencyProperty.Register()` is invoked as follows:

```

HeightProperty = DependencyProperty.Register(
    "Height",
    typeof(double),
    typeof(FrameworkElement),
    new FrameworkPropertyMetadata((double)0.0,
        FrameworkPropertyMetadataOptions.AffectsMeasure,

```

```

new PropertyChangedCallback(FrameworkElement.OnTransformDirty)),
new ValidateValueCallback(FrameworkElement.IsWidthHeightValid));

```

The first argument to `DependencyProperty.Register()` is the name of the normal CLR property on the class (`Height` in this case), while the second argument is the type information of the underlying data type it is encapsulating (a `double`). The third argument specifies the type information of the class that this property belongs to (`FrameworkElement` in this case). While this might seem redundant (after all, the `HeightProperty` field is already defined within the `FrameworkElement` class), this is a very clever aspect of WPF in that it allows one class to register properties on another (even if the class definition has been sealed!).

The fourth argument passed to `DependencyProperty.Register()` in this example is what really gives dependency properties their own unique flavor. Here a `FrameworkPropertyMetadata` object is passed that describes various details regarding how WPF should handle this property with respect to callback notifications (if the property needs to notify others when the value changes) and various options (represented by the `FrameworkPropertyMetadataOptions` enum) that control what is effected by the property in question (Does it work with data binding?, Can it be inherited?, etc.). In this case, the constructor arguments of `FrameworkPropertyMetadata` break down as so:

```

new FrameworkPropertyMetadata(
    // Default value of property.
    (double)0.0,
    // Metadata options.
    FrameworkPropertyMetadataOptions.AffectsMeasure,
    // Delegate pointing to method called when property changes.
    new PropertyChangedCallback(FrameworkElement.OnTransformDirty)
)

```

Because the final argument to the `FrameworkPropertyMetadata` constructor is a delegate, note that its constructor parameter is pointing to a static method on the `FrameworkElement` class named `OnTransformDirty()`. I won't bother to show the code behind this method, but be aware that any time you are building a custom dependency property, you can specify a `PropertyChangedCallback` delegate to point to a method that will be called when your property value has been changed.

This brings me to the final parameter passed to the `DependencyProperty.Register()` method, a second delegate of type `ValidateValueCallback`, which points to a method on the `FrameworkElement` class which is called to ensure the value assigned to the property is valid:

```
new ValidateValueCallback(FrameworkElement.IsWidthHeightValid)
```

This method contains logic you might normally expect to find in the set block of a property (more information on this point in the next section):

```

private static bool IsWidthHeightValid(object value)
{
    double num = (double) value;
    return ((!DoubleUtil.IsNaN(num) && (num >= 0.0))
        && !double.IsPositiveInfinity(num));
}

```

Once the `DependencyProperty` object has been registered, the final task is to wrap the field within a normal CLR property (`Height` in this case). Notice, however, that the get and set scopes do not simply return or set a class-level double-member variable, but do so indirectly using the `GetValue()` and `SetValue()` methods from the `System.Windows.DependencyObject` base class:

```
public double Height
{
    get { return (double) base.GetValue(HeightProperty); }
    set { base.SetValue(HeightProperty, value); }
}
```

Important Notes Regarding CLR Property Wrappers

So, just to recap the story thus far, dependency properties look like a normal every day property when you get or set their values in XAML or code, but behind the scenes they are implemented with much more elaborate coding techniques. Remember, the whole reason to go through this process is to build a custom control that has custom properties that need to integrate with WPF services that demand communication with a dependency property (e.g., animation, data binding, and styles).

Even though part of the implementation of a dependency property includes defining a CLR wrapper, *you should never put validation logic in the set block*. For that matter, the CLR wrapper of a dependency property *should never do anything other than call GetValue() or SetValue()*.

The reason is that the WPF runtime has been constructed in such a way that when you write XAML that seems to set a property, such as

```
<Button x:Name="myButton" Height="100" .../>
```

the runtime will completely bypass the set block of the `Height` property and *directly* call `SetValue()`! The reason for this odd behavior has to do with a simple optimization technique. If the WPF runtime were to directly call the set block of the `Height` property, it would have to perform runtime reflection to figure out where the `DependencyProperty` field (specified by the first argument to `SetValue()`) is located, reference it in memory, and so forth. The same story holds true if you were write XAML which retrieves the value of the `Height` property; `GetValue()` is called directly.

Since this is the case, why do you need to build this CLR wrapper at all? Well, WPF XAML does not allow you to call functions in markup, so the following markup would be an error:

```
<!-- Nope! Can't call methods in WPF XAML! -->
<Button x:Name="myButton" this.SetValue("100") .../>
```

In effect, when you set or get a value in markup using the CLR wrapper, think of it as a way to tell the WPF runtime, "Hey! Go call `GetValue()` / `SetValue()` for me, since I can't do it in markup!"

Now, what if you call the CLR wrapper in code like so:

```
Button b = new Button();
b.Height = 10;
```

In this case, if the set block of the `Height` property contained code other than a call to `SetValue()`, it *would* execute as the WPF XAML parser optimization is not involved. The short answer is that when registering a dependency property, use a `ValidateValueCallback` delegate to point to a method that performs the data validation. This ensures that the correct behavior will occur, regardless of whether you use XAML or code to get/set a dependency property.

Building a Custom Dependency Property

If you have a slight headache at this point in the chapter, this is a perfectly normal response. Building dependency properties can take some time to get used to. However, for better or worse, it is part of the process of building many custom WPF controls, so let's take a look at how to build a dependency property.

Begin by creating a new WPF Application named `CustomDepPropApp`. Now, using the Project menu, activate the Add UserControl menu option, and create a control named `ShowNumberControl.xaml` (Figure 31-1).




Figure 31-1. Inserting a new custom `UserControl`

Note You will learn more details about the WPF `UserControl` later in this chapter, so just following along as shown for now.

Just like a window, WPF `UserControl` types have a XAML file and a related code file. Update the XAML of your user control to define a single `Label` control in the Grid:

```
<UserControl x:Class="CustomDepPropApp.ShowNumberControl"
    xmlns="http://schemas.microsoft.com/winfx/2006/xaml/presentation"
```

```

xmlns:x="http://schemas.microsoft.com/winfx/2006/xaml"
xmlns:mc="http://schemas.openxmlformats.org/markup-compatibility/2006"
xmlns:d="http://schemas.microsoft.com/expression/blend/2008"
mc:Ignorable="d"
d:DesignHeight="300" d:DesignWidth="300">
<Grid>
    <Label x:Name="numberDisplay" Height="50" Width="200" Background="LightBlue"/>
</Grid>
</UserControl>

```

In the code file of this custom control, create a normal, everyday .NET property which wraps an int and sets the Content property of the Label with the new value:

```

public partial class ShowNumberControl : UserControl
{
    public ShowNumberControl()
    {
        InitializeComponent();
    }

    // A normal, everyday .NET property
    private int currNumber = 0;
    public int CurrentNumber
    {
        get { return currNumber; }
        set
        {
            currNumber = value;
            numberDisplay.Content = CurrentNumber.ToString();
        }
    }
}

```

Now, update the XAML definition of your window to declare an instance of your custom control within a StackPanel layout manager. Because your custom control is not part of the core WPF assembly stack, you will need to define a custom XML namespace which maps to your control (see Chapter 27). Here is the required markup:

```

<Window x:Class="CustomDepPropApp.MainWindow"
    xmlns="http://schemas.microsoft.com/winfx/2006/xaml/presentation"
    xmlns:x="http://schemas.microsoft.com/winfx/2006/xaml"
    xmlns:myCtrls="clr-namespace:CustomDepPropApp"
    Title="Simple Dependency Property App" Height="150" Width="250"
    WindowStartupLocation="CenterScreen">

    <StackPanel>
        <myCtrls:ShowNumberControl x:Name="myShowNumberCtrl" CurrentNumber="100"/>
    </StackPanel>
</Window>

```

As you can see, the Visual Studio 2010 designer appears to correctly display the value that you set in the CurrentNumber property (Figure 31-2).



Figure 31-2. It appears your property works as expected...

However, what if you want to apply an animation object to the CurrentNumber property so that the value changes from 100 to 200 over the period of 10 seconds? If you wanted to do so in markup, you might update your <myCtrls:ShowNumberControl> scope as so:

```
<myCtrls:ShowNumberControl x:Name="myShowNumberCtrl" CurrentNumber="100">
<myCtrls:ShowNumberControl.Triggers>
  <EventTrigger RoutedEvent = "myCtrls:ShowNumberControl.Loaded">
    <EventTrigger.Actions>
      <BeginStoryboard>
        <Storyboard TargetProperty = "CurrentNumber">
          <Int32Animation From = "100" To = "200" Duration = "0:0:10"/>
        </Storyboard>
      </BeginStoryboard>
    </EventTrigger.Actions>
  </EventTrigger>
</myCtrls:ShowNumberControl.Triggers>
</myCtrls:ShowNumberControl>
```

If you attempt to run your application, the animation object cannot find a proper target, so it is ignored. The reason is that the CurrentNumber property has not been registered as a dependency property! To fix matters, return to the code file of your custom control, and completely comment out the current property logic (including the private backing field). Now, position your mouse cursor within the scope of the class and type in the propdp code snippet (Figure 31-3).




Figure 31-3. The `propdp` code snippet provides a starting point for building a dependency property

After you have typed `propdp`, press the Tab key twice. You will find the snippet expands to give you the basic skeleton of a dependency property (Figure 31-4).




Figure 31-4. The expanded snippet

The simplest version of the `CurrentNumber` property will look like so:

```

public partial class ShowNumberControl : UserControl
{
    public int CurrentNumber
    {
        get { return (int)GetValue(CurrentNumberProperty); }
        set { SetValue(CurrentNumberProperty, value); }
    }

    public static readonly DependencyProperty CurrentNumberProperty =
        DependencyProperty.Register("CurrentNumber",
            typeof(int),

```

```

        typeof(ShowNumberControl),
        new UIPropertyMetadata(0));
    ...
}

```

This is similar to what you saw in the implementation of the `Height` property; however, the code snippet registers the property inline rather than within a static constructor (which is fine). Also notice that a `UIPropertyMetadata` object is used to define the default value of the integer (0) rather than the more complex `FrameworkPropertyMetadata` object.

Adding a Data Validation Routine

Although you now have a dependency property named `CurrentNumber`, you still won't see your animation take hold. The next adjustment you might want to make is to specify a function to call to perform some data validation logic. For this example, assume that you need to ensure that the value of `CurrentNumber` is between 0 and 500.

To do so, add a final argument to the `DependencyProperty.Register()` method of type `ValidateValueCallback`, which points to a method named `ValidateCurrentNumber`.

`ValidateValueCallback` is a delegate that can only point to methods returning `bool` and take an object as the only argument. This object represents the new value that is being assigned. Implement `ValidateCurrentNumber` to return `true` or `false`, if the incoming value is within the expected range:

```

public static readonly DependencyProperty CurrentNumberProperty =
    DependencyProperty.Register("CurrentNumber", typeof(int), typeof(ShowNumberControl),
        new UIPropertyMetadata(100),
        new ValidateValueCallback(ValidateCurrentNumber));

public static bool ValidateCurrentNumber(object value)
{
    // Just a simple business rule. Value must be between 0 and 500.
    if (Convert.ToInt32(value) >= 0 && Convert.ToInt32(value) <= 500)
        return true;
    else
        return false;
}

```

Responding to the Property Change

OK, so now you have a valid number, but still no animation. The final change you need to make is to specify a second argument to the constructor of `UIPropertyMetadata`, which is a `PropertyChangedCallback` object. This delegate can point to any method that takes a `DependencyObject` as the first parameter and a `DependencyPropertyChangedEventArgs` as the second. First, update your code as so:

```

// Note the second param of UIPropertyMetadata constructor.
public static readonly DependencyProperty CurrentNumberProperty =
    DependencyProperty.Register("CurrentNumber", typeof(int), typeof(ShowNumberControl),
        new UIPropertyMetadata(100,
            new PropertyChangedCallback(PropertyChanged)));

```

```
new ValidateValueCallback(ValidateCurrentNumber));
```

Within the `CurrentNumberChanged()` method, your ultimate goal is to change the `Content` of the `Label` to the new value assigned by the `CurrentNumber` property. You have one big problem, however: the `CurrentNumberChanged()` method is static, as it must be to work with the static `DependencyProperty` object. So how are you supposed to gain access to the `Label` for the current instance of `ShowNumberControl`? That reference is contained in the first `DependencyObject` parameter. You can find the new value using the incoming event arguments. Here is the necessary code which will change the `Content` property of the `Label`:

```
private static void CurrentNumberChanged(DependencyObject depObj,
    DependencyPropertyChangedEventArgs args)
{
    // Cast the DependencyObject into ShowNumberControl
    ShowNumberControl c = (ShowNumberControl)depObj;

    // Get the Label control in the ShowNumberControl.
    Label theLabel = c.numberDisplay;

    // Set the label with the new value.
    theLabel.Content = args.NewValue.ToString();
}
```

Whew! That was a long way to go just to change the output of a label. The benefit is that your `CurrentNumber` dependency property can now be the target of a WPF style, an animation object, the target of a data binding operation, and so forth. Figure 31-5 shows your completed application (and yes, it really is changing the value while running).




Figure 31-5. Animation at last!

That wraps up your look at WPF dependency properties. While I hope you have a much better idea about what these constructs allow you to do and have a better idea of how to make your own, please be aware that there are many details I have not covered here.

If you find yourself in a position where you are building a number of custom controls which support custom properties, please look up the topic "Properties" under the "WPF Fundamentals" node of the .NET Framework 4.0 SDK documentation. Here, you will find many more examples of building dependency properties, attached properties, various ways to configure property metadata, and a slew of other details.

Source Code The CustomDepPropApp project is included under the Chapter 31 subdirectory.

Understanding Routed Events

Properties are not the only .NET programming construct to be given a facelift in order to work well within the WPF API. The standard CLR event model has also been refined just a bit to ensure that events can be processed in a manner that is fitting for XAML's description of a tree of objects. Assume you have a new WPF Application project named WPFRoutedEventArgs. Now, update the XAML description of the initial window by adding the following `<Button>` control which defines some complex content:

```
<Button Name="btnClickMe" Height="75" Width = "250"
    Click ="btnClickMe_Clicked">
    <StackPanel Orientation ="Horizontal">
        <Label Height="50" FontSize ="20">Fancy Button!</Label>
        <Canvas Height ="50" Width = "100" >
            <Ellipse Name = "outerEllipse" Fill ="Green" Height ="25"
                Width ="50" Cursor="Hand" Canvas.Left="25" Canvas.Top="12"/>
            <Ellipse Name = "innerEllipse" Fill ="Yellow" Height = "15" Width = "36"
                Canvas.Top="17" Canvas.Left="32"/>
        </Canvas>
    </StackPanel>
</Button>
```

Notice in the `<Button>`'s opening definition you have handled the `Click` event by specifying the name of a method to be called when the event is raised. The `Click` event works with the `RoutedEventHandler` delegate, which expects an event handler that takes an object as the first parameter and a `System.Windows.RoutedEventArgs` as the second. Implement this handler as so:

```
public void btnClickMe_Clicked(object sender, RoutedEventArgs e)
{
    // Do something when button is clicked.
    MessageBox.Show("Clicked the button");
}
```

If you run your application, you will see this message box display, regardless of which part of the button's content you click on (the green Ellipse, the yellow Ellipse, the Label or the Button's surface). This is a good thing. Imagine how tedious WPF event handling would be if you were forced to handle a `Click` event for each and every one of these sub-elements. Not only would the creation of separate event handlers for each aspect of the Button be labor intensive, you would end up with some mighty nasty code to maintain down the road.

Thankfully, WPF *routed events* take care of ensuring that your single `Click` event handler will be called regardless of which part of the button is clicked automatically. Simply put, the routed events model automatically propagates an event up (or down) a tree of objects, looking for an appropriate handler.

Specifically speaking, a routed event can make use of three *routing strategies*. If an event is moving from the point of origin up to other defining scopes within the object tree, the event is said to be a *bubbling event*. Conversely, if an event is moving from the outermost element (e.g., a `Window`) down to

the point of origin, the event is said to be a *tunneling event*. Finally, if an event is raised and handled only by the originating element (which is what could be described as a normal CLR event), it is said to be a *direct event*.

The Role of Routed Bubbling Events

In the current example, if the user clicks the inner yellow oval, the Click event bubbles out to the next level of scope (the Canvas), then to the StackPanel, and finally to the Button where the Click event handler is handled. In a similar way, if the user clicks the Label, the event is bubbled to the StackPanel and then finally to the Button element.

Given this bubbling routed event pattern, you have no need to worry about registering specific Click event handlers for all members of a composite control. However, if you wished to perform custom clicking logic for multiple elements within the same object tree, you can do so.

By way of illustration, assume you need to handle the clicking of the outerEllipse control in a unique manner. First, handle the MouseDown event for this subelement (graphically rendered types such as the Ellipse do not support a click event; however, they can monitor mouse button activity via - MouseDown, MouseUp, etc.):

```
<Button Name="btnClickMe" Height="75" Width = "250"
    Click ="btnClickMe_Clicked">
    <StackPanel Orientation ="Horizontal">
        <Label Height="50" FontSize ="20">Fancy Button!</Label>
        <Canvas Height ="50" Width = "100" >
            <Ellipse Name = "outerEllipse" Fill ="Green"
                Height ="25" MouseDown ="outerEllipse_MouseDown"
                Width ="50" Cursor="Hand" Canvas.Left="25" Canvas.Top="12"/>
            <Ellipse Name = "innerEllipse" Fill ="Yellow" Height = "15" Width ="36"
                Canvas.Top="17" Canvas.Left="32"/>
        </Canvas>
    </StackPanel>
</Button>
```

Then implement an appropriate event handler, which for illustrative purposes will simply change the Title property of the main window:

```
public void outerEllipse_MouseDown(object sender, MouseButtonEventArgs e)
{
    // Change title of window.
    this.Title = "You clicked the outer ellipse!";
}
```

With this, you can now take different courses of action depending on where the end user has clicked (which boils down to the outer ellipse and everywhere else within the button's scope).

Note Routed bubbling events always move from the point of origin to the *next defining scope*. Thus, in this example, if you were to click the `innerEllipse` object, the event would be bubbled to the `Canvas`, *not* to the `outerEllipse`, as they are both `Ellipse` types within the scope of `Canvas`.

Continuing or Halting Bubbling

Currently, if the user clicks the `outerEllipse` object, it will trigger the registered `MouseDown` event handler for this `Ellipse` object, at which point the event bubbles to the button's `Click` event. If you wish to inform WPF to stop bubbling up the tree of objects, you can set the `Handled` property of the `RoutedEventArgs` parameter to `true`:

```
public void outerEllipse_MouseDown(object sender, MouseButtonEventArgs e)
{
    // Change title of window.
    this.Title = "You clicked the outer ellipse!";

    // Stop bubbling!
    e.Handled = true;
}
```

In this case, you would find that the title of the window is changed, but you will not see the `MessageBox` displayed by the `Click` event handler of the `Button`. In a nutshell, routed bubbling events make it possible to allow a complex group of content to act either as a single logical element (e.g., a `Button`) or as discrete items (e.g., an `Ellipse` within the `Button`).

The Role of Routed Tunneling Events

Strictly speaking, routed events can be *bubbling* (as just described) or *tunneling* in nature. Tunneling events (which all begin with the `Preview` suffix—e.g., `PreviewMouseDown`) drill down from the topmost element into the inner scopes of the object tree. By and large, each bubbling event in the WPF base class libraries is paired with a related tunneling event that fires *before* the bubbling counterpart. For example, before the bubbling `MouseDown` event fires, the tunneling `PreviewMouseDown` event fires first.

Handling a tunneling event looks just like the processing of handling any other events; simply assign the event handler name in XAML (or, if needed, use the corresponding C# event-handling syntax in your code file) and implement the handler in the code file. Just to illustrate the interplay of tunneling and bubbling events, begin by handling the `PreviewMouseDown` event for the `outerEllipse` object:

```
<Ellipse Name = "outerEllipse" Fill = "Green" Height = "25"
        MouseDown = "outerEllipse_MouseDown"
        PreviewMouseDown = "outerEllipse_PreviewMouseDown"
        Width = "50" Cursor = "Hand" Canvas.Left = "25" Canvas.Top = "12" />
```

Next, retrofit the current C# class definition by updating each event handler (for all objects) to append data about the current event into a `string` member variable named `mouseActivity`, using the incoming event args object. This will allow you to observe the flow of events firing in the background:

```

public partial class MainWindow : Window
{
    string mouseActivity = string.Empty;
    public MainWindow()
    {
        InitializeComponent();
    }

    public void btnClickMe_Clicked(object sender, RoutedEventArgs e)
    {
        AddEventInfo(sender, e);
        MessageBox.Show(mouseActivity, "Your Event Info");

        // Clear string for next round.
        mouseActivity = "";
    }

    private void AddEventInfo(object sender, RoutedEventArgs e)
    {
        mouseActivity += string.Format(
            "{0} sent a {1} event named {2}.\\n", sender,
            e.RoutedEvent.RoutingStrategy,
            e.RoutedEvent.Name);
    }

    private void outerEllipse_MouseDown(object sender, MouseButtonEventArgs e)
    {
        AddEventInfo(sender, e);
    }

    private void outerEllipse_PreviewMouseDown(object sender, MouseButtonEventArgs e)
    {
        AddEventInfo(sender, e);
    }
}

```

Notice that you are not halting the bubbling of an event for any event handler. If you run this application, you will see a unique message box display based on where you click the button. Figure 31-6 shows the result of clicking on the outer Ellipse object:




Figure 31-6. Tunneling first, bubbling second

So, why do WPF events typically tend to come in pairs (one tunneling and one bubbling)? The answer is that by previewing events, you have the power to perform any special logic (data validation, disable bubbling action, etc.) before the bubbling counterpart fires. By way of an example, assume you have a `TextBox` that should only contain numerical data. You could handle the `PreviewKeyDown` event, and if you see the user has entered non-numerical data, you could cancel the bubbling event by setting the `Handled` property to true.

As you would guess, when you are building a custom control that contains custom events, you could author the event in such a way that it can bubble (or tunnel) through a tree of XAML. For the purpose of this chapter, I will not be examining how to build custom routed events (however, the process is not that different from building a custom dependency property). If you are interested, check out the topic “Routed Events Overview” within the .NET Framework 4.0 SDK documentation. Here, you will find a number of tutorials which will help you on your way.

■ **Source Code** The `WPFRoutedEventArgs` project is included under the Chapter 31 subdirectory.

Logical Trees, Visual Trees and Default Templates

There are a few more preparatory topics to investigate before you begin learning how to build custom controls. Specifically, you need to learn the distinction between a *logical tree*, a *visual tree* and a *default template*. When you are typing XAML into Visual Studio 2010, Expression Blend, or a tool such as `kaxaml.exe`, your markup is the *logical view* of the XAML document. As well, if you author C# code that adds new items to a `StackPanel` control, you are inserting new items into the logical tree. Essentially, a logical view represents how your content will be positioned within the various layout managers for a main `Window` (or another root element, such as `Page` or `NavigationWindow`).

However, behind every logical tree, there is a much more verbose representation termed a *visual tree*, which is used internally by WPF to correctly render out elements onto the screen. Within any visual tree, there will be full details of the templates and styles used to render out each object, including any necessary drawings, shapes, visuals and animations.

It is useful to understand the distinction between logical and visual trees because when you are building a custom control template, you are essentially replacing all or part of the default visual tree of a control and inserting your own. Therefore, if you want a `Button` control to be rendered as a star shape, you could define a new star template and plug it into the `Button`'s visual tree. Logically, the `Button` is still of type `Button`, and it supports all of the properties, methods and events as expected. But visually, it has taken on a whole new appearance. This fact alone makes WPF an extremely useful API, given that other toolkits would require you to build a brand new class to make a star shaped button. With WPF, you simply need to define new markup.

■ **Note** WPF controls are often described as *lookless*. This refers to the fact that the look and feel of a WPF control is completely independent (and customizable) from its behavior.

Programmatically Inspecting a Logical Tree

While analyzing a window's logical tree at runtime is not a tremendously common WPF programming activity, it is worth mentioning that the `System.Windows` namespace defines a class named `LogicalTreeHelper` which allows you to inspect the structure of a logic tree at runtime. To illustrate the connection between logic trees, visual trees and control templates, create a new WPF Application named `TreesAndTemplatesApp`.

Update the markup for your window so that it contains two Button controls and a large read-only TextBox with scroll bars enabled. Make sure you use the IDE to handle the Click event of each button. The following XAML will do nicely:

```
<Window x:Class="TreesAndTemplatesApp.MainWindow"
    xmlns="http://schemas.microsoft.com/winfx/2006/xaml/presentation"
    xmlns:x="http://schemas.microsoft.com/winfx/2006/xaml"
    Title="Fun with Trees and Templates" Height="518"
    Width="836" WindowStartupLocation="CenterScreen">

    <DockPanel LastChildFill="True">
        <Border Height="50" DockPanel.Dock="Top" BorderBrush="Blue">
            <StackPanel Orientation="Horizontal">
                <Button x:Name="btnShowLogicalTree" Content="Logical Tree of Window"
                    Margin="4" BorderBrush="Blue" Height="40" Click="btnShowLogicalTree_Click"/>
                <Button x:Name="btnShowVisualTree" Content="Visual Tree of Window"
                    BorderBrush="Blue" Height="40" Click="btnShowVisualTree_Click"/>
            </StackPanel>
        </Border>
        <TextBox x:Name="txtDisplayArea" Margin="10" Background="AliceBlue" IsReadOnly="True"
            BorderBrush="Red" VerticalScrollBarVisibility="Auto"
            HorizontalScrollBarVisibility="Auto" />
    </DockPanel>
</Window>
```

Within your C# code file, define a string member variable named `dataToShow`. Now, within the Click handler for the `btnShowLogicalTree` object, call a helper function which calls itself recursively in order to populate the string variable with the logical tree of the Window. To do so, you will call the static `GetChildren()` method of `LogicalTreeHelper`. Here is the code:

```
private void btnShowLogicalTree_Click(object sender, RoutedEventArgs e)
{
    dataToShow = "";
    BuildLogicalTree(0, this);
    this.txtDisplayArea.Text = dataToShow;
}

void BuildLogicalTree(int depth, object obj)
{
    // Add the type name to the dataToShow member variable.
    dataToShow += new string(' ', depth) + obj.GetType().Name + "\n";
```

```

// If an item is not a DependencyObject, skip it.
if (!(obj is DependencyObject))
    return;

// Make a recursive call for each logical child
foreach (object child in LogicalTreeHelper.GetChildren(
    obj as DependencyObject))
    BuildLogicalTree(depth + 5, child);
}

```

If you run your application and click this first button, you will see a tree print out in the text area, which is just about an exact replica of the original XAML (Figure 31-7).




Figure 31-7. Viewing a logical tree at runtime

Programmatically Inspecting a Visual Tree

A Window's visual tree can also be inspected at runtime using the `VisualTreeHelper` class of `System.Windows.Media`. Here is a Click implementation of the second Button control (`btnShowVisualTree`), which performs similar recursive logic to build a textual representation of the visual tree:

```

private void btnShowVisualTree_Click(object sender, RoutedEventArgs e)
{
    dataToShow = "";
    BuildVisualTree(0, this);
    this.txtDisplayArea.Text = dataToShow;
}

void BuildVisualTree(int depth, DependencyObject obj)
{
    // Add the type name to the dataToShow member variable.
    dataToShow += new string(' ', depth) + obj.GetType().Name + "\n";
}

```

```

// Make a recursive call for each visual child
for (int i = 0; i < VisualTreeHelper.GetChildrenCount(obj); i++)
    BuildVisualTree(depth + 1, VisualTreeHelper.GetChild(obj, i));
}

```

As you can see in Figure 31-8, the visual tree exposes a number of lower-level rendering agents such as ContentPresenter, AdornerDecorator, TextBoxLineDrawingVisual, and so forth.




Figure 31-8. Viewing a visual tree at runtime

Programmatically Inspecting a Control's Default Template

Recall that a visual tree is used by WPF to understand how to render a Window and all contained elements. Every WPF control stores its own set of rendering commands within its default template. Programmatically speaking, any template can be represented as an instance of the ControlTemplate class. As well, you can obtain a control's default template by using the aptly named Template property:

```

// Get the default template of the Button.
Button myBtn = new Button();
ControlTemplate template = myBtn.Template;

```

Likewise, you could create a new `ControlTemplate` object in code and plug it into a control's `Template` property:

```
// Plug in a new template for the button to use.
Button myBtn = new Button();
ControlTemplate customTemplate = new ControlTemplate();

// Assume this method adds all the code for a star template
MakeStarTemplate(customTemplate);
myBtn.Template = customTemplate;
```

While you could build a new template in code, it is far more common to do so in XAML. In fact, Expression Blend has a large number of tools which can be used to define a template with minimal fuss and bother.

However, before you start building your own templates, let's finish the current example and add the ability to view the default template of a WPF control at runtime. This can be a really useful way to take a look at the overall composition of a template. First, update the markup of your window with a new `StackPanel` of controls docked to the left side of the master `DockPanel`, defined as so:

```
<Border DockPanel.Dock="Left" Margin="10" BorderBrush="DarkGreen"
       BorderThickness="4" Width="358">
    <StackPanel>
        <Label Content="Enter Full Name of WPF Control" Width="340" FontWeight="DemiBold" />
        <TextBox x:Name="txtFullName" Width="340" BorderBrush="Green"
                 Background="BlanchedAlmond" Height="22"
                 Text="System.Windows.Controls.Button" />
        <Button x:Name="btnTemplate" Content="See Template" BorderBrush="Green"
                Height="40" Width="100" Margin="5"
                Click="btnTemplate_Click" HorizontalAlignment="Left" />
        <Border BorderBrush="DarkGreen" BorderThickness="2" Height="260"
               Width="301" Margin="10" Background="LightGreen" >
            <StackPanel x:Name="stackTemplatePanel" />
        </Border>
    </StackPanel>
</Border>
```

Do take note of the empty `StackPanel`, `stackTemplatePanel`, as you will refer to it in code. Anyway, your window should now look something like Figure 31-9.




Figure 31-9. The updated UI of your window

The upper left text area allows you to enter in the fully qualified name of a WPF control located the PresentationFramework.dll assembly. Once the library is loaded, you will dynamically create an instance of the object and display it in the large square in the bottom left. Last but not least, the control's default template will be displayed in the right hand text area. First, add a new member variable to your C# class of type Control:

```
private Control ctrlToExamine = null;
```

Here is the remaining code, which will require you to import the System.Reflection, System.Xml and System.Windows.Markup namespaces:

```
private void btnTemplate_Click(object sender, RoutedEventArgs e)
{
    dataToShow = "";
    ShowTemplate();
    this.txtDisplayArea.Text = dataToShow;
}

private void ShowTemplate()
{
    // Remove the control which is currently in the preview area.
    if (ctrlToExamine != null)
        stackTemplatePanel.Children.Remove(ctrlToExamine);
```

```
try
{
    // Load PresentationFramework, and create an instance of the
    // specified control. Give it a size for display purposes, then add to the
    // empty StackPanel.
    Assembly asm = Assembly.Load("PresentationFramework, Version=4.0.0.0, " +
        "Culture=neutral, PublicKeyToken=31bf3856ad364e35");
    ctrlToExamine = (Control)asm.CreateInstance(txtFullName.Text);
    ctrlToExamine.Height = 200;
    ctrlToExamine.Width = 200;
    ctrlToExamine.Margin = new Thickness(5);
    stackTemplatePanel.Children.Add(ctrlToExamine);

    // Define some XML settings to preserve indentation.
    XmlWriterSettings xmlSettings = new XmlWriterSettings();
    xmlSettings.Indent = true;

    // Create a StringBuilder to hold the XAML.
    StringBuilder strBuilder = new StringBuilder();

    // Create an XmlWriter based on our settings.
    XmlWriter xWriter = XmlWriter.Create(strBuilder, xmlSettings);

    // Now save the XAML into the XmlWriter object based on the ControlTemplate.
    XamlWriter.Save(ctrlToExamine.Template, xWriter);

    // Display XAML in the text box.
    dataToShow = strBuilder.ToString();
}
catch (Exception ex)
{
    dataToShow = ex.Message;
}
```

The bulk of the work is just tinkering with the compiled BAML resource to map it into a XAML string. Figure 31-10 shows your final application in action, displaying the default template of the DatePicker control.




Figure 31-10. Investigating a ControlTemplate at runtime

Great! Hopefully you have a better idea about how logical trees, visual trees, and control templates work together. Now you can spend the remainder of this chapter learning how to build custom templates and user controls.

■ **Source Code** The `TreesAndTemplatesApp` project is included under the Chapter 31 subdirectory.

Building a Custom Control Template with Visual Studio 2010

When you are building a custom template for a control, you could do so with nothing but C# code. Using this approach, you would be adding data to a `ControlTemplate` object and then assigning it to a control's `Template` property. Most of the time, however, you will define the look and feel of a `ControlTemplate` using XAML, and to help in the endeavor, you will typically want to use Expression Blend to do so. You will use Expression Blend for this very thing in the final example of this chapter, but for now, you will build a simple template using Visual Studio 2010. Although this IDE does not include as many template design tools as Expression Blend, using Visual Studio 2010 is a good way to learn the nuts and bolts of template construction.

Create a brand new WPF Application named `ButtonTemplate`. For this project, you are more interested in the mechanics of creating and using templates, so the markup for this main window is very simple:

```
<Window x:Class="ButtonTemplate.MainWindow"
    xmlns="http://schemas.microsoft.com/winfx/2006/xaml/presentation"
    xmlns:x="http://schemas.microsoft.com/winfx/2006/xaml"
    Title="Fun with Templates" Height="350" Width="525">
    <StackPanel>
        <Button x:Name="myButton" Width="100" Height="100"
            Click="myButton_Click"/>
    </StackPanel>
</Window>
```

In the `Click` event handler, simply display a message box (via `MessageBox.Show()`) which displays a message confirming the clicking of the control. Remember, when you build custom templates, the *behavior* of the control is constant but the *look* may vary.

Currently, this `Button` is rendered using the default template, which, as the last example illustrated, is a BAML resource within a given WPF assembly. When you wish to define your own template, you are essentially replacing this default visual tree with your own creation. To begin, update the definition of the `<Button>` element to specify a new template using property element syntax. This template will give the control a round appearance:

```
<Button x:Name="myButton" Width="100" Height="100"
    Click="myButton_Click">
    <Button.Template>
        <ControlTemplate>
            <Grid x:Name="controlLayout">
                <Ellipse x:Name="buttonSurface" Fill = "LightBlue"/>
                <Label x:Name="buttonCaption" VerticalAlignment = "Center"
                    HorizontalAlignment = "Center"
                    FontWeight = "Bold" FontSize = "20" Content = "OK!"/>
            </Grid>
        </ControlTemplate>
    </Button.Template>
</Button>
```

Here, you have defined a template which consists of a named `Grid` control containing a named `Ellipse` and a `Label`. Because your `Grid` has no defined rows or columns, each child stacks on top of the previous control, allowing you to have centering of content. Now, if you run your application, you will notice that the `Click` event will *only* fire when the mouse cursor is within the bounds of the `Ellipse` (i.e. not in the corners around the edges of the ellipse)! This is a great feature of the WPF template architecture: you do not need to recalculate hit-testing, bounds checking, or any other low level detail. So, if your template used a `Polygon` object to render some oddball geometry, you can rest assured that the mouse hit testing details are relative to the shape of the control, not the larger bounding rectangle.

Templates as Resources

Currently, your template is embedded to a specific `Button` control, which limits your reuse options. Ideally, you would place your template into a resource dictionary, so you can reuse your round button

template between projects, or at minimum, move it into the application resource container for reuse within this project. Let's move the local Button resource to the application level using Visual Studio 2010. First, locate the Template property for your Button in the Properties editor. Now, click on the small black diamond icon and select "Extract Value to Resource..." (see Figure 31-11).




Figure 31-11. Extracting a local resource

From the resulting dialog box, define a new template named RoundButtonTemplate, which is stored in App.xaml (Figure 31-12).




Figure 31-12. Placing your resource into App.xaml

At this point, you will find the following data in your Application object's markup:

```
<Application x:Class="ButtonTemplate.App"
    xmlns="http://schemas.microsoft.com/winfx/2006/xaml/presentation"
    xmlns:x="http://schemas.microsoft.com/winfx/2006/xaml"
    StartupUri="MainWindow.xaml">
    <Application.Resources>
        <ControlTemplate x:Key="RoundButtonTemplate">
            <Grid x:Name="controlLayout">
                <Ellipse x:Name="buttonSurface" Fill = "LightBlue"/>
                <Label x:Name="buttonCaption" VerticalAlignment = "Center"
                    HorizontalAlignment = "Center">
```

```

        FontWeight = "Bold" FontSize = "20" Content = "OK!"/>
    </Grid>
</ControlTemplate>
</Application.Resources>
</Application>

```

You may wish to constrain where this template can be applied. Like a WPF style, you can add the TargetType attribute to any `<ControlTemplate>`. Update the `<ControlTemplate>` start tag to ensure that only Button controls can use this template:

```
<ControlTemplate x:Key="RoundButtonTemplate" TargetType ="Button">
```

Now, because this resource is available for the entire application, you can define any number of round buttons. Go ahead and create two additional Button controls which use this template for testing purposes (no need to handle the Click event for these new items).

```

<StackPanel>
    <Button x:Name="myButton" Width="100" Height="100"
        Click="myButton_Click"
        Template="{StaticResource RoundButtonTemplate}"></Button>
    <Button x:Name="myButton2" Width="100" Height="100"
        Template="{StaticResource RoundButtonTemplate}"></Button>
    <Button x:Name="myButton3" Width="100" Height="100"
        Template="{StaticResource RoundButtonTemplate}"></Button>
</StackPanel>

```

Incorporating Visual Cues using Triggers

When you define a custom template, all of the visual cues of the default template are removed as well. For example, the default button template contains markup which informs the control how to look when certain UI events occur, such as when it receives focus, when it is clicked with the mouse, when it is enabled (or disabled), and so on. Users are quite accustomed to these sort of visual cues, as it gives the control somewhat of a tactile response. However, your RoundButtonTemplate does not define any such markup, so the look of the control is identical regardless of the mouse activity. Ideally, your control should look slightly different when clicked (maybe via a color change or drop shadow) to let the user know the visual state has changed.

When WPF was first released, the way to add in such visual cues was to add to the template any number of triggers which would typically change values of object properties or start a storyboard animation (or both) when the trigger condition was true. By way of example, update your RoundButtonTemplate with the following markup, which will change the color of the control to blue and the Foreground color to yellow when the mouse is over the surface:

```

<ControlTemplate x:Key="RoundButtonTemplate" TargetType="Button" >
    <Grid x:Name="controlLayout">
        <Ellipse x:Name="buttonSurface" Fill="LightBlue" />
        <Label x:Name="buttonCaption" Content="OK!" FontSize="20" FontWeight="Bold"
            HorizontalAlignment="Center" VerticalAlignment="Center" />
    </Grid>
    <ControlTemplate.Triggers>
        <Trigger Property = "IsMouseOver" Value = "True">

```

```

<Setter TargetName = "buttonSurface" Property = "Fill" Value = "Blue"/>
<Setter TargetName = "buttonCaption" Property = "Foreground"
Value = "Yellow"/>
</Trigger>
</ControlTemplate.Triggers>
</ControlTemplate>
```

If you run the program yet again, you should find the color does toggle based on whether or not the mouse is within the Ellipse area. Here is another trigger, which will shrink the size of the Grid (and therefore all child elements) when the control is pressed via the mouse. Add this to your <ControlTemplate.Triggers> collection:

```

<Trigger Property = "IsPressed" Value="True">
<Setter TargetName="controlLayout"
Property="RenderTransformOrigin" Value="0.5,0.5"/>
<Setter TargetName="controlLayout" Property="RenderTransform">
<Setter.Value>
<ScaleTransform ScaleX="0.8" ScaleY="0.8"/>
</Setter.Value>
</Setter>
</Trigger>
```

At this point, you have a custom template with a few visual cues incorporated using WPF triggers. As you will see in the next (and final) example of this chapter, .NET 4.0 introduces an alternative way to incorporate visual cues using the Visual State Manager. Before you get to that point, let's talk about the role of the {TemplateBinding} markup extension and the ContentPresenter class.

The Role of {TemplateBinding} Markup Extension

Your template can only be applied to Button controls, and therefore it would stand to reason that you could set properties on the <Button> element that will cause the template to render itself in a unique manner. For example, right now, the Fill property of the Ellipse is hard coded to be blue and the Content of the Label is always set to the string value "OK". Of course, you might want buttons of different colors and text values, so you might try to define the following buttons in your main window:

```

<StackPanel>
<Button x:Name="myButton" Width="100" Height="100"
Background="Red" Content="Howdy!"
Click="myButton_Click"
Template="{StaticResource RoundButtonTemplate}" />
<Button x:Name="myButton2" Width="100" Height="100"
Background="LightGreen" Content="Cancel!"
Template="{StaticResource RoundButtonTemplate}" />
<Button x:Name="myButton3" Width="100" Height="100"
Background="Yellow" Content="Format"
Template="{StaticResource RoundButtonTemplate}" />
</StackPanel>
```

However, regardless of the fact that each Button is setting a unique Background and Content value, you still end up with three blue buttons which contain the text "OK". The problem is that the properties

of the control using the template (Button) have properties which do not match identically with the items on the template (such as the Fill property of the Ellipse). As well, although the Label does have a Content property, the value defined in the <Button> scope is not automatically routed to the internal child of the template.

You can solve these issues by using the {TemplateBinding} markup extension when you build your template. This allows you to capture property settings defined by the control using your template and use them to set values in the template itself. Here is a reworked version of RoundButtonTemplate, which now uses this markup extension to map the Background property of the Button to the Fill property of the Ellipse; it also makes sure the Content of the Button is indeed passed to the Content property of the Label:

```
<ControlTemplate x:Key="RoundButtonTemplate" TargetType="Button">
    <Grid x:Name="controlLayout">
        <Ellipse x:Name="buttonSurface" Fill="{TemplateBinding Background}"/>
        <Label x:Name="buttonCaption" Content="{TemplateBinding Content}"
            FontSize="20" FontWeight="Bold"
            HorizontalAlignment="Center" VerticalAlignment="Center" />
    </Grid>
    <ControlTemplate.Triggers>
        ...
    </ControlTemplate.Triggers>
</ControlTemplate>
```

With this update, you can now create buttons of various colors and textual values (Figure 31-13).




Figure 31-13. Template bindings allow values to pass through to the internal controls

The Role of ContentPresenter

When you designed your template, you used a Label to display the textual value of the control. Like the Button, the Label supports a Content property. Therefore, given your use of {TemplateBinding}, you could define a Button which contained complex content beyond that of a simple string. For example:

```
<Button x:Name="myButton4" Width="100" Height="100" Background="Yellow"
    Template="{StaticResource RoundButtonTemplate}">
    <Button.Content>
        <ListBox Height="50" Width="75">
            <ListBoxItem>Hello</ListBoxItem>
            <ListBoxItem>Hello</ListBoxItem>
            <ListBoxItem>Hello</ListBoxItem>
        </ListBox>
    </Button.Content>
</Button>
```

For this particular control, things work just as hoped. However, what if you need to pass in complex content to a template member that does *not* have a Content property? When you wish to define a generalized *content display area* in a template, you can use the ContentPresenter class as opposed to a specific type of control (Label or TextBlock). You have no need to do so for this example; however, here is some simple markup which illustrates how you could build a custom template that uses ContentPresenter to show the value of the Content property of the control using the template:

```
<!-- This button template will display whatever is set
    to the Content of the hosting button -->
<ControlTemplate x:Key="NewRoundButton" TargetType="Button">
    <Grid>
        <Ellipse Fill="{TemplateBinding Background}" />
        <ContentPresenter HorizontalAlignment="Center"
            VerticalAlignment="Center" />
    </Grid>
</ControlTemplate>
```

Incorporating Templates into Styles

Currently, your template simply defines a basic look and feel of the Button control. However, the process of establishing the basic properties of the control (content, font size, font weight, etc.) is the responsibility of the Button itself:

```
<!-- Currently the Button must set basic property values, not the template -->
<Button x:Name ="myButton" Foreground ="Black" FontSize ="20" FontWeight ="Bold"
    Template ="{StaticResource RoundButtonTemplate}" Click ="myButton_Click"/>
```

If you wish, you could establish these values *in the template*. By doing so, you can effectively create a default look and feel. As you may have already realized, this is a job for WPF styles. When you build a style (to account for basic property settings), you can define a template *within the style!* Here is your updated application resource in the application resources in App.xaml, which has been rekeyed as RoundButtonStyle:

```

<!-- A style containing a template -->
<Style x:Key ="RoundButtonStyle" TargetType ="Button">
    <Setter Property ="Foreground" Value ="Black"/>
    <Setter Property ="FontSize" Value ="14"/>
    <Setter Property ="FontWeight" Value ="Bold"/>
    <Setter Property="Width" Value="100"/>
    <Setter Property="Height" Value="100"/>
    <!-- Here is the template! -->
    <Setter Property ="Template">
        <Setter.Value>
            <ControlTemplate TargetType ="Button">
                <Grid x:Name="controlLayout">
                    <Ellipse x:Name="buttonSurface" Fill="{TemplateBinding Background}"/>
                    <Label x:Name="buttonCaption" Content ="{TemplateBinding Content}"
                           HorizontalAlignment="Center" VerticalAlignment="Center" />
                </Grid>
            <ControlTemplate.Triggers>
                <Trigger Property = "IsMouseOver" Value = "True">
                    <Setter TargetName = "buttonSurface" Property = "Fill" Value = "Blue"/>
                    <Setter TargetName = "buttonCaption" Property = "Foreground" Value = "Yellow"/>
                </Trigger>
                <Trigger Property = "IsPressed" Value="True">
                    <Setter TargetName="controlLayout"
                           Property="RenderTransformOrigin" Value="0.5,0.5"/>
                    <Setter TargetName="controlLayout" Property="RenderTransform">
                        <Setter.Value>
                            <ScaleTransform ScaleX="0.8" ScaleY="0.8"/>
                        </Setter.Value>
                    </Setter>
                </Trigger>
            </ControlTemplate.Triggers>
        </ControlTemplate>
    </Setter.Value>
</Setter>
</Style>

```

With this update, you can now create button controls by setting the `Style` property as so:

```

<Button x:Name="myButton" Background="Red" Content="Howdy!">
    <Click="myButton_Click" Style="{StaticResource RoundButtonStyle}" />

```

While the rendering and behavior of the button is identical, the benefit of nesting templates within styles is that you are able to provide a canned set of values for common properties.

That wraps up your look at how to use Visual Studio 2010 to build custom templates for a control. However, before you conclude this chapter and move onto the world of web development using ASP.NET, you will look at how Expression Blend can be used to not only generate control templates but to create custom UserControls.

■ **Source Code** The ButtonTemplate project can be found under the Chapter 31 subdirectory.

Building Custom UserControls with Blend

During your examination of dependency properties, you were briefly introduced to the concept of a `UserControl`. In some ways, a `UserControl` is the next logical step after a control template. Recall that when you build a control template, you are essentially applying a *skin* which changes the physical appearance of a WPF control. A custom `UserControl`, however, allows you to literally build a new class type that may contain unique members (methods, events, properties, etc.). As well, many custom `UserControls` use templates and styles; however, it is also just fine if the control's tree of markup is defined directly within the `<UserControl>` scope.

Recall that you can add a `UserControl` project item to any Visual Studio 2010 WPF application, including creating a `UserControl` library project, which is a *.dll that contains nothing but a collection of `UserControls` to make use of across projects.

In this final section of the chapter, I will make use of Expression Blend to show you a few very interesting development techniques, including creating a new control from a geometry, working with the animation editor, and incorporating visual cues using the .NET 4.0 Visual State Manager (VSM). While going through these topics, remember that you can certainly achieve the same end result if you make use of Visual Studio 2010; it will just require more manually typing for the markup.

Creating a `UserControl` Library Project

The goal for this final example of the chapter is to build a WPF application that represents a simple jackpot game. While you could bundle all of the logic in a new WPF executable, you will instead place your custom controls in a dedicated library project. Begin by launching Expression Blend, and from the File | New Project menu create a new WPF Control Library project named `MyCustomControl` (Figure 31-14).




Figure 31-14. A new Blend WPF Control Library project

Renaming the Initial UserControl

This project type will provide you with an initial UserControl named `MainControl`. Let's rename this control to `SpinControl`. To do so, begin by changing the name of the `MainControl.xaml` file to `SpinControl.xaml` via the Projects tab. Next, open the XAML editor for your initial control, and change the `x:Class` attribute as shown here (also, delete the `x:Name` attribute completely). Then, set the `Height` and `Width` of the `UserControl` to 150 each:

```
<UserControl
    xmlns="http://schemas.microsoft.com/winfx/2006/xaml/presentation"
    xmlns:x="http://schemas.microsoft.com/winfx/2006/xaml"
    xmlns:d="http://schemas.microsoft.com/expression/blend/2008"
    xmlns:mc="http://schemas.openxmlformats.org/markup-compatibility/2006"
    mc:Ignorable="d"
    x:Class="MyCustomControl.SpinControl"
    Width="150" Height="150">
    <Grid/>
</UserControl>
```

Last but not least, open the C# code file that is paired to your XAML document, and change the name of this class (and the constructor) to `SpinControl`:

```
public partial class SpinControl
{
    public SpinControl()
```

```

    {
        this.InitializeComponent();
    }
}

```

Now, just for a sanity check, build your entire project just to ensure you don't have any typos.

Designing the SpinControl

The purpose of the custom SpinControl is to cycle through three image files in a random manner whenever the Spin() method is called. The downloadable code for this book includes three image files (*Cherries.png*, *Jackpot.jpg* and *Limes.jpg*) which represent the possible images that could be displayed, so feel free to add them to your current project using the Project | Add Existing Item... menu option. When you add these images to your Blend project, they will automatically be configured to be embedded into the resulting assembly.

The visual design of the SpinControl is quite simple. Using the Assets Library, include a Border control which uses a BorderThickness value of 5, and using the Brushes editor, select a BorderBrush color of your liking. Next, place an Image control (named *imgDisplay*) within the Grid, and set the Stretch property to the value Fill. When you are done, the Grid should be configured similar to the following:

```

<Grid x:Name="LayoutRoot">
    <Border BorderBrush="#FFD51919" BorderThickness="5"/>
    <Image x:Name="imgDisplay" Margin="8" Stretch="Fill"/>
</Grid>

```

Finally, set the Source property of the Image control to one of your three images. Your designer should now look something like Figure 31-15.




Figure 31-15. The UI of the SpinControl

Adding the Initial C# Code

Now that the markup is complete, use the Events tab of the Blend Properties window to handle the `Loaded` event for your control, and specify a method named `SpinControl_Loaded`. In your code window, declare an array of three `BitmapImage` objects that are filled with the embedded binary image files when the `Loaded` event fires:

```
public partial class SpinControl
{
    // An array of BitmapImage objects.
    private BitmapImage[] images = new BitmapImage[3];

    public SpinControl()
    {
        this.InitializeComponent();
    }

    private void SpinControl_Loaded(object sender, System.Windows.RoutedEventArgs e)
    {
        // Fill the ImageSource array with each image.
        images[0] = new BitmapImage(new Uri("Cherries.png", UriKind.Relative));
        images[1] = new BitmapImage(new Uri("Jackpot.jpg", UriKind.Relative));
        images[2] = new BitmapImage(new Uri("Limes.jpg", UriKind.Relative));
    }
}
```

Next, define a public method named `Spin()`, which is implemented to randomly show one of the three `BitmapImage` objects in the `Image` control and return the value of the random number:

```
public int Spin()
{
    // Randomly put one of the images into the Image control.
    Random r = new Random(DateTime.Now.Millisecond);
    int randomNumber = r.Next(3);
    this.imgDisplay.Source = images[randomNumber];
    return randomNumber;
}
```

Defining an Animation using Blend

Your `SpinControl` is almost complete; however, to make things more visual appealing to the user, you will now use Blend to define an animation that will make the `Image` control appear to flip in a rotation in order to give the illusion that the graphical image has spun. You could author some C# code which preformed the animation logic; however, in this example, you will make use of the integrated animation editor of Blend to define a XAML storyboard.

Ensure that the designer of your `SpinControl` is the active window in your project. Now, using the Objects and Timeline editor, select your `Image` control, and then click on the "New Storyboard" button (Figure 31-16).




Figure 31-16. Creating a new Storyboard using Expression Blend

From the resulting dialog box, name your storyboard SpinImageStoryboard. Once you have clicked the OK button, you will notice that the Objects and Timeline editor has changed its appearance. Specifically, you'll see a time line editor, which can be more easily viewed by pressing the F6 key to arrange the IDE into *animation editor mode* (press F6 again to toggle back to the previous IDE layout).

This editor allows you to capture how an object will change over units of time called *keyframes*. To begin, click the yellow arrow of the timeline and drag it to the 0.5 second mark. Once you have done so, click the Record Keyframe button, which is located right above the zero second mark. When you are done, your time line editor should look like Figure 31-17.




Figure 31-17. Defining a new keyframe

You will also notice that your visual editor is now in *record mode*, signified by the red border around the visual designer. You are free to now change any property of an object using the Properties editor. While you are making changes, these are being recorded by the IDE and are written out as XAML animation instructions. For this animation, locate the Transform editor in the Properties window of Expression Blend, and pick the Flip Y Access option (Figure 31-18).



Figure 31-18. Applying a transformation to the Image control

Now, go back to the Objects and Timeline editor, and click on your SpinImageStoryboard story board resource (Figure 31-19).




Figure 31-19. Selecting the SpinImageStoryboard for editing

Once you select a story board for editing, you can configure various settings on the storyboard itself, such as auto-reversing or repeat behaviors using the Properties editor. For your animation storyboard, click the AutoReverse checkbox (Figure 31-20).




Figure 31-20. Auto reversing your animation

At this point, you can test your animation! Just click the Play button (Figure 31-21). You should see your image flip and then reverse back to the original upright display.




Figure 31-21. Testing your animation

In summary, you have defined a simple animation which will take place over a total of 1 second (1/2 a second for the flipping of the image and an additional 1/2 a second to reverse the transformation). You can now exit the animation editor by clicking on the recording button on your visual designer (Figure 31-22).



Figure 31-22. Exiting the animation editor

■ **Note** Your animation only changed a single property of a single object. Note that a storyboard can change any number of properties (for any number of objects) over various key frames. To do so, simply drag the yellow timeline to a new unit of time, click the Add Keyframe button, and change properties on the object selected in Objects and Timeline.

If you were to view the underlying XAML, you will see that Blend has added a new <Storyboard> to your UserControl's resource dictionary:

```

<UserControl.Resources>
    <Storyboard x:Key="SpinImageStoryboard" AutoReverse="True">
        <PointAnimationUsingKeyFrames BeginTime="00:00:00"
            Storyboard.TargetName="imgDisplay"
            Storyboard.TargetProperty="(UIElement.RenderTransformOrigin)">
            <SplinePointKeyFrame KeyTime="00:00:01" Value="0.5,0.5"/>
        </PointAnimationUsingKeyFrames>
        <DoubleAnimationUsingKeyFrames BeginTime="00:00:00"
            Storyboard.TargetName="imgDisplay"
            Storyboard.TargetProperty=
                "(UIElement.RenderTransform).(TransformGroup.Children)[0]
                .(ScaleTransform.ScaleY)">
            <SplineDoubleKeyFrame KeyTime="00:00:01" Value="-1"/>
        </DoubleAnimationUsingKeyFrames>
    </Storyboard>
</UserControl.Resources>

```

Programmatically Starting our Storyboard

Before you move onto the construction of the WPF Application that will make use of your custom button, you have a final task to attend to. By default, when you use the Blend animation editor, it will add a trigger that will start your storyboard when the `UserControl` (or `Window`, in the case of a WPF application project) loads into memory:

```

<UserControl.Triggers>
    <EventTrigger RoutedEvent="FrameworkElement.Loaded">
        <BeginStoryboard Storyboard="{StaticResource SpinImageStoryboard}" />
    </EventTrigger>
</UserControl.Triggers>

```

You can verify this by clicking on the Triggers editor (which can be opened via the Windows menu of Expression Blend; see Figure 31-23).




Figure 31-23. Deleting the automatically added trigger

In addition to spinning when the control loads, you will also spin when the `Spin()` method is called. Import the `System.Windows.Media.Animation` namespace in your C# code file, and update your `Spin()` method to invoke the story board like so:

```
public int Spin()
{
    // Randomly put of the images into the Image control.
    Random r = new Random(DateTime.Now.Millisecond);
    int randomNumber = r.Next(3);
    this.imgDisplay.Source = images[randomNumber];

    // Start the storyboard animation!
    ((Storyboard)Resources["SpinImageStoryboard"]).Begin();
    return randomNumber;
}
```

That completes your custom control library! Go ahead and build your project to ensure you don't have any errors. Now let's make use of this control from within a WPF Application.

Source Code The `MyCustomControl` project can be found under the Chapter 31 subdirectory.

Creating the Jackpot Deluxe WPF Application

Create a brand new WPF Application project named `JackpotDeluxe` using Expression Blend, and set a reference to `MyCustomControl.dll` using the `Project | Add Reference...` menu option. Because your control is defined in an external assembly, update the opening element of the `Window` to define a new XML namespace named `custom` that maps to your `MyCustomControl` namespace:

```
<Window
    xmlns="http://schemas.microsoft.com/winfx/2006/xaml/presentation"
    xmlns:x="http://schemas.microsoft.com/winfx/2006/xaml"
    xmlns:custom="clr-namespace:MyCustomControl;assembly=MyCustomControl"
    x:Class="JackpotDeluxe.MainWindow"
    x:Name="Window"
    Title="MainWindow"
    Width="640" Height="438">
    <Grid/>
</Window>
```

You will build your complete UI of this window in just a few moments; however, before you do, you will make one additional custom control.

Extracting a UserControl from a Drawing Geometry

Expression Blend has a number of very useful shortcuts that can make the process of building custom controls very simple. When you stop to think about it, the chances are very good that many custom controls begin life as a simple graphic created by a graphic artist. To illustrate, select your Grid in the Objects and Timeline editor, and then pick the Pencil tool in your Toolbox (which can be seen if you click and hold the Pen button). Use this tool to draw an interesting image of your liking. In Figure 31-24, you can see my (somewhat sad) attempt at rendering a star shaped image, with the Fill property set to an orange colored brush and the Stroke property set to a blue brush.




Figure 31-24. Using the Pencil control to render a unique shape

Now, if you look at the XAML which was generated on your behalf, you will see that Expression Blend defined a Path object. So let's say that you would like to use this geometry as the starting point for a custom control. To do so, simply right click on the Path object on the designer, and select the Make Into UserControl... option (Figure 31-25).



Figure 31-25. Transforming a geometry into a new UserControl

As soon as you select this option, you will be asked to name your control, which I will assume is `StarButton` (you can leave all other settings of this dialog to their default values). Expression Blend will then create a brand new `UserControl` derived class with a corresponding XAML and C# code file! As well, the original `Path` object on the `Window` has been replaced with an instance of the new control, which is mapped to a new XML namespace in the `MainWindow.xaml` file:

```
<Window
    xmlns="http://schemas.microsoft.com/winfx/2006/xaml/presentation"
    xmlns:x="http://schemas.microsoft.com/winfx/2006/xaml"
    xmlns:custom="clr-namespace:MyCustomControl;assembly=MyCustomControl"
    xmlns:local="clr-namespace:JackpotDeluxe"
    x:Class="JackpotDeluxe.MainWindow"
    x:Name="Window"
    Title="MainWindow"
    Width="640" Height="438">
    <Grid>
        <local:StarButton HorizontalAlignment="Left"
            Margin="102,41,0,0" VerticalAlignment="Top"
            Width="136" Height="131"/>
    </Grid>
</Window>
```

You will build the real UI of your `Window` in just a moment, but leave this control in place for the time being.

The Role of .NET 4.0 Visual States

Recall that one of the important tasks of custom control development is adding in visual cues for the end user. In an earlier example of this chapter, you added a few visual cues to a custom `Button` template by using WPF triggers. You could certainly use triggers for `StarButton` as well; however, as of .NET 4.0, WPF supports an alternative way to do so via *visual state groups*.

Note The concept of visual states was first introduced in the Silverlight API. Many felt that the use of visual states (and the related Visual State Manager) was a simpler alternative to WPF triggers, and therefore WPF incorporated this alternative approach into the API beginning with .NET 4.0.

Using WPF visual states, you are able to define a group of related states that your control could be in at any given time. Think of a visual state group as little more than a named container for related UI cues. Ultimately, the names of the groups you define are completely up to you; however, some common group names might include `MouseStateGroup`, `FocusedStateGroup`, or `EnabledStateGroup`.

Once you have defined a set of visual state groups, you then define the individual states for a specific group. For example, `MouseStateGroup` could define three possible mouse-centric states named `MouseEnterStar`, `MouseExitStar`, and `MouseDownStar`. The `FocusedStateGroup` might define two states named `GainFocusStar` and `LoseFocusStar`.

After you have defined the states for a group, you will then define storyboards that represent the UI cues that will occur when your control transitions into a given state. For example, you could create a storyboard for the MouseEnterStar state which causes the control to change color. Maybe you have a second storyboard for the MouseDownStar state, which causes the control to shrink (or grow) in size. You can use the integrated animation editor of Blend to quickly define each storyboard.

Once you have all of your states defined, you can then force your control to move into any given state using two approaches. If you wish to move between states in code, you can call the static `GoToState()` method of the `VisualStateManager` class. Simply specify the name of a state and the related storyboard will execute.

Note If you wish to transition between states using only markup, you can define triggers which will move between states using the `GoToStateAction` XAML element.

Defining Visual States for the StarButton Control

To add visual states to the `StarButton` control, first ensure that the visual editor for your `StarButton` `UserControl` is the active window in the Blend IDE. Now, locate the States tab (which can be opened via the Windows menu of Expression Blend) and click the Add State Group button (Figure 31-26).




Figure 31-26. Adding a new visual state group

Now, change the name of the generated group (currently named `VisualStateGroup`) to the more fitting name, `MouseStateGroup`. Once you do, notice the Add State button (Figure 31-27).




Figure 31-27. The *MouseStateGroup*

Using the Add State button, add three states to the *MouseStateGroup*, named *MouseEnterStar*, *MouseExitStar* and *MouseDownStar* (Figure 31-28).




Figure 31-28. The states of the *MouseStateGroup*

Each one of your states can now be defined in terms of a storyboard. First, select the *MouseEnterStar* state. Now, using the Properties window, pick a new color for the *Fill* property (I made mine a darker shade of orange). Feel free to change properties of other aspects of your control if you wish, such as changing the shape of your control by moving the control points on the visual editor or changing the *StrokeThickness* property.

Next, select the *MouseExitStar* state, and notice it will set the *Fill* color back to the original value, which is perfect for this example. Pick the *MouseDownStar* state, and use the Properties window to apply a simple transformation to the control (I elected to apply a slight skew to the control).

Defining State Transition Timings

At this point, you have successfully defined a single visual state group with three states. By default, when you transition between states, it will happen immediately because the Default transition value is set to zero seconds (you'll see this listed directly under the name of each state group within the States tab). If you wish, you can define custom amounts of time that should transpire as a control moves between states.

Let's configure the MouseDownStar state in such a way that it will execute the storyboard over a period of 2 seconds. To do so, first click the Add Transition button. Here, you will see a listing of all the possible transitions for the current state. Pick the first listing, which represents the act of moving from the current state into the MouseDownStar state (Figure 31-29).




Figure 31-29. Changing the timing for this state transition

Once you pick this option, define a 1 second amount of time for this transition (Figure 31-30).




Figure 31-30. Defining a one second amount of time for this transition to occur

Viewing the Generated XAML

That is all you need to do for your visual state group. If you click on the XAML tab for your control, you will see the markup which was created by the IDE. Based on how many properties you changed, you could be looking at a good amount of XAML. However, the basic skeleton will look something like so:

```
<VisualStateManager.VisualStateGroups>
<VisualStateGroup x:Name="MouseStateGroup">
    <VisualStateGroup.Transitions>
        <VisualTransition GeneratedDuration="00:00:01" To="MouseDownStar"/>
    </VisualStateGroup.Transitions>
    <VisualState x:Name="MouseEnterStar">
```

```

<Storyboard>
    <!-- Storyboard for MouseEnterStar -->
</Storyboard>
</VisualState>
<VisualState x:Name="MouseExitStar"/>
<VisualState x:Name="MouseDownStar">
    <Storyboard>
        <!-- Storyboard for MouseDownStar -->
    </Storyboard>
</VisualState>
</VisualStateGroup>
</VisualStateManager.VisualStateGroups>

```

Now that you have all of your states in place, all you need to do is to move between them when appropriate.

Changing Visual States in Code using the `VisualStateManager` Class

To complete your `StarButton`, you will use the `VisualStateManager` class to move between your states. Using the Events tab of the Properties window, handle the `MouseDown`, `MouseEnter` and `MouseLeave` events on your custom `UserControl`. Implement each handler to move into the related state as so:

```

public partial class StarButton : UserControl
{
    ...
    private void StarControl_MouseDown(object sender,
        System.Windows.Input.MouseEventArgs e)
    {
        // Parameter 1 : Which control am I working with?
        // Parameter 2 : Which state do I want to transition to?
        // Parameter 3 : Do I want to use transition times?
        VisualStateManager.GoToState(this, "MouseDownStar", true);
    }

    private void StarControl_MouseEnter(object sender,
        System.Windows.Input.MouseEventArgs e)
    {
        VisualStateManager.GoToState(this, "MouseEnterStar", true);
    }

    private void StarControl_MouseLeave(object sender,
        System.Windows.Input.MouseEventArgs e)
    {
        VisualStateManager.GoToState(this, "MouseExitStar", true);
    }
}

```

That completes the construction of your second custom control for this project! If you run your project, you should be able to test that your visual states are working correctly by interacting with the `StarButton` on your initial window.

Finalizing the Jackpot Deluxe Application

Now that you have your custom controls in place, you can wrap things up quite rapidly. Delete the current `StarControl` that is on your `Window`, and redefine the layout root to be a `StackPanel` rather than the current `Grid`. Here is one possible layout for your window (Figure 31-31).



Figure 31-31. The layout of the Jackpot Deluxe window

The key aspects of this markup are the definition of three custom `SpinControl` objects (named `imgFirst`, `imgSecond`, and `imgThird`) and an instance of the `StarButton` control (named `btnSpin`), which has handled the `MouseDown` event.

In addition, you will make use of three `TextBlock` controls (named `txtInstructions`, `txtScore` and `txtAttempts`) which will be used to inform the user about their current score, current number of attempts, and a general text message. Here is the full markup for the root `StackPanel`, which maintains a few nested `StackPanel` objects to boot:

```
<StackPanel x:Name="LayoutRoot" Background="#FF0F0202" Orientation="Vertical">
  <TextBlock x:Name="txtInstructions" Width="639" Height="96" Foreground="Yellow"
    HorizontalAlignment="Left" FontSize="24"
    TextAlignment="Center" Text="Try to Score 100 Points in 20 Attempts!"/>
```

```

<StackPanel Height="184" Width="639" Orientation="Horizontal">
    <StackPanel.Background>
        <LinearGradientBrush EndPoint="0.5,1" StartPoint="0.5,0">
            <GradientStop Color="#FF000000"/>
            <GradientStop Color="#FFB08282" Offset="1"/>
        </LinearGradientBrush>
    </StackPanel.Background>

    <!-- The SpinControls -->
    <custom:SpinControl x:Name="imgFirst" Height="125" Margin="70,0,0,0" Width="125"/>
    <custom:SpinControl x:Name="imgSecond" Height="125" Margin="70,0,0,0" Width="125"/>
    <custom:SpinControl x:Name="imgThird" Height="125" Margin="70,0,0,0" Width="125"/>
</StackPanel>

<StackPanel Height="120" Orientation="Horizontal">
    <!-- The StarButton -->
    <local:StarButton x:Name="btnSpin" HorizontalAlignment="Left" Margin="102,8,0,0"
        VerticalAlignment="Top" Width="100" Height="108" MouseDown="btnSpin_MouseDown"/>
    <TextBlock x:Name="txtScore" Text="Score: 0" FontFamily="Comic Sans MS" Width="140"
        Height="50" FontWeight="Bold" FontSize="24"
        Foreground="#FF6F0269" Margin="80,0,0,0" />
    <TextBlock x:Name="txtAttempts" Text="Attempts: 0" Height="19" Width="82"
        Foreground="#FF28EA16" Margin="70,0,0,0"/>
</StackPanel>

</StackPanel>

```

Within the C# code file, define three private member variables to keep track of the player's point total, the current number of attempts, and the maximum number of allowed spins:

```

public partial class MainWindow : Window
{
    private int totalPoints = 0;
    private int totalAttempts = 0;
    private int MaxAttempts = 20;
    ...
}

```

Now, define two private helper methods, which will be called if the user wins (defined as getting 100 points in 20 tries or less) or loses:

```

private void DoLosingCondition()
{
    // Change text for losing!
    this.txtInstructions.Text = "YOU LOSE!";
    this.txtInstructions.FontSize = 80;
    this.txtInstructions.Foreground = new SolidColorBrush(Colors.Gray);

    // Disable button, game over dude!
    this.btnSpin.IsEnabled = false;
}

```

```

private void DoWinningCondition()
{
    // Change text for winning!
    this.txtInstructions.Text = "YOU WIN!";
    this.txtInstructions.FontSize = 80;
    this.txtInstructions.Foreground = new SolidColorBrush(Colors.Orange);

    // Disable button, game over dude!
    this.btnSpin.IsEnabled = false;
}

```

As you can see, both of these methods will change the `Text` property of `txtInstructions` to a fitting message and disable your spin button.

The remaining bit of code is the logic behind the clicking of your `StarButton`. Consider the following implementation of the `MouseDown` event handler:

```

private void btnSpin_MouseDown(object sender,
    System.Windows.Input.MouseEventArgs e)
{
    // Add 1 to number of tries.
    this.txtAttempts.Text = string.Format("Attempts: {0}",
        (++totalAttempts).ToString());

    // Last attempt??
    if (totalAttempts >= MaxAttempts)
    {
        DoLosingCondition();
    }

    // Spin each control.
    int randomOne = this.imgFirst.Spin();
    int randomTwo = this.imgSecond.Spin();
    int randomThree = this.imgThird.Spin();

    // Calculate the new score. To make things simple, players only get
    // points if all three images are identical.
    if (randomOne == randomTwo && randomTwo == randomThree)
    {
        // Adjust points.
        totalPoints += 10;
        this.txtScore.Text = string.Format("Score: {0}", totalPoints.ToString());

        // Did they get 100 or more points?
        if (totalPoints >= 100)
        {
            DoWinningCondition();
        }
    }
}

```

This logic is very simple. Each time they click the custom StarButton, you check if they have reached the maximum number of attempts, and if so, display the losing condition. If they still have some attempts remaining, you spin each SpinControl object and check if each image is identical. If so, you add some points to the player total and check for the winning condition. Figure 31-32 shows the final end result:



Figure 31-32. The completed Jackpot Deluxe application!

That concludes the examination of building desktop applications using the Windows Presentation Foundation API. Over these last five chapters, you have learned quite a bit about this aspect of .NET development; however, there is much more to learn. As well, you have used Expression Blend to build a number of example applications.

Just like Visual Studio 2010, Expression Blend has a dedicated documentation system. If you are serious about learning the ins-and-outs of Expression Blend, be sure to consult the integrated help system. (If Expression Blend is loaded on your desktop, just press the F1 key.) Here, you will find dozens of excellent tutorials which will deepen your understanding of this key aspect of WPF (and Silverlight) application development (Figure 31-33).




Figure 31-33. Be kind to yourself and be sure to examining the help system of Expression Blend

Summary

This chapter examined a number of related WPF topics, all of which are focused on the construction of custom user controls. You started by investigating how WPF places a unique spin on traditional .NET programming primitives, specifically properties and events. As you have seen, a *dependency property* allows you to build a property which can integrate within the WPF set of services (animations, data bindings, styles and so on). On a related note, *routed events* provide a way for an event to flow up or down a tree of markup.

You then examined the relationship between a *logical tree* and *visual tree*. The logical tree is basically a one-to-one correspondence of the markup you would author to describe a WPF root element. Behind this logic tree is a much deeper visual tree that contains detailed rendering instructions.

The role of a *default template* was then examined. Remember, when you are building custom templates, you are essentially ripping out all (or part) of a control's visual tree and replacing it with your own custom implementation. From here, you learned a number of ways to build custom *UserControl* classes, including the use of the .NET 4.0 Visual State Manager, Expression Blend, and the integrated animation editor.

PART 7

■ ■ ■

Building Web Applications with ASP.NET



Building ASP.NET Web Pages

Until now, all of the examples in this book have focused on console-based and desktop graphical user interfaces created using the WPF API. The remainder of the text will explore how the .NET platform facilitates the construction of browser-based presentation layers using a technology named ASP.NET. To begin, you'll quickly review a number of key web development concepts (HTTP, HTML, client-side scripting, postbacks) and examine the role of Microsoft's commercial web server (IIS) as well as that of the ASP.NET development web server.

With this brief web primer out of the way, the remainder of this chapter concentrates on the structure of ASP.NET web pages (including the single-page and code-behind model) and examines the functionality of the `Page` base class. Along the way, you'll be introduced to the role of ASP.NET web controls, the directory structure of an ASP.NET web site, and how to use a `Web.config` file to control the runtime operation of your web sites via XML instructions.

Note If you wish to load any of the ASP.NET web site projects found within this book's downloadable source code, launch Visual Studio 2010 and select `File > Open > Web Site...` menu option. From the resulting dialog box, click on the `File System` button (mounted on the left hand side), and select the folder containing the web project files. This will load all content for the current web application into the Visual Studio IDE.

The Role of HTTP

Web applications are very different animals from graphical desktop applications. The first obvious difference is that a production-level web application involves at least two networked machines: one hosting the web site and the other viewing data within a web browser. Of course, during development it is entirely possible to have a single machine play the role of both the browser-based client and the hosting web server which serves up content. Given the nature of web applications, the networked machines in question must agree upon a particular wire protocol to determine how to send and receive data. The wire protocol that connects the computers in question is the Hypertext Transfer Protocol (HTTP).

The HTTP Request/Response Cycle

When a client machine launches a web browser (such as Opera, Mozilla Firefox, Apple Safari or Microsoft Internet Explorer), an *HTTP request* is made to access a particular resource (typically a web page) on the remote server machine. HTTP is a text-based protocol that is built upon a standard request/response paradigm. For example, if you navigate to `http://www.facebook.com`, the browser software leverages a web technology termed *Domain Name Service* (DNS) that converts the registered URL into a numerical value termed an *IP address*. At this point, the browser opens a socket connection (typically via port 80 for a nonsecure connection) and sends the HTTP request for processing to the target site.

The web server receives the incoming HTTP request and may choose to process out any client-supplied input values (such as values within a text box, check box, or list box) in order to format a proper HTTP *response*. Web programmers may leverage any number of technologies (CGI, ASP, ASP.NET, JSP, etc.) to dynamically generate the content to be emitted into the HTTP response. At this point, the client-side browser renders the returned HTML sent from the web server. Figure 32-1 illustrates the basic HTTP request/response cycle.




Figure 32-1. The HTTP request/response cycle

HTTP Is a Stateless Protocol

Another aspect of web development that is markedly different from traditional desktop programming is the fact that HTTP is essentially a *stateless* wire protocol. As soon as the web server sends a response to the client browser, everything about the previous interaction is forgotten. This is certainly not the case in a traditional desktop application, where the state of the executable is most often alive and kicking until the user shuts down the main window of the application.

Given this point, as a web developer, it is up to you take specific steps to “remember” information (such as items in a shopping cart, credit card numbers, and home addresses) about the users who are currently logged on to your site. As you will see in Chapter 34, ASP.NET provides numerous ways to handle state, using techniques such as session variables, cookies, and the application cache as well as the ASP.NET profile management API.

Understanding Web Applications and Web Servers

A *web application* can be understood as a collection of files (e.g., *.htm, *.aspx, image files, XML-based file data) and related components (such as a .NET code library) stored within a particular set of

directories on a web server. As shown in Chapter 34, ASP.NET web applications have a specific life cycle and provide numerous events (such as initial startup or final shutdown) that you can hook into to perform specialized processing during your website's operation.

A *web server* is a software product in charge of hosting your web applications; it typically provides a number of related services such as integrated security, File Transfer Protocol (FTP) support, mail exchange services, and so forth. Internet Information Services (IIS) is the Microsoft enterprise-level web server product, and it offers intrinsic support for classic ASP as well as ASP.NET web applications.

Assuming you have IIS properly installed on your workstation, you can interact with IIS from the Administrative Tools folder (located in the Control Panel folder) by double-clicking the Internet Information Services applet. Figure 32-2 shows the Default Web Site node of IIS 7 where a majority of the configuration details occur (if you are running earlier versions of IIS, your UI will look different).




Figure 32-2. The IIS applet can be used to configure the runtime behavior of Microsoft IIS

The Role of IIS Virtual Directories

A single IIS installation is able to host numerous web applications, each of which resides in a *virtual directory*. Each virtual directory is mapped to a physical directory on the machine's hard drive. For example, if you create a new virtual directory named CarsAreUs, the outside world can navigate to this site using a URL such as `http://www.MyDomain.com/CarsAreUs` (assuming your site's IP address has been registered with a DNS of `www.MyDomain.com`). Under the hood, this virtual directory maps to a physical root directory on the web server which contains the content of the CarsAreUs web application.

As you will see later in this chapter, when you create ASP.NET web applications using Visual Studio 2010, you have the option of having the IDE generate a new virtual directory for the current website automatically. However, if required, you are certainly able to manually create a virtual directory by hand by right-clicking the Default Web Site node of IIS and selecting Add Virtual Directory from the context menu.

The ASP.NET Development Web Server

Prior to .NET 2.0, ASP.NET developers were required to make use of IIS virtual directories during the development and testing of their web applications. In many cases, this tight dependency on IIS made team development more complex than necessary, not to mention that many network administrators frowned upon installing IIS on every developer's machine.

Happily, there is the option of a lightweight web server named the ASP.NET Development Web Server. This utility allows developers to host an ASP.NET web application outside the bounds of IIS. Using this tool, you can build and test your web pages from any folder on your machine. This is quite helpful for team development scenarios and for building ASP.NET web applications on versions of Windows that do not support IIS installations.

Most of the examples in this book will make use of the ASP.NET Development Web Server (via the correct Visual Studio 2010 project option) rather than hosting web content under an IIS virtual directory. While this approach can simplify the development of your web application, be aware that this web server is *not* intended to host production-level web applications. It is intended purely for development and testing purposes. Once a web application is ready for prime time, your site will need to be copied to an IIS virtual directory.

■ **Note** The Mono project (see Appendix B) provides a free ASP.NET plug-in for the Apache web server. This makes it possible to build and host ASP.NET web applications on operating systems other than Microsoft Windows. Check out <http://www.mono-project.com/ASP.NET> for details.

The Role of HTML

Once you have configured a directory to host your web application and you have chosen a web server to serve as the host, you need to create the content itself. Recall that a web application is simply a set of files that constitute the functionality of the site. To be sure, many of these files will contain Hypertext Markup Language (HTML) statements. HTML is a standard markup language used to describe how literal text, images, external links, and various HTML controls are to be rendered within the client-side browser.

While it is true that modern IDEs (including Visual Studio 2010) and web development platforms (such as ASP.NET) generate much of the HTML automatically, you will do well to have a working knowledge of HTML as you work with ASP.NET.

■ **Note** Recall from Chapter 2 that Microsoft has released a number of free IDEs under the Express family of products (such as Visual C# Express). If you are interested in web development, you may wish to also download Visual Web Developer Express. This free IDE is geared exclusively towards the construction of ASP.NET web applications.

While this section will most certainly not cover all aspects of HTML, it will touch on some basics. This will help you better understand the markup generated on your behalf by the ASP.NET programming model.

HTML Document Structure

An HTML file consists of a set of tags that describe the look and feel of a given web page. The basic structure of an HTML document tends to remain the same. For example, *.htm files (or, equivalently, *.html files) open and close with <html> and </html> tags, typically define a <body> section, and so forth. Keep in mind that traditional HTML is *not* case sensitive. Therefore, in the eyes of the hosting browser, <HTML>, <html>, and <HtmL> are identical.

To illustrate some HTML basics, open Visual Studio 2010 and create empty HTML Page file via the File ➤ New ➤ File menu selection (notice that you are not making a web project at this point, you are just opening a blank HTML file for editing). Once you have done so, save it as default.htm in a convenient location. You should see the following initial markup:

```
<!DOCTYPE html PUBLIC "-//W3C//DTD XHTML 1.0 Transitional//EN"
    "http://www.w3.org/TR/xhtml1/DTD/xhtml1-transitional.dtd">
<html xmlns="http://www.w3.org/1999/xhtml" >
    <head>
        <title>Untitled Page</title>
    </head>
    <body>

    </body>
</html>
```

First of all, notice that this HTML file opens with a DOCTYPE processing instruction. This informs the IDE that the contained HTML tags should be validated against the XHTML standard. As mentioned, traditional HTML was very *loose* in its syntax. Beyond the case insensitivity issue, it was permissible to define an opening element (such as
 for a line break) that did not have a corresponding closing break (</br> in this case). The XHTML standard is a W3C specification that adds some much-needed rigor to the basic HTML markup language.

Note By default, Visual Studio 2010 validates all HTML documents against the XHTML 1.0 Transitional validation scheme to ensure the markup is in sync with the XHTML standard. If you wish to specify an alternative validation scheme (such as HTML 4.01), activate the Tools ➤ Options dialog box, expand the Text Editor node, expand the HTML node, and then select the Validation node. On a related note, if you would rather not see validation warnings, simply uncheck the Show Errors check box found in the same location.

The <html> and </html> tags are used to mark the beginning and end of your document. Notice that the opening <html> tag is further qualified with an xmlns (XML namespace) attribute that qualifies the various tags that may appear within this document (again, by default these tags are based on the XHTML standard). Web browsers use these particular tags to understand where to begin applying the rendering formats specified in the body of the document. The <body> scope is where the vast majority of the actual content is defined. To spruce things up just a bit, update the title of your page as so:

```
<head>
    <title>This is my simple web page</title>
</head>
```

Not surprisingly, the <title> tags are used to specify the text string that should be placed in the title bar of the calling web browser.

The Role of an HTML Form

The real meat of most *.htm files occurs within the scope of the <form> elements. An *HTML form* is simply a named group of related UI elements typically used to gather user input. Do not confuse an HTML form with the entire display area shown by a given browser. In reality, an HTML form is more of a *logical grouping* of widgets placed in the <form> and </form> tag set:

```
<html xmlns="http://www.w3.org/1999/xhtml" >
<head>
    <title>This is my simple web page</title>
</head>
<body>
    <form id="defaultPage">
        <!-- Insert web UI content here -->
    </form>
</body>
</html>
```

This form has been assigned the ID of "defaultPage". Typically, the opening <form> tag supplies an action attribute that specifies the URL to which to submit the form data, as well as the method of transmitting that data itself (POST or GET). For the time being, let's look at the sorts of items that can be placed in an HTML form (beyond simple literal text).

The Visual Studio 2010 HTML Designer Tools

Visual Studio 2010 provides an HTML tab on the Toolbox that allows you to select an HTML control that you wish to place on your HTML designer (see Figure 32-3).




Figure 32-3. The HTML tab of the Toolbox

■ **Note** When you are building ASP.NET web pages, you will *not* be using these HTML controls to create the user interface! Rather, you will use the ASP.NET web controls, which will render back the correct HTML on your behalf.

Similar to the process of building a Windows Forms or WPF application, these HTML controls can be dragged onto the HTML designer surface. If you click on the Split button on the bottom of the HTML editor, the bottom pane of the HTML editor will display the HTML visual layout and the upper pane will show the related markup. Another benefit of this editor is that as you select markup or an HTML UI element, the corresponding representation is highlighted (Figure 32-4).




Figure 32-4. The Visual Studio 2010 HTML designer

Visual Studio 2010 also allows you to edit the overall look and feel of the *.htm file or a given HTML control in the <form> using the Properties window. For example, if you select DOCUMENT from the drop-down list of the Properties window, you are able to configure various aspects of the HTML page, such as the background color, background image (if any), title, and so forth (Figure 32-5).




Figure 32-5. The Visual Studio Properties window can be used to configure the HTML markup

As you use the Properties window to configure an aspect of your web page, the IDE will update the HTML accordingly. Here is a minor change to your page that now sets the background color of the overall document:

```
<html xmlns="http://www.w3.org/1999/xhtml" >
<head>
    <title>This is my simple web page</title>
</head>
<body bgcolor="#ffffcc">
    <form id="defaultPage">
        <!-- Insert web UI content here -->
    </form>
</body>
</html>
```

Building an HTML Form

Update the `<body>` of the `default.htm` file to display some literal text that prompts the user to enter a message (be aware that you can enter and format literal textual content by typing directly in the HTML designer). Here you are using the `<h1>` tag to set a header weight, `<p>` for a paragraph block and `<i>` for italic text:

```
<html xmlns="http://www.w3.org/1999/xhtml" >
<head>
    <title>This is my simple web page</title>
</head>
<body bgcolor="#ffffcc">
    <!-- Prompt for user input-->
```

```

<h1 align="center">Simple HTML Page</h1>
<p align="center">
    <br/>
    <i>Please enter a message</i>.
</p>

<form id="defaultPage">
</form>

</body>
</html>

```

Now let's build the HTML form itself. In general, each HTML control is described using an `id` attribute (used to identify the item programmatically) and a `type` attribute (used to specify which UI element you are interested in placing in the `<form>` declaration). Depending on which UI widget you have declared, you will find additional attributes specific to the control that can be modified using the Properties window.

The UI you will build here will contain one text field and two button types. The first button will be used to run a client side script and the other to reset the form input fields to the default values. Update your HTML form as so:

```

<!-- Build a form to get user info -->
<form id="defaultPage">
    <p align="center">
        Your Message:
        <input id="txtUserMessage" type="text"/></p>
    <p align="center">
        <input id="btnShow" type="button" value="Show!"/>
        <input id="btnReset" type="reset" value="Reset"/>
    </p>
</form>

```

Notice that you have assigned relevant IDs to each control (`txtUserMessage`, `btnShow`, and `btnReset`) and that each input item has an extra attribute named `type` that marks these input controls as UI items that automatically clear all fields to their initial values (`type="reset"`), receive text input (`type="text"`), or function as a simple client side button which does not post back to the web server (`type="button"`).

Save your file, then right click on the designer and select the View in Browser menu option. Figure 32-6 shows the current page with Google Chrome.



Figure 32-6. Your simple default.htm page

■ **Note** When you select the View in Browser option, Visual Studio 2010 will automatically launch the ASP.NET Development web server to host your content.

The Role of Client-Side Scripting

In addition to HTML UI elements, a given *.htm file may contain blocks of script code that will be processed by the requesting browser. There are two major reasons why client-side scripting is used:

- To validate user input in the browser before posting back to the web server
- To interact with the Document Object Model (DOM) of the browser

Regarding the first point, understand that the inherent evil of a web application is the need to make frequent round-trips (termed *postbacks*) to the server machine to update the HTML to be rendered into the browser. While postbacks are unavoidable, you should always be mindful of ways to minimize travel across the wire. One technique that saves postbacks is to use client-side scripting to validate user input before submitting the form data to the web server. If an error is found, such as not supplying data within a required field, you can alert the user to the error without incurring the cost of posting back to the web server. (After all, nothing is more annoying to users than posting back on a slow connection, only to receive instructions to address input errors!)

■ **Note** Be aware that even when performing client-side validation (for improved response time), validation should also occur on the web server itself. This will ensure that the data has not been tampered with as it was sent across the wire. The ASP.NET validation controls will automatically perform client- and server-side validation (more on this in the following chapter).

Client-side scripts can also be used to interact with the underlying object model (the Document Object Model or DOM) of the web browser itself. Most commercial browsers expose a set of objects that can be leveraged to control how the browser should behave.

When a browser parses an HTML page, it builds an object tree in memory, representing all the contents of the Web page (forms, input controls, etc). Browsers provide an API called DOM that exposes the object tree and allows you to modify its contents programmatically. For example, you can write JavaScript that executes in the browser to get the values from specific controls, change the color of a control, add new controls to the page dynamically, etc.

One major annoyance is the fact that different browsers tend to expose similar, *but not identical*, object models. Thus, if you emit a block of client-side script code that interacts with the DOM, it may not work identically on all browsers (thus, testing is always a must!).

ASP.NET provides the `HttpRequest.Browser` property, which allows you to determine at runtime the capacities of the browser and device that sent the current request. You can use this information to stylize how to emit back the HTTP response in the most optimal manner. But you rarely need to worry about this, unless you are implementing custom controls, because all the standard Web controls in ASP.NET automatically know how to render themselves appropriately based on the browser type. This remarkable capability is known as *adaptive rendering*, and it's implemented out-of-the-box for all standard ASP.NET controls.

There are many scripting languages that can be used to author client-side script code. Two of the more popular ones are VBScript and JavaScript. VBScript is a subset of the Visual Basic 6.0 programming language. Be aware that Microsoft Internet Explorer is the only web browser that has built-in support for client-side VBScript support (other browsers may or may not provide optional plug-ins). Note that if you wish your HTML pages to work correctly in any commercial web browser, do *not* use VBScript for your client-side scripting logic.

The other popular scripting language is JavaScript. It's important to note that JavaScript is in no way, shape, or form the same as the Java language. While JavaScript and Java have a somewhat similar syntax, JavaScript is not a full-fledged OOP language, and thus it is far less powerful than Java. The good news is that all modern-day web browsers support JavaScript, which makes it a natural candidate for client-side scripting logic.

A Client-Side Scripting Example

To illustrate the role of client-side scripting, let's first examine how to intercept events sent from client-side HTML GUI widgets. To capture the Click event for the Show button, select `btnShow` from the upper-left drop-down list of the HTML form designer and select the `onclick` event from the right drop-down list. This will add an `onclick` attribute to the definition of the Show button:

```
<input id="btnShow" type="button" value="Show!"  
      onclick="return btnShow_onclick()" />
```

Visual Studio 2010 will also create an empty JavaScript function that will be called when the user clicks the button. Within this stub, use the `alert()` method to display a client-side message box containing the value in the text box via the `value` property:

```
<script language="javascript" type="text/javascript">  
// <![CDATA[  
    function btnShow_onclick() {  
        alert(txtUserMessage.value);  
    }  
]]>
```

```
// ]]>
</script>
```

Note that the scripting block has been wrapped within a CDATA section. The reason for this is simple. If your page ends up on a browser that does not support JavaScript, the code will be treated as a comment block and ignored. Of course, your page may be less functional, but the upside is that your page will not blow up when rendered by the browser.

In any case, if you view your page in a browser once again, you should be able to type a message and see it pop up in a client side message box (Figure 32-7).




Figure 32-7. Invoking a client side JavaScript function

As well, when you click on the Reset button, you should find that the text area is cleared of data, as this particular button has been created by specifying type="reset".

Posting Back to the Web Server

This simple HTML page is executing all functionality within the hosting browser. A *real* web page needs to post back to a resource on the web server, passing all of the input data at the same time. Once the server side resource receives this data, it can use it to build a proper HTTP response.

The action attribute on the opening <form> tag specifies the recipient of the incoming form data. Possible receivers include mail servers, other HTML files on the web server, a classic (COM-based) Active Server Pages (ASP) file, an ASP.NET web page, and so forth.

Beyond the action attribute, you will also likely have a *submit button*, which when clicked, will transmit the form data to the web application via an HTTP request. You have no need to do so for this example; however, here is an update to the default.htm file, specifying the following attribute in the opening <form> tag:

```
<form id="defaultPage"
      action="http://localhost/Cars/ClassicAspPage.asp" method="GET">
  <input id="btnPostBack" type="submit" value="Post to Server!"/>
  ...
</form>
```

When the submit button for this form is clicked, the form data is sent to the `ClassicAspPage.aspx` at the specified URL. When you specify `method="GET"` as the mode of transmission, the form data is appended to the query string as a set of name/value pairs separated by ampersands. You may have seen this sort of data in your browser before, for example:

```
http://www.google.com/search?hl=en&source=hp&q=vikings&cts=1264370773666&aq=f&aql=&aqi=g1g-z1g1g-z1g1g-z1g4&oq=
```

The other method of transmitting form data to the web server is to specify `method="POST"`:

```
<form id="defaultPage"
      action="http://localhost/Cars/ClassicAspPage.aspx" method = "POST">
...
</form>
```

In this case, the form data is not appended to the query string. Using POST, the form data is not directly visible to the outside world. More important, POST data does not have a character-length limitation; many browsers have a limit for GET queries.

Postbacks under ASP.NET

When you are building ASP.NET based web sites, the framework will take care of the posting mechanics on your behalf. One of the many benefits of building a web site using ASP.NET is that the programming model layers on top of standard HTTP Request/Response an event driven system. Thus, rather than manually setting an `action` attribute and defining an HTML `submit` button, you can simply handle events on the ASP.NET web controls using standard C# syntax.

Using this event driven model, you can very easily post back to the web server using a large number of controls. If you require, you can post back to the web server if the user clicks on a radio button, an item in a list box, a day on a calendar control, and so on. In each case, you simply handle the correct event, and the ASP.NET runtime will automatically emit back the correct HTML posting data.

■ **Source Code** The SimpleWebPage website is included under the Chapter 32 subdirectory.

The Feature Set of the ASP.NET API

At this point, your whirlwind review of classic web application development is complete, and you are ready to dive into ASP.NET itself. Before you create your first web application, let me set the stage regarding the major features of .NET's web development API, as seen from the major versions of the framework.

Major Features of ASP.NET 1.0-1.1

The first release of ASP.NET (version 1.x) contained a number of features that allow developers to build web applications in a strongly typed and object oriented manner. Here are some key features which are supported in all versions of the .NET platform:

- ASP.NET provides a model termed *code-behind*, which allows you to separate presentation logic (HTML) from business logic (C# code).
- ASP.NET pages are coded using .NET programming languages, rather than server side scripting languages. The code files are compiled into valid .NET *.dll assemblies (which translates into much faster execution).
- Web controls allow programmers to build the GUI of a web application in a manner similar to building a Windows Forms/WPF application.
- By default, ASP.NET web controls automatically maintain their state during postbacks using a hidden form field named `_VIEWSTATE`.
- ASP.NET web applications can make use of any of the assemblies within the .NET base class libraries (of course, it makes little sense to make use of desktop GUI APIs such as Windows Forms within the context of a web app).
- ASP.NET web applications can be easily configured using standard IIS settings or using a web application configuration file (`Web.config`).

The first point I want to elaborate on here is the fact that the UI of an ASP.NET web page is built using any number of *web controls*. Unlike a typical HTML control, web controls are executed on the web server and will emit back to the HTTP response their correct HTML tags. This alone is a huge benefit of ASP.NET in that the amount of HTML you must manually author by hand diminishes greatly. By way of a quick example, assume you have defined the following ASP.NET web control in an ASP.NET web page:

```
<asp:Button ID="btnMyButton" runat="server" Text="Button" BorderColor="Blue"
    BorderStyle="Solid" BorderWidth="5px" />
```

You'll learn the details of declaring ASP.NET web controls soon enough, but for right now, notice that many attributes of the `<asp:Button>` control look very similar to the properties you have encountered in the Windows Forms and WPF examples (`BorderColor`, `Text`, `BorderStyle`, etc.). The same is true for all ASP.NET web controls because when Microsoft built the web control toolkit, these widgets were purposely designed to look and feel like their desktop counterparts.

Now, if a browser makes a call to the `*.aspx` file containing this control, the control responds by emitting into the output stream the following HTML declaration:

```
<input type="submit" name="btnMyButton" value="Button" id="btnMyButton"
    style="border-color:Blue; border-width:5px; border-style:Solid;" />
```

Notice how the web control emits back standard HTML (or XHTML, based on your settings) that can be rendered in any browser. Given this, understand that using ASP.NET web controls in no way ties you to the Microsoft family of operating systems or to Microsoft Internet Explorer. Any operating system or browser (including those on handheld devices such as the Apple iPhone or BlackBerry devices) can view an ASP.NET web page.

Next, note from the previous list of features that an ASP.NET web application will be compiled into a .NET assembly. Thus, your web projects are no different than any .NET *.dll built during this book. The compiled web application will be composed of CIL code, an assembly MANIFEST, and type metadata. This has a number of huge benefits, most notably performance gains, strong typing, and the ability to be micromanaged by the CLR (e.g., garbage collection, etc.).

Finally, ASP.NET web applications provide a programming model whereby you can partition your page's markup from its related C# code base using *code files*. You'll learn about this topic in just a bit, but know that this feature addresses a common complaint found when building classic (COM-based) ASP pages, where a typical *.asp file was a confused mismatch of HTML and script code. Using code files, the markup you type will map to a full-blown object model that is merged with your C# code file via partial class declarations.

Major Features of ASP.NET 2.0

ASP.NET 1.x was a major step in the right direction, and ASP.NET 2.0 provided many additional bells and whistles that helped ASP.NET move from a way to build dynamic *web pages* to a way to build feature rich *web sites*. Consider this partial list of key features:

- Introduction of the ASP.NET Development web server (which means developers no longer need IIS installed on their development computers).
- A large number of new web controls that handle many complex situations (navigation controls, security controls, new data binding controls, etc.).
- The introduction of *master pages*, which allow developers to attach a common UI frame to a set of related pages.
- Support for *themes*, which offer a declarative manner to change the look and feel of the entire web application on the web server.
- Support for *Web Parts*, which allow end users to customize the look and feel of a web page and store their settings for later use (a la portals).
- Introduction of a web-based configuration and management utility that maintains the various *Web.config* files.

Beyond the ASP.NET Development web server, one of the biggest additions brought forth with ASP.NET 2.0 was the introduction of *master pages*. As you are aware, most web sites have a look and feel which is common to all pages on the site. Consider a commercial web site such as www.amazon.com. Every page has the same elements, such as a common header, common footer, common navigation menus and so on.

Using a master page, you can model this common functionality and define *placeholders* that other *.aspx files can plug into. This makes it very easy to quickly reshape the overall look and feel of your site (reposition the navigation bar, change the header logo, and so on) by simply changing the master page, leaving the other *.aspx files unmodified.

■ **Note** Master pages are so useful that as of Visual Studio 2010, all new ASP.NET web projects will include a master page by default.

ASP.NET 2.0 also added many new web controls into the mix, including controls that automatically incorporate common security features (log in controls, password recovery controls, etc), controls that allow you to layer a navigational structure on top of a set of related *.aspx files, and even more controls for performing complex data binding operations, where the necessary SQL queries could be generated using a set of ASP.NET web controls.

Major Features of ASP.NET 3.5 (and .NET 3.5 SP1)

.NET 3.5 added the ability for ASP.NET web applications to make use of the LINQ programming model (also introduced in .NET 3.5) and the following web-centric features:

- New controls to support Silverlight development (recall that this is a WPF-based API for designing rich media content for a website).
- Support for data binding against ADO.NET entity classes (see Chapter 23).
- Support for ASP.NET Dynamic Data. This is a Ruby on Rails-inspired web framework that can be used to build data driven web applications. It exposes tables in a database by encoding it in the URI of the ASP.NET web service, and the data in the table is automatically rendered to HTML.
- Integrated support for Ajax-style development, which essentially allows for micro-postbacks to refresh part of a web page as quickly as possible.

One of the most welcomed features in ASP.NET 3.5 was a new set of controls that allow for Ajax development. This web-centric API makes it possible to refresh a small portion of a larger web page in the most efficient manner possible. While Ajax can be used by any web development API, doing so within an ASP.NET site is very simple because the Ajax controls do all of the heavy lifting by emitting back the necessary client side JavaScript code on your behalf.

The ASP.NET Dynamic Data project templates, introduced with .NET 3.5 Service Pack 1, provide a new model to build sites that are driven heavily by a relational database. Of course, most web sites will need to communicate with databases to some extent, but the ASP.NET Dynamic Data projects are tightly connected to the ADO.NET Entity Framework and are squarely focused on the rapid development of data-driven sites (similar to what one might build when using Ruby).

Major Features of ASP.NET 4.0

And this brings me to the web features that ship with the current version of the framework, .NET 4.0. Beyond allowing you to leverage the overall .NET 4.0 features, here is a hit list of some of the key web-centric features:

- The ability to compress “view state” data using the GZIP standard.
- Updated browser definitions to ensure that ASP.NET pages render correctly on new browsers and devices (Google Chrome, Apple iPhone, BlackBerry devices, etc.).
- Ability to customize the output of validation controls using a cascading style sheet (CSS).

- Inclusion of the ASP.NET Chart control, which allows for building ASP.NET pages that include intuitive charts for complex statistical or financial analysis.
- Official support for the ASP.NET Model View Controller project template, which decreases the dependency among application layers by using the Model-View-Controller (MVC) pattern.

Note that this list of ASP.NET 1.0-4.0 features is in no way all inclusive, but it does accentuate just how feature-rich this web API truly is. Truth be told, if I were to cover every possible feature of ASP.NET, this book would easily double in size (triple, perhaps). Since this is not realistic, the goal for the remainder of text is to examine the core features of ASP.NET that you will likely use on a day-to-day basis. Be sure to make use of the .NET Framework 4.0 SDK documentation to check out the features not covered here.

Note If you require a comprehensive treatment of building web applications using ASP.NET, I suggest picking up a copy of *Pro ASP.NET 4.0 in C# 2010, Third Edition* by Matthew MacDonald (Apress, 2010).

Building a Single File ASP.NET Web Page

As it turns out, an ASP.NET web page can be constructed using one of two approaches, the first of which is to build a single *.aspx file that contains a blend of server-side code and HTML. Using this *single-file page model* approach, the server-side code is placed within a `<script>` scope, but the code itself is *not* script code proper (e.g., VBScript/JavaScript). Rather, the code within a `<script>` block are written in your .NET language of choice (C#, Visual Basic, etc.).

If you are building a web page that contains very little code (but a good deal of static HTML), a single-file page model may be easier to work with, as you can see the code and the markup in one unified *.aspx file. In addition, placing your procedural code and HTML markup into a single *.aspx file provides a few other advantages:

- Pages written using the single-file model are slightly easier to deploy or to send to another developer.
- Because there is no dependency between multiple files, a single-file page is easier to rename.
- Managing files in a source code control system is slightly easier, as all the action is taking place in a single file.

On the downside, the single file page model can lead to the same problems you had under classic COM-based ASP: a single file that is doing too much (defining UI markup and programming logic in one place). Nevertheless, you'll begin your journey of ASP.NET by examining the single-file page model.

Your goal is to build an *.aspx file that displays the Inventory table of the AutoLot database (created in Chapter 21) using the connected layer (but, as you would guess, you could also use the disconnected layer or the Entity Framework). To begin, launch Visual Studio 2010 and create a new Web Form using the File ➤ New ➤ File menu option (see Figure 32-8).




Figure 32-8. Creating a new single file ASP.NET page

Once you have done so, save this file as Default.aspx under a new directory on your hard drive that you can easily find later (for example, C:\MyCode\SinglePageModel).

Referencing AutoLotDAL.dll

Next, use Windows Explorer to create a subdirectory under the SinglePageModel folder named *bin*. The specially named *bin* subdirectory is a registered name with the ASP.NET runtime engine. Into the \bin folder of a website's root, you are able to deploy any private assemblies used by the web application. For this example, place a copy of AutoLotDAL.dll (see Chapter 21) into the C:\MyCode\SinglePageModel\bin folder.

Note As shown later in this chapter, when you use Visual Studio 2010 to create a ASP.NET web project, the IDE will maintain the \bin folder on your behalf.

Designing the UI

Now, using the Visual Studio 2010 Toolbox, select the Standard tab and drag and drop a Button, Label, and GridView control (the GridView widget can be found under the Data tab of the Toolbox) onto the page designer between the opening and closing `<form>` elements. Feel free to make use of the Properties window to set various visual properties settings as you choose. Also, be sure to give each web widget a proper name

via the ID attribute. Figure 32-9 shows one possible design. (I kept the example's look and feel intentionally bland to minimize the amount of control markup, but feel free to spruce things up to your liking.)




Figure 32-9. The Default.aspx GUI

Now, locate the `<form>` section of your page. Notice how each web control has been defined using an `<asp:>` tag. After this tag prefix, you will find the name of an ASP.NET web control (Label, GridView and Button). Before the closing tag of a given element, you will find a series of name/value pairs that correspond to the settings you made in the Properties window, for example:

```
<form id="form1" runat="server">
<div>
    <asp:Label ID="lblInfo" runat="server"
        Text="Click on the Button to Fill the Grid">
    </asp:Label>
    <br />
    <br />
    <asp:GridView ID="carsGridView" runat="server">
    </asp:GridView>
    <br />
    <asp:Button ID="btnFillData" runat="server" Text="Fill Grid" />
</div>
</form>
```

You will dig into the full details of ASP.NET web controls later in Chapter 33. Until then, recall that web controls are objects processed on the web server that emit back their HTML representation into the outgoing HTTP response automatically. Beyond this major benefit, ASP.NET web controls mimic a desktop-like programming model in that the names of the properties, methods, and events typically echo a Windows Forms/WPF counterpart.

Adding the Data Access Logic

Handle the Click event for the Button type using either the Visual Studio Properties window (via the lightning bolt icon) or the drop-down boxes mounted at the top of the designer window (like you did for

this chapter's HTML review section). Once you do, you will find your Button's definition has been updated with an OnClick attribute that is assigned to the name of the Click event handler you entered:

```
<asp:Button ID="btnFillData" runat="server"
    Text="Fill Grid" OnClick="btnFillData_Click"/>
```

Now, within the *.aspx server side `<script>` block author the Click event handler. Add the following code, noticing that the incoming parameters are a dead-on match for the target of the `System.EventHandler` delegate, which you have seen in many examples in this book:

```
<script runat="server">
    protected void btnFillData_Click(object sender, EventArgs args)
    {
    }
</script>
```

The next step is to populate the `GridView` using the functionality of your `AutoLotDAL.dll` assembly. To do so, you must use the `<%@ Import %>` directive to specify that you are using the `AutoLotConnectedLayer` namespace.

Note You will only need to use the `<%@ Import %>` directive if you are building a page with the single file code model. If you are using the default code file approach, you will simply use the `using` keyword of C# to include namespaces in your code file. The same is true for the `<%@ Assembly %>` directive, described next.

In addition, you need to inform the ASP.NET runtime that this single-file page is referencing the `AutoLotDAL.dll` assembly via the `<%@ Assembly %>` directive (more details on directives in just a moment). Here is the remaining relevant page logic of the `Default.aspx` file (modify your connection string as required):

```
<%@ Page Language="C#" %>
<%@ Import Namespace = "AutoLotConnectedLayer" %>
<%@ Assembly Name = "AutoLotDAL" %>

<!DOCTYPE html PUBLIC "-//W3C//DTD XHTML 1.0 Transitional//EN"
    "http://www.w3.org/TR/xhtml1/DTD/xhtml1-transitional.dtd">

<script runat="server">
    void btnFillData_Click(object sender, EventArgs args)
    {
        InventoryDAL dal = new InventoryDAL();
        dal.OpenConnection(@"Data Source=(local)\SQLEXPRESS;" +
            "Initial Catalog=AutoLot;Integrated Security=True");
```

```

carsGridView.DataSource = dal.GetAllInventory();
carsGridView.DataBind();
dal.CloseConnection();
}
</script>
<html xmlns="http://www.w3.org/1999/xhtml" >
...
</html>

```

Before you dive into the details behind the format of this *.aspx file, let's try a test run. First, save your *.aspx file. Now, right click anywhere on the *.aspx designer and select the View in Browser menu option, which will launch the ASP .NET Development web server, at which point the web controls render back their corresponding HTML tags. Figure 32-10 shows the output once you click the Fill Grid button.

When the page is served, you will initially see your Label and Button controls. However, when you click your button control, a postback occurs to the web server, at which point the web controls render back their corresponding HTML tags. Figure 32-10 shows the output once you click the Fill Grid button.




Figure 32-10. ASP.NET provides a declarative data binding model

Given, the current UI is quite bland. To spice up the current example, select the GridView control on the designer, and using the context menu (that tiny arrow on the upper left of the control), select the Auto Format option (Figure 32-11).




Figure 32-11. A richer GridView control!

From the resulting dialog box, pick a template that suits your fancy (I picked “Slate”). Once you click OK, view the generated control declaration, which is quite a bit richer than before:

```
<asp:GridView ID="carsGridView" runat="server" BackColor="White"
    BorderColor="#E7E7FF" BorderStyle="None" BorderWidth="1px" CellPadding="3"
    GridLines="Horizontal">
    <AlternatingRowStyle BackColor="#F7F7F7" />
    <FooterStyle BackColor="#B5C7DE" ForeColor="#4A3C8C" />
    <HeaderStyle BackColor="#4A3C8C" Font-Bold="True" ForeColor="#F7F7F7" />
    <PagerStyle BackColor="#E7E7FF" ForeColor="#4A3C8C" HorizontalAlign="Right" />
    <RowStyle BackColor="#E7E7FF" ForeColor="#4A3C8C" />
    <SelectedRowStyle BackColor="#738A9C" Font-Bold="True" ForeColor="#F7F7F7" />
    <SortedAscendingCellStyle BackColor="#F4F4FD" />
    <SortedAscendingHeaderStyle BackColor="#5A4C9D" />
    <SortedDescendingCellStyle BackColor="#D8D8F0" />
    <SortedDescendingHeaderStyle BackColor="#3E3277" />
</asp:GridView>
```

If you view your application again and click on your button, you will now see a more interesting UI (Figure 32-12), shown via Apple Safari on my Windows 7 install.




Figure 32-12. Your simple web page in Apple Safari

That was simple, yes? Of course, as they say, the devil is in the details, so let's dig a bit deeper into the composition of this *.aspx file, beginning with examining the role of the `<%@Page... %>` directive. Do be aware that the topics you examine will apply directly to the more preferred *code file* model examined next.

The Role of ASP.NET Directives

A given *.aspx file will typically open with a set of *directives*. ASP.NET directives are always denoted with `<%@ ... %>` markers and may be qualified with various attributes to inform the ASP.NET runtime how to process the attribute in question.

Every *.aspx file must have at minimum a `<%@Page%>` directive that is used to define the managed language used within the page (via the `language` attribute). Also, the `<%@Page%>` directive may define the name of the related code-behind file (examined soon), and so on. Table 32-1 documents some of the more interesting `<%@Page%>`-centric attributes.

Table 32-1. Select Attributes of the `<%@Page%>` Directive

Attribute	Meaning in Life
CodePage	Specifies the name of the related code-behind file
EnableTheming	Establishes whether the controls on the *.aspx page support ASP.NET themes

Table 32-1. Select Attributes of the `<%@Page%>` Directive (continued)

Attribute	Meaning in Life
EnableViewState	Indicates whether view state is maintained across page requests (more details on this property in Chapter 33)
Inherits	Defines a class in the code-behind page the *.aspx file derives from, which can be any class derived from <code>System.Web.UI.Page</code>
MasterPageFile	Sets the master page used in conjunction with the current *.aspx page
Trace	Indicates whether tracing is enabled

In addition to the `<%@Page%>` directive, a given *.aspx file may specify various `<%@Import%>` directives to explicitly state the namespaces required by the current page and `<%@Assembly%>` directives to specify the external code libraries used by the site (typically placed under the \bin folder of the website).

In this example, you specified you were making use of the types within the `AutoLotConnectedLayer` namespace within the `AutoLotDAL.dll` assembly. As you would guess, if you need to make use of additional .NET namespaces, you simply specify multiple `<%@Import%>/<%@Assembly%>` directives.

Given your current knowledge of .NET, you may wonder how this *.aspx file avoided specifying additional `<%@Import%>` directives to gain access to the `System` namespace in order to gain access to the `System.Object` and `System.EventHandler` types (among others). The reason is that all *.aspx pages automatically have access to a set of key namespaces that are defined within the `web.config` file under your installation path of the .NET platform. Within this XML-based file, you would find a number of autoimported namespaces, including the following:

```

<pages>
  <namespaces>
    <add namespace="System"/>
    <add namespace="System.Collections"/>
    <add namespace="System.Collections.Generic"/>
    <add namespace="System.Collections.Specialized"/>
    <add namespace="System.Configuration"/>
    <add namespace="System.Data.Entity.Design" />
    <add namespace="System.Data.Linq" />
    <add namespace="System.Linq" />
    <add namespace="System.Text" />
    <add namespace="System.Text.RegularExpressions" />
    <add namespace="System.Web" />
    <add namespace="System.Web.Caching" />
    <add namespace="System.Web.SessionState" />
    <add namespace="System.Web.Security" />
    <add namespace="System.Web.Profile" />
    <add namespace="System.Web.UI" />
    <add namespace="System.Web.UI.WebControls" />
    <add namespace="System.Web.UI.WebControls.WebParts" />
    <add namespace="System.Web.UI.HtmlControls" />
  ...

```

```
</namespaces>
</pages>
```

To be sure, ASP.NET does define a number of other directives that may appear in an *.aspx file above and beyond `<%@Page%>`, `<%@Import%>`, and `<%@Assembly%>`; however, I'll reserve commenting on those for the time being. You'll see examples of other directives as you progress through the remaining chapters.

Analyzing the “Script” Block

Under the single-file page model, an *.aspx file may contain server-side scripting logic that executes on the web server. In this case, it is *critical* that all of your server-side code blocks are defined to execute at the server, using the `runat="server"` attribute. If the `runat="server"` attribute is not supplied, the runtime assumes you have authored a block of *client-side* script to be emitted into the outgoing HTTP response, and it will throw an exception. That being said, here is a proper server side `<script>` block:

Note All ASP.NET web controls will need to have the `runat="server"` attribute in their opening declaration. If not, they will not render their HTML into the outbound HTTP response.

```
<script runat="server">
    void btnFillData_Click(object sender, EventArgs args)
    {
        InventoryDAL dal = new InventoryDAL();
        dal.OpenConnection(@"Data Source=(local)\SQLEXPRESS;" +
            "Initial Catalog=AutoLot;Integrated Security=True");
        carsGridView.DataSource = dal.GetAllInventory();
        carsGridView.DataBind();
        dal.CloseConnection();
    }
</script>
```

The signature of this helper method should look strangely familiar. Recall that a given control event handler must match the pattern defined by a related .NET delegate. The delegate in question is `System.EventHandler` that can only call methods that take `System.Object` as the first parameter and `System.EventArgs` as the second.

Analyzing the ASP.NET Control Declarations

The final point of interest in this first example is the declaration of the `Button`, `Label`, and `GridView` web controls. Like classic ASP and raw HTML, ASP.NET web widgets are scoped within `<form>` elements. This time, however, the opening `<form>` element is marked with the `runat="server"` attribute and is qualified with the `asp:` tag prefix. Any control which takes this prefix is a member of the ASP.NET control library and has a corresponding C# class representation in a given .NET namespace of the .NET base class libraries. Here you find:

```

<form id="form1" runat="server">
<div>
    <asp:Label ID="lblInfo" runat="server"
        Text="Click on the Button to Fill the Grid">
    </asp:Label>
    <br />
    <br />
    <asp:GridView ID="carsGridView" runat="server">
        ...
    </asp:GridView>
    <br />
    <asp:Button ID="btnFillData" runat="server" Text="Fill Grid" OnClick="btnFillData_Click"/>
</div>
</form>

```

The `System.Web.UI.WebControls` namespace of the `System.Web.dll` assembly contains a majority of the ASP.NET web controls. If you were to open the Visual Studio 2010 Object Browser, you could, for example, locate the `Label` control (Figure 32-13).




Figure 32-13. All ASP.NET control declarations map to a .NET class type

As you can see, an ASP.NET web control has an inheritance chain with `System.Object` at the very top. The `WebControl` parent class is a common base to all ASP.NET controls and defines all the common UI properties you would expect (`BackColor`, `Height`, etc.). The `Control` class is also very common within the framework; however, it defines more infrastructure-centric members (data binding, view state, etc) rather than a child's graphical look and feel. You'll learn more about these classes in Chapter 33.

Compilation Cycle for Single-File Pages

If you are making use of the single-file page model, the HTML markup, server side `<script>` blocks, and web control definitions are dynamically compiled into a class type deriving from `System.Web.UI.Page` when the first request is made. The name of this class is based on the name of the `*.aspx` file and takes an `_aspx` suffix (e.g., a page named `MyPage.aspx` becomes a class named `MyPage_aspx`). Figure 32-14 illustrates the basic process.




Figure 32-14. The compilation model for single-file pages

This dynamically compiled assembly is deployed to a runtime-defined subdirectory under the `C:\Windows\Microsoft.NET\Framework\v4.0\Temporary ASP.NET Files` root directory. The path beneath this root will differ based on a number of factors (hash codes, etc.), but if you are determined, eventually you will find the `*.dll` (and supporting files) in question. Figure 32-15 shows the generated assembly for the `SinglePageModel` example shown earlier in this chapter.




Figure 32-15. The ASP.NET autogenerated assembly

If you were to open this assembly into a tool such as ildasm.exe or reflector.exe, sure enough you will find a class extending Page, which each web control defined as a member of the class. Now, do be aware that you will typically never need to manually find, or in any way modify, these autogenerated assemblies. However, it is important to point out that if you change any aspect of your *.aspx file, it will be dynamically recompiled when a browser request the web page.

■ **Source Code** The SinglePageModel website is included under the Chapter 32 subdirectory.

Building an ASP.NET Web Page using Code Files

While the single file code model can be helpful at times, the default approach taken by Visual Studio 2010 (when creating a new web project) is to make use of a technique known as *code-behind*, which allows you to separate your programming code from your HTML presentation logic using two distinct files. This model works quite well when your pages contain a significant amount of code or when multiple developers are working on the same website. The code-behind model offers other benefits as well:

- Because code-behind pages offer a clean separation of HTML markup and code, it is possible to have designers working on the markup while programmers author the C# code.
- Code is not exposed to page designers or others who are working only with the page markup (as you might guess, HTML folks are not always interested in viewing reams of C# code).
- Code files can be used across multiple *.aspx files.

Regardless of which approach you take, there is *no* difference in terms of performance. In fact, many ASP.NET web applications will benefit from building sites that make use of both approaches.

To illustrate the code-behind page model, let's recreate the previous example using a blank Visual Studio 2010 Web Site template (note that Visual Studio 2010 is not required to build pages using code-behind). Activate the File ▶ New ▶ Web Site menu option and select the Empty Web Site template, as shown in Figure 32-16.




Figure 32-16. The Empty Web Site template

Notice in Figure 32-16 that you are able to select the location of your new site. If you select File System, your content files will be placed within a local directory and pages will be served via the ASP.NET development web server. If you select FTP or HTTP, your site will be hosted within a new virtual directory maintained by IIS. For this example, it makes no difference which option you select, but for simplicity I suggest selecting the File System option and specifying a new folder named C:\CodeBehindPageModel.

■ **Note** The Empty Web Site project template will automatically include a web.config file, which is similar to an App.config file for a desktop executable. You'll learn about the format of this file later in the chapter.

Now, using Website ▶ Add New Item... menu option, insert a new Web Form item named Default.aspx. You'll notice that, by default, the Place code in separate file checkbox is checked automatically, which is exactly what you want (Figure 32-17).




Figure 32-17. Inserting a new Web Form with code separation

Once again, make use of the designer to build a UI consisting of a Label, Button, and GridView, and make use of the Properties window to build a UI of your liking.

Note that the `<%@ Page` directive has been updated with a few new attributes:

```
<%@ Page Language="C#" AutoEventWireup="true"
    CodeFile="Default.aspx.cs" Inherits="_Default" %>
```

The `CodeFile` attribute is used to specify the related external file that contains this page's coding logic. By default, these code-behind files are named by adding the suffix `.cs` to the name of the `*.aspx` file (`Default.aspx.cs` in this example). If you examine Solution Explorer, you will see this code-behind file is visible via a subnode on the Web Form icon (see Figure 32-18).




Figure 32-18. The associated code-behind file for a given `*.aspx` file

If you were to open your code-behind file, you would find a partial class deriving from `System.Web.UI.Page` with support for handling the `Load` event. Notice that the name of this class (`_Default`) is identical to the `Inherits` attribute within the `<%@Page%>` directive:

```
public partial class _Default : System.Web.UI.Page
{
    protected void Page_Load(object sender, EventArgs e)
    {
    }
}
```

Referencing the AutoLotDAL.dll Assembly

As previously mentioned, when creating web application projects using Visual Studio 2010, you do not need to manually build a `\bin` subdirectory and copy private assemblies by hand. For this example, activate the Add Reference dialog box using the Website menu option and reference `AutoLotDAL.dll`. When you do so, you will see the new `\bin` folder within Solution Explorer, as shown in Figure 32-19.




Figure 32-19. Visual Studio typically maintains special ASP.NET folders

Updating the Code File

Handle the `Click` event for the `Button` type by double-clicking the `Button` placed on the designer. As before, the `Button` definition has been updated with an `OnClick` attribute. However, the server-side event handler is no longer placed within a `<script>` scope of the `*.aspx` file but as a method of the `_Default` class type.

To complete this example, add a `using` statement for `AutoLotConnectedLayer` inside your code-behind file and implement the handler using the previous logic:

```
using AutoLotConnectedLayer;

public partial class _Default : System.Web.UI.Page
{
    protected void Page_Load(object sender, EventArgs e)
    {
```

```

}
protected void btnFillData_Click(object sender, EventArgs e)
{
    InventoryDAL dal = new InventoryDAL();
    dal.OpenConnection(@"Data Source=(local)\SQLEXPRESS;" +
        "Initial Catalog=AutoLot;Integrated Security=True");
    carsGridView.DataSource = dal.GetAllInventory();
    carsGridView.DataBind();
    dal.CloseConnection();
}
}

```

At this point, you can run your web site by pressing the Ctrl+F5 key combination. Once again, the ASP.NET development web server will fire up, serving your page into your hosting browser.

Compilation Cycle for Multifile Pages

The compilation process of a page making use of the code-behind model is similar to that of the single-file model. However, the type deriving from `System.Web.UI.Page` is composed of three files rather than the expected two.

Recall that the `Default.aspx` file was connected to a partial class named `_Default` within the code-behind file. In addition, a third aspect of the partial class generated in memory, which contains in-memory code that correctly sets properties and events on your web controls.

In any case, once the assembly has been created upon the initial HTTP request, it will be reused for all subsequent requests, and thus will not have to be recompiled. Understanding this factoid should help explain why the first request of an `*.aspx` page takes the longest and subsequent hits to the same page are extremely efficient.

Note Under ASP.NET, it is possible to precompile all pages (or a subset of pages) of a website using a command-line tool named `aspnet_compiler.exe`. Check out the .NET Framework 4.0 SDK documentation for details.

Debugging and Tracing ASP.NET Pages

When you are building ASP.NET web projects, you can use the same debugging techniques as you would with any other sort of Visual Studio 2010 project type. Thus, you can set breakpoints in your code-behind file (as well as embedded “script” blocks in an `*.aspx` file), start a debug session (via the F5 key, by default), and step through your code.

However, to debug your ASP.NET web applications, your site must contain a properly configured `Web.config` file. By default, all Visual Studio 2010 web projects will automatically have a `Web.config` file. However, debugging support is initially disabled (as debugging would degrade performance). When you start a debugging session, the IDE will prompt you whether you would like to modify `Web.config` to enable debugging. Once you have opted to do so, the `<compilation>` element of the `Web.config` file is updated like so:

```
<compilation debug="true" targetFramework="4.0"/>
```

On a related note, you are also able to enable *tracing support* for an *.aspx file by setting the Trace attribute to true within the <%@Page%> directive (it is also possible to enable tracing for your entire site by modifying the Web.config file):

```
<%@ Page Language="C#" AutoEventWireup="true"
    CodeFile="Default.aspx.cs" Inherits="_Default" Trace="true" %>
```

Once you do, the emitted HTML contains numerous details regarding the previous HTTP request/response (server variables, session and application variables, request/response, etc.). To insert your own trace messages into the mix, you can use the Trace property inherited from System.Web.UI.Page.

Anytime you wish to log a custom message (from a script block or C# source code file), simply call the static Trace.Write() method. The first argument represents the name of your custom category, the second argument specifies the trace message. To illustrate, update the Click handler of your Button with the following code statement:

```
protected void btnFillData_Click(object sender, EventArgs e)
{
    Trace.Write("CodeFileTraceInfo!", "Filling the grid!");
    ...
}
```

Run your project once again and click the button. You will find your custom category and custom message are present and accounted for. In Figure 32-20, take note of the highlighted message that displays the trace information.




Figure 32-20. Logging custom trace messages

At this point, you have seen how to build a single ASP.NET web page using the single-file and code-behind approach. The remaining topics of this chapter will take a deeper look into the composition of an ASP.NET web project, as well as ways to interact with the HTTP request/response and the life cycle of a Page derived class. Before you dive in, I need to clarify the distinction between an ASP.NET Web Site and an ASP.NET Web Application.

■ **Source Code** The CodeBehindPageModel website is included under the Chapter 32 subdirectory.

ASP.NET Web Sites and ASP.NET Web Applications

When you are about to build a new ASP.NET web application, you will need to make a choice regard which of two project formats you will make use of, specifically an *ASP.NET Web Site* or an *ASP.NET Web Application*. Your choice of web project will control the way in which Visual Studio organizes and processes your web application starter files, the type of initial project files that are created, and how much control you have over the resulting composition of the compiled .NET assembly.

When ASP.NET was first released with .NET 1.0, the only option was to build what is now termed a *web application*. Under this model, you have direct control over the name and location of the compiled output assembly. As well, under this model, the in-memory partial class which contains control declarations and configurations is *not* in memory but rather found within another physical C# code file.

Web applications are useful when you are migrating older .NET 1.1 web sites into .NET 2.0 and higher projects. Web applications are also helpful when you wish to build a single Visual Studio 2010 Solution that can contain multiple projects (for example, the web application and three related .NET code libraries). To build an ASP.NET Web Application, you activate the File ▶ New Project... menu item and pick a template from the Web category (Figure 32-21).




Figure 32-21. The Visual Studio Web Application Templates

You have no need to do so now; however, assume you did create a new ASP.NET Web Application project. You will find a large number of starter files (which will make sense as you work through the chapters to come), but most importantly note that each ASP.NET web page is composed of three files;

the *.aspx file (for markup), the *.Designer.cs file (for designer-generated C# code), and the primary C# code file (for your event handlers, custom methods and whatnot). See Figure 32-22.




Figure 32-22. Under the Web Application model, each web page is composed of three files

In stark contrast, the Visual Studio 2010 ASP.NET Web Site project templates (found under the File ➤ New Web Site... menu option) hides the *.Designer.cs file in favor of an in-memory partial class. Moreover, ASP.NET Web Site projects support a number of specially named folders, such as App_Code. Within this folder, you can place any C# (or VB) code files that are not directly mapped to your web pages, and the runtime compiler will dynamically compile them as required. This is a great simplification to the normal act of building a dedicated .NET code library and referencing it in new projects. On a related note, a Web Site project can be pushed as-is to a production web server without the need to precompile the site as you would need to do with an ASP.NET Web Application.

In this book, I'll make use of ASP.NET Web Site project types, as they do offer some simplifications to the process of building web applications under the .NET platform. However, regardless of which approach you take, you will have access to the same overall programming model.

Note Because the Visual Studio 2010 ASP.NET project templates generate a great deal of starter code (master pages, content pages, script libraries, a log in page, etc), this book will opt to use the Blank web site template. However, once you have completed reading the ASP.NET chapters of this text, make sure you create a new ASP.NET web site project and examine this starter code first hand.

The ASP.NET Web Site Directory Structure

When you create a new ASP.NET Web Site project, your project may contain any number of specifically named subdirectories, each of which has a special meaning to the ASP.NET runtime. Table 32-3 documents these special subdirectories.

Table 32-3. Special ASP.NET Subdirectories

Subfolder	Meaning in Life
App_Browsers	Folder for browser definition files that are used to identify individual browsers and determine their capabilities
App_Code	Folder for source code for components or classes that you want to compile as part of your application. ASP.NET compiles the code in this folder when pages are requested. Code in the App_Code folder is automatically accessible by your application
App_Data	Folder for storing Access *.mdb files, SQL Express *.mdf files, XML files, or other data stores
App_GlobalResources	Folder for *.resx files that are accessed programmatically from application code
App_LocalResources	Folder for *.resx files that are bound to a specific page
App_Themes	Folder that contains a collection of files that define the appearance of ASP.NET web pages and controls
App_WebReferences	Folder for proxy classes, schemas, and other files associated with using a web service in your application
Bin	Folder for compiled private assemblies (*.dll files). Assemblies in the Bin folder are automatically referenced by your application

If you are interested in adding any of these known subfolders to your current web application, you may do so explicitly using the Website ► Add Folder menu option. However, in many cases, the IDE will automatically do so as you naturally insert related files into your site. For example, inserting a new class file into your project will automatically add an App_Code folder to your directory structure if one does not currently exist.

Referencing Assemblies

Although the Web Site templates do generate an *.sln file to load your *.aspx files into the IDE, there is no longer a related *.csproj file. However, an ASP.NET Web Application projects records all external assemblies within *.csproj. So where are the external assemblies recorded under ASP.NET?

As you have seen, when you reference a private assembly, Visual Studio 2010 will automatically create a \bin directory within your directory structure to store a local copy of the binary. When your code base makes use of types within these code libraries, they are automatically loaded on demand.

If you reference a shared assembly located in the Global Assembly Cache, Visual Studio 2010 will automatically insert a Web.config file into your current web solution (if one is not currently in place) and record the external reference within the <assemblies> element. For example, if you again activate the

Web Site ► Add Reference menu option and this time select a shared assembly (such as `System.Data.OracleClient.dll`), you will find that your `Web.config` file has been updated as follows:

```
<assemblies>
  <add assembly="System.Data.OracleClient, Version=4.0.0.0,
    Culture=neutral, PublicKeyToken=B03F5F7F11D50A3A"/>
</assemblies>
```

As you can see, each assembly is described using the same information required for a dynamic load via the `Assembly.Load()` method (see Chapter 15).

The Role of the App_Code Folder

The `App_Code` folder is used to store source code files that are not directly tied to a specific web page (such as a code-behind file) but are to be compiled for use by your website. Code within the `App_Code` folder will be automatically compiled on the fly on an as-needed basis. After this point, the assembly is accessible to any other code in the website. To this end, the `App_Code` folder is much like the `Bin` folder, except that you can store source code in it instead of compiled code. The major benefit of this approach is that it is possible to define custom types for your web application without having to compile them independently.

A single `App_Code` folder can contain code files from multiple languages. At runtime, the appropriate compiler kicks in to generate the assembly in question. If you would rather partition your code, however, you can define multiple subdirectories that are used to hold any number of managed code files (`*.vb`, `*.cs`, etc.).

For example, assume you have added an `App_Code` folder to the root directory of a website application that has two subfolders, `MyCSharpCode` and `MyVbNetCode`, that contain language-specific files. Once you do, you are able to update your `Web.config` file to specify these subdirectories using a `<codeSubDirectories>` element nested within the `<configuration>` element:

```
<compilation debug="true" strict="false" explicit="true">
  <codeSubDirectories>
    <add directoryName="MyCSharpCode" />
    <add directoryName="MyVbNetCode" />
  </codeSubDirectories>
</compilation>
```

Note The `App_Code` directory will also be used to contain files that are not language files but are useful nonetheless (`*.xsd` files, `*.wsdl` files, etc.).

Beyond `Bin` and `App_Code`, the `App_Data` and `App_Themes` folders are two additional special subdirectories that you should be familiar with, both of which will be detailed in the next several chapters. As always, consult the .NET Framework 4.0 SDK documentation for full details of the remaining ASP.NET subdirectories if you require further information.

The Inheritance Chain of the Page Type

As you have just seen, all .NET web pages eventually derive from `System.Web.UI.Page`. Like any base class, this type provides a polymorphic interface to all derived types. However, the `Page` type is not the only member in your inheritance hierarchy. If you were to locate the `System.Web.UI.Page` class (within the `System.Web.dll` assembly) using the Visual Studio 2010 object browser, you would find that `Page` is-a `TemplateControl`, which is-a `Control`, which is-a `Object` (see Figure 32-23).




Figure 32-23. The inheritance chain of `Page`

Each of these base classes brings a good deal of functionality to each and every *.aspx file. For the majority of your projects, you will make use of the members defined within the `Page` and `Control` parent classes. The functionality gained from the `System.Web.UI.TemplateControl` class is only of interest if you are building custom Web Form controls or interacting with the rendering process.

The first parent class of interest is `Page` itself. Here you will find numerous properties that enable you to interact with various web primitives such as application and session variables, the HTTP request/response, theme support, and so forth. Table 32-4 describes some (but by no means all) of the core properties.

Table 32-4. Select Properties of the `Page` Type

Property	Meaning in Life
<code>Application</code>	Allows you to interact with data that can be accessed across the entire website for all users
<code>Cache</code>	Allows you to interact with the cache object for the current website
<code>ClientTarget</code>	Allows you to specify how this page should render itself based on the requesting browser

Table 32-4. Select Properties of the Page Type (continued)

Property	Meaning in Life
IsPostBack	Gets a value indicating whether the page is being loaded in response to a client postback or whether it is being loaded and accessed for the first time
MasterPageFile	Establishes the master page for the current page
Request	Provides access to the current HTTP request
Response	Allows you to interact with the outgoing HTTP response
Server	Provides access to the <code>HttpServerUtility</code> object, which contains various server-side helper functions
Session	Allows you to interact with the session data for the current caller
Theme	Gets or sets the name of the theme used for the current page
Trace	Provides access to a <code>TraceContext</code> object, which allows you to log custom messages during debugging sessions

Interacting with the Incoming HTTP Request

As you saw earlier in this chapter, the basic flow of a web application begins with a client requesting a web page, possibly filling in user information, and clicking a “Submit button” to post back the HTML form data to a given web page for processing. In most cases, the opening tag of the `form` statement specifies an `action` attribute and a `method` attribute that indicates the file on the web server that will be sent the data in the various HTML widgets, as well as the method of sending this data (GET or POST):

```
<form name="defaultPage" id="defaultPage"
      action="http://localhost/Cars/ClassicAspPage.asp" method = "GET">
...
</form>
```

All ASP.NET pages support the `System.Web.UI.Page.Request` property, which provides access to an instance of the `HttpRequest` class type (see Table 32-5 for some common members of this class).

Table 32-5. Members of the *HttpRequest* Type

Member	Meaning in Life
ApplicationPath	Gets the ASP.NET application's virtual application root path on the server
Browser	Provides information about the capabilities of the client browser
Cookies	Gets a collection of cookies sent by the client browser
FilePath	Indicates the virtual path of the current request
Form	Gets a collection of HTTP form variables
Headers	Gets a collection of HTTP headers
HttpMethod	Indicates the HTTP data transfer method used by the client (GET, POST)
IsSecureConnection	Indicates whether the HTTP connection is secure (i.e., HTTPS)
QueryString	Gets the collection of HTTP query string variables
RawUrl	Gets the current request's raw URL
RequestType	Indicates the HTTP data transfer method used by the client (GET, POST)
ServerVariables	Gets a collection of web server variables
UserHostAddress	Gets the IP host address of the remote client
UserHostName	Gets the DNS name of the remote client

In addition to these properties, the *HttpRequest* type has a number of useful methods, including the following:

- *MapPath()*: Maps the virtual path in the requested URL to a physical path on the server for the current request
- *SaveAs()*: Saves details of the current HTTP request to a file on the web server, which can prove helpful for debugging purposes.
- *ValidateInput()*: If the validation feature is enabled via the *Validate* attribute of the page directive, this method can be called to check all user input data (including cookie data) against a predefined list of potentially dangerous input data.

Obtaining Brower Statistics

The first interesting aspect of the `HttpRequest` type is the `Browser` property, which provides access to an underlying `HttpBrowserCapabilities` object. `HttpBrowserCapabilities`, in turn, exposes numerous members that allow you to programmatically investigate statistics regarding the browser that sent the incoming HTTP request.

Create a new ASP.NET website named `FunWithPageMembers` (again, elect to use the File System option). Your first task is to build a UI that allows users to click a Button web control (named `btnGetBrowserStats`) to view various statistics about the calling browser. These statistics will be generated dynamically and attached to a `Label` type (named `lblOutput`). The button's `Click` event handler is as follows:

```
protected void btnGetBrowserStats_Click(object sender, EventArgs e)
{
    string theInfo = "";
    theInfo += string.Format("<li>Is the client AOL? {0}</li>",
        Request.Browser.AOL);
    theInfo += string.Format("<li>Does the client support ActiveX? {0}</li>",
        Request.Browser.ActiveXControls);
    theInfo += string.Format("<li>Is the client a Beta? {0}</li>",
        Request.Browser.Beta);
    theInfo += string.Format("<li>Does the client support Java Applets? {0}</li>",
        Request.Browser.JavaApplets);
    theInfo += string.Format("<li>Does the client support Cookies? {0}</li>",
        Request.Browser.Cookies);
    theInfo += string.Format("<li>Does the client support VBScript? {0}</li>",
        Request.Browser.VBScript);
    lblOutput.Text = theInfo;
}
```

Here you are testing for a number of browser capabilities. As you would guess, it is (very) helpful to discover a browser's support for ActiveX controls, Java applets, and client-side VBScript code. If the calling browser does not support a given web technology, your `*.aspx` page will be able to take an alternative course of action.

Access to Incoming Form Data

Other aspects of the `HttpResponse` type are the `Form` and `QueryString` properties. These two properties allow you to examine the incoming form data using name/value pairs. While you could make use of the `HttpRequest.Form` and `HttpRequest.QueryString` properties to access client-supplied form data on the web server, ASP.NET provides a more elegant, object-oriented approach. Given that ASP.NET supplies you with server-side web controls, you are able to treat HTML UI elements as true objects. Therefore, rather than obtaining the value within a text box as follows

```
protected void btnGetFormData_Click(object sender, System.EventArgs e)
{
    // Get value for a widget with ID txtFirstName.
    string firstName = Request.Form("txtFirstName");
```

```
// Use this value in your page...
}
```

you can simply ask the server-side widget directly via the `Text` property for use in your program, like so

```
protected void btnGetFormData_Click(object sender, System.EventArgs e)
{
    // Get value for a widget with ID txtFirstName.
    string firstName = txtFirstName.Text;

    // Use this value in your page...
}
```

Not only does this approach lend itself to solid OO principles, but also you do not need to concern yourself with how the form data was submitted (GET or POST) before obtaining the values. Furthermore, working with the widget directly is much more type-safe, given that typing errors are discovered at compile time rather than runtime. Of course, this is not to say that you will *never* need to make use of the `Form` or `QueryString` property in ASP.NET; rather, the need to do so has greatly diminished and is usually optional.

The IsPostBack Property

Another very important member of `HttpRequest` is the `IsPostBack` property. Recall that “postback” refers to a web page posting back to the same URL at the Web server. Given this definition, understand that the `IsPostBack` property will return true if the current HTTP request has been sent by a user currently in session, and false if this is the user’s first interaction with the page.

Typically, the need to determine whether the current HTTP request is indeed a postback is most helpful when you wish to execute a block of code only the first time the user accesses a given page. For example, you may wish to populate an ADO.NET `DataSet` when the user first accesses an `*.aspx` file and cache the object for later use. When the caller returns to the page, you can avoid the need to hit the database unnecessarily (of course, some pages may require that the `DataSet` always be updated upon each request, but that is another issue). Assuming your `*.aspx` file has handled the page’s `Load` event (described in detail later in this chapter), you could programmatically test for postback conditions as follows:

```
protected void Page_Load(object sender, System.EventArgs e)
{
    // Fill DataSet only the very first time
    // the user comes to this page.
    if (!IsPostBack)
    {
        // Populate DataSet and cache it!
    }
    // Use cached DataSet.
}
```

Interacting with the Outgoing HTTP Response

Now that you have a better understanding of how the `Page` type allows you to interact with the incoming HTTP request, the next step is to see how to interact with the outgoing HTTP response. In ASP.NET, the `Response` property of the `Page` class provides access to an instance of the `HttpResponse` type. This type defines a number of properties that allow you to format the HTTP response sent back to the client browser. Table 32-6 lists some core properties.

Table 32-6. Properties of the `HttpResponse` Type

Property	Meaning in Life
<code>Cache</code>	Returns the caching semantics of the web page (see Chapter 34)
<code>ContentEncoding</code>	Gets or sets the HTTP character set of the output stream
<code>ContentType</code>	Gets or sets the HTTP MIME type of the output stream
<code>Cookies</code>	Gets the <code>HttpCookie</code> collection that will be returned to the browser
<code>Output</code>	Enables text output to the outgoing HTTP content body
<code>OutputStream</code>	Enables binary output to the outgoing HTTP content body
<code>StatusCode</code>	Gets or sets the HTTP status code of output returned to the client
<code>StatusDescription</code>	Gets or sets the HTTP status string of output returned to the client
<code>SuppressContent</code>	Gets or sets a value indicating that HTTP content will not be sent to the client

Also, consider the partial list of methods supported by the `HttpResponse` type described in Table 32-7.

Table 32-7. Methods of the `HttpResponse` Type

Method	Meaning in Life
<code>Clear()</code>	Clears all headers and content output from the buffer stream
<code>End()</code>	Sends all currently buffered output to the client and then closes the socket connection
<code>Flush()</code>	Sends all currently buffered output to the client
<code>Redirect()</code>	Redirects a client to a new URL
<code>Write()</code>	Writes values to an HTTP output content stream
<code>WriteFile()</code>	Writes a file directly to an HTTP content output stream

Emitting HTML Content

Perhaps the most well-known aspect of the `HttpResponse` type is the ability to write content directly to the HTTP output stream. The `HttpResponse.Write()` method allows you to pass in any HTML tags and/or text literals. The `HttpResponse.WriteFile()` method takes this functionality one step further, in that you can specify the name of a physical file on the web server whose contents should be rendered to the output stream (this is quite helpful to quickly emit the contents of an existing *.htm file).

To illustrate, assume you have added another `Button` type to your current *.aspx file that implements the server-side `Click` event handler like so:

```
protected void btnHttpResponse_Click(object sender, EventArgs e)
{
    Response.Write("<b>My name is:</b><br>");
    Response.Write(this.ToString());
    Response.Write("<br><br><b>Here was your last request:</b><br>");
    Response.WriteFile("MyHTMLPage.htm");
}
```

The role of this helper function (which you can assume is called by some server-side event handler) is quite simple. The only point of interest is the fact that the `HttpResponse.WriteFile()` method is now emitting the contents of a server-side *.htm file within the root directory of the website.

Again, while you can always take this old-school approach and render HTML tags and content using the `Write()` method, this approach is far less common under ASP.NET than with classic ASP. The reason is (once again) due to the advent of server-side web controls. Thus, if you wish to render a block of textual data to the browser, your task is as simple as assigning a string to the `Text` property of a `Label` widget.

Redirecting Users

Another aspect of the `HttpResponse` type is the ability to redirect the user to a new URL:

```
protected void btnWasteTime_Click(object sender, EventArgs e)
{
    Response.Redirect("http://www.facebook.com");
}
```

If this event handler is invoked via a client-side postback, the user will automatically be redirected to the specified URL.

Note The `HttpResponse.Redirect()` method will always entail a trip back to the client browser. If you simply wish to transfer control to an *.aspx file in the same virtual directory, the `HttpServerUtility.Transfer()` method, accessed via the inherited `Server` property, is more efficient.

So much for investigating the functionality of `System.Web.UI.Page`. I will examine the role of the `System.Web.UI.Control` base class in the next chapter. Next up, let's examine the life and times of a `Page`-derived object.

Source Code The `FunWithPageMembers` website is included under the Chapter 32 subdirectory.

The Life Cycle of an ASP.NET Web Page

Every ASP.NET web page has a fixed life cycle. When the ASP.NET runtime receives an incoming request for a given `*.aspx` file, the associated `System.Web.UI.Page`-derived type is allocated into memory using the type's default constructor. After this point, the framework will automatically fire a series of events. By default, the `Load` event is automatically accounted for, where you can add your custom code:

```
public partial class _Default : System.Web.UI.Page
{
    protected void Page_Load(object sender, EventArgs e)
    {
        Response.Write("Load event fired!");
    }
}
```

Beyond the `Load` event, a given `Page` is able to intercept any of the core events in Table 32-8, which are listed in the order in which they are encountered (consult the .NET Framework 4.0 SDK documentation for details on all possible events that may fire during a page's lifetime).

Table 32-8. Select Events of the `Page` Type

Event	Meaning in Life
PreInit	The framework uses this event to allocate any web controls, apply themes, establish the master page, and set user profiles. You may intercept this event to customize the process.
Init	The framework uses this event to set the properties of web controls to their previous values via postback or view state data.
Load	When this event fires, the page and its controls are fully initialized, and their previous values are restored. At this point, it is safe to interact with each web widget.
<i>"Event that triggered the postback"</i>	There is, of course, no event of this name. This "event" simply refers to whichever event caused the browser to perform the postback to the web server (such as a <code>Button</code> click).

Table 32-8. Select Events of the Page Type (continued)

Event	Meaning in Life
PreRender	All control data binding and UI configuration has occurred and the controls are ready to render their data into the outbound HTTP response.
Unload	The page and its controls have finished the rendering process, and the page object is about to be destroyed. At this point, it is a runtime error to interact with the outgoing HTTP response. You may, however, capture this event to perform any page-level cleanup (close file or database connections, perform any form of logging activity, dispose of objects, etc.).

When a C# programmer needs to handle events beyond Load, you may be surprised to find that there is no IDE support to do so! Rather, you must manually author a method in your code file taking the name `Page_NameOfEvent`. For example, here is how you can handle the Unload event:

```
public partial class _Default : System.Web.UI.Page
{
    protected void Page_Load(object sender, EventArgs e)
    {
        Response.Write("Load event fired!");
    }

    protected void Page_Unload(object sender, EventArgs e)
    {
        // No longer possible to emit data to the HTTP
        // response, so we will write to a local file.
        System.IO.File.WriteAllText(@"C:\MyLog.txt", "Page unloading!");
    }
}
```

■ **Note** Each event of the Page type works in conjunction with the `System.EventHandler` delegate; therefore, the subroutines that handle these events always take an `Object` as the first parameter and an `EventArgs` as the second parameter.

The Role of the AutoEventWireup Attribute

When you wish to handle events for your page, you will need to update your `<script>` block or code-behind file with an appropriate event handler. However, if you examine the `<%@Page%>` directive, you will notice a specific attribute named `AutoEventWireUp`, which, by default, is set to `true`:

```
<%@ Page Language="C#" AutoEventWireup="true"
CodeFile="Default.aspx.cs" Inherits="_Default" %>
```

With this default behavior, each page-level event handler will automatically be handled if you enter the appropriately named method. However, if you disable AutoPageWireUp by setting this attribute to false

```
<%@ Page Language="C#" AutoEventWireup="false"
  CodeFile="Default.aspx.cs" Inherits="_Default" %>
```

the page-level events will no longer be captured. As its name suggests, this attribute (when enabled) will generate the necessary event riggings within the autogenerated partial class described earlier in this chapter. Even if you disable AutoEventWireup, you can still process page-level events by making use of C# event-handling logic, for example:

```
public _Default()
{
    // Explicitly hook into the Load and Unload events.
    this.Load += new Page_Load();
    this.Unload += new Page_Unload();
}
```

As you might suspect, you will usually leave AutoEventWireup enabled.

The Error Event

Another event that may occur during your page's life cycle is Error. This event will be fired if a method on the Page-derived type triggered an exception that was not explicitly handled. Assume that you have handled the Click event for a given Button on your page, and within the event handler (which I named btnGetFile_Click), you attempt to write out the contents of a local file to the HTTP response.

Also assume you have *failed* to test for the presence of this file via standard structured exception handling. If you have rigged up the page's Error event in the default constructor, you have one final chance to deal with the problem on this page before the end user finds an ugly error. Consider the following code:

```
public partial class _Default : System.Web.UI.Page
{
    void Page_Error(object sender, EventArgs e)
    {
        Response.Clear();
        Response.Write("I am sorry...I can't find a required file.<br>");
        Response.Write(string.Format("The error was: <b>{0}</b>",
            Server.GetLastError().Message));
        Server.ClearError();
    }

    protected void Page_Load(object sender, EventArgs e)
    {
        Response.Write("Load event fired!");
    }

    protected void Page_Unload(object sender, EventArgs e)
    {
```

```

// No longer possible to emit data to the HTTP
// response at this point, so we will write to a local file.
System.IO.File.WriteAllText(@"C:\MyLog.txt", "Page unloading!");
}

protected void btnPostBack_Click(object sender, EventArgs e)
{
    // Nothing happens here, this is just to ensure a
    // postback to the page.
}
protected void btnTriggerError_Click(object sender, EventArgs e)
{
    System.IO.File.ReadAllText(@"C:\IDontExist.txt");
}

```

Notice that your Error event handler begins by clearing out any content currently within the HTTP response and emits a generic error message. If you wish to gain access to the specific `System.Exception` object, you may do so using the `HttpServerUtility.GetLastError()` method exposed by the inherited `Server` property:

```
Exception e = Server.GetLastError();
```

Finally, note that before exiting this generic error handler, you are explicitly calling the `HttpServerUtility.ClearError()` method via the `Server` property. This is required, as it informs the runtime that you have dealt with the issue at hand and require no further processing. If you forget to do so, the end user will be presented with the runtime's error page. Figure 32-24 shows the result of this error-trapping logic.




Figure 32-24. Page-level error handling

At this point, you should feel confident with the composition of an ASP.NET Page type. Now that you have such a foundation, you can turn your attention to the role of ASP.NET web controls, themes, and master pages, all of which are the subject of remaining chapters. To wrap up this chapter, however, let's examine the role of the `Web.config` file.

■ **Source Code** The `PageLifecycle` website is included under the Chapter 32 subdirectory.

The Role of the Web.config File

By default, all C# ASP.NET web applications created with Visual Studio 2010 are automatically provided with a `Web.config` file. However, if you ever need to manually insert a `Web.config` file into your site (e.g., when you are working with the single-page model and have not created a web solution), you may do so using the `Website > Add New Item` menu option. In either case, within this scope of a `Web.config` file you are able to add settings that control how your web application will function at runtime.

Recall during your examination of .NET assemblies (in Chapter 15) that you learned client applications can leverage an XML-based configuration file to instruct the CLR how it should handle binding requests, assembly probing, and other runtime details. The same holds true for ASP.NET web applications, with the notable exception that web-centric configuration files are always named `Web.config` (unlike `*.exe` configuration files, which are named based on the related client executable).

The full structure of a `Web.config` file is rather verbose. However, Table 32-9 outlines some of the more interesting subelements that can be found within a `Web.config` file.

Table 32-9. Select Elements of a `Web.config` File

Element	Meaning in Life
<code><appSettings></code>	This element is used to establish custom name/value pairs that can be programmatically read in memory for use by your pages using the <code>ConfigurationManager</code> type.
<code><authentication></code>	This security-related element is used to define the authentication mode for this web application.
<code><authorization></code>	This is another security-centric element used to define which users can access which resources on the web server.
<code><connectionStrings></code>	This element is used to hold external connection strings used within this website.
<code><customErrors></code>	This element is used to tell the runtime exactly how to display errors that occur during the functioning of the web application.
<code><globalization></code>	This element is used to configure the globalization settings for this web application.
<code><namespaces></code>	This element documents all of the namespaces to include if your web application has been precompiled using the new <code>aspnet_compiler.exe</code> command-line tool.
<code><sessionState></code>	This element is used to control how and where session state data will be stored by the .NET runtime.
<code><trace></code>	This element is used to enable (or disable) tracing support for this web application.

A `Web.config` file may contain additional subelements above and beyond the set presented in Table 32-9. The vast majority of these items are security related, while the remaining items are useful only during advanced ASP.NET scenarios such as creating with custom HTTP headers or custom HTTP modules (topics that are not covered here).

The ASP.NET Website Administration Utility

Although you are always free to modify the content of a `Web.config` file directly using Visual Studio 2010, ASP.NET web projects can make use of a handy web-based editor that will allow you to graphically edit numerous elements and attributes of your project's `Web.config` file. To launch this tool, activate the **Website ▶ ASP.NET Configuration** menu option.

If you were to click the tabs located on the top of the page, you would quickly notice that most of this tool's functionality is used to establish security settings for your website. However, this tool also makes it possible to add settings to your `<appSettings>` element, define debugging and tracing settings, and establish a default error page.

You'll see more of this tool in action where necessary; however, do be aware that this utility will *not* allow you to add all possible settings to a `Web.config` file. There will most certainly be times when you will need to manually update this file using your text editor of choice.

Summary

Building web applications requires a different frame of mind than is used to assemble traditional desktop applications. In this chapter, you began with a quick and painless review of some core web topics, including HTML, HTTP, the role of client-side scripting, and server-side scripts using classic ASP. The bulk of this chapter was spent examining the architecture of an ASP.NET page. As you have seen, each `*.aspx` file in your project has an associated `System.Web.UI.Page`-derived class. Using this OO approach, ASP.NET allows you to build more reusable and OO-aware systems.

After examining some of the core functionality of a page's inheritance chain, this chapter then discussed how your pages are ultimately compiled into a valid .NET assembly. We wrapped up by exploring the role of the `Web.config` file and overviewed the ASP.NET Web Site Administration tool.



ASP.NET Web Controls, Master Pages and Themes

The previous chapter concentrated on the composition and behavior of ASP.NET Page objects. This chapter will dive into the details of the *web controls* that make up a page's user interface. After examining the overall nature of an ASP.NET web control, you will come to understand how to make use of several UI elements including the validation controls and various data binding controls.

The bulk of this chapter will examine the role of *master pages* and show how they provide a simplified manner to define a common UI skeleton that will be replicated across the pages in your website. Closely related to the topic of master pages is the use of site navigation controls (and a related *.sitemap file) that allow you to define the navigational structure of a multi-paged site via a server side XML file.

To wrap things up, you will learn about the role of ASP.NET themes. Conceptually, themes serve the same purpose as a cascading style sheet; however, ASP.NET themes are applied on the web server (as opposed to within the client side browser) and therefore have access to server side resources.

Understanding the Nature of Web Controls

A major benefit of ASP.NET is the ability to assemble the UI of your pages using the types defined in the `System.Web.UI.WebControls` namespace. As you have seen, these controls (which go by the names *server controls*, *web controls*, or *Web Form controls*) are extremely helpful in that they automatically generate the necessary HTML for the requesting browser and expose a set of events that may be processed on the web server. Furthermore, because each ASP.NET control has a corresponding class in the `System.Web.UI.WebControls` namespace, it can be manipulated in an object-oriented manner.

When you configure the properties of a web control using the Visual Studio 2010 Properties window, your edits are recorded in the opening control declaration of a given element in the *.aspx file as a series of name/value pairs. Thus, if you add a new TextBox to the designer of a given *.aspx file and change the ID, BorderStyle, BorderWidth, BackColor, and Text properties, the opening `<asp:TextBox>` tag is modified accordingly (however, note that the Text value becomes the inner text of the TextBox scope):

```
<asp:TextBox ID="txtNameTextBox" runat="server" BackColor="#C0FFC0"
    BorderStyle="Dotted" BorderWidth="3px">Enter Your Name</asp:TextBox>
```

Given that the declaration of a web control eventually becomes a member variable from the `System.Web.UI.WebControls` namespace (via the dynamic compilation cycle examined in Chapter 32), you are able to interact with the members of this type within a server-side `<script>` block or the page's

code-behind file. If you add a new Button control to an*.aspx file, you can handle the Click event and write a server side handler that changes the background color of the TextBox:

```
partial class _Default : System.Web.UI.Page
{
    protected void btnChangeTextBoxColor_Click(object sender, System.EventArgs e)
    {
        // Change color of text box object in code.
        this.txtNameTextBox.BackColor = System.Drawing.Color.DarkBlue;
    }
}
```

All ASP.NET web controls ultimately derive from a common base class named `System.Web.UI.WebControls.WebControl`. In turn, `WebControl` derives from `System.Web.UI.Control` (which derives from `System.Object`). `Control` and `WebControl` each define a number of properties common to all server-side controls. Before I examine the inherited functionality, let's formalize what it means to handle a server-side event.

Understanding Server-Side Event Handling

Given the current state of the World Wide Web, it is impossible to avoid the fundamental nature of browser/web server interaction. Whenever these two entities communicate, there is always an underlying, stateless HTTP request-and-response cycle. While ASP.NET server controls do a great deal to shield you from the details of the raw HTTP protocol, always remember that treating the Web as an event-driven entity is just a magnificent smoke-and-mirrors show provided by the CLR, and it is not identical to the event-driven model of a Windows-based UI.

For example, although the `System.Windows.Forms`, `System.Windows.Controls`, and `System.Web.UI.WebControls` namespaces define types with the same simple names (Button, TextBox, Label, and so on), they do not expose an identical set of events. For example, there is no way to handle a server-side `MouseMove` event when the user moves the cursor over a Web Form Button control. Obviously, this is a good thing. (Who wants to post back to the server each time the user mouse moves in the browser?)

The bottom line is that a given ASP.NET web control will expose a limited set of events, all of which ultimately result in a postback to the web server. Any necessary client-side event processing will require you to author blurbs of *client-side* JavaScript/VBScript script code to be processed by the requesting browser's scripting engine. Given that ASP.NET is primarily a server-side technology, I will not be addressing the topic of authoring client-side scripts.

■ **Note** Handling an event for a given web control using Visual Studio 2010 can be done in an identical manner as doing so for a Windows Forms control. Simply select the widget from the designer and click the lightning bolt icon on the Properties window.

The AutoPostBack Property

It is also worth pointing out that many of the ASP.NET web controls support a property named `AutoPostBack` (most notably, the `CheckBox`, `RadioButton`, and `TextBox` controls, as well as any widget that derives from the abstract `ListControl` type). By default, this property is set to `false`, which disables an immediate postback to the server (even if you have indeed rigged up the event in the code-behind file). In most cases, this is the exact behavior you require, given that UI elements such as check boxes typically don't require postback functionality. In other words, you don't want to post back to the server immediately after the user checks or unchecks a checkbox, as the page object can obtain the state of the widget within a more natural `Button Click` event handler.

However, if you wish to cause any of these widgets to post back to a server-side event handler immediately, simply set the value of `AutoPostBack` to `true`. This technique can be helpful if you wish to have the state of one widget automatically populate another value within another widget on the same page. To illustrate, assume you have a web page that contains a single `TextBox` (named `txtAutoPostBack`) and a single `ListBox` control (named `lstTextBoxData`). Here is the relevant markup:

```
<form id="form1" runat="server">
  <asp:TextBox ID="txtAutoPostBack" runat="server"></asp:TextBox>
  <br/>
  <asp:ListBox ID="lstTextBoxData" runat="server"></asp:ListBox>
</form>
```

Now, handle the `TextChanged` event of the `TextBox`, and within the server-side event handler, populate the `ListBox` with the current value in the `TextBox`:

```
partial class _Default : System.Web.UI.Page
{
    protected void txtAutoPostBack_TextChanged(object sender, System.EventArgs e)
    {
        lstTextBoxData.Items.Add(txtAutoPostBack.Text);
    }
}
```

If you run the application as is, you will find that as you type in the `TextBox`, nothing happens. Furthermore, if you type in the `TextBox` and tab to the next control, nothing happens. The reason is that the `AutoPostBack` property of the `TextBox` is set to `false` by default. However, if you set this property to `true`

```
<asp:TextBox ID="txtAutoPostBack"
  runat="server" AutoPostBack="true" ... >
</asp:TextBox>
```

you will find that when you tab away from the `TextBox` (or press the `Enter` key), the `ListBox` is automatically populated with the current value in the `TextBox`. To be sure, beyond the need to populate the items of one widget based on the value of another widget, you will typically not need to alter the state of a widget's `AutoPostBack` property (and even then, sometimes this can be accomplished purely in client script, removing the need for server interaction at all).

The Control and WebControl Base Classes

The `System.Web.UI.Control` base class defines various properties, methods, and events that allow the ability to interact with core (typically non-GUI) aspects of a web control. Table 33-1 documents some, but not all, members of interest.

Table 33-1. Select Members of `System.Web.UI.Control`

Member	Meaning in Life
<code>Controls</code>	This property gets a <code>ControlCollection</code> object that represents the child controls within the current control.
<code>DataBind()</code>	This method binds a data source to the invoked server control and all its child controls.
<code>EnableTheming</code>	This property establishes whether the control supports theme functionality (the default is true).
<code>HasControls()</code>	This method determines whether the server control contains any child controls.
<code>ID</code>	This property gets or sets the programmatic identifier assigned to the server control.
<code>Page</code>	This property gets a reference to the <code>Page</code> instance that contains the server control.
<code>Parent</code>	This property gets a reference to the server control's parent control in the page control hierarchy.
<code>SkinID</code>	This property gets or sets the <i>skin</i> to apply to the control, which allows you to set the look and feel using server side resources.
<code>Visible</code>	This property gets or sets a value that indicates whether a server control is rendered as a UI element on the page.

Enumerating Contained Controls

The first aspect of `System.Web.UI.Control` we will examine is the fact that all web controls (including `Page` itself) inherit a custom controls collection (accessed via the `Controls` property). Much like in a Windows Forms application, the `Controls` property provides access to a strongly typed collection of `WebControl` derived types. Like any .NET collection, you have the ability to add, insert, and remove items dynamically at runtime.

While it is technically possible to add web controls directly to a Page-derived type, it is easier (and more robust) to make use of a Panel control. The Panel class represents a container of widgets that may or may not be visible to the end user (based on the value of its `Visible` and `BorderStyle` properties).

To illustrate, create a new Empty Web Site named DynamicCtrls and add a new web page to your project. Using the Visual Studio 2010 page designer, add a Panel control (named `myPanel1`) that contains a `TextBox`, `Button`, and `HyperLink` widget named whatever you choose (be aware that the designer requires that you drag internal items within the UI of the Panel type). Next, place a `Label` widget outside the scope of the Panel (named `lblControlInfo`) to hold the rendered output. Here is one possible HTML description:

```
<html xmlns="http://www.w3.org/1999/xhtml">
<head runat="server">
    <title>Dynamic Control Test</title>
</head>
<body>
    <form id="form1" runat="server">
        <div>
            <hr />
            <h1>Dynamic Controls</h1>
            <asp:Label ID="lblTextBoxText" runat="server"></asp:Label>
            <hr />
            </div>

            <!-- The Panel has three contained controls -->
            <asp:Panel ID="myPanel" runat="server" Width="200px"
                BorderColor="Black" BorderStyle="Solid" >
                <asp:TextBox ID="TextBox1" runat="server"></asp:TextBox><br/>
                <asp:Button ID="Button1" runat="server" Text="Button"/><br/>
                <asp:HyperLink ID="HyperLink1" runat="server">HyperLink
                </asp:HyperLink>
            </asp:Panel>
        <br />
        <br />
        <asp:Label ID="lblControlInfo" runat="server"></asp:Label>
    </form>
</body>
</html>
```

With this markup, your page designer will look something like that of Figure 33-1.




Figure 33-1. The UI of the Dynamic Controls web page

Assume in the `Page_Load()` event you wish to obtain details regarding the controls contained within the Panel and assign this information to the Label control (named `lblControlInfo`). Consider the following C# code:

```
public partial class _Default : System.Web.UI.Page
{
    private void ListControlsInPanel()
    {
        string theInfo = "";
        theInfo = string.Format("<b>Does the panel have controls? {0}</b><br/>",
            myPanel.HasControls());

        // Get all controls in the panel.
        foreach (Control c in myPanel.Controls)
        {
            if (!object.ReferenceEquals(c.GetType(),
                typeof(System.Web.UI.LiteralControl)))
            {
                theInfo += "*****<br/>";
                theInfo += string.Format("Control Name? {0}<br/>", c.ToString());
                theInfo += string.Format("ID? {0}<br/>", c.ID);
                theInfo += string.Format("Control Visible? {0}<br/>", c.Visible);
                theInfo += string.Format("ViewState? {0}<br/>", c.EnableViewState);
            }
        }
        lblControlInfo.Text = theInfo;
    }

    protected void Page_Load(object sender, System.EventArgs e)
    {
    }
}
```

```

        ListControlsInPanel();
    }
}

```

Here, you iterate over each `WebControl` maintained on the `Panel` and perform a check to see whether the current type is of type `System.Web.UI.LiteralControl`, and if so, we skip over it. This class is used to represent literal HTML tags and content (such as `
`, text literals, etc.). If you do not do this sanity check, you might be surprised to find many more controls in the scope of the `Panel` (given the `*.aspx` declaration seen previously). Assuming the control is not literal HTML content, you then print out some various statistics about the widget. Figure 33-2 shows the output.




Figure 33-2. Enumerating controls at runtime

Dynamically Adding and Removing Controls

Now, what if you wish to modify the contents of a `Panel` at runtime? Let's update the current page to support an additional `Button` (named `btnAddWidgets`) that dynamically adds three new `TextBox`

controls to the Panel and another Button (named btnClearPanel) that clears the Panel widget of all controls. The Click event handlers for each are shown here:

```
protected void btnClearPanel_Click(object sender, System.EventArgs e)
{
    // Clear all content from the panel, then re-list items.
    myPanel.Controls.Clear();
    ListControlsInPanel();
}

protected void btnAddWidgets_Click(object sender, System.EventArgs e)
{
    for (int i = 0; i < 3; i++)
    {
        // Assign an ID so we can get
        // the text value out later
        // using the incoming form data.
        TextBox t = new TextBox();
        t.ID = string.Format("newTextBox{0}", i);
        myPanel.Controls.Add(t);
        ListControlsInPanel();
    }
}
```

Notice that you assign a unique ID to each TextBox (e.g., newTextBox0, newTextBox1, and so on). If you run your page, you should be able to add new items to the Panel control and clear the Panel of all content.

Interacting with Dynamically Created Controls

Now, if you want to obtain the values within these dynamically generated TextBoxes, you can do so in a variety of ways. First, update your UI with one additional Button (named btnGetTextData), a final Label control named lblTextBoxData, and handle the Click event for the Button.

To get access to the data within the dynamically created text boxes, you have a few options. One approach is to loop over each item contained within the incoming HTML form data (accessed via `HttpRequest.Form`) and concatenate the textual information to a locally scoped `System.String`. Once you have exhausted the collection, assign this string to the `Text` property of the new Label control:

```
protected void btnGetTextData_Click(object sender, System.EventArgs e)
{
    string textBoxValues = "";
    for (int i = 0; i < Request.Form.Count; i++)
    {
        textBoxValues += string.Format("<li>{0}</li><br/>", Request.Form[i]);
    }
    lblTextBoxData.Text = textBoxValues;
}
```

When you run the application, you will find that you are able to view the content of each text box, including some rather long (unreadable) string data. This string contains the *view state* for each control on the page. You'll learn about the role of view state in Chapter 35.

To clean up the output, you could instead pluck out the textual data for your uniquely named items (`newTextBox0`, `newTextBox1` and `newTextBox2`). Consider the following update:

```
protected void btnGetTextData_Click(object sender, System.EventArgs e)
{
    // Get each text box by name.
    string lableData = string.Format("<li>{0}</li><br/>",
        Request.Form.Get("newTextBox0"));
    lableData += string.Format("<li>{0}</li><br/>",
        Request.Form.Get("newTextBox1"));
    lableData += string.Format("<li>{0}</li><br/>",
        Request.Form.Get("newTextBox2")));
    lblTextBoxData.Text = lableData;
}
```

Using either approach, you will notice that once the request has been processed, the text boxes disappear. Again, the reason has to do with the stateless nature of HTTP. If you wish to maintain these dynamically created TextBoxes between postbacks, you need to persist these objects using ASP.NET state programming techniques (again, see Chapter 35).

■ Source Code The DynamicCtrls website is included under the Chapter 33 subdirectory.

Functionality of the WebControl Base Class

As you can tell, the `Control` type provides a number of non-GUI-related behaviors (the controls collection, autopostback support, etc.). On the other hand, the `WebControl` base class provides a graphical polymorphic interface to all web widgets, as suggested in Table 33-2.

Table 33-2. Select Properties of the `WebControl` Base Class

Property	Meaning in Life
<code>BackColor</code>	Gets or sets the background color of the web control.
<code>BorderColor</code>	Gets or sets the border color of the web control.
<code>BorderStyle</code>	Gets or sets the border style of the web control.
<code>BorderWidth</code>	Gets or sets the border width of the web control.
<code>Enabled</code>	Gets or sets a value indicating whether the web control is enabled.


Table 33-2. Select Properties of the *WebControl* Base Class (continued)

Property	Meaning in Life
CssClass	Allows you to assign a class defined within a Cascading Style Sheet to a web widget.
Font	Gets font information for the web control.
ForeColor	Gets or sets the foreground color (typically the color of the text) of the web control.
Height, Width	Get or set the height and width of the web control.
TabIndex	Gets or sets the tab index of the web control.
ToolTip	Gets or sets the tool tip for the web control to be displayed when the cursor is over the control.

Almost all of these properties are self-explanatory, so rather than drill through the use of them one by one, let's instead check out a number of ASP.NET Web Form controls in action.

Major Categories of ASP.NET Web Controls

The ASP.NET web control library can be broken down into several broad categories, all of which can be viewed within the Visual Studio 2010 Toolbox (provided you have an *.aspx page open for design!). See Figure 33-3.

**Figure 33-3.** The categories of ASP.NET web controls

Under the Standard area of the Toolbox, you will find the most frequently used controls, including Button, Label, TextBox and ListBox. In addition to these vanilla-flavored UI elements, the Standard area also lists more exotic web controls such as Calendar, Wizard, and AdRotator (Figure 33-4).




Figure 33-4. The Standard ASP.NET web controls

The Data section is where you can find a set of controls used for data binding operations, including the new ASP.NET Chart control, which allows you to render out graphical chart data (pie charts, line charts) typically as the result of a data binding operation (see Figure 33-5).




Figure 33-5. Data centric ASP.NET web controls

The ASP.NET validation controls (found in the Validation area of the toolbox) are very interesting in that they can be configured to emit back blocks of client side JavaScript that will test input fields for valid data. If a validation error occurs, the user will see an error message and will not be allowed to post back to the web server until the error is corrected.

The Navigation node of the Toolbox is where you will find a small set of controls (Menu, SiteMapPath and TreeView) which typically work in conjunction with a *.sitemap file. As briefly mentioned earlier in this chapter, these navigation controls allow you to describe the structure of a multi-paged site using XML descriptions.

The *really* exotic set of ASP.NET web controls would have to be the Login controls (Figure 33-6).




Figure 33-6. Security ASP.NET web controls

These controls can radically simplify how to incorporate basic security features (password recovery, login screens, etc.) into your web applications. In fact, these controls are so powerful, they will even dynamically create a dedicated database to store credentials (saved under the App_Data folder of your website) if you do not already have a specific security database.

Note The remaining categories of web controls shown in the Visual Studio toolbox (such as WebParts, AJAX Extensions and Dynamic Data) are for more specialized programming needs and will not be examined here.

A Brief Word Regarding System.Web.UI.HtmlControls

Truth be told, there are two distinct web control toolkits that ship with ASP.NET. In addition to the ASP.NET web controls (within the `System.Web.UI.WebControls` namespace), the base class libraries also provides the `System.Web.UI.HtmlControls` control library.

The HTML controls are a collection of types that allow you to make use of traditional HTML controls on a web forms page. However, unlike simple HTML tags, HTML controls are object-oriented entities that can be configured to run on the server and thus support server-side event handling. Unlike ASP.NET web controls, HTML controls are quite simplistic in nature and offer little functionality beyond standard HTML tags (`HtmlButton`, `HtmlInputControl`, `HtmlTable`, etc.).

The HTML controls can be useful if your team has a clear division between those who build HTML UIs and .NET developers. HTML folks can make use of their web editor of choice using familiar markup tags and pass the HTML files to the development team. At this point, developers can configure these HTML controls to run as server controls (by right-clicking an HTML widget within Visual Studio 2010). This will allow developers to handle server-side events and work with the HTML widget programmatically.

The HTML controls provide a public interface that mimics standard HTML attributes. For example, to obtain the information within an input area, you make use of the `Value` property rather than the web control-centric `Text` property. Given that the HTML controls are not as feature-rich as the ASP.NET web controls, I won't make further mention of them in this text.

Web Control Documentation

You will get a chance to work with a number of ASP.NET web controls during the remainder of this book; however, you should certainly take a moment to search the .NET Framework 4.0 SDK documentation for the `System.Web.UI.WebControls` Namespace. Here you will find explanations and code examples for each member of the namespace (Figure 33-7).




Figure 33-7. All ASP.NET web controls are documented in the .NET Framework 4.0 SDK documentation

Building the ASP.NET Cars Web Site

Given that many of the “simple” controls look and feel so close to their Windows Forms counterparts, I won’t bother to enumerate the details of the basic widgets (Buttons, Labels, TextBoxes, etc.). Rather, let’s build a new website that illustrates working with several of the more exotic controls as well as the ASP.NET master page model and aspects of the data binding engine. Specifically, this next example will illustrate the following techniques:

- Working with master pages
- Working with site map navigation
- Working with the `GridView` control
- Working with the `Wizard` control

To begin, create an Empty Web Site project named AspNetCarsSite. Note that we are not yet creating a new ASP.NET Web Site project, as this will add a number of starter files to the mix which we have not yet examined. For this project, we will add what we need manually.

Working with ASP.NET Master Pages

Many websites provide a consistent look and feel across multiple pages (a common menu navigation system, common header and footer content, company logo, etc.). Under ASP.NET 1.x, developers made extensive use of UserControls and custom web controls to define web content that was to be used across multiple pages. While UserControls and custom web controls are still a very valid option under ASP.NET, we are also provided with *master pages* that complement these existing technologies.

Simply put, a master page is little more than an ASP.NET page that takes a *.master file extension. On their own, master pages are not viewable from a client-side browser (in fact, the ASP.NET runtime will not serve this flavor of web content). Rather, master pages define a common UI layout shared by all pages (or a subset of pages) in your site.

As well, a *.master page will define various content placeholder areas that establish a region of UI real estate other *.aspx files may plug into. As you will see, *.aspx files that plug their content into a master file look and feel a bit different from the *.aspx files we have been examining. Specifically, this flavor of an *.aspx file is termed a *content page*. Content pages are *.aspx files that do not define an HTML <form> element (that is the job of the master page).

However, as far as the end user is concerned, a request is made to a given *.aspx file. On the web server, the related *.master file and any related *.aspx content pages are blended into a single unified HTML page declaration.

To illustrate the use of master pages and content pages, begin by inserting a new master page into your website via the Website ▶ Add New Item menu selection (Figure 33-8 shows the resulting dialog box).




Figure 33-8. Inserting a new *.master file

The initial markup of the MasterPage.master file looks like the following:

```
<%@ Master Language="C#" AutoEventWireup="true"
   CodeFile="MasterPage.master.cs" Inherits="MasterPage" %>

<!DOCTYPE html PUBLIC "-//W3C//DTD XHTML 1.0 Transitional//EN"
 "http://www.w3.org/TR/xhtml1/DTD/xhtml1-transitional.dtd">

<html xmlns="http://www.w3.org/1999/xhtml">
<head runat="server">
  <title>Untitled Page</title>
  <asp:ContentPlaceHolder id="head" runat="server">
    </asp:ContentPlaceHolder>
</head>
<body>
  <form id="form1" runat="server">
    <div>
      <asp:ContentPlaceHolder id="ContentPlaceHolder1" runat="server">
        </asp:ContentPlaceHolder>
    </div>
  </form>
</body>
</html>
```

The first point of interest is the new `<%@Master%>` directive. For the most part, this directive supports the same attributes as the `<%@Page%>` directive described in the previous chapter. Like Page types, a master page derives from a specific base class, which in this case is `MasterPage`. If you were to open up your related code file, you would find the following class definition:

```
public partial class MasterPage : System.Web.UI.MasterPage
{
  protected void Page_Load(object sender, EventArgs e)
  {
  }
}
```

The other point of interest within the markup of the master is the `<asp:ContentPlaceHolder>` definition. This region of a master page represents the area of the master that the UI widgets of the related *.aspx content file may plug into, not the content defined by the master page itself.

If you do intend to plug in an *.aspx file within this region, the scope within the `<asp:ContentPlaceHolder>` and `</asp:ContentPlaceHolder>` tags will typically remain empty. However, if you so choose, you are able to populate this area with various web controls that function as a default UI to use in the event that a given *.aspx file in the site does not supply specific content. For this example, assume that each *.aspx page in your site will indeed supply custom content, and therefore your `<asp:ContentPlaceHolder>` elements will be empty.

Note A *.master page may define as many content placeholders as necessary. As well, a single *.master page may nest additional *.master pages.

You are able to build a common UI of a *.master file using the same Visual Studio 2010 designers used to build *.aspx files. For this site, you will add a descriptive Label (to serve as a common welcome message), an AdRotator control (which will randomly display one of two image files), and a TreeView control (to allow the user to navigate to other areas of the site). Here is some possible markup:

```
<html xmlns="http://www.w3.org/1999/xhtml">
<head runat="server">
    <title>Untitled Page</title>
    <asp:ContentPlaceHolder id="head" runat="server">
        </asp:ContentPlaceHolder>
</head>
<body>
    <form id="form1" runat="server">
        <div>
            <hr />
            <asp:Label ID="Label1" runat="server" Font-Size="XX-Large"
                Text="Welcome to the ASP.NET Cars Super Site!"></asp:Label>
            <asp:AdRotator ID="myAdRotator" runat="server"/>
            &nbsp;<br />
            <br />
            <asp:TreeView ID="navigationTree" runat="server">
                </asp:TreeView>
            <hr />
        </div>
        <div>
            <asp:ContentPlaceHolder id="ContentPlaceHolder1" runat="server">
            </asp:ContentPlaceHolder>
        </div>
        </form>
    </body>
</html>
```

Figure 33-9 shows the design time view of the current master page.




Figure 33-9. The *.master file's shared UI

Feel free to enhance the look of your TreeView control by using the inline editor of the control and selecting the Auto Format... link. For my example, I selected the Arrow theme from the resulting dialog and ended up with the following control markup:

```
<asp:TreeView ID="navigationTree" runat="server"
    ImageSet="Arrows">
    <HoverNodeStyle Font-Underline="True" ForeColor="#5555DD" />
    <NodeStyle Font-Names="Verdana" Font-Size="8pt" ForeColor="Black"
        HorizontalPadding="5px" NodeSpacing="0px" VerticalPadding="0px" />
    <ParentNodeStyle Font-Bold="False" />
    <SelectedNodeStyle Font-Underline="True" ForeColor="#5555DD"
        HorizontalPadding="0px" VerticalPadding="0px" />
</asp:TreeView>
```

Working with the TreeView Control Site Navigation Logic

ASP.NET ships with several web controls that allow you to handle site navigation: SiteMapPath, TreeView, and Menu. As you would expect, these web widgets can be configured in multiple ways. For example, each of these controls can dynamically generate its nodes via an external XML file (or an XML-based *.sitemap file), programmatically generate nodes in code, or through markup using the designers of Visual Studio 2010.

Your navigation system will be dynamically populated using a *.sitemap file. The benefit of this approach is that we can define the overall structure of our website in an external file and then bind it to a TreeView (or Menu) control on the fly. This way, if the navigational structure of your website changes, we simply need to modify the *.sitemap file and reload the page. To begin, insert a new Web.sitemap file into your project using the Website ▶ Add New Item menu option to bring up the dialog box shown in Figure 33-10.




Figure 33-10. Inserting a new Web.sitemap file

As you can see, the initial `Web.sitemap` file defines a topmost item with two subnodes:

```
<?xml version="1.0" encoding="utf-8" ?>
<siteMap xmlns="http://schemas.microsoft.com/AspNet/SiteMap-File-1.0" >
  <siteMapNode url="" title="" description="">
    <siteMapNode url="" title="" description="" />
    <siteMapNode url="" title="" description="" />
  </siteMapNode>
</siteMap>
```

If we were to bind this structure to a `Menu` control, we would find a topmost menu item with two submenus. Therefore, when you wish to define subitems, simply define new `<siteMapNode>` elements within the scope of an existing `<siteMapNode>`. In any case, the goal is to define the overall structure of your website within a `Web.sitemap` file using various `<siteMapNode>` elements. Each one of these elements can define a title and URL attribute. The URL attribute represents which *.aspx file to navigate to when the user clicks a given menu item (or node of a `TreeView`). Your site map will contain three site map nodes (underneath the top-level site map node), as follows:

- *Home: Default.aspx*
- *Build a Car: BuildCar.aspx*
- *View Inventory: Inventory.aspx*

Your menu system has a single topmost `Welcome` item with three subelements. Therefore, you can update the `Web.sitemap` file as follows, but be aware that each `url` value must be unique (if not, you will receive a runtime error):

```
<?xml version="1.0" encoding="utf-8" ?>
<siteMap xmlns="http://schemas.microsoft.com/AspNet/SiteMap-File-1.0" >
  <siteMapNode url="" title="Welcome!" description="">
    <siteMapNode url("~/Default.aspx" title="Home"
      description="The Home Page" />
    <siteMapNode url "~/BuildCar.aspx" title="Build a car"
      description="Create your dream car" />
    <siteMapNode url "~/Inventory.aspx" title="View Inventory"
      description="See what is in stock" />
  </siteMapNode>
</siteMap>
```

Note The `~/` prefix before each page in the `url` attribute is a notation that represents the root of the website.

Now, despite what you may be thinking, you do not associate a `Web.sitemap` file directly to a `Menu` or `TreeView` control using a given property. Rather, the *.master or *.aspx file that contains the UI widget that will display the `Web.sitemap` file must contain a `SiteMapDataSource` component. This type will automatically load the `Web.sitemap` file into its object model when the page is requested. The `Menu` and `TreeView` types then set their `DataSourceID` property to point to the `SiteMapDataSource` instance.

To add a new SiteMapDataSource to your *.master file and automatically set the DataSourceID property, you can make use of the Visual Studio 2010 designer. Activate the inline editor of the TreeView control (i.e., click the tiny arrow in the top-right corner of the TreeView) and select New Data Source, as shown in Figure 33-11.




Figure 33-11. Adding a new SiteMapDataSource

From the resulting dialog box, select the SiteMap icon. This will set the DataSourceID property of the Menu item as well as add a new SiteMapDataSource component to your page. This is all you need to do to configure your TreeView control to navigate to the additional pages on your site. If you wish to perform additional processing when the user selects a given menu item, you may do so by handling the SelectedNodeChanged event. There is no need to do so for this example, but be aware that you are able to determine which menu item was selected using the incoming event arguments.

Establishing Bread Crumbs with the SiteMapPath Type

Before moving on to the AdRotator control, add a SiteMapPath type (located in the Navigation tab in the toolbox) onto your *.master file, beneath the content placeholder element. This widget will automatically adjust its content based on the current selection of the menu system. As you may know, this can provide a helpful visual cue for the end user (formally, this UI technique is termed *breadcrumbs*). Once you complete this example, you will notice that when you select the Welcome ► Build a Car menu item, the SiteMapPath widget updates accordingly automatically.

Working with the AdRotator

The role of the ASP.NET AdRotator widget is to randomly display a given image at some position in the browser. Go ahead and add an AdRotator widget to the designer. Once you do, it is displayed as an empty placeholder. Functionally, this control cannot do its magic until you assign the AdvertisementFile property to point to the source file that describes each image. For this example, the data source will be a simple XML file named Ads.xml.

To add the XML file to the Web site, go to the Website ► Add New Item menu option and select XML file. Name the file Ads.xml and specify a unique <Ad> element for each image you wish to display. At minimum, each <Ad> element specifies the image to display (ImageUrl), the URL to navigate to if the image is selected (TargetUrl), mouseover text (AlternateText), and the weight of the ad (Impressions):

```
<Advertisements>
  <Ad>
    <ImageUrl>SlugBug.jpg</ImageUrl>
    <TargetUrl>http://www.Cars.com</TargetUrl>
    <AlternateText>Your new Car?</AlternateText>
    <Impressions>80</Impressions>
  </Ad>
  <Ad>
    <ImageUrl>car.gif</ImageUrl>
    <TargetUrl>http://www.CarSuperSite.com</TargetUrl>
    <AlternateText>Like this Car?</AlternateText>
    <Impressions>80</Impressions>
  </Ad>
</Advertisements>
```

Here you have specified two image files (car.gif and slugbug.jpg). As a result, you will need to ensure that these files are in the root of your website (these files have been included with this book's code download). To add them to your current project, select the Website ► Add Existing Item menu option. At this point, you can associate your XML file to the AdRotator control via the AdvertisementFile property (in the Properties window):

```
<asp:AdRotator ID="myAdRotator" runat="server"
  AdvertisementFile="~/Ads.xml"/>
```

Later when you run this application and post back to the page, you will be randomly presented with one of two image files.

Defining the Default Content Page

Now that you have a master page established, you can begin designing the individual *.aspx pages that will define the UI content to merge within the <asp:ContentPlaceHolder> tag of the master page. The *.aspx files that are merged within a master page are called *content pages* and have a few key differences from a normal, standalone ASP.NET web page.

In a nutshell, the *.master file defines the <form> section of the final HTML page. Therefore, the existing <form> area within the *.aspx file will need to be replaced with an <asp:Content> scope. While you could update the markup of your initial *.aspx file by hand, you can insert a new content page to your project; simply right-click anywhere on the designer surface of the *.master file and select the Add Content Page menu option. This will generate a new *.aspx file with the following initial markup:

```
<%@ Page Language="C#" MasterPageFile="~/MasterPage.master"
  AutoEventWireup="true" CodeFile="Default.aspx.cs"
  Inherits="_Default" Title="Untitled Page" %>
```

```
<asp:Content ID="Content1"
    ContentPlaceHolderID="head" Runat="Server">
</asp:Content>
<asp:Content ID="Content2"
    ContentPlaceHolderID="ContentPlaceHolder1" Runat="Server">
</asp:Content>
```

First, notice that the `<%@Page%>` directive has been updated with a new `MasterPageFile` attribute that is assigned to your `*.master` file. Also note that rather than having a `<form>` element, we have an `<asp:Content>` scope (currently empty) that has set the `ContentPlaceHolderID` value identical to the `<asp:ContentPlaceHolder>` component in the master file.

Given these associations, the content page understands where to plug in its content, while the master's content is displayed in a read-only nature on the content page. There is no need to build a complex UI for your `Default.aspx` content area. For this example, simply add some literal text that provides some basic site instructions, as you see in Figure 33-12 (also notice on the upper right of the content page that there is a link to switch to the related master file).




Figure 33-12. Authoring the first content page

Now, if you run your project, you will find that the UI content of the `*.master` and `Default.aspx` files have been merged into a single stream of HTML. As you can see from Figure 33-13, the end user is unaware that the master page even exists. Also, as you refresh the page (via the F5 key), you should see the AdRotator randomly displaying one of two images.




Figure 33-13. At runtime, master files and content pages render back a single form

■ **Note** Do be aware that a Page object's master page can be assigned programmatically within the PreInit event of a Page derived type using the inherited Master property.

Designing the Inventory Content Page

To insert the Inventory.aspx content page into your current project, open the *.master page in the IDE, select Website ▶ Add Content Page, and rename this file to Inventory.aspx. The role of the Inventory content page is to display the contents of the Inventory table of the AutoLot database within a GridView control.

The ASP.NET GridView control has the ability to represent connection string data and SQL Select, Insert, Update, and Delete statements (or alternatively stored procedures) *in markup*. Therefore, rather than authoring all of the necessary ADO.NET code by hand, you can allow the SqlDataSource class to generate the markup for you. Using the visual designers, you are able to assign the DataSourceID property of the GridView to the SqlDataSource component.

With a few simple mouse clicks, you can configure the GridView to automatically select, update, and delete records of the underlying data store. While this zero-code mindset greatly simplifies the amount of boilerplate code, understand that this simplicity comes with a loss of control and may not be the best approach for an enterprise-level application. This model can be wonderful for low-trafficked pages, prototyping a website, or smaller in-house applications.

To illustrate how to work with the GridView (and the data access logic) in a declarative manner, begin by updating the Inventory.aspx content page with a descriptive Label control. Next, open the Server Explorer tool (via the View menu) and make sure you have added a data connection to the AutoLot database created during your examination of ADO.NET (see Chapter 21 for a walkthrough of the process of adding a data connection). Now, select the Inventory table in Server Explorer and drag it onto the content area of the Inventory.aspx file. Once you have done so, the IDE responds by performing the following steps:

1. Your `web.config` file was updated with a new `<connectionStrings>` element.
 2. A `SqlDataSource` component was configured with the necessary `Select`, `Insert`, `Update`, and `Delete` logic.
 3. The `DataSourceID` property of the `GridView` has been set to the new `SqlDataSource` component.
-

Note As an alternative, you can configure a `GridView` widget using the inline editor. Select `New Data Source` from the `Choose Data Source` drop-down box. This will activate a wizard that walks you through a series of steps to connect this component to the required data source.

If you examine the opening declaration of the `GridView` control, you will see that the `DataSourceID` property has been set to the `SqlDataSource` you just defined:

```
<asp:GridView ID="GridView1" runat="server" AutoGenerateColumns="False"
    DataKeyNames="CarID" DataSourceID="SqlDataSource1"
    EmptyDataText="There are no data records to display.">
    <Columns>
        <asp:BoundField DataField="CarID" HeaderText="CarID" ReadOnly="True"
            SortExpression="CarID" />
        <asp:BoundField DataField="Make" HeaderText="Make" SortExpression="Make" />
        <asp:BoundField DataField="Color" HeaderText="Color" SortExpression="Color" />
        <asp:BoundField DataField="PetName" HeaderText="PetName"
            SortExpression="PetName" />
    </Columns>
</asp:GridView>
```

The `SqlDataSource` type is where a majority of the action is taking place. In the markup that follows, notice that this type has recorded the necessary SQL statements (with parameterized queries, no less) to interact with the `Inventory` table of the `AutoLot` database. As well, using the `$` syntax of the `ConnectionString` property, this component will automatically read the `<connectionStrings>` value from `web.config`:

```
<asp:SqlDataSource ID="SqlDataSource1" runat="server"
    ConnectionString="<%$ ConnectionStrings:AutoLotConnectionString1 %>"
    DeleteCommand="DELETE FROM [Inventory] WHERE [CarID] = @CarID"
    InsertCommand="INSERT INTO [Inventory] ([CarID], [Make], [Color], [PetName])
        VALUES (@CarID, @Make, @Color, @PetName)"
    ProviderName="<%$ ConnectionStrings:AutoLotConnectionString1.ProviderName %>"
    SelectCommand="SELECT [CarID], [Make], [Color], [PetName] FROM [Inventory]"
    UpdateCommand="UPDATE [Inventory] SET [Make] = @Make,
        [Color] = @Color, [PetName] = @PetName WHERE [CarID] = @CarID">
    <DeleteParameters>
        <asp:Parameter Name="CarID" Type="Int32" />
    </DeleteParameters>
    <UpdateParameters>
```

```
<asp:Parameter Name="Make" Type="String" />
<asp:Parameter Name="Color" Type="String" />
<asp:Parameter Name="PetName" Type="String" />
<asp:Parameter Name="CarID" Type="Int32" />
</UpdateParameters>
<InsertParameters>
    <asp:Parameter Name="CarID" Type="Int32" />
    <asp:Parameter Name="Make" Type="String" />
    <asp:Parameter Name="Color" Type="String" />
    <asp:Parameter Name="PetName" Type="String" />
</InsertParameters>
</asp:SqlDataSource>
```

At this point, you are able to run your web program, click the View Inventory menu item, and view your data, as shown in Figure 33-14. (Note that I updated my DataView grid with a unique look and feel using the inline designer.)



The screenshot shows a web browser window titled "Untitled Page" with the URL "http://localhost:3123/AspNetCarsSite/". The page content is as follows:

Welcome to the ASP.NET Cars Super Site!

 Want a Blue SLUG BUG?
Come to [Cars.com!](#)

▼ Welcome!

- ▷ Home
- ▷ Build a car
- ▷ [View Inventory](#)

CarID	Make	Color	PetName
83	Ford	Rust	Rusty
107	Ford	Red	Snake
555	Ford	Yellow	Buzz
678	Yugo	Green	Chunker
904	VW	Black	Hank
1000	BMW	Black	Bimmer
1001	BMW	Tan	Daisy
1992	Saab	Pink	Pinkey
2222	Yugo	Blue	

Welcome! : [View Inventory](#)

Figure 33-14. The zero-code model of the `SqlDataSource` component

Enabling Sorting and Paging

The GridView control can easily be configured for sorting (via column name hyperlinks) and paging (via numeric or next/previous hyperlinks). To do so, activate the inline editor and check the appropriate options, as shown in Figure 33-15.




Figure 33-15. Enabling sorting and paging

When you run your page again, you will be able to sort your data by clicking the column names and scrolling through your data via the paging links (provided you have enough records in the Inventory table!).

Enabling In-Place Editing

The final detail of this page is to enable the `GridView` control's support for in-place activation. Given that your `SqlDataSource` already has the necessary `Delete` and `Update` logic, all you need to do is check the `Enable Deleting` and `Enable Editing` check boxes of the `GridView` (see Figure 33-15 for a reference point). Sure enough, when you navigate back to the `Inventory.aspx` page, you are able to edit and delete records (as shown in Figure 33-16) and update the underlying `Inventory` table of the `AutoLot` database.

The screenshot shows a web browser window titled "Untitled Page" displaying the "Welcome to the ASP.NET Cars Super Site!" page. The URL in the address bar is `http://localhost:3123/AspNetCarsSite/Inventory.aspx`. The page features a navigation menu on the left with links like "Welcome!", "Home", "Build a car", and "View Inventory". Below the menu is a `GridView` control showing a list of cars with columns: CarID, Make, Color, and PetName. The first row is selected, and its "Make" cell contains the value "BMW" with a cursor, indicating it is being edited. The "Color" cell for this row contains "Red". The "PetName" cell contains "Snake". The other rows show car details: Ford (Rust, Rusty), Ford (Yellow, Buzz), Yugo (Green, Chunker), VW (Black, Hank), BMW (Black, Bimmer), BMW (Tan, Daisy), Saab (Pink, Pinkey), and Yugo (Blue, empty). Each row has "Edit" and "Delete" links. At the bottom of the grid, there is a link "Welcome! : View Inventory".

	CarID	Make	Color	PetName
Edit Delete	83	Ford	Rust	Rusty
Update Cancel	107	BMW	Red	Snake
Edit Delete	555	Ford	Yellow	Buzz
Edit Delete	678	Yugo	Green	Chunker
Edit Delete	904	VW	Black	Hank
Edit Delete	1000	BMW	Black	Bimmer
Edit Delete	1001	BMW	Tan	Daisy
Edit Delete	1992	Saab	Pink	Pinkey
Edit Delete	2222	Yugo	Blue	

Welcome! : [View Inventory](#)

Figure 33-16. Editing and deleting functionality

■ **Note** Enabling in-place editing for a `GridView` requires that the database table be assigned a primary key. If you do not see these options enabled, chances are you forgot to set `CarID` as the primary key of the `Inventory` table within the `AutoLot` database.

Designing the Build-a-Car Content Page

The final task for this example is to design the `BuildCar.aspx` content page. Insert this file into the current project (via the `Website > Add Content Page` menu option). This new page will make use of the ASP.NET Wizard web control, which provides a simple way to walk the end user through a series of related steps. Here, the steps in question will simulate the act of building an automobile for purchase.

Place a descriptive `Label` and `Wizard` control onto the content area. Next, activate the inline editor for the `Wizard` and click the `Add/Remove WizardSteps` link. Add a total of four steps, as shown in Figure 33-17.




Figure 33-17. Configuring our wizard

Once you have defined these steps, you will notice that the `Wizard` defines an empty content area where you can now drag and drop controls for the currently selected step. For this example, update each step with the following UI elements (be sure to provide a fitting ID value for each item using the Properties window):

- *Pick Your Model:* A `TextBox` control
- *Pick Your Color:* A `ListBox` control
- *Name Your Car:* A `TextBox` control
- *Delivery Date:* A `Calendar` control

The `ListBox` control is the only UI element of the `Wizard` that requires additional steps. Select this item on the designer (making sure you first select the `Pick Your Color` link) and fill this widget with a set of colors using the `Items` property of the Properties window. Once you do, you will find markup much like the following within the scope of the `Wizard` definition:

```
<asp:ListBox ID="ListBoxColors" runat="server" Width="237px">
  <asp:ListItem>Purple</asp:ListItem>
  <asp:ListItem>Green</asp:ListItem>
  <asp:ListItem>Red</asp:ListItem>
  <asp:ListItem>Yellow</asp:ListItem>
  <asp:ListItem>Pea Soup Green</asp:ListItem>
  <asp:ListItem>Black</asp:ListItem>
  <asp:ListItem>Lime Green</asp:ListItem>
</asp:ListBox>
```

Now that you have defined each of the steps, you can handle the `FinishButtonClick` event for the autogenerated Finish button. Be aware, however, that you won't see this Finish button until you select the final step of the wizard on the designer. Once you have selected the final step, simply double click on the Finish button to generate the event handler. Within the server-side event handler, obtain the selections from each UI element and build a description string that is assigned to the `Text` property of an additional Label type named `lblOrder`:

```
public partial class Default2 : System.Web.UI.Page
{
  protected void Page_Load(object sender, EventArgs e)
  {
  }

  protected void carWizard_FinishButtonClick(object sender,
    System.Web.UI.WebControls.WizardNavigationEventArgs e)
  {
    // Get each value.
    string order = string.Format("{0}, your {1} {2} will arrive on {3}.",
      txtCarPetName.Text, ListBoxColors.SelectedValue,
      txtCarModel.Text,
      carCalendar.SelectedDate.ToShortDateString());

    // Assign to label
    lblOrder.Text = order;
  }
}
```

At this point, your `AspNetCarsSite` web application is complete! Figure 33-18 shows the Wizard in action.




Figure 33-18. The Wizard control in action

That wraps up your first look of various ASP.NET web controls, master pages, content pages and site map navigation. Next up, let's look at the functionality of the ASP.NET validation controls.

■ **Source Code** The AspNetCarsSite website is included under the Chapter 33 subdirectory.

The Role of the Validation Controls

The next set of Web Form controls we will examine are known collectively as *validation controls*. Unlike the other Web Form controls we've examined, validation controls are not used to emit HTML for

rendering purposes, but are used to emit client-side JavaScript (and possibly related server-side code) for the purpose of form validation. As illustrated at the beginning of this chapter, client-side form validation is quite useful because you can ensure that various constraints are in place before posting back to the web server, thereby avoiding expensive round-trips. Table 33-3 gives a rundown of the ASP.NET validation controls.

Table 33-3. ASP.NET Validation Controls

Control	Meaning in Life
CompareValidator	Validates that the value of an input control is equal to a given value of another input control or a fixed constant.
CustomValidator	Allows you to build a custom validation function that validates a given control.
RangeValidator	Determines that a given value is in a predetermined range.
RegularExpressionValidator	Checks whether the value of the associated input control matches the pattern of a regular expression.
RequiredFieldValidator	Ensures that a given input control contains a value (i.e., is not empty).
ValidationSummary	Displays a summary of all validation errors of a page in a list, bulleted list, or single-paragraph format. The errors can be displayed inline and/or in a pop-up message box.

All of the validation controls ultimately derive from a common base class named `System.Web.UI.WebControls.BaseValidator`, and therefore they have a set of common features. Table 33-4 documents the key members.

Table 33-4. Common Properties of the ASP.NET Validators

Member	Meaning in Life
ControlToValidate	Gets or sets the input control to validate.
Display	Gets or sets the display behavior of the error message in a validation control.
EnableClientScript	Gets or sets a value indicating whether client-side validation is enabled.
ErrorMessage	Gets or sets the text for the error message.
ForeColor	Gets or sets the color of the message displayed when validation fails.

To illustrate working with these validation controls, create a new Empty Web Site project named ValidatorCtrls and insert a new Web Form named Default.aspx. To begin, place four (well-named) TextBox controls (with four corresponding and descriptive Labels) onto your page. Next, place a RequiredFieldValidator, RangeValidator, RegularExpressionValidator, and CompareValidator type adjacent to each respective input field. Last of all, add a single Button and final Label (see Figure 33-19).




Figure 33-19. ASP.NET validation controls will ensure your form data is correct before allowing postback

Now that you have an initial UI, let's walk through the process of configuring each validator.

The RequiredFieldValidator

Configuring the RequiredFieldValidator is straightforward. Simply set the ErrorMessage and ControlToValidate properties accordingly using the Visual Studio 2010 Properties window. Here is the resulting markup that ensures the txtRequiredField text box is not empty:

```
<asp:RequiredFieldValidator ID="RequiredFieldValidator1"
    runat="server" ControlToValidate="txtRequiredField"
    ErrorMessage="Oops! Need to enter data.">
</asp:RequiredFieldValidator>
```

The RequiredFieldValidator supports an InitialValue property. You can use this property to ensure that the user enters any value other than the initial value in the related TextBox. For example, when the user first posts to a page, you may wish to configure a TextBox to contain the value "Please enter your name". Now, if you did not set the InitialValue property of the RequiredFieldValidator, the runtime would assume that the string "Please enter your name" is valid. Thus, to ensure a required

TextBox is valid only when the user enters anything other than “Please enter your name”, configure your widgets as follows:

```
<asp:RequiredFieldValidator ID="RequiredFieldValidator1"
    runat="server" ControlToValidate="txtRequiredField"
    ErrorMessage="Oops! Need to enter data."
    InitialValue="Please enter your name">
</asp:RequiredFieldValidator>
```

The RegularExpressionValidator

The RegularExpressionValidator can be used when you wish to apply a pattern against the characters entered within a given input field. To ensure that a given TextBox contains a valid US Social Security number, you could define the widget as follows:

```
<asp:RegularExpressionValidator ID="RegularExpressionValidator1"
    runat="server" ControlToValidate="txtRegExp"
    ErrorMessage="Please enter a valid US SSN."
    ValidationExpression="\d{3}-\d{2}-\d{4}">
</asp:RegularExpressionValidator>
```

Notice how the RegularExpressionValidator defines a ValidationExpression property. If you have never worked with regular expressions before, all you need to be aware of for this example is that they are used to match a given string pattern. Here, the expression "\d{3}-\d{2}-\d{4}" is capturing a standard US Social Security number of the form xxx-xx-xxxx (where x is any digit).

This particular regular expression is fairly self-explanatory; however, assume you wish to test for a valid Japanese phone number. The correct expression now becomes much more complex: "(0\d{1,4}-|\(\d{1,4}\)?)?\d{1,4}-\d{4}". The good news is that when you select the ValidationExpression property using the Properties window, you can pick from a predefined set of common regular expressions by clicking the ellipse button.

Note If you are interested in regular expressions, you will be happy to know that the .NET platform supplies two namespaces (`System.Text.RegularExpressions` and `System.Web.RegularExpressions`) devoted to the programmatic manipulation of such patterns.

The RangeValidator

In addition to a `MinimumValue` and `MaximumValue` property, RangeValidators have a property named `Type`. Because you are interested in testing the user-supplied input against a range of whole numbers, you need to specify `Integer` (which is *not* the default!):

```
<asp:RangeValidator ID="RangeValidator1"
    runat="server" ControlToValidate="txtRange"
    ErrorMessage="Please enter value between 0 and 100.">
```

```
    MaximumValue="100" MinimumValue="0" Type="Integer">
</asp:RangeValidator>
```

The RangeValidator can also be used to test whether a given value is between a currency value, date, floating-point number, or string data (the default setting).

The CompareValidator

Finally, notice that the CompareValidator supports an Operator property:

```
<asp:CompareValidator ID="CompareValidator1" runat="server"
    ControlToValidate="txtComparison"
    ErrorMessage="Enter a value less than 20." Operator="LessThan"
    ValueToCompare="20" Type="Integer">
</asp:CompareValidator>
```

Given that the role of this validator is to compare the value in the text box against another value using a binary operator, it should be no surprise that the Operator property may be set to values such as LessThan, GreaterThan, Equal, and NotEqual. Also note that the ValueToCompare is used to establish a value to compare against. Do notice here that we have set the Type attribute to Integer. By default, the CompareValidator will be testing against string values!

Note The CompareValidator can also be configured to compare a value within another Web Form control (rather than a hard-coded value) using the ControlToValidate property.

To finish up the code for this page, handle the Click event for the Button control and inform the user that he or she has succeeded in the validation logic:

```
public partial class _Default : System.Web.UI.Page
{
    protected void Page_Load(object sender, EventArgs e)
    {

    }
    protected void btnPostBack_Click(object sender, EventArgs e)
    {
        lblValidationComplete.Text = "You passed validation!";
    }
}
```

Now, navigate to this page using your browser of choice. At this point, you should not see any noticeable changes. However, when you attempt to click the Submit button after entering bogus data, your error message is suddenly visible. Once you enter valid data, the error messages are removed and postback occurs.

If you look at the HTML rendered by the browser, you see that the validation controls generate a client-side JavaScript function that makes use of a specific library of JavaScript functions that is automatically downloaded to the user's machine. Once the validation has occurred, the form data is posted back to the server, where the ASP.NET runtime will perform the *same* validation tests on the web server (just to ensure that no along-the-wire tampering has taken place).

On a related note, if the HTTP request was sent by a browser that does not support client-side JavaScript, all validation will occur on the server. In this way, you can program against the validation controls without being concerned with the target browser; the returned HTML page redirects the error processing back to the web server.

Creating Validation Summaries

The next validation-centric topic we will examine here is the use of the `ValidationSummary` widget. Currently, each of your validators displays its error message at the exact place in which it was positioned at design time. In many cases, this may be exactly what you are looking for. However, on a complex form with numerous input widgets, you may not want to have random blobs of red text pop up. Using the `ValidationSummary` type, you can instruct all of your validation types to display their error messages at a specific location on the page.

The first step is to simply place a `ValidationSummary` on your *.aspx file. You may optionally set the `HeaderText` property of this type as well as the `DisplayMode`, which by default will list all error messages as a bulleted list.

```
<asp:ValidationSummary id="ValidationSummary1"
    runat="server" Width="353px"
    HeaderText="Here are the things you must correct.">
</asp:ValidationSummary>
```

Next, you need to set the `Display` property to `None` for each of the individual validators (e.g., `RequiredFieldValidator`, `RangeValidator`) on the page. This will ensure that you do not see duplicate error messages for a given validation failure (one in the summary pane and another at the validator's location). Figure 33-20 shows the summary pane in action.




Figure 33-20. Using a validation summary

Last but not least, if you would rather have the error messages displayed using a client-side MessageBox, set the ValidationSummary control's ShowMessageBox property to true and the ShowSummary property to false.

Defining Validation Groups

It is also possible to define *groups* for validators to belong to. This can be very helpful when you have regions of a page that work as a collective whole. For example, you may have one group of controls in a Panel object to allow the user to enter his or her mailing address and another Panel containing UI elements to gather credit card information. Using groups, you can configure each group of controls to be validated independently.

Insert a new page into your current project named ValidationGroups.aspx that defines two Panels. The first Panel object expects a TextBox to contain some form of user input (via a RequiredFieldValidator) and the second Panel expects a US SSN value (via a RegularExpressionValidator). Figure 33-21 shows one possible UI.




Figure 33-21. These Panel objects will independently configure their input areas

To ensure that the validators function independently, simply assign each validator and the control being validated to a uniquely named group using the ValidationGroup property. In the following possible markup, note that the Click event handlers used here are essentially empty stubs in the code file, and they are only used to allow postback to occur to the web server:

```
<form id="form1" runat="server">

    <asp:Panel ID="Panel1" runat="server" Height="83px" Width="296px">
        <asp:TextBox ID="txtRequiredData" runat="server"
            ValidationGroup="FirstGroup">
        </asp:TextBox>
        <asp:RequiredFieldValidator ID="RequiredFieldValidator1" runat="server"
            ErrorMessage="*Required field!" ControlToValidate="txtRequiredData"
            ValidationGroup="FirstGroup">
        </asp:RequiredFieldValidator>
        <asp:Button ID="bntValidateRequired" runat="server"
            OnClick="bntValidateRequired_Click"
            Text="Validate" ValidationGroup="FirstGroup" />
    </asp:Panel>

    <asp:Panel ID="Panel2" runat="server" Height="119px" Width="295px">
        <asp:TextBox ID="txtSSN" runat="server"
            ValidationGroup="SecondGroup">
        </asp:TextBox>
        <asp:RegularExpressionValidator ID="RegularExpressionValidator1"
            runat="server" ControlToValidate="txtSSN"
            ErrorMessage="*Need SSN" ValidationExpression="\d{3}-\d{2}-\d{4}"
            ValidationGroup="SecondGroup">
        </asp:RegularExpressionValidator>&nbsp;
        <asp:Button ID="btnValidateSSN" runat="server"
            OnClick="btnValidateSSN_Click" Text="Validate" />
    </asp:Panel>

```

```
    ValidationGroup="SecondGroup" />
</asp:Panel>

</form>
```

Now, right-click this page's designer and select the View In Browser menu option to verify each panel's widgets operate in a mutually exclusive manner.

■ **Source Code** The ValidatorCtrls website is included under the Chapter 33 subdirectory.

Working with Themes

At this point, you have had the chance to work with numerous ASP.NET web controls. As you have seen, each control exposes a set of properties (many of which are inherited by `System.Web.UI.WebControls.WebControl`) that allow you to establish a given UI look and feel (background color, font size, border style, and whatnot). Of course, on a multipaged website, it is quite common for the site as a whole to define a common look and feel for various types of widgets. For example, all `TextBoxes` might be configured to support a given font, all `Buttons` have a custom image, and all `Calendars` have a light blue border.

Obviously, it would be very labor intensive (and error prone) to establish the *same* property settings for *every* widget on *every* page within your website. Even if you were able to manually update the properties of each UI widget on each page, imagine how painful it would be when you now need to change the background color for each `TextBox` yet again. Clearly, there must be a better way to apply sitewide UI settings.

One approach to simplifying the application of a common UI look and feel is to define *style sheets*. If you have a background in web development, you are aware that style sheets define a common set of UI-centric settings that are applied on the browser. As you would hope, ASP.NET web controls can be assigned a given style by assigning the `CssStyle` property.

However, ASP.NET ships with a complementary technology to define a common UI termed *themes*. Unlike a style sheet, themes are applied on the web server (rather than the browser) and can be done so programmatically or declaratively. Given that a theme is applied on the web server, it has access to all the server-side resources on the website. Furthermore, themes are defined by authoring the same markup you would find within any *.aspx file (as you may agree, the syntax of a style sheet is a bit on the terse side).

Recall from Chapter 32 that ASP.NET web applications may define any number of special subdirectories, one of which is `App_Themes`. This single subdirectory may be further partitioned with additional subdirectories, each of which represents a possible theme on your site. For example, consider Figure 33-22, which illustrates a single `App_Themes` folder containing three subdirectories, each of which has a set of files that make up the theme itself.




Figure 33-22. A single App_Theme folder may define numerous themes

Understanding *.skin Files

The one file that every theme subdirectory is sure to have is a *.skin file. These files define the look and feel for various web controls. To illustrate, create a new website named FunWithThemes. Next, insert a new *.skin file (using the Website ▶ Add New Item menu option) named BasicGreen.skin, as shown in Figure 33-23.




Figure 33-23. Inserting *.skin files

Visual Studio 2010 will prompt you to confirm this file can be added into an App_Themes folder (which is exactly what we want). If you were now to look in your Solution Explorer, you would

indeed find your App_Themes folder has a subfolder named BasicGreen containing your new BasicGreen.skin file.

A *.skin file is where you are able to define the look and feel for various widgets using ASP.NET control declaration syntax. Sadly, the IDE does not provide designer support for *.skin files. One way to reduce the amount of typing time is to insert a temporary *.aspx file into your program (temp.aspx, for example) that can be used to build up the UI of the widgets using the Visual Studio 2010 page designer.

The resulting markup can then be copied and pasted into your *.skin file. When you do so, however, you *must* delete the ID attribute for each web control! This should make sense, given that we are not trying to define a UI look and feel for a particular Button (for example) but *all* Buttons.

This being said, here is the markup for BasicGreen.skin that defines a default look and feel for the Button, TextBox, and Calendar types:

```
<asp:Button runat="server" BackColor="#80FF80"/>
<asp:TextBox runat="server" BackColor="#80FF80"/>
<asp:Calendar runat="server" BackColor="#80FF80"/>
```

Notice that each widget still has the runat="server" attribute (which is mandatory), and none of the widgets have been assigned an ID attribute.

Now, let's define a second theme named CrazyOrange. Using the Solution Explorer, right-click your App_Themes folder and add a new theme named CrazyOrange. This will create a new subdirectory under your site's App_Themes folder.

Next, right-click the new CrazyOrange folder within the Solution Explorer and select Add New Item. From the resulting dialog box, add a new *.skin file. Update the CrazyOrange.skin file to define a unique UI look and feel for the same web controls. For example:

```
<asp:Button runat="server" BackColor="#FF8000"/>
<asp:TextBox runat="server" BackColor="#FF8000"/>
<asp:Calendar BackColor="White" BorderColor="Black"
  BorderStyle="Solid" CellSpacing="1"
  Font-Names="Verdana" Font-Size="9pt" ForeColor="Black" Height="250px"
  NextPrevFormat="ShortMonth" Width="330px" runat="server">
  <SelectedDayStyle BackColor="#333399" ForeColor="White" />
  <OtherMonthDayStyle ForeColor="#999999" />
  <TodayDayStyle BackColor="#999999" ForeColor="White" />
  <DayStyle BackColor="#CCCCCC" />
  <NextPrevStyle Font-Bold="True" Font-Size="8pt" ForeColor="White" />
  <DayHeaderStyle Font-Bold="True" Font-Size="8pt"
    ForeColor="#333333" Height="8pt" />
  <TitleStyle BackColor="#333399" BorderStyle="Solid"
    Font-Bold="True" Font-Size="12pt"
    ForeColor="White" Height="12pt" />
</asp:Calendar>
```

At this point, your Solution Explorer should like Figure 33-24.




Figure 33-24. A single website with multiple themes

Now that your site has a few themes defined, the next logical question is how to apply them to your pages? As you might guess, there are many ways to do so.

Note To be sure, these example themes are quite bland by design (in order to reduce the amount of markup on the printed page). Feel free to spruce things up to your liking.

Applying Sitewide Themes

If you wish to make sure that every page in your site adheres to the same theme, the simplest way to do so is to update your `web.config` file. Open your current `web.config` file and define a `<pages>` element within the scope of your `<system.web>` root element. If you add a theme attribute to the `<pages>` element, this will ensure that every page in your website is assigned the selected theme (which is, of course, the name of one of the subdirectories under `App_Theme`). Here is the core update:

```
<configuration>
  <system.web>
    ...
    <pages theme="BasicGreen">
      </pages>
    </system.web>
  </configuration>
```

If you were to now place various Buttons, Calendars, and TextBoxes onto your `Default.aspx` file and run the application, you would find each widget has the UI of `BasicGreen`. If you were to update the theme attribute to `CrazyOrange` and run the page again, you would find the UI defined by this theme is used instead.

Applying Themes at the Page Level

It is also possible to assign themes on a page-by-page level. This can be helpful in a variety of circumstances. For example, perhaps your `web.config` file defines a sitewide theme (as described in the previous section); however, you wish to assign a different theme to a specific page. To do so, you can simply update the `<%@Page%>` directive. If you are using Visual Studio 2010 to do so, you will be happy to find that IntelliSense will display each defined theme within your `App_Theme` folder.

```
<%@ Page Language="C#" AutoEventWireup="true"
    CodeFile="Default.aspx.cs" Inherits="_Default" Theme ="CrazyOrange" %>
```

Because you assigned the `CrazyOrange` theme to this page, but the `Web.config` file specified the `BasicGreen` theme, all pages *but this page* will be rendered using `BasicGreen`.

The SkinID Property

Sometimes you wish to define a set of possible UI look and feel scenarios for a single widget. For example, assume you want to define two possible UIs for the `Button` type within the `CrazyOrange` theme. When you wish do so, you may differentiate each look and feel using the `SkinID` property of a control within the `*.skin` file:

```
<asp:Button runat="server" BackColor="#FF8000"/>
<asp:Button runat="server" SkinID = "BigFontButton"
    Font-Size="30pt" BackColor="#FF8000"/>
```

Now, if you have a page that makes use of the `CrazyOrange` theme, each `Button` will, by default, be assigned the unnamed `Button` skin. If you wish to have various buttons within the `*.aspx` file make use of the `BigFontButton` skin, simply specify the `SkinID` property within the markup:

```
<asp:Button ID="Button2" runat="server"
    SkinID="BigFontButton" Text="Button" /><br />
```

Assigning Themes Programmatically

Last but not least, it is possible to assign a theme in code. This can be helpful when you wish to provide a way for end users to select a theme for their current session. Of course, we have not yet showed you how to build stateful web applications, so the current theme selection will be forgotten between postbacks. In a production-level site, you may wish to store the user's current theme selection within a session variable, or persist the theme selection to a database.

To illustrate how to assign a theme programmatically, update the UI of your `Default.aspx` file with three new `Button` controls as shown in Figure 33-25. Once you have done so, handle the `Click` event for each `Button` type.




Figure 33-25. The updated UI of the themes example

Now be aware that you can only assign a theme programmatically during specific phases of your page's life cycle. Typically, this will be done within the `Page_PreInit` event. This being said, update your code file as follows:

```
partial class _Default : System.Web.UI.Page
{
    protected void btnNoTheme_Click(object sender, System.EventArgs e)
    {
        // Empty strings result in no theme being applied.
        Session["UserTheme"] = "";

        // Triggers the PreInit event again.
        Server.Transfer(Request.FilePath);
    }

    protected void btnGreenTheme_Click(object sender, System.EventArgs e)
    {
        Session["UserTheme"] = "BasicGreen";

        // Triggers the PreInit event again.
        Server.Transfer(Request.FilePath);
    }

    protected void btnOrangeTheme_Click(object sender, System.EventArgs e)
    {
        Session["UserTheme"] = "CrazyOrange";
    }
}
```

```

// Triggers the PreInit event again.
Server.Transfer(Request.FilePath);
}

protected void Page_PreInit(object sender, System.EventArgs e)
{
    try
    {
        Theme = Session["UserTheme"].ToString();
    }
    catch
    {
        Theme = "";
    }
}

```

Notice that we are storing the selected theme within a session variable (see Chapter 33 for details) named `UserTheme`, which is formally assigned within the `Page_PreInit()` event handler. Also note that when the user clicks a given Button, we programmatically force the `PreInit` event to fire by calling `Server.Transfer()` and requesting the current page once again. If you were to run this page, you would now find that you can establish your theme via various Button clicks.

■ Source Code The FunWithThemes web site is included under the Chapter 33 subdirectory.

Summary

This chapter examined how to make use of various ASP.NET web controls. We began by examining the role of the `Control` and `WebControl` base classes, and you learned how to dynamically interact with a panel's internal controls collection. Along the way, you were exposed to the new site navigation model (`*.sitemap` files and the `SiteMapDataSource` component), the new data binding engine (via the `SqlDataSource` component and the `GridView` control), and various validation -controls.

The latter half of this chapter examined the role of master pages and themes. Recall that master pages can be used to define a common layout for a set of pages on your site. Also recall that the `*.master` file defines any number of content placeholders to which content pages plug in their custom UI content. Finally, as you were shown, the ASP.NET theme engine allows you to declaratively or programmatically apply a common UI look and feel to your widgets on the web server.



ASP.NET State Management Techniques

The previous two chapters concentrated on the composition and behavior of ASP.NET pages and the web controls they contain. This chapter builds on that information by examining the role of the Global.asax file and the underlying `HttpApplication` type. As you will see, the functionality of `HttpApplication` allows you to intercept numerous events that enable you to treat your web application as a cohesive unit, rather than a set of stand-alone *.aspx files driven by a master page.

In addition to investigating the `HttpApplication` type, this chapter also addresses the all-important topic of state management. Here you will learn the role of view state, session and application variables (including the application cache), cookie data, and the ASP.NET Profile API.

The Issue of State

At the beginning of the Chapter 32, I pointed out that HTTP on the Web results in a *stateless* wire protocol. This very fact makes web development extremely different from the process of building an executable assembly. For example, when you are building a Windows Forms application, you can rest assured that any member variables defined in the Form-derived class will typically exist in memory until the user explicitly shuts down the executable:

```
public partial class MainWindow : Form
{
    // State data!
    private string userFavoriteCar = "Yugo";
}
```

In the World Wide Web environment, however, you are not afforded the same luxurious assumption. To prove the point, create a new Empty Web Site project named SimpleStateExample and insert a new Web Form. In the code-behind file of your *.aspx file, define a page-level string variable named `userFavoriteCar`:

```
public partial class _Default : System.Web.UI.Page
{
    // State data?
    private string userFavoriteCar = "Yugo";
```

```
protected void Page_Load(object sender, EventArgs e)
{
}
}
```

Next, construct the web UI as shown in Figure 34-1.




Figure 34-1. The UI for the simple state page

The server-side Click event handler for the Set button (named `btnSetCar`) allows the user to assign the string member variable to the value within the TextBox (named `txtFavCar`):

```
protected void btnSetCar_Click(object sender, EventArgs e)
{
    // Store fave car in member variable.
    userFavoriteCar = txtFavCar.Text;
}
```

The Click event handler for the Get button (`btnGetCar`) displays the current value of the member variable within the page's Label widget (`lblFavCar`):

```
protected void btnGetCar_Click(object sender, EventArgs e)
{
    // Show value of member variable.
    lblFavCar.Text = userFavoriteCar;
}
```

Now, if you were building a Windows Forms application, you would be right to assume that once the user sets the initial value, it would be remembered throughout the life of the desktop application. Sadly, when you run this web application, you find that each time you post back to the web server (by clicking either button), the value of the `userFavoriteCar` string variable is set back to the initial value of “Yugo”; therefore, the Label’s text is continuously fixed.

Again, given that HTTP has no clue how to automatically remember data once the HTTP response has been sent, it stands to reason that the `Page` object is destroyed almost instantly. As a result, when the client posts back to the `*.aspx` file, a new `Page` object is constructed that will reset any page-level member variables. This is clearly a major issue. Imagine how useless online shopping would be if every

time you posted back to the web server, any and all information you previously entered (such as the items you wished to purchase) were discarded. When you wish to remember information regarding the users who are logged on to your site, you need to make use of various state management techniques.

■ **Note** This issue is in no way limited to ASP.NET. Java web applications, CGI applications, classic ASP applications, and PHP applications all must contend with the thorny issue of state management.

To remember the value of the `userFavoriteCar` string type between postbacks, one approach is to store the value of this string type in a *session variable*. We will examine the details of session state in the pages that follow. For the sake of completion, however, here are the necessary updates for the current page (note that you are no longer using the private string member variable, so feel free to comment out or remove the definition altogether):

```
public partial class _Default : System.Web.UI.Page
{
    // State data?
    // private string userFavoriteCar = "Yugo";

    protected void Page_Load(object sender, EventArgs e)
    {

    }

    protected void btnSetCar_Click(object sender, EventArgs e)
    {
        // Store value to be remembered in session variable.
        Session["UserFavCar"] = txtFavCar.Text;
    }

    protected void btnGetCar_Click(object sender, EventArgs e)
    {
        // Get session variable value.
        lblFavCar.Text = (string)Session["UserFavCar"];
    }
}
```

If you now run the application, the value of your favorite automobile will be preserved across postbacks, thanks to the `HttpSessionState` object manipulated indirectly by the inherited `Session` property.

■ **Source Code** The SimpleStateExample web site is included under the Chapter 34 subdirectory.

ASP.NET State Management Techniques

ASP.NET provides several mechanisms you can use to maintain stateful information in your web applications. Specifically, you can:

- Use ASP.NET view state.
- Use ASP.NET control state.
- Define application-level data.
- Use the cache object.
- Define session-level data.
- Define cookie data.

In addition to these techniques, if you want to persist user data in a permanent manner, ASP.NET provides an out-of-the-box Profile API. We'll examine the details of each approach in turn, beginning with the topic of ASP.NET view state.

Understanding the Role of ASP.NET View State

The term *view state* has been thrown out a few times here and in the previous two chapters without a formal definition, so let's demystify this term once and for all. Under classic (COM-based) ASP, web developers were required to manually repopulate the values of the incoming form widgets during the process of constructing the outgoing HTTP response. For example, if the incoming HTTP request contained five text boxes with specific values, the *.asp file required script code to extract the current values (via the Form or QueryString collections of the Request object) and manually place them back into the HTTP response stream. Needless to say, this was a drag. If the developer failed to do so, the caller was presented with a set of five empty text boxes!

Under ASP.NET, we no longer have to manually scrape out and repopulate the values in the HTML widgets because the ASP.NET runtime automatically embeds a hidden form field (named `_VIEWSTATE`), which will flow between the browser and a specific page. The data assigned to this field is a Base64-encoded string that contains a set of name/value pairs representing the values of each GUI widget on the page at hand.

The `System.Web.UI.Page` base class's `Init` event handler is the entity in charge of reading the incoming values in the `_VIEWSTATE` field to populate the appropriate member variables in the derived class. (This is why it is risky at best to access the state of a web widget within the scope of a page's `Init` event handler.)

Also, just before the outgoing response is emitted back to the requesting browser, the `_VIEWSTATE` data is used to repopulate the form's widgets. Clearly, the best thing about this aspect of ASP.NET is that it just happens without any work on your part. Of course, you are always able to interact with, alter, or disable this default functionality if you so choose. To understand how to do this, let's see a concrete view state example.

Demonstrating View State

First, create a new Empty Web Site called ViewStateApp and insert a new Web Form. On your .aspx page, add a single ASP.NET ListBox web control named myListBox and a single Button control named btnPostback. Handle the Click event for the Button to provide a way for the user to post back to the web server:

```
public partial class _Default : System.Web.UI.Page
{
    protected void Page_Load(object sender, EventArgs e)
    {
    }

    protected void btnPostback_Click(object sender, EventArgs e)
    {
        // No-op. This is just here to allow a postback.
    }
}
```

Now, using the Visual Studio 2010 Properties window, access the Items property and add four ListItems to the ListBox using the associated dialog box. The resulting markup looks like this:

```
<asp:ListBox ID="myListBox" runat="server">
    <asp:ListItem>Item One</asp:ListItem>
    <asp:ListItem>Item Two</asp:ListItem>
    <asp:ListItem>Item Three</asp:ListItem>
    <asp:ListItem>Item Four</asp:ListItem>
</asp:ListBox>
```

Note that you are hard-coding the items in the ListBox directly within the *.aspx file. As you already know, all <asp:> definitions in an HTML form will automatically render back their HTML representation before the final HTTP response (provided they have the runat="server" attribute).

The <%@Page%> directive has an optional attribute called EnableViewState that by default is set to true. To disable this behavior, simply update the <%@Page%> directive as follows:

```
<%@ Page Language="C#" AutoEventWireup="true"
    CodeFile="Default.aspx.cs" Inherits="_Default"
    EnableViewState = "false" %>
```

So, what exactly does it mean to disable view state? The answer is, it depends. Given the previous definition of the term, you would think that if you disable view state for an *.aspx file, the values in your ListBox would not be remembered between postbacks to the web server. However, if you were to run this application as is, you might be surprised to find that the information in the ListBox is retained regardless of how many times you post back to the page.

In fact, if you examine the source HTML returned to the browser (by right-clicking the page within the browser and selecting View Source), you may be further surprised to see that the hidden __VIEWSTATE field is *still present*:

```
<input type="hidden" name="__VIEWSTATE" id="__VIEWSTATE"
    value="/wEPDwUKLTM4MTM2MDM4NGRkqGC6gjEV25JnddkJiRmoIc10SIA=" />
```

However, assume that your `ListBox` is dynamically populated within the code-behind file rather than within the HTML `<form>` definition. First, remove the `<asp:ListItem>` declarations from the current *.aspx file:

```
<asp:ListBox ID="myListBox" runat="server">
</asp:ListBox>
```

Next, fill the list items within the Load event handler in your code-behind file:

```
protected void Page_Load(object sender, EventArgs e)
{
    if (!IsPostBack)
    {
        // Fill ListBox dynamically!
        myListBox.Items.Add("Item One");
        myListBox.Items.Add("Item Two");
        myListBox.Items.Add("Item Three");
        myListBox.Items.Add("Item Four");
    }
}
```

If you post to this updated page, you'll find that the first time the browser requests the page, the values in the `ListBox` are present and accounted for. However, on postback, the `ListBox` is suddenly empty. The first rule of ASP.NET view state is that its effect is only realized when you have widgets whose values are dynamically generated through code. If you hard-code values within the *.aspx file's `<form>` tags, the state of these items is always remembered across postbacks (even when you set `EnableViewState` to `false` for a given page).

If the idea of disabling view state for the entire *.aspx file seems a bit too aggressive, know that every descendent of the `System.Web.UI.Control` base class inherits the `EnableViewState` property, which makes it very simple to disable view state on a control-by-control basis:

```
<asp:GridView id="myHugeDynamicallyFilledGridOfData" runat="server"
    EnableViewState="false">
</asp:GridView>
```

Note Under .NET 4.0, large view state data values are automatically compressed, to help reduce the size of this hidden form field.

Adding Custom View State Data

In addition to the `EnableViewState` property, the `System.Web.UI.Control` base class provides a protected property named `ViewState`. Under the hood, this property provides access to a `System.Web.UI.StateBag` type, which represents all the data contained within the `__VIEWSTATE` field. Using the indexer of the `StateBag` type, you can embed custom information within the hidden `__VIEWSTATE` form field using a set of name/value pairs. Here's a simple example:

```
protected void btnAddToVS_Click(object sender, EventArgs e)
{
    ViewState["CustomViewStateItem"] = "Some user data";
    lblVValue.Text = (string)ViewState["CustomViewStateItem"];
}
```

Because the `System.Web.UI.StateBag` type has been designed to operate on `System.Object` types, when you wish to access the value of a given key, you should explicitly cast it into the correct underlying data type (in this case, a `System.String`). Be aware, however, that values placed within the `_VIEWSTATE` field cannot literally be any object. Specifically, the only valid types are `Strings`, `Integers`, `Booleans`, `ArrayLists`, `Hashtables`, or an array of these types.

So, given that .aspx pages can insert custom bits of information into the `_VIEWSTATE` string, the next logical question is when you would want to do so. Most of the time, custom view-state data is best suited for user-specific preferences. For example, you may establish view-state data that specifies how a user wishes to view the UI of a `GridView` (such as a sort order). However, view-state data is not well-suited for full-blown user data, such as items in a shopping cart or cached `DataSets`. When you need to store this sort of complex information, you must work with session or application data. Before we get to that point, though, you need to understand the role of the `Global.asax` file.

Source Code The `ViewStateApp` web site is included under the Chapter 34 subdirectory.

The Role of the `Global.asax` File

At this point, an ASP.NET application may seem little more than a set of .aspx files and their respective web controls. While you could build a web application by simply linking a set of related web pages, you will most likely need a way to interact with the web application as a whole. To this end, an ASP.NET application may choose to include an optional `Global.asax` file via the `Web Site > Add New Item` menu option, as shown in Figure 34-2 (notice you are selecting the Global Application Class icon).




Figure 34-2. The Global.asax file

Simply put, Global.asax is just about as close to a traditional double-clickable *.exe as you can get in the world of ASP.NET, meaning this type represents the runtime behavior of the web site itself. When you insert a Global.asax file into a web project, you'll see it's little more than a <script> block containing a set of event handlers:

```
<%@ Application Language="C#" %>

<script runat="server">
    void Application_Start(object sender, EventArgs e)
    {
        // Code that runs on application startup.
    }

    void Application_End(object sender, EventArgs e)
    {
        // Code that runs on application shutdown.
    }

    void Application_Error(object sender, EventArgs e)
    {
        // Code that runs when an unhandled error occurs.
    }

    void Session_Start(object sender, EventArgs e)
    {
        // Code that runs when a new session is started.
    }
}
```

```

void Session_End(object sender, EventArgs e)
{
    // Code that runs when a session ends.
    // Note: The Session_End event is raised only when the sessionstate mode
    // is set to InProc in the Web.config file. If session mode is set to
    // StateServer or SQLServer, the event is not raised.
}
</script>

```

Looks can be deceiving, however. At runtime, the code within this `<script>` block is assembled into a class type deriving from `System.Web.HttpApplication` (if you have a background in ASP.NET 1.x, you may recall that the `Global.asax` code-behind file literally did define a class deriving from `HttpApplication`).

As mentioned, the members defined inside `Global.asax` are event handlers that allow you to interact with application-level (and session-level) events. Table 34-1 documents the role of each member.

Table 34-1. Core Types of the `System.Web` Namespace

Event Handler	Meaning in Life
<code>Application_Start()</code>	This event handler is called the very first time the web application is launched. Thus, this event will fire exactly once over the lifetime of a web application. It is an ideal place to define application-level data used throughout your web application.
<code>Application_End()</code>	This event handler is called when the application is shutting down. This will occur when the last user times out or if you manually shut down the application via IIS.
<code>Session_Start()</code>	This event handler is fired when a new user reaches your application. Here you can establish any user-specific data points you want to preserve across postbacks.
<code>Session_End()</code>	This event handler is fired when a user's session has terminated (typically through a predefined timeout).
<code>Application_Error()</code>	This is a global error handler that will be called when an unhandled exception is thrown by the web application.

The Global Last-Chance Exception Event Handler

First, let me point out the role of the `Application_Error()` event handler. Recall that a specific page may handle the `Error` event to process any unhandled exception that occurred within the scope of the page itself. In a similar light, the `Application_Error()` event handler is the final place to handle an exception that was not handled by a given page. As with the page-level `Error` event, you are able to access the specific `System.Exception` using the inherited `Server` property:

```

void Application_Error(object sender, EventArgs e)
{
    // Obtain the unhandled error.
    Exception ex = Server.GetLastError();

    // Process error here...

    // Clear error when finished.
    Server.ClearError();
}

```

Given that the `Application_Error()` event handler is the last-chance exception handler for your web application, it is quite common to implement this method in such a way that the user is transferred to a predefined error page on the server. Other common duties may include sending an e-mail to the web administrator or writing to an external error log.

The `HttpApplication` Base Class

As mentioned, the `Global.asax` script is dynamically generated as a class deriving from the `System.Web.HttpApplication` base class, which supplies some of the same sort of functionality as the `System.Web.UI.Page` type (without a visible user interface). Table 34-2 documents the key members of interest.

Table 34-2. Key Members Defined by the `System.Web.HttpApplication` Type

Property	Meaning in Life
<code>Application</code>	This property allows you to interact with application-level data, using the exposed <code>HttpApplicationState</code> type.
<code>Request</code>	This property allows you to interact with the incoming HTTP request, using the underlying <code>HttpRequest</code> object.
<code>Response</code>	This property allows you to interact with the incoming HTTP response, using the underlying <code>HttpResponse</code> object.
<code>Server</code>	This property gets the intrinsic server object for the current request, using the underlying <code>HttpServerUtility</code> object.
<code>Session</code>	This property allows you to interact with session-level data, using the underlying <code>HttpSessionState</code> object.

Again, given that the `Global.asax` file does not explicitly document that `HttpApplication` is the underlying base class, it is important to remember that all of the rules of the “is-a” relationship do indeed apply. For example, if you were to apply the dot operator to the `base` keyword (or if you prefer, the `this` keyword) within any of the members in `Global.asax`, you would find you have immediate access to all members of the chain of inheritance, as you see in Figure 34-3.




Figure 34-3. Remember that `HttpApplication` is the parent of the type lurking within `Global.asax`

Understanding the Application/Session Distinction

Under ASP.NET, application state is maintained by an instance of the `HttpApplicationState` type. This class enables you to share global information across all users (and all pages) using your ASP.NET application. Not only can application data be shared by all users on your site, but also if the value of an application-level data point changes, the new value is seen by all users on their next postback.

On the other hand, session state is used to remember information for a specific user (again, such as items in a shopping cart). Physically, a user's session state is represented by the `HttpSessionState` class type. When a new user reaches an ASP.NET web application, the runtime will automatically assign that user a new session ID, which by default will expire after 20 minutes of inactivity. Thus, if 20,000 users are logged on to your site, you have 20,000 distinct `HttpSessionState` objects, each of which is automatically assigned a unique session ID. The relationship between a web application and web sessions is shown in Figure 34-4.

If you have ever worked with classic ASP, you might recall that application- and session-state data is represented using distinct COM objects (e.g., `Application` and `Session`). Under ASP.NET, Page-derived types as well as the `HttpApplication` type use identically named properties (i.e., `Application` and `Session`), which expose the underlying `HttpApplicationState` and `HttpSessionState` types.




Figure 34-4. The application/session state distinction

Maintaining Application-Level State Data

The `HttpApplicationState` type enables developers to share global information across multiple users in an ASP.NET application. Table 34-3 describes some core members of this type.

Table 34-3. Members of the `HttpApplicationState` Type

Members	Meaning in Life
<code>Add()</code>	This method allows you to add a new name/value pair to the <code>HttpApplicationState</code> object. Do note that this method is typically <i>not</i> used in favor of the indexer of the <code>HttpApplicationState</code> class.
<code>AllKeys</code>	This property returns an array of <code>string</code> objects that represent all the names in the <code>HttpApplicationState</code> type.
<code>Clear()</code>	This method deletes all items in the <code>HttpApplicationState</code> object. This is functionally equivalent to the <code>RemoveAll()</code> method.
<code>Count</code>	This property gets the number of item objects in the <code>HttpApplicationState</code> type.
<code>Lock(), UnLock()</code>	These two methods are used when you wish to alter a set of application variables in a thread-safe manner.
<code>RemoveAll(), Remove(), RemoveAt()</code>	These methods remove a specific item (by string name) within the <code>HttpApplicationState</code> object. <code>RemoveAt()</code> removes the item via a numerical indexer.

To illustrate working with application state, create a new Empty Web Site project named AppState (and insert a new Web Form). Next, insert a new Global.asax file. When you create data members that can be shared among all users, you need to establish a set of name/value pairs. In most cases, the most natural place to do so is within the Application_Start() event handler in Global.asax.cs, for example:

```
void Application_Start(Object sender, EventArgs e)
{
    // Set up some application variables.
    Application["SalesPersonOfTheMonth"] = "Chucky";
    Application["CurrentCarOnSale"] = "Colt";
    Application["MostPopularColorOnLot"] = "Black";
}
```

During the lifetime of your web application (which is to say, until the web application is manually shut down or until the final user times out), any user on any page may access these values as necessary. Assume you have a page that will display the current discount car within a Label via a button Click event handler:

```
protected void btnShowCarOnSale_Click(object sender, EventArgs arg)
{
    lblCurrCarOnSale.Text = string.Format("Sale on {0}'s today!",
        (string)Application["CurrentCarOnSale"]);
}
```

As with the ViewState property, notice how you should cast the value returned from the `HttpApplicationState` object into the correct underlying type because the `Application` property operates on general `System.Object` types.

Now, given that the `Application` property can hold any type, it should stand to reason that you can place custom types (or any .NET object) within your site's application state. Assume you'd rather maintain the three current application variables within a strongly typed class named `CarLotInfo`:

```
public class CarLotInfo
{
    public CarLotInfo(string s, string c, string m)
    {
        salesPersonOfTheMonth = s;
        currentCarOnSale = c;
        mostPopularColorOnLot = m;
    }

    // Public for easy access, could also make use of automatic
    // property syntax.
    public string salesPersonOfTheMonth;
    public string currentCarOnSale;
    public string mostPopularColorOnLot;
}
```

With this helper class in place, you could modify the `Application_Start()` event handler as follows:

```
void Application_Start(Object sender, EventArgs e)
{
```

```

// Place a custom object in the application data sector.
Application["CarSiteInfo"] =
    new CarLotInfo("Chucky", "Colt", "Black");
}

```

and then access the information using the public field data within a server-side Click event handler for a Button control named btnShowAppVariables:

```

protected void btnShowAppVariables_Click(object sender, EventArgs e)
{
    CarLotInfo appVars =
        ((CarLotInfo)Application["CarSiteInfo"]);
    string appState =
        string.Format("<li>Car on sale: {0}</li>",
        appVars.currentCarOnSale);
    appState +=
        string.Format("<li>Most popular color: {0}</li>",
        appVars.mostPopularColorOnLot);
    appState +=
        string.Format("<li>Big shot SalesPerson: {0}</li>",
        appVars.salesPersonOfTheMonth);
    lblAppVariables.Text = appState;
}

```

Given that the current car-on-sale data is now exposed from a custom class type, your btnShowCarOnSale Click event handler would also need to be updated, like so:

```

protected void btnShowCarOnSale_Click1(object sender, EventArgs e)
{
    lblCurrCarOnSale.Text = String.Format("Sale on {0}'s today!",
        ((CarLotInfo)Application["CarSiteInfo"]).currentCarOnSale);
}

```

Modifying Application Data

You may programmatically update or delete any or all application-wide data items using members of the `HttpApplicationState` type during the execution of your web application. For example, to delete a specific item, simply call the `Remove()` method. If you wish to destroy all application-level data, call `RemoveAll()`:

```

private void CleanAppData()
{
    // Remove a single item via string name.
    Application.Remove("SomeItemIDontNeed");

    // Destroy all application data!
    Application.RemoveAll();
}

```

If you want to change the value of an existing application-level data item, you need only make a new assignment to the data item in question. Assume your page now has a Button that allows your user to change the current hotshot salesperson by reading in a value from a TextBox named txtNewSP. The Click event handler is as you'd expect:

```
protected void btnSetNewSP_Click(object sender, EventArgs e)
{
    // Set the new Salesperson.
    ((CarLotInfo)Application["CarSiteInfo"]).salesPersonOfTheMonth
        = txtNewSP.Text;
}
```

If you run the web application, you'll find that the application-level data item has been updated. Furthermore, given that application variables are accessible by any user on any page in the Web application, if you launched three or four instances of your web browser, you'd find that if one instance changes the current hotshot salesperson, each of the other browsers displays the new value on postback. Figure 34-5 shows some possible output.




Figure 34-5. Displaying application data

Understand that if you have a situation where a set of application-level variables must be updated as a unit, you risk the possibility of data corruption (since it is technically possible that an application-level data point may be changed while another user is attempting to access it!). You could take the long road and manually lock down the logic using threading primitives of the System.Threading namespace, but the `HttpApplicationState` type has two methods, `Lock()` and `Unlock()`, that automatically ensure thread safety:

```
// Safely access related application data.
Application.Lock();
Application["SalesPersonOfTheMonth"] = "Maxine";
```

```
Application["CurrentBonusedEmployee"] = Application["SalesPersonOfTheMonth"];
Application.UnLock();
```

Handling Web Application Shutdown

The `HttpApplicationState` type is designed to maintain the values of the items it contains until one of two situations occurs: the last user on your site times out (or manually logs out) or someone manually shuts down the web site via IIS. In either case, the `Application_End()` method of the `HttpApplication`-derived type will automatically be called. Within this event handler, you are able to perform whatever sort of cleanup is necessary:

```
void Application_End(Object sender, EventArgs e)
{
    // Write current application variables
    // to a database or whatever else you need to do...
}
```

Source Code The AppState web site is included under the Chapter 34 subdirectory.

Working with the Application Cache

ASP.NET provides a second and more flexible way to handle application-wide data. As you recall, the values within the `HttpApplicationState` object remain in memory as long as your web application is alive and kicking. Sometimes, however, you may want to maintain a piece of application data only for a specific period of time. For example, you may wish to obtain an ADO.NET `DataSet` that is valid for only five minutes. After that time, you may want to obtain a fresh `DataSet` to account for possible database updates. While it's technically possible to build this infrastructure using `HttpApplicationState` and some sort of handcrafted monitor, the ASP.NET application cache greatly simplifies your task.

As its name suggests, the `ASP.NET System.Web.Caching.Cache` object (which is accessible via the `Context.Cache` property) allows you to define objects that are accessible by all users from all pages for a fixed amount of time. In its simplest form, interacting with the cache looks identical to interacting with the `HttpApplicationState` type:

```
// Add an item to the cache.
// This item will *not* expire.
Context.Cache["SomeStringItem"] = "This is the string item";

// Get item from the cache.
string s = (string)Context.Cache["SomeStringItem"];
```

Note If you wish to access the cache from within Global.asax, you need to use the Context property. However, if you are within the scope of a System.Web.UI.Page-derived type, you can access the Cache object directly via the page's Cache property.

The System.Web.Caching.Cache class defines only a small number of members beyond the type's indexer. You can use the Add() method to insert a new item into the cache that is not currently defined (if the specified item is already present, Add() effectively does nothing). The Insert() method will also place a member into the cache. If the item is currently defined, however, Insert() will replace the current item with the new object. Since this is generally the behavior you'll desire, I'll focus on the Insert() method exclusively.

Fun with Data Caching

Let's see an example. To begin, create a new Empty Web Site named CacheState and insert a Web Form and a Global.asax file. Like an application-level data item maintained by the `HttpApplicationState` type, the cache may hold any `System.Object`-derived type and is often populated within the `Application_Start()` event handler. For this example, the goal is to automatically update the contents of a `DataSet` every 15 seconds. The `DataSet` in question will contain the current set of records from the `Inventory` table of the AutoLot database created during our discussion of ADO.NET.

Given these design notes, set a reference to `AutoLotDAL.dll` (see Chapter 21) and update your `Global.asax` like so (code analysis to follow):

```
<%@ Application Language="C#" %>
<%@ Import Namespace = "AutoLotConnectedLayer" %>
<%@ Import Namespace = "System.Data" %>

<script runat="server">
    // Define a static-level Cache member variable.
    static Cache theCache;

    void Application_Start(Object sender, EventArgs e)
    {
        // First assign the static 'theCache' variable.
        theCache = Context.Cache;

        // When the application starts up,
        // read the current records in the
        // Inventory table of the AutoLot DB.
        InventoryDAL dal = new InventoryDAL();
        dal.OpenConnection(@"Data Source=(local)\SQLEXPRESS;" +
            "Initial Catalog=AutoLot;Integrated Security=True");
        DataTable theCars = dal.GetAllInventory();
        dal.CloseConnection();

        // Now store DataTable in the cache.
        theCache.Insert("AppDataTable",
```

```

theCars,
null,
DateTime.Now.AddSeconds(15),
Cache.NoSlidingExpiration,
CacheItemPriority.Default,
new CacheItemRemovedCallback(UpdateCarInventory));
}

// The target for the CacheItemRemovedCallback delegate.
static void UpdateCarInventory(string key, object item,
    CacheItemRemovedReason reason)
{
    InventoryDAL dal = new InventoryDAL();
    dal.OpenConnection(@"Data Source=(local)\SQLEXPRESS;" +
        "Initial Catalog=AutoLot;Integrated Security=True");
    DataTable theCars = dal.GetAllInventory();
    dal.CloseConnection();

    // Now store in the cache.
    theCache.Insert("AppDataTable",
        theCars,
        null,
        DateTime.Now.AddSeconds(15),
        Cache.NoSlidingExpiration,
        CacheItemPriority.Default,
        new CacheItemRemovedCallback(UpdateCarInventory));
}
...
</script>

```

First, notice we've defined a static Cache member variable. The reason is that you've defined two static members that need to access the Cache object. Recall that static methods do not have access to inherited members, so you can't use the Context property!

Inside the Application_Start() event handler, you fill a DataTable and insert it into the application cache. As you would guess, the Context.Cache.Insert() method has been overloaded a number of times. Here, you supply a value for each possible parameter. Consider the following commented call to Insert():

```

theCache.Insert("AppDataTable",      // Name used to identify item in the cache.
    theCars,                      // Object to put in the cache.
    null,                         // Any dependencies for this object?
    DateTime.Now.AddSeconds(15),   // Absolute timeout value.
    Cache.NoSlidingExpiration,    // Don't use sliding expiration (see below)
    CacheItemPriority.Default,    // Priority level of cache item.
    // Delegate for CacheItemRemove event.
    new CacheItemRemovedCallback(UpdateCarInventory));

```

The first two parameters simply make up the name/value pair of the item. The third parameter allows you to define a CacheDependency object (which is null in this case, as the DataTable does not depend on anything).

The `DateTime.Now.AddSeconds(15)` parameter specifies an absolute expiration time. It means the cache item will definitely be evicted from the cache after 15 seconds. Absolute expiration is useful for data items that need to be constantly refreshed (such as a stock ticker).

The `Cache.NoSlidingExpiration` parameter specifies that the cache item doesn't use sliding expiration. Sliding expiration is a way of keeping an item in the cache for at least a certain amount of time. For example, if you set a sliding expiration of 60 seconds for a cache item, it will live in the cache for at least 60 seconds. If any web page accesses the cache item within that time, the clock is reset and the cache item has a fresh 60 seconds to live. If no web page accesses the cache item in 60 seconds, the item is removed from the cache. Sliding expiration is useful for data that might be expensive (time-wise) to generate, but which might not be used very frequently by web pages.

Note that you can't specify both an absolute expiration and a sliding expiration for a given cache item. You set either an absolute expiration (and use `Cache.NoSlidingExpiration`) or a sliding expiration (and use `Cache.NoAbsoluteExpiration`).

Finally, as you can see from the signature of the `UpdateCarInventory()` method, the `CacheItemRemovedCallback` delegate can only call methods that match the following signature:

```
void UpdateCarInventory(string key, object item, CacheItemRemovedReason reason)
{
}
```

So, at this point, when the application starts up, the `DataTable` is populated and cached. Every 15 seconds, the `DataTable` is purged, updated, and reinserted into the cache. To see the effects of doing this, you need to create a page that allows for some degree of user interaction.

Modifying the *.aspx File

Update the UI of your initial *.aspx file as shown in Figure 34-6.



Figure 34-6. The cache application GUI

In the page's Load event handler, configure your GridView to display the current contents of the cached DataTable the first time the user posts to the page (be sure to import the System.Data and AutoLotConnectedLayer namespaces within your code file):

```
protected void Page_Load(object sender, EventArgs e)
{
    if (!IsPostBack)
    {
        carsGridView.DataSource = (DataTable)Cache["AppDataTable"];
        carsGridView.DataBind();
    }
}
```

In the Click event handler of the Add This Car button, insert the new record into the AutoLot database using the InventoryDAL type. Once the record has been inserted, call a helper function named RefreshGrid(), which will update the UI:

```
protected void btnAddCar_Click(object sender, EventArgs e)
{
    // Update the Inventory table
    // and call RefreshGrid().
```

```

InventoryDAL dal = new InventoryDAL();
dal.OpenConnection(@"Data Source=(local)\SQLEXPRESS;" +
    "Initial Catalog=AutoLot;Integrated Security=True");
dal.InsertAuto(int.Parse(txtCarID.Text), txtCarColor.Text,
    txtCarMake.Text, txtCarPetName.Text);
dal.CloseConnection();
RefreshGrid();
}

private void RefreshGrid()
{
    InventoryDAL dal = new InventoryDAL();
    dal.OpenConnection(@"Data Source=(local)\SQLEXPRESS;" +
        "Initial Catalog=AutoLot;Integrated Security=True");
    DataTable theCars = dal.GetAllInventory();
    dal.CloseConnection();

    carsGridView.DataSource = theCars;
    carsGridView.DataBind();
}

```

Now, to test the use of the cache, begin by running the current program (Ctrl+F5) and copy the URL appearing in the browser to your clipboard. Next, launch a second instance of your browser (using the Start button) and paste the URL into this instance. At this point you should have two instances of your web browser, both viewing Default.aspx and showing identical data.

In one instance of the browser, add a new automobile entry. Obviously, this results in an updated GridView viewable from the browser that initiated the postback.

In the second browser instance, click the Refresh button (F5). You should not see the new item, since the Page_Load event handler is reading directly from the cache. (If you did see the value, the 15 seconds had already expired. Either type faster or increase the amount of time the DataTable will remain in the cache.) Wait a few seconds and click the Refresh button from the second browser instance one more time. Now you should see the new item, given that the DataTable in the cache has expired and the CacheItemRemovedCallback delegate target method has automatically updated the cached DataTable.

As you can see, the major benefit of the Cache type is that you can ensure that when an item is removed, you have a chance to respond. In this example, you certainly could avoid using the Cache and simply have the Page_Load() event handler always read directly from the AutoLot database (but this would potentially be much slower than the caching approach). Nevertheless, the point should be clear: the cache allows you to automatically refresh data using the cache mechanism.

■ Source Code The CacheState web site is included under the Chapter 34 subdirectory.

Maintaining Session Data

So much for our examination of application-level and cached data. Next, let's check out the role of per-user data. As mentioned earlier, a *session* is little more than a given user's ongoing interaction with a web application, which is represented via a unique HttpSessionState object. To maintain stateful

information for a particular user, you can use the Session property in your web page class or in Global.asax. The classic example of the need to maintain per-user data is an online shopping cart. Again, if 10 people all log on to an online store, each individual will have a unique set of items that she (may) intend to purchase, and that data needs to be maintained.

When a new user joins to your web application, the .NET runtime automatically assigns the user a unique session ID, which is used to identify that user. Each session ID identifies a custom instance of the HttpSessionState type to hold on to user-specific data. Inserting or retrieving session data is syntactically identical to manipulating application data, for example:

```
// Add/retrieve session data for current user.
Session["DesiredCarColor"] = "Green";
string color = (string) Session["DesiredCarColor"];
```

In Global.asax, you can intercept the beginning and end of a session via the Session_Start() and Session_End() event handlers. Within Session_Start(), you can freely create any per-user data items, while Session_End() allows you to perform any work you may need to do when the user's session has terminated:

```
<%@ Application Language="C#" %>
...
void Session_Start(Object sender, EventArgs e)
{
    // New session! Prep if required.
}

void Session_End(Object sender, EventArgs e)
{
    // User logged off/timed out. Tear down if needed.
}
```

Like application state, session state may hold any System.Object-derived type, including your custom classes. For example, assume you have a new Empty Web Site project (named SessionState) that defines a class named UserShoppingCart:

```
public class UserShoppingCart
{
    public string desiredCar;
    public string desiredCarColor;
    public float downPayment;
    public bool isLeasing;
    public DateTime dateOfPickUp;

    public override string ToString()
    {
        return string.Format(
            "Car: {0}<br>Color: {1}<br>$ Down: {2}<br>Lease: {3}<br>Pick-up Date: {4}",
            desiredCar, desiredCarColor, downPayment, isLeasing,
            dateOfPickUp.ToString("MM/dd/yyyy"));
    }
}
```

Now, insert a `Global.asax` file. Within the `Session_Start()` event handler, you can now assign each user a new instance of the `UserShoppingCart` class:

```
void Session_Start(Object sender, EventArgs e)
{
    Session["UserShoppingCartInfo"]
        = new UserShoppingCart();
}
```

As the user traverses your web pages, you are able to pluck out the `UserShoppingCart` instance and fill the fields with user-specific data. For example, assume you have a simple `*.aspx` page that defines a set of input controls that correspond to each field of the `UserShoppingCart` type, a Button for setting the values, and two Labels that will be used to display the user's session ID and session information (see Figure 34-7).




Figure 34-7. The session application GUI

The server-side Click event handler for the Button control is straightforward (scrape out values from TextBoxes and display the shopping cart data on a Label control):

```

protected void btnSubmit_Click(object sender, EventArgs e)
{
    // Set current user prefs.
    UserShoppingCart cart =
        (UserShoppingCart)Session["UserShoppingCartInfo"];
    cart.dateOfPickUp = myCalendar.SelectedDate;
    cart.desiredCar = txtCarMake.Text;
    cart.desiredCarColor = txtCarColor.Text;
    cart.downPayment = float.Parse(txtDownPayment.Text);
    cart.isLeasing = chkIsLeasing.Checked;
    lblUserInfo.Text = cart.ToString();
    Session["UserShoppingCartInfo"] = cart;
}

```

Within `Session_End()`, you may wish to persist the fields of the `UserShoppingCart` to a database or whatnot (however, as you will see at the conclusion of this chapter, the ASP.NET Profile API will do so automatically). As well, you may wish to implement `Session_Error()` to trap any faulty input (or perhaps make use of various validation controls on the `Default.aspx` page to account for such user errors).

In any case, if you were to launch two or three instances of your browser of choice all posting to the same URL (via a copy/paste operation as you did for the data cache example), you would find that each user is able to build a custom shopping cart that maps to his unique instance of `HttpSessionState`.

Additional Members of HttpSessionState

The `HttpSessionState` class defines a number of other members of interest beyond the type indexer. First, the `SessionID` property will return the current user's unique ID. If you wish to view the automatically assigned session ID for this example, handle the `Load` event of your page as follows:

```

protected void Page_Load(object sender, EventArgs e)
{
    lblUserID.Text = string.Format("Here is your ID: {0}",
        Session.SessionID);
}

```

The `Remove()` and `RemoveAll()` methods may be used to clear items out of the user's instance of `HttpSessionState`:

```
Session.Remove("SomeItemWeDontNeedAnymore");
```

The `HttpSessionState` type also defines a set of members that control the expiration policy of the current session. Again, by default each user has 20 minutes of inactivity before the `HttpSessionState` object is destroyed. Thus, if a user enters your web application (and therefore obtains a unique session ID), but then does not return to the site within 20 minutes, the runtime assumes the user is no longer interested and destroys all session data for that user. You are free to change this default 20-minute expiration value on a user-by-user basis using the `Timeout` property. The most common place to do so is within the scope of your `Session_Start()` method:

```

void Session_Start(Object sender, EventArgs e)
{
    // Each user has 5 minutes of inactivity.
}

```

```
Session.Timeout = 5;
Session["UserShoppingCartInfo"]
    = new UserShoppingCart();
}
```

■ **Note** If you do not need to tweak each user's Timeout value, you can alter the 20-minute default for all users via the Timeout attribute of the `<sessionState>` element within the `Web.config` file (examined at the end of this chapter).

The benefit of the `Timeout` property is that you have the ability to assign specific timeout values separately for each user. For example, imagine you have created a web application that allows users to pay cash for a given membership level. You may say that Gold members should time out within one hour, while Wood members should get only 30 seconds. This possibility begs the question, how can you remember user-specific information (such as the current membership level) if users close the browser and come back at a later time? One possible answer is through the use of the `HttpCookie` type. (And speaking of cookies . . .)

■ **Source Code** The `SessionState` web site is included under the Chapter 34 subdirectory.

Understanding Cookies

The next state management technique we'll examine is the persisting of data within a *cookie*, which is often realized as a text file (or set of files) on the user's machine. When a user joins a given site, the browser checks to see whether the user's machine has a cookie file for the URL in question and, if so, appends this data to the HTTP request.

The receiving server-side web page can then read the cookie data to create a GUI based on the current user preferences. I'm sure you've noticed that when you visit certain of your favorite web sites, they somehow "just know" the sort of content you wish to see. The reason (in part) may have to do with a cookie stored on your computer that contains information relevant to a given web site.

■ **Note** The exact location of your cookie files will depend on which browser and operating system you happen to be using.

The contents of a given cookie file will obviously vary among URLs, but keep in mind that they are ultimately text files. Thus, cookies are a horrible choice for maintaining sensitive information about the current user (such as a credit card number, password, and the like). Even if you take the time to encrypt the data, a crafty hacker could decrypt the value and use it for evil purposes. In any case, cookies do play

a role in the development of web applications, so let's check out how ASP.NET handles this particular state management technique.

Creating Cookies

First of all, understand that ASP.NET cookies can be configured to be either persistent or temporary. A *persistent* cookie is typically regarded as the classic definition of cookie data, in that the set of name/value pairs is physically saved to the user's hard drive. A *temporary* cookie (also termed a *session cookie*) contains the same data as a persistent cookie, but the name/value pairs are never saved to the user's hard drive; rather, they exist *only* while the browser is open. Once the user shuts down the browser, all data contained in the session cookie is destroyed.

The `System.Web.HttpCookie` type is the class that represents the server side of the cookie data (persistent or temporary). When you wish to create a new cookie in your web page code, you access the `Response.Cookies` property. Once the new `HttpCookie` is inserted into the internal collection, the name/value pairs flow back to the browser within the HTTP header.

To check out cookie behavior firsthand, create a new Empty Web Site (named `CookieStateApp`) and create the UI of the first Web Form (which you will need to insert) displayed in Figure 34-8.




Figure 34-8. The UI of `CookieStateApp`

Within the first button's Click event handler, build a new `HttpCookie` and insert it into the `Cookie` collection exposed from the `HttpRequest.Cookies` property. Be very aware that the data will not persist itself to the user's hard drive unless you explicitly set an expiration date using the `HttpCookie.Expires` property. Thus, the following implementation will create a temporary cookie that is destroyed when the user shuts down the browser:

```
protected void btnCookie_Click(object sender, EventArgs e)
{
    // Make a temp cookie.
    HttpCookie theCookie =
        new HttpCookie(txtCookieName.Text,
                       txtCookieValue.Text);
    Response.Cookies.Add(theCookie);
}
```

However, the following generates a persistent cookie that will expire three months from today:

```
protected void btnCookie_Click(object sender, EventArgs e)
{
    HttpCookie theCookie =
        new HttpCookie(txtCookieName.Text,
                       txtCookieValue.Text);
    theCookie.Expires = DateTime.Now.AddMonths(3);
    Response.Cookies.Add(theCookie);
}
```

Reading Incoming Cookie Data

Recall that the browser is the entity in charge of accessing persisted cookies when navigating to a previously visited page. If a browser decides to send a cookie to the server, you can access the incoming data in your *.aspx page via the `HttpRequest.Cookies` property. To illustrate, implement the `Click` event handler for the second button like so:

```
protected void btnShowCookie_Click(object sender, EventArgs e)
{
    string cookieData = "";
    foreach (string s in Request.Cookies)
    {
        cookieData += string.Format("<li><b>Name</b>: {0}, <b>Value</b>: {1}</li>",
                                    s, Request.Cookies[s].Value);
    }
    lblCookieData.Text = cookieData;
}
```

If you now run the application and click your new button, you will find that the cookie data has indeed been sent by your browser and accessed successfully in your *.aspx code at the server.

■ Source Code The `CookieStateApp` web site is included under the Chapter 34 subdirectory.

The Role of the <sessionState> Element

At this point in the chapter, you have examined numerous ways to remember information about your users. As you have seen, view state and application, cache, session, and cookie data are manipulated programmatically in more or less the same way (via a class indexer). As you have also seen, Global.asax has methods that allow you to intercept and respond to events that occur during your web application's lifetime.

By default, ASP.NET will store session state in-process. The plus side is that access to the information is as fast as possible. However, the downside is that if this AppDomain crashes (for whatever reason), all of the user's state data is destroyed. Furthermore, when you store state data as an in-process *.dll, you cannot interact with a networked web farm. This default mode of storage works just fine if your web application is hosted by a single web server. As you might guess, however, this model is not ideal for a farm of web servers, given that session state is "trapped" within a given AppDomain.

Storing Session Data in the ASP.NET Session State Server

Under ASP.NET, you can instruct the runtime to host the session state *.dll in a surrogate process named the ASP.NET session state server (aspnet_state.exe). When you do so, you are able to offload the *.dll from aspnet_wp.exe into a unique *.exe, which can be located on any machine within the web farm. Even if you intend to run the aspnet_state.exe process on the same machine as the web server, you gain the benefit of partitioning the state data in a unique process (as it is more durable).

To make use of the session state server, the first step is to start the aspnet_state.exe Windows service on the target machine by typing the following in a Visual Studio 2010 Command Prompt window (note that you will need admin privileges to do so):

```
net start aspnet_state
```

Alternatively, you can start aspnet_state.exe using the Services applet accessed from the Administrative Tools folder of the Control Panel, as shown in Figure 34-9.




Figure 34-9. Starting `aspnet_state.exe` using the Services applet

The key benefit of this approach is that you can use the Properties window to configure `aspnet_state.exe` to start automatically when the machine boots up. In any case, once the session state server is running, add the following `<sessionState>` element of your `Web.config` file as follows:

```

<system.web>
  <sessionState
    mode="StateServer"
    stateConnectionString="tcpip=127.0.0.1:42626"
    sqlConnectionString="data source=127.0.0.1;Trusted_Connection=yes"
    cookieless="false"
    timeout="20"
  />
  ...
</system.web>

```

That's it! At this point, the CLR will host session-centric data within `aspnet_state.exe`. In this way, if the AppDomain hosting the web application crashes, the session data is preserved. Moreover, note that the `<sessionState>` element can also support a `stateConnectionString` attribute. The default TCP/IP address value (127.0.0.1) points to the local machine. If you would rather have the .NET runtime use the `aspnet_state.exe` service located on another networked machine (again, think web farms), you are free to update this value.

Storing Session Data in a Dedicated Database

Finally, if you require the highest degree of isolation and durability for your web application, you may choose to have the runtime store all your session state data within Microsoft SQL Server. The appropriate update to the Web.config file is simple:

```
<sessionState  
    mode="SQLServer"  
    stateConnectionString="tcpip=127.0.0.1:42626"  
    sqlConnectionString="data source=127.0.0.1;Trusted_Connection=yes"  
    cookieless="false"  
    timeout="20"  
/>
```

However, before you attempt to run the associated web application, you need to ensure that the target machine (specified by the sqlConnectionString attribute) has been properly configured. When you install the .NET Framework 4.0 SDK (or Visual Studio 2010), you will be provided with two files named `InstallSqlState.sql` and `UninstallSqlState.sql`, located by default under `C:\Windows\Microsoft.NET\Framework\<version>`. On the target machine, you must run the `InstallSqlState.sql` file using a tool such as the Microsoft SQL Server Management Studio (which ships with Microsoft SQL Server).

Once you have run `InstallSqlState.sql`, you will find a new SQL Server database has been created (`ASPState`), which contains a number of stored procedures called by the ASP.NET runtime, as well as a set of tables used to store the session data itself. (Also, the `tempdb` database has been updated with a set of tables for swapping purposes.) As you'd guess, configuring your web application to store session data within SQL Server is the slowest of all possible options. The benefit is that user data is as durable as possible (even if the web server is rebooted).

Note If you make use of the ASP.NET session state server or SQL Server to store your session data, you must make sure that any custom types placed in the `HttpSessionState` object have been marked with the `[Serializable]` attribute.

Understanding the ASP.NET Profile API

So far you have examined numerous techniques that allow you to remember user-level and application-level bits of data. However, these techniques suffer from one major limitation: they exist only as long as the user is in session and the web application is running! However, many web sites require the ability to persist user information across sessions. For example, perhaps you need to give users the ability to build an account on your site. Maybe you need to persist instances of a `ShoppingCart` class across sessions (for an online shopping site). Or perhaps you wish to persist basic user preferences (themes, etc.).

While you most certainly could build a custom database (with several stored procedures) to hold such information, you would then need to build a custom code library to interact with these database objects. This is not necessarily a complex task, but the bottom line is that *you* are the individual in charge of building this sort of infrastructure.

To help simplify matters, ASP.NET ships with an out-of-the-box user profile management API and database system for this very purpose. In addition to providing the necessary infrastructure, the Profile API allows you to define the data to be persisted directly within your Web.config file (for purposes of simplification); however, you are also able to persist any [Serializable] type. Before we get too far ahead of ourselves, let's check out where the Profile API will be storing the specified data.

The ASPNETDB.mdf Database

Every ASP.NET web site built with Visual Studio 2010 can support an App_Data subdirectory. By default, the Profile API (as well as other services, such as the ASP.NET role membership API, which is not examined in this text) is configured to make use of a local SQL Server 2010 database named ASPNETDB.mdf, located within the App_Data folder. This default behavior is due to settings within the machine.config file for the current .NET installation on your machine. In fact, when your code base makes use of any ASP.NET service requiring the App_Data folder, the ASPNETDB.mdf data file will be automatically created on the fly if a copy does not currently exist.

If you'd rather have the ASP.NET runtime communicate with an ASPNETDB.mdf file located on another networked machine, or you'd prefer to install this database on an instance of SQL Server 7.0 (or higher), you will need to manually build ASPNETDB.mdf using the aspnet_regsql.exe command-line utility. Like any good command-line tool, aspnet_regsql.exe provides numerous options; however, if you run the tool with no arguments, like so:

```
aspnet_regsql
```

you will launch a GUI-based wizard that will walk you through the process of creating and installing ASPNETDB.mdf on your machine (and version of SQL Server) of choice.

Now, assuming your site is not using a local copy of the database under the App_Data folder, the final step is to update your Web.config file to point to the unique location of your ASPNETDB.mdf. Assume you have installed ASPNETDB.mdf on a machine named ProductionServer. The following (partial) machine.config file would instruct the Profile API where to find the necessary database items in their default location (you could add a custom Web.config to change these defaults):

```
<configuration>
  <connectionStrings>
    <add name="LocalSqlServer"
      connectionString ="Data Source=ProductionServer;Integrated
      Security=SSPI;Initial Catalog=aspnetdb;"
      providerName="System.Data.SqlClient"/>
  </connectionStrings>
  <system.web>
    <profile>
      <providers>
        <clear/>
        <add name="AspNetSqlProfileProvider"
          connectionStringName="LocalSqlServer"
          applicationName="/"
          type="System.Web.Profile.SqlProfileProvider, System.Web,
          Version=4.0.0.0,
          Culture=neutral, PublicKeyToken=b03f5f7f11d50a3a" />
      </providers>
    </profile>
  </system.web>
</configuration>
```

```
</system.web>
</configuration>
```

Like most *.config files, this looks much worse than it is. Basically we are defining a <connectionString> element with the necessary data, followed by a named instance of the SqlProfileProvider (this is the default provider used regardless of physical location of the ASPNETDB.mdf).

Note For simplicity, I will assume that you'll use the autogenerated ASPNETDB.mdf database located under your web application's App_Data subdirectory.

Defining a User Profile Within Web.config

As mentioned, a user profile is defined within a Web.config file. The really nifty aspect of this approach is that you can interact with this profile in a strongly typed manner using the inherited Profile property in your code files. To illustrate this, create a new Empty Web Site named FunWithProfiles, add a new *.aspx file, and open your Web.config file for editing.

Our goal is to make a profile that models the home address of the users who are in session, as well as the total number of times they have posted to this site. Not surprisingly, profile data is defined within a <profile> element using a set of name/data type pairs. Consider the following profile, which is created within the scope of the <system.web> element:

```
<profile>
  <properties>
    <add name="StreetAddress" type="System.String" />
    <add name="City" type="System.String" />
    <add name="State" type="System.String" />
    <add name="TotalPost" type="System.Int32" />
  </properties>
</profile>
```

Here, we have specified a name and CLR data type for each item in the profile (of course, we could add additional items for zip code, name, and so forth, but I am sure you get the idea). Strictly speaking, the type attribute is optional; however, the default is a System.String. As you would guess, there are many other attributes that can be specified in a profile entry to further qualify how this information should be persisted in ASPNETDB.mdf. Table 34-4 illustrates some of the core attributes.

Table 34-4. Select Attributes of Profile Data

Attribute	Example Values	Meaning in Life
allowAnonymous	True False	Restricts or allows anonymous access to this value. If it is set to false, anonymous users won't have access to this profile value.
defaultValue	String	The value to return if the property has not been explicitly set.


Table 34-4. Select Attributes of Profile Data (continued)

Attribute	Example Values	Meaning in Life
Name	String	A unique identifier for this property.
Provider	String	The provider used to manage this value. It overrides the defaultProvider setting in Web.config or machine.config.
readOnly	True False	Restricts or allows write access (the default is false, i.e. it's not read-only).
serializeAs	String XML Binary	The format of a value when persisting in the data store.
type	Primitive User-defined type	A .NET primitive type or class. Class names must be fully qualified (e.g., MyApp.UserData.ColorPrefs).

We will see some of these attributes in action as we modify the current profile. For now, let's see how to access this data programmatically from within our pages.

Accessing Profile Data Programmatically

Recall that the whole purpose of the ASP.NET Profile API is to automate the process of writing data to (and reading data from) a dedicated database. To test this out for yourself, update the UI of your Default.aspx file with a set of TextBoxes (and descriptive Labels) to gather the street address, city, and state of the user. As well, add a Button (named btnSubmit) and a final Label (named lblUserData) that will be used to display the persisted data, as shown in Figure 34-10.

**Figure 34-10.** The UI of the FunWithProfiles Default.aspx page

Now, within the Click event handler of the button, make use of the inherited Profile property to persist each point of profile data based on what the user has entered in the related TextBox. Once you have persisted each piece of data within ASPNETDB.mdf, read each piece of data out of the database and format it into a string that is displayed on the lblUserData Label type. Finally, handle the page's Load event, and display the same information on the Label type. In this way, when users come to the page, they can see their current settings. Here is the complete code file:

```
public partial class _Default : System.Web.UI.Page
{
    protected void Page_Load(object sender, EventArgs e)
    {
        GetUserAddress();
    }
    protected void btnSubmit_Click(object sender, EventArgs e)
    {
        // Database writes happening here!
        Profile.StreetAddress = txtStreetAddress.Text;
        Profile.City = txtCity.Text;
        Profile.State = txtState.Text;

        // Get settings from database.
        GetUserAddress();
    }

    private void GetUserAddress()
    {
        // Database reads happening here!
        lblUserData.Text = String.Format("You live here: {0}, {1}, {2}",
            Profile.StreetAddress, Profile.City, Profile.State);
    }
}
```

Now if you run this page, you will notice a lengthy delay the first time Default.aspx is requested. The reason is that the ASPNETDB.mdf file is being created on the fly and placed within your App_Data folder. You can verify this for yourself by refreshing Solution Explorer (see Figure 34-11).




Figure 34-11. Behold ASPNETDB.mdf!

You will also find that the first time you come to this page, the `lblUserData` Label does not display any profile data, as you have not yet entered your data into the correct table of `ASPNETDB.mdf`. Once you enter values in the TextBox controls and post back to the server, you will find this Label is formatted with the persisted data.

Now, for the really interesting aspect of this technology. If you shut down your browser and rerun your web site, you will find that your previously entered profile data has indeed been persisted, as the Label displays the correct information. This begs the obvious question, how were you remembered?

For this example, the Profile API used your Windows network identity, which was obtained via your current machine credentials. However, when you are building public web sites (where the users are not part of a given domain), rest assured that the Profile API integrates with the Forms-based authentication model of ASP.NET and also supports the notion of “anonymous profiles,” which allow you to persist profile data for users who do not currently have an active identity on your site.

Note This edition of the text does not address ASP.NET security topics (such as Forms-based authentication or anonymous profiles). Consult the .NET Framework 4.0 SDK documentation for details.

Grouping Profile Data and Persisting Custom Objects

To wrap up this chapter, allow me to make a few additional comments on how profile data may be defined within a `Web.config` file. The current profile simply defined four pieces of data that were exposed directly from the profile type. When you build more complex profiles, it can be helpful to group related pieces of data under a unique name. Consider the following update:

```
<profile>
  <properties>
    <group name = "Address">
      <add name="StreetAddress" type="String" />
      <add name="City" type="String" />
      <add name="State" type="String" />
    </group>
    <add name="TotalPost" type="Integer" />
  </properties>
</profile>
```

This time we have defined a custom group named `Address` to expose the street address, city, and state of our user. To access this data in our pages would now require us to update our code base by specifying `Profile.Address` to get each subitem. For example, here is the updated `GetUserAddress()` method (the Click event handler for the Button would need to be updated in a similar manner):

```
private void GetUserAddress()
{
  // Database reads happening here!
  lblUserData.Text = String.Format("You live here: {0}, {1}, {2}",
    Profile.Address.StreetAddress,
    Profile.Address.City, Profile.Address.State);
}
```

Before you run this example, you need to delete `ASPNETDB.mdf` from your `App_Data` folder, to ensure the database schema is refreshed. Once you have done so, you should be able to run your web site example without error.

Note A profile can contain as many groups as you feel are necessary. Simply define multiple `<group>` elements within your `<properties>` scope.

Finally, it is worth pointing out that a profile may also persist (and obtain) custom objects to and from `ASPNETDB.mdf`. To illustrate, assume you wanted to build a custom class (or structure) that will represent the user's address data. The only requirement expected by the Profile API is that the type be marked with the `[Serializable]` attribute, for example:

```
[Serializable]
public class UserAddress
{
    public string Street = string.Empty;
    public string City = string.Empty;
    public string State = string.Empty;
}
```

With this class in place, our profile definition can now be updated as follows (notice I removed the custom group, although this is not mandatory):

```
<profile>
    <properties>
        <add name="AddressInfo" type="UserAddress" serializeAs="Binary"/>
        <add name="TotalPost" type="Integer" />
    </properties>
</profile>
```

Note that when you are adding `[Serializable]` types to a profile, the `type` attribute is the fully qualified named of the type being persisted. As you will see from the Visual Studio 2010 IntelliSense, your core choices are binary, XML, or string data. Now that we are capturing street address information as a custom class type, we (once again) need to update our code base:

```
private void GetUserAddress()
{
    // Database reads happening here!
    lblUserData.Text = String.Format("You live here: {0}, {1}, {2}",
        Profile.AddressInfo.Street, Profile.AddressInfo.City,
        Profile.AddressInfo.State);
}
```

To be sure, there is much more to the Profile API than I've had space to cover here. For example, the `Profile` property actually encapsulates a type named `ProfileCommon`. Using this type, you are able to programmatically obtain all information for a given user, delete (or add) profiles to `ASPNETDB.mdf`, update aspects of a profile, and so forth.

Moreover, the Profile API has numerous points of extensibility that can allow you to optimize how the profile manager accesses the tables of the ASPNETDB.mdf database. As you would expect, there are many ways to decrease the number of “hits” this database takes. Interested readers are encouraged to consult the .NET Framework 4.0 SDK documentation for further details.

■ **Source Code** The FunWithProfiles web site is included under the Chapter 34 subdirectory.

Summary

In this chapter, you rounded out your knowledge of ASP.NET by examining how to leverage the `HttpApplication` type. As you have seen, this type provides a number of default event handlers that allow you to intercept various application- and session-level events. The bulk of this chapter was spent exploring a number of state management techniques. Recall that view state is used to automatically repopulate the values of HTML widgets between postbacks to a specific page. Next, you checked out the distinction of application- and session-level data, cookie management, and the ASP.NET application cache.

Finally, this chapter exposed you to the ASP.NET Profile API. As you have seen, this technology provides an out-of-the-box solution to the issue of persisting user data across sessions. Using your web site’s `Web.config` file, you can define any number of profile items (including groups of items and `[Serializable]` types) that will automatically be persisted into `ASPNETDB.mdf`.



Programming with Windows Forms

Since the release of the .NET platform (circa 2001), the base class libraries have included a particular API named Windows Forms, represented primarily by the `System.Windows.Forms.dll` assembly. The Windows Forms toolkit provides the types necessary to build desktop graphical user interfaces (GUIs), create custom controls, manage resources (e.g., string tables and icons), and perform other desktop-centric programming tasks. In addition, a separate API named GDI+ (represented by the `System.Drawing.dll` assembly) provides additional types that allow programmers to generate 2D graphics, interact with networked printers, and manipulate image data.

The Windows Forms (and GDI+) APIs remain alive and well within the .NET 4.0 platform, and they will exist within the base class library for quite some time (arguably forever). However, Microsoft has shipped a brand new GUI toolkit called Windows Presentation Foundation (WPF) since the release of .NET 3.0. As you saw in Chapters 27–31, WPF provides a massive amount of horsepower that you can use to build bleeding-edge user interfaces, and it has become the preferred desktop API for today's .NET graphical user interfaces.

The point of this appendix, however, is to provide a tour of the traditional Windows Forms API. One reason it is helpful to understand the original programming model: you can find many existing Windows Forms applications out there that will need to be maintained for some time to come. Also, many desktop GUIs simply might not require the horsepower offered by WPF. When you need to create more traditional business UIs that do not require an assortment of bells and whistles, the Windows Forms API can often fit the bill.

In this appendix, you will learn the Windows Forms programming model, work with the integrated designers of Visual Studio 2010, experiment with numerous Windows Forms controls, and receive an overview of graphics programming using GDI+. You will also pull this information together in a cohesive whole by wrapping things up in a (semi-capable) painting application.

■ **Note** Here's one proof that Windows Forms is not disappearing anytime soon: .NET 4.0 ships with a brand new Windows Forms assembly, `System.Windows.Forms.DataVisualization.dll`. You can use this library to incorporate charting functionality into your programs, complete with annotations; 3D rendering; and hit-testing support. This appendix will not cover this new .NET 4.0 Windows Forms API; however, you can look up the `System.Windows.Forms.DataVisualization.Charting` namespace if you want more information.

The Windows Forms Namespaces

The Windows Forms API consists of hundreds of types (e.g., classes, interfaces, structures, enums, and delegates), most of which are organized within various namespaces of the `System.Windows.Forms.dll` assembly. Figure A-1 shows these namespaces displayed in the Visual Studio 2010 object browser.




Figure A-1. The namespaces of `System.Windows.Forms.dll`

Far and away the most important Windows Forms namespace is `System.Windows.Forms`. At a high level, you can group the types within this namespace into the following broad categories:

- *Core infrastructure*: These are types that represent the core operations of a Windows Forms program (e.g., `Form` and `Application`) and various types to facilitate interoperability with legacy ActiveX controls, as well as interoperability with new WPF custom controls.
- *Controls*: These are types used to create graphical UIs (e.g., `Button`, `MenuStrip`, `ProgressBar`, and `DataGridView`), all of which derive from the `Control` base class. Controls are configurable at design time and are visible (by default) at runtime.
- *Components*: These are types that do not derive from the `Control` base class, but still may provide visual features to a Windows Forms program (e.g., `ToolTip` and `ErrorProvider`). Many components (e.g., the `Timer` and `System.ComponentModel.BackgroundWorker`) are not visible at runtime, but can be configured visually at design time.
- *Common dialog boxes*: Windows Forms provides several canned dialog boxes for common operations (e.g., `OpenFileDialog`, `PrintDialog`, and `ColorDialog`). As you would hope, you can certainly build your own custom dialog boxes if the standard dialog boxes do not suit your needs.

Given that the total number of types within `System.Windows.Forms` is well over 100 strong, it would be redundant (not to mention a terrible waste of paper) to list every member of the Windows Forms

family. As you work through this appendix, however, you will gain a firm foundation that you can build on. In any case, be sure to check out the .NET Framework 4.0 SDK documentation for additional details.

Building a Simple Windows Forms Application

As you might expect, modern .NET IDEs (e.g., Visual Studio 2010, C# 2010 Express, and SharpDevelop) provide numerous form designers, visual editors, and integrated code-generation tools (wizards) to facilitate the construction of Windows Forms applications. These tools are extremely useful, but they can also hinder the process of learning Windows Forms, because these same tools tend to generate a good deal of boilerplate code that can obscure the core object model. Given this, you will create your first Windows Forms example using a Console Application project as a starting point.

Begin by creating a Console Application named SimpleWinFormsApp. Next, use the Project ▶ Add Reference menu option to set a reference to the `System.Windows.Forms.dll` and `System.Drawing.dll` assemblies through the .NET tab of the resulting dialog box. Next, update your `Program.cs` file with the following code:

```
using System;
using System.Collections.Generic;
using System.Linq;
using System.Text;

// The minimum required windows forms namespaces.
using System.Windows.Forms;

namespace SimpleWinFormsApp
{
    // This is the application object.
    class Program
    {
        static void Main(string[] args)
        {
            Application.Run(new MainWindow());
        }
    }

    // This is the main window.
    class MainWindow : Form {}
}
```

Note When Visual Studio 2010 finds a class that extends `System.Windows.Forms.Form`, it attempts to open the related GUI designer (provided this class is the first class in the C# code file). Double-clicking the `Program.cs` file from the Solution Explorer opens the designer, but don't do that yet! You will work with the Windows Forms designer in the next example; for now, be sure you right-click on the C# file containing your code within the Solution Explorer and select the View Code option.

This code represents the absolute simplest Windows Forms application you can build. At a bare minimum, you need a class that extends the `Form` base class and a `Main()` method to call the static `Application.Run()` method (you can find more details on `Form` and `Application` later in this chapter). Running your application now reveals that you have a resizable, minimizable, maximizable, and closable topmost window (see Figure A-2).




Figure A-2. A simple Windows Forms application

■ **Note** When you run this program, you will notice a command prompt looming in the background of your topmost window. This is because, when you create a Console Application, the `/target` flag sent to the C# compiler defaults to `/target:exe`. You can change this to `/target:winexe` (preventing the display of the command prompt) by double-clicking the Properties icon in the Solution Explorer and changing the Output Type setting to Windows Application using the Application tab.

Granted, the current application is not especially exciting, but it does illustrate how simple a Windows Forms application can be. To spruce things up a bit, you can add a custom constructor to your `MainWindow` class, which allows the caller to set various properties on the window to be displayed:

```
// This is the main window.
class MainWindow : Form
{
    public MainWindow() {}
    public MainWindow(string title, int height, int width)
    {
        // Set various properties from the parent classes.
        Text = title;
        Width = width;
        Height = height;
```

```

    // Inherited method to center the form on the screen.
    CenterToScreen();
}
}

```

You can now update the call to `Application.Run()`, as follows:

```

static void Main(string[] args)
{
    Application.Run(new MainWindow("My Window", 200, 300));
}

```

This is a step in the right direction, but any window worth its salt requires various user interface elements (e.g., menu systems, status bars, and buttons) to allow for input. To understand how a `Form`-derived type can contain such elements, you must understand the role of the `Controls` property and the underlying controls collection.

Populating the Controls Collection

The `System.Windows.Forms.Control` base class (which is the inheritance chain of the `Form` type) defines a property named `Controls`. This property wraps a custom collection nested in the `Control` class named `ControlsCollection`. This collection (as the name suggests) references each UI element maintained by the derived type. Like other containers, this type supports several methods for inserting, removing, and finding a given UI widget (see Table A-1).

Table A-1. *ControlCollection Members*

Member	Meaning in Life
<code>Add()</code> <code>AddRange()</code>	You use these members to insert a new <code>Control</code> -derived type (or array of types) in the collection.
<code>Clear()</code>	This member removes all entries in the collection.
<code>Count</code>	This member returns the number of items in the collection.
<code>Remove()</code> <code>RemoveAt()</code>	You use these members to remove a control from the collection.

When you wish to populate the UI of a `Form`-derived type, you typically follow a predictable series of steps:

- Define a member variable of a given UI element within the `Form`-derived class.
- Configure the look and feel of the UI element.
- Add the UI element to the form's `ControlsCollection` container using a call to `Controls.Add()`.

Assume you wish to update your `MainWindow` class to support a File ➤ Exit menu system. Here are the relevant updates, with code analysis to follow:

```
class MainWindow : Form
{
    // Members for a simple menu system.
    private MenuStrip mnuMainMenu = new MenuStrip();
    private ToolStripMenuItem mnuFile = new ToolStripMenuItem();
    private ToolStripMenuItem mnuFileExit = new ToolStripMenuItem();

    public MainWindow(string title, int height, int width)
    {
        ...
        // Method to create the menu system.
        BuildMenuSystem();
    }

    private void BuildMenuSystem()
    {
        // Add the File menu item to the main menu.
        mnuFile.Text = "&File";
        mnuMainMenu.Items.Add(mnuFile);

        // Now add the Exit menu to the File menu.
        mnuFileExit.Text = "E&xit";
        mnuFile.DropDownItems.Add(mnuFileExit);
        mnuFileExit.Click += (o, s) => Application.Exit();

        // Finally, set the menu for this Form.
        Controls.Add(this.mnuMainMenu);
        MainMenuStrip = this.mnuMainMenu;
    }
}
```

Notice that the `MainWindow` type now maintains three new member variables. The `MenuStrip` type represents the entirety of the menu system, while a given `ToolStripMenuItem` represents any topmost menu item (e.g., File) or submenu item (e.g., Exit) supported by the host.

You configure the menu system within the `BuildMenuSystem()` helper function. Notice that the text of each `ToolStripMenuItem` is controlled through the `Text` property; each menu item has been assigned a string literal that contains an embedded ampersand symbol. As you might already know, this syntax sets the Alt key shortcut. Thus, selecting Alt+F activates the File menu, while selecting Alt+X activates the Exit menu. Also notice that the File `ToolStripMenuItem` object (`mnuFile`) adds subitems using the `DropDownItems` property. The `MenuStrip` object itself adds a topmost menu item using the `Items` property.

Once you establish the menu system, you can add it to the controls collection (through the `Controls` property). Next, you assign your `MenuStrip` object to the form's `MainMenuStrip` property. This step might seem redundant, but having a specific property such as `MainMenuStrip` makes it possible to dynamically establish which menu system to show a user. You might change the menu displayed based on user preferences or security settings.

The only other point of interest is the fact that you handle the `Click` event of the File ➤ Exit menu; this helps you capture when the user selects this submenu. The `Click` event works in conjunction with a standard delegate type named `System.EventHandler`. This event can only call methods that take a

`System.Object` as the first parameter and a `System.EventArgs` as the second. Here, you use a lambda expression to terminate the entire application with the static `Application.Exit()` method.

Once you recompile and execute this application, you will find your simple window sports a custom menu system (see Figure A-3).



Figure A-3. A simple window, with a simple menu system

The Role of `System.EventArgs` and `System.EventHandler`

`System.EventHandler` is one of many delegate types used within the Windows Forms (and ASP.NET) APIs during the event-handling process. As you have seen, this delegate can only point to methods where the first argument is of type `System.Object`, which is a reference to the object that sent the event. For example, assume you want to update the implementation of the lambda expression, as follows:

```
mnuFileExit.Click += (o, s) =>
{
    MessageBox.Show(string.Format("{0} sent this event", o.ToString()));
    Application.Exit();
};
```

You can verify that the `mnuFileExit` type sent the event because the string is displayed within the message box:

```
"E&xit sent this event"
```

You might be wondering what purpose the second argument, `System.EventArgs`, serves. In reality, the `System.EventArgs` type brings little to the table because it simply extends `Object` and provides practically nothing by way of addition functionality:

```
public class EventArgs
{
    public static readonly EventArgs Empty;
    static EventArgs();
    public EventArgs();
}
```

However, this type is useful in the overall scheme of .NET event handling because it is the parent to many (useful) derived types. For example, the `MouseEventArgs` type extends `EventArgs` to provide details regarding the current state of the mouse. `KeyEventArgs` also extends `EventArgs` to provide details of the

state of the keyboard (such as which key was pressed); PaintEventArgs extends EventArgs to yield graphically relevant data; and so forth. You can also see numerous EventArgs descendants (and the delegates that make use of them) not only when working with Windows Forms, but when working with the WPF and ASP.NET APIs, as well.

While you could continue to build more functionality into your MainWindow (e.g., status bars and dialog boxes) using a simple text editor, you would eventually end up with hand cramps because you have to author all the grungy control configuration logic manually. Thankfully, Visual Studio 2010 provides numerous integrated designers that take care of these details on your behalf. As you use these tools during the remainder of this chapter, always remember that these tools authoring everyday C# code; there is nothing magical about them whatsoever.

■ Source Code You can find the SimpleWinFormsApp project under the Appendix A subdirectory.

The Visual Studio Windows Forms Project Template

When you wish to leverage the Windows Forms designer tools of Visual Studio 2010, you typically begin by selecting the Windows Forms Application project template using the File ▶ New Project menu option. To get comfortable with the core Windows Forms designer tools, create a new application named SimpleVSWinFormsApp (see Figure A-4).




Figure A-4. The Visual Studio Windows Forms Project Template

The Visual Designer Surface

Before you begin to build more interesting Windows applications, you will re-create the previous example leveraging the designer tools. Once you create a new Windows Forms project, you will notice that Visual Studio 2010 presents a designer surface to which you can drag-and-drop any number of controls. You can use this same designer to configure the initial size of the window simply by resizing the form itself using the supplied grab handles (see Figure A-5).



Figure A-5. The visual forms designer

When you wish to configure the look-and-feel of your window (as well as any control placed on a form designer), you do so using the Properties window. Similar to a Windows Presentation Foundation project, this window can be used to assign values to properties, as well as to establish event handlers for the currently selected item on the designer (you select a configuration using the drop-down list box mounted on the top of the Properties window).

Currently, your form is devoid of content, so you see only a listing for the initial Form, which has been given a default name of Form1, as shown in the read-only Name property of Figure A-6.




Figure A-6. The Properties window for setting properties and handling events

■ **Note** You can configure the Properties window to display its content by category or alphabetically using the first two buttons mounted beneath the drop-down list box. I'd suggest that you sort the items alphabetically to find a given property or event quickly.

The next designer element to be aware of is the Solution Explorer window. All Visual Studio 2010 projects support this window, but it is especially helpful when building Windows Forms applications to be able to (1) change the name of the file and related class for any window quickly, and (2) view the file that contains the designer-maintained code (you'll learn more information on this tidbit in just a moment). For now, right-click the `Form1.cs` icon and select the Rename option. Name this initial window to something more fitting: `MainWindow.cs`. The IDE will ask you if you wish to change the name of your initial class; it's fine to do this.

Dissecting the Initial Form

Before you build your menu system, you need to examine exactly what Visual Studio 2010 has created by default. Right-click the `MainWindow.cs` icon from the Solution Explorer window and select View Code. Notice that the form has been defined as a partial type, which allows a single type to be defined within multiple code files (see Chapter 5 for more information about this). Also, note that the form's constructor makes a call to a method named `InitializeComponent()` and your type *is-a* Form:

```
namespace SimpleVSWinFormsApp
{
    public partial class MainWindow : Form
    {
        public MainWindow()
        {
            InitializeComponent();
        }
    }
}
```

As you might be expecting, `InitializeComponent()` is defined in a separate file that completes the partial class definition. As a naming convention, this file always ends in `.Designer.cs`, preceded by the name of the related C# file containing the Form-derived type. Using the Solution Explorer window, open your `MainWindow.Designer.cs` file. Now, ponder the following code (this snippet strips out the code comments for simplicity; your code might differ slightly, based on the configurations you did in the Properties window):

```
partial class MainWindow
{
    private System.ComponentModel.IContainer components = null;

    protected override void Dispose(bool disposing)
    {
        if (disposing && (components != null))
        {

```

```

        components.Dispose();
    }
    base.Dispose(disposing);
}

private void InitializeComponent()
{
    this.SuspendLayout();
    this.AutoScaleDimensions = new System.Drawing.SizeF(6F, 13F);
    this.AutoScaleMode = System.Windows.Forms.AutoScaleMode.Font;
    this.ClientSize = new System.Drawing.Size(422, 114);
    this.Name = "Form1";
    this.Text = "Form1";
    this.ResumeLayout(false);
}
}

```

The `IContainer` member variable and `Dispose()` methods are little more than infrastructure used by the Visual Studio designer tools. However, notice that the `InitializeComponent()` is present and accounted for. Not only is this method invoked by a form's constructor at runtime, Visual Studio makes use of this same method at design time to render correctly the UI seen on the Forms designer. To see this in action, change the value assigned to the `Text` property of the window to "My Main Window". Once you activate the designer, the form's caption will update accordingly.

When you use the visual design tools (e.g., the Properties window or the form designer), the IDE updates `InitializeComponent()` automatically. To illustrate this aspect of the Windows Forms designer tools, ensure that the Forms designer is the active window within the IDE and find the `Opacity` property listed in the Properties window. Change this value to 0.8 (80%); this gives your window a slightly transparent look-and-feel the next time you compile and run your program. Once you make this change, reexamine the implementation of `InitializeComponent()`:

```

private void InitializeComponent()
{
...
    this.Opacity = 0.8;
}

```

For all practical purposes, you should ignore the `*.Designer.cs` files and allow the IDE to maintain them on your behalf when you build a Windows Forms application using Visual Studio. If you were to author syntactically (or logically) incorrect code within `InitializeComponent()`, you might break the designer. Also, Visual Studio often reformats this method at design time. Thus, if you were to add custom code to `InitializeComponent()`, the IDE might delete it! In any case, remember that each window of a Windows Forms application is composed using partial classes.

Dissecting the Program Class

Beyond providing implementation code for an initial `Form`-derived type, the Windows Application project types also provide a static class (named `Program`) that defines your program's entry point, `Main()`:

```

static class Program
{

```

```
[STAThread]
static void Main()
{
    Application.EnableVisualStyles();
    Application.SetCompatibleTextRenderingDefault(false);
    Application.Run(new MainWindow());
}
```

The `Main()` method invokes `Application.Run()` and a few other calls on the `Application` type to establish some basic rendering options. Last but not least, note that the `Main()` method has been adorned with the `[STAThread]` attribute. This informs the runtime that if this thread happens to create any classic COM objects (including legacy ActiveX UI controls) during its lifetime, the runtime must place these objects in a COM-maintained area termed the *single-threaded apartment*. In a nutshell, this ensures that the COM objects are thread-safe, even if the author of a given COM object did not explicitly include code to ensure this is the case.

Visually Building a Menu System

To wrap up this look at the Windows Forms visual designer tools and move on to some more illustrative examples, activate the Forms designer window, locate the Toolbox window of Visual Studio 2010, and find the `MenuStrip` control within the Menus & Toolbars node (see Figure A-7).




Figure A-7. Windows Forms controls you can add to your designer surface

Drag a `MenuStrip` control onto the top of your Forms designer. Notice that Visual Studio responds by activating the menu editor. If you look closely at this editor, you will notice a small triangle on the top-right of the control. Clicking this icon opens a context-sensitive inline editor that allows you to make numerous property settings at once (be aware that many Windows Forms controls have similar inline editors). For example, click the Insert Standard Items option, as shown in Figure A-8.




Figure A-8. The inline menu editor

In this example, Visual Studio was kind enough to establish an entire menu system on your behalf. Now open your designer-maintained file (`MainWindow.Designer.cs`) and note the numerous lines of code added to `InitializeComponent()`, as well as several new member variables that represent your menu system (designer tools are good things!). Finally, flip back to the designer and undo the previous operation by clicking the `Ctrl+Z` keyboard combination. This brings you back to the initial menu editor and removes the generated code. Using the menu designer, type in a topmost File menu item, followed by an Exit submenu (see Figure A-9).




Figure A-9. Manually building our menu system

If you take a look at `InitializeComponent()`, you will find the same sort of code you authored by hand in the first example of this chapter. To complete this exercise, flip back to the Forms designer and click the lightning bolt button mounted on the Properties window. This shows you all of the events you can handle for the selected control. Make sure you select the `Exit` menu (named `exitToolStripMenuItem` by default), then locate the `Click` event (see Figure A-10).




Figure A-10. Establishing Events with the IDE

At this point, you can enter the name of the method to be called when the item is clicked; or, if you feel lazy at this point, you can double-click the event listed in the Properties window. This lets the IDE pick the name of the event handler on your behalf (which follows the pattern, *NameOfControl_NameOfEvent()*). In either case, the IDE will create stub code, and you can fill in the implementation details:

```
public partial class MainWindow : Form
{
    public MainWindow()
    {
        InitializeComponent();
        CenterToScreen();
    }
    private void exitToolStripMenuItem_Click(object sender, EventArgs e)
    {
        Application.Exit();
    }
}
```

If you so desire, you can take a quick peek at `InitializeComponent()`, where the necessary event riggings have also been accounted for:

```
this.exitToolStripMenuItem.Click +=  
    new System.EventHandler(this.exitToolStripMenuItem_Click);
```

At this point, you probably feel more comfortable moving around the IDE when building Windows Forms applications. While there are obviously many additional shortcuts, editors, and integrated code wizards, this information is more than enough for you to press onward.

The Anatomy of a Form

So far you have examined how to build simple Windows Forms applications with (and without) the aid of Visual Studio; now it's time to examine the `Form` type in greater detail. In the world of Windows Forms, the `Form` type represents any window in the application, including the topmost main windows, child windows of a multiple document interface (MDI) application, as well as modal and modeless dialog boxes. As Figure A-11 shows, the `Form` type gathers a good deal of functionality from its parent classes and the numerous interfaces it implements.




Figure A-11. The inheritance chain of `System.Windows.Forms.Form`

Table A-2 offers a high-level look at each parent class in the `Form`'s inheritance chain.

Table A-2. Base Classes in the Form Inheritance Chain

Parent Class	Meaning in Life
<code>System.Object</code>	Like any class in .NET, a <code>Form</code> <i>is-a</i> object.
<code>System.MarshalByRefObject</code>	Types deriving from this class are accessed remotely through a <i>reference to</i> (not a local copy of) the remote type.
<code>System.ComponentModel.Component</code>	This class provides a default implementation of the <code>IComponent</code> interface. In the .NET universe, a component is a type that supports design-time editing, but it is not necessarily visible at runtime.

Table A-2. Base Classes in the Form Inheritance Chain (continued)

Parent Class	Meaning in Life
System.Windows.Forms.Control	This class defines common UI members for all Windows Forms UI controls, including the Form type itself.
System.Windows.Forms.ScrollableControl	This class defines support for horizontal and vertical scrollbars, as well as members, which allow you to manage the viewport shown within the scrollable region.
System.Windows.Forms.ContainerControl	This class provides focus-management functionality for controls that can function as a container for other controls.
System.Windows.Forms.Form	This class represents any custom form, MDI child, or dialog box.

Although the complete derivation of a Form type involves numerous base classes and interfaces, you should keep in mind that you are *not* required to learn the role of each and every member of each and every parent class or implemented interface to be a proficient Windows Forms developer. In fact, you can easily set the majority of the members (specifically, properties and events) you use on a daily basis using the Visual Studio 2010 Properties window. That said, it is important that you understand the functionality provided by the Control and Form parent classes.

The Functionality of the Control Class

The System.Windows.Forms.Control class establishes the common behaviors required by any GUI type. The core members of Control allow you to configure the size and position of a control, capture keyboard and mouse input, get or set the focus/visibility of a member, and so forth. Table A-3 defines some properties of interest, which are grouped by related functionality.

Table A-3. Core Properties of the Control Type

Property	Meaning in Life
BackColor ForeColor BackgroundImage Font Cursor	These properties define the core UI of the control (e.g., colors, font for text, and the mouse cursor to display when the mouse is over the widget).
Anchor Dock AutoSize	These properties control how the control should be positioned within the container.

Table A-3. Core Properties of the Control Type (continued)

Property	Meaning in Life
Top Left Bottom Right Bounds ClientRectangle Height Width	These properties specify the current dimensions of the control.
Enabled Focused Visible	These properties encapsulate a Boolean that specifies the state of the current control.
ModifierKeys	This static property checks the current state of the modifier keys (e.g., Shift, Ctrl, and Alt) and returns the state in a Keys type.
MouseButtons	This static property checks the current state of the mouse buttons (left, right, and middle mouse buttons) and returns this state in a MouseButtons type.
TabIndex TabStop	You use these properties to configure the tab order of the control.
Opacity	This property determines the opacity of the control (0.0 is completely transparent; 1.0 is completely opaque).
Text	This property indicates the string data associated with this control.
Controls	This property allows you to access a strongly typed collection (e.g., ControlsCollection) that contains any child controls within the current control.

As you might guess, the `Control` class also defines a number of events that allow you to intercept mouse, keyboard, painting, and drag-and-drop activities, among other things. Table A-4 lists some events of interest, grouping them by related functionality.

Table A-4. Events of the Control Type

Event	Meaning in Life
Click DoubleClick MouseEnter MouseLeave MouseDown MouseUp MouseMove MouseHover MouseWheel	These events that let you interact with the mouse.
KeyPress KeyUp KeyDown	These events let you interact with the keyboard.
DragDrop DragEnter DragLeave DragOver	You use these events to monitor drag-and-drop activity.
Paint	This event lets you to interact with the graphical rendering services of GDI+.

Finally, the `Control` base class also defines a several methods that allow you to interact with any `Control`-derived type. As you examine the methods of the `Control` type, notice that a many of them have an `On` prefix, followed by the name of a specific event (e.g., `OnMouseMove`, `OnKeyUp`, and `OnPaint`). Each of these `On`-prefixed virtual methods is the default event handler for its respective event. If you override any of these virtual members, you gain the ability to perform any necessary pre- or post-processing of the event before (or after) invoking the parent's default implementation:

```
public partial class MainWindow : Form
{
    protected override void OnMouseDown(MouseEventArgs e)
    {
        // Add custom code for MouseDown event here.

        // Call parent implementation when finished.
        base.OnMouseDown(e);
    }
}
```

This can be helpful in some circumstances (especially if you want to build a custom control that derives from a standard control), but you will often handle events using the standard C# event syntax (in fact, this is the default behavior of the Visual Studio designers). When you handle events in this manner, the framework calls your custom event handler once the parent's implementation has completed. For example, this code lets you manually handle the `MouseDown` event:

```

public partial class MainWindow : Form
{
    public MainWindow()
    {
        ...
        MouseDown += new MouseEventHandler(MainWindow_MouseDown);
    }

    private void MainWindow_MouseDown(object sender, MouseEventArgs e)
    {
        // Add code for MouseDown event.
    }
}

```

You should also be aware of a few other methods, in addition to the just described `OnXXX()` methods:

- `Hide()`: Hides the control and sets the `Visible` property to `false`.
- `Show()`: Shows the control and sets the `Visible` property to `true`.
- `Invalidate()`: Forces the control to redraw itself by sending a `Paint` event (you learn more about graphical rendering using GDI+ later in this chapter).

The Functionality of the Form Class

The `Form` class is typically (but not necessarily) the direct base class for your custom `Form` types. In addition to the large set of members inherited from the `Control`, `ScrollableControl`, and `ContainerControl` classes, the `Form` type adds additional functionality in particular to main windows, MDI child windows, and dialog boxes. Let's start with the core properties in Table A-5.

Table A-5. Properties of the `Form` Type

Property	Meaning in Life
<code>AcceptButton</code>	Gets or sets the button on the form that is clicked when the user presses the Enter key.
<code>ActiveMdiChild</code>	Used within the context of an MDI application.
<code>IsMdiChild</code>	
<code>IsMdiContainer</code>	
<code>CancelButton</code>	Gets or sets the button control that will be clicked when the user presses the Esc key.
<code>ControlBox</code>	Gets or sets a value that indicates whether the form has a control box (e.g., the minimize, maximize, and close icons in the upper right of a window).
<code>FormBorderStyle</code>	Gets or sets the border style of the form. You use this in conjunction with the <code>FormBorderStyle</code> enumeration.

Table A-5. Properties of the Form Type (continued)

Property	Meaning in Life
Menu	Gets or sets the menu to dock on the form.
MaximizeBox	Used to determine whether this form will enable the maximize and minimize boxes.
MinimizeBox	
ShowInTaskbar	Determines whether this form will be seen on the Windows taskbar.
StartPosition	Gets or sets the starting position of the form at runtime, as specified by the <code>FormStartPosition</code> enumeration.
WindowState	Configures how the form is to be displayed on startup. You use this in conjunction with the <code>FormWindowState</code> enumeration.

In addition to numerous `On`-prefixed default event handlers, Table A-6 provides a list of some core methods defined by the `Form` type.

Table A-6. Key Methods of the Form Type

Method	Meaning in Life
Activate()	Activates a given form and gives it focus.
Close()	Closes the current form.
CenterToScreen()	Places the form in the center of the screen
LayoutMdi()	Arranges each child form (as specified by the <code>MdiLayout</code> enumeration) within the parent form.
Show()	Displays a form as a modeless window.
ShowDialog()	Displays a form as a modal dialog box.

Finally, the `Form` class defines a number of events, many of which fire during the form's lifetime (see Table A-7).

Table A-7. Select Events of the Form Type

Event	Meaning in Life
Activated	This event occurs whenever the form is <i>activated</i> , which means that the form has been given the current focus on the desktop.
FormClosed FormClosing	You use these events to determine when the form is about to close or has closed.
Deactivate	This event occurs whenever the form is <i>deactivated</i> , which means the form has lost the current focus on the desktop.
Load	This event occurs after the form has been allocated into memory, but is not yet visible on the screen.
MdiChildActive	This event is sent when a child window is activated.

The Life Cycle of a Form Type

If you have programmed user interfaces using GUI toolkits such as Java Swing, Mac OS X Cocoa, or WPF, you know that *window types* have many events that fire during their lifetime. The same holds true for Windows Forms. As you have seen, the life of a form begins when the class constructor is called prior to being passed into the `Application.Run()` method.

Once the object has been allocated on the managed heap, the framework fires the Load event. Within a Load event handler, you are free to configure the look-and-feel of the Form, prepare any contained child controls (e.g., ListBoxes and TreeViews), or allocate resources used during the Form's operation (e.g., database connections and proxies to remote objects).

Once the Load event fires, the next event to fire is Activated. This event fires when the form receives the focus as the active window on the desktop. The logical counterpart to the Activated event is (of course) Deactivate, which fires when the form loses the focus as the active window. As you can guess, the Activated and Deactivate events can fire numerous times over the life of a given Form object as the user navigates between active windows and applications.

Two events fire when the user chooses to close a given form: FormClosing and FormClosed. The FormClosing event is fired first and is an ideal place to prompt the end user with the much hated (but useful) message: “Are you *sure* you wish to close this application?” This step gives the user a chance to save any application-centric data before terminating the program.

The FormClosing event works in conjunction with the FormClosingEventHandler delegate. If you set the FormClosingEventArgs.Cancel property to true, you prevent the window from being destroyed and instruct it to return to normal operation. If you set FormClosingEventArgs.Cancel to false, the FormClosed event fires, and the Windows Forms application exits, which unloads the AppDomain and terminates the process.

This snippet updates your form's constructor and handles the Load, Activated, Deactivate, FormClosing, and FormClosed events (you might recall from Chapter 11 that the IDE will autogenerate the correct delegate and event handler when you press the Tab key twice after typing +=):

```
public MainWindow()
{
```

```

InitializeComponent();

// Handle various lifetime events.
FormClosing += new FormClosingEventHandler(MainWindow_Closing);
Load += new EventHandler(MainWindow_Load);
FormClosed += new FormClosedEventHandler(MainWindow_Closed);
Activated += new EventHandler(MainWindow_Activated);
Deactivate += new EventHandler(MainWindow_Deactivate);
}

```

Within the Load, FormClosed, Activated, and Deactivate event handlers, you must update the value of a new Form-level string member variable (named lifeTimeInfo) with a simple message that displays the name of the event that has just been intercepted. Begin by adding this member to your Form derived class:

```

public partial class MainWindow : Form
{
    private string lifeTimeInfo = "";
...
}
```

The next step is to implement the event handlers. Notice that you display the value of the lifeTimeInfo string within a message box in the FormClosed event handler:

```

private void MainWindow_Load(object sender, System.EventArgs e)
{
    lifeTimeInfo += "Load event\n";
}

private void MainWindow_Activated(object sender, System.EventArgs e)
{
    lifeTimeInfo += "Activate event\n";
}

private void MainWindow_Deactivate(object sender, System.EventArgs e)
{
    lifeTimeInfo += "Deactivate event\n";
}

private void MainWindow_Closed(object sender, FormClosedEventArgs e)
{
    lifeTimeInfo += "FormClosed event\n";
    MessageBox.Show(lifeTimeInfo);
}
```

Within the FormClosing event handler, you prompt the user to ensure that she wishes to terminate the application using the incoming FormClosingEventArgs. In the following code, the MessageBox.Show() method returns a DialogResult type that contains a value representing which button has been selected by the end user. Here, you craft a message box that displays Yes and No buttons; therefore, you want to discover whether the return value from Show() is DialogResult.No:

```

private void MainWindow_Closing(object sender, FormClosingEventArgs e)
{
```

```

lifeTimeInfo += "FormClosing event\n";

// Show a message box with Yes and No buttons.
DialogResult dr = MessageBox.Show("Do you REALLY want to close this app?",
    "Closing event!", MessageBoxButtons.YesNo);

// Which button was clicked?
if (dr == DialogResult.No)
    e.Cancel = true;
else
    e.Cancel = false;
}

```

Let's make one final adjustment. Currently, the File ➤ Exit menu destroys the entire application, which is a bit aggressive. More often, the File ➤ Exit handler of a top-most window calls the inherited Close() method, which fires the close-centric events and then tears down the application:

```

private void exitToolStripMenuItem_Click(object sender, EventArgs e)
{
    // Application.Exit();
    Close();
}

```

Now run your application and shift the form into and out of focus a few times (to trigger the Activated and Deactivate events). When you eventually shut down the application, you will see a message box that looks something like the message shown in Figure A-12.




Figure A-12. The life and times of a Form-derived type

■ **Source Code** You can find the SimpleVSWinFormsApp project under the Appendix A subdirectory.

Responding to Mouse and Keyboard Activity

You might recall that the `Control` parent class defines a set of events that allow you to monitor mouse and keyboard activity in a variety of manners. To check this out firsthand, create a new Windows Forms Application project named `MouseAndKeyboardEventsApp`, rename the initial form to `MainWindow.cs` (using the Solution Explorer), and handle the `MouseMove` event using the Properties window. These steps generate the following event handler:

```
public partial class MainWindow : Form
{
    public MainWindow()
    {
        InitializeComponent();
    }

    // Generated via the Properties window.
    private void MainWindow_MouseMove(object sender, MouseEventArgs e)
    {
    }
}
```

The `MouseMove` event works in conjunction with the `System.Windows.Forms.MouseEventHandler` delegate. This delegate can only call methods where the first parameter is a `System.Object`, while the second is of type `MouseEventArgs`. This type contains various members that provide detailed information about the state of the event when mouse-centric events occur:

```
public class MouseEventArgs : EventArgs
{
    public MouseEventArgs(MouseButtons button, int clicks, int x,
        int y, int delta);

    public MouseButtons Button { get; }
    public int Clicks { get; }
    public int Delta { get; }
    public Point Location { get; }
    public int X { get; }
    public int Y { get; }
}
```

Most of the public properties are self-explanatory, but Table A-8 provides more specific details.

Table A-8. Properties of the `MouseEventArgs` Type

Property	Meaning in Life
Button	Gets which mouse button was pressed, as defined by the <code>MouseButtons</code> enumeration.
Clicks	Gets the number of times the mouse button was pressed and released.


Table A-8. Properties of the MouseEventArgs Type (continued)

Property	Meaning in Life
Delta	Gets a signed count of the number of detents (which represents a single notch of the mouse wheel) for the current mouse rotation.
Location	Returns a Point that contains the current X and Y location of the mouse.
X	Gets the x-coordinate of a mouse click.
Y	Gets the y-coordinate of a mouse click.

Now it's time to implement your `MouseMove` handler to display the current X- and Y-position of the mouse on the Form's caption; you do this using the `Location` property:

```
private void MainWindow_MouseMove(object sender, MouseEventArgs e)
{
    Text = string.Format("Mouse Position: {0}", e.Location);
}
```

When you run the application and move the mouse over the window, you find the position displayed on the title area of your `MainWindow` type (see Figure A-13).

**Figure A-13.** Intercepting mouse movements

Determining Which Mouse Button Was Clicked

Another common mouse-centric detail to attend to is determining which button has been clicked when a `MouseUp`, `MouseDown`, `MouseClicked`, or `MouseDoubleClick` event occurs. When you wish to determine exactly which button was clicked (whether left, right, or middle), you need to examine the `Button` property of the `EventArgs` class. The value of the `Button` property is constrained by the related `MouseButtons` enumeration:

```
public enum MouseButtons
{
    Left,
```

```

    Middle,
    None,
    Right,
    XButton1,
    XButton2
}

```

Note The XButton1 and XButton2 values allow you to capture forward and backwards navigation buttons that are supported on many mouse-controller devices.

You can see this in action by handling the `MouseDown` event on your `MainWindow` type using the Properties window. The following `MouseDown` event handler displays which mouse button was clicked inside a message box:

```

private void MainWindow_MouseDown (object sender, MouseEventArgs e)
{
    // Which mouse button was clicked?
    if(e.Button == MouseButtons.Left)
        MessageBox.Show("Left click!");
    if(e.Button == MouseButtons.Right)
        MessageBox.Show("Right click!");
    if (e.Button == MouseButtons.Middle)
        MessageBox.Show("Middle click!");
}

```

Determining Which Key Was Pressed

Windows applications typically define numerous input controls (e.g., the `TextBox`) where the user can enter information using the keyword. When you capture keyboard input in this manner, you do not need to handle keyboard events explicitly because you can extract the textual data from the control using various properties (e.g., the `Text` property of the `TextBox` type).

However, if you need to monitor keyboard input for more exotic purposes (e.g., filtering keystrokes on a control or capturing keypresses on the form itself), the base class libraries provide the `KeyUp` and `KeyDown` events. These events work in conjunction with the `KeyEventHandler` delegate, which can point to any method taking an `object` as the first parameter and `KeyEventArgs` as the second. You define this type like this:

```

public class KeyEventArgs : EventArgs
{
    public KeyEventArgs(Keys keyData);

    public virtual bool Alt { get; }
    public bool Control { get; }
    public bool Handled { get; set; }
    public Keys KeyCode { get; }
    public Keys KeyData { get; }
}

```

```

public int KeyValue { get; }
public Keys Modifiers { get; }
public virtual bool Shift { get; }
public bool SuppressKeyPress { get; set; }
}

```

Table A-9 documents some of the more interesting properties supported by `KeyEventArgs`.

Table A-9. Properties of the `KeyEventArgs` Type

Property	Meaning in Life
Alt	Gets a value that indicates whether the Alt key was pressed.
Control	Gets a value that indicates whether the Ctrl key was pressed.
Handled	Gets or sets a value that indicates whether the event was fully handled in your handler.
KeyCode	Gets the keyboard code for a <code>KeyDown</code> or <code>KeyUp</code> event.
Modifiers	Indicates which modifier keys (e.g., Ctrl, Shift, and/or Alt) were pressed.
Shift	Gets a value that indicates whether the Shift key was pressed.

You can see this in action by handling the `KeyDown` event as follows:

```

private void MainWindow_KeyDown(object sender, KeyEventArgs e)
{
    Text = string.Format("Key Pressed: {0} Modifiers: {1}",
        e.KeyCode.ToString(), e.Modifiers.ToString());
}

```

Now compile and run your program. You should be able to determine which mouse button was clicked, as well as which keyboard key was pressed. For example, Figure A-14 shows the result of pressing the Ctrl and Shift keys simultaneously.




Figure A-14. Intercepting keyboard activity

■ **Source Code** You can find the MouseAndKeyboardEventsApp project under the Appendix A subdirectory.

Designing Dialog Boxes

Within a graphical user interface program, dialog boxes tend to be the primary way to capture user input for use within the application itself. Unlike other GUI APIs you might have used previously, there Windows Forms has no Dialog base class. Rather, dialog boxes under Windows Forms are simply types that derive from the Form class.

In addition, many dialog boxes are intended to be nonsizable; therefore, you typically want to set the FormBorderStyle property to FormBorderStyle.FixedSingle. Also, dialog boxes typically set the MinimizeBox and MaximizeBox properties to false. In this way, the dialog box is configured to be a fixed constant. Finally, if you set the ShowInTaskbar property to false, you will prevent the form from being visible in the Windows taskbar.

Let's look at how to build and manipulate dialog boxes. Begin by creating a new Windows Forms Application project named CarOrderApp and rename the initial Form1.cs file to MainWindow.cs using Solution Explorer. Next, use the Forms designer to create a simple File ➤ Exit menu, as well as a Tool ➤ Order Automobile... menu item (remember: you create a menu by dragging a ToolStrip from the Toolbox and then configuring the menu items in the designer window). Once you do this, handle the Click event for the Exit and Order Automobile submenus using the Properties window.

You implement the File ➤ Exit menu handler so it terminates the application with a call to Close():

```
private void exitToolStripMenuItem_Click(object sender, EventArgs e)
{
    Close();
}
```

Now use the Project menu of Visual Studio to select the Add Windows Forms menu option and name your new form OrderAutoDialog.cs (see Figure A-15).

For this example, design a dialog box that has the expected OK and Cancel buttons (named btnOK and btnCancel, respectively), as well as three TextBox controls named txtMake, txtColor, and txtPrice. Now use the Properties window to finalize the design of your dialog box, as follows:

- Set the FormBorderStyle property to FixedDialog.
- Set the MinimizeBox and MaximizeBox properties to false.
- Set theStartPosition property to CenterParent.
- Set the ShowInTaskbar property to false.




Figure A-15. Inserting new dialog boxes using Visual Studio

The DialogResult Property

Finally, select the OK button and use the Properties window to set the `DialogResult` property to `OK`. Similarly, you can set the `DialogResult` property of the Cancel button to (you guessed it) `Cancel`. As you will see in a moment, the `DialogResult` property is quite useful because it enables the launching form to determine quickly which button the user has clicked; this enables you to take the appropriate action. You can set the `DialogResult` property to any value from the related `DialogResult` enumeration:

```
public enum DialogResult
{
    Abort, Cancel, Ignore, No,
    None, OK, Retry, Yes
}
```

Figure A-16 shows one possible design of your dialog box; it even adds in a few descriptive Label controls.




Figure A-16. The OrderAutoDialog type

Configuring the Tab Order

You have created a somewhat interesting dialog box; the next step is formalize the tab order. As you might know, users expect to be able to shift focus using the Tab key when a form contains multiple GUI widgets. Configuring the tab order for your set of controls requires that you understand two key properties: `TabStop` and `TabIndex`.

You can set the `TabStop` property to true or false, based on whether or not you wish this GUI item to be reachable using the Tab key. Assuming that you set the `TabStop` property to true for a given control, you can use the `TabIndex` property to establish the order of activation in the tabbing sequence (which is zero-based), as in this example:

```
// Configure tabbing properties.
txtMake.TabIndex = 0;
txtMake.TabStop = true;
```

The Tab Order Wizard

You can set the `TabStop` and `TabIndex` manually using the Properties window; however, the Visual Studio 2010 IDE supplies a Tab Order Wizard that you can access by choosing View ▶ Tab Order (be aware that you will not find this menu option unless the Forms designer is active). Once activated, your design-time form displays the current `TabIndex` value for each widget. To change these values, click each item in the order you prefer the controls to tab (see Figure A-17).




Figure A-17. The Tab Order Wizard

You can exit the Tab Order Wizard by pressing the Esc key.

Setting the Form's Default Input Button

Many user-input forms (especially dialog boxes) have a particular button that automatically responds to the user pressing the Enter key. Now assume that you want the Click event handler for btnOK invoked when the user presses the Enter key. Doing so is as simple as setting the form's AcceptButton property as follows (you can establish this same setting using the Properties window):

```
public partial class OrderAutoDialog : Form
{
    public OrderAutoDialog()
    {
        InitializeComponent();

        // When the Enter key is pressed, it is as if
        // the user clicked the btnOK button.
        this.AcceptButton = btnOK;
    }
}
```

■ **Note** Some forms require the ability to simulate clicking the form's Cancel button when the user presses the Esc key. You can accomplish this by assigning the CancelButton property of the Form to the Button object that represents the clicking of the Cancel button.

Displaying Dialog Boxes

When you wish to display a dialog box, you must first decide whether you wish to launch the dialog box in a *modal* or *modeless* fashion. As you might know, modal dialog boxes must be dismissed by the user before he can return to the window that launched the dialog box in the first place; for example, most About boxes are modal in nature. To show a modal dialog box, call `ShowDialog()` off your dialog box object. On the other hand, you can display a modeless dialog box by calling `Show()`, which allows the user to switch focus between the dialog box and the main window (e.g., a Find/Replace dialog box).

For this example, you want to update the Tools ► Order Automobile... menu handler of the `MainWindow` type to show the `OrderAutoDialog` object in a modal manner. Consider the following initial code:

```
private void orderAutomobileToolStripMenuItem_Click(object
    sender, EventArgs e)
{
    // Create your dialog object.
    OrderAutoDialog dlg = new OrderAutoDialog();

    // Show as modal dialog box, and figure out which button
    // was clicked using the DialogResult return value.
    if (dlg.ShowDialog() == DialogResult.OK)
    {
        // They clicked OK, so do something...
    }
}
```

Note You can optionally call the `ShowDialog()` and `Show()` methods by specifying an object that represents the owner of the dialog box (which for the form loading the dialog box would be represented by `this`). Specifying the owner of a dialog box establishes the z-ordering of the form types and also ensures (in the case of a modeless dialog box) that all owned windows are also disposed of when the main window is destroyed.

Be aware that when you create an instance of a `Form`-derived type (`OrderAutoDialog` in this case), the dialog box is *not* visible on the screen, but simply allocated into memory. It is not until you call `Show()` or `ShowDialog()` that the form becomes visible. Also, notice that `ShowDialog()` returns the `DialogResult` value that has been assigned to the button (the `Show()` method simply returns `void`).

Once `ShowDialog()` returns, the form is no longer visible on the screen, but is still in memory. This means you can extract the values in each `TextBox`. However, you will receive compiler errors if you attempt to compile the following code:

```
private void orderAutomobileToolStripMenuItem_Click(object sender, EventArgs e)
{
    // Create your dialog object.
    OrderAutoDialog dlg = new OrderAutoDialog();

    // Show as modal dialog box, and figure out which button
```

```
// was clicked using the DialogResult return value.
if (dlg.ShowDialog() == DialogResult.OK)
{
    // Get values in each text box? Compiler errors!
    string orderInfo = string.Format("Make: {0}, Color: {1}, Cost: {2}",
        dlg.txtMake.Text, dlg.txtColor.Text, dlg.txtPrice.Text);
    MessageBox.Show(orderInfo, "Information about your order!");
}
```

The reason you get compiler errors is that Visual Studio 2010 declares the controls you add to the Forms designer as *private* member variables of the class! You can verify this fact by opening the OrderAutoDialog.Designer.cs file.

While a prim-and-proper dialog box might preserve encapsulation by adding public properties to get and set the values within these text boxes, you can take a shortcut and redefine them by using the **public** keyword. To do so, select each TextBox on the designer, and then set the **Modifiers** property of the control to **Public** using the Properties window. This changes the underlying designer code:

```
partial class OrderAutoDialog
{
    ...
    // Form member variables are defined within the designer-maintained file.
    public System.Windows.Forms.TextBox txtMake;
    public System.Windows.Forms.TextBox txtColor;
    public System.Windows.Forms.TextBox txtPrice;
}
```

At this point, you can compile and run your application. Once you launch your dialog box, you should be able to see the input data displayed within a message box (provided you click the OK button).

Understanding Form Inheritance

So far, each one of your custom windows/dialog boxes in this chapter has derived directly from **System.Windows.Forms.Form**. However, one intriguing aspect of Windows Forms development is the fact that **Form** types can function as the base class to derived Forms. For example, assume you create a .NET code library that contains each of your company's core dialog boxes. Later, you decide that your company's About box is a bit on the bland side, and you wish to add a 3D image of your company logo. Rather than having to re-create the entire About box, you can extend the basic About box, thereby inheriting the core look-and-feel:

```
// ThreeDAboutBox "is-a" AboutBox
public partial class ThreeDAboutBox : AboutBox
{
    // Add code to render company logo...
```

To see form inheritance in action, insert a new form into your project using the Project ► Add Windows Form menu option. This time, however, pick the Inherited Form icon, and name your new form **ImageOrderAutoDialog.cs** (see Figure A-18).




Figure A-18. Adding a derived form to your project

This option brings up the Inheritance Picker dialog box, which shows you each of the forms in your current project. Notice that the Browse button allows you to pick a form in an external .NET assembly. Here, simply pick your OrderAutoDialog class.

Note You must compile your project at least one time to see the forms of your project in the Inheritance Picker dialog box because this tool reads from the assembly metadata to show you your options.

Once you click the OK button, the visual designer tools show each of the base controls on your parent controls; each control has a small arrow icon mounted on the upper-left of the control (symbolizing inheritance). To complete your derived dialog box, locate the PictureBox control from the Common Controls section of the Toolbox and add one to your derived form. Next, use the Image property to select an image file of your choosing. Figure A-19 shows one possible UI, using a (crude) hand drawing of a junker automobile (a lemon!).




Figure A-19. The UI of the ImageOrderAutoDialog class

With this, you can now update the Tools ► Order Automobile... Click event handler to create an instance of your derived type, rather than the OrderAutoDialog base class:

```
private void orderAutomobileToolStripMenuItem_Click(object sender, EventArgs e)
{
    // Create the derived dialog object.
    ImageOrderAutoDialog dlg = new ImageOrderAutoDialog();
    ...
}
```

■ **Source Code** You can find the CarOrderApp project under the Appendix A subdirectory.

Rendering Graphical Data Using GDI+

Many GUI applications require the ability to generate graphical data dynamically for display on the surface of a window. For example, perhaps you have selected a set of records from a relational database and wish to render a pie chart (or bar chart) that visually shows items in stock. Or, perhaps you want to re-create some old-school video game using the .NET platform. Regardless of your goal, GDI+ is the API to use when you need to render data graphically within a Windows Forms application. This technology is bundled within the `System.Drawing.dll` assembly, which defines a number of namespaces (see Figure A-20).




Figure A-20. The namespaces of `System.Drawing.dll`

■ **Note** A friendly reminder: WPF has its own graphical rendering subsystem and API; you use GDI+ only within a Windows Forms application.

Table A-10 documents the role of the key GDI+ namespaces at a high level.

Table A-10. Core GDI+ Namespaces

Namespace	Meaning in Life
<code>System.Drawing</code>	This is the core GDI+ namespace that defines numerous types for basic rendering (e.g., fonts, pens, and basic brushes), as well as the almighty <code>Graphics</code> type.
<code>System.Drawing.Drawing2D</code>	This namespace provides types used for more advanced 2D/vector graphics functionality (e.g., gradient brushes, pen caps, and geometric transforms).
<code>System.Drawing.Imaging</code>	This namespace defines types that allow you to manipulate graphical images (e.g., change the palette, extract image metadata, manipulate metafiles, etc.).
<code>System.Drawing.Printing</code>	This namespace defines types that allow you to render images to the printed page, interact with the printer itself, and format the overall appearance of a given print job.
<code>System.Drawing.Text</code>	This namespace allows you to manipulate collections of fonts.

The System.Drawing Namespace

You can find the vast majority of the types you'll use when programming GDI+ applications in the `System.Drawing` namespace. As you might expect, you can find classes that represent images, brushes, pens, and fonts. `System.Drawing` also defines a several related utility types, such as `Color`, `Point`, and `Rectangle`. Table A-11 lists some (but not all) of the core types.

Table A-11. Core Types of the `System.Drawing` Namespace

Type	Meaning in Life
<code>Bitmap</code>	This type encapsulates image data (*.bmp or otherwise).
<code>Brush</code> <code>Brushes</code> <code>SolidBrush</code> <code>SystemBrushes</code> <code>TextureBrush</code>	You use brush objects to fill the interiors of graphical shapes, such as rectangles, ellipses, and polygons.
<code>BufferedGraphics</code>	This type provides a graphics buffer for double buffering, which you use to reduce or eliminate flicker caused by redrawing a display surface.
<code>Color</code> <code>SystemColors</code>	The <code>Color</code> and <code>SystemColors</code> types define a number of static read-only properties you use to obtain specific colors for the construction of various pens/brushes.
<code>Font</code> <code>FontFamily</code>	The <code>Font</code> type encapsulates the characteristics of a given font (e.g., type name, bold, italic, and point size). <code>FontFamily</code> provides an abstraction for a group of fonts that have a similar design, but also certain variations in style.
<code>Graphics</code>	This core class represents a valid drawing surface, as well as several methods to render text, images, and geometric patterns.
<code>Icon</code> <code>SystemIcons</code>	These classes represent custom icons, as well as the set of standard system-supplied icons.
<code>Image</code> <code>ImageAnimator</code>	<code>Image</code> is an abstract base class that provides functionality for the <code>Bitmap</code> , <code>Icon</code> , and <code>Cursor</code> types. <code>ImageAnimator</code> provides a way to iterate over a number of <code>Image</code> -derived types at some specified interval.
<code>Pen</code> <code>Pens</code> <code>SystemPens</code>	Pens are objects you use to draw lines and curves. The <code>Pens</code> type defines several static properties that return a new <code>Pen</code> of a given color.
<code>Point</code> <code>PointF</code>	These structures represent an (x, y) coordinate mapping to an underlying integer or float, respectively.

Table A-11. Core Types of the System.Drawing Namespace (continued)

Type	Meaning in Life
Rectangle	These structures represent a rectangular dimension (again, these map to an underlying integer or float).
RectangleF	
Size	These structures represent a given height/width (again, these map to an underlying integer or float).
SizeF	
StringFormat	You use this type to encapsulate various features of textual layout (e.g., alignment and line spacing).
Region	This type describes the interior of a geometric image composed of rectangles and paths.

The Role of the Graphics Type

The `System.Drawing.Graphics` class serves as the gateway to GDI+ rendering functionality. This class not only represents the surface you wish to draw upon (such as a form's surface, a control's surface, or a region of memory), but also defines dozens of members that allow you to render text, images (e.g., icons and bitmaps), and numerous geometric patterns. Table A-12 gives a partial list of members.

Table A-12. Select Members of the Graphics Class

Method	Meaning in Life
FromHdc()	These static methods provide a way to obtain a valid <code>Graphics</code> object from a given image (e.g., icon and bitmap) or GUI control.
FromHwnd()	
FromImage()	
Clear()	This method fills a <code>Graphics</code> object with a specified color, erasing the current drawing surface in the process.
DrawArc()	You use these methods to render a given image or geometric pattern.
DrawBeziers()	All <code>DrawXXX()</code> methods require that you use GDI+ Pen objects.
DrawCurve()	
DrawEllipse()	
DrawIcon()	
DrawLine()	
DrawLines()	
DrawPie()	
DrawPath()	
DrawRectangle()	
DrawRectangles()	
DrawString()	

Table A-12. Select Members of the Graphics Class (continued)

Method	Meaning in Life
FillEllipse()	You use these methods to fill the interior of a given geometric shape.
FillPie()	All FillXXX() methods require that you use GDI+ Brush objects.
FillPolygon()	
FillRectangle()	
FillPath()	

Note that you cannot create the `Graphics` class directly using the new keyword because there are no publicly defined constructors. So, how do you obtain a valid `Graphics` object? I'm glad you asked!

Obtaining a Graphics Object with the Paint Event

The most common way to obtain a `Graphics` object is to use the Visual Studio 2010 Properties window to handle the `Paint` event on the window you want to render upon. This event is defined in terms of the `PaintEventHandler` delegate, which can point to any method taking a `System.Object` as the first parameter and a `PaintEventArgs` as the second.

The `PaintEventArgs` parameter contains the `Graphics` object you need to render onto the Form's surface. For example, create a new Windows Application project named `PaintEventApp`. Next, use Solution Explorer to rename your initial `Form.cs` file to `MainWindow.cs`, and then handle the `Paint` event using the Properties window. This creates the following stub code:

```
public partial class MainWindow : Form
{
    public MainWindow()
    {
        InitializeComponent();
    }

    private void MainWindow_Paint(object sender, PaintEventArgs e)
    {
        // Add your painting code here!
    }
}
```

Now that you have handled the `Paint` event, you might wonder when it will fire. The `Paint` event fires whenever a window becomes *dirty*; a window is considered dirty whenever it is resized, uncovered by another window (partially or completely), or minimized and then restored. In all these cases, the .NET platform ensures that the `Paint` event handler is called automatically whenever your `Form` needs to be redrawn. Consider the following implementation of `MainWindow_Paint()`:

```
private void MainWindow_Paint(object sender, PaintEventArgs e)
{
    // Get the graphics object for this Form.
    Graphics g = e.Graphics;

    // Draw a circle.
    g.FillEllipse(Brushes.Blue, 10, 20, 150, 80);
```

```

// Draw a string in a custom font.
g.DrawString("Hello GDI+", new Font("Times New Roman", 30),
    Brushes.Red, 200, 200);

// Draw a line with a custom pen.
using (Pen p = new Pen(Color.YellowGreen, 10))
{
    g.DrawLine(p, 80, 4, 200, 200);
}
}

```

Once you obtain the `Graphics` object from the incoming `PaintEventArgs` parameter, you call `FillEllipse()`. Notice that this method (as well as any `Fill`-prefixed method) requires a `Brush`-derived type as the first parameter. While you could create any number of interesting brush objects from the `System.Drawing.Drawing2D` namespace (e.g., `HatchBrush` and `LinearGradientBrush`), the `Brushes` utility class provides handy access to a variety of solid-colored brush types.

Next, you make a call to `DrawString()`, which requires a string to render as its first parameter. Given this, GDI+ provides the `Font` type, which represents not only the name of the font to use when rendering the textual data, but also related characteristics, such as the point size (30, in this case). Also notice that `DrawString()` requires a `Brush` type; as far as GDI+ is concerned, "Hello GDI+" is nothing more than a collection of geometric patterns to fill on the screen. Finally, `DrawLine()` is called to render a line using a custom `Pen` type, 10 pixels wide. Figure A-21 shows the output of this rendering logic.




Figure A-21. A simple GDI+ rendering operation

■ **Note** In the preceding code, you explicitly dispose of the `Pen` object. As a rule, when you directly create a GDI+ type that implements `IDisposable`, you call the `Dispose()` method as soon as you are done with the object. Doing this lets you release the underlying resources as soon as possible. If you do not do this, the resources will eventually be freed by the garbage collector in a nondeterministic manner.

Invalidate the Form's Client Area

During the flow of a Windows Forms application, you might need to fire the Paint event in your code explicitly, rather than waiting for the window to become *naturally dirty* by the actions of the end user. For example, you might be building a program that allows the user to select from a number of predefined images using a custom dialog box. Once the dialog box is dismissed, you need to draw the newly selected image onto the form's client area. Obviously, if you were to wait for the window to become naturally dirty, the user would not see the change take place until the window was resized or uncovered by another window. To force a window to repaint itself programmatically, you call the inherited Invalidate() method:

```
public partial class MainForm : Form
{
    ...
    private void MainForm_Paint(object sender, PaintEventArgs e)
    {
        Graphics g = e.Graphics;
        // Render the correct image here.
    }

    private void GetImageFromDialog()
    {
        // Show dialog box and get new image.
        // Repaint the entire client area.
        Invalidate();
    }
}
```

The Invalidate() method has been overloaded a number of times. This allows you to specify a specific rectangular portion of the form to repaint, rather than having to repaint the entire client area (which is the default). If you wish to update only the extreme upper-left rectangle of the client area, you can write the following code:

```
// Repaint a given rectangular area of the Form.
private void UpdateUpperArea()
{
    Rectangle myRect = new Rectangle(0, 0, 75, 150);
    Invalidate(myRect);
}
```

Source Code You can find the PaintEventApp project under the Appendix A subdirectory.

Building a Complete Windows Forms Application

Let's conclude this introductory look at the Windows Forms and GDI+ APIs by building a complete GUI application that illustrates several of the techniques discussed in this chapter. The program you will create is a rudimentary painting program that allows users to select between two shape types (a circle or

rectangle) using the color of their choice to render data to the form. You will also allow end users to save their pictures to a local file on their hard drive for later use with object serialization services.

Building the Main Menu System

Begin by creating a new Windows Forms application named MyPaintProgram and rename your initial Form1.cs file to MainWindow.cs. Now design a menu system on this initial window that supports a topmost File menu that provides Save..., Load..., and Exit submenus (see Figure A-22).




Figure A-22. The File menu system

■ **Note** If you specify a single dash (-) as a menu item, you can define separators within your menu system.

Next, create a second topmost Tools menu that provides options to select a shape and color to use for rendering, as well as an option to clear the form of all graphical data (see Figure A-23).




Figure A-23. The Tools Menu System

Finally, handle the `Click` event for each one of these subitems. You will implement each handler as you progress through the example; however, you can finish up the File ► Exit menu handler by calling `Close()`:

```
private void exitToolStripMenuItem_Click(object sender, EventArgs e)
{
    Close();
}
```

Defining the ShapeData Type

Recall that this application will allow end users to select from two predefined shapes in a given color. You will provide a way to allow users to save their graphical data to a file, so you want to define a custom class type that encapsulates each of these details; for the sake of simplicity, you do this using C# automatic properties (see Chapter 5 for more details on how to do this). Begin by adding a new class to your project named `ShapeData.cs` and implementing this type as follows:

```
[Serializable]
class ShapeData
{
    // The upper left of the shape to be drawn.
    public Point UpperLeftPoint { get; set; }

    // The current color of the shape to be drawn.
    public Color Color { get; set; }

    // The type of shape.
    public SelectedShape ShapeType { get; set; }
}
```

Here, `ShapeData` uses three automatic properties that encapsulates various types of data, two of which (`Point` and `Color`) are defined in the `System.Drawing` namespace, so be sure to import this namespace into your code file. Also, notice that this type has been adorned with the `[Serializable]` attribute. In an upcoming step, you will configure your `MainWindow` type to maintain a list of `ShapeData` types that you persist using object serialization services (see Chapter 20 for more details).

Defining the ShapePickerDialog Type

You can allow the user to choose between the circle or rectangle image type by creating a simple custom dialog box named `ShapePickerDialog` (insert this new Form now). Beyond adding the obligatory OK and Cancel buttons (each of which you should assign fitting `DialogResult` values), this dialog box uses of a single `GroupBox` that maintains two `RadioButton` objects: `radioButtonCircle` and `radioButtonRect`. Figure A-24 shows one possible design.




Figure A-24. The ShapePickerDialog type

Now, open the code window for your dialog box by right-clicking the Forms designer and selecting the View Code menu option. Within the `MyPaintProgram` namespace, define an enumeration (named `SelectedShape`) that defines names for each possible shape:

```
public enum SelectedShape
{
    Circle, Rectangle
}
```

Next, update your current `ShapePickerDialog` class type:

- Add an automatic property of type `SelectedShape`. The caller can use this property to determine which shape to render.
- Handle the `Click` event for the `OK` button using the Properties window.
- Implement this event handler to determine whether the circle radio button has been selected (through the `Checked` property). If so, set your `SelectedShape` property to `SelectedShape.Circle`; otherwise, set this property to `SelectedShape.Rectangle`.

Here is the complete code:

```
public partial class ShapePickerDialog : Form
{
    public SelectedShape SelectedShape { get; set; }

    public ShapePickerDialog()
    {
        InitializeComponent();
    }

    private void btnOK_Click(object sender, EventArgs e)
    {
        if (radioButtonCircle.Checked)
            SelectedShape = SelectedShape.Circle;
        else
```

```

    SelectedShape = SelectedShape.Rectangle;
}
}

```

That wraps up the infrastructure of your program. Now all you need to do is implement the Click event handlers for the remaining menu items on the main window.

Adding Infrastructure to the MainWindow Type

Returning to the construction of the main window, add three new member variables to this Form. These member variables allow you to keep track of the selected shape (through a SelectedShape enum member variable), the selected color (represented by a System.Drawing.Color member variable), and through each of the rendered images held in a generic List<T> (where T is of type ShapeData):

```

public partial class MainWindow : Form
{
    // Current shape / color to draw.
    private SelectedShape currentShape;
    private Color currentColor = Color.DarkBlue;

    // This maintains each ShapeData.
    private List<ShapeData> shapes = new List<ShapeData>();
    ...
}

```

Next, you handle the MouseDown and Paint events for this Form-derived type using the Properties window. You will implement them in a later step; for the time being, however, you should find that the IDE has generated the following stub code:

```

private void MainWindow_Paint(object sender, PaintEventArgs e)
{
}

private void MainWindow_MouseDown(object sender, MouseEventArgs e)
{
}

```

Implementing the Tools Menu Functionality

You can allow a user to set the currentShape member variable by implementing the Click handler for the Tools ▶ Pick Shape... menu option. You use this to launch your custom dialog box; based on a user's selection, you assign this member variable accordingly:

```

private void pickShapeToolStripMenuItem_Click(object sender, EventArgs e)
{
    // Load our dialog box and set the correct shape type.
    ShapePickerDialog dlg = new ShapePickerDialog();
    if (DialogResult.OK == dlg.ShowDialog())
    {
}

```

```

        currentShape = dlg.SelectedShape;
    }
}

```

You can let a user set the `currentColor` member variable by implementing the `Click` event handler for the Tools ► Pick Color... menu so it uses the `System.Windows.Forms.ColorDialog` type:

```

private void pickColorToolStripMenuItem_Click(object sender, EventArgs e)
{
    ColorDialog dlg = new ColorDialog();

    if (dlg.ShowDialog() == DialogResult.OK)
    {
        currentColor = dlg.Color;
    }
}

```

If you were to run your program as it now stands and select the Tools ► Pick Color menu option, you would get the dialog box shown in Figure A-25.




Figure A-25. The stock `ColorDialog` type

Finally, you implement the Tools ► Clear Surface menu handler so it empties the contents of the `List<T>` member variable and programmatically fires the `Paint` event using a call to `Invalidate()`:

```

private void clearSurfaceToolStripMenuItem_Click(object sender, EventArgs e)
{
    shapes.Clear();

    // This will fire the paint event.
    Invalidate();
}

```

Capturing and Rendering the Graphical Output

Given that a call to `Invalidate()` fires the `Paint` event, you need to author code within the `Paint` event handler. Your goal is to loop through each item in the (currently empty) `List<T>` member variable and render a circle or square at the current mouse location. The first step is to implement the `MouseDown` event handler and insert a new `ShapeData` type into the generic `List<T>` type, based on the user-selected color, shape type, and current location of the mouse:

```
private void MainWindow_MouseDown(object sender, MouseEventArgs e)
{
    // Make a ShapeData type based on current user
    // selections.
    ShapeData sd = new ShapeData();
    sd.ShapeType = currentShape;
    sd.Color = currentColor;
    sd.UpperLeftPoint = new Point(e.X, e.Y);

    // Add to the List<T> and force the form to repaint itself.
    shapes.Add(sd);
    Invalidate();
}
```

At this point, you can implement your `Paint` event handler:

```
private void MainWindow_Paint(object sender, PaintEventArgs e)
{
    // Get the Graphics object for this window.
    Graphics g = e.Graphics;

    // Render each shape in the selected color.
    foreach (ShapeData s in shapes)
    {
        // Render a rectangle or circle 20 x 20 pixels in size
        // using the correct color.
        if (s.ShapeType == SelectedShape.Rectangle)
            g.FillRectangle(new SolidBrush(s.Color),
                           s.UpperLeftPoint.X, s.UpperLeftPoint.Y, 20, 20);
        else
            g.FillEllipse(new SolidBrush(s.Color),
                          s.UpperLeftPoint.X, s.UpperLeftPoint.Y, 20, 20);
    }
}
```

If you run your application at this point, you should be able to render any number of shapes in a variety of colors (see Figure A-26).




Figure A-26. *MyPaintProgram* in action

Implementing the Serialization Logic

The final aspect of this project involves implementing Click event handlers for the File ► Save... and File ► Load... menu items. Given that ShapeData has been marked with the [Serializable] attribute (and given that List<T> itself is serializable), you can quickly save out the current graphical data using the Windows Forms SaveFileDialog type. Begin by updating your using directives to specify you are using the System.Runtime.Serialization.Formatters.Binary and System.IO namespaces:

```
// For the binary formatter.
using System.Runtime.Serialization.Formatters.Binary;
using System.IO;
```

Now update your File ► Save... handler, as follows:

```
private void saveToolStripMenuItem_Click(object sender, EventArgs e)
{
    using (SaveFileDialog saveDlg = new SaveFileDialog())
    {
        // Configure the look and feel of the save dialog box.
        saveDlg.InitialDirectory = ".";
        saveDlg.Filter = "Shape files (*.shapes)|*.shapes";
        saveDlg.RestoreDirectory = true;
        saveDlg.FileName = "MyShapes";

        // If they click the OK button, open the new
        // file and serialize the List<T>.
        if (saveDlg.ShowDialog() == DialogResult.OK)
        {
            Stream myStream = saveDlg.OpenFile();
            if ((myStream != null))
            {
                // Save the shapes!
            }
        }
    }
}
```

```
        BinaryFormatter myBinaryFormat = new BinaryFormatter();
        myBinaryFormat.Serialize(myStream, shapes);
        myStream.Close();
    }
}
}
```

The File ► Load event handler opens the selected file and deserializes the data back into the List<T> member variable with the help of the Windows Forms OpenFileDialog type:

```
private void loadToolStripMenuItem_Click(object sender, EventArgs e)
{
    using (OpenFileDialog openDlg = new OpenFileDialog())
    {
        openDlg.InitialDirectory = ".";
        openDlg.Filter = "Shape files (*.shapes)|*.shapes";
        openDlg.RestoreDirectory = true;
        openDlg.FileName = "MyShapes";

        if (openDlg.ShowDialog() == DialogResult.OK)
        {
            Stream myStream = openDlg.OpenFile();
            if ((myStream != null))
            {
                // Get the shapes!
                BinaryFormatter myBinaryFormat = new BinaryFormatter();
                shapes = (List<ShapeData>)myBinaryFormat.Deserialize(myStream);
                myStream.Close();
                Invalidate();
            }
        }
    }
}
```

After Chapter 20, the overall serialization logic here should look familiar. It is worth pointing out that the `SaveFileDialog` and `OpenFileDialog` types both support a `Filter` property that is assigned a rather cryptic string value. This filter controls a number of settings for the save/open dialog boxes, such as the file extension (*.shapes). You use the `FileName` property to control what the default name of the file you want to create—`MyShapes`, in this example.

At this point, your painting application is complete. You should now be able to save and load your current graphical data to any number of *.shapes files. If you want to enhance this Windows Forms program, you might wish to account for additional shapes, or even to allow the user to control the size of the shape to draw or perhaps select the format used to save the data (e.g., binary, XML, or SOAP; see Chapter 20).

Summary

This chapter examined the process of building traditional desktop applications using the Windows Forms and GDI+ APIs, which have been part of the .NET Framework since version 1.0. At minimum, a Windows Forms application consists of a type-extending `Form` and a `Main()` method that interacts with the `Application` type.

When you want to populate your forms with UI elements (e.g., menu systems and GUI input controls), you do so by inserting new objects into the inherited `Controls` collection. This chapter also showed you how to capture mouse, keyboard, and rendering events. Along the way, you learned about the `Graphics` type and many ways to generate graphical data at runtime.

As mentioned in this chapter's overview, the Windows Forms API has been (in some ways) superseded by the WPF API introduced with the release of .NET 3.0 (which you learned about in some detail in Part 6 of this book). While it is true that WPF is the choice for supercharged UI front ends, the Windows Forms API remains the simplest (and in many cases, most direct) way to author standard business applications, in-house applications, and simple configuration utilities. For these reasons, Windows Forms will be part of the .NET base class libraries for years to come.



Platform-Independent .NET Development with Mono

This appendix introduces you to the topic of cross-platform C# and .NET development using an open source implementation of .NET named *Mono* (in case you are wondering about the name, *mono* is a Spanish word for monkey, which is a reference to the various monkey-mascots used by the initial creators of the Mono platform, Ximian Corporation). In this appendix, you will learn about the role of the Common Language Infrastructure (CLI), the overall scope of Mono, and various Mono development tools. At the conclusion of this appendix—and given your work over the course of this book—you will be in a perfect position to dig further into Mono development as you see fit.

Note If you require a detailed explanation of cross-platform .NET development, I recommend picking up a copy of *Cross-Platform .NET Development: Using Mono, Portable .NET, and Microsoft .NET* by Mark Easton and Jason King (Apress, 2004).

The Platform-Independent Nature of .NET

Historically speaking, when programmers used a Microsoft development language (e.g., VB6) or Microsoft programming framework (e.g., MFC, COM, or ATL), they had to resign themselves to building software that (by-and-large) executed only on the Windows family of operating systems. Many .NET developers, accustomed to previous Microsoft development options, are frequently surprised when they learn that .NET is *platform-independent*. But it's true. You can create, compile, and execute .NET assemblies on operating systems other than Microsoft Windows.

Using open source .NET implementations such as Mono, your .NET applications can find happy homes on numerous operating systems, including Mac OS X, Solaris, AIX, and numerous flavors of Unix/Linux. Mono also provides an installation package for (surprise, surprise) Microsoft Windows. Thus, it is possible to build and run .NET assemblies on the Windows operating system, without ever installing the Microsoft .NET Framework 4.0 SDK or the Visual Studio 2010 IDE.

■ **Note** Be aware that the Microsoft .NET Framework 4.0 SDK and Visual Studio 2010 are your best options for building .NET software for the Windows family of operating systems.

Even after developers learn about .NET code's cross-platform capabilities, they often assume that the scope of platform-independent .NET development is limited to little more than *Hello World* console applications. The reality is that you can build production-ready assemblies that use ADO.NET, Windows Forms (in addition to alternative GUI toolkits such as GTK# and Cocoa#), ASP.NET, LINQ, and XML web services by taking advantage of many of the core namespaces and language features you have seen featured throughout this book.

The Role of the CLI

.NET's cross-platform capabilities are implemented differently than the approach taken by Sun Microsystems and its handling of the Java programming platform. Unlike Java, Microsoft itself does not provide .NET installers for Mac, Linux, and so on. Rather, Microsoft has released a set of formalized specifications that other entities can use as a road map for building .NET distributions for their platform(s) of choice. Collectively, these specifications are termed the *Common Language Infrastructure* (CLI).

As briefly mentioned in Chapter 1, Microsoft submitted two formal specifications to ECMA (European Computer Manufacturers Association) when it released C# and the .NET platform to the world at large. Once approved, Microsoft submitted these same specifications to the International Organization for Standardization (ISO), and these specifications were ratified shortly thereafter.

So, why should you care? These two specifications provide a road map for other companies, developers, universities, and other organizations to build their own custom distributions of the C# programming language and the .NET platform. The two specifications in question are:

- *ECMA-334*: Defines the syntax and semantics of the C# programming language.
- *ECMA-335*: Defines many details of the .NET platform, collectively called the *Common Language Infrastructure*.

ECMA-334 tackles the lexical grammar of C# in an extremely rigorous and scientific manner (as you might guess, this level of detail is quite important to those who want to implement a C# compiler). However, ECMA-335 is the meatier of the two specifications, so much so that it has been broken down into six partitions (see Table B-1).

Table B-1. ECMA-335 Specification Partitions

ECMA-335 Partition	Meaning in Life
Partition I: Concepts and Architecture	Describes the overall architecture of the CLI, including the rules of the Common Type System, the Common Language Specification, and the mechanics of the .NET runtime engine.
Partition II: Metadata Definition and Semantics	Describes the details of the .NET metadata format.
Partition III: CIL Instruction Set	Describes the syntax and semantics of the common intermediate language (CIL) programming language.
Partition IV: Profiles and Libraries	Provides a high-level overview of the minimal and complete class libraries that must be supported by a CLI-compatible .NET distribution.
Partition V: Debug Interchange Formats	Provides details of the portable debug interchange format (CILDB). Portable CILDB files provide a standard way to exchange debugging information between CLI producers and consumers.
Partition VI: Annexes	Represents a collection of <i>odds and ends</i> ; it clarifies topics such as class library design guidelines and the implementation details of a CIL compiler.

The point of this appendix is not to dive into the details of the ECMA-334 and ECMA-335 specifications—nor must you know the ins-and-outs of these documents to understand how to build platform-independent .NET assemblies. However, if you are interested, you can download both of these specifications for free from the ECMA website (<http://www.ecma-international.org/publications/standards>).

The Mainstream CLI Distributions

To date, you can find two mainstream implementations of the CLI beyond Microsoft's CLR, Microsoft Silverlight, and the Microsoft .NET Compact Framework (see Table B-2).

Table B-2. Mainstream .NET CLI Distributions

CLI Distribution	Supporting Website	Meaning in Life
Mono	www.mono-project.com	Mono is an open source and commercially supported distribution of .NET sponsored by Novell Corporation. Mono is targeted to run on many popular flavors of Unix/Linux, Mac OS X, Solaris, and Windows.
Portable .NET	www.dotgnu.org	Portable .NET is distributed under the GNU General Public License. As the name implies, Portable .NET intends to function on as many operation systems and architectures as possible, including esoteric platforms such as BeOS, Microsoft Xbox, and Sony PlayStation (no, I'm not kidding about the last two!).

Each of the CLI implementations shown in Table B-2 provide a fully function C# compiler, numerous command-line development tools, a global assembly cache (GAC) implementation, sample code, useful documentation, and dozens of assemblies that constitute the base class libraries.

Beyond implementing the core libraries defined by Partition IV of ECMA-335, Mono and Portable .NET provide Microsoft-compatible implementations of `mscorlib.dll`, `System.Core.dll`, `System.Data.dll`, `System.Web.dll`, `System.Drawing.dll`, and `System.Windows.Forms.dll` (among many others).

The Mono and Portable .NET distributions also ship with a handful of assemblies specifically targeted at Unix/Linux and Mac OS X operating systems. For example, `Cocoa#` is a .NET wrapper around the preferred Mac OS GUI toolkit, Cocoa. In this appendix, I will not dig into these OS-specific binaries; instead, I'll focus on using the OS-agnostic programming stacks.

■ **Note** This appendix will not examine Portable .NET; however, it is important to know that Mono is not the only platform-independent distribution of the .NET platform available today. I recommend you take some time to play around with Portable .NET in addition to the Mono platform.

The Scope of Mono

Given that Mono is an API built on existing ECMA specifications that originated from Microsoft, you would be correct in assuming that Mono is playing a constant game of catch up as newer versions of Microsoft's .NET platform are released. At the time of this writing, Mono is compatible with C# 2008 (work on the new C# 2010 language features are in development as I type) and .NET 2.0. This means you can build ASP.NET websites, Windows Forms applications, database-centric applications using ADO.NET, and (of course) simple console applications.

Currently, Mono is *not* completely compatible with the new features of C# 2010 (e.g., optional arguments and the dynamic keyword) or with all aspects of .NET 3.0-4.0. This means that Mono applications are currently unable (again, at the time of this writing) to use the following Microsoft .NET APIs:

- Windows Presentation Foundation (WPF)
- Windows Communication Foundation (WCF)
- Windows Workflow Foundation (WF)
- LINQ to Entities (however, LINQ to Objects and LINQ to XML are supported)
- Any C# 2010 specific language features

Some of these APIs might eventually become part of the standard Mono distribution stacks. For example, according to the Mono website, future versions of the platform (2.8-3.0) will provide support for C# 2010 language features and .NET 3.5-4.0 platform features.

In addition to keeping-step with Microsoft's core .NET APIs and C# language features, Mono also provides an open source distribution of the Silverlight API named *Moonlight*. This enables browsers that run under Linux based operating systems to host and use Silverlight / Moonlight web applications. As you might already know, Microsoft's Silverlight already includes support for Mac OS X; and given the Moonlight API, this technology has truly become cross-platform.

Mono also supports some .NET based technologies that do *not* have a direct Microsoft equivalent. For example, Mono ships with GTK#, a .NET wrapper around a popular Linux-centric GUI framework named GTK. One compelling Mono-centric API is MonoTouch, which allows you to build applications for Apple iPhone and iTouch devices using the C# programming language.

■ **Note** The Mono website includes a page that describes the overall road map of Mono's functionality and the project's plans for future releases (www.mono-project.com/plans).

A final point of interest regarding the Mono feature set: Much like Microsoft's .NET Framework 4.0 SDK, the Mono SDK supports several .NET programming languages. While this appendix focuses on C#, Mono also provides support for a Visual Basic compiler, as well as support for many other .NET-aware programming languages.

Obtaining and Installing Mono

Now that you have a better idea what you can do with the Mono platform, let's turn our attention to obtaining and installing Mono itself. Navigate to the Mono website (www.mono-project.com) and locate the Download tab to navigate to the downloads page. Here you can download a variety of installers (see Figure B-1).




Figure B-1. The Mono Download Page

This appendix assumes that you are installing the Windows distribution of Mono (note that installing Mono will not interfere whatsoever with any existing installation of Microsoft .NET or Visual Studio IDEs). Begin by downloading the current, stable Mono installation package for Microsoft Windows and saving the setup program to your local hard drive.

When you run the setup program, you are given a chance to install a variety of Mono development tools beyond the expected base class libraries and the C# programming tools. Specifically, the installer will ask you whether you wish to include GTK# (the open source .NET GUI API based on the Linux-centric GTK toolkit) and XSP (a stand-alone web server, similar to Microsoft's ASP.NET development web server [`webdev.webserver.exe`]). This appendix also assumes you have opted for a Full Installation, which selects each option in the setup script (see Figure B-2).




Figure B-2. Select All Options for Your Mono Installation

Examining Mono's Directory Structure

By default, Mono installs under `C:\Program Files\Mono-<version>` (at the time of this writing, the latest version of Mono is 2.4.2.3; however, your version number will almost certainly be different). Beneath that root, you can find several subdirectories (see Figure B-3).




Figure B-3. The Mono Directory Structure

For this appendix, you need to concern yourself only with the following subdirectories:

- **bin:** Contains a majority of the Mono development tools, including the C# command-line compilers.
- **lib\mono\gac:** Points to the location of Mono's global assembly cache.

Given that you run the vast majority of Mono's development tools from the command line, you will want to use the Mono command prompt, which automatically recognizes each of the command-line development tools. You can activate the command prompt (which is functionally equivalent to the Visual Studio 2010 command prompt) by selecting Start ▶ All Programs ▶ Mono <version> For Windows menu option. To test your installation, enter the following command and press the Enter key:

```
mono --version
```

If all is well, you should see various details regarding the Mono runtime environment. Here is the output on my Mono development machine:

```
Mono JIT compiler version 2.4.2.3 (tarball)
Copyright (C) 2002-2008 Novell, Inc and Contributors. www.mono-project.com

TLS:           normal
GC:            Included Boehm (with typed GC)
SIGSEGV:       normal
Notification: Thread + polling
Architecture: x86
Disabled:      none
```

The Mono Development Languages

Similar to the Microsoft's CLR distribution, Mono ships with a number of managed compilers:

- `mcs`: The Mono C# compiler
- `vbnc`: The Mono Visual Basic .NET compiler
- `booc`: The Mono Boo language compiler
- `ilasm`: The Mono CIL compilers

While this appendix focuses only on the C# compilers, you should keep in mind that the Mono project does ship with a Visual Basic compiler. While this tool is currently under development, the intended goal is to bring the world of human-readable keywords (e.g., `Inherits`, `MustOverride`, and `Implements`) to the world of Unix/Linux and Mac OS X (see www.mono-project.com/Visual_Basic for more details).

Boo is an object-oriented, statically typed programming language for the CLI that sports a Python-based syntax. Check out <http://boo.codehaus.org> for more details on the Boo programming language. Finally, as you might have guessed, `ilasm` is the Mono CIL compiler.

Working with the C# Compiler

The C# compiler for the Mono project was `mcs`, and it's fully compatible with C# 2008. Like the Microsoft C# command-line compiler (`csc.exe`), `mcs` supports response files, a `/target:` flag (to define the assembly type), an `/out:` flag (to define the name of the compiled assembly), and a `/reference:` flag (to update the manifest of the current assembly with external dependencies). You can view all the options of `mcs` using the following command:

```
mcs -?
```

Building Mono Applications using MonoDevelop

When you install Mono, you will not be provided with a graphical IDE. However, this does not mean you must build all of your Mono applications at the command prompt! In addition to the core framework, you can also download the free MonoDevelop IDE. As its name suggests, MonoDevelop was built using the core code base of SharpDevelop (see Chapter 2).

You can download the MonoDevelop IDE from the Mono website, and it supports installation packages for Mac OS X, various Linux distributions, and (surprise!) Microsoft Windows! Once installed, you might be pleased to find an integrated debugger, IntelliSense capabilities, numerous project templates (e.g., ASP.NET and Moonlight). You can get a taste of what the MonoDevelop IDE brings to the table by perusing Figure B-4.




Figure B-4. The MonoDevelop IDE

Microsoft-Compatible Mono Development Tools

In addition to the managed compilers, Mono ships with various development tools that are functionally equivalent to tools found in the Microsoft .NET SDK (some of which are identically named). Table B-3 enumerates the mappings between some of the commonly used Mono/Microsoft .NET utilities.

Table B-3. Mono Command-Line Tools and Their Microsoft .NET Counterparts

Mono Utility	Microsoft .NET Utility	Meaning in Life
al	al.exe	Manipulates assembly manifests and builds multifile assemblies (among other things).
gacutil	gacutil.exe	Interacts with the GAC.
mono when run with the -aot option as a startup parameter to the executing assembly	ngen.exe	Performs a precompilation of an assembly's CIL code.

Table B-3. Mono Command-Line Tools and Their Microsoft .NET Counterparts (continued)

Mono Utility	Microsoft .NET Utility	Meaning in Life
wsdl	wsdl.exe	Generates client-side proxy code for XML web services.
disco	disco.exe	Discovers the URLs of XML web services located on a web server.
xsd	xsd.exe	Generates type definitions from an XSD schema file.
sn	sn.exe	Generates key data for a strongly named assembly.
monodis	ildasm.exe	The CIL disassembler
ilasm	ilasm.exe	The CIL assembler
xsp2	webdev.webserver.exe	A testing and development ASP.NET web server

Mono-Specific Development Tools

Mono also ships with development tools for which no direct Microsoft .NET Framework 3.5 SDK equivalents exist (see Table B-4).

Table B-4. Mono Tools That Have No Direct Microsoft .NET SDK Equivalent

Mono-Specific Development Tool	Meaning in Life
monop	The monop (mono print) utility displays the definition of a specified type using C# syntax (see the next section for a quick example).
SQL#	The Mono Project ships with a graphical front end (SQL#) that allows you to interact with relational databases using a variety of ADO.NET data providers.
Glade 3	This tool is a visual development IDE for building GTK# graphical applications.

■ **Note** You can load SQL# and Glade by using the Windows Start button and navigating to the Applications folder within the Mono installation. Be sure to do this because this illustrates definitively how rich the Mono platform has become.

Using monop

You can use the monop utility (short for mono print) to display the C# definition of a given type within a specified assembly. As you might suspect, this tool can be quite helpful when you wish to view a method signature quickly, rather than digging through the formal documentation. As a quick test, try entering the following command at a Mono command prompt:

```
monop System.Object
```

You should see the definition of your good friend, `System.Object`:

```
[Serializable]
public class Object {
    public Object ();
    public static bool Equals (object objA, object objB);
    public static bool ReferenceEquals (object objA, object objB);
    public virtual bool Equals (object obj);
    protected override void Finalize ();
    public virtual int GetHashCode ();
    public Type GetType ();
    protected object MemberwiseClone ();
    public virtual string ToString ();
}
```

Building .NET Applications with Mono

Now let's look at Mono in action. You begin by building a code library named `CoreLibDumper.dll`. This assembly contains a single class type named `CoreLibDumper` that supports a static method named `DumpTypeToFile()`. The method takes a string parameter that represents the fully qualified name of any type within `mscorlib.dll` and obtains the related type information through the reflection API (see Chapter 15), dumping the class member signatures to a local file on the hard drive.

Building a Mono Code Library

Create a new folder on your C: drive named `MonoCode`. Within this new folder, create a subfolder named `CorLibDumper` that contains the following C# file (named `CorLibDumper.cs`):

```

// CorLibDumper.cs
using System;
using System.Reflection;
using System.IO;

// Define assembly version.
[assembly:AssemblyVersion("1.0.0.0")]

namespace CorLibDumper
{
    public class TypeDumper
    {
        public static bool DumpTypeToFile(string typeToDisplay)
        {
            // Attempt to load type into memory.
            Type theType = null;
            try
            {
                // Second parameter to GetType() controls if an
                // exception should be thrown if the type is not found.
                theType = Type.GetType(typeToDisplay, true);
            } catch { return false; }

            // Create local *.txt file.
            using(StreamWriter sw =
                File.CreateText(string.Format("{0}.txt", theType.FullName)))
            {
                // Now dump type to file.
                sw.WriteLine("Type Name: {0}", theType.FullName);
                sw.WriteLine("Members:");
                foreach(MemberInfo mi in theType.GetMembers())
                    sw.WriteLine("\t-> {0}", mi.ToString());

                }
            return true;
        }
    }
}

```

Like the Microsoft C# compiler, Mono's C# compilers support the use of response files (see Chapter 2). While you could compile this file by specifying each required argument manually at the command line, you can instead create a new file named `LibraryBuild.rsp` (in the same location as `CorLibDumper.cs`) that contains the following command set:

```

/target:library
/out:CorLibDumper.dll
CorLibDumper.cs

```

You can now compile your library at the command line, as follows:

```
mcs @LibraryBuild.rsp
```

This approach is functionally equivalent to the following (more verbose) command set:

```
mcs /target:library /out:CorLibDumper.dll CorLibDumper.cs
```

Assigning CoreLibDumper.dll a Strong Name

Mono supports the notion of deploying strongly named assemblies (see Chapter 15) to the Mono GAC. To generate the necessary public/private key data, Mono provides the `sn` command-line utility, which functions more or less identically to Microsoft's tool of the same name. For example, the following command generates a new *.snk file (specify the `-?` option to view all possible commands):

```
sn -k myTestKeyPair.snk
```

You can tell the C# compiler to use this key data to assign a strong name to `CorLibDumper.dll` by updating your `LibraryBuild.rsp` file with the following additional command:

```
/target:library  
/out:CorLibDumper.dll  
/keyfile:myTestKeyPair.snk  
CorLibDumper.cs
```

Now recompile your assembly:

```
mcs @LibraryBuild.rsp
```

Viewing the Updated Manifest with monodis

Before you deploy the assembly to the Mono GAC, you should familiarize yourself with the `monodis` command-line tool, which is the functional equivalent of Microsoft's `ildasm.exe` (without the GUI front end). Using `monodis`, you can view the CIL code, manifest, and type metadata for a specified assembly. In this case, you want to view the core details of your (now strongly named) assembly using the `--assembly` flag. Figure B-5 shows the result of the following command set:

```
monodis --assembly CorLibDumper.dll
```

```
C:\CoreLibDumper>monodis --assembly CorLibDumper.dll
Assembly Table
Name: CorLibDumper
Hash Algorithm: 0x000008004
Version: 1.0.0.0
Flags: 0x000000001
PublicKey: BlobPtr (0x000000036)
Dump:
0x00000000: 00 24 00 00 04 80 00 00 94 00 00 00 06 02 00 00
0x00000010: 00 24 00 00 52 53 41 31 00 04 00 00 11 00 00 00
0x00000020: E1 ED 29 DC B4 AC 44 00 EE 2B 59 64 79 1E 9F B0
0x00000030: 52 B0 A8 6B EE 98 3A 2D 81 F5 4B AC 11 1E D6 2B
0x00000040: DA E1 ED F7 04 30 5A 25 B9 C7 F2 79 A1 33 E8 0E
0x00000050: A8 A3 FC D4 F9 BB 86 B5 D7 22 53 AB 3A 58 F5 0F
0x00000060: 7F F9 AC 3E D6 4D DB EE 48 8E CB C0 45 73 81 4A
0x00000070: 03 7E E5 B1 C2 E6 9A 26 6B 86 FD 07 D5 ED F9 79
0x00000080: 04 E1 F8 E8 F2 11 B6 23 4A A9 26 B8 8F 07 B1 A7
0x00000090: 19 22 32 53 21 BA 9B 03 E8 21 27 80 99 EF B6 88
Culture:
```

Figure B-5. Viewing the CIL Code, Metadata, and Manifest of an Assembly with monodis

The assembly's manifest now exposes the public key value defined in myTestKeyPair.snk.

Installing Assemblies into the Mono GAC

So far you have provided `CorLibDumper.dll` with a strong name; you can install it into the Mono GAC using `gacutil`. Like Microsoft's tool of the same name, Mono's `gacutil` supports options to install, uninstall, and list the current assemblies installed under `C:\Program Files\Mono-<version>\lib\mono\gac`. The following command deploys `CorLibDumper.dll` to the GAC and sets it up as a shared assembly on the machine:

```
gacutil -i CorLibDumper.dll
```

Note Be sure to use a Mono command prompt to install this binary to the Mono GAC! If you use the Microsoft `gacutil.exe` program, you'll install `CorLibDumper.dll` into the Microsoft GAC!

After you run the command, opening the `\gac` directory should reveal a new folder named `CorLibDumper` (see Figure B-6). This folder defines a subdirectory that follows the same naming conventions as Microsoft's GAC (`versionOfAssembly__publicKeyToken`).




Figure B-6. Deploying Your Code Library to the Mono GAC

■ **Note** Supplying the `-l` option to `gacutil` lists out each assembly in the Mono GAC.

Building a Console Application in Mono

Your first Mono client will be a simple, console-based application named `ConsoleClientApp.exe`. Create a new file in your `C:\MonoCode\CorLibDumper` folder, `ConsoleClientApp.cs`, that contains the following `Program` class definition:

```
// This client app makes use of the CorLibDumper.dll
// to dump type information to a file.
using System;
using CorLibDumper;

namespace ConsoleClientApp
{
    public class Program
    {
        public static void Main(string[] args)
        {
            Console.WriteLine("***** The Type Dumper App *****\n");

            // Ask user for name of type.
            string typeName = "";
            Console.Write("Please enter type name: ");
            typeName = Console.ReadLine();

            // Now send it to the helper library.
            if(TypeDumper.DumpTypeToFile(typeName))

```

```
        Console.WriteLine("Data saved into {0}.txt", typeName);
    else
        Console.WriteLine("Error! Can't find that type...");  
    }  
}  
}
```

Notice that the `Main()` method prompts the user for a fully qualified type name. The `TypeDumper.DumpTypeToFile()` method uses the user-entered name to dump the type's members to a local file. Next, create a `ClientBuild.rsp` file for this client application and reference `CorLibDumper.dll`:

```
/target:exe  
/out:ConsoleClientApp.exe  
/reference:CorLibDumper.dll  
ConsoleClientApp.cs
```

Now, use a Mono command prompt to compile the executable using `mcs`, as shown here:

mcs @ClientBuild.rsp

Loading Your Client Application in the Mono Runtime

At this point, you can load `ConsoleClientApp.exe` into the Mono runtime engine by specifying the name of the executable (with the `*.exe` file extension) as an argument to Mono:

```
mono ConsoleClientApp.exe
```

As a test, enter `System.Threading.Thread` at the prompt and press the Enter key. You will now find a new file named `System.Threading.Thread.txt` containing the type's metadata definition (see Figure B-7).




Figure B-7. The Results of Running Your Client Application

Before moving on to a Windows Forms-based client, try the following experiment. Use Windows Explorer to rename the `CorLibDumper.dll` assembly from the folder containing the client application to `DontUseCorLibDumper.dll`. You should still be able to run the client application successfully because the only reason you needed access to this assembly when building the client was to update the client manifest. At runtime, the Mono runtime will load the version of `CorLibDumper.dll` you deployed to the Mono GAC.

However, if you open Windows Explorer and attempt to run your client application by double-clicking `ConsoleClientApp.exe`, you might be surprised to find a `FileNotFoundException` is thrown. At first glance, you might assume this is due to the fact that you renamed `CorLibDumper.dll` from the location of the client application. However, the true reason for the error is that you just loaded `ConsoleClientApp.exe` into the Microsoft CLR!

To run an application under Mono, you must pass it into the Mono runtime through Mono. If you do not, you will be loading your assembly into the Microsoft CLR, which assumes all shared assemblies are installed into the Microsoft GAC located in the `<%windir%>\Assembly` directory.

Note If you double-click your executable using Windows Explorer, you will load your assembly into the Microsoft CLR, not the Mono runtime!

Building a Windows Forms Client Program

Before continuing, be sure to rename `DontUseCorLibDumper.dll` back to `CorLibDumper.dll`, so you can compile the next example. Next, create a new C# file named `WinFormsClientApp.cs` and save it in the same location as your current project files. This file defines two class types:

```
using System;
using System.Windows.Forms;
using CorLibDumper;
using System.Drawing;

namespace WinFormsClientApp
{
    // Application object.
    public static class Program
    {
        public static void Main(string[] args)
        {
            Application.Run(new MainWindow());
        }
    }

    // Our simple Window.
    public class MainWindow : Form
    {
        private Button btnDumpToFile = new Button();
        private TextBox txtTypeName = new TextBox();
```

```
public MainWindow()
{
    // Config the UI.
    ConfigControls();
}

private void ConfigControls()
{
    // Configure the Form.
    Text = "My Mono Win Forms App!";
    ClientSize = new System.Drawing.Size(366, 90);
    StartPosition = FormStartPosition.CenterScreen;
    AcceptButton = btnDumpToFile;

    // Configure the Button.
    btnDumpToFile.Text = "Dump";
    btnDumpToFile.Location = new System.Drawing.Point(13, 40);

    // Handle click event anonymously.
    btnDumpToFile.Click += delegate
    {
        if(TypeDumper.DumpTypeToFile(txtTypeName.Text))
            MessageBox.Show(string.Format(
                "Data saved into {0}.txt",
                txtTypeName.Text));
        else
            MessageBox.Show("Error! Can't find that type...");
    };
    Controls.Add(btnDumpToFile);

    // Configure the TextBox.
    txtTypeName.Location = new System.Drawing.Point(13, 13);
    txtTypeName.Size = new System.Drawing.Size(341, 20);
    Controls.Add(txtTypeName);
}
}
```

To compile this Windows Forms application using a response file, create a file named `WinFormsClientApp.rsp`, and add the following commands:

```
/target:winexe  
/out:WinFormsClientApp.exe  
/r:CorlibDumper.dll  
/r:System.Windows.Forms.dll  
/r:System.Drawing.dll  
WinFormsClientApp.cs
```

Now make sure this file is saved in the same folder as your example code, and supply this response file as an argument to `mcs` (using the `@` token):

```
msc @WinFormsClientApp.rsp
Finally, run your Windows Forms application using Mono:
```

```
mono WinFormsClientApp.exe
```

Figure B-8 shows a possible test run.




Figure B-8. A Windows Forms Application Built Using Mono

Executing Your Windows Forms Application Under Linux

So far, this appendix has shown you how to create a few assemblies that you could also have compiled using the Microsoft .NET Framework 4.0 SDK. However, the importance of Mono becomes clear when you view Figure B-9, which shows the same exact Windows Forms application running under SuSe Linux. Notice how the Windows Forms application has taken on the correct look and feel of my current desktop theme.



Figure B-9. Executing the Windows Forms Application Under SuSe Linux

■ **Source Code** You can find the CorLibDumper project under the Appendix B subdirectory.

The preceding examples shows how you can compile and execute the same exact C# code shown during this appendix on Linux (or any OS supported by Mono) using the same Mono development tools. In fact, you can deploy or recompile any of the assemblies created in this text that do not use .NET 4.0 programming constructs to a new Mono-aware OS and run them directly using the Mono runtime utility. Because all assemblies contain platform-agnostic CIL code, you do not need to recompile the applications whatsoever.

Who is Using Mono?

In this short appendix, I've tried to capture the promise of the Mono platform in a few simple examples. Granted, if you intend only to build .NET programs for the Windows family of operating systems, you might not have encountered companies or individuals who actively use Mono. Regardless, Mono is alive and well in the programming community for Mac OS X, Linux, and Windows.

For example, navigate to the /Software section of the Mono website:

<http://mono-project.com/Software>

At this location, you can find a long-running list of commercial products built using Mono, including development tools, server products, video games (including games for the Nintendo Wii and iPhone), and medical point-of-care systems.

If you take a few moments to click the provided links, you will quickly find that Mono is completely equipped to build enterprise-level, real-world .NET software that is truly cross-platform.

Suggestions for Further Study

If you have followed along with the materials presented in this book, you already know a great deal about Mono, given that it is an ECMA-compatible implementation of the CLI. If you want to learn more about Mono's particulars, the best place to begin is with the official Mono website (www.mono-project.com). Specifically, you should examine the page at www.mono-project.com/Use, which serves an entry point to a number of important topics, including database access using ADO.NET, web development using ASP.NET, and so on.

I have also authored some Mono-centric articles for the DevX website (www.devx.com) that you might find interesting:

- “Mono IDEs: Going Beyond the Command Line”: This article examines many Mono-aware IDEs.
- “Building Robust UIs in Mono with Gtk#”: This article examines building desktop applications using the GTK# toolkit as an alternative to Windows Forms.

Finally, you should familiarize yourself with Mono's documentation website (www.go-mono.com/docs). Here you will find documentation on the Mono base class libraries, development tools, and other topics (see Figure B-10).




Figure B-10. The Online Mono Documentation

Note The website with Mono's online documentation is community supported; therefore, don't be too surprised if you find some incomplete documentation links! Given that Mono is an ECMA-compatible distribution of Microsoft .NET, you might prefer to use the feature-rich MSDN online documentation when exploring Mono.

Summary

The point of this appendix was to provide an introduction to the cross-platform nature of the C# programming language and the .NET platform when using the Mono framework. You have seen how Mono ships with a number of command-line tools that allow you to build a wide variety of .NET assemblies, including strongly named assemblies deployed to the GAC, Windows Forms applications, and .NET code libraries.

You've also learned that Mono is not fully compatible with the .NET 3.5 or .NET 4.0 programming APIs (WPF, WCF, WF, or LINQ) or the C# 2010 language features. Efforts are underway (through the Olive project) to bring these aspects of the Microsoft .NET platform to Mono. In any case, if you need to build .NET applications that can execute under a variety of operating systems, the Mono project is a wonderful choice for doing so.



Index

SPECIAL CHARACTERS AND NUMERICS

- (dash) symbol, 44
- operator, 445, 452
-- operator
 CIL representation, 452
 overloadability, 445
 overloading, 449
-? option, 663
- pointer-centric operator, 479
-- pointer-centric operator, 479
- unary operator, 445
! operator, 121
!= operator, 102, 120, 163, 445, 450, 452
!= pointer-centric operator, 479
character, 47
% operator, 431, 445
<%@Assembly%> directives, 1398, 1402,
 1403
%= operator, 445
%ERRORLEVEL% variable, 76
%FlowDocument> element, 1228
& (ampersand) suffix, 23, 677
& operator, 445, 482
& pointer-centric operator, 479
& symbol, 1094
&& operator, 121, 506
&= operator, 445
* operator, 482
 CIL representation, 452

overloadability, 445
overloading, 453
* pointer-centric operator, 479
*= operator, 445
. (dot) prefix, 655
". " notation, 779
/? flag, 565
/ operator, 445
/= operator, 445
/addmodule flag, 551
/checked flag, 110, 111
/clrheader flag, 535
/connectionstring: option, 962
/debug flag, 663
/dll flag, 663
/exe flag, 664
/FalseString property, 93
/GODMODE value, 1139
/headers flag, 534
/i option, 565
/key flag, 664
/keyf option, 575
/keyfile option, 562
/l option, 565
/language: option, 962
/lldl option, 576
/main option, 74
/mode:FullGeneration option, 961
/noconfig option, 48
/nostdlib option, 45
/out flag, 44, 575, 1569
/out option, C# compiler, 44, 551

/output flag, 664
 /out:TestApp.exe flag, 48
 /pluralize option, 962
 /project: option, 961
 /r flag, 45, 46, 48
 /r option, 49
 /reference flag, 45, 48, 1569
 /reference option, 57
 /t flag, 44
 /target flag, 44, 550, 1514, 1569
 /target:exe option, 44, 1514
 /target:library option, C# compiler, 44
 /target:module option, C# compiler, 44
 /target:winexe option, 44, 1149, 1514
 /t:exe flag, 44
 /t:library option, 551
 /u option, 565
 /unsafe flag, 480
 ? operator, 137
 ?? operator, nullable types, 164–165
 ? suffix, 162, 163
 ? token, 115
 [] (index operator), accessing items from arrays, 439
 \" escape character, 100
 \\ escape character, 100
 \\" escape character, 101
 \\\ escape character, 101
 \a escape character, 100
 \gac directory, 1575
 \Images folder, 1287
 \n escape character, 101
 \r escape character, 101
 \SQLEXPRESS token, 854
 \t escape character, 101
 ^ operator, 445
 ^= operator, 445
 __VIEWSTATE field, 1392, 1476, 1477, 1478, 1479
 __?VIEWSTATE form field, 1478
 _contentLoaded member variable, 1150, 1151
 _Default class, 1409, 1410
 _Exception interface, 262
 { and } tokens, 210
 | operator, 445
 || operator, 121
 |= operator, 445
 ~ (tilde symbol), 303
 ~ operator, 445
 ~/ prefix, 1446
 + (plus) operator, 23, 99, 100, 1094
 + (plus token), 589
 + binary operator, 445, 447
 + operator, 452
 + pointer-centric operator, 479
 + symbol, 99
 + unary operator, 445
 ++ operator
 CIL representation, 452
 overloadability, 445
 overloading, 449
 ++ pointer-centric operator, 479
 += and -= operator overloading, 448
 += operator, 408, 409
 CIL representation, 452
 overloadability, 445
 += syntax, 423, 428
 < operator, 120, 452
 < pointer-centric operator, 479
 <%@Page%> directive, 1401, 1402, 1403, 1409, 1411, 1424, 1443, 1449, 1469, 1477
 <<= operator, 445
 << operator, 445
 <= operator, 120, 445, 452
 <= pointer-centric operator, 479
 < operator, 445
 -= operator, 422, 445, 452
 ==< operator, 437
 == operator, 120
 CIL representation, 452
 overloadability, 445
 overloading, 450
 == operetor, 102
 == pointer-centric operator, 479
 => pointer-centric operator, 479
 >, 445
 -> operator, 484
 >= operator, 120, 452

>> operator, 445
 >>= operator, 445
 > operator, 120
 > pointer-centric operator, 479
 -> pointer-centric operator, 479
 0 (integer), 1335
 0x prefix, 675
 0X58 opcode, 656
 0X59 opcode, 656
 0X73 opcode, 656
 2D arrays, 443
 2D geometric objects, 1246
 2D graphical data, 1119, 1254
 2D graphics, 1120
 2D vector images, 1254, 1271
 3D animation, 1118
 3D functionality, 1118
 3D graphical data, 1119
 3D graphics, 1120
 100% C# code, 1139
 100% code approach, 1078
 100% XAML free, 1144, 1145

A

ABCs. *See* addresses, bindings, and contracts
 Abort() method, 742
 About boxes, 1542, 1543
 AboutToBlow event, 420, 428, 429, 430
 aboutToBlowCounter integer, 429
 abstract attribute, 669
 abstract classes, 240, 244
 abstract FileInfo base class, 777–778
 abstract keyword, 188, 240, 241, 244
 abstract members, 191, 241, 321, 695
 abstract methods, 244
 abstract stream class, 792–794
 abstraction, 837
 Accelerate() method, 265, 266, 267, 274, 277, 405, 406, 420, 425
 AccelerationRatio property, Timeline class, 1305

AcceptAllChanges() method, 959
 AcceptButton property, 1529, 1541
 AcceptChanges() method, 888, 889, 893, 895, 896
 access modifiers, 303
 default, 193
 and nested types, 194
 overview, 192
 accessing profile data programmatically, 1505–1507
 accessor method, 194, 195, 196, 198, 200, 206
 Accessories menu option, 43
 accessors and mutators, for encapsulation of classes, 195–197
 Account property, 1065
 ACID (Atomic, Consistent, Isolated, Durable), 878
 action attribute, 1384, 1390, 1417
 Action<> delegate, 771
 Action<T> delegate, 763, 765, 766
 Activate() method, 1530
 Activated event, 1531, 1532, 1533
 Activator.CreateInstance() method, 601, 602, 710
 Active Server Pages (ASP).NET Web Application, 1412, 1413, 1414
 Active Server Pages (ASP).NET Web page, 1412, 1414
 Active Server Pages (ASP).NET Web Site, 1412, 1413
 Active Template Library (ATL), 6
 ActiveMDIChild property, 1529
 ActiveX Data Objects (ADO), 1394, 1420
 ActiveX UI controls, 1522
 activities, WF 4.0, 1088–1093
 collection, 1092–1093
 connecting in flowchart workflow, 1094
 control flow, 1089
 error handling, 1092–1093
 flowchart, 1089–1090
 messaging, 1090–1091
 primitives, 1091
 runtime, 1091
 transaction, 1091–1092

Activity Library project, 1103
<Activity> element, 1082, 1104
<Activity> node, 1081
Activity1.xaml file, 1103
ActualHeight property,
 FrameworkElement type, 1133
ActualWidth property, FrameworkElement
 type, 1133
<Ad> element, 1448
adaptive rendering, 1389
Add another item area, 1218
Add another item button, 1217, 1230
Add another item dropdown list, 1218
Add button, 224, 226, 719
Add class menu item, 195
Add Content Page menu option, 1448,
 1455
Add Existing Item menu option, 226, 273,
 325, 343, 984, 986, 1242, 1448
Add Existing Item option, 277, 1358
Add Function Import menu option, 980
Add Installer option, 1064
Add Keyframe button, 1362
add mnemonic, 656
Add New Case link, 1108
Add New Diagram menu option, 846
Add New Item dialog box, 1298
Add New Item menu option, 224, 325, 531,
 938, 962, 1037, 1109, 1240, 1445,
 1448
Add New Item menu selection, 1442
Add New Stored Procedure option, 843
Add New Table option, 841
add opcode, 678
Add Project Data Source link, 927
Add Reference dialog box, 57, 492, 541,
 546, 547, 567, 714, 715, 716, 1105
Add Reference menu option, 57, 96, 541,
 547, 1072, 1364, 1513
Add References dialog box, 53, 552, 716
Add Service Reference dialog box, 1067,
 1075
Add Service Reference menu option, 1043,
 1047
Add State button, 1367, 1368
Add State Group button, 1367
Add Sticky Note button, 1234
Add TabItem option, 1213
Add This Car button, 1492
Add Transition button, 1369
Add UserControl menu option, 1331
Add Web Reference option, 1018
Add Windows Form menu option, 1543
Add Windows Forms menu option, 1538
add_ prefix, 421
add_AboutToBlow() method, 421
add_Exploded() method, 421
<add> elements, 578
AddChild() method, 1138
AddComplete() method, 736, 737, 738, 739
AddDefaultEndpoints() method, 1040,
 1063
AddInventoryRow() method, 934
AddMemoryPressure() method,
 System.GC class, 298
AddObject() method, 959, 974
.addon directive, 421
AddOne() method, 757
AddParams parameter, 747
AddPerson() method, 368
AddRange() method, 1515
AddRecord() method, 943
AddRecords() method, 951
AddRef() method, 292
Add/Remove WizardSteps link, 1455
address attribute, 1039
address element, 1037
Address group, 1507
addresses, bindings, and contracts (ABCs)
 addresses, 1031–1032
bindings
 HTTP-based, 1029–1030
 MSMQ-based, 1031
 overview, 1028
 TCP-based, 1030
contracts, 1027
 establishing within App.config files,
 1037
 specifying in code, 1062–1063

AddServiceEndpoint() method, 1040, 1051, 1063
AddToCollection<T> activity, WF 4.0, 1092
AddWithThreads application, 747
AddWithThreads project, 749
 Administrative Tools folder, 1066, 1500
 ADO (ActiveX Data Objects), 1394, 1420
 ADO.NET
 abstracting data providers using interfaces, 837–840
 additional namespaces, 831–832
 building reusable data access library
 adding connection logic, 863
 adding deletion logic, 865
 adding insertion logic, 863–864
 adding selection logic, 866
 adding update logic, 865
 executing stored procedure, 869–871
 overview, 861
 parameterized command objects, 867–869
 connected layer of
 command objects, 858
 connection objects, 854–856
 ConnectionStringBuilder objects, 856–857
 overview, 853
 creating AutoLot database
 authoring GetPetName() stored procedure, 843
 creating customers and orders tables, 844
 creating inventory table, 840–842
 visually creating table relationships, 846–847
 creating console UI-based front end
 DeleteCar() method, 875
 InsertNewCar() method, 875–876
 ListInventory() method, 874
 LookUpPetName() method, 876
 Main() method, 872
 overview, 871
 ShowInstructions() method, 873
 UpdateCarPetName() method, 876

data provider factory model
 <connectionStrings> element, 852–853
 complete data provider factory example, 848–851
 overview, 847
 potential drawback with provide factory model, 851–852
 data providers
 Microsoft-supplied, 829–830
 overview, 827
 System.Data.OracleClient.dll, 830–831
 third-party, obtaining, 831
 data readers, 859–861
 database transactions
 adding CreditRisks table to AutoLot database, 879–880
 adding transaction method to InventoryDAL, 880–882
 key members of transaction object, 878–879
 overview, 877
 testing, 882–883
 high-level definition of, 825–827
 overview, 825
 System.Data namespace, types of
 IDataReader and IDataRecord interfaces, 836
 IDbCommand interface, 834
 IDbConnection interface, 833
 IDbDataAdapter and IDataAdapter interfaces, 835
 IDbDataParameter and IDataParameter interfaces, 834–835
 IDbTransaction interface, 834
 overview, 832
 AdoNetTransaction application, 882
 AdoNetTransaction project, 883
 AdornerDecorator, 1344
 adornments, 22
 AdRotator control, 1439, 1444, 1447, 1448, 1449
 AdRotator widget, 1447–1448

Ads.xml file, 1447, 1448
 Advanced button, 110, 1067
 Advanced Properties button, 1301
 Advanced properties square, 1297
 Advanced Property options, 1236
 AdvertisementFile property, 1447, 1448
 Age property, 200, 379, 384
 Aggregate<T>() method, 500
 aggregation, 232
 AirVehicles assembly, 550
 AirVehicles namespace, 550
 airvehicles.dll file, 551–552
 al utility, Mono, 1570
 alert() method, 1389
 al.exe utility, 575, 1570
 aliases, resolving name clashes with, 528–530
 AllKeys property, `HttpApplicationState` type, 1484
 allowAnonymous attribute, 1504
 AllowDBNull property, 890, 891
 AllowMultiple property, 612
 allSongs object, 314
 AllTracks class, 313, 315
 AllTracks object, 315, 316
 AllTracks variable, 314, 315
 alpha, red, green and blue (ARGB), 1259
 Alt key shortcut, 1197, 1516
 Alt property, 1537
 Alt+F shortcut, 1516
 Alt+X shortcut, 1516
 ALTER PROCEDURE statement, 843
 altering configuration files using `SvcConfigEditor.exe`, 1059–1061
 AlternateText text, 1448
 AlternatingRowBackground property, 1243
 AlternationCount property, 1243
 ampersand (&) suffix, 23, 677
 Ancestors<T>() method, 1000
 Anchor property, 1526
 and opcode, 678
 angle brackets, 620
 Angle property, 1307
 Animatable, 1272
 Animate<T> parameter, 1305
 animated styles, WPF, 1318
 Animation classes, 1304, 1305, 1308
 animation editor mode, 1360
 Animation elements, 1310
 Animation objects, 1308, 1309
 animation services, WPF
 Animation class types, 1304–1305
 authoring animation in C# code, 1306–1307
 authoring animation in XAML
 discrete key frames, 1311–1312
 event triggers, 1310–1311
 overview, 1309
 storyboards, 1310
 looping animation, 1308–1309
 overview, 1303
 pacing of animation, controlling, 1307–1308
 From property, 1305
 By property, 1305
 To property, 1305
 reversing animation, 1308–1309
 Timeline Base class, 1305
 Animation token, 1304
 animation tools, 1304
 animations
 authoring, 1304
 building, 1304
 defining with Expression Blend, 1359–1363
 key frame, 1304
 linear interpolation, 1304
 path-based, 1304
 programmatically starting storyboard, 1363–1364
 annotations, Documents tab, 1232–1234
 AnnotationService class, 1234
 AnnotationService object, 1234
 AnnotationStore, 1234
 anonymous methods, 9, 427–430, 763
 anonymous profiles, 1507
 anonymous types, 493
 containing anonymous types, 478
 equality for, 476–478
 internal representation of, 474–475

overview, 473
 ToString() and GetHashCode(), 476

AnonymousMethods project, 430
AnonymousTypes project, 474, 479
Any() method, 1107
API (application programming interface),
 1013, 1014, 1015, 1016, 1017, 1391–
 1395
API (CardSpace application programming
 interface), 1023, 1030
API (C/Windows application programming
 interface), 4
API (Simple application programming
 interface)XML (for Extensible
 Markup Language)SAX (), 993
API (Windows Application Programming
 Interface), 260, 285, 286, 729
API features
 1.0-1.1, 1392–1393
 2.0, 1393–1394
 3.5 (and .NET 3.5 SP1), 1394
 4.0, 1394–1395
 overview, 1391
App_Browsers subdirectory, 1414
App_Code directory, 1415
App_Code folder, 1072, 1414, 1415
App_Code subdirectory, 1414
App_Data folder, 1415, 1440, 1503, 1506,
 1508
App_Data subdirectory, 1414, 1503
App_GlobalResources subdirectory, 1414
App_LocalResources subdirectory, 1414
App_Theme folder, 1466, 1469
App_Themes folder, 1415, 1465, 1466, 1467
App_Themes subdirectory, 1414
App_WebReferences subdirectory, 1414
App.config file, 557, 558, 849, 852, 857, 871,
 932, 984, 986, 1037
AppConfigReaderApp application, 578, 579
AppDomain shutdown, 304
AppDomain.CreateDomain() method, 643
AppDomain.DefineDynamicAssembly()
 method, 693
AppDomain.Load() method, 645
AppDomains (application domains)
Creating
 loading assemblies into custom
 application domains, 645
 overview, 643–644
 programmatically unloading
 AppDomains, 646–648
Default, interacting with, 640–643
Overview, 637–639
System.AppDomain class, 638–639
AppDomains (application domains),
 defined, 625
Append member, FileMode enumeration,
 787
AppendText() method, FileInfo class, 785,
 789
AppExit() method, 1137
Application cache
 data caching, 1489–1491
 modifying *.aspx file, 1491–1493
 overview, 1488
Application class, 1138, 1139, 1144, 1145
Application.Windows collection,
 enumerating, 1130
 constructing, 1129–1130
 overview, 1128
Application Component Object Model
 (COM) object, 1483
Application data, modifying, 1486–1487
Application -derived class, 1137
Application directory, 553
Application domains (AppDomains),
 defined, 625
Application error code, C# programming,
 76–77
Application markup, 1350
Application object, 73, 74, 1129
Application programming interface (API),
 1013, 1014, 1015, 1016, 1017, 1391–
 1395
Application property, 1416, 1482, 1483,
 1485
Application resources, embedding, 1289–
 1291
Application roots, and object lifetime, 294–
 295

application shutdown, handling, 1488
 application state
 handling web application shutdown, 1488
 maintaining application-level state
 data, 1484–1486
 modifying application data, 1486–1487
 overview, 1483
 Application tab, 74, 531, 565, 571, 919, 1144, 1514
 Application type, 1121, 1522
 application variable, web-based, 1124
 Application_End() method, 1481, 1488
 Application_Error() event, 1481, 1482
 Application_Start() event, 1481, 1485, 1489, 1490
 <Application> element, 1156
 ApplicationCommands class, WPF, 1201
 ApplicationCommands object, 1205
 ApplicationCommands.Help command, 1203
 Application.Current property, 1140
 <ApplicationDefinition> element, 1149
 Application-derived class, 1130, 1147, 1153
 Application-derived type, 1130, 1153, 1166
 ApplicationException class, 276
 Application.Exit() method, 1517
 application-level exceptions
 (System.ApplicationException), 273–276
 application-level resources, 1296–1297
 application-level state data, maintaining, 1484–1486
 ApplicationPath property, 1418
 Application.Resources scope, 1297, 1299
 Application.Run() method, 1514, 1515, 1522, 1531
 applications
 building, 1513–1518, 1551–1560
 adding infrastructure to
 MainWindow type, 1555
 capturing and rendering graphical output, 1557
 implementing serialization logic, 1558–1560
 implementing Tools menu functionality, 1555–1556
 main menu system, 1552–1553
 populating controls collection, 1515–1517
 ShapeData type, 1553
 ShapePickerDialog type, 1553–1555
 System.EventArgs and System.EventHandler, 1517–1518
 client, building, 1046–1050
 composition of, 1025–1027
 web, 1380–1382
 Applications folder, 1572
 Applications tab, 984
 Application.Windows collection, enumerating, 1130
 Application.Windows property, 1138
 apply attribute, 575
 Apply Resource option, 1297
 ApplyingAttributes application, 606
 <appSettings> element, 578, 839, 849, 852, 1427
 AppStartUp() method, 1137
 AppState project, 1485
 App.xaml file, 1297, 1303, 1313, 1323, 1350, 1354
 arbitrary actions, connecting WPF commands to, 1203–1204
 ARGB (alpha, red, green and blue), 1259
 Args property, 1140
 ArgumentException exception, 631
 ArgumentOutOfRangeException class, 260, 272, 277, 278, 279
 arguments
 array as, 142
 command-line, 1139
 optional, 180–181
 workflow
 defining, 1105–1106
 defining using workflow designer, 1084–1086
 passing to workflows using WorkflowInvoker class, 1084
 retrieving output, 1113–1114
 Arguments button, 1084, 1094

arithmetic operations, 756
Array class, 519
Array object, 513
Array of [T] option, 1098
array variable, 137
ArrayList class, 362, 365, 366, 367, 371, 1479
ArrayList.Add() method, 366
ArrayOfObjects() method, 139, 140
Array.Reverse() method, 144
arrays
 as arguments, 142
 defined, 137
 generating documents from, 1004–1005
 implicitly typed local, 139
 initialization syntax, 138
 of interface types, 334
 multidimensional, 140–141
 of objects, 139–140
 overview, 137
 primitive, applying LINQ queries to, 496–503
 as return values, 142
 System.Array class, 142–144
Array.Sort() method, 144
as keyword, 249, 307, 330
ASC (ascending), 910
ascending (ASC), 910
ascending operator, 509, 514
AsDataView<T>() method, 949
AsEnumerable() method, 947, 948
AskForBonus() method, 146
AsmReader class, 697
*.asmx file, 1017
ASP (Active Server Pages).NET Web Application, 1412, 1413, 1414
ASP (Active Server Pages).NET Web page, 1412, 1414
ASP (Active Server Pages).NET Web Site, 1412, 1413
ASP applications, 1475
*.asp file, 1476
`asp\:` tag prefix, 1403
`<asp:>` definitions, 1477
`<asp\:>` tag, 1397

AsParallel() method, 771
AsParallel()method, 772
AsParallel() method, 772
`<asp\:Button>` control, 1392
`<asp:Content>` scope, 1448, 1449
`<asp:ContentPlaceHolder>` component, 1449
`<asp:ContentPlaceHolder>` definition, 1443
`<asp:ContentPlaceHolder>` element, 1443
`<asp:ContentPlaceHolder>` tag, 1443, 1448
`<asp:ListItem>` declarations, 1478
ASP.NET Development web server, 1393
ASP.NET Java web applications, 1475
ASP.NET master pages, 1442–1448
ASP.NET session state server, 1500, 1502
ASP.NET state management techniques
 application cache
 data caching, 1489–1491
 modifying *.aspx file, 1491–1493
 overview, 1488
 application/session distinction
 handling web application shutdown, 1488
 maintaining application-level state data, 1484–1486
 modifying application data, 1486–1487
 overview, 1483
 cookies
 creating, 1498–1499
 overview, 1497
 reading incoming data, 1499
 Global.asax file
 global last-chance exception event handler, 1481–1482
 HttpApplication base class, 1482
 overview, 1479
 maintaining session data, 1493–1497
 overview, 1473
Profile API
 accessing profile data programmatically, 1505–1507
ASPNETDB.mdf database, 1503–1504

- defining user profiles within *Web.config*, 1504–1505
- grouping profile data and persisting custom objects, 1507–1509
- overview, 1502
- role of `<sessionState>` elements
 - storing session data in ASP.NET
 - session state servers, 1500–1501
 - storing session data in dedicated databases, 1502
- view state
 - adding custom data, 1478–1479
 - demonstrating, 1477–1478
 - overview, 1476
- ASP.NET themes
 - `*.skin` files, 1466–1468
 - applying at page level, 1469
 - applying sitewide, 1468
 - assigning programmatically, 1469–1471
 - overview, 1465
 - `SkinID` property, 1469
- ASP.NET web controls
 - `AutoPostBack` property, 1431
 - categories of
 - documentation, 1441
 - overview, 1438
 - `System.Web.UI.HtmlControls`, 1440–1441
 - control and `WebControl` base classes
 - dynamically adding and removing controls, 1435–1436
 - enumerating contained controls, 1432–1435
 - interacting with dynamically created controls, 1436–1437
 - `WebControl` base class, 1437–1438
 - overview, 1429
 - server-side event handling, 1430
- ASP.NET Web pages, building
 - API features
 - 1.0–1.1, 1392–1393
 - 2.0, 1393–1394
 - 3.5 (and .NET 3.5 SP1), 1394
 - 4.0, 1394, 1395
 - overview, 1391
- client-side scripting, 1388–1390
- HTTP
 - request/response cycle, 1380
 - stateless protocols, 1380
- Hypertext Markup Language (HTML)
 - building forms, 1386–1387
 - document structure, 1383–1384
 - forms, 1384
 - overview, 1382
 - Visual Studio 2010 designer tools, 1384–1386
- incoming HTTP requests
 - access to incoming form data, 1419–1420
 - `IsPostBack` property, 1420
 - obtaining browser statistics, 1419
 - overview, 1417
- inheritance chain of `Page` type, 1416
- life cycle of
 - `AutoEventWireup` attribute, 1424–1425
 - Error event, 1425–1426
 - overview, 1423
- outgoing HTTP response
 - emitting HTML content, 1422
 - overview, 1421
 - redirecting users, 1422–1423
- posting back to Web servers, 1390–1391
- single file Web pages
 - adding data access logic, 1397–1401
 - ASP.NET control declarations, 1403–1404
 - ASP.NET directives, 1401–1403
 - compilation cycle for single-file pages, 1405–1406
 - designing UI, 1396–1397
 - overview, 1395
 - referencing `AutoLotDAL.dll`, 1396
 - "script" block, 1403
- using code files
 - compilation cycle for multifile pages, 1410
 - debugging and tracing ASP.NET pages, 1410–1411
 - overview, 1406

referencing AutoLotDAL.dll
 assembly, 1409
 updating code file, 1409–1410
 Web applications and servers
 ASP.NET development web server,
 1382
 IIS virtual directories, 1381
 overview, 1380
 Web site directory structure
 App_Code folder, 1415
 overview, 1413
 referencing assemblies, 1414–1415
 Web sites and Web applications, 1412–
 1413
 Web.config files, 1427–1428
 ASP.NET Web Service template, Visual
 Studio, 1017
 aspnet_compiler.exe tool, 1410, 1427
 aspnet_Regsql.exe, 1503
 aspnet_state.exe, 1500, 1501
 aspnet_wp.exe, 1500
 AspNetCarsSite application, 1456
 AspNetCarsSite project, 1442
 AspNetCarsSite website, 1457
 ASPNETDB.mdf database, 1503–1504,
 1506, 1507, 1508, 1509
 <asp:TextBox> tag, 1429
 .aspx files, 1479
 *.aspx files, modifying, 1491–1493
 *.aspx page, 1495, 1499
 .aspx pages, 1477, 1479
 assemblies, 12–19. *See also* .NET
 assemblies
 CLS compliant, 612
 and Common Intermediate Language
 (CIL)
 benefits of, 16–17
 compiling to platform-specific
 instructions, 17
 overview, 14–15
 documenting
 defining assembly, 585
 referenced assemblies, 585
 dynamically loading, 596–598
 exploring using ildasm.exe
 overview, 33
 viewing assembly metadata, 35
 viewing Common Intermediate
 Language (CIL) code, 34
 viewing type metadata, 34
 exploring using Reflector, 35–36
 external, 536, 1081
 friend, 545
 interop, 714, 717
 interoperability, 714, 716
 loaded
 enumerating, 641–642
 receiving assembly load
 notifications, 643
 loading, 553, 645
 localized, 598
 metadata, 17–18
 multi-file, 14
 production-ready, 1562
 referencing external, 32, 1414–1415
 with csc.exe, 45–46
 with Visual Studio 2010, 57
 resource-only, defining, 1300–1301
 shared, 598–600
 single-file, 14
 workflow, importing, 1105
 WPF
 Application class, 1128–1130
 overview, 1126–1127
 Window class, 1130–1135
 <assemblies> element, 1414
 assembly, 13
 Assembly class, 587, 596
 .assembly directive, 662, 666, 667
 Assembly directory, 559
 .assembly extern block, 542
 .assembly extern directives, 19, 660, 667
 .assembly extern tokens, 542, 554, 660
 --assembly flag, 1574
 Assembly Information button, 543, 565,
 571, 919, 984
 assembly linker, 575
 assembly manifest, 18–19
 assembly metadata, 35, 536, 586
 Assembly reference, 596

Assembly table, 585
 assembly token, 585, 1159
 Assembly type, 596
 Assembly Version number, 571
 [assembly:] tag, 612
 <assemblyBinding> element, 555
 AssemblyBuilder member, 689
 AssemblyBuilder type, 692, 693
 AssemblyCompanyAttribute attribute, 613
 AssemblyCopyrightAttribute attribute, 613
 [AssemblyCulture] attribute, 562
 AssemblyCultureAttribute attribute, 614
 AssemblyDescriptionAttribute attribute, 614
 <assemblyIdentity> element, 573–577
 AssemblyInfo.cs file, 543, 544, 562, 563, 613, 658
 [AssemblyKeyFile] attribute, 560, 562
 AssemblyKeyFileAttribute attribute, 614
 assembly-level (and module-level) attributes, 612–613
 AssemblyLoad event, AppDomain class, 640
 Assembly.Load() method, 597, 598, 599, 602, 1415
 AssemblyLoadEventHandler delegate, 643
 Assembly.LoadFrom() method, 598, 602
 AssemblyName class, System.Reflection Namespace, 587
 AssemblyName type, 599, 693
 AssemblyProductAttribute attribute, 614
 AssemblyRef #n tokens, 585
 AssemblyRef for the System.Windows.Forms assembly, 585
 AssemblyResolve event, AppDomain class, 640
 AssemblyTrademarkAttribute attribute, 614
 [AssemblyVersion] attribute, 560, 562, 660
 AssemblyVersionAttribute attribute, 614
 Assets Library, 1212, 1213, 1217, 1222, 1229, 1236, 1320, 1358
 Assign activity, 1091, 1107, 1108, 1111
 assigning themes programmatically, 1469–1471
 Associations folder, 983
 AsyncCallback delegate, 736–738, 1069
 AsyncCallback object, 736
 AsyncCallback parameter, 399
 AsyncCallbackDelegate project, 739, 747
 AsyncDelegate application, 733
 AsyncDelegate project, 735
 AsyncDelegate property, 738
 asynchronous delegate pattern, .NET, 1086
 asynchronous delegates, 762
 asynchronous method invocations, 22, 727, 731, 739
 asynchronously method, 398
 AsyncPattern property, 1035
 AsyncResult class, 738, 774
 AsyncState property, 739
 AsyncWaitHandle property, IAsyncResult interface, 735
 ATL (Active Template Library), 6
 Atomic, Consistent, Isolated, Durable (ACID), 878
 atomic operations, 729
 attached properties, 1162, 1326
 Attribute code snippet, Visual Studio 2010, 610
 Attribute suffix, 607
 Attribute token, 607
 AttributedCarLibrary assembly, 611, 614, 615
 AttributedCarLibrary project, 609
 AttributedCarLibrary.dll, 615
 attributes
 .NET applying in C#, 606–607
 attribute consumers, 605–606
 C# attribute shorthand notation, 607–608
 obsolete attribute in action, 608–609
 overview, 604
 specifying constructor parameters for, 608
 assembly-level (and module-level), 612–613

CIL, 655
 custom
 applying, 610
 named property syntax, 610–611
 overview, 609
 restricting usage, 611–612
 using early binding, 614–615
 using late binding, 615–617
 using to customize serialization, 823
 XAML, 1160–1161

Attributes() method, 1000
 Attributes property, FileSystemInfo class, 778
 AttributeTargets enumeration, 611
 [AttributeUsage] attribute, 611, 612
 <authentication> element, 1427
 authoring animations, 1304
 Authorization property, 1040
 <authorization> element, 1427
 auto attribute, 669
 Auto Format link, 1445
 Auto Format option, 1399
 autocomplete window, 50
 autocompletion, 49, 50
 AutoEventWireup attribute, 1424–1425
 autogenerated code, 932
 autogenerated data adapter object, 932
 AutoIncrement property, DataColumn class, 890, 892
 autoincrementing fields, 892
 AutoIncrementSeed property, DataColumn class, 890, 892
 AutoIncrementStep property, DataColumn class, 890, 892
 AutoLot (Version 2) project, 938
 AutoLot (Version Three) folder, 938
 AutoLot Data Access Layer project, 862
 AutoLot database, 849, 850, 921, 922, 953, 954, 1492, 1493
 adding CreditRisks table to, 879–880
 creating
 authoring GetPetName() stored procedure, 843
 creating customers and orders tables, 844
 creating inventory table, 840–842
 visually creating table relationships, 846–847
 AutoLot database icon, 849
 AutoLot project, 917
 AutoLotConnDAL.cs file, 862
 AutoLotConnectedLayer class, 1409
 AutoLotConnectedLayer namespace, 862, 882, 1073, 1398, 1402, 1492
 AutoLotCUIClient application, 871, 877, 882
 AutoLotDAL (Version 2) project, 920
 AutoLotDAL (Version 3) project, 940
 AutoLotDAL Code Library project, 880
 AutoLotDAL namespace, 984, 986, 1242
 AutoLotDAL project, 862, 871, 882, 984
 AutoLotDAL Version 4.0
 invoking stored procedure, 985–986
 mapping stored procedure, 980–981
 navigation properties, 982–985
 overview, 979
 AutoLotDAL_EF.edmx project, 979
 AutoLotDAL.AutoLotDataSetTableAdapter s namespace, 940
 AutoLotDAL.dll assembly
 adding disconnection functionality to
 configuring data adapters using SqlCommandBuilder class, 918–919
 defining initial class types, 917
 GetAllInventory() method, 919
 setting version numbers, 919
 testing disconnected functionality, 920–921
 UpdateInventory() method, 919
 referencing, 1396, 1409
 AutoLotDAL.sln file, 938
 AutoLotDataReader application, 853
 AutoLotDataReader project, 861
 AutoLotDataSet.xsd file, 938
 AutoLotDisconnectedLayer class, 917, 1105
 AutoLotDisconnectedLayer namespace, 917, 945

AutoLotDisconnectionLayer namespace, 862
 AutoLot.dll assembly, 927, 938, 940, 984, 1105, 1106, 1112
 autoLotDS object, 924
 AutoLotEDM_GUI application, 986
 AutoLotEDMClient application, 984
 AutoLotEDMClient example, 986
 AutoLotEntities class, 954, 959, 970, 971, 974
 AutoLotInventory variable, 1106
 AutoLot.mdf file, 189
 AutoLotService project, 1076
 AutoLotService.cs file, 1073
 AutoLotWCFService class, 1071
 automatic properties
 and default values, 208–210
 interacting with, 208
 overview, 206–207
 automatically referenced feature, 45
 autonomous entities, 1021
 AutoPageWireUp attribute, 1425
 AutoPostBack property, 1431
 AutoProps project, 206, 210
 AutoResetEvent class, 748–749
 AutoResetEvent object, 1087
 AutoResetEvent variable, 748
 AutoReverse property, 1305, 1308
 AutoSize property, 1526
 Average() method, 516

■ B

back tick character, 594
 BackColor property, 1429, 1437, 1526
 Background and Content value, 1352
 Background garbage collection, 297
 Background property, 1133, 1160, 1161, 1273, 1293, 1297, 1301, 1353
 Background threads, 749–750
 BackgroundColor property,
 System.Console class, 81
 BackgroundImage property, 1526

BAML (Binary Application Markup Language), transforming markup into .NET assembly, 1151–1152
 *.baml file extension, 1151, 1152
 base addresses, specifying, 1038–1040
 base classes
 casting rules
 is keyword, 250
 as keyword, 249
 overview, 247–248
 controlling creation of with base keyword, 228–230
 libraries, role of in .NET, 8
 multiple, 222
 base keyword, 229, 237, 254, 654, 1482
 <baseAddress> element, 1051, 1052
 BaseAddresses property, 1040
 baseAddresses scope, 1039
 <baseAddresses> element, 1039, 1050
 BaseDirectory property, AppDomain class, 639
 BasedOn property, 1315
 BasedOn, Style class, 1313
 BaseStream member, BinaryReader class, 800
 BaseStream member, BinaryWriter class, 800
 BASIC (Beginner's All-purpose Symbolic Instruction Code), 997
 BasicConsoleIO project, 85
 BasicDataTypes project, 88, 97
 BasicGreen theme, 1469
 BasicGreen.skin file, 1466, 1467
 BasicHttpBinding class, 1029, 1031, 1037, 1042, 1046, 1049, 1051, 1053, 1054, 1070
 BasicHttpBinding object, 1050
 BasicHttpBinding option, 1029
 BasicHttpBinding protocol, 1029
 <basicHttpBinding> element, 1029, 1050
 BasicInheritance project, 219, 225
 BasicMath class, 395
 *.bat file extension, 76, 77
 bear_paper.design file, 1275
 Beep() method, System.Console class, 81

beforefieldinit item, 611
 Begin method, 1035, 1069
 BEGIN TRANSACTION statement, 878
 BeginAnimation() method, 1307, 1309
 BeginCatchBlock() method, 690
 BeginClose() method, 1040
 BeginEdit() method, 893, 896
 BeginExceptionBlock() method, 690
 BeginFinallyBlock() method, 690
 BeginInvoke() method, 399, 400, 732, 734,
 736, 738, 760, 774, 1086
 Beginner's All-purpose Symbolic
 Instruction Code (BASIC), 997
 BeginOpen() method, 1040
 BeginScope() method, 690
 <BeginStoryboard> element, 1310
 BeginTime property, 1305, 1308
 BeginTransaction() method, 834, 855, 882
 behavior, 321
 behaviorConfiguration attribute, 1043,
 1055
 behaviors element, 1042, 1043, 1050
 BenefitPackage class, 232, 234
 BenefitPackageLevel class, 234
 BenefitPackageLevel enumeration, 234
 BenefitsPackage type, 233
 beq opcode, 678
 Bezier curve, 1257
 bgt opcode, 678
 BigFontButton skin, 1469
 BigInteger class, 96
 BigInteger data type, 90, 95, 96, 97
 BigInteger object, 96
 BigInteger structure, 95
 BigInteger variable, 89, 96
 BigInteger.Multiply() method, 97
 bin directory, Mono, 1568
 Bin folder, 1414, 1415
 Bin subdirectory, 1414
 Binary Application Markup Language
 (BAML), transforming markup into
 .NET assembly, 1151–1152
 binary CIL opcodes, 655

binary format, serializing
 DataTable/DataSet objects in,
 902–903
 binary operator overloading, 445–447
 binary resources, WPF
 embedding application resources,
 1289–1291
 loose resources
 configuring, 1287
 including files in project, 1286–1287
 overview, 1285
 programmatically loading images,
 1288–1289
 BinaryCars.bin file, 903
 BinaryFormatter class, 529, 606, 807, 808,
 902
 BinaryFormatter type, 808
 deserializing, 812–813, 819
 serializing, 811–813
 type fidelity, 810
 BinaryOp class, 398, 399
 BinaryOp delegate, 398, 399, 402, 403, 404,
 729, 730, 732, 733, 736
 BinaryOp type, 738
 BinaryOp variable, 738
 BinaryReader class, 776
 BinaryReader type, 27
 BinaryReaders class, 799–801
 BinaryResourcesApp application, 1285,
 1291
 BinaryWriter class, 776
 BinaryWriterReader project, 800, 801
 BinaryWriters class, 799–801
 bind early, 600
 bin\Debug folder, 602
 binders, 709
 binding element, 1037
 Binding keyword, 1238
 <binding> element, 1054
 bindingConfiguration attribute, 1054
 BindingFlags enumeration, 592
 <bindingRedirect> element, 573
 bindings
 changing settings for, 1053–1054

DataTable objects to Windows Forms
 GUIs
 DataView type, 912–913
 deleting rows from DataTable, 907–908
 hydrating DataTable from generic List<T>, 904–906
 overview, 903
 selecting rows based on filter criteria, 908–911
 updating rows within DataTable, 911
 early, attributes using, 614–615
 exposing single services using multiple, 1052–1053
 HTTP-based, 1029–1030
 late
 attributes using, 615–617
 invoking methods with no parameters, 602–603
 invoking methods with parameters, 603–604
 overview, 600
 System.Activator class, 601–602
 MSMQ-based, 1031
 overview, 1028
 selecting, 1056–1057
 TCP-based, 1030
 bindings element, 1042, 1050, 1054
 BindingSource class, 931
 Bitmap class, 31
 Bitmap type, 1547
 BitmapImage class, 1288
 BitmapImage objects, 1359
 BitVector32 type, 363
 black box programming, 195
 ble opcode, 678
 Blend brush editor, 1269
 Blend code editor, 1221
 Blend Designer, 1210
 Blend editor, 1228
 Blend project, 1358
 Blend Properties editor, 1209
 Blend Properties window, 1217, 1221, 1359
 Blend Resources window, 1321
 Blend window, 1211
 Blend XAML editor, 1210
 block elements, Documents API, 1227
 Blocks (Collection) property, 1230
 Blocks editor, 1230
 BlockUIContainer element, 1227
 blt opcode, 678
 blue value, 717
 <body> scope, 1383, 1386
 Boo programming language, 50, 1569
 booc compiler, Mono, 1569
 bool data type, 86, 93, 112, 162
 bool field, 736
 bool keyword, 89
 bool? member, 163
 bool parameter, 882
 bool value, 1140, 1335
 bool variable, 88, 89, 311, 748, 1307
 boolArray type, 138
 Boolean data type, 162, 1479
 Boolean expression, 1107
 Boolean parameter, 298
 Boolean property, 1235
 Boolean variable, 736, 1096
 Border control, 1358
 Border menu option, 1220
 BorderBrush color, 1358
 BorderBrush property, Control Type, 1133
 BorderColor property, WebControl Base Class, 1437
 BorderStyle property, 1429, 1433, 1437
 BorderThickness property, Control Type, 1133
 BorderThickness value, 1358
 BorderWidth property, 1429, 1437
 Bottom property, 1527
 Bounds member, 1254
 Bounds property, 1527
 box opcode, 678
 boxedInt object, 364
 boxing, 365
 boxing operation, 364
 br opcodes, 682

 tag, 1435

bread crumbs, establishing with
 SiteMapPath type, 1447
breadcrumbs technique, 1447
break keyword, 117, 122
brower statistics, obtaining, 1419
Browse For Types option, 1095, 1106, 1107
Browse tab, 57, 541, 546, 567
Browser property, 1418, 1419
Brush editors, 1171, 1260, 1269–1271, 1301
Brush object, 1248
Brush type, 1269, 1547, 1550
brushes
 configuring in code, 1260–1261
 configuring using Visual Studio 2010,
 1258–1260
Brushes area, 1269
Brushes class, 1550
Brushes editor, 1222, 1269, 1358
Brushes type, 1547
BSTR data type, 7
btnAddWidgets control, 1435
btnCancel button, 1538
btnCancel control, 771, 772
btnChangeMakes class, 911
btnClear control, 1226
btnClearPanel control, 1436
btnDisplayMakes class, 908
btnDownload control, 768
btnExecute control, 771
btnExitApp variable, 1150
btnExitApp_Clicked() method, 1150
btnGetCar button, 1474
btnGetOrderInfo class, 925
btnGetStats control, 768
btnGetStats_Click() method, 770
btnGetTextData control, 1436
btnLoad control, 1226
btnOK button, 1538
btnPostback button, 1477
btnReset class, 1387
btnSave control, 1226
btnSetCar button, 1474
btnShow class, 1387, 1389
btnShowAppVariables button, 1486
btnShowCarOnSale button, 1486

btnShowLogicalTree object, 1342
btnShowVisualTree control, 1343
btnSpin control, 1371
btnSpinner object, 1307
btnSubmit button, 1505
btnUpdateDatabase class, 921
btnUpdateInventory control, 937
bubbling events, 1337, 1339
BufferedGraphics type, 1547
BufferedStream class, 776
BufferHeight property, System.Console
 class, 82
BufferWidth property, System.Console
 class, 82
bugs, 259–260
Build a Car menu item, 1447
Build a Car node, 1446
Build Action property, 1287, 1289, 1292
Build menu, Visual Studio 2010, 1290
Build tab, 110, 657
build tools, automated, 43
Build-a-Car, designing content page,
 1455–1457
BuildCar.aspx, 1446
BuildMenuSystem() method, 1516
BuildTableRelationship() method, 923,
 924
Bukovics, Bruce, 1077
business process, defining role of WF 4.0
 in, 1078
>> button, 1212, 1213
Button class, 920, 921, 1396, 1397, 1398,
 1399, 1408, 1409, 1422, 1423
Button Click event, 1431
Button controls, 718, 768, 1198, 1226, 1292,
 1315, 1318, 1319, 1342, 1469
Button element, 1160, 1202, 1338
Button object, implementing Click event,
 1175–1176
Button property, 1534, 1535
Button skin, 1469
Button template, 1366
Button type, 1146, 1159, 1164, 1173, 1175,
 1341, 1467, 1469
<Button> control, 1337

<Button> definition, 1132, 1160
 <Button> element, 1150, 1158, 1172, 1349, 1352
 <Button> tag, 1132
 </Button> tag, 1161
 <Button> tag, 1161, 1293
 </Button> tag, 1293
 button1_Click event, 1172
 <Button.Background> scope, 1161
 <Button.Context> scope, 1181
 Button.HeightProperty, 1305
 Buttons control, 1262
 buttons, determining which was clicked, 1535–1536
 Buttons widget, 1441
 ButtonTemplate application, 1349
 ButtonTemplate project, 1356
 by GetInvocationList() method, 404
 by operator, 509
 By property, Animation class types, 1305
 by value parameter, 160
 byte data type, 86, 108, 109, 145, 146
 ByteAnimation class, 1304

■ C

C command, 1257
 C string format character, 84
 C# 4.0 language features
 COM interoperability using, 718–724
 COM interoperability without, 722–724
 C# applications
 and .NET Framework 4.0 Software Development Kit (SDK), 41–42
 building with csc.exe
 command line flags, 43–44
 compiling multiple source files, 46–47
 overview, 42
 referencing external assemblies, 45–46
 referencing multiple external assemblies, 46
 response files, 47–49

building with Notepad++, 49–50
 building with SharpDevelop
 overview, 50
 test project, 51–53
 building with Visual C# 2010 Express, 53–54
 building with Visual Studio 2010
 Class View utility, 58–59
 code expansions, 63–64
 integrated .NET Framework 4.0 documentation, 67–69
 New Project dialog box, 56
 Object Browser utility, 60
 overview, 54
 refactoring code, 60–63
 Solution Explorer Utility, 56–58
 unique features of, 55
 Visual Class Designer, 64–67
 overview, 41
 C# compiler, 15, 32, 44, 47, 172, 605, 609, 703, 704, 1569
 C# Console Application project, 263, 277
 C# language
 anonymous methods, 427–430, 706
 custom type conversions
 among related class types, 454–455
 anonymous types, 473–478
 creating routines, 455–457
 explicit conversions for square types, 458
 extension methods, 460–470
 implicit conversion routines, 458–459
 internal representation of custom conversion routines, 460
 numerical, 454
 partial methods, 470–473
 events
 creating custom event arguments, 424–425
 event keyword, 419–421
 generic EventHandler<T> delegate, 426
 hidden methods of, 421
 incoming, listening to, 422–423

- overview, 418
- registering, simplifying using Visual Studio 2010, 423–424
- indexer methods**
 - definitions on interface types, 444
 - multiple dimensions, 443–444
 - overloading, 443
 - overview, 439–440
 - string values, 441–442
- LINQ query operators**
 - aggregation operations, 516–517
 - basic selection syntax, 510–511
 - LINQ as better Venn diagramming tool, 515–516
 - obtaining counts using enumerable, 513
 - obtaining subsets of data, 511
 - overview, 508–509
 - projecting new data types, 512–513
 - removing duplicates, 516
 - reversing result sets, 514
 - sorting expressions, 514
- operator overloading**
 - `+=` and `-+`, 448
 - binary, 445–447
 - comparison, 450
 - equality, 449–450
 - internal representation of, 451–452
 - overview, 444
 - unary, 448–449
- pointer types**
 - `*` and `&` operators, 482
 - field access with pointers, 484
 - overview, 479–480
 - pinning types with fixed keywords, 485–486
 - `sizeof` keyword, 486
 - `stackalloc` keyword, 485
 - `unsafe` (and `safe`) swap function, 483
 - `unsafe` keyword, 481–482
- C# programming constructs**, 73–123, 125–165
 - application error code, 76–77
 - arrays
 - as arguments, 142
 - implicitly typed local, 139
 - initialization syntax, 138
 - multidimensional, 140–141
 - of objects, 139–140
 - overview, 137
 - as return values, 142
 - `System.Array` class, 142–144
 - command-line arguments, 77–79
 - data type conversions
 - narrowing data conversions, 108–110
 - overflow checking, 110–111
 - overview, 106–107
 - `System.Convert`, 112
 - `unchecked` keyword, 111
 - enum type
 - declaring variables, 146–147
 - discovering name/value pairs of, 148–150
 - overview, 144
 - `System.Enum` type, 147
 - underlying storage for, 145–146
 - `if/else` statement, 120
 - implicitly typed local variables
 - are strongly typed data, 115
 - overview, 112–113
 - restrictions on, 114–115
 - usefulness of, 116
 - iteration constructs
 - `do/while` loop, 119
 - `foreach` loop, 118
 - `for` loop, 117
 - `while` loop, 119
 - methods
 - default parameter-passing behavior, 126–127
 - named parameters, 133–134
 - optional parameters, 131–132
 - `out` modifier, 127–128
 - overloading of, 135–137
 - overview, 125
 - `params` modifier, 130–131
 - `ref` modifier, 128–129
 - nullable types
 - `??` operator, 164–165

- overview, 162
- working with, 163–164
- reference types
 - passing by reference, 160
 - passing by value, 158–160
- string data
 - basic manipulation, 98–99
 - concatenation, 99–100
 - escape characters, 100–101
 - overview, 97
 - strings and equality, 102
 - strings are immutable, 102–104
 - `System.Text.StringBuilder` type, 104–105
 - verbatim strings, 101–102
- structure type, 151–153
- switch statement, 121–123
- system data types
 - class hierarchy, 90–92
 - and new operator, 89–90
 - numerical data types, 92
 - overview, 86–87
 - parsing values from string data, 94
 - `System.Boolean`, 93
 - `System.Char`, 93–94
 - `System.DateTime`, 95
 - `System.Numerics`, 95–97
 - `System.TimeSpan`, 95
 - variable declaration, 88–89
- `System.Console` class
 - basic input and output with, 82–83
 - formatting numerical data, 84–85
 - formatting output, 83
 - overview, 81
- `System.Environment` class, 79–81
- value types
 - containing reference types, 157–158
 - overview, 154
 - vs. reference types, 155–156, 161–162
 - variations on `Main()` method, 75–76
- C# Snap-In, 619–620
- C# Windows Application solution, 51
- C++ Component Object Model (COM)
 - developers, 260
- C++ function pointer, 397
- C++/Microsoft Foundation Classes (MFC), 4
- cache application Graphical User Interface (GUI), 1492
- Cache object, 1489, 1490
- Cache property, 1416, 1421, 1489
- Cache type, 1493
- Cache variable, 1490
- CacheDependency object, 1491
- CacheItemRemovedCallback delegate, 1491, 1493
- Cache.NoAbsoluteExpiration field, 1491
- Cache.NoSlidingExpiration field, 1491
- Cache.NoSlidingExpiration parameter, 1491
- CacheState project, 1489
- Calc class, 14, 15, 17
- Calc.Add() method, 34
- Calc.cs file, 16, 18, 33
- Calc.exe application, 35
- Calc.exe assembly, 33
- Calc.exe file, 18, 19
- CalculateAverage() method, 130, 131
- Calc.vb code file, 16
- Calendar control, 1439, 1455
- Calendar type, 1467
- call opcode, 678, 690
- callback functions, 397
- CallbackContract property, 1034
- callbacks, 397, 398
- calling tier, 885, 886
- CallMeHere() method, 413
- callvirt opcode, 690
- Cancel button, 1294, 1296, 1297
- Cancel() method, 772, 858
- Cancel property, 1141
- cancelation request, 766–767
- CancelButton property, 1529, 1541
- CancelEdit() method, 893
- CancelEventArgs class, 1141
- CancelEventArgs.Cancel property, 1141
- CancelEventHandler delegate, 1141
- cancellation tokens, 766
- CancellationScope activity, WF 4.0, 1092

CancellationToken property, 767
 CancellationTokenSource class, 766
 CancellationTokenSource object, 766, 772
 CancellationTokenSource token, 767
 cancelToken object, 772
 cancelToken variable, 766
 CanExecute attribute, 1205
 CanExecute event, 1203, 1205
 CanExecute handler, 1205
 CanExecute property, 1205
 CanExecuteRoutedEventArgs object, 1205
 CanHelpExecute() method, 1204
 CanRead member, Stream class, 792
 CanSeek member, Stream class, 792
 Canvas area, 1186
 Canvas class, 1138, 1162, 1250, 1252
 Canvas object, 1252, 1264, 1276
 Canvas panels, 1186–1188
 Canvas scope, 1339
 Canvas type, 1188
 <Canvas> tags, 1186
 Canvas.Bottom property, 1187, 1188
 Canvas.Left property, 1187, 1188
 Canvas.Right property, 1187, 1188
 Canvas.Top property, 1187, 1188
 CanWrite member, Stream class, 792
 Caption property, carIDColumn object, 891
 Caption property, DataColumn class, 890
 capturing graphical output, 1557
 Car constructor, 584
 Car reference, 291
 Car type
 extension methods, 465
 viewing type metadata for, 583–584
 Car variable, 169, 209
 CarAboutToBlow() method, 428
 Car.Accelerate() method, 269, 270
 carArray variable, 346
 CarAvailableInZipCode() method, 471, 473
 Car.CarEngineHandler object, 411
 Car.cs file, 167, 206, 273, 277, 343, 571, 972
 CarDelegate application, 405
 CarDelegate project, 411
 CarDelegateMethodGroupConversion application, 412
 CarDelegateMethodGroupConversion project, 413
 CarDelegateWithLambdas project, 437
 CardSpace application programming interface (API), 1023, 1030
 CarEngineHandler class, 406
 CarEngineHandler delegate, 408, 420, 425
 CarEngineHandler objects, 418
 carErrors.txt file, 281
 CaretIndex property, 1200
 CarEventArgs class, 425
 CarEventArgs type, 425
 CarEvents application, 420
 CarEvents example, retrofitting using lambda expressions, 436–437
 CarEvents project, 424
 CarExploded() method, 428
 car.gif file, 1448
 CarID column, 842, 890, 898
 CarID field, 846
 CarID key, 846
 CarID value, 843
 carIDColumn class, 892
 CarIDColumn column, 934
 carIDColumn object, 891, 892
 CarID/CustID values, 844
 CarInfoHelper class, 684
 carIsDead variable, 263
 CarIsDeadException class, 273, 274, 276, 278, 279, 280, 281
 CarIsDeadException constructor, 281
 CarIsDeadException object, 280
 CarIsDeadException type, 274, 275
 CarIsDeadException.cs file, 277
 CarLibrary assembly, 538, 561
 CarLibrary icon, 566
 CarLibrary namespace, 532, 602
 CarLibrary project, 541, 545, 546
 CarLibrary.dll assembly, 544, 545, 546, 547, 568, 569, 570, 573, 574, 575
 CarLibrary.EngineState enumeration, 582, 583
 CarLibrary.EngineState.engineAlive, 583

CarLibrary.exe file, 554
CarLibraryPolicy.xml file, 575
CarLocator class, 471, 472
CarLotInfo class, 1485
CarNickname property, 969, 971
CarOrderApp project, 1538, 1545
Cars property, 955, 971, 974
Cars web site, building
 defining default content pages, 1448–1449
 designing Build-a-Car content page, 1455–1457
 designing Inventory content pages, 1450–1452
 enabling in-place editing, 1454
 enabling sorting and paging, 1453
 master pages
 AdRotator widget, 1447–1448
 bread crumbs, establishing with **SiteMapPath** type, 1447
 overview, 1442–1444
 TreeView control site, 1445–1447
 overview, 1441
Cars.cd file, 224
carsDataSet.xml file, 901
cascading style sheet (CSS), 1394
case-sensitive languages, 74
CaseSensitive member, 897
CaseSensitive property, 887
casting operations, 247, 366, 1107
catch blocks, 267, 273, 277, 278, 279, 280, 690
catch keyword, 109, 249, 261
catch logic, 268, 270, 271, 277, 281
catch scope, 274, 278, 279, 281
catching exceptions, 266–267
CDATA scope, 1147
CDATA section, 1390
CenterToScreen() method, 1530
-**centric** dot notation, 667
ceq opcode, 678
CGI applications, 1475
cgt opcode, 678
Change Layout Type menu option, 1211
ChangeDatabase() method, 855
Channel property, 1046
char array, 98
char data type, 87
char keyword, 93
char variable, 89
character data, 102
Check button, 1196, 1198
Check for arithmetic overflow/underflow
 check box, 110
CheckBox control, 1235, 1431
Checked event, 1220
checked keyword, 73, 108, 109, 110, 111
Checked property, 1554
CheckInventoryWorkflowLib project, 1103
CheckInventoryWorkflowLib.dll assembly, 1112
CheckInventory.xaml file, 1103
Cherries.png file, 1358
child class, 189
ChildRelations member, 897
Choose Data Source dropdown box, 927, 986, 1451
CIL. *See* common intermediate language
CILCar argument, 686
CILCar class, 684
CILCar object, 687
CILCar parameter, 685
CILCarInfo class, 685
CILCarInfo.Display() method, 686
CilCars example, 688
CILCars namespace, 684, 685
CILCars.dll assembly, 686
CILCars.il file, 683
CILTypes assembly, 667
CilTypes example, 683
CILTypes.il file, compiling, 672–673
Circle class, 191, 244, 324, 328, 525
Circle type, 243, 246
circleOption **RadioButton**, 1251
Class attribute, 1146, 1177
class constructor, 675
Class Designer. *Name*, 66
Class Designer Toolbox, 65, 66, 225
Class Details window, 65, 66, 225
Class Diagram icon, 224

Class Diagram viewer, 65
 .class directive, 655, 660, 668, 669, 670, 677
 class extern tokens, 551
 class hierarchy, of system data types, 90–92
 Class icon, 167
 class keyword, 19, 167, 1158
 class libraries, isolating strongly typed database code into
 deleting data with generated codes, 942–943
 inserting data with generated codes, 941–942
 invoking stored procedures using generated codes, 943
 overview, 938
 selecting data with generated codes, 940–941
 viewing generated codes, 939–940
 Class Library project, 538, 547, 937, 939
 class library relationship, 8
 Class Library template, 1023
 Class member, 695
 class token, 677
 class types
 access modifiers
 default, 193
 and nested types, 194
 overview, 192
 automatic properties
 and default values, 208–210
 interacting with, 208
 overview, 206–207
 Common Type System (CTS), 19
 constant field data
 constants, 214–216
 read-only fields, 215–216
 static read-only fields, 216
 constructors
 custom, 172
 default, 171–173
 overview, 170
 conversions, 454–455
 defining in CIL, 668–669
 encapsulation services
 internal representation of properties, 202–203
 overview, 194
 read-only and write-only properties, 204–205
 static properties, 205–206
 using .NET properties, 198–200
 using properties within class
 definition, 200–201
 using traditional accessors and mutators, 195–197
 visibility levels of properties, 204
 new keyword, 170
 object initializer syntax
 calling custom constructors with, 212–213
 inner types, 213–214
 overview, 210–211
 and optional arguments, 180–181
 overview, 167
 partial types, 217–218
 static keyword
 classes, 187–188
 constructors, 185–187
 field data, 182–185
 methods, 181–182
 this keyword
 chaining constructor calls using, 176–178
 and constructor flow, 178–181
 overview, 174–175
 Class View tool, 59, 939
 Class View utility, Visual Studio 2010, 58–59
 Class View window, 970
 Class1.cs, 711
 ClassDiagram1.cd file, 224
 classes
 abstract, 240
 allocation onto managed heap, 291
 characteristics of, 19, 20
 creating instances of, 291
 custom, 204
 generic

default keyword in generic code, 390–391
 generic base classes, 391–392
 overview, 388–389
 specifying type parameters for, 372–374
 sealed, 232
 classical inheritance, 220
 ClassModifier keyword, 1156, 1159
 clean entities, 990
 Clean Solution option, Visual Studio 2010, 1290
 CleanUp() method, 311
 Clear() method, 82, 143, 888, 1421, 1484, 1515, 1548
 Clear Surface menu handler, 1556
 ClearCollection<T> activity, WF 4.0, 1092
 ClearErrors() method, 893
 clearing, InkCanvas data, 1226–1227
 CLI (Common Language Infrastructure)
 mainstream distributions, 1563–1564
 role of, 1562–1563
 Click event handler, 720, 908, 909, 925, 937, 1251, 1337, 1338, 1398, 1419
 Click event, implementing for Button object, 1175–1176
 Click implementation, 1343
 ClickOnce technology, 1121, 1124
 Clicks property, 1534
 client applications, building
 configuring TCP-based binding, 1049–1050
 generating proxy code using svcutil.exe, 1046–1047
 generating proxy code using Visual Studio 2010, 1047–1048
 client area, invalidating, 1551
 Client Assembly, 828
 client element, 1042
 client proxy, refreshing, 1056–1057
 client tier, 885, 886
 <client> element, 1046
 ClientBuild.rsp file, 1577
 Client.cs file, 552
 ClientRectangle property, 1527
 clients, invoking services asynchronously from, 1067–1069
 client-side scripting, 1388–1390
 ClientTarget property, 1416
 Clip property, 1255
 ClipGeometry property, 1255
 ClipToBounds property, 1265
 Clone() method, 323, 350, 351, 352, 353, 354, 888
 cloneable objects, building, 349–354
 CloneablePoint application, 349
 CloneablePoint project, 354
 CloneableType class, 323
 CloneMe() method, 323, 331
 cloning, 349
 Close() member
 BinaryReader class, 800
 BinaryWriter class, 800
 Stream class, 792
 TextWriter class, 795
 Close() method, DatabaseReader class, 189
 CloseConnection() method, 863
 Closed event, implementing, 1177
 CloseMainWindow() method, System.Diagnostics.Process class, 629
 CloseTimeout property, 1040
 Closing event, 1141, 1142
 CLR (Common Language Runtime)
 data type, 1504
 defined, 25–26
 property wrappers, 1325, 1326, 1328, 1330
 clr-namespace token, 1081, 1159
 CLS (Common Language Specification), 3, 7, 23–25, 605, 612
 [CLSCompliant] attribute, 25, 605
 clt opcode, 678
 cnStr value, 849
 Code activity, 1109–1111
 code annotations, 604
 code, autogenerated, 932
 Code Definition window, 608
 code expansions, Visual Studio 2010, 63–64

code file model, 1401
 code files
 building Web pages using, 1406–1411
 updating, 1409–1410
 code library, 532
 code reuse, 190, 532
 code snippet edit mode, 63
 <Code> element, 1147
 CodeActivity activity, 1109
 CodeActivity<T> value, 1109
 CodeActivityContext, 1109
 <codeBase> element, 556, 576–577
 <codeBase> value, 598
 CodeBaseClient application, 576, 577
 CodeBaseClient project, 577
 code-behind files, building WPF
 applications using
 MainWindow class, adding code file
 for, 1165
 MyApp class, adding code file for, 1166
 processing files with msbuild.exe,
 1166–1167
 code-behind technique, 1392, 1406
 code-conversion utility, 51
 CodeFile attribute, 1408
 CodePage attribute, 1401
 codes
 deleting data with, 942–943
 inserting data with, 941–942
 invoking using stored procedures, 943
 selecting data with, 940–941
 viewing, 939–940
 <codeSubDirectories> element, 1415
 coding
 keyword color, 49
 against ServiceHost type, 1038
 Collapse or Expand option, 329
 Collect() method, 298, 300
 Collection (Items) dialog box, 1218
 Collection (Items) property, 1217, 1219
 collection activities, WF 4.0, 1092–1093
 collection objects, applying LINQ queries
 to
 accessing contained subobjects, 506–
 507
 applying LINQ queries to nongeneric
 collections, 507–508
 filtering data using OfType<T>(), 508
 overview, 505
 CollectionCount() method, System.GC
 class, 298
 collection/object initialization syntax, 491
 collections
 nongeneric, applying LINQ queries to,
 507–508
 of objects, serializing, 816–817
 person only, 368
 .Collections.Specialized namespace, 363
 colon operator, 133, 177, 220, 223, 393
 Color class, 1261
 color coding, 49
 Color enum, 194
 Color object, 1225, 1261
 Color property, 1110, 1258
 color selector, 1259
 Color type, 1547
 ColorAnimation class, 1304
 ColorAnimation type, 1304
 ColorChanged handler, 1221
 ColorChanged() method, 1224, 1225
 ColorColumn column, 934
 ColorConverter class, 1225
 Colors enumeration, 1261
 Column Properties editor, 842
 <ColumnDefinition> element, 1191
 ColumnMapping property, DataColumn
 class, 890
 ColumnName property, DataColumn
 class, 890
 Columns class, 890, 891
 Columns collection, 900, 941, 943
 Columns indexer, 934
 Columns property, 890, 892
 COM (Application Component Object
 Model) object, 1483
 COM (C++ Component Object Model)
 developers, 260
 COM (Component Object Model)
 classes, 5
 clients, 261

- frameworks, 889
- interfaces, 261
- objects, 1483
- programming language comparison, 5–6
- servers, 5
- COM (Session Component Object Model) object, 1483
- COM interoperability
 - simplifying using dynamic data
 - common COM interop pain points, 717–718
 - embedding interop metadata, 716–717
 - overview, 714
 - role of Primary Interop Assemblies (PIAs), 715
 - using C# 4.0 language features, 718–724
 - without C# 4.0 language features, 722–724
- COM+ layer, 1016
- COM+ objects, 1015, 1022
- COM+/Enterprise Services, 1015
- Combine menu, 1268
- Combine() method, 401
- CombinedGeometry class, 1255
- ComboBox control, Ink API tab, 1224–1226
- ComboBoxItem control, 1218, 1225
- ComboBoxItem objects, 1219, 1225
- comboColors control, 1219
- comContracts element, 1042
- comma-delimited list, 130, 393
- command builder type, 918
- command line, generating strong names at, 561–563
- Command object, 827, 828, 834
- command prompt
 - Mono, 1568, 1572, 1577
 - Visual Studio 2010, 33, 534
- Command property, connecting WPF commands to, 1202–1203
- CommandBinding objects, 1203
- <CommandBinding> definitions, 1205
- CommandBindings collection, 1205
- CommandCollection property, 937
- command-line arguments, C# programming, 77–79
- command-line compiler, 537, 550, 552
- command-line parameters, 43, 76
- CommandText property, 858, 867, 870
- CommandTimeout member, 858
- CommandTimeout property, 959
- CommandType enum, 858
- CommandType property, 858
- CommandType.StoredProcedure value, 870
- Commit() method, 879, 882
- COMMIT statement, 878
- committed transactions, 878
- Common Controls section, 1544
- common dialog boxes category, 1512
- common intermediate language (CIL)
 - .NET base class library, C#, and CIL data type mappings, 673
- and assemblies
 - benefits of, 16–17
 - compiling to platform-specific instructions, 17
 - overview, 14–15
- attributes, role of, 655
- building .NET assembly with
 - building CILCarClient.exe, 686–687
 - building CILCars.dll, 683–686
 - compiling CILTypes.il file, 672–673
- defining and implementing interfaces in, 670
- defining class types in, 668–669
- defining current assembly in, 667
- defining enums in, 671
- defining field data in, 674–675
- defining generics in, 671–672
- defining member parameters, 676–677
- defining namespaces in, 668
- defining properties in, 676
- defining structures in, 670–671
- defining type constructors in, 675
- defining type members in, 674–677
- directives, role of, 655
- exploring assemblies using ildasm.exe, 34

- opcodes
 - .maxstack directive, 680
 - declaring local variables in CIL, 680–681
 - hidden this reference, 682
 - mapping parameters to local variables in CIL, 681
 - overview, 677–679
 - representing iteration constructs in CIL, 682–683
 - role of, 655
- overview, 653
- reasons for learning grammar of, 653–654
- round-trip engineering
 - authoring CIL code using SharpDevelop, 665–666
 - compiling CIL code using ilasm.exe, 663–664
 - interacting with CIL, 662–663
 - overview, 658–660
 - role of CIL code labels, 661–662
 - role of pverify.exe, 666
 - specifying externally referenced assemblies in, 666
 - stack-based nature of, 656–658
- Common Language Infrastructure (CLI)
 - mainstream distributions, 1563–1564
 - role of, 1562–1563
- Common Language Runtime (CLR)
 - data type, 1504
 - defined, 25–26
 - property wrappers, 1325, 1326, 1328, 1330
- Common Language Specification (CLS), 3, 7, 23–25, 605, 612
- Common Object Request Broker Architecture (CORBA), 1014
- Common Object Runtime Execution Engine, 25
- Common Properties area, 1214, 1218, 1220, 1236
- Common Properties section, 1217, 1219
- Common Type System (CTS)
 - class types, 19
 - data types, 22–23
 - delegate types, 21–22
 - enumeration types, 21
 - interface types, 20
 - structure types, 20
 - type members, 22
- commonBehaviors element, 1042
- CommonSnappableTypes namespace, 621
- CommonSnappableTypes.dll assembly, 618, 619, 621, 622
- CommunicationState enumeration, 1041
- Company property, 206
- [CompanyInfo] attribute, 619, 623
- CompanyInfoAttribute attribute, 619
- companyName field, 206
- comparable objects, building
 - custom properties, custom sort types, 358
 - overview, 354–356
 - specifying multiple sort orders (IComparer), 357–358
- ComparableCar application, 355
- ComparableCar project, 359
- Compare() method, 97, 383
- CompareExchange() method, Interlocked class, 756
- CompareTo() method, 355, 356
- CompareValidator control, 1458
- CompareValidator type, 1459
- CompareValidator widget, 1461–1462
- comparison operator overloading, 450
- CompensableActivity activity, WF 4.0, 1092
- Competed event, 1091
- compilation cycle for multifile pages, 1410
- compilation cycle for single-file pages, 1405–1406
- <compilation> element, 1410
- <Compile> elements, 1166
- compiler error, 88, 128, 132
- compiler flags, 44
- compile-time error, 115, 139
- Complain() method, 181, 182
- Completed event, 1307
- Completed property, 1088
- Complex structure, 95

Component, 1301
 Component Object Model. *See* COM
 component tray, 931
 ComponentCommands class, WPF, 1201
 components category, 1512
 composition, of applications, 1025–1027
 Concat() method, 516
 concatenation, of string data, 99–100
 concatenation symbol, 1094
 conceptual model, 958
 concurrency, 728–729, 750–758
 concurrent garbage collection, 297
 Condition editor, 1107
 Condition property, 1097
 conditional code compilation, partial methods, 472
 *.config file extension, 554
 *.config files, 555, 556, 569, 570, 573, 574, 848, 849, 850, 852, 853
 configuration files, altering using SvcConfigEditor.exe, 1059–1061
 <configuration> element, 555, 1415
 ConfigurationManager class, 1427
 ConfigurationManager type, 839
 ConfigurationManager.AppSettings indexer, 849, 852
 ConfigurationManager.ConnectionStrings indexer, 852
 ConfigurationName property, 1034
 ConfigureAdapter() method, 917, 918
 ConfigureCUI() method, 62
 ConfigureGrid() method, 1242
 configuring tab order, 1540
 configuring TCP-based binding, 1049–1050
 Connect() method, 1151
 Connect Timeout segment, 855
 connected layer, of ADO.NET
 command objects, 858
 connection objects, 854–856
 ConnectionStringBuilder objects, 856–857
 overview, 853
 Connection member, 858
 connection object, 827, 833, 839
 Connection property, 853, 858, 879, 959
 connection string, 854, 856
 Connection String property, 849
 connection timeout setting, 855
 ConnectionState enumeration, 855, 856
 ConnectionState values, 856
 ConnectionState.Closed value, 856
 ConnectionState.Open value, 856
 connectionString attributes, 852
 ConnectionString property, 849, 855, 857, 1451
 <connectionString> element, 1504
 ConnectionStringBuilder objects, 856–857
 <connectionStrings> element, 847, 852–853, 871, 932, 1427, 1451
 <connectionStrings> value, 1451
 ConnectionTimeout property, 855
 Consistent, 878
 Console Application project, 273, 712
 Console class, 28, 75, 81, 82, 181
 Console namespace, 30, 532
 Console project, 712
 Console type, 82, 754
 console user interface (CUI), 81
 Console window, 566
 Console.Beep() method, 312
 ConsoleClientApp.cs, 1576
 ConsoleClientApp.exe, 1578
 ConsoleClientApp.exe file, 1576, 1577
 ConsoleColor enumeration, 81
 ConsoleColor variables, 133
 Console.ReadLine() method, 61, 75, 750, 875, 1095
 Console.WriteLine() method, 83, 136, 178, 366, 430, 434, 551, 663, 690, 731
 const keyword, 214, 218
 constant field data
 constants, 214–216
 read-only fields, 215–216
 static read-only fields, 216
 ConstData project, 214, 217
 Constraint type, System.Data namespace, 832
 constraints, 361
 Constraints member, 897
 ConstructingXmlDocs application, 1002

ConstructorBuilder, `DefineProperty()`
 method, 696
ConstructorBuilder member, 689
ConstructorBuilder type, 690, 696
constructors
 arguments, 205
 chaining calls, 176–178, 180, 199
 for classes
 custom, 172
 default, 171–173
 overview, 170
 definition, single, 180
 emitting, 696–697
 flow of, and `this` keyword, 178–180
 static, 185–187
contained controls, enumerating, 1432–
 1435
ContainerControl class, 1529
containers
 generating documents from, 1004–1005
 type-safe, 367
ContainerVisual class, 1277
ContainerVisual object, 1258
containment, programming for, 232–235
containment/delegation model, 190, 219,
 232
Contains() method, 97, 98
content display area, 1354
content model, WPF, 1226
content pages
 default, 1448–1449
 designing, 1455–1457
Content property, 1131, 1132, 1181, 1185,
 1218, 1219, 1236, 1238, 1353, 1354
ContentControl class, 1117, 1131, 1132,
 1181, 1185
ContentEncoding property, 1421
ContentPlaceHolderID value, 1449
ContentPresenter class, 1344, 1352, 1354
ContentProperty class, 1241
ContentType property, 1421
context 0 (default context), application
 domain, 648
context attributes, 649
Context property, 1489, 1490
ContextBoundObject class, 757
Context.Cache property, 1488
Context.Cache.Insert() method, 1490
context.Inventories, 1242
ContextMenu property
 FrameworkElement type, 1133
contextual boundaries, AppDomain, 625
contextual keyword, 199
continue keyword, 117
contract element, 1037
contracts
 data, 1070–1076
 operational, service types as, 1035–1036
 WCF, 1027
contravariance, 9, 10, 414
Control class, 1132, 1314, 1404, 1416, 1512,
 1515, 1526–1529
control declarations, ASP.NET, 1403–1404
control flow activities, WF 4.0, 1089
Control Flow area, 1104
Control Library section, 1184
Control Panel, 1500
Control property, 1537
control templates, WPF
 building custom with Visual Studio
 2010
 `{TemplateBinding}` markup
 extension, 1352–1353
 ContentPresenter, 1354
 incorporating templates into styles,
 1354–1355
 incorporating visual cues using
 triggers, 1351–1352
 overview, 1348
 templates as resources, 1349–1351
default
 overview, 1341–1343
 programmatically inspecting, 1344–
 1348
Control type, 1132, 1133, 1346, 1437
control-agnostic events, 1200
ControlBox property, 1529
ControlCollection object, 1432
controls. *See also* ASP.NET web controls
 collection, populating, 1515–1517

contained, enumerating, 1432–1435
 created dynamically, 1436–1437
 dynamically adding and removing,
 1435–1436
 dynamically created, 1436–1437
 for validation
 CompareValidator widget, 1461–
 1462
 creating summaries, 1462–1463
 defining groups, 1463–1465
 overview, 1457–1458
 RangeValidator widget, 1460–1461
 RegularExpressionValidator widget,
 1460
 RequiredFieldValidator widget,
 1459–1460
 WebControl base class, 1437–1438
 Controls node, 1229
 Controls property, 1432, 1515, 1516, 1527
 Controls.Add() method, 1515
 ControlsCollection class, 1515
 ControlsCollection container, 1515
 ControlTemplate class, 1344
 ControlTemplate object, 1348
 <ControlTemplate> tag, 1351
 <ControlTemplate.Triggers> collection,
 1352
 ControlToValidate property, 1458, 1459,
 1461
 conversion routines, custom, 460
 conversions, numerical, 454
 Convert class, 112
 Convert() method, 1241
 Convert to New Resource option, 1301
 Convert type, 112
 ConvertBack() method, 1241
 Cookie collection, 1498
 cookies
 creating, 1498–1499
 overview, 1497
 reading incoming data, 1499
 Cookies property, 1418, 1421
 CookieStateApp project, 1498
 cool factor, 600
 Copy command, 1200
 Copy Local property, 568
 Copy() method, 888, 897
 Copy to Output Directory property, 1008,
 1287, 1289
 CopyTo() method
 Array class, 143
 FileInfo class, 785
 CopyToDataTable<T>() method, 948
 CORBA (Common Object Request Broker
 Architecture), 1014
 core assemblies of Windows
 Communication Foundation
 (WCF), 1022
 core infrastructure category, 1512
 Core user input controls, WPF, 1179
 CoreLibDumper class, 1572
 CoreLibDumper.dll, assigning strong
 name to, 1574
 CoreLibDumper.dll library, 1572
 cores, 761
 CorLibDumper folder, 1572, 1575
 CorLibDumper project, 1580
 CorLibDumper.dll assembly, 1574, 1575,
 1577, 1578
 CorrelationScope activity, WF 4.0, 1090
 corrupted state exceptions (CSE), 285, 286
 Count() method, 513, 516, 1515
 Count property, 934, 1484
 Count<>() method, 509
 covariance, 9, 10, 414
 CPU-agnostic intermediate language, 536
 CrazyOrange folder, 1467
 CrazyOrange theme, 1467, 1469
 CrazyOrange.skin file, 1467
 Create() method
 DirectoryInfo class, 778
 FileInfo class, 785, 786
 FileMode enumeration, 787
 Create New SQL Server Database menu
 option, 840
 CREATE PROCEDURE statement, 843
 CreateCommand() method, 322
 CreateDataReader() method, 900, 944
 CreateDataTable() method, 906
 CreateDataView() method, 912

CreateDomain() method, AppDomain class, 638
 CreateInstance() method, 601, 638
 CreateMyAsm() method, 691, 692, 693, 697
 CreateNew member, FileMode enumeration, 787
 CreateObject<T> () method, 959
CreateSalesMemoActivity.cs, 1109
 CreateSubdirectory() method, DirectoryInfo class, 778, 781
 CreateText() method, FileInfo class, 785, 789
 CreateThread() function, 626
 CreateUsingLateBinding() method, 602
 CreationTime property, FileSystemInfo class, 778
 Credentials property, 1040
 CreditRisks table, adding to AutoLot database, 879–880
 cross-language inheritance, 549
 *.cs extension file, 45, 289
 *.cs file extension, 43, 46, 47, 50, 55, 217
 csc (C-sharp compiler), 42
 csc.exe compiler, 15, 24, 41, 43, 45, 46, 47, 48, 1149
 csc.exe file, building C# applications with command line flags, 43–44
 compiling multiple source files, 46–47
 overview, 42
 referencing external assemblies, 45–46
 referencing multiple external assemblies, 46
 response files, 47–49
 csc.rsp response file, 48
 CSE (corrupted state exceptions), 285, 286
 C-sharp compiler (csc), 42
 CSharpCarClient application, 546
 CSharpCarClient project, 546, 547
 CSharpCarClient.exe application, 553
 CSharpCarClient.exe file, 547, 553, 554, 555
 CSharpCarClient.exe.config file, 554, 555, 557
 CSharpModule class, 619
 CSharpModule type, 620
 CSharpSnapIn project, 619, 620
 CSharpSnapIn.dll assembly, 618, 621, 623
 *.csproj file, 1148, 1150, 1151, 1166
 CSS (cascading style sheet), 1394
 CssClass property, WebControl Base Class, 1438
 CssStyle property, 1465
 C-style function pointer, 21
 .ctor directive, 675
 ctor token, 675, 689
 Ctrl+M keystroke, 544, 581
 Ctrl+Z keyboard shortcut, 1268, 1523
 CTS (Common Type System)
 class types, 19
 data types, 22–23
 delegate types, 21–22
 enumeration types, 21
 interface types, 20
 structure types, 20
 type members, 22
 CTS (enumeration types, Common Type System), 21
 CType operator, 1107
 cubic Bezier curve, 1257
 CUI (console user interface), 81
 curly brackets, 83, 138
 currBalance field, 183
 Current () method, 344
 Current Inventory table, 916
 Current property, Application class, 1129
 Current value, 896
 currentColor variable, 1556
 CurrentContext property,
 System.Threading.Thread Class, 741
 CurrentDomain property, AppDomain class, 639
 CurrentNumber property, 1333, 1334, 1335, 1336
 CurrentNumberChanged() method, 1336
 CurrentPriority member, ProcessThread type, 633
 currentShape variable, 1251, 1252, 1555

CurrentThread property,
 System.Threading.Thread Class,
 741

currentVideoGames array, 519
 currentVideoGames variable, 500
 currInterestRate field, 183, 185
 currInterestRate variable, 186
 currPay field, Employee class, 196
 currSpeed field, 170, 686
 Cursor property, 1133, 1198, 1526
 curves, cubic Bezier, 1257
 CustID field, 846
 CustID key, 846
 CustID parameter, 882
 CustID value, 845
 custom attributes
 applying, 610
 named property syntax, 610–611
 overview, 609
 restricting usage, 611–612
 custom classes, 204, 758
 custom constructor, 153
 custom conversion routines, internal
 representation of, 460
 custom event arguments, creating, 424–
 425
 custom exceptions, building, 273–276
 custom interfaces, defining, 325–327
 custom layout manager, rendering to,
 1280–1282
 custom metadata viewer
 displaying various odds and ends, 592
 fields and properties, 591
 generic types, 594
 implemented interfaces, 591
 implementing Main() method, 592–593
 method parameters and return values,
 594–595
 methods, 590
 overview, 590
 custom namespaces, defining
 creating nested namespaces, 530
 default namespace of Visual Studio
 2010, 531
 overview, 525–526

resolving name clashes with aliases,
 528–530
 resolving name clashes with fully
 qualified names, 527–528
 custom objects, persisting, 1507–1509
 .custom tokens, 542, 544
 custom type conversions
 among related class types, 454–455
 anonymous types
 containing anonymous types, 478
 equality for, 476–478
 internal representation of, 474–475
 overview, 473
 ToString() and GetHashCode(), 476
 creating routines, 455–457
 explicit conversions for square types,
 458
 extension methods
 extending interface types with, 469–
 470
 extension libraries, 467–468
 importing types that define, 465–466
 IntelliSense mechanism, 466–467
 invoking on instance level, 463
 invoking statically, 464
 overview, 460–462
 scope of, 464–465
 implicit conversion routines, 458–459
 internal representation of custom
 conversion routines, 460
 numerical, 454
 partial methods, 470–473
 custom view state data, adding, 1478–1479
 CustomAttribute tokens, 586
 CustomAttributeBuilder member, 689
 CustomBinding class, 1028
 CustomConversions project, 455, 460
 CustomDepPropApp application, 1331
 CustomDepPropApp project, 1337
 CustomEnumerator project, 345
 CustomEnumeratorWithYield application,
 346
 CustomEnumeratorWithYield project, 349
 <customErrors> element, 1427

customers table, creating in AutoLot database, 844
CCustomException class, 273
 CustomException namespace, 343
 CustomException project, 273
 CustomGenericMethods application, 385
 CustomGenericMethods project, 388
 CustomInterface application, 325
 CustomInterface project, 335
 customizing Soap/Binary serialization processes
 overview, 818–819
 using attributes, 823
 using *ISerializable*, 820–822
 CustomNamespaces application, 525
 CustomNamespaces namespace, 527
 CustomNamespaces project, 531
 CustomNamespaces.exe assembly, 525
 CustomSerialization project, 821
 CustomValidator control, 1458
 CustomVisualFrameworkElement class,
 1283
 CustomVisualFrameworkElement objects,
 1281
 Cut command, 1200
 Cut operation, 1202
 C/Windows application programming interface (API), 4

D

D command, 872
 D string format character, 84
 daemon threads, 750
 dash (-) symbol, 44
 data
 2D graphical, 1254
 deleting with generated codes, 942–943
 inserting with generated codes, 941–
 942
 interactive graphical, 1246
 interoperability, 716
 private, 195
 private points of, 207

public point of, 199
 read-only field, 215
 selecting with generated codes, 940–
 941
 stack-based, 366
 data access library, ADO.NET, reusing
 adding connection logic, 863
 adding deletion logic, 865
 adding insertion logic, 863–864
 adding selection logic, 866
 adding update logic, 865
 executing stored procedure, 869–871
 overview, 861–862
 parameterized command objects, 867–
 869
 data access logic, adding, 1397–1401
 data adapter class, 913
 data adapters
 configuring using SqlCommandBuilder
 class, 918–919
 mapping database names to friendly
 names, 916
 overview, 913
 prepping, 922–923
 simple data adapter example, 914–915
 strongly typed, 936–937
 data allocation, in-memory, 183, 184
 data binding
 entities, to Windows Forms GUIs, 986–
 989
WPF
 Data Binding tab, 1236
 DataContext property, 1239
 DataGrid tab, 1242–1244
 establishing data bindings, 1236–
 1238, 1241–1242
 IValueConverter interface, data
 conversion using, 1240–1241
 overview, 1235
 Data Binding option, 1236
 Data Binding tab, WPF, 1214, 1236
 data caching, 1489–1491
 Data Connections node, 840
 data contracts, designing
 examining Web.config files, 1075

- implementing service contracts, 1073–1074
- overview, 1070
- role of *.svc files, 1074
- testing services, 1075–1076
- using Web-Centric service project templates, 1071–1073
- Data Control Language (DCL)**, 885
- Data Definition Language (DDL)**, 885
- data parallelism, 763–766
- data points, 189
- Data property**, 270–272, 274, 1101, 1254, 1255, 1256, 1257, 1267
- data provider factory model**, ADO.NET
 - <connectionStrings> element, 852–853
 - complete data provider factory example, 848–851
 - overview, 847
 - potential drawback with provide factory model, 851–852
- data providers**, ADO.NET
 - abstracting using interfaces, 837–840
 - Microsoft-supplied, 829–830
 - overview, 827–828
 - system.Data.OracleClient.dll, 830–831
 - third-party, obtaining, 831
- data readers**, ADO.NET, 859–861
- data relationships and multitablet DataSet objects**
 - building table relationships, 924
 - navigating between related tables, 925–927
 - overview, 921
 - prepping data adapters, 922–923
 - updating database tables, 924
- Data Source Configuration Wizard**, 928, 931, 933, 936
- Data Source name**, 854
- data templates**, 1244
- data type conversions**
 - narrowing data conversions, 108–110
 - overflow checking, 110–111
 - overview, 106–107
 - System.Convert, 112
 - unchecked keyword, 111
- data type variable**, 90
- data types**
 - Common Type System (CTS), 22–23
 - nullable, 837
- data validation logic**, 210
- DataAdapter object**, 828
- Database Diagrams node**, 846
- Database Explorer window**, 840
- Database Management System (DBMS)**, 827, 829, 830, 886
- database management systems (DBMS)**, 830, 851, 867
- database names**, mapping to friendly names, 916
- Database property**, 855
- database tables**, updating, 924
- database transactions**, ADO.NET
 - adding CreditRisks table to AutoLot database, 879–880
 - adding transaction method to InventoryDAL class, 880–882
 - key members of transaction object, 878–879
 - overview, 877
 - testing, 882–883
- DatabaseReader class**, 164, 189
- .DataBind()** method, 1432
- data-binding logic**, 1236
- data-binding model**, WPF, 1135
- DataColumn class**, 885, 887, 889, 890, 891, 892, 894, 904
- DataColumn objects**, 886, 890, 891, 892, 893, 898, 906
- DataColumn types**
 - adding objects to DataTable types, 892–893
 - building, 891–892
 - enabling autoincrementing fields, 892
 - overview, 889–890
 - System.Data namespace, 832
- DataContext property**, 1239
- [DataContract] attribute**, 1027, 1070
- DataGridView control**, 1242
- DataGridView objects**, 1235
- DataGridView tab**, WPF, 1214, 1242–1244

DataGridView class, 903, 904, 906, 907, 912, 920, 921, 924, 927, 928
DataGridView control, 927–932
DataGridView object, 906, 921, 986
DataGridView widget, 322
DataGridView wizard, 939
dataGridViewCustomers widget,
 DataGridView class, 921
DataGridViewDataDesigner project, 927, 938
dataGridViewInventory widget,
 DataGridView class, 921
dataGridViewOrders widget, **DataGridView**
 class, 921
dataGridViewYugosView class, 912
[DataMember] attribute, 1027, 1070, 1071
DataParallelismWithForEach application, 763
DataParallelismWithForEach project, 768
DataProviderFactory application, 848, 853
DataProviderFactory project, 853
DataProviderFactory.exe assembly, 848
DataReader class, 900
DataReader object, 827
DataRelation class, 885, 887, 925
DataRelation collection, 921
DataRelation objects, 921, 924
DataRelation type, **System.Data**
 namespace, 832
DataRelationCollection class, 887
DataRow class, 885, 893, 895, 896, 934, 935, 939, 941, 946, 947
DataRow indexers, 948
DataRow objects, 886, 893, 894, 895, 896, 907, 908, 916, 947
DataRow type
 DataRowVersion property, 896–897
 overview, 893
 RowState property, 894–896
DataRow type, **System.Data** namespace, 832
DataRow.AcceptChanges() method, 896
DataRow.BeginEdit() method, 896
DataRow.CancelEdit() method, 896
DataRowCollection class, 895
DataRow.EndEdit() method, 896
DataRowExtensions class, 946
DataRowExtensions.Field<T>() Extension
 method, 948
DataRow.RejectChanges() method, 897
DataRows, strongly typed, 935
DataRowState enumeration, 894, 895
DataRowState property, 896
DataRowVersion enumeration, 896
DataRowVersion property, 896–897
DataSet class, 885, 886, 932, 933, 937, 938, 939, 1420, 1479, 1488
DataSet container, 951
Dataset Designer, Visual Studio 2010, 933
DataSet extensions library, 945–946
DataSet member, 897
DataSet model, 929
DataSet objects, 494, 864, 885, 886, 899, 932, 945, 946, 951
DataSet types
 building, 889
 key methods of, 888
 key properties of, 887
 overview, 886
 programming to with LINQ
 DataSet extensions library, 945–946
 obtaining LINQ-compatible
 datatables, 946–947
 overview, 943–944
 populating new **DataTable**s from
 LINQ queries, 948–950
 role of
 DataRowExtensions.Field<T>()
 Extension method, 948
 System.Data namespace, 832
DataSetName property, 887
DataSets
 inserting **DataTable**s into, 898
 obtaining data in, 898–899
 strongly typed, 932–934
DataSet.WriteXml() method, 890
DataSource property, 855, 906, 913, 921, 949
DataSourceID property, 1446, 1447, 1450, 1451

DataTable class, 866, 885, 886, 888, 891, 892, 935, 936, 937, 939
 DataTable objects, binding to Windows Forms GUIs
 DataGridView type, 912–913
 deleting rows from DataTable, 907–908
 hydrating DataTable from generic List<T>, 904–906
 overview, 903
 selecting rows based on filter criteria, 908–911
 updating rows within DataTable, 911
 DataTable type
 adding objects to, 892–893
 inserting into DataSets, 898
 obtaining data in DataSets, 898–899
 overview, 897
 processing data using DataTableReader objects, 899–901
 serializing DataTable/DataSet objects as XML, 901–902
 serializing DataTable/DataSet objects in binary format, 902–903
 System.Data namespace, 832
 DataTable variable, 906
 DataTable.AcceptChanges() method, 896
 DataTableCollection class, 887
 DataTableCollection type, 443
 DataTable/DataSet objects
 serializing as XML, 901–902
 serializing in binary format, 902–903
 DataTableExtensions class, 946, 947
 DataTableMapping class, 916
 DataTableMappingCollection collection, 916
 DataTable.NewRow() method, 894
 DataTableReader class, 900, 1074
 DataTableReader objects, using to processing data, 899–901
 DataTableReader type, System.Data namespace, 832
 DataTables class
 hydrating from generic List<T>, 904–906
 populating from LINQ queries, 948–950
 strongly typed, 934
 dataToShow variable, 1342
 DataType property, DataColumn class, 890
 DataTypeFunctionality() method, 93
 DataView class, 885, 912, 913, 949
 DataView object, 904
 DataView type, 832, 912–913
 DatePicker control, 1347
 DateTime class, 132
 DateTime structure, 95
 DateTime type, 85, 95
 DateTime variable, 89
 DateTime.Now.AddSeconds(15) parameter, 1491
 DbCommand class, 827, 847, 957
 DbCommand type, 858
 DbConnection class, 827, 837, 847, 855, 957
 DbDataAdapter class, 828, 847, 886, 913, 914
 DbDataReader class, 827, 847
 DbDataReader object, 858
 DbDataReader type, 859
 DBMS (Database Management System), 827, 829, 830, 886
 DBMS (database management systems), 830, 851, 867
 DbParameter class, 828, 847
 DbParameter objects, 858
 DbParameter type, specifying parameters using, 867–869
 DbProviderFactories class, 848
 DbProviderFactory class, 848
 DbProviderFactory object, 848
 DbTransaction class, 828, 847
 DbType property, 868
 DCL (Data Control Language), 885
 DCOM (Distributed Component Object Model), 1014–1015, 1019
 DDL (Data Definition Language), 885
 Deactivate event, 1531, 1532, 1533
 deactivated, 1531
 Debug folder, 76, 546, 1114, 1149, 1287
 Debug tab, Visual Studio 2010, 79, 80
 debugging ASP.NET pages, 1410–1411

DecelerationRatio property, Timeline class, 1305
 decimal data type, 87
 DeclareImplicitVars() method, 113
 DeclareLocal() method, 690
 Decrement() method, 756, 757
 dedicated databases, storing session data in, 1502
 deep copy, 350
 default application domain, 638
 default constructor, 89, 153, 211, 212, 393
 default content pages, 1448–1449
 default context (context 0), application domain, 648
 Default edit area, 1107
 default endpoints, 1051–1052
 default input button, setting, 1541
 default keyword, 390
 Default namespace option, 531
 Default property, 1106
 Default value, 896, 1368
 Default.aspx file, 1446, 1449, 1468, 1469, 1493, 1505, 1506
 Default.aspx page, 1496, 1505
 DefaultDrawingAttributes property, 1224
 defaultProvider, 1505
 default(T) syntax, 390
 defaultValue attribute, 1504
 DefaultValue property, DataColumn class, 890
 DefaultView member, 897
 DefineConstructor() method, 696
 DefineDefaultConstructor() method, 697
 DefineDynamicModule() method, 694
 DefineEnum() method, 694
 DefineLabel() method, 690
 DefineMethod() method, 697
 DefineResource() method, 694
 DefineType() method, 694
 defining groups, 1463–1465
 user profiles within Web.config, 1504–1505
 DefiningGeometry property, Shape class, 1248

definitions on interface types, 444
 Delay activity, WF 4.0, 1091
 Delegate, 412
 delegate keyword, 21, 398, 399, 400, 401, 432
 delegate variable, 412
 Delegate.Combine() method, 409, 421
 DelegateCovariance application, 413
 DelegateCovariance project, 415
 delegate/event model, 9
 Delegate.Remove() method, 410, 421
 delegates .NET delegate type, 397–398
 asynchronous nature of BeginInvoke() and EndInvoke() methods, 732
 overview, 731
 System.IAsyncResult interface, 732–733
 defining delegate type in C#, 398–400
 delegate covariance, 413–415
 generic, 415–418
 method group conversion syntax, 411–413
 sending object state notifications using enabling multicasting, 408–409
 overview, 405–407
 removing targets from delegate's invocation list, 410–411
 simplest possible delegate example, 402–404
 System.MulticastDelegate and System.Delegate base classes, 400–401
 delegation, programming for, 232–235
 DELETE command, 914
 delete keyword, 9, 289
 Delete() method
 DataRow class, 895, 907
 Directory class, 783
 DirectoryInfo class, 778
 FileInfo class, 785
 FileSystemInfo class, 778
 Delete statement, 861, 862, 1450
 Delete Sticky Note button, 1234

DeleteCar() method, 875
DeleteCommand property, 914, 918, 949
Deleted value, 895
DeleteObject() method, 959, 975, 976
deleting records, 974–975
Delta property, 1535
demonstrating view state, 1477–1478
dependency properties, WPF
 building custom, 1331–1336
 CLR property wrappers, 1330
 examining existing, 1327–1330
 overview, 1325–1326
DependencyObject class, 1135, 1326
DependencyObject parameter, 1335, 1336
DependencyProperty field, 1326, 1330
DependencyProperty object, 1328, 1330, 1336
DependencyProperty variable, 1326
DependencyPropertyChangedEventArgs parameter, 1335
DependencyProperty.Register() method, 1326, 1328, 1329, 1335
<dependentAssembly> element, 573, 574
deprecated, 830
Dequeue() method, 382, 383
derived class, casting rules
 is keyword, 250
 as keyword, 249
 overview, 247–248
derived types, 323, 324
DerivedCars.cs file, 540
DESC (descending), 910
DescendantNodes<T>() method, 1000
Descendants() method, 1008
Descendants<T> method, 1000
descending (DESC), 910
descending operator, 509, 514
Description property, 610, 615, 1065
Desendants() method, 1001
deserialization, defined, 804
Deserialize() method
 BinaryFormatter type, 811, 813
 IFormatter interface, 809
 SoapFormatter type, 813
deserializing objects, 812–813
Design tab, SharpDevelop, 52
designer toolbox, SharpDevelop, 52
<Designer> element, 970
.Designer.cs file, 1520
*.Designer.cs files, 1521
desktop applications, WPF and XAML, 1121–1123
desktop markup, 1119
desktop program, navigation-based, 1124
Detached value, 895
development web server, ASP.NET, 1382
diagnostics element, 1043
dialog boxes
 designing
 configuring tab order, 1540
 DialogResult property, 1539
 displaying dialog boxes, 1542–1543
 overview, 1538
 setting form's default input button, 1541
 Tab Order Wizard, 1540–1541
 understanding form inheritance, 1543–1545
 WPF, 1183
Dialog class, 1538
DialogResult enumeration, 1539
DialogResult property, 1539
DialogResult type, 1532
DialogResult values, 1542, 1553
diamond button, 1293
dictionaries, merged resource, 1298–1299
Dictionary object, 1088, 1105
Dictionary-> object, 1094
Dictionary-> variable, 1086
Dictionary<K,V> object, 952
Dictionary<string, object> variable, 1084
Dictionary< TKey, TValue > class, 377
DictionaryEntry type, 271
digital signature, 560, 561
dimensions, indexers with multiple, 443–444
direct event, 1338
Direct Selection button, 1213
Direction property, 843, 868, 871
directives

ASP.NET, 1401–1403
 role of CIL, 655
 directly creating types, 797–798
Directory class, 776, 777
Directory method, *FileInfo class*, 785
Directory types, 782–783
DirectoryApp project, 783
Directory.GetFiles() method, 764
DirectoryInfo class, 776, 777
DirectoryInfo types
 abstract *FileSystemInfo base class*, 777–778
 creating subdirectories with
 DirectoryInfo type, 781–782
 enumerating files with *DirectoryInfo type*, 780–781
DirectoryName method, *FileInfo class*, 785
DirectX layer, 1120
dirty entities, 990
dirty window, 1549
DisableAllButton style, 1319
Disassembler window, 36
disco utility, Mono, 1571
disco.exe utility, Microsoft .NET, 1571
disconnected functionality, testing, 920–921
disconnected layer, of ADO.NET
 adding disconnection functionality to
 AutoLotDAL.dll
 configuring data adapters using
 SqlCommandBuilder class, 918–919
 defining initial class types, 917
GetAllInventory() method, 919
 setting version numbers, 919
 testing disconnected functionality, 920–921
UpdateInventory() method, 919
binding DataTable objects to Windows Forms GUIs
DataView type, 912–913
 deleting rows from *DataTable*, 907–908
 hydrating *DataTable* from generic *List<T>*, 904–906
 overview, 903
 selecting rows based on filter criteria, 908–911
 updating rows within *DataTable*, 911
data adapters
 mapping database names to friendly names, 916
 overview, 913
 simple data adapter example, 914–915
 DataColumn types
 adding objects to *DataTable* types, 892–893
 building, 891–892
 enabling autoincrementing fields, 892
 overview, 889–890
DataRow type
DataRowVersion property, 896–897
 overview, 893
RowState property, 894–896
DataSet types
 building, 889
 key methods of, 888
 key properties of, 887
 overview, 886
DataTable type
 inserting into *Datasets*, 898
 obtaining data in *Datasets*, 898–899
 overview, 897
 processing data using
 DataTableReader objects, 899–901
 serializing *DataTable/DataSet* objects as XML, 901–902
 serializing *DataTable/DataSet* objects in binary format, 902–903
isolating strongly typed database code into class libraries
 deleting data with generated codes, 942–943
 inserting data with generated codes, 941–942
 invoking stored procedure using generated codes, 943

- overview, 938
- selecting data with generated codes, 940–941
- viewing generated codes, 939–940
- multitabled DataSet objects and data relationships
 - building table relationships, 924
 - navigating between related tables, 925–927
- overview, 921
- prepping data adapters, 922–923
- updating database tables, 924
- overview, 885
- programming with LINQ to DataSet types
 - DataSet extensions library, 945–946
 - obtaining LINQ-compatible datatables, 946–947
 - overview, 943–944
 - populating new DataTables from LINQ queries, 948–950
 - role of
 - `DataRowExtensions.Field<T>()`
 - Extension method, 948
- Windows Forms database designer tools
 - app.config files, 932
 - completing Windows Forms applications, 937
 - DataGridView control, 927–932
 - strongly typed data adapters, 936–937
 - strongly typed DataRows, 935
 - strongly typed DataSets, 932–934
 - strongly typed DataTables, 934
- disconnection functionality, adding to `AutoLotDAL.dll`
 - configuring data adapters using `SqlCommandBuilder` class, 918–919
 - defining initial class types, 917
 - `GetAllInventory()` method, 919
 - setting version numbers, 919
 - testing disconnected functionality, 920–921
- `UpdateInventory()` method, 919
- discrete key frames, authoring animation in XAML, 1311–1312
- DiscreteStringKeyFrame elements, 1312
- Dispatcher class, 1135
- Dispatcher property, 1135
- DispatcherObject class, 1135
- Display() method, 685
- display name, 598, 599
- Display property, 1458, 1462
- DisplayBaseClass<T> method, 388
- DisplayCarInfo() method, 684
- DisplayCompanyData() method, 623
- DisplayDefiningAssembly() method, 461, 462, 463
- DisplayDelegateInfo() method, 404
- DisplayFancyMessage() method, 133, 134
- displaying dialog boxes, 1542–1543
- DisplayName property, 1093, 1094, 1104
- DisplayStats() method, 203, 208, 237, 239, 240
- DisplayTable() method, 874
- DisplayTypes() method, 596
- disposable objects, 305–309
- Dispose() method, 305, 306, 307, 308, 309, 310, 311, 312, 833, 1550
- Distinct() method, 509, 516
- Distributed Component Object Model (DCOM), 1014–1015, 1019
- distributed computing APIs
 - .NET remoting, 1016
 - COM+/Enterprise Services, 1015
 - Distributed Component Object Model (DCOM), 1014–1015
 - Microsoft Message Queuing (MSMQ), 1015–1016
 - named pipes, sockets, and P2P, 1019
 - overview, 1013
 - XML web services, 1016–1019
- distributed system, 1013
- div opcode, 678
- Divide() method, 394
- *.dll assembly, 44, 1103, 1159, 1500
- *.dll code library, 534

*.dll file extension, 12–13, 14, 532, 559, 663, 1083
 DLL hell, 6, 577
 *.dll module, 14
 *.dll .NET binaries, 12
 [DllImport] attribute, 605
 DLR. *See* dynamic types and Dynamic Language Runtime
 DNS (Domain Name Service), 1380, 1381
 DNS (Domain Name System), 1418
 do keyword, 682
 Dock property, 1326, 1526
 DockPanel class, 1138, 1162, 1326
 DockPanel panels, 1193–1194
 DockPanel types, 1194
 <DockPanel> element, 1194, 1196, 1198, 1264
 DOCTYPE instruction, 1383
 document annotations, 1120
 document controls, WPF, 1183
 document layout managers, WPF, 1228
 Document Object Model (DOM), 993, 995, 1011, 1388, 1389
 Document Outline window, 1181, 1182, 1295
 Document property, 1229, 1230
 document structure, HTML, 1383–1384
 documentation, 585–586, 1441
 Documents API, WPF
 block elements, 1227
 document layout managers, 1228
 inline elements, 1227
 documents, generating from arrays and containers, 1004–1005
 Documents tab, WPF
 annotations, enabling, 1232–1234
 overview, 1228–1229
 populating FlowDocument
 using Blend, 1230–1231
 using code, 1231–1232
 saving and loading FlowDocument, 1234–1235
 sticky notes, enabling, 1232–1234
 Doing more work in Main()! message, 734
 DoIt() method, 619, 620, 622

DOM (Document Object Model), 993, 995, 1011, 1388, 1389
 DOM models vs. XML APIs, 995–996
 domain first programming, 962
 Domain Name Service (DNS), 1380, 1381
 Domain Name System (DNS), 1418
 DomainUnload event
 AppDomain class, 640
 AppDomain type, 647
 DontUseCorLibDumper.dll, 1578
 dot(.) prefix, 655
 dot operator, 152, 290, 302, 339, 519, 703
 dotNetFx40_Client_x86_x64.exe runtime profile, 37
 dotNetFx40_Client_x86.exe setup program, 37
 dotnetfx40_full_setup.exe setup program, 41
 dotNetFx40_Full_x86_x64.exe runtime profile, 37
 dotNetFx40_Full_x86.exe setup program, 37
 DotNetLanguages.net, 11
 double arguments, 131
 double array, 130
 double data type, 87, 96, 130, 135
 double value, 1240, 1261
 DoubleAnimation class, 1304
 DoubleAnimation object, 1304, 1307, 1309
 <DoubleAnimation> element, 1310
 DoubleAnimationUsingKeyFrames class, 1304
 DoubleAnimationUsingPath class, 1304
 DoubleAnimationUsingPath property, 1255
 DoubleClick event, 1528
 doubles array, 130
 DoWhile activity, WF 4.0, 1089
 do/while loop, 117, 119, 872
 download cache, 537, 576
 download page, Mono website, 1565
 Download tab, Mono website, 1565
 DownloadString() method, 768
 DownloadStringAsyn() method, 768
 DownloadStringCompleted event, 768

DragDrop event, 1528
 DragEnter event, 1528
 DragLeave event, 1528
 DragOver event, 1528
 Draw() method, 242, 243, 244, 245, 246, 337, 338, 340, 341, 342
 DrawArc() method, 1548
 DrawBeziers() method, 1548
 DrawCurve() method, 1548
 DrawEllipse() method, 1548
 DrawIcon() method, 1548
 DrawIn3D() method, 332
 DrawInBoundingBox() method, 340
 Drawing class, 1258, 1271
 Drawing object, 1258, 1271
 Drawing type, 1272
 DrawingAttributes object, 1224
 DrawingBrush
 building using geometries, 1272–1273
 painting with, 1273–1274
 DrawingBrush class, 1258
 DrawingBrush object, 1272, 1278
 DrawingBrush type, 1258
 DrawingContext class, 1278, 1279
 DrawingContext object, 1278, 1279
 <DrawingGeometry> element, 1273
 DrawingGroup property, 1255
 DrawingGroup type, 1271
 DrawingImage, containing drawing types in, 1274–1275
 DrawingImage object, 1272
 drawings and geometries, rendering
 graphical data using
 building DrawingBrush using
 geometries, 1272–1273
 containing drawing types in
 DrawingImage, 1274–1275
 painting with DrawingBrush, 1273–1274
 DrawingVisual class, 1135, 1277, 1278–1279, 1282
 DrawingVisual instance, 1279
 DrawingVisual object, 1258, 1272, 1280
 DrawLine() method, 1548, 1550
 DrawLines() method, 1548
 DrawPath() method, 1548
 DrawPie() method, 1548
 DrawRectangles() method, 1548
 DrawString() method, 1548, 1550
 DrawUpsideDown() method, 340
 dreamCar object, 549
 DriveInfo class, 776
 DriveInfo class types, 783–784
 DriveInfoApp project, 784
 DriveNames variable, 1098, 1099
 driverName field, 175
 Drop activity here area, 1081
 dropdown area, 1217
 DropDownItems property, 1516
 Dump menu option, 659
 dumpbin.exe file, 535
 DumpTypeToFile() method, 1572
 duplex messaging, 1030
 Duration object, 1307
 Duration property, 1306, 1307, 1310
 dynamic assemblies
 emitting
 assembly and module set, 693–694
 constructors, 696–697
 HelloClass type and String Member variable, 695–696
 overview, 691–692
 SayHello() method, 697
 ModuleBuilder type, role of, 694–695
 overview, 688
 System.Reflection.Emit namespace, 689–690
 System.Reflection.Emit.ILGenerator, role of, 690–691
 using dynamically generated assembly, 697
 dynamic data, 720
 dynamic keyword, 7, 10, 115, 701, 705, 706, 709, 713, 714, 718
 dynamic loading, 596, 617
 dynamic types and Dynamic Language Runtime (DLR)
 C# dynamic keyword
 calling members on dynamically declared data, 703–704

- limitations of, 706–707
 - overview, 701–702
 - practical uses of, 707
 - role of Microsoft.CSharp.dll
 - assembly, 705
 - scope of, 706
 - COM interoperability
 - simplifying using dynamic data, 714–718
 - using C# 4.0 language features, 718–724
 - without C# 4.0 language features, 722–724
 - role of DLR
 - dynamic runtime lookup of expression trees, 709–710
 - expression trees, 708
 - overview, 707
 - System.Dynamic namespace, 709
 - simplifying late bound calls using
 - dynamic types
 - leveraging dynamic keyword to pass arguments, 711–713
 - overview, 710
 - dynamic typing, 115
 - dynamic variable, 703
 - dynamically adding and removing controls, 1435–1436
 - dynamically created controls, 1436–1437
 - dynamically generated assembly, 697
 - DynamicAsmBuilder application, 691
 - DynamicAsmBuilder project, 698
 - DynamicCtrls, Empty Web Site, 1433
 - DynamicCtrls website, 1437
 - DynamicKeyword application, 701
-
- E**
- E string format character, 84
 - E_FILENOTFOUND constant, 260
 - early binding, attributes using, 614–615
 - Easton, Mark, 1561
 - theEBook class level string variable, 768
 - ECMA (European Computer Manufacturers Association), 1562
 - ECMA International web site, 654
 - ECMA-334 specification, 38, 1562
 - ECMA-335 specification, 38, 1562
 - Edit Columns dialog, 988
 - Edit menu, 1196, 1202
 - edit mode, for code snippets, 63
 - EditingCommands class, WPF, 1202
 - EditMode property, 1222
 - EDM. *See* entity data model
 - EdmGen.exe file, 961
 - *.edmx file, 958
 - generating, 961–965
 - viewing generated data, 968–970
 - <edmx:ConceptualModels> element, 969
 - <edmx:Edmx> element, 968
 - edmxResourcesToEmbed subdirectory, 970
 - <edmx:Runtime> element, 968
 - EF. *See* Entity Framework
 - EightBallClient class, 1046
 - EightBallServiceMEXBehavior element, 1043
 - Element Property tab, 1237
 - ElementName value, 1238
 - elements, XAML, 1160–1161
 - Elements<T> method, 1000
 - Ellipse area, 1352
 - ellipse button, 1097, 1106, 1107, 1230
 - Ellipse class, 1162, 1247, 1256
 - Ellipse element, 1258
 - Ellipse object, 1250, 1252, 1339, 1340
 - Ellipse types, 1254, 1339
 - <Ellipse> element, 1225, 1267
 - <Ellipse> tag, 1132
 - EllipseGeometry class, 1255
 - EllipseGeometry object, 1255
 - ellipses
 - adding to canvas, 1249–1252
 - removing from canvas, 1252–1253
 - Else branch, 1110, 1111
 - else statement, 120
 - Embed Interop Types property, 716, 718, 720, 722

embedding, interop metadata, 716–717
Emit() method, 690, 691, 696
EmitCall() method, 690
 emitting HTML content, 1422
EmitWriteLine() method, 690, 697
 empAge field, 200
 empBenefits object, 232
 empID field, Employee class, 196
 Employee class, 195, 196, 227, 228, 229, 230, 232, 234, 235, 237
 Employee object, 200, 240
 Employee type, 203, 205, 233
 EmployeeApp project, 195, 206, 217, 218, 226
 EmployeeApp.exe assembly, 202
 Employee.cs file, 195, 217, 226
 Employee.Internal.cs file, 217, 226
 Employees project, 241
 empName field, 196, 197
 empSSN variable, 203
 Empty Web Site project, 1473, 1477, 1485, 1489, 1494, 1498, 1504
 Empty Web Site template, Visual Studio, 1406, 1407
 EmpType enumeration, 144, 145, 146, 147, 149
 EmpType variable, 146
 Enable Deleting check box, 1454
 Enable Editing check box, 1454
Enable() method, 1234
EnableAnnotations() method, 1233
 EnableClientScript property, 1458
 Enabled property, 1437, 1527
 EnabledStateGroup, 1366
 EnableTheming attribute, 1401
 EnableTheming property, 1432
 EnableViewState attribute, 1402, 1477, 1478
 EnableViewState property, 1478
 enabling
 autoincrementing fields, 892
 in-place editing, 1454
 metadata exchange, 1043–1045
 sorting and paging, 1453
 Encapsulate Field refactoring, 61

encapsulation
 of classes
 internal representation of properties, 202–203
 overview, 194
 read-only and write-only properties, 204–205
 static properties, 205–206
 using .NET properties, 198–200
 using properties within class
 definition, 200–201
 using traditional accessors and mutators, 195–197
 visibility levels of properties, 204
 as pillar of OOP, 189
End() method, 1035, 1069, 1421
EndClose() method, 1040
EndEdit() method, 893
EndExceptionBlock() method, 690
EndInvoke() method, 399, 400, 732, 733, 734, 738, 774, 1086
EndOpen() method, 1040
<endpoint> element, 1032, 1037, 1039, 1043, 1046, 1050, 1051, 1052, 1054, 1075
 endpoints, 1037, 1051–1052, 1072
EndScope() method, 690
EnforceConstraints property, 888
EngineState enumeration, viewing type
 metadata for, 582–583
 enlist each command object, 882
Enqueue() method, 382, 383
EnterLogData() method, 131, 132
EntiryDataReader, 961
 entities, 953–955
 entity classes, 973
 entity client, 956–957
 Entity Client Data Reader Object, 978–979
 entity data model (EDM), building and analyzing
 enhancing generated source code, 972–973
 generating *.edmx file, 961–965
 reshaping Entity Data, 965–967

- viewing generated *.edmx file data, 968–970
- viewing generated source code, 970–971
- viewing mappings, 967
- Entity Framework (EF)**
 - AutoLotDAL Version 4.0
 - invoking stored procedure, 985–986
 - mapping stored procedure, 980–981
 - navigation properties, 982–984, 984–985
 - overview, 979
 - building and analyzing entity data
 - model (EDM)
 - enhancing generated source code, 972–973
 - generating *.edmx file, 961–965
 - reshaping Entity Data, 965–967
 - viewing generated *.edmx file data, 968–970
 - viewing generated source code, 970–971
 - viewing mappings, 967
 - data binding entities to Windows Forms GUIs, 986–989
 - programming against conceptual model
 - deleting records, 974–975
 - Entity Client Data Reader Object, 978–979
 - overview, 973
 - querying with Entity SQL, 977–978
 - querying with LINQ to Entities, 975–977
 - updating records, 975
 - role of
 - *.edmx file, 958
 - entities, 953–955
 - entity client, 956–957
 - object services, 956
 - ObjectContext and ObjectSet<T> classes, 958–960
 - overview, 951–952
 - Entity model, 929
 - Entity Model Data Wizard, 963
- Entity Set Name field, 967
- Entity Set value, 967
- Entity SQL, querying with, 977–978
- Entity Types folder, 965
- EntityCommand class, 957
- EntityConnection class, 957
- EntityDataReader class, 957, 961
- EntityKey object, 974
- EntityObject class, 956
- EntityState property, 975
- <EntityType> node, 969
- .entrypoint directive, 662
- .entrypoint opcode, 687
- enum attribute, 671
- enum keyword, 21, 654
- enum type
 - declaring variables, 146–147
 - discovering name/value pairs of, 148–150
 - overview, 144
 - System.Enum type, 147
 - underlying storage for, 145–146
- enum value, 675
- enum variable, 147, 148
- EnumBuilder member, 689
- enumData object, 947
- Enumerable class, 513, 514, 515, 516, 517, 520
- Enumerable methods, 503
- enumerable types, building
 - building iterator methods with yield keyword, 346
 - building named iterator, 347–348
 - internal representation of iterator method, 348–349
 - overview, 343–345
- Enumerable.OfType<T>() method, 507
- EnumerableRowCollection class, 947, 948
- Enumerable.Where() method, 519
- EnumerateMachineDataWF project, 1093
- EnumerateMachineInfoWF project, 1103
- enumerating contained controls, 1432–1435
- enumerating files, with DirectoryInfo type, 780–781

enumeration types, Common Type System (CTS), 21
 enumerations, 21, 144, 145, 147, 671
`Enum.Format()` method, 148
`Enum.GetUnderlyingType()` method, 147, 148
`Environment` class, 79, 181
`Environment` type, 80, 81
`Environment.GetCommandLineArgs()` method, 1140
 ephemeral generations, 296, 297
 Equal value, 1461
 equality operator, 164, 449–450, 476–478
`Equals()` method, 91, 97, 102, 251, 253, 449, 450, 476, 477
 Erase mode, 1223
 Erase Mode! value, 1218
 EraseByStoke mode, 1223
 eraseRadio control, 1219
 Error event, 1425–1426, 1481
 error handling activities, WF 4.0, 1092–1093
 Error List window, Visual Studio 2010, 605, 608
 error window, Visual Studio 2010, 246
`ErrorMessage` property, 1458, 1459
 escape characters, 100–101, 1174
 European Computer Manufacturers Association (ECMA), 1562
 event handling, server-side, 1430
 event keyword, 397, 406, 419–421
 event model, WPF, 1139
 event triggers, authoring animation in XAML, 1310–1311
`EventArgs` class, 1424, 1517, 1518
`EventBuilder` member, 689
`EventHandler<T>` delegate, generic, 426
`EventInfo` class, `System.Reflection Namespace`, 587
 events, C#
 creating custom event arguments, 424–425
 event keyword, 419–421
 generic `EventHandler<T>` delegate, 426
 hidden methods of, 421
 incoming, listening to, 422–423
 overview, 418
 registering, simplifying event using Visual Studio 2010, 423–424
 Events tab, 1171, 1181, 1370
`<EventTrigger>` element, 1311
`Except()` method, 515
 Exception base class, 272
 exception block, 690
 Exception class, 267
 Exception code snippet template, 277
 exception event handler, 1481–1482
 exception handling. *See* structured exception handling
 Exception object, 1101
 Exception property, 1097
 exception-derived type, 272
`Exchange()` method, `Interlocked` class, 756
`*.exe` assembly, 686
`*.exe` file extension, 12, 13, 14–15, 532, 664, 1124
`*.exe` module, 14
 Execute button, 771
`Execute()` method, 1109
`ExecuteAssembly()` method, `AppDomain` class, 638
 Executed attribute, 1205
 Executed events, 1203, 1205
 Executed handlers, 1206
`ExecuteFunction()` method, 985
`ExecuteFunction<T>()` method, 959
`ExecuteNonQuery()` method, 859, 861, 862, 863, 871, 882
`ExecuteReader()` method, 834, 853, 858, 859, 861
`ExecuteScalar()` method, 859
`ExecuteStoreCommand()` method, 959
 Existing Item menu option, 1287
 Exists property, `FileSystemInfo` class, 778
`ExistsInCollection<T>` activity, WF 4.0, 1092
 Exit event, 1128, 1129, 1136, 1137, 1147
 Exit handler, 1130
 Exit menu, 1516, 1523, 1538
 Exit option, 1196

ExitCode property, `System.Environment`
 class, 81

ExitEventArgs class, 1137

ExitEventHandler delegate, 1137

ExitTime property, `System.Diagnostics`.
 Process class, 628

exitToolStripMenuItem menu, 1523

Expander control, 1198, 1206

Expander widget, 1195

ExpenseIt WPF sample program, 1124

explicit attribute, 669

explicit cast operation, 107, 249, 1107

explicit conversions

- for square types, 458
- when required, 454

explicit interface implementation, 336,
 337, 339, 342

explicit keyword, 455, 456

explicit load, 554

explicitly implemented interface, 338

explicitly pop, 679

Exploded event, 420, 421, 428

exponential format, 84

exponential notation, 84

Export All button, 1276

Export button, 720

Export dialog box, 1276

Export menu option, 1276

exporting, design document to XAML,
 1275–1276

ExportToExcel() method, 720, 722

exposing single services using multiple
 bindings, 1052–1053

Expression area, 1107

Expression Blend

- building user interface with
 key aspects of, 1207–1213
- TabControl control, 1213–1215
- establishing data bindings using, 1236–
 1238
- extracting resources in, 1301–1303
- generating WPF styles with, 1320–1324
- populating FlowDocument, 1230–1231
- UserControls, building custom
 animation, defining, 1359–1362

initial C# code, 1359

overview, 1356

programmatically starting
 storyboard, 1363–1364

renaming initial, 1357–1358

SpinControl, 1358

working with shapes using
 brush and transformation editors,
 1269–1271

combining shapes, 1268

converting shapes to paths, 1267–
 1268

overview, 1266

selecting shape to render from tool
 palette, 1266–1267

Expression property, `DataTable` class,
 890

expression trees, 708–710

extendable applications

- C# Snap-In, 619–620
- CommonSnappableTypes.dll, 619
- extendable Windows Forms
 application, 621–624

overview, 618

Visual Basic Snap-In, 620

extendable Windows Forms application,
 621–624

ExtendedProperties collection, 898

ExtendedProperties property, 887

extending interface types, 469–470

extends attribute, 655, 660, 669, 670

extends clause, 670

Extends token, 583

Extensible Application Markup Language
 (XAML), 993

Extensible Hypertext Markup Language
 (XHTML), 1383, 1392

Extensible Markup Language (XML), 995,
 996, 997, 998, 999, 1000, 1001,
 1002, 1003, 1004

Extensible Markup Language (XML)
 schema editor, 902

Extensible Markup Language Path
 Language (XPath), 993

- Extensible Markup Language Query (XQuery), 993
- Extensible Markup Language Schema Definition (XSD) editor, 902
- Extensible Stylesheet Language Family Transformations (XSLT), 993
- extension libraries, 467–468
- extension methods
 - extending interface types with, 469–470
 - extension libraries, 467–468
 - importing types that define, 465–466
 - IntelliSense mechanism, 466–467
 - invoking on instance level, 463
 - invoking statically, 464
 - overview, 460–462
 - scope of, 464–465
- Extension property, `FileSystemInfo` class, 778
- ExtensionMethods project, 461, 467
- Extensions class, 1000
- extern attribute, 662
- external assemblies
 - loading, 596
 - referencing, 32
- External AssemblyReflector application, 597
- external attribute, 666
- external code libraries, 1083
- external XAML files, 1082
- ExternalAssemblyReflector application, 596
- Extract Interface refactoring, 61
- Extract Method option, 61
- Extract Method refactoring, 61
- Extract value to Resource option, 1293
- extracting resources
 - changing after, 1295
 - in Expression Blend, 1301–1303

- F**
- F string format character, 84
- F suffix, 87
- F# language, 10
- Factory property, `Task` class, 766
- false branch, 1097
- false operator, 445
- false value, 330
- FCLs (Framework class libraries), 3
- feed project template, RSS, 1024
- Field #n token, 583
- field access, with pointers, 484
- field data
 - defining in CIL, 674–675
 - static, 182–185
- .field directive, 674
- Field<T>() method, 948
- FieldBuilder member, 689
- FieldBuilder type, 696
- FieldCount property, 860
- FieldInfo array, 591
- FieldInfo class, `System.Reflection Namespace`, 587
- FieldModifier keyword, 1156, 1159
- fields, custom metadata viewer, 591
- FIFO (first-in, first-out), 362, 377
- Figure class, 1230
- Figure element, 1227
- Figure type, 1227
- File | Open menu option, 33, 35
- File class, 776, 777
- file extensions, 532
- File menu, 1205, 1516, 1523, 1552
- File Open dialog box, 622
- .file token, 551
- File Transfer Protocol (FTP), 1381, 1407
- file types, 789–791
- file-centric methods, 790–791
- FileExit_Click() method, 1197
- FileInfo class
 - `AppendText()` method, 789
 - `Create()` method, 786
 - `CreateText()` method, 789
 - function of, 776, 777
 - `Open()` method, 786–788
 - `OpenRead()` method, 788
 - `OpenText()` method, 789
 - `OpenWrite()` method, 788
 - overview, 785

File(*Info*) types, 777–778
 FileMode enumeration, 787
FileName property, 1559
FileNotFoundException class, 260, 281
FileNotFoundException error, 1578
FileNotFoundException exception, 554, 555, 569
FileNotFoundException object, 281
File.Open() method, 281, 1175
FilePath property, 1418
files
 enumerating with **DirectoryInfo** type, 780–781
 watching programmatically, 801–804
FileStream class, 776
FileStream object, 788
FileStreamApp project, 793, 794
FileStreams class, 793–794
FileSystemInfo abstract base class, 777–778
FileSystemWatcher class, 776, 801, 802
Fill color, 1368
Fill(*)* method, 835, 914, 915, 916, 919, 937
Fill property, 1249, 1250, 1258, 1260, 1273, 1294, 1352, 1353, 1365, 1368
FillBehavior property, **Timeline** class, 1306
FillContains() method, 1254
FillDataSet() method, 891, 898
FillDataSetUsingSqlDataAdapter
 application, 914
FillDataSetUsingSqlDataAdapter project, 917
FillEllipse() method, 1549, 1550
FillPath() method, 1549
FillPie() method, 1549
FillPolygon() method, 1549
FillRectangle() method, 1549
FillTheseValues() method, 128
filter criteria, selecting rows based on, 908–911
Filter property, 1559
filtering data, using **OfType<T>()**, 508
finalizable objects, 302–305
FinalizableDisposableClass project, 310, 312
finalization queue, 305
finalization reachable table, 305
Finalize() method, 252, 298, 302, 303, 305, 306, 310
finally blocks, 282, 304, 690
finally clause, 756
finally keyword, 261
FindAll() method, 430, 431, 432, 491
FindByCarID() method, 934
FindLongestWord() method, 769
FindLongestWord() method, 770
FindMembers() method, **System.Type** class, 588
Find/Replace dialog box, 1542
FindTenMostCommon() method, 769, 770
Finish button, 930, 1456
FinishButtonClick event, 1456
First<*T*>(*)* method, 500
FirstChanceException event, **AppDomain** class, 640
first-in, first-out (FIFO), 362, 377
FirstName property, 379, 702
firstName variable, 99
FirstOrDefault(*)* method, 976
FirstWorkflowExampleApp project, 1079, 1088
fixed keywords, pinning types with, 485–486
fixed pointer-centric keyword, 479
<FixedDocument> element, 1228
fixeddocuments (WYSIWYG), 1120
fixed-point formatting, 84
flags, 44, 535
Flip value, 129
Flip Y Access option, 1360
float data type, 87, 154
float variable, 87
Floater class, 1230
Floater element, 1227
Floater type, 1227
Flop value, 129
flow chart workflow, 1089
Flow Control area, 1107
flow documents, 1120
flowchart activities, WF 4.0, 1089–1090

Flowchart activity, 1090, 1093, 1094, 1107
 Flowchart section, Toolbox, 1093
 flowchart workflows
 connecting activities in, 1094
 defining workflow wide variables, 1095–
 1096
 FlowDecision activity, 1096–1097, 1098
 ForEachT activity, 1099–1100
 InvokeMethod activity, 1094–1095
 overview, 1093
 TerminateWorkflow activity, 1097
 FlowDecision activity, 1090, 1094, 1096–
 1097, 1098
 FlowDocument
 loading, 1234–1235
 populating, 1230–1232
 saving, 1234–1235
 FlowDocument container, 1231
 FlowDocument data, 1235
 FlowDocument object, 1228, 1234
 FlowDocumentPageViewer manager, 1228
 FlowDocumentReader control, 1229
 FlowDocumentReader manager, 1228
 FlowDocumentReader object, 1231, 1233
 FlowDocumentScrollView manager,
 1228, 1231
 FlowSwitch<T> activity, 1090, 1097
 Flush() method
 BinaryWriter class, 800
 Stream class, 792
 TextWriter class, 795
 Focusable property, UIElement type, 1134
 Focused property, 1527
 FocusedStateGroup, 1366
 Font property, 1438, 1526
 Font type, 1547
 FontFamily property, Control Type, 1133
 FontFamily type, 1547
 FontSize attribute, 1326
 FontSize property, Control Type, 1133
 FontStretch property, Control Type, 1133
 FontWeight property, Control Type, 1133
 Foo() method, 704, 705
 for keyword, 117, 122, 682
 for loop, 77, 78, 117, 682
 for statement, 117
 ForAll() method, 771
 forcing garbage collection, 299–302
 ForEachT activity, 1099–1100
 foreach code, 63
 foreach construct, 63, 343, 345, 346, 497,
 500
 foreach enumeration, 346, 1100
 foreach iteration, 906
 foreach keyword, 78, 118, 344, 346, 349,
 682, 771, 1099
 foreach logic, 502
 foreach loop, 118, 245, 346, 590, 594, 985
 foreach scope, 623
 foreach style, 362
 foreach syntax, 346
 ForEach<T> activity, WF 4.0, 1089
 ForEach<T> mini designer, 1100
 foreach/in loop, 117
 foreach-like iteration, 368
 foreach-style iteration, 376
 ForeColor property, 1438, 1458, 1526
 Foreground color, 1351
 Foreground property, Control Type, 1133
 foreground threads, 749–750
 ForegroundColor property,
 System.Console class, 81
 Fork class, 334
 Form class, 766, 1473, 1514, 1515, 1529–
 1530, 1538
 Form collection, 1476
 form data, accessing, 1419–1420
 form elements, 1396
 form inheritance, 1543–1545
 Form property, 1418, 1419, 1420
 form statement, 1417
 Form string, 1532
 Form type
 Control class, 1526–1529
 Form class, 1529–1530
 life cycle, 1531–1533
 overview, 1525
 <form> element, 1384, 1385, 1387, 1390,
 1397, 1403, 1442, 1448, 1449, 1478
 Form1.cs file, 763, 920, 1552

Form1.cs icon, 1520
 Format drop-down list, 1276
 Format() method, String system type, 97
 FormatException class, 260
 FormatNumericalData() method, 84
 FormattedResponse argument, 1105, 1107
 FormattedResponse variable, 1108, 1111
 FormattedText object, 1279
 formatters, for serialization
 IFormatter and IRemotingFormatter
 interfaces, 809–810
 overview, 808
 type fidelity among formatters, 810–811
 formatting, 84
 FormBorderStyle enumeration, 1529
 FormBorderStyle property, 1529, 1538
 FormBorderStyle.FixedDialog property, 1538
 FormClosed event, 989, 1531, 1532
 FormClosing event, 1531, 1532
 FormClosingEventArgs event, 1532
 FormClosingEventArgs.Cancel property, 1531
 FormClosingEventHandler delegate, 1531
 Form.cs file, 1549
 form's client area, invalidating, 1551
 form's default input button, setting, 1541
 Forms designer, 1522, 1523
 forms, HTML, 1384
 Forms-based authentication model, 1507
 FormStartPosition enumeration, 1530
 FormWindowState enumeration, 1530
 Fortran syntax, 12
 Frame class, 1124, 1155
 Framework class libraries (FCLs), 3
 FrameworkElement class, 1117, 1248,
 1271, 1278, 1280, 1281, 1282, 1292,
 1327, 1329
 FrameworkElement type, 1133, 1134, 1272
 FrameworkPropertyMetadata constructor, 1329
 FrameworkPropertyMetadata object, 1329,
 1335
 FrameworkPropertyMetadataOptions enum, 1329

freachable table, 305
 friend assemblies, 545
 friendly names, mapping database names to, 916
 FriendlyName property, 639
 from operator, 497, 510, 517, 518
 From property, 1305, 1307, 1310
 FromHdc() method, 1548
 FromHwnd() method, 1548
 FromImage() method, 1548
 FTP (File Transfer Protocol), 1381, 1407
 Full Installation option, Mono website, 1566
 FullName property, FileInfo class, 778
 fully qualified name, 31, 252, 532
 Func<> delegates, 492, 517, 518, 519, 520
 Func<> type, 521
 Func<T> delegate, 763
 Function Imports folder, 980
 function pointer, C-style, 21
 FunWithArrays application, 144
 FunWithArrays project, 137
 FunWithEnums project, 144, 150
 FunWithGenericCollections project, 385
 FunWithLinqExpressions application, 509
 FunWithLinqExpressions project, 517
 FunWithMethods application, 134
 FunWithMethods project, 126
 FunWithPageMembers website, 1419
 FunWithProfiles project, 1504
 FunWithStrings project, 98, 106
 FunWithStructures project, 151, 154
 FunWithThemes web site, 1471
 FunWithThemes website, 1466

G

G string format character, 84
 GAC (Global Assembly Cache), 32, 51, 533,
 559, 560, 561, 565–566, 1022, 1414
 gacutil utility, Mono, 1570, 1575
 gacutil.exe utility, 565, 566, 576, 1570, 1575
 GainFocusStar, 1366

Garage class, 209, 343, 346, 347
 Garage object, 210
 garbage collection
 background (.NET 4.0), 297
 concurrent (.NET 1.0 - 3.5), 297
 forcing, 299–302
 GC.Collect() method, 298, 299, 300, 301, 302
 GCHandleMode enumeration, 298, 300
 *.g.cs file, 1150, 1165
 GC.SuppressFinalize() method, 310
 GC.WaitForPendingFinalizers() method, 300
 GDI+, rendering graphical data using, 1545–1551
 Graphics type, 1548–1549
 invalidating form's client area, 1551
 obtaining Graphics object with Paint event, 1549–1550
 overview, 1545–1546
 System.Drawing namespace, 1547
 general catch statements, 279–280
 general exceptions, throwing, 265–266
 Generate Asynchronous Operators check box, 1068
 Generate option, 963
 generation 0 objects, 296
 generation 1 objects, 296, 297
 generation 2 objects, 296, 297
 generational value, 297
 generic List<T>, hydrating DataTables from, 904–906
 generic members, 22
 generic types, 22, 594
 GenericDelegate application, 415
 GenericDelegate project, 418
 GenericPoint project, 388, 391
 generics
 constraining type parameters
 examples using where keyword, 393–394
 lack of operator constraints, 394–395
 overview, 392
 creating custom generic methods, 385–388

creating custom generic structures and classes, 388–392
 defining in CIL, 671–672
 generic type parameters, 371–375
 non-generic collections, issues with
 overview, 361–362
 performance, 363–367
 type safety, 367–371
 System.Collections.Generic namespace
 collection initialization syntax, 378
 List<T> class, 379–380
 overview, 376–377
 Queue<T> class, 382–383
 SortedSet<T> class, 383–385
 Stack<T> class, 380–381
 geometries. *See* drawings and geometries
 Geometry class, 1254, 1255, 1257
 Geometry objects, 1246, 1248, 1254, 1255
 Geometry property, 1255
 Geometry type, 1257
 GeometryDrawing class, 1246
 GeometryDrawing object, 1258
 GeometryDrawing property, 1255
 GeometryDrawing type, 1271
 <GeometryDrawing> element, 1275
 GeometryGroup class, 1255
 GeometryGroup object, 1255
 <GeometryGroup> element, 1272
 GeometryTransform property, Shape class, 1248
 get () methods, 592
 get block, 204
 Get button, 1474
 get directive, 676
 get keyword, 204
 get method, 195, 196, 198, 202
 GET method, 1384, 1391, 1417, 1418, 1420
 get scope, 198, 199
 get_prefix, 202, 676
 get_PetName() method, 584
 get_SocialSecurityNumber() method, 203
 get_XXX() method, 202
 GetAllInventory() method, 919, 921, 1107
 GetAllInventoryAsDataTable() method, 874

GetAllInventoryAsList() method, 874
GetAllTracks() method, 314, 315
GetArea() method, 1254
GetAssemblies() method, 638, 641
GetBenefitCost() method, 232
GetBoolFromDatabase() method, 163
GetChanges() method, 888
GetChildren() method, 1342
GetCoffee() method, 382, 383
GetColumnError() method, 893
GetColumnsInError() method, 893
GetCommandLineArgs() method, 78, 79
GetConstructors method (), System.Type class, 588
GetCurrentPay() method, 197
GetCurrentProcess() method, System.Diagnostics.Process class, 629
GetCurrentThreadId() method, AppDomain class, 639
GetDirectories() method, DirectoryInfo class, 778
GetDomain() method, System.Threading.Thread Class, 741
GetDomainID() method, System.Threading.Thread Class, 741
GetDrives() method, DriveInfo class, 783
GetEnumerator() method, 343, 344, 345, 346, 348, 349
<GetEnumerator>d_0 type, 348
GetEvents() method, System.Type class, 588
GetFactory() method, DbProviderFactories class, 848, 849
GetFields() method, System.Type class, 588
GetFiles() method, DirectoryInfo class, 779, 780
GetGeneration() method, System.GC class, 298
GetHashCode() method, 91, 251, 252, 255, 476

GetID() method, 197
GetILGenerator() method, 696
GetInterfaces() method, 588, 591
GetIntFromDatabase() method, 163, 164
GetInventory() method, 1072
GetInvocationList() method, 402
GetLogicalDrives() method, 782, 1098
GetMembers() method, System.Type class, 588
GetMethods() method, System.Type class, 588
GetMsg() method, 691
GetName() method, 197
GetNestedTypes() method, System.Type class, 588
GetNumberOfPoints() method, 324
GetObjectByKey() method, 959, 974, 975
GetObjectData() method, 820, 822
GetParameters() method, 594
GetPerson() method, 368
GetPetName() method, 67, 843
GetPetName procedure, 869, 943
GetPosition() method, 1143
GetProcesses() method, System.Diagnostics.Process class, 629
GetProperties() method, System.Type class, 588
GetRandomNumber() method, 181, 182
GetRenderBounds() method, 1254
GetSchema() method, 855
GetStringArray() method, 142
GetStringSubset() method, 505
getter method, 194
Getter/Setter tokens, 584
GetTheCars() method, 348
<GetTheCars>d_6 type, 348
GetTotalMemory() method, System.GC class, 298
GetType() method, 140, 147, 252, 324, 588
 GetUserAddress() method, 1507
GetUserData() method, 82
GetValue() method, 578, 1109, 1135, 1328, 1330
GetValues() method, 148

GetVisualChild() method, 1281
GiveBonus() method, 235, 236, 237, 239, 240
GivePromotion() method, 249, 250
 Glade 3 tool, Mono, 1571, 1572
 Global Application Class icon, 1479
 global application object, 1140
 Global Assembly Cache, 848
 Global Assembly Cache (GAC), 32, 51, 533, 559, 560, 561, 565–566, 1022, 1414
 global last-chance exception event handler, 1481–1482
 Global.asax file
 global last-chance exception event handler, 1481–1482
 HttpApplication base class, 1482
 overview, 1479–1480
 Global.asax script, 1482
 Global.asax.cs, 1485
 <globalization> element, 1427
 globally unique identifier (GUID), 351, 560, 889, 899
 GlyphRunDrawing type, 1271
 -godmode option, 79
 goto keyword, 117, 122
 GoToState() method, 1367
 GoToStateAction, 1367
 gradient brush, 1259, 1292
 gradient offset, 1259
 gradient stop, 1259
 gradient strip, 1259
 Gradient Tool icon, 1269
 GradientStop objects, 1261
 graphical content, 1188
 graphical data, rendering using GDI+
 Graphics type, 1548–1549
 invalidating form's client area, 1551
 obtaining Graphics object with Paint event, 1549–1550
 overview, 1545–1546
 System.Drawing namespace, 1547
 graphical layer, 1277
 graphical output, capturing and rendering, 1557
 graphical systems, immediate-mode, 1245
 graphical transformation objects, 1264
 Graphical User Interface (GUI), 38, 81, 903, 904, 1006, 1007, 1059, 1060, 1061, 1389
 Graphical User Interface Toolkit (GTK#), 1565, 1566
 graphics
 retained-mode, 1245
 vector, 1120
 Graphics class, 1549
 Graphics object, obtaining with Paint event, 1549–1550
 Graphics type, 1548–1549
 GreaterThan value, 1461
 *.resources file, 1151
 Grid class, 1138, 1160, 1162
 Grid control, 1349
 Grid panels, 1186, 1191–1193
 <Grid> control, 1228
 <Grid> layout manager, 1211
 <Grid> type, 1173, 1174, 1191, 1196, 1198, 1216
 Grid.Column property, 1192
 <Grid.ColumnDefinitions> element, 1191
 gridInventory, 1242
 Grid.Row property, 1192
 Grid.RowDefinitions element, 1191
 GridSplitter types, 1192–1193
 <GridSplitter> control, 1192, 1193
 GridView class, 1396, 1397, 1398, 1399, 1403, 1408, 1479, 1492, 1493
 GridView control, 1441, 1450, 1451, 1453, 1454
 GridView widget, 1451
 GridWithSplitter.xaml file, 1193
 group box, 1220
 group name, 1220
 group operator, 509
 <group> elements, 1508
 GroupBox class, 907, 925
 grouping
 conceptual, 1078
 profile data, 1507–1509
 GroupName property, 1220
 groups, defining, 1463–1465

GrowLabelFont.xaml file, 1309
 Grunt value, 147
 GTK# (Graphical User Interface Toolkit),
 1565, 1566
 GUI (cache application Graphical User
 Interface), 1492
 GUI (Graphical User Interface), 38, 81, 903,
 904, 1006, 1007, 1059, 1060, 1061,
 1389
 GUI (session application Graphical User
 Interface), 1495
 GUI animation tools, 1304
 GUI editor, 543
 GUI framework, 618
 GUID (globally unique identifier), 351, 560,
 889, 899
 GZIP standard, 1394

H

H command, 1257
 <h1> tag, 1386
 Halo8.exe application, WPF, 43
 Handle property, System. Diagnostics.
 Process class, 628
 Handled property, 1339, 1341, 1537
 [HandledProcessCorruptedStateException
 s] attribute, 286
 hard-code, 1236
 has-a relationship, 5, 190, 213, 219, 232,
 806
 HasChanges() method, 888
 HasControls() method, 1432
 HasErrors property, 888, 893
 hash code, 255, 256, 560, 561
 HashSet<T> class, 377
 Hashtable class, 362, 1479
 Hashtable types, 251, 255
 HasValue property, 163, 164
 HatchBrush object, 1550
 header information, Windows, 534
 Header property, 1214
 Header values, 1196
 Headers property, 1418

HeaderText property, 1462
 heap allocation, 291, 366
 Height attribute, 1146
 Height property, 1133, 1145, 1152, 1187,
 1193, 1304, 1305, 1326, 1327, 1438
 Height value, 1188, 1189, 1193
 HeightProperty field, 1329
 Helicopter class, 550
 helicopter.cs file, 550, 551
 Hello World application, 27
 -HelloClass constructor, 696
 HelloClass type, emitting, 695–696
 HelloMsg.cs file, 46
 HelloProgram.cs file, 658
 HelloProgram.exe file, 659
 HelloProgram.il file, 664
 HelloWebService.asmx file, 1017
 HelloWorld class, 691, 695, 697
 HelloWorld() method, 1018
 helloWorldClass variable, 697
 HelloWorldWebService project, 1019
 Help cursor, 1314
 Help Library Manager, 68
 Help menu, SharpDevelop, 53
 Help page, 68
 Helper class, rigging up UI to, 1009–1011
 HelpExecuted() method, 1204
 HelpLink property, 262, 268, 269–270
 [helpstring] attribute, 658
 hexadecimal formatting, 84
 Hexagon class, 189, 191, 324, 525
 Hexagon object, 333
 Hexagon type, 243, 328, 329
 hidden this reference, 682
 Hide() method, 1529
 hit test operations, responding to, 1282–
 1284
 HitTest() method, 1283
 HitTestResult object, 1252
 HitTestResultCallback delegate, 1283
 Home node, 1446
 Horizontal split button, 1170
 Horizontal value, 1190
 HorizontalAlignment property,
 FrameworkElement type, 1133

HorizontalContentAlignment property, Control Type, 1133
HorseAndBuggy class, 607
HorseAndBuggy type, 607
<host> element, 1039, 1043
hosting
 services within Windows services
 creating Windows service installer, 1064–1065
 enabling MEX, 1064
 installing Windows service, 1066–1067
 overview, 1061
 specifying ABCs in code, 1062–1063
Windows Communication Foundation (WCF) services
 <system.serviceModel> element, 1042
 coding against ServiceHost type, 1038
 enabling metadata exchange, 1043–1045
 establishing ABCs within App.config files, 1037
 overview, 1036
 ServiceHost type, 1040–1041
 specifying base addresses, 1038–1040
 href property, 577
 HRESULTs, 260
HTML. *See* HyperText Markup Language
HTML attributes, 1441
HTML controls, 1441
HTML tab, Visual Studio, 1384
HTML widget, 1440
<html> tag, 1383
HtmlButton tag, 1440
HtmlInputControl tag, 1440
HtmlTable tag, 1440
HTTP. *See* Hypertext Transfer Protocol
HTTP GET method, 1043
HttpApplication class, 1481, 1482, 1488
HttpApplication type, 1473, 1483
HttpApplicationState class, 1484

HttpApplicationState object, 1484, 1485, 1488
HttpApplicationState type, 1482, 1483, 1484, 1486, 1487, 1488, 1489
HTTP-based bindings, 1029–1030
HttpBrowserCapabilities class, 1419
HttpBrowserCapabilities object, 1419
HttpCookie class, 1498
HttpCookie collection, 1421
HttpCookie type, 1497, 1498
HttpCookie.Expires property, 1498
HttpMethod property, 1418
HttpRequest class, 1417, 1418, 1419, 1420
HttpRequest object, 1482
HttpRequest.Browser property, 1389
HttpRequest.Cookies property, 1498, 1499
HttpRequest.Form form, 1436
HttpRequest.Form property, 1419
HttpRequest.QueryString property, 1419
HttpResponse class, 1419, 1421, 1422
HttpResponse object, 1482
HttpResponse.Redirect() method, 1422
HttpResponse.Write() method, 1422
HttpResponse.WriteLine() method, 1422
HttpServerUtility object, 1417, 1482
HttpServerUtility.ClearError() method, 1426
HttpServerUtility.GetLastError() method, 1426
HttpServerUtility.Transfer() method, 1422
HttpSessionState class, 1483, 1496–1497
HttpSessionState object, 1482, 1483, 1493, 1496, 1502
HttpSessionState type, 1483, 1494
HyperLink widget, 1433
HyperText Markup Language (HTML)
 building forms, 1386–1387
 document structure, 1383–1384
 forms, 1384, 1477
 overview, 1382
 representation, 1477
 requests, 1482
 response, 1477, 1482
 Visual Studio 2010 designer tools, 1384–1386

widgets, 1476

Hypertext Transfer Protocol (HTTP)

- overview, 1379
- request/response cycle, 1380
- requests, incoming, 1417–1420
- response, outgoing, 1421–1423
- stateless protocols, 1380

I

I command, 872

-i command, 566

i parameter, 433

i variable, 682, 683

<i> tag, 1386

IAdvancedDraw interface, 340

IAppFunctionality interface, 619, 620, 622

IAsyncResult compatible object, 733

IAsyncResult interface, 399, 734, 735, 774

IAsyncResult parameter, 732, 736, 738, 739

IAsyncResult-compatible object, 732

IAsyncResult-compatible parameter type, 732

IAutoLotService.cs file, 1072

IBasicMath class, 1054

IBasicMath interface, 469

IBasicMath.cs file, 1057

IClassFactory interface, 7

ICloneable class, 323

ICloneable interface, 158, 323, 349–354, 362

ICloneableExample application, 323

ICloneableExample project, 324

ICollection interface, 362, 377, 378

ICollection<T> interface, 376, 377, 378

ICommand interface, 1201, 1205

IComparable interface

- building, 354–359
- overloading comparison operators, 450

IComparable<T> interface, 354

IComparer interface, 143, 357–358

IComparer<T> interface, 358, 376, 383

IComponent interface, 1525

IComponentConnector interface, 1151

Icon type, 1547

IContextProperty interface, 651

ICreateErrorInfo interface, 261

ICustomFormatter interface, 85

ID attribute, 1397

Id member, ProcessThread type, 633

ID property, 198, 200, 628, 1429, 1432

IDataAdapter interface, 828, 835

IDataAdapter type, System.Data namespace, 832

IDataParameter interface, 828, 834–835

IDataParameter type, System.Data namespace, 832

IDataReader interface, 827, 836

IDataReader type, System.Data namespace, 832

IDataReader.IsDBNull() method, 837

IDataRecord interface, 827, 836

IDbCommand interface, 827, 834

IDbCommand type, System.Data namespace, 832

IDbConnection interface, 321, 327, 827, 833

IDbConnection parameter, 837

IDbDataAdapter interface, 828

IDbDataAdapter type, System.Data namespace, 833

IDbDataAdapterinterface, 835

IDbDataParameter interface, 828, 834–835

IDbTransaction interface, 828, 834, 878, 879

IDbTransaction type, System.Data namespace, 833

IDE (integrated development environment), 932, 996, 1024, 1025, 1379, 1381, 1382, 1386, 1396, 1410

IdealProcessor member, ProcessThread type, 633

IDictionary interface, 262, 270, 362

IDictionary<string, object> interface, 1113

IDictionary< TKey, TValue > interface, 376

IDispatch interface, 7, 709

IDisposable class, 863, 1550

IDisposable interface, 289, 305, 306, 307, 308, 309
 IDraw3D interface, 331, 332, 333
 IDrawable interface, 339, 341, 393
 IDropTarget interface, 322
 IDynamicObject interface, 709
 IEightBall interface, 1033, 1046
 IEnumerable interface, building
 building iterator methods with `yield`
 keyword, 346
 building named iterator, 347–348
 internal representation of iterator
 method, 348–349
 overview, 343–345
 IEnumerable type, 504
 IEnumerable<int> interface, 499
 IEnumerable<string>, 498, 505
 IEnumerable<T> class, 497, 504, 505, 506,
 507, 945, 948
 IEnumerable<T> enumeration, 961
 IEnumerable<T> interface, 376, 377, 500,
 763, 765, 1000
 IEnumerable<T> object, 507
 IEnumerable<T> variable, 499
 IEnumerator interface, building
 building iterator methods with `yield`
 keyword, 346
 building named iterator, 347–348
 internal representation of iterator
 method, 348–349
 overview, 343–345
 IEnumerator<T> interface, 376
 IErrorInfo interface, 261
 If activity, 1089, 1107–1108, 1110
 if keyword, 122
 if scope, 250
 if statement, 120, 1317
 if/else branches, 1104
 if/else statement, 119, 120
 if/else/then statement, 1107
 IFormatter interface, 809–810
 IIS (Internet Information Services), 1025,
 1026, 1036, 1037, 1040, 1071, 1074,
 1379, 1381, 1382
 IIS virtual directories, 1381

IL (Intermediate Language), 12, 13
 *.il file, modifying, 662–663
 ilasm compiler, Mono, 1569
 ilasm utility, Mono, 1571
 ilasm.exe compiler, 666
 ildasm.exe file
 compiling CIL code using, 663–664
 exploring assemblies using
 overview, 33
 viewing assembly metadata, 35
 viewing Common Intermediate
 Language (CIL) code, 34
 viewing type metadata, 34
 ILGenerator class, 691, 696, 697
 ILGenerator member, 689
 ILGenerator objects, 690
 ILGenerator type, 690, 696
 IList interface, 362
 IList<T> interface, 376
 Image control, 1274, 1275, 1278, 1279,
 1286, 1289, 1358, 1359
 Image property, 1544
 Image type, 1547
 ImageAnimator type, 1547
 ImageBrush type, 1258
 ImageDrawing class, 1246
 ImageDrawing object, 1258
 ImageDrawing type, 1271
 ImageOrderAutoDialog class, 1545
 ImageOrderAutoDialog.cs file, 1543
 images
 2D vector, 1271
 programmatically loading, 1288–1289
 ImageSource object, 1258
 ImageSource property, 1258
 ImageUrl image, 1448
 IMetadataExchange class, 1055
 imgDisplay control, 1358
 imgFirst object, 1371
 imgSecond object, 1371
 imgThird object, 1371
 immediate-mode graphical systems, 1245
 immutability, 103
 implemented interfaces, custom metadata
 viewer, 591

implements attribute, 655, 669, 670
 implements clause, 670
 Implements keyword, 620
 implicit cast, 248
 implicit conversion
 routines, 458–459
 when required, 454
 implicit keyword, 455, 456, 459
 implicit load, 554
 implicit typing, 113, 701, 702
 implicitly pop, 680
 implicitly sealed, 223
 implicitly typed local arrays, 139
 implicitly typed local variables
 are strongly typed data, 115
 overview, 112–113
 restrictions on, 114–115
 usefulness of, 116
 ImplicitlyTypedLocalVars project, 112, 117
 <%@Import%> directives, 1398, 1402, 1403
 <Import> elements, 1149
 importing
 Inventory.xml files, 1007–1008
 types that define, 465–466
 Imports area, 1105
 Imports button, 1105
 Imports editor, 1105
 Imports keyword, 548
 Imports statement, 548
 in operator, 497, 509, 510, 517, 518
 In32Animation class, 1304
 InArgument<> properties, 1109
 InArgument<T> class, 1109
 InArgument<T> object., 1109
 inaryFormatter class, 529
 Include attribute, 1149
 incoming cookie data, reading, 1499
 incoming HTTP requests
 access to incoming form data, 1419–1420
 IsPostBack property, 1420
 obtaining brower statistics, 1419
 overview, 1417–1418
 incoming parameter, 146
 Increment() method, 756, 757
 index operator ([]), accessing items from arrays, 439
 indexer methods
 definitions on interface types, 444
 function of, 439
 multiple dimensions, 443–444
 overloading, 443
 overview, 439–440
 string values, 441–442
 IndexOutOfRangeException class, 260
 IndexOutOfRangeException type, 262
 infrastructure, adding to MainWindow type, 1555
 inheritance. *See also* polymorphism
 base class/derived class casting rules
 is keyword, 250
 as keyword, 249
 overview, 247–248
 basic mechanics of
 multiple base classes, 222
 overview, 219
 sealed keyword, 222–223
 specifying parent class of existing class, 220–221
 cross-language, 549
 details of
 adding sealed class, 231–232
 controlling base class creation with base keyword, 228–230
 overview, 226–227
 protected keyword, 230
 multiple, with interface types, 341–342
 overview, 219
 pillar of OOP, 189–191
 programming for
 containment/delegation, 232–235
 revising Visual Studio class diagrams, 224–225
 System.Object class
 overriding system.Object.Equals(), 254–255
 overriding
 System.Object.GetHashCode(), 255–256

overriding `System.Object.ToString()`, 254
 overview, 250–253
 testing modified person class, 257–258
 testing your modified person class, 256
 inheritance chain, 615, 1416
 Inheritance icon, Class Designer Toolbox, 66
 Inheritance Picker dialog box, 1544
 Inherited Form icon, 1543
 Inherited property, 612
 Inherits attribute, 1402, 1409
 Inherits keyword, 549
 init attribute, 681
 Init event, 1423, 1476
`InitClass()` method, 934
`InitDAD()` method, Program class, 643
 Initial Catalog name, 854
 initial class types, 917
`InitializeComponent()` method, 1151, 1153, 1165, 1203, 1520, 1521, 1523, 1524
`InitializeCorrelation` activity, WF 4.0, 1090
 initialValue property, 1459
 Ink API controls, 1183
 Ink API support types, 1183
 Ink API tab, WPF
 ComboBox control, 1224–1226
 InkCanvas control, 1222–1227
 overview, 1216
 RadioButton control, 1220–1222
 ToolBar, 1217–1219
 ink controls, WPF, 1182–1183
 Ink mode, 1223
 Ink Mode! value, 1218
 InkCanvas control, WPF, 1222–1227
 InkCanvasEditingMode enumeration, 1223
 inkRadio control, 1219
 inkToolbar control, 1217
 inkToolbar node, 1217
 inline elements, WPF, 1227
 inline menu editor, 1522, 1523
 in-memory data allocation, 183, 184
 in-memory representation, 9
 inner exceptions, 281
 innerEllipse object, 1339
 InnerException property, 263, 281
 in/out parameter, 871
 in-place editing, enabling, 1454
 input button, setting default, 1541
 input parameter, 78, 871
 input/output (I/O), 8
 INSERT command, 914
`Insert()` method, 97, 365, 380, 441, 1489, 1490
 Insert request, 861
 Insert Snippet option, 63
 Insert Standard Items option, 1522
 Insert statement, 862, 863, 955, 974, 1450
`InsertAuto()` method, 863, 864, 865, 868, 875, 876, 1074
`InsertCar()` method, 1072, 1073
 InsertCommand property, 914, 918, 949
 Insert/Delete logic, 882
`InsertNewCar()` method, 875–876
`InsertNewElement()` method, 1008
 installing
 Mono, 1565–1568
 strongly named assemblies to GAC, 565–566
 Windows service, 1066–1067
`InstallSqlState.sql` file, 1502
`installutil MathWindowsServiceHost.exe` command, 1066
 instance attribute, 675
 instance data, 182
 instance level, invoking extension methods on, 463
 int data type, 86, 87, 92, 96, 106, 107, 108, 112, 116, 145
 int parameters, 106
 int type, 356
 int variable, 107, 363, 364, 1289
 intArray declaration, 138
 IntCollection class, 369
 integer (0), 1335
 Integer data type, 135, 1479

integrated development environment (IDE), 932, 996, 1024, 1025, 1379, 1381, 1382, 1386, 1396, 1410

IntelliSense, 136, 466–467, 704

IntelliSense window, 423

interactive graphical data, 1246

interface attribute, 670

interface implementation, 336, 337, 339, 342

interface keyword, 20, 325

Interface member, 695

interface types

- Common Type System (CTS), 20
- definitions on, 444
- extending, 469–470

InterfaceExtensions project, 469, 470

InterfaceHierarchy application, 339

InterfaceHierarchy project, 340

InterfaceNameClash application, 336

InterfaceNameClash project, 339

interfaces

- building cloneable objects, 349–354
- building comparable objects, 354–359
- building enumerable types
 - building iterator methods with yield keyword, 346
 - building named iterator, 347–348
- internal representation of an iterator method, 348–349
- overview, 343–345
- custom, defining, 325–327
- defining and implementing in CIL, 670
- designing hierarchies, 339–342
- explicit implementation of, resolving name clashes via, 336–339
- generic, specifying type parameters for, 374–375
- implementing, 327–328
- invoking interface members at object level, 329–331
- as parameters, 331–333
- as return values, 333
- types
 - arrays of, 334

interface types vs. abstract base classes, 322–325

overview, 321

Interlocked class, 740, 756, 757

Interlocked.CompareExchange() method, 757

Interlocked.Exchange() method, 757

Interlocked.Increment() method, 757

Intermediate Language (IL), 12, 13

Intermediate Language Disassembler utility, 33

internal data, of objects, 194

internal keyword, 20, 125, 193, 194, 545

internal modifier, 193, 194

internal reference counter, 292

internal representation

- of anonymous types, 474–475
- of overloaded operators, 451–452

InternalsVisibleToAttribute class, 545

International Organization for Standardization (ISO), 1562

Internet Information Services (IIS), 1025, 1026, 1036, 1037, 1040, 1071, 1074, 1379, 1381, 1382

Internet Protocol (IP) address, 1380, 1381, 1418

interop assemblies, 10, 714, 717

interop library, 716

interoperability assemblies, 714, 716

interoperability data, 716

interoperating, 1121

Interrupt() method, 742

Intersect() method, 515

Intersect<>() method, 509

into operator, 509

intrinsic control command objects, WPF, 1201

intval variable, 757

Invalidate() method, 1246, 1529, 1551, 1556, 1557

invalidating form's client area, 1551

InvalidCastException exception, 329, 365

InvalidOperationException errors, 636

Inventories property, 959

Inventory database, 973

Inventory objects, 984, 989, 1242
 Inventory property, 932, 934
 Inventory schema, 954
 Inventory table, 840–842, 850, 853, 860, 861, 862, 863, 864, 865
 Inventory table icon, 842
 Inventory variable, 1107
 Inventory.aspx file, 1446, 1450
 Inventory.aspx page, 1454
 InventoryDAL class, 862, 863, 864, 865, 874, 875, 880–882
 InventoryDAL object, 863, 872
 InventoryDAL type, 867, 870, 875, 1492
 InventoryDALDisconnectedGUI application, 920
 InventoryDALDisconnectedGUI project, 921
 InventoryDALDisLayer class, 917, 920, 1106
 InventoryDALDisLayer object, 918, 921
 InventoryDALDisLayer variable, 1106, 1107
 InventoryDataSet class, 932, 933, 936
 InventoryDataSet.Designer.cs file, 933
 InventoryDataSet.xsd file, 933
 InventoryDataTable class, 934, 936, 941
 InventoryDataTable variable, 934
 InventoryEDMConsoleApp application, 961
 InventoryEDMConsoleApp example, 979
 InventoryEDM.Designer.cs file, 970
 InventoryEDM.edmx file, 962, 968
 InventoryEDM.edmx node, 970
 InventoryRecord class, 1072, 1074
 InventoryRow class, 934
 InventoryTableAdapter class, 936, 937, 940
 Inventory.xlsx file, 721, 1007–1008
 invisible brushes, 1249
 Invoke() method, 398, 399, 400, 403, 602, 711, 730, 1084, 1086
 InvokeMember() method, System.Type class, 588
 InvokeMethod activity, 1091, 1094–1095, 1096, 1098, 1099
 invoking extension methods, 463–464
 invoking services asynchronously from clients, 1067–1069
 invoking statically, 464
 I/O (input/output), 8
 I/O and object serialization
 abstract stream class, 792–794
 BinaryWriters and BinaryReaders classes, 799–801
 configuring objects for serialization
 overview, 806
 public fields, private fields, and public properties, 807–808
 Serializable types, 807
 customizing Soap/Binary serialization processes
 overview, 818–819
 using attributes, 823
 using ISerializable interface, 820–822
 Directory type, 782–783
 Directory(Info) and File(Info) types, 777–778
 DirectoryInfo type
 creating subdirectories with, 781–782
 enumerating files with, 780–781
 overview, 778–779
 DriveInfo class type, 783–784
 file type, 789–791
 FileInfo class
 AppendText() method, 789
 Create() method, 786
 CreateText() method, 789
 Open() method, 786–788
 OpenRead() method, 788
 OpenText() method, 789
 OpenWrite() method, 788
 overview, 785
 files, watching programmatically, 801–804
 object serialization, 804–806
 overview, 775
 serialization formatters
 IFormatter and IRemotingFormatter interfaces, 809–810

overview, 808
 type fidelity among formatters, 810–811
 serializing collections of objects, 816–817
 serializing objects using
 BinaryFormatter type, 811–813
 serializing objects using SoapFormatter
 type, 813
 serializing objects using XmlSerializer
 type, 814–816
 StreamWriters and StreamReaders
 classes
 directly creating types, 797–798
 overview, 794
 reading from text files, 796–797
 writing to text files, 795–796
 StringWriters and StringReaders
 classes, 798–799
 System.IO namespace, 775–776
 IO namespace, 530
 IP (Internet Protocol) address, 1380, 1381, 1418
 IPointy interface, 325, 326, 327, 328, 329, 330, 333, 334, 335
 IPrintable interface, 341
 IRemotingFormatter interface, 809–810
 IronPython language, 708
 IronRuby language, 708
 is keyword, 250, 272, 307, 330–331
 is-a relationships, 189, 190, 219, 220, 228, 248, 806
 IsAbstract property, System.Type class, 588
 IsAlive property, 741
 IsArray property, System.Type class, 588
 IsBackground property, 741, 750
 IsChecked property, 1220
 IsCOMObject property, System.Type class, 588
 IsCompleted property, 734, 735
 IsCreditRisk column, 880
 IsEnabled property, UIElement type, 1134
 IsEnum property, System.Type class, 588
 ISerializable interface, 262, 818, 820–822
 IService1.cs file, 1057
 IService.cs file, 1072
 ISet<T> interface, 376
 IsEvenNumber() method, 431
 isFlipped variable, 1265
 IsFocused property, UIElement type, 1134
 IsGenericParameter property,
 System.Type class, 588
 IsGenericTypeDefinition property,
 System.Type class, 588
 IShape interface, 341
 IsInitiating property, 1035
 IsInterface property, System.Type class, 588
 IsMDIChildIsMDIContainer property, 1529
 IsMouseDirectlyOver property, UIElement
 type, 1134
 IsMouseOver property, 1134, 1318
 IsNestedPrivate property, System.Type
 class, 588
 IsNestedPublic property, System.Type
 class, 588
 IsNull() method, 893
 IsNullable property, 868
 ISO (International Organization for
 Standardization), 1562
 IsolationLevel enumeration, 879
 IsolationLevel property, 879
 IsOneWay property, 1035
 IsPetNameNull() method, 935
 IsPostBack property, 1417, 1420
 IsPrimitive property, System.Type class, 588
 IsSealed property, System.Type class, 588
 IsSecureConnection property, 1418
 IssuesWithNon-genericCollections
 project, 371
 IsTabStop property, Control Type, 1133
 IsTerminating property, 1035
 ISupportInitialize interface, 261
 IsValueType property, System.Type class, 588
 IsVisible property, UIElement type, 1134
 ItemArray property, 893

<ItemGroup> element, 1149
 ItemHeight value, 1189
 Items (Collection) dialog box, 1218
 Items (Collection) property, 1217, 1219
 Items property, 1455, 1477, 1516
 ItemsSource collection, 1242
 ItemsSource property, 1164
 ItemWidth value, 1189
 iteration constructs
 do/while loop, 119
 foreach loop, use of var within, 118
 for loop, 117
 representing in CIL, 682–683
 while loop, 119
 IterationsAndDecisions project, 117, 122
 iterator methods
 building with yield keyword, 346
 internal representation of, 348–349
 iterators, 346
 IUnknown interface, 7
 IValueConverter interface, data conversion using, 1240–1241

J

Jackpot Deluxe WPF application
 .NET 4.0 visual states
 changing using VisualStateManager class, 1370
 overview, 1366
 for StarButton control, 1367–1368
 state transition timings, 1368–1369
 viewing generated XAML, 1369–1370
 extracting UserControl from drawing geometry, 1365–1366
 finalizing, 1371–1375
 overview, 1364
 Jackpot.jpg file, 1358
 jagged arrays, 141
 JaggedMultidimensionalArray() method, 141
 Java, programming language comparison, 5
 Java Virtual Machine (JVM), 25

JavaScript language, 1389
 JIT (just-in-time) compiler, 536
 JIT compiler, 17, 544, 656
 Jitter, 17
 Join() method, 742
 JpegBitmapEncoder class, 1280
 *.jpg files, 763, 764
 just-in-time (JIT) compiler, 536
 JVM (Java Virtual Machine), 25
 -k flag, 561

K

kaxaml editor, 1155, 1256, 1263, 1276, 1309
 kaxaml.exe file, 1154–1156, 1173, 1186, 1187, 1341
 key frame animations, 1304
 Key property, DictionaryEntry type, 271
 keyboard activity, 1534–1537
 keyboard events, intercepting, 1143–1144
 KeyCode property, 1537
 KeyDown event, 1143, 1144, 1528, 1536, 1537
 KeyEventArgs class, 1143, 1517, 1536, 1537
 KeyEventArgs type, 1537
 KeyEventHandler delegate, 1536
 keyframes, 1360
 KeyNotFoundException exception, 377
 KeyPress event, 1528
 keys, determining which was pressed, 1536–1537
 KeyUp event, 1134, 1143, 1528, 1536
 keyword color coding, 49
 keywords
 pinning types with, 485–486
 XAML, 1156–1159
 Kill() method, System.Diagnostics.Process class, 629, 635
 King, Jason, 1561
 Knife class, 334

L

L command, 566, 872, 876

L suffix, 87
 Label class, 912, 920, 925, 1241, 1396, 1397, 1399, 1403, 1404, 1408
 Label control, 1227, 1240, 1331, 1354, 1434, 1436, 1439, 1455, 1485, 1495
 Label object, 1236, 1309
 Label type, 1304, 1456, 1506
 Label widget, 322, 1422, 1433, 1474
 <Label> control, 1241
 <Label> element, 1132, 1225
 lambda expressions, 430–437, 491–492
 building query expressions using enumerable type and, 519–520
 with multiple (or zero) parameters, 435–436
 parts of, 433
 processing arguments within multiple statements, 433–434
 retrofitting CarEvents example using, 436–437
 lambda operator, 10, 397, 491, 765
 LambdaExpressionsMultipleParams application, 435
 LambdaExpressionsMultipleParams project, 436
 LambdaExpressionSyntax() method, 434
 LAN (Local Area Network), 1019
 language attribute, 1401
 Language Integrated Queries. *See* LINQ
 language integration, 16
 language keywords, 23
 language-neutral form, 532
 LastAccessTime, 778
 LastChildFill attribute, 1194
 last-in, first-out (LIFO), 362, 377
 LastName property, 379, 702
 LastWriteTime property, FileSystemInfo class, 778
 late binding
 attributes using, 615–617
 calls, simplifying using dynamic types, 710–713
 invoking methods with no parameters, 602–603
 invoking methods with parameters, 603–604
 overview, 600
 System.Activator class, 601–602
 LateBindingApp application, 601
 LateBindingWithDynamic application, 711
 LateBindingWithDynamic project, 711, 712
 Layout area, 1218
 layout buttons, 1231
 Layout controls, WPF, 1180
 Layout section, 1217
 LayoutMdi() method, 1530
 LayoutRoot icon, 1211
 LayoutRoot item, 1211
 LayoutRoot node, 1213
 LayoutTransform property, 1262, 1264
 lazy objects, 313–317
 Lazy<> class, 314, 315, 316
 Lazy<> type, 315
 Lazy<> variable, 315, 316
 LazyObjectInstantiation project, 313, 316
 lblControlInfo control, 1434
 lblFavCar widget, 1474
 lblTextBoxData control, 1436
 lblUserData label, 1505, 1506, 1507
 ldarg opcode, 679, 681
 ldc opcode, 679
 ldfld opcode, 679
 ldflda opcode, 686
 ldloc opcode, 679
 ldnull opcode, 293
 ldobj opcode, 679
 ldstr opcode, 104, 655, 657, 679
 Left property, 1527
 Length member
 FileInfo class, 785
 Stream class, 792
 Length property
 Array class, 143, 144
 String system type, 97
 LessThan value, 1461
 lexical scope, 690
 lib\mono\gac directory, Mono, 1568
 libraries

- .NET code, 581
 - COM type, 581
 - consuming workflow, 1112–1114
 - of extension, 467–468
 - external code, 1083
 - isolating workflows into dedicated
 - arguments, defining, 1105–1106
 - assemblies, importing, 1105
 - Assign activity, 1107
 - Code activity, 1109–1111
 - defining project, 1103–1104
 - If activity, 1107–1108
 - namespaces, importing, 1105
 - Switch activity, 1107–1108
 - variables, defining, 1106–1107
 - unloading, 639
- LibraryBuild.rsp file, 1573, 1574
- life cycle
- of ASP.NET Web pages
 - AutoEventWireup attribute, 1424–1425
 - Error event, 1425–1426
 - overview, 1423
 - of Form type, 1531–1533
- lifeTimeInfo string, 1532
- lifeTimeInfo variable, 1532
- LIFO (last-in, first-out), 362, 377
- Lightning Bolt button, 1221, 1523
- lightweight class type, 151
- lightweight events, 473
- Limes.jpg file, 1358
- Line class, 1247, 1256
- line geometry, 1261
- Line object, 1250, 1252
- Line type, 1254
- <Line> element, 1267
- linear gradient, 1258
- linear interpolation animations, 1304
- LinearGradientBrush class, 1161
- LinearGradientBrush object, 1550
- LinearGradientBrush type, 1161, 1258
- LineBreak class, 1230
- LineBreak element, 1227
- LineBreak type, 1227
- LineGeometry class, 1255
- LineGeometry object, 1255
- lines
- adding to canvas, 1249–1252
 - removing from canvas, 1252–1253
- LinkedList<T> class, 377
- LinkedListNode<T> type, 377
- LINQ
- programming to DataSet types with
 - DataSet extensions library, 945–946
 - obtaining LINQ-compatible
 - datatables, 946–947
 - overview, 943–944
 - populating new DataTables from
 - LINQ queries, 948–950
 - role of
 - DataRowExtensions.Field<T>()
 - Extension method, 948
 - queries, populating new DataTables
 - from, 948–950
 - LINQ to DataSet term, 494
 - LINQ to Entities, querying with, 975–977, 984–985
 - LINQ to Objects
 - applying LINQ queries to collection
 - objects
 - accessing contained subobjects, 506–507
 - applying LINQ queries to
 - nongeneric collections, 507–508
 - filtering data using OfType<T>(), 508
 - overview, 505
 - applying LINQ queries to primitive
 - arrays
 - extension methods, 500
 - implicitly typed local variables, 498–500
 - overview, 496–497
 - result set, 498
 - role of deferred execution, 501–502
 - role of immediate execution, 502–503
 - applying to collection objects, 508
 - C# LINQ query operators
 - aggregation operations, 516–517

basic selection syntax, 510–511
 LINQ as better Venn diagramming tool, 515–516
 obtaining counts using enumerable, 513
 obtaining subsets of data, 511
 overview, 508–509
 projecting new data types, 512–513
 removing duplicates, 516
 reversing result sets, 514
 sorting expressions, 514
 internal representation of LINQ query statements
 building query expressions using enumerable type and anonymous methods, 520
 building query expressions using enumerable type and lambda expressions, 519–520
 building query expressions using enumerable type and raw delegates, 521–522
 building query expressions with query operators, 518
 overview, 517
 LINQ specific programming constructs
 anonymous types, 493
 extension methods, 492–493
 implicit typing of local variables, 490
 lambda expressions, 491–492
 object and collection initialization syntax, 491
 overview, 489
 returning result of LINQ query, 503–505
 role of LINQ, 493–495
LINQ to XML
 System.Xml.Linq namespaces, 997–1002
XElement and XDocument objects
 generating documents from arrays and containers, 1004–1005
 loading and parsing XML content, 1006
 overview, 1002–1003
XML APIs

vs. DOM models, 995–996
 overview, 993–994
 Visual Basic (VB) literal syntax, 996–997
XML documents
 building UI of LINQ to XML App, 1007
 defining LINQ to XML Helper class, 1008–1009
 importing Inventory.xml files, 1007–1008
 overview, 1006
 rigging up UI to Helper class, 1009–1011
 LINQ-compatible datatables, obtaining, 946–947
LinqOverArray application, 496
LinqOverArray project, 503
LinqOverArrayUsingEnumerable project, 522
LinqOverCollections project, 505, 508
LinqOverDataSet example, 949
LinqOverDataTable() method, 945
LinqRetValues application, 504
LinqRetValues project, 505
LinqToDataSetApp application, 946
LinqToXmlFirstLook application, 993
LinqToXmlObjectModel class, 1008
LinqToXmlWinApp application, 1007
LinqUsingEnumerable application, 518
 Linux operating system, executing Windows Forms application under, 1580
List block, 1231
List class, 1230
List element, 1227, 1231
List type, 1227
List<> class, 370
List<> object, 371, 372
List<Car> collection, 906
List<Car> parameter, 506
List<NewCar> object, 866
List<T> class, 371, 373, 374, 377, 379–380, 491, 719, 763, 1074
List<T> container, 1004

List<T> object, 952
 List<T> type, 373, 493, 505
 List<T> variable, 374, 506, 671, 905, 1556, 1557, 1559
 ListBox class, 1164
 ListBox control, 1224, 1225, 1319, 1431, 1439, 1455, 1477, 1478
 ListBox type, 621
 ListBox web control, 1477
 ListBoxes control, 1531
 listCars variable, 905
 ListControl type, 1431
 ListDictionary type, 363
 ListFields() method, 591
 ListInterfaces() method, 591
 ListInventory() method, 874
 ListInventoryViaList() method, 874
 ListMethods() method, 590, 594, 595
 listOfHandlers delegate, 406
 listOfHandlers variable, 407, 418
 lists
 comma-delimited, 130
 semicolon-delimited, 46
 literal attribute, 674
 literal floating point data, 96
 Load event, 719, 989, 1409, 1420, 1423, 1424, 1478, 1492, 1496, 1506
 Load() method, 554, 596, 639, 1006
 loaded assemblies, 641–643
 Loaded event, 1173, 1174, 1278, 1288, 1289, 1311, 1359
 LoadExternalModule() method, 622, 623
 LoadFrom() method, 554, 596
 loading
 assemblies, into custom application domains, 645
 images programmatically, 1288–1289
 InkCanvas data, 1226–1227
 XML content, 1006
 Local Area Network (LAN), 1019
 local variables
 accessing, C#, 429–430
 declaring in CIL, 680–681
 mapping parameters to in CIL, 681
 LocalBuilder member, 689
 localized assemblies, 598
 LocalNullableVariables() method, 163
 .locals directive, 657, 681
 LocalVarDeclarations() method, 89
 Location property, 1535
 lock keyword, synchronization using, 753–754
 Lock() method, *HttpApplicationState* type, 1484, 1487
 lock scope, 754
 lock statement, 757
 lock token, 753
 locks, threading primitives, 729
 logging support, 1078
 logical model, 958
 logical operators, C#, 120, 121
 logical resources, 1285
 logical trees, WPF, 1341–1348
 logical view, 1341
 LogicalTreeHelper class, 1342
 Login controls, 1440
 lollipop notation, 328
 long data type, 87
 longhand notation, 718
 longhand reflection calls, 711
 lookless, 1341
 LookUpColorsForMake() method, 1009
 LookUpPetName() method, 876
 looping animation, 1308–1309
 loops. *See* iteration constructs
 loose resources, WPF
 configuring, 1287
 including files in project, 1286–1287
 lstTextBoxData control, 1431

M

M command, 1257
 MacDonald, Matthew, 1395
 machine.config file, 1051, 1063, 1503, 1505
 MachineName class, 1031
 MachineName property,
 System.Diagnostics.Process class, 628

MachineName property,
 System.Environment class, 81
 magic numbers, 146
 MagicEightBallService class, 1033, 1052
 MagicEightBallServiceClient application,
 1046
 MagicEightBallServiceClient project, 1048,
 1075
 MagicEightBallServiceClient.exe.config
 file, 1050
 MagicEightBallServiceHost project, 1036,
 1045, 1051
 MagicEightBallServiceHost.exe
 application, 1059
 MagicEightBallServiceHTTP directory,
 1036, 1045, 1048
 MagicEightBallServiceHTTPDefaultBindin
 gs project, 1057
 MagicEightBallServiceLib namespace,
 1036
 MagicEightBallServiceLib project, 1032,
 1036
 MagicEightBallServiceLib.dll assembly,
 1036, 1049
 MagicEightBallTCP project, 1050
 main menu system, 1552–1553
 Main() method
 implementing, 872
 Program class, 34
 variations on, 75–76
 WPF application, 626
 MainControl.xaml file, 1357
 MainForm class, 905, 906, 989
 MainForm_Load() method, 937
 MainForm.cs file, 763, 920
 MainMenuStrip property, 1516
 MainWindow class
 adding code file for, 1165
 defining, 1146–1147
 MainWindow property, 1129, 1137
 MainWindow type, 1516, 1535, 1553, 1555
 MainWindow_Paint() method, 1549
 MainWindow.baml file, 1151
 MainWindow.cs file, 1520, 1534, 1549, 1552
 MainWindow.cs icon, 1520
 MainWindow.Designer.cs file, 1520, 1523
 MainWindow.g.cs file, 1150, 1165
 MainWindowTitle property,
 System.Diagnostics.Process class,
 629
 MainWindow.xaml file, 1146, 1149, 1151,
 1165, 1173, 1174, 1294, 1366
 Make Into UserControl option, 1365
 Make property, 1110
 MakeACar() method, 291, 292, 293
 MakeColumn column, 934
 MakeNewAppDomain() method, 645
 Manage Help Settings tool, 68
 managed attributes, 675
 managed code, 10
 managed heap, 289, 291, 292, 293, 294
 managed resources, 311
 ManagedThreadId property, 731
 Manager class, 226, 227, 228
 Manager object, 229
 Manager type, 229, 230
 MANIFEST assembly, 544, 712
 MANIFEST data, 542
 MANIFEST icon, 35, 542
 MapPath() method, 1418
 mapping database names to friendly
 names, 916
 Mapping Details window, 967, 968, 969
 mappings, viewing, 967
 Margin property, 1195
 markup, 1119
 markup extensions, XAML, 1163–1165
 markup tags, 1440
 MarkupExtension class, 1163
 massive numerical value, 96
 master constructor, 177, 178, 179, 201
 *.master file, 1442, 1444, 1446, 1447, 1448
 master pages
 AdRotator widget, 1447–1448
 bread crumbs, establishing with
 SiteMapPath type, 1447
 overview, 1442–1444
 TreeView control site navigation Logic,
 1445–1447
 Master property, 1450

<%@Master%> directive, 1443
 MasterPage class, 1443
 MasterPageFile attribute, 1402, 1449
 MasterPageFile property, 1417
 MasterPage.master file, 1443
 Math class, 181
 MathClient application, 1067
 MathClient project, 1070, 1075
 MathExtensions class, 469
 MathLib.dll code library, 43
 MathLibrary assembly, 574
 MathLibrary project, 711
 MathLibrary.dll assembly, 711, 712
 MathMessage delegate, 435
 MathService.cs file, 1058
 MathServiceLibrary namespace, 1057, 1058
 MathServiceLibrary project, 1057
 MathServiceLibrary.dll assembly, 1062
 MathWindowsServiceHost project, 1062, 1066, 1067
 MathWinService.cs file, 1062
 MatrixTransform type, 1262
 Max() method, 516
 MAX_IMAGES constant, 1289
 Max<>() method, 509
 Max<T>() method, 500
 MaxGeneration method, System.GC class, 298
 MaxHeight property, FrameworkElement type, 1133
 MaximizeBox property, 1530, 1538
 MaximumValue property, 1460
 MaxSpeed variable, 263
 .maxstack directive, 662, 680
 MaxValue property, 92, 93
 MaxWidth property, FrameworkElement type, 1133
 mcs compiler, Mono, 1569
 MDI (multiple document interface) application, 1525
 MdiChildActive event, 1531
 Media controls, WPF, 1180
 MediaCommands class, WPF, 1201
 MediaPlayer type, 1272
 member parameters, defining in CIL, 676–677
 member shadowing, 245–247
 member variables, 167
 MemberInfo class, System.Reflection Namespace, 587
 members, 22, 374
 MemberType property, MethodBase object, 268
 MemberwiseClone() method, 252, 349, 351, 353, 354
 MemoryStream class, 776
 MemoryStream object, 1234
 Menu class, 1196
 Menu control, 1439, 1445, 1446
 Menu item, 1447
 Menu property, 1530
 menu systems
 building visually, 1522–1524
 building window frame using nested panels, 1196–1197
 <Menu> definition, 1197
 MenuItem element, 1202, 1205
 MenuItem objects, 1196
 Menus & Toolbars node, 1522
 ToolStrip component, 621
 ToolStrip control, 1522
 ToolStrip object, 1516
 ToolStrip type, 1516
 Merge() method, 888
 merged resource dictionaries, defining, 1298–1299
 Message property, 109, 263, 265, 267, 273, 275, 276, 284
 Message Transmission Optimization Mechanism (MTOM), 1029
 MessageBox class, 540, 1137
 MessageBox.Show() method, 663, 686, 746, 1349, 1532
 messageDetails field, 274
 MessageToShow argument, 1084, 1085
 messaging activities, WF 4.0, 1090–1091
 metadata. *See also* type metadata
 of assemblies, 17–18
 interop, embedding, 716–717

tables, 494
 types, 536

metadata exchange (MEX)
 behavior configuration, 1054–1055
 enabling, 1043–1045

metadata viewer. *See* custom metadata viewer

MetaInfo window, 586

method attribute, 1417

method group conversion, 9, 412

method implementation, 13

method invocations, asynchronous, 22

Method member, 401

method overriding, 236

method parameters and return values, 594–595

Method property, 404

method scope, 186, 290, 296

method signature, 132, 1572

MethodAttributes.Public method, 697

MethodBase object, 263, 268

MethodBase.DeclaringType property, 268

MethodBuilder class, 697

MethodBuilder member, 689

MethodBuilder type, 690

MethodInfo class, 587, 710, 711

MethodInfo object, 602

MethodInfo type, 590

MethodInfo.Invoke() method, 602

MethodInfo.Name property, 590

MethodName property, 1095, 1098

MethodOverloading application, 137

MethodOverloading project, 135

methods

- anonymous, C#, 427, 429–430
- custom generic, creating, 385–388
- custom metadata viewer, 590
- of DataSet types, 888
- default parameter-passing behavior, 126–127
- extension, 10
- invoking asynchronously
 - overview, 733
 - passing and receiving custom state data, 738–739

role of AsyncCallback delegate, 736–738

role ofAsyncResult class, 738

synchronizing calling thread, 734–735

named parameters, 133–134

with no parameters, invoking, 602–603

optional parameters, 131–132

out modifier, 127–128

overloading of, 135–137

overridable, 238

overview, 125

with parameters, invoking, 603–604

params modifier, 130–131

ref modifier, 128–129

static, 181–182

MEX. *See* metadata exchange

MFC (C++/Microsoft Foundation Classes), 4

MFC (Microsoft Foundation Classes), 4, 25

mfc42.dll library, 25

MI (multiple inheritance), with interface types, 341–342

Microsoft Expression Blend, 1119

Microsoft Foundation Classes (MFC), 4, 25

Microsoft GAC, 1575

Microsoft Intermediate Language (MSIL), 13

Microsoft Message Queuing (MSMQ), 1015–1016, 1019, 1020, 1023, 1028, 1031, 1032

Microsoft namespace, 30

Microsoft SQL Server data provider, 829

Microsoft SQL Server Management Studio, 1502

Microsoft SQL Server Mobile data provider, 829

Microsoft Transaction Server (MTS), 1015

Microsoft.CSharp namespace, 30

Microsoft.CSharp.dll assembly, 705

Microsoft.CSharp.RuntimeBinder namespace, 705

Microsoft.CSharp.Targets file, 1149

Microsoft.ManagementConsole namespace, 30

Microsoft.Office.Interop.Excel.dll
 assembly, 720
Microsoft.SqlServer.Server namespace,
 831
Microsoft-supplied data providers, 829–
 830
Microsoft.Win32 namespace, 30, 1183,
 1206
Microsoft.WinFX.targets file, 1149
MIIInterfaceHierarchy application, 341
MIIInterfaceHierarchy project, 342
**MIME (Multipurpose Internet Mail
 Extensions)**, 1421
Min() method, 516
Min<>() method, 509
MinHeight property, *FrameworkElement*
 type, 1133
MinimizeBox property, 1530, 1538
MinimumValue property, 1460
MiniVan class, 220, 221, 222, 602
MiniVan objects, 453, 602
MinValue property, 92, 93
MinWidth property, *FrameworkElement*
 type, 1133
Miscellaneous category, 1229
MissingPrimaryKeyException exception,
 832
mnuFile object, 1516
mnuFileExit type, 1517
Model Browser window, 966, 983
Model-View-Controller (MVC) pattern,
 1395
Modified value, 895
ModifierKeys property, 1527
modifiers, for methods
 out, 127–128
 params, 130–131
 ref, 128–129
Modifiers property, 1537, 1543
modifying application data, 1486–1487
Module class, *System.Reflection*
 Namespace, 587
module option, 550
module set of process, 634
[module:] tag, 612
Module1.vb code file, 548
ModuleBuilder class, 694
ModuleBuilder member, 689
ModuleBuilder type, 694–695
ModuleBuilder.CreateType() method, 695
ModuleBuilder.SetEntryPoint() method,
 689
module-level manifest, 537, 551
modules, 14, 44, 536
Modules property,
System.Diagnostics.Process class,
 629
modulo statement, 433, 434
Monitor class, 740, 756
Monitor object, 740
Monitor.Enter() method, 756
Monitor.Exit() method, 756
MonitoringIsEnabled property,
AppDomain class, 639
Monitor.Pulse() method, 756
Monitor.PulseAll() method, 756
monitors, threading primitives, 729
Monitor.Wait() method, 756
Mono
 building .NET applications with
 building console application in
 Mono, 1576–1578
 building Mono code library, 1572–
 1575
 building Windows Forms Client
 program, 1578–1580
development languages
 MonoDevelop IDE, 1569–1570
 working with C# compiler, 1569
development tools, Microsoft-
 compatible
 Mono-specific development tools,
 1571–1572
 overview, 1570
directory structure of, 1567–1568
further study of, 1581–1582
obtaining and installing, 1565–1568
overview, 1561
scope of, 1564–1565
who uses, 1581

Mono <version> For Windows option, 1568
 Mono GAC, installing assemblies into, 1575
 mono print, 1572
 Mono project, 39, 1126
 Mono SDK, 1565
 MonoDevelop IDE, 666, 1569–1570
 monodis tool, viewing updated manifest with, 1574–1575
 monodis utility, Mono, 1571
 monop tool, Mono, 1571, 1572
 Moonlight, Silverlight API, 1565
 Motorcycle class, 173, 174, 176, 177, 178, 606, 610
 Motorcycle object, 179
 mouse activity
 determining which button was clicked, 1535–1536
 overview, 1534
 mouse events, intercepting, 1142–1143
 mouse operation, 1280
 mouseActivity variable, 1339
 MouseAndKeyboardEventsApp project, 1534, 1538
 MouseButtonEventArgs, 1252
 MouseButtons enumeration, 1534, 1535
 MouseButtons property, 1527
 MouseClick event, 1535
 MouseDoubleClick event, 1133, 1535
 MouseDown event, 1134, 1142, 1248, 1276, 1283, 1338, 1339, 1370, 1371, 1373
 MouseDownStar state, 1366, 1367, 1368, 1369
 MouseEnter event, 1134, 1142, 1172, 1196, 1197, 1199, 1306, 1370, 1528
 MouseEnterStar state, 1366, 1367, 1368
 MouseEventArgs class, 1142, 1535
 MouseEventArgs parameter, 1534
 MouseEventArgs type, 1517
 MouseExit event, 1196
 MouseExit handler, 1197
 MouseExitStar state, 1366, 1368
 MouseHover event, 1528
 MouseLeave event, 1134, 1142, 1199, 1370, 1528
 MouseLeftButtonDown event, 1250, 1251
 MouseMove event, 1134, 1142, 1143, 1430, 1528, 1534, 1535
 MouseRightButtonDown event, 1252
 MouseStateGroup, 1366, 1367, 1368
 MouseUp event, 1142, 1338, 1528, 1535
 MouseWheel event, 1528
 MoveNext() method, 344, 348
 MoveTo() method
 DirectoryInfo class, 779
 FileInfo class, 785
 MSBuild, 43
 msbuild.exe utility, 1148, 1149, 1150, 1151, 1153
 processing files with
 building WPF applications using code-behind files, 1166–1167
 building WPF applications with XAML, 1148–1150
 mscoree.dll library, 25, 26, 37
 mscorlib reference, 662
 [mscorlib]System.Collections.ArrayList, 677
 [mscorlib]System.Collections.ArrayList type, 677
 [mscorlib]System.Enum, 671
 [mscorlib]System.ValueType, 671
 mscorlib.dll assembly, 22, 26, 27, 32, 361, 587, 590, 595, 601, 1572
 MSIL (Microsoft Intermediate Language), 13
 MSMQ (Microsoft Message Queuing), 1015–1016, 1019, 1020, 1023, 1028, 1031, 1032
 MSMQ-based bindings, 1031
 MsmqIntegrationBinding class, 1031, 1032
 <msmqIntegrationBinding> element, 1031
 msvbvm60.dll library, 25
 MTOM (Message Transmission Optimization Mechanism), 1029
 MTS (Microsoft Transaction Server), 1015
 mul opcode, 678
 MulticastDelegate class, 401, 403, 412
 multicasting, 22

- multicore processors, 727
- multidimensional array, 866
- multidimensional arrays, 140–141
- multi-file assemblies, 14, 536–538, 586
- multifile NET assemblies, building and
 - consuming
 - `airvehicles.dll` file, 551–552
 - consuming multifile assembly, 552
 - overview, 550
 - `ufo.netmodule` file, 551
- multifile pages, compilation cycle for, 1410
- MultifileAssembly code files, 553
- multi-language, programming languages, 12
- Multiline property, 1007
- multiple (or zero) parameters, lambda expressions with, 435–436
- multiple base classes, 222
- multiple bindings, exposing single services using, 1052–1053
- multiple conditions, 1317
- multiple dimensions, indexers with, 443–444
- multiple document interface (MDI)
 - application, 1525
- multiple exceptions
 - finally blocks, 282
 - general catch statements, 279–280
 - inner exceptions, 281
 - overview, 277–278
 - rethrowing, 280
- multiple inheritance (MI), with interface types, 341–342
- multiple sort orders, specifying, 357–358
- multiple statements, processing
 - arguments within, 433–434
- `Multiply()` method, 96, 394
- Multipurpose Internet Mail Extensions (MIME), 1421
- multitabled DataSet objects and data relationships
 - building table relationships, 924
 - navigating between related tables, 925–927
 - overview, 921
- prepping data adapters, 922–923
- updating database tables, 924
- MultitabledDataSetApp application, 921
- MultitabledDataSetApp project, 927
- multithreaded and parallel programming
 - asynchronous nature of delegates
 - `BeginInvoke()` and `EndInvoke()` methods, 732
 - overview, 731
 - `System.IAsyncResult` interface, 732–733
 - brief review of .NET delegate, 729–731
 - CLR thread pool, 760–761
 - concurrency, 750–758
 - invoking methods asynchronously
 - overview, 733–735
 - passing and receiving custom state data, 738–739
 - role of `AsyncCallback` delegate, 736–738
 - role of `AsyncResult` class, 738
 - synchronizing calling thread, 734–735
- overview, 727
- parallel LINQ queries (PLINQ)
 - cancelling, 772–774
 - opting in to, 772
 - overview, 771
- parallel programming under .NET
 - platform
 - handling cancellation request, 766–767
 - overview, 761
 - role of `Parallel` class, 763
 - `Task` class, 765–766
 - task parallel library API, 762–763
 - task parallelism, 768–771
 - understanding data parallelism, 763–766
 - process/appdomain/context/thread relationship
 - overview, 727
 - problem of concurrency, 728–729
 - role of thread synchronization, 729

programmatically creating secondary threads
 AutoResetEvent class, 748–749
 foreground and background threads, 749–750
 overview, 744
 ParameterizedThreadStart delegate, 747
 ThreadStart delegate, 745–746
 programming with timer callbacks, 758–759
 synchronization
 using [Synchronization] attribute, 757–758
 using C# lock keyword, 753–754
 using System.Threading.Interlocked type, 756–757
 using System.Threading.Monitor type, 755–756
 System.Threading namespace, 739–740
 System.Threading.Thread class
 Name property, 743
 obtaining statistics about current thread, 742
 overview, 741
 Priority property, 744
 MultiThreadedPrinting project, 751, 755
 MultiThreadSharedData program, 756
<MultiTrigger> element, 1317
 MusicMedia enum, 570
 mutator method, 194, 195, 196, 198, 200, 206
 Mutex class, System.Threading namespace, 740
 MVC (Model-View-Controller) pattern, 1395
 My other string value, 104
 My3DShapes namespace, 527, 530
 MyApp class, adding code file for, 1166
 MyApp.g.cs file, 1150, 1153, 1166
 MyApp.xaml file, 1147, 1149, 1166
 MyAssembly.dll assembly, 691
 MyBaseClass namespace, 668, 669
 myBrush key, 1296
 myBrush resource, 1294
 MyBrushesLibrary project, 1300
 MyBrushes.xaml file, 1299, 1300, 1301
 myCar object, 291, 474, 475
 myCar reference, 291
 myCars list, 506
 MyCars.dll assembly, 532
 MyCompany namespace, 668
 MyConnectionFactory project, 837, 840
 MyConnectionFactory.dll assembly, 840
 MyConnectionFactory.exe application, 840
 MyControls.dll library, 1159
 MyCoolApp.exe application, 48
 myCtrls tag, 1159
<myCtrls>ShowNumberControl> scope, 1333
 MyCustomControl namespace, 1364
 MyCustomControl project, 1356, 1364
 MyCustomControl.dll assembly, 1364
 MyDefaultNamespace namespace, 531
 MyDerivedClass class, 669
 MyDirectoryWatcher project, 804
 myDocumentReader control, 1229, 1233
 MyDoubleConverter class, 1240
 MyEBookReader project, 771
 MyEBookReader, Windows Forms application, 768
 MyEnum enumeration, 674
 MyEventHandler() method, 427
 MyExtendableApp.exe assembly, 618
 MyExtensionsLibrary project, 469
 MyExtensionsLibraryClient project, 469
 MyExtensionsLibrary.dll assembly, 468
 MyGenericDelegate<T>, 416
 MyGenericMethods class, 388
 myInkCanvas control, 1222
 myKeyFile.snk file, 564
 myListBox listbox, 1477
 MyLocalVariables() method, 680
 MyMathClass class, 214, 215
 MyMathClass.PI constant, 215
 MyPage_aspx class, 1405
 MyPaintProgram namespace, 1554
 myPanel control, 1433
 MyPoint type, 155

MyPrivateQ queue, 1032
 myProxy.cs file, 1046
 MyResourceWrapper class, 303, 304, 306,
 310, 311, 312
 MySDWinApp solution, 51
 myShapes array, 245
 MyShapes namespace, 525, 526, 527
 MyShell.exe application, 43
 MySqlConnectionString class, 828
 myTabSystem control, 1213
 MyTarget method, 417
 MyTestKeyPair folder, 561
 MyTestKeyPair.snk file, 561, 562
 myTestKeyPair.snk file, 1575
 MyTypeViewer assembly, 595
 MyTypeViewer.exe, 593
 MyWordPad application, 1195
 MyWordPad project, 1207
 MyXamlPad project, 1168, 1178
 MyXamlPad.exe application, 1309
 MyXamlPad.exe file, 1175, 1177, 1186,
 1187, 1311

N

N string format character, 84
 name attribute, 577, 1037, 1054, 1505
 name clashes, resolving via explicit
 interface implementation of, 336–
 339
 Name edit area, 1213
 name field, 174, 175
 Name keyword, 1158
 Name method, FileInfo class, 785
 name parameter, 174
 Name property
 Employee class, 200, 201
 FileSystemInfo class, 778
 FrameworkElement type, 1133
 System.Threading.Thread class, 743
 Name values, 511, 595
 named argument syntax, 180
 named arguments, 133
 named parameters, for methods, 133–134

named pipes, 1019
 NameOfControl_NameOfEvent() method,
 1524
 namespace concept, 27
 .namespace directive, 655, 668
 namespace keyword, 525
 Namespace property, 1034
 namespaces, 27–32, 1512–1513
 accessing programmatically, 30–32
 custom, 525–531
 default, of Visual Studio 2010, 531
 defining in CIL, 668
 Microsoft root namespace, 30
 nested, 530
 referencing external assemblies, 32
 workflow, 1105
<namespaces> element, 1427
 name/value pairs, 147, 493, 1088
 naming convention, 537
 narrowing conversion, 107
 narrowing operation, 106, 107
 NarrowingAttempt() method, 108
 naturally dirty windows, 1551
 Navigate to Event Handler menu option,
 1205
 navigating between related tables, 925–927
 Navigation node, 1439
 Navigation Properties section, 982
 navigation properties, using within LINQ
 to Entity queries, 984–985
 Navigation tab, 1447
 navigation-based applications, 1124
 navigation-based desktop program, 1124
 NavigationCommands class, WPF, 1202
 NavigationWindow class, 1124, 1155
 NavigationWindow element, 1341
 ndexOutOfRangeException class, 272
 nested assembly attribute, 669
 nested famandassem attribute, 669
 nested family attribute, 669
 nested famorassem attribute, 669
 nested namespaces, creating, 530
 nested panels, WPF, building window
 frame using
 finalizing UI design, 1198

menu system, 1196–1197
 MouseEnter event handler,
 implementing, 1199
 MouseLeave event handler,
 implementing, 1199
 overview, 1195
 spell checking logic, implementing,
 1200
 StatusBar, 1198
 ToolBar, 1197–1198
 nested private attribute, 669
 nested public attribute, 669
 nested type definitions, 233–235
 Nested Types node, InventoryDataSet
 icon, 934
 NestedAssembly member, 695
 NestedFamAndAssem member, 695
 NestedFamily member, 695
 NestedFamORAssem member, 695
 NestedPrivate member, 695
 NestedPublic member, 695
 .NET 4.0 visual states
 changing using VisualStateManager
 class, 1370
 overview, 1366
 for StarButton control, 1367–1368
 state transition timings, 1368–1369
 viewing generated XAML, 1369–1370
 .NET assemblies
 <codeBase> element, 576–577
 building with CIL
 building CILCarClient.exe, 686–687
 building CILCars.dll, 683–686
 defining custom namespaces
 creating nested namespaces, 530
 default namespace of Visual Studio
 2010, 531
 overview, 525–526
 resolving name clashes with aliases,
 528–530
 resolving name clashes with fully
 qualified names, 527–528
 format of

CIL (common intermediate language) code, type metadata, and assembly manifest, 536
 CLR file header, 535
 optional assembly resources, 536
 overview, 533
 single-file and multifile assemblies, 536–538
 Windows file header, 534–535
 multifile, building and consuming
 airvehicles.dll file, 551–552
 Consuming multifile assembly, 552
 overview, 550
 ufo.netmodule file, 551
 private
 configuration files and Visual Studio
 2010, 556–558
 configuring private assemblies, 554–556
 identity of private assembly, 553
 probing process, 553–554
 publisher policy assemblies, 574–575
 role of, 532–533
 shared
 configuring, 569–574
 Consuming, 567–569
 generating strong names at
 command line, 561–563
 generating strong names using
 Visual Studio 2010, 563–564
 installing strongly named
 assemblies to GAC, 565–566
 overview, 558–559
 strong names, overview, 560–561
 viewing .NET 4.0 GAC using
 Windows Explorer, 566
 single-file assembly, building and
 Consuming
 building C# client application, 545–547
 building Visual Basic client
 application, 547–549
 CIL (common intermediate language), 544

- cross-language inheritance in
 - action, 549
 - manifest, 541–544
 - overview, 538–540
 - type metadata, 544–545
- `System.Configuration` namespace, 577
- transforming markup into
 - BAML, 1151–1152
 - mapping application data to C# code, 1153
 - mapping window data to C# code, 1150–1151
 - XAML-to-assembly process, 1153–1154
- .NET attributes
 - applying in C#, 606–607
 - attribute consumers, 605–606
 - C# attribute shorthand notation, 607–608
 - obsolete attribute, 608–609
 - overview, 604
 - specifying constructor parameters for, 608
- .NET exception handling, 260–262
- .NET executable program, process entry point, 626
- .NET Framework 4.0 SDK documentation, 282, 299, 307, 530, 545, 740, 756, 773, 1184, 1336
- .NET Framework 4.0 Software Development Kit (SDK), 41–42, 67–69
- .NET module, 536
- .NET platform, parallel programming under
 - data parallelism, 763–766
 - handling cancelation request, 766–767
 - overview, 761
 - role of `Parallel` class, 763
 - `Task` class, 765–766
 - task parallel library API, 762–763
 - task parallelism, 768–771
- .NET properties, using for encapsulation of classes, 198–200
- .NET remoting, 1016
- .NET-aware programming languages, 10–12
- *.netmodule file extension, 537, 548, 550, 586
- `NetMsmqBinding` class, 1031, 1032
- `netMsmqBinding` class, 1042
- <`netMsmqBinding`> element, 1031
- `NetNamedPipeBinding` class, 1030, 1032
- <`netNamedPipeBinding`> element, 1030
- `NetPeerTcpBinding` class, 1030, 1032
- <`netPeerTcpBinding`> element, 1030
- `NetTcpBinding` class, 1030, 1032, 1049, 1054, 1070
- `NetTcpBinding` object, 1050
- <`netTcpBinding`> element, 1030, 1050
- New button, 1229
- New Connection button, 929, 963
- `new()` constraint, 393
- New Data Source option, 1447
- <`New Event Handler`> option, 1172
- New Folder menu option, 1286
- new instance, 253
- new keyword, 89, 90, 125, 153, 170, 171, 209, 291, 292–293, 588
- new object pointer, 292
- new operator, and system data types, 89–90
- New option, 563
- New Project button, 1207
- New Project dialog box, 51, 56, 621, 1024, 1057, 1079, 1103, 1207
- New project menu command, 1207, 1356
- New Project menu option, 538, 1300, 1518
- New Solution menu option, 665
- New Storyboard button, 1359
- New Web Site dialog box Visual Studio 2010, 1025
- `newarr` opcode, 678
- `NewCar` class, 864
- `NewCar` object, 876
- `NewCarDialog.cs` file, 719
- `NewCarDialog.designer.cs` file, 719
- `NewCarDialog.resx` file, 719
- `NewLine` member, `TextWriter` class, 795

NewLine property, System.Environment class, 81
 newobj instruction, 292
 newobj opcode, 678
 newVersion attribute, 573
 Next button, 928
 next object pointer, 292
 NextResult() method, 861
 ngen.exe command-line tool, 17
 ngen.exe utility, Microsoft .NET, 1570
 inheritance chain, 1326
 Nodes<T> method, 1000
 nonabstract, 1145
 None radio button, 981
 non-ephemeral generation, 297
 non-generic collections
 applying LINQ queries to, 507–508
 issues with
 overview, 361–362
 performance, 363–367
 type safety, 367–371
 nonnullable variable, 162
 non-optional parameters, 132
 [NonSerialized] attribute, 605, 606
 nonstatic class data, 182
 nonstatic method, 182, 188
 NoNullAllowedException exception, 832
 not opcode, 678
 not System.Int32, 366
 Notepad++, building C# applications with, 49–50
 NotEqual value, 1461
 Nothing value, 1107
 NotPublic member, 695
 notserialized token, 606
 Now property, DateTime class, 132
 null brush, 1259
 null reference, 209, 254, 293, 330
 null, setting object references to, 293–294
 nullable types
 ?? operator, 164–165
 overview, 162
 working with, 163–164
 Nullable<T> structure type, 163
 NullableTypes application, 165

NullableTypes project, 162
 NullReferenceException, 407
 numb1 value, 106
 numb2 value, 106
 numerical conversions, 454
 numerical data types, 92, 127
 numerical formatting, 84
 numerical value, 96, 298

O

obj variable, 602
 object (logical) resources, WPF
 {DynamicResource} markup extension, 1295–1296
 {StaticResource} markup extension, 1294
 application-level resources, 1296–1297
 changing after extraction, 1295
 extracting in Expression Blend, 1301–1303
 merged resource dictionaries, defining, 1298–1299
 resource-only assembly, defining, 1300–1301
 Resources property, 1292
 window-wide resources, defining, 1292–1294
 object argument, 1335
 Object Browser utility, Visual Studio 2010, 60, 223, 1247, 1404
 Object class, 189, 251, 252, 1137, 1416, 1424
 object construction, parameterized, 4
 object context boundaries
 context-agile and context-bound types, 649
 defining context-bound object, 649–650
 inspecting object's context, 650–651
 overview, 648
 object data type, 87
 object generations, 296–297
 object graphs, 294, 295, 805–806
 object initializer syntax

- calling custom constructors with, 212–213
 - inner types, 213–214
 - overview, 210–211
- object instance, 194
- object keyword, 251
- object lifetime
 - and application roots, 294–295
 - classes, defined, 289–290
 - disposable and finalizable blended technique, 309–312
 - disposable objects, 305–309
 - finalizable and disposable blended technique, 309–312
 - finalizable objects, 302–305
 - garbage collection, 297–302
 - lazy objects, 313–317
 - and new keyword, 292–293
 - object generations, 296–297
 - object references, setting to null, 293–294
 - objects, defined, 289–290
 - overview, 291–294
 - references, defined, 289–290
 - System.GC type, 298–302
- object model
 - Excel, 721
 - Microsoft Office, 718
 - Microsoft Office Excel, 715
- Object option, 987
- object parameters, 386, 399, 1139, 1337, 1536
 - object references, setting to null, 293–294
 - object resources, 1285
 - object serialization. *See* I/O and object serialization
 - object services, 956
 - Object type, 513
 - object user, 306
 - object variable, 196, 365, 702
 - ObjectContext class, 958–960, 967, 970, 971, 973, 974
 - ObjectIDGenerator type, System.Runtime.Serialization namespace, 818
- ObjectInitializers application, 211
- ObjectInitializers project, 214
- object-oriented layer, 4
- object-oriented programming (OOP)
 - overview, 188
 - pillars of
 - encapsulation, 189
 - inheritance, 189–191
 - polymorphism, 191–192
- ObjectOverrides application, 252
- ObjectOverrides namespace, 253
- ObjectOverrides project, 253, 257
- ObjectParameter object, 986
- ObjectParameter type, 986
- ObjectQuery<T> object, 976
- ObjectResourcesApp application, 1292
- ObjectResourcesApp project, 1300, 1301, 1303
- objects
 - 2D geometric, 1246
 - adding to DataTable types, 892–893
 - allocation onto managed heap, 293
 - arrays of, 139–140
 - command, 834
 - connection, 833
 - disposable, 311, 312
 - transaction, 834
 - unreachable, 291
 - urgency level of, 298
- Objects and Timeline editor, 1213, 1215, 1217, 1222, 1229, 1236, 1359, 1360, 1361, 1365
- Objects window, 1270
- ObjectSet<Car> collection, 977
- ObjectSet<Car> data member, 971
- ObjectSet<Car> field, 974
- ObjectSet<Car> variable, 960
- ObjectSet<Inventory> member, 959
- ObjectSet<Order> variable, 959
- ObjectSet<T> classe, 958–960
- ObjectSet<T> field, 975
- ObjectSet<T> property, 967
- ObjectSet<T> variables, 967, 971
- obsolete attribute, 608–609
- [Obsolete] attribute, 605, 607, 608, 609

ObsoleteAttribute class, 607
 ObtainAnswerToQuestion() method, 1035, 1059
 ObtainVehicleDelegate delegate, 415
 Octagon class, 337
 Octagon object, 337
 Octagon type, 337
 ODBC data provider, 829, 830
 OdbcConnection class, 828
 OdbcConnection object, 321
 OdbcDataAdapter class, 913
 OfType<T>() method, 507, 508
 oldVersion attribute, 573, 574
 OLE DB data provider, 829, 830
 on operator, 509
 On prefix, 1528
 OnCarEngineEvent() method, 408
 OnCarNicknameChanged() method, 972
 OnCarNicknameChanging() method, 972
 OnClick attribute, 1389, 1398, 1409
 [OnDeserialized] attribute, 818
 [OnDeserializing] attribute, 818
 OnDragDrop() method, 322
 OnDragEnter() method, 322
 OnDragLeave() method, 322
 OnDragOver() method, 322
 OnKeyUp event, 1528
 OnMouseMove event, 1528
 OnPaint event, 1528
 OnPaint() method, 1245
 [OnSerialized] attribute, 819
 [OnSerializing] attribute, 819
 OnStart() method, 1062
 OnStop() method, 1062
 OnTransformDirty() method, 1329
 OnZipCodeLookup() method, 473
 OO wrapper, 599
 OOP. *See* object-oriented programming
 Opacity property, 1307, 1521, 1527
 opcodes
 .maxcdn directive, 680
 declaring local variables in CIL, 680–681
 hidden this reference, 682

mapping parameters to local variables in CIL, 681
 overview, 677–679
 representing iteration constructs in CIL, 682–683
 role of CIL, 655
 OpCodes class, 696
 OpCodes member, 689
 Open command, WPF, 1204–1206
 Open member, FileMode enumeration, 787
 Open() method, 189, 322, 785, 786–788, 855, 1040, 1051
 OpenConnection() method, 863
 OpenFileDialog dialog box, 1183
 OpenFileDialog type, 1559
 OpenOrCreate member, FileMode enumeration, 787
 OpenRead() method, FileInfo class, 785, 788
 OpenText() method, FileInfo class, 785, 789
 OpenTimeout property, 1040, 1053
 OpenWrite() method, FileInfo class, 785, 788
 operation codes, 655
 operational contracts, service types as, 1035–1036
 OperationCanceledException error, 767
 [OperationContract] attribute, 1027, 1033, 1034, 1035, 1073
 operations, Venn diagramming, 1268
 operator keyword, 654
 operator overloading
 += and +=, 448
 binary, 445–447
 comparison, 450
 equality, 449–450
 internal representation of, 451–452
 overview, 444
 unary, 448–449
 Operator property, 1461
 optional arguments, 131, 133, 134
 optional parameters, for methods, 131–132
 [OptionalField] attribute, 819

or opcode, 678
 or zero (multiple) parameters, lambda expressions with, 435–436
OracleConnection class, 828
OracleConnection object, 321
 Order Automobile menu, 1538
OrderAutoDialog class, 1544, 1545
OrderAutoDialog object, 1542
OrderAutoDialog.cs file, 1538
OrderAutoDialog.Designer.cs file, 1543
OrderBy() method, 519, 520
 orderby operator, 497, 509, 514, 517, 518
OrderedEnumerable type, 519
OrderedEnumerable<TElement, TKey>
 type, 498
OrderedEnumerable`2, 498
OrderID values, 844, 845
 Orders column, 988
 Orders property, 959
 Orders table, 840, 844, 845, 846, 921, 939, 979, 984
 Ordinal property, **DataTable** class, 891
 Orientation property, 1189, 1190, 1263
 Original value, 896
 OSVersion property, 1163
 Other Windows menu option, 840, 965, 1181
 out argument, 400
 out keyword, 127
 out modifier, 127–128, 159
 out parameter, 400, 429
 [out] token, 677
 outer variables, 429
 outerEllipsis control, 1338
 outerEllipsis object, 1339
 outgoing HTTP response, 1421–1423
 emitting HTML content, 1422
 redirecting users, 1422–1423
 output argument, 1105
 output, formatting for **System.Console** class, 83–85
 output parameters, 127, 128, 129, 843, 871, 1103
 Output property, 1421
 Output Type setting, 1144
 output variables, 127
OutputStream property, 1421
 overflow checking, 110–111
 overflow condition, 109
 OverloadedOps project, 453
 overloading methods, 135–137, 443
 overloading operators
 `+=` and `-+`, 448
 binary, 445–447
 comparison, 450
 equality, 449–450
 internal representation of, 451–452
 overview, 444
 unary, 448–449
 overridable methods, 238
 override keyword, 236–238, 246, 303, 549

P

P command, 872, 876
 <p> tag, 1386
 P2P (peer-to-peer) services, 1019
 pacing of animation, controlling, 1307–1308
 Padding property, 1133, 1195
 PadLeft() method, String system type, 97
 PadRight() method, String system type, 97
 Page class, 1124, 1144, 1155, 1379, 1406, 1411, 1416, 1417, 1421, 1423
 Page element, 1341
 page level themes, applying, 1469
 Page objects, 1124, 1125, 1155, 1450, 1474
 Page property, 1432
 Page type, inheritance chain of, 1416
 Page_Load event, 1493
 Page_Load() method, 1434, 1493
 Page_NameOfEvent method, 1424
 Page_PreInit() method, 1470, 1471
 <Page> control, 1155
 <Page> definition, 1163
 <Page> element, 1149, 1155, 1156, 1164
 <Page> scope, 1276
 Pages control, 1292
 <pages> element, 1468

paging, enabling, 1453
 Paint event, 1245, 1528, 1529, 1549–1550,
 1555, 1556, 1557
 PaintEventApp project, 1549, 1551
 PaintEventArgs class, 1518
 PaintEventArgs parameter, 1549, 1550
 PaintEventHandler delegate, 1549
 Panel class, 1433
 Panel control, 1433, 1436
 Panel object, 1463
 Panel type, 1184, 1433
 Panel widget, 1436
 PanelMarkup folder, 1186
 panels, WPF
 enabling scrolling for, 1194–1195
 nested, building window frame using
 finalizing UI design, 1198
 menu system, 1196–1197
 MouseEnter/MouseLeave event
 handlers, implementing, 1199
 overview, 1195
 spell checking logic, implementing,
 1200
 StatusBar, 1198
 ToolBar, 1197–1198
 overview, 1184–1185
 positioning content within
 Canvas panels, 1186–1188
 DockPanel panels, 1193–1194
 Grid panels, 1191–1193
 StackPanel panels, 1190–1191
 WrapPanel panels, 1188–1190
 Paragraph block, 1230, 1231
 Paragraph class, 1230
 Paragraph element, 1227, 1231
 Paragraph type, 1227
 <Paragraph> element, 1227
 Parallel activity, WF 4.0, 1089
 Parallel class, 763, 771
 Parallel Language Integrated Query
 (PLINQ), 494, 762, 771–774, 1010
 parallel programming. *See* multithreaded
 and parallel programming
 parallel programming library, 761
 ParallelEnumerable class, 771
 Parallel.For() method, 763, 766
 Parallel.ForEach() method, 763, 765, 766,
 767
 ParallelForEach<T> activity, WF 4.0, 1089
 Parallel.Invoke() method, 768, 771
 ParallelOptions object, 766, 767
 parameter arrays, 9, 130
 parameter modifiers, 126, 159
 Parameter object, 828
 parameter values, 133
 ParameterBuilder member, 689
 ParameterInfo class, System.Reflection
 Namespace, 587
 parameterized command objects, 867–869
 parameterized object construction, 4
 parameterized queries, 867
 ParameterizedThreadStart delegate, 740,
 744, 745, 747, 750
 ParameterName property, 868, 869
 parameters. *See also* type parameters
 interfaces as, 331–333
 for methods
 default passing behavior, 126–127
 named, 133–134
 optional, 131–132
 specifying using DbParameter type,
 867–869
 type, 372
 Parameters member, 858
 Parameters property, 834
 params argument, 131
 params keyword, 130, 400, 676
 params modifier, for methods, 130–131
 parent class, of existing class, 220–221
 Parent member, DirectoryInfo class, 779
 Parent property, 1432
 parent/child relationships, 190
 ParentRelations member, 897
 Parse() method, 96, 1006
 ParseFromStrings() method, 94
 parsing XML content, 1006
 partial class types, 217–218
 partial keyword, 9, 217, 218, 471, 472, 972
 partial methods, 470–473
 partial rollback, 879

PartialMethods project, 471, 473
 partitions, of ECMA-335, 38, 1563
 PasswordBox control, 1227
 Paste command, 1200
 Path class, 776, 1247, 1253, 1254, 1255, 1257, 1271
 Path definition, 1267
 Path menu, 1268
 Path objects, 1256, 1257, 1268, 1276, 1365, 1366
 Path settings, 1273
 PATH variable, 42
 <Path> element, 1256
 path-based animations, 1304
 PathGeometry class, 1255, 1256
 PathGeometry property, 1255
 paths, 1254–1257, 1267–1268
 PathSegment class, 1257
 PathSegment type, 1257
 Patient Details button, 1122
 Pause() method, 313
 Pay property, Employee class, 200
 Peek() method, 381, 382, 383, 796
 PeekChar() method, BinaryReader class, 800
 peer-to-peer (P2P) services, 1019
 Pen button, 1365
 Pen class, 1261
 Pen object, 1262, 1273, 1550
 Pen tool, 1266, 1267
 Pen type, 1547
 Pencil control, 1365
 Pencil tool, 1266, 1267, 1365
 pens, configuring, 1261–1262
 Pens type, 1547
 PeopleCollection class, 440
 performance issues, non-generic collections, 363–367
 PerformanceCar.vb file, 549
 Persist activity, WF 4.0, 1091
 persistence support, 1078
 persistent cookie, 1498
 persisting custom objects, 1507–1509
 Person class, 158, 159, 160, 254, 256, 367, 382, 702
 Person objects, 159, 253, 368, 371, 373, 379, 380, 385, 442, 493
 person only collection, 368
 Person type, 160
 PersonCollection class, 368
 PetName column, 170, 892, 910, 916
 PetName property, 242, 247, 506, 549, 966
 PetName string, 66
 PetNameComparer class, 359
 peverify.exe file, 666, 672, 687
 PHP applications, 1475
 physical model, 958
 PI constant, 216
 PIAs (Primary Interop Assemblies), 715
 Pick activity, WF 4.0, 1089
 Pick Color menu option, 1556
 Pick Your Color link, 1455
 PickBranch activity, WF 4.0, 1089
 PictureBox control, 1544
 PID (process identifier), 625, 631
 pinning types, with fixed keywords, 485–486
 PInvoke (Platform Invocation Services), 303
 Place code in separate file checkbox, 1407
 placeholder parameter, 373, 867
 placeholder value, 84
 placeholders, 9, 83, 135, 372, 375, 1393
 Platform Invocation Services (PInvoke), 303
 platform-independent, nature of .NET, 37–39, 1561–1565
 platform-independent .NET development.
See Mono
 Play() method, 313
 PLINQ (Parallel Language Integrated Query), 494, 762, 771–774, 1010
 PLINQDataProcessingWithCancellation application, 771
 PLINQDataProcessingWithCancellation project, 773
 plug-ins, Silverlight, 1126
 plus (+) operator, 23, 99, 100, 1094
 plus token (+), 589
 Point class

overloading binary operators, 445, 446, 448
 overloading comparison operators, 450
 overloading equality operators, 449
 overloading unary operators, 448
Point objects, 211, 378, 491
 point of no return, 1091
Point structure, 151, 153, 155, 156, 388
Point type, 152, 212, 213, 1143, 1547
Point variable, 152, 153, 211
PointAnimationUsingKeyFrames class, 1304
PointAnimationUsingPath class, 1304
PointColor enum, 212
PointDescription type, 351
PointDescription variable, 351
 pointer types
 * and & operators, 482
 field access with pointers (`->` operator), 484
 overview, 479–480
 pinning types with fixed keywords, 485–486
 `sizeof` keyword, 486
 `stackalloc` keyword, 485
 unsafe (and safe) swap function, 483
 `unsafe` keyword, 481–482
PointF type, 1547
PointRef class, 155, 156
Points property, 327, 329, 1253
PointyTestClass project, 335
 policies, 1021, 1022
Polygon class, 1247, 1253
Polygon object, 1349
Polygon type, 1253, 1254
Polyline class, 1247, 1253, 1261
Polyline type, 1253, 1254
 polylines and polygons, 1253–1254
 polymorphic behavior, 22
 polymorphic fabric, 618
 polymorphic interface, 191, 241, 323, 619
 polymorphism. *See also* inheritance
 abstract classes, 240
 member shadowing, 245–247
 override keyword, 236–238
 overview, 235
 pillar of OOP, 191–192
 polymorphic interface, 241–245
 virtual keyword, 236–238
 virtual members, 238–239
Pop() method, 380, 381
pop opcode, 679
PopulateDocument() method, 1231
 populating controls collection, 1515–1517
 populating new **DataTables** from LINQ queries, 948–950
 Port value, 1031
Portable.NET, 39
<**portType**> elements, 1034
 Position member, **Stream** class, 793
 positional parameters, 134
 POST method, 1384, 1391, 1417, 1418, 1420
 posting back to Web servers, 1390–1391
 precious items, 305
Predicate<T> delegate, 432
Predicate<T> object, 430
PreInit event, 1423, 1450, 1471
 pre-JIT, 17
Prepare() method, 859
 prepared query, 859
PreRender event, 1424
PresentationCore.dll assembly, 1127, 1135, 1157, 1168, 1183, 1271, 1304
PresentationFramework.dll assembly, 1127, 1135, 1146, 1157, 1168, 1180, 1183, 1232, 1247, 1346
 Preview suffix, 1339
PreviewKeyDown event, 1341
PreviewMouseDoubleClick event, Control type, 1133
PreviewMouseDown event, 1339
PrimAndProperCarEvents project, 426, 427, 436
 Primary Interop Assemblies (PIAs), 715
 primary module, 14
 primary namespace, 1157
 primary thread, 626
PrimaryKey member, 897
PrimaryKey property, 898
 primitive arrays, applying LINQ queries to

extension methods, 500
 implicitly typed local variables, 498–500
 overview, 496–497
 result set, 498
 role of deferred execution, 501–502
 role of immediate execution, 502–503
primitives activities, WF 4.0, 1091
Primitives area, 1107
Primitives section, 1080
PrintArray() method, 142
PrintCustomerOrders() method, 985
PrintDataSet() method, 898, 900, 906, 915, 916
PrintDocument() method, 17
Printer class, 745, 751, 757, 760
Printer instance, 751
Printer object, 751
Printer.PrintNumbers() method, 750
printf() method, 83
PrintInventory() method, 941
PrintMessage() method, 657
PrintNumbers() method, 745, 751, 752, 754, 760
PrintState() method, 168, 169
PrintTable() method, 900
PrintTime() method, 759
Priority property,
 System.Threading.Thread class, 741, 744
PriorityLevel member, **ProcessThread**
 type, 633
private assembly, 533, 547
private attribute, 669
private backing field, 207
private data, 152, 195
private fields, 807–808
private key data, 561
private keys, 560
private keyword, 188, 189, 193, 194, 196, 233
private method, 753
private modifier, 192, 194
private .NET assemblies
 configuration files and Visual Studio
 2010, 556–558

configuring private assemblies, 554–556
 identity of private assembly, 553
 probing process, 553–554
private object member variable, 753
private points of data, 207
private static object member variable, 754
privatePath attribute, 555, 556
<privatePath> element, 569, 576
Pro WF: Windows Workflow in .NET 4.0, 1077
<probing> element, 555
process identifier (PID), 625, 631
Process type, **System.Diagnostics**
 namespace, 628
ProcessCreditRisk() method, 880, 882
processes
 interacting with under .NET platform
 controlling process startup using
ProcessStartInfo class, 636–637
 enumerating running processes, 630
 investigating process's module set, 634
 investigating process's thread set, 631–634
 investigating specific process, 631
 overview, 627–629
 starting and stopping processes
 programmatically, 635–636
 role of Windows process, 626–627, 652
Processes tab, **Windows Task Manager**
 utility, 625
ProcessExit event, **AppDomain** class, 640
ProcessExit event, **AppDomain** type, 647
ProcessFiles() method, 764, 766
Process.GetProcessById() method, 631
Process.GetProcesses() method, 630
ProcessIntData() method, 773
ProcessManipulator application, 630
ProcessModule type, **System.Diagnostic**
 namespace, 628
ProcessModuleCollection type,
System.Diagnostic namespace, 628
ProcessMultipleExceptions project, 277

`ProcessName` property, `System.Diagnostics.Process` class, 629
`ProcessorAffinity` member, `ProcessThread` type, 633
`ProcessorCount` property, 1163
processors, multicore, 727
`ProcessStartInfo` class, controlling process startup using, 636–637
`ProcessStartInfo` type, `System.Diagnostic` namespace, 628
`ProcessThread` type, `System.Diagnostic` namespace, 628
`ProcessThreadCollection` type, `System.Diagnostic` namespace, 628
`ProductInfo` objects, 509
`ProductInfo[]` parameter, 511, 512, 514
production-ready assemblies, 1562
Profile API
 accessing profile data
 programmatically, 1505–1507
 `ASPNETDB.mdf` database, 1503–1504
 defining user profiles within `Web.config`, 1504–1505
 grouping profile data and persisting custom objects, 1507–1509
 overview, 1502
profile data
 accessing programmatically, 1505–1507
 grouping, 1507–1509
Profile property, 1504, 1506, 1508
`<profile>` element, 1504
Profile.Address group, 1507
ProfileCommon type, 1508
Program class, 1521–1522
Program type, 107, 155, 660
Program.cs file, 73, 507, 712, 1083, 1086, 1112, 1513
programmatic idiom, 23
programmatically assigning themes, 1469–1471
programmatically watching files, 801–804
Programmer value, 132
programming languages
 .NET-aware, 10–12

comparison of
 .NET, 6–7
 C++/Microsoft Foundation Classes (MFC), 4
 Component Object Model (COM), 5–6
 C/Windows application programming interface (API), 4
 Java, 5
 overview, 3
 Visual Basic 6.0, 4
programming logic, 1147
Project menu, 1018, 1298, 1331, 1538
Project node, 225
Project Properties editor, Visual Studio 2010, 74
Project Properties, viewing with Solution Explorer Utility, 58
Project Properties window, 58
project templates, 1023–1025, 1071–1073
Project window, 1321
Projects menu option, 1207
Projects tab, 1207, 1357
Project/Solution menu option, 1242
propdp code snippet, 1333, 1334
properties
 automatic
 and default values, 208–210
 interacting with, 208
 overview, 206–207
 custom, 358
 custom metadata viewer, 591
 defining in CIL, 676
 and encapsulation of classes
 .NET, 198–200
 within class definition, 200–201
 internal representation of, 202–203
 read-only and write-only, 204–205
 static, 205–206
 visibility levels of, 204
Properties editor, 543, 565, 940, 1211, 1214, 1218, 1236, 1350, 1360, 1361
Properties icon
 Solution Explorer, 58, 613
 Visual Studio 2010, 79

Properties list box, 1237
 Properties node, 543, 562, 919
 Properties page, 563
 Properties property, 1129, 1139
 Properties tab, 1208
 Properties window
 SharpDevelop, 52
 Solution Explorer, 1008
 Visual Studio 2010, 849, 966, 1095, 1106,
 1250, 1287, 1385, 1386, 1429, 1526
<properties> scope, 1508
.property directive, 676
-Property suffix, 1242
property syntax, automatic, 207
property values, setting, 10
PropertyBuilder() method, 689, 696
PropertyChangedCallback delegate, 1329
PropertyChangedCallback object, 1335
PropertyCollection object, 887
property-element syntax, XAML, 1132,
 1161, 1260
<PropertyGroup> element, 1149
 PropertyInfo class, System.Reflection
 Namespace, 587
 PropertyInfo.GetValue() method, 617
property/value pairs, 1312
Proposed value, 896, 897
protected field, 231
protected internal modifiers, 193, 194
protected keyword, 189, 193, 194, 204, 230
protected methods, 231
protected modifier, 193, 194
ProtectionLevel property, 1034
<protocolMapping> element, 1051
protocols, stateless, 1380
Provider attribute, 1505
provider value, 849
proxy class, 1018, 1046
proxy code, generating
 using svcutil.exe, 1046–1047
 using Visual Studio 2010, 1047–1048
PTSalesPerson class, 231, 236, 239
public access modifier, 168
public attribute, 655, 669
public fields, 195, 807–808

public key token, 569, 573
public key value, 532
public keys, 560
public keyword, 20, 125, 152, 193, 194,
 1543
public methods, 196, 695, 753
public modifier, 192, 193, 194
public point of data, 199
public properties, 152, 807–808
public read-only field, 195
PublicDelegateProblem project, 419
publicKeyToken attribute, 577
.publickeytoken directive, 542
.publickeytoken instruction, 542
.publickeytoken tag, 569
publicKeyToken values, 566, 577, 599
PublicKeyToken=null convention, 598
public/private key data, 560, 561
publisher policy assemblies, 574–575
<publisherPolicy> element, 575
Push() method, 380

■ Q

Q command, 872, 876
QC (Queued Components), 1016
queries. *See also LINQ*
QueriesTableAdapter class, 943
query expressions, 116, 494, 495
query operators, 494, 495, 518
query pattern implementation, 945
querying
 with Entity SQL, 977–978
 with LINQ to Entities, 975–977
QueryOverInts() method, 501
QueryOverStrings() method, 496, 497, 498
QueryString collection, 1476
QueryString property, 1418, 1419, 1420
QueryStringsWithAnonymousMethods()
 method, 520
QueryStringsWithEnumerableAndLambda
 s() method, 519, 520
QueryStringsWithOperators() method,
 518, 520

Queue class, 362
 Queue<T> class, 377, 382–383
 Queue<T> object, 382
 Queued Components (QC), 1016
 QueueUserWorkItem() method, 760

R

radial gradient brush, 1258, 1259
 RadialGradientBrush object, 1294
 RadialGradientBrush type, 1258, 1293
 Radio class, 190, 193, 263
 Radio type, 273
 RadioButton class, 1218, 1220, 1223
 RadioButton control, Ink API tab, 1220–1222
 RadioButton objects, 1249, 1553
 radioButtonCircle object, 1553
 RadioButtonClicked handler, 1221
 RadioButtonClicked() method, 1223
 radioButtonRect object, 1553
 Radio.cs file, 273, 277, 343
 RadiusX property, 1250
 RadiusY property, 1250
 Random member variable, 182
 RangeValidator control, 1458
 RangeValidator type, 1459
 RangeValidator widget, 1460–1461
 Rank property, Array class, 143
 raw Predicate<T> delegate, 491
 RawUrl property, 1418
 RCW (Runtime Callable Wrapper), 714, 715
 Read() member
 BinaryReader class, 800
 Stream class, 793
 TextReader class, 796
 ReadAllBytes() method, File class, 790
 ReadAllLines() method, File class, 790
 ReadAllText() method, File class, 791
 ReadBlock() method, TextReader class, 797
 ReadByte() method, FileStream class, 793
 ReadByte() method, Stream class, 793
 reading, from text files, 796–797

reading incoming cookie data, 1499
 ReadLine() method, TextReader class, 82, 797
 readOnly attribute, 1505
 read-only fields, constant field data, 215–216
 readonly modifier, 216, 218
 ReadOnly property, DataColumn class, 891
 ReadToEnd() method, TextReader class, 797
 ReadXml() method, 889, 901
 ReadXmlSchema() method, 901
 ReadXXXX() method, BinaryReader class, 800
 real types, 1082
 Really Simple Syndication (RSS) library, 1024
 Reason property, 1098
 Receive activity, WF 4.0, 1090
 Recent tab, 57, 541
 Record Keyframe button, 1360
 record mode, 1360
 records
 deleting, 974–975
 updating, 975
 Rectangle class, 213, 214, 341, 378, 1247, 1256
 Rectangle element, 1192
 Rectangle objects, 491, 1248, 1250, 1252
 Rectangle type, 157, 455, 456, 457, 458, 459, 1250, 1254, 1547, 1548
 Rectangle variable, 157, 213
 <Rectangle> element, 1267, 1268
 RectangleF type, 1548
 RectangleGeometry class, 1255
 RectangleGeometry object, 1255
 rectangular array, 140, 141
 RectMultidimensionalArray() method, 141
 Redirect() method, 1421
 redirecting users, 1422–1423
 ref arguments, 10, 400
 ref keyword, 129, 483
 ref modifier, 126, 128–129, 159, 160
 ref parameter, 126, 400, 429
 Refactor menu, 60, 61, 336

- refactoring code, Visual Studio 2010, 60–63
- reference count, 292, 293
- Reference folder, 568
- Reference parameters, 129
- reference, passing reference types by, 160
- reference types
 - passing by reference, 160
 - passing by value, 158–160
 - vs. value types, 155–156, 161–162
 - value types containing, 157–158
- reference variable, 290
- References folder, Solution Explorer, 57, 620, 716
- referencing
 - assemblies, 1414–1415
 - AutoLotDAL.dll, 1396–1409
- reflection
 - obtaining Type reference using System.Object.GetType(), 588–589
 - obtaining Type reference using System.Type.GetType(), 589
 - obtaining Type reference using typeof(), 589
 - overview, 586
 - System.Type class, 587
- reflection calls, longhand, 711
- ReflectionOnly value, 694
- Reflector, exploring assemblies using, 35–36
- reflector.exe file, 36, 498, 581, 658, 755, 1151, 1157, 1290, 1327
- ReflectOverQueryResults() method, 498
- ref/out parameters, 291
- RefreshGrid() method, 1492
- refreshing client proxy, 1056–1057
- RefTypeValTypeParams project, 158, 161
- Region type, 1548
- RegisterWithCarEngine() method, 406, 407, 408, 409
- registering events, simplifying using Visual Studio 2010, 423–424
- RegularExpressionValidator control, 1458
- RegularExpressionValidator widget, 1459, 1460
- RejectChanges() method, 889, 893
- relational data, 494
- Relations property, 887
- relationships
 - class library, 8
 - has-a, 5, 190, 213, 219, 232
 - is-a, 189, 190, 219, 220, 228, 248
 - parent/child, 190
- Relative value, 1291
- relaxed delegates, 414
- Release() method, 292
- rem opcode, 678
- remoting layer, 1016
- RemotingFormat member, 897
- RemotingFormat property, 888, 902
- Remove() method, 98, 365, 402, 410, 1000, 1484, 1486, 1496, 1515
- Remove Parameters refactoring, 61
- remove_ prefix, 421
- remove_AboutToBlow() method, 421
- remove_Exploded() method, 421
- Remove<T>() method, 1000
- RemoveAll() method, 402, 1484, 1486, 1496
- RemoveAt() method, 1484, 1515
- RemoveFromCollection<T> activity, WF 4.0, 1092
- RemoveInventoryRow() method, 934
- RemoveMemoryPressure() method, System.GC class, 298
- removeon directive, 421
- RemoveRecord() method, 975
- removing controls, dynamically, 1435–1436
- Rename option, 1520
- Rename refactoring, 61
- RenamedEventHandler delegate type, 802
- rendering graphical data using GDI+ Graphics type, 1548–1549
- invalidating form's client area, 1551
- obtaining Graphics object with Paint event, 1549–1550
- overview, 1545–1546
- System.Drawing namespace, 1547
- rendering graphical output, 1557
- RenderingWithShapes application, 1247

- RenderingWithShapes project, 1263
 RenderingWithVisuals application, 1278
 RenderOpen() method, 1279
 RenderTargetBitmap object, 1279, 1280
 RenderTransform object, 1265, 1307
 RenderTransform property, 1134, 1248, 1263, 1307
 Reorder Parameters refactoring, 61
 RepeatBehavior property, 1306, 1308, 1310
 RepeatBehavior.Forever method, 1309
 Replace() method, 98, 99
 Request object, 1476
 Request property, 1417, 1482
 RequestedColor argument, 1105, 1107
 RequestedMake argument, 1105, 1107
 RequestedMake variable, 1110
 request/response cycle, 1380
 RequestType property, 1418
 RequiredFieldValidator control, 1458
 RequiredFieldValidator type, 1459
 RequiredFieldValidator widget, 1459–1460
 Reset Current Workspace menu option, 1212
 Reset() method, 344, 348
 ResetPoint() method, 390
 resource system, WPF
 binary resources
 embedding application resources, 1289–1291
 loose resources, 1286–1287
 overview, 1285
 programmatically loading images, 1288–1289
 object (logical) resources
 {DynamicResource} markup
 extension, 1295–1296
 {StaticResource} markup extension, 1294
 application-level resources, 1296–1297
 changing after extraction, 1295
 extracting in Expression Blend, 1301–1303
 merged resource dictionaries, defining, 1298–1299
 resource-only assembly, defining, 1300–1301
 Resources property, 1292
 window-wide resources, defining, 1292–1294
 ResourceDictionary object, 1292
 <ResourceDictionary> elements, 1299, 1321
 <ResourceDictionary.MergedDictionaries> scope, 1299
 resource-only assembly, defining, 1300–1301
 resources
 managed, 311
 unmanaged, 289, 303, 305, 311
 Resources indexer, 1296
 Resources link, 11
 Resources property, 1134, 1292, 1295
 Resources tab, 1303
 Resources view, 1322
 Responding property, System.Diagnostics.Process class, 629
 response files, for csc.exe, 47–49
 Response property, 1417, 1421, 1482
 Response.Cookies property, 1498
 Result property, 1095
 Results View option, 502
 Resume() method, 742
 ret opcode, 678
 retained-mode graphics, 1245
 Rethrow activity, WF 4.0, 1092
 rethrowing exceptions, 280
 return keyword, 75
 return values, 871
 array as, 142
 interfaces as, 333
 ReturnType property, 594
 Reverse() method, 143
 Reverse<>() method, 509
 Reverse<T>() method, 514
 ReverseDigits() method, 461, 462
 reversing animation, 1308–1309
 RichTextBox control, 1228, 1231, 1234
 RichTextBox manager, 1228

Right property, 1527
right-click operation, 1203
Rollback() method, 879
ROLLBACK statement, 878
rolled back, 878
Root member, DirectoryInfo class, 779
root namespace, 30
RotateTransform object, 1263, 1264, 1307
RotateTransform type, 1262
RoundButtonStyle, 1354
RoundButtonTemplate, 1350, 1351, 1353
round-trip engineering, 658
RoundTrip example, 666
RoutedEventArgs parameter, 1339
routed events, WPF
 overview, 1337
 routed bubbling events, 1338–1339
 routed tunneling events, 1339–1341
RoutedEventArgs class, 1139
RoutedEventHandler delegate, 1139, 1337
routines
 creating custom conversion, 455–457
 custom conversion, 460
 implicit conversion, 458–459
routing strategies, 1337
row filtering, 909
RowBackground property, 1243
<RowDefinition> element, 1191
RowError property, 893
RowFilter property, DataView class, 913
RowNotInTableException exception, 832
rows
 deleting from DataTables, 907–908
 selecting based on filter criteria, 908–911
 updating within DataTables, 911
Rows category, 1243
Rows collection, 900, 941, 943
Rows indexer, 934
RowState enumeration, 893
RowState property, 893, 894–896, 919
RowState.Added value, 919
RowState.Deleted value, 919
RowState.Modified value, 919
*.rsp file extension, 47, 48, 659

RSS (Really Simple Syndication) library, 1024
rtspecialname attribute, 675
rtspecialname token, 689
RTTI (Runtime Type Identification)
 method, 252
Run element, 1227
Run() method, 1086, 1128
Run objects, 1231
Run value, 694
RunAndSave value, 694
runat="server" attribute, 1403, 1467, 1477
RunMyApplication() method, 286
running processes, enumerating, 630
runtime
 activities, WF 4.0, 1091
 deploying .NET, 36–37
 exceptions, 249
Runtime Callable Wrapper (RCW), 714, 715
runtime engine
 Mono, 1577
 WF 4.0, 1083–1088
runtime type discovery, 586
Runtime Type Identification (RTTI)
 method, 252
<runtime> element, 555
RuntimeBinderException class, 704, 705
rw object, 312
rw2 object, 312

■ S

S command, 872
safe swap function, 483
SAFEARRAY data type, 6, 7
SAFEARRAY structure, 6
SalesPerson class, 226, 227, 236, 237, 239
SalesPerson constructor, 229
SalesPerson type, 230, 231
SalesPerson.cs file, 227
Samples menu selection, 1275
sane subset, 4
satellite assemblies, 536
Save button, 1235

Save command, WPF, 1204–1206
 Save() method, 879
 save points, 879
 Save value, 694
 SaveAs() method, 1418
 SaveChanges() method, 958, 959, 974, 990
 SaveFileDialog dialog box, 1183
 SaveFileDialog type, 1558, 1559
 saving, InkCanvas data, 1226–1227
 SavingChanges event, 959, 973
 SavingsAccount class, 183, 184, 185
 SavingsAccount object, 183, 185, 186, 187
 SayHello() method, 691, 697
 sbyte data type, 86
 ScaleTransform type, 1262
 Scene elements list box, 1237
 <Schema> node, 969
 scope, 464–465
 scope ambiguity, 174, 175
 <script> block, 1395, 1403, 1405, 1424,
 1429, 1480, 1481
 <script> scope, 1409
 ScrollableControl class, 1529
 ScrollBar object, 1236, 1237, 1238
 ScrollBar type, 1240
 ScrollBar value, 1240
 ScrollBars property, 1007
 scrolling, enabling for panels, 1194–1195
 ScrollViewer class, 1194
 ScrollViewer.xaml file, 1194
 SDK (.NET Framework 4.0 Software
 Development Kit), 41–42, 67–69
 SDK (software development kit), 997, 1015,
 1022, 1026, 1042, 1046, 1074, 1395,
 1410, 1423
 sealed attribute, 669
 sealed class, adding, 231–232
 sealed keyword, 222–223, 239
 Sealed member, 695
 sealing, virtual members, 239
 Search box, 1297
 Search edit box, 68, 69
 search editor, 1231
 secondary threads
 creating programmatically

AutoResetEvent class, 748–749
 foreground and background
 threads, 749–750
 overview, 744
 ParameterizedThreadStart delegate,
 747
 ThreadStart delegate, 745–746
 worker threads, 626
 Section class, 1230
 Section element, 1227
 Section type, 1227
 SELECT command, 914
 Select items, 1213
 Select() method, 519, 520, 793, 800, 908,
 909, 910, 911
 Select mode, 1223, 1224
 Select Mode! value, 1218
 Select New Data Source option, 1451
 Select Object editor, 1218, 1219
 select operator, 497, 509, 510, 517
 SELECT statement, 914, 974, 977
 Select statements, 512, 861, 862, 1450
 SelectCommand property, 914, 915, 918,
 949
 SelectedIndex property, 1224
 SelectedItem method, 1225
 SelectedItem property, 1224
 SelectedNodeChanged event, 1447
 SelectedShape enumeration, 1554, 1555
 SelectedShape property, 1554
 SelectedShape type, 1554
 SelectedShape value, 1251
 SelectedShape.Circle property, 1554
 SelectedShape.Rectangle property, 1554
 SelectedValue property, 1224
 selecting bindings, 1056–1057
 Selection button, 1213
 selection method, 866
 Selection tool, 1222, 1229
 SelectionChanged event, 1221, 1319
 selectRadio control, 1219
 self-describing, 533
 semantically related, 33
 semantics, 666

Semaphore class, System.Threading namespace, 740
 semicolon-delimited list, 46
 Send activity, WF 4.0, 1090
 SendAndReceiveReply activity, WF 4.0, 1090
 SendAPersonByReference() method, 160
 SendAPersonByValue() method, 159, 160
 Separator control, 1218
 <Separator> element, 1196
 Sequence activity, 1089, 1093, 1104, 1106, 1107, 1110, 1111
 Sequence node, 1107
 sequential attribute, 669
 Serializable member, 695
 serializable token, 606
 serializable types, 807
 [Serializable] attribute, 605, 606, 807, 1070, 1502, 1508, 1553, 1558
 [Serializable] type, 1503, 1508
 serialization. *See* I/O and object serialization
 SerializationFormat.Binary class, 902
 SerializationInfo class, 819
 Serialize() method
 BinaryFormatter type, 811, 812
 IFormatter interface, 809, 816
 SoapFormatter type, 813
 serializeAs attribute, 1505
 serializing
 collections of objects, 816–817
 DataTable/DataSet objects as XML, 901–902
 DataTable/DataSet objects in binary format, 902–903
 objects using BinaryFormatter type, 811–813
 objects using SoapFormatter type, 813
 objects using XmlSerializer type, 814–816
 server controls, 1429
 Server Explorer, Visual Studio 2010, 955, 1450
 Server name text box, 841

Server property, 1417, 1422, 1426, 1481, 1482
 servers, 1380–1382
 server-side event handling, 1430
 Server.Transfer() method, 1471
 ServerVariables property, 1418
 Service assembly, WCF, 1025, 1026
 service behavior, 1043
 service contracts, 1027
 service contracts, implementing, 1073–1074
 Service host, WCF, 1026
 Service Library option, WCF, 1025
 Service Library Project template, WCF
 altering configuration files using SvcConfigEditor.exe, 1059–1061
 building simple math services, 1057–1058
 testing with WcfTestClient.exe, 1058–1059
 Service Library template, Visual Studio 2010, 1023, 1024
 Service References folder, 1056
 service types, 1027
 service types as operational contracts, 1035–1036
 Service Website project templates, 1025
 <service> element, 1037, 1043, 1055
 Service1.cs file, 1058
 [ServiceContract] attribute, 1027, 1033, 1034, 1035
 ServiceContractAttribute class, 1034
 Service.cs file, 1073
 serviced component, 1015
 ServiceHost class, 1026, 1037, 1038, 1039, 1040, 1041, 1043, 1062, 1063
 ServiceHost object, 1051
 ServiceHost type, 1026, 1038, 1040–1041
 serviceInstaller1 component, 1065
 <serviceMetadata> element, 1055
 ServiceName property, 1065
 service-oriented architecture (SOA) tenets, 1021–1022
 serviceProcessInstaller1 component, 1065
 ServiceReference namespace, 1048

services
 exposing using multiple bindings, 1052–1053
 invoking asynchronously from clients, 1067–1069
 testing, 1075–1076

Services applet, Control Panel, 1500, 1501

services element, 1037, 1043

<service.serviceModel> element, 1040, 1042, 1043

Service.svc file, 1074

session application Graphical User Interface (GUI), 1495

Session Component Object Model (COM) object, 1483

session cookie, 1498

session data
 maintaining, 1493–1497
 storing in ASP.NET session state servers, 1500–1501
 storing in dedicated databases, 1502

session ID, 1494, 1495, 1496

session information, 1495

Session property, 1417, 1482, 1483

session state
 handling web application shutdown, 1488
 maintaining application-level state data, 1484–1486
 modifying application data, 1486–1487
 overview, 1483

Session_End() event, 1481, 1494, 1496

Session_Error() event, 1496

Session_Start() method, 1481, 1494, 1495, 1496

SessionID property, HttpSessionState class, 1496

SessionMode property, 1035

SessionState project, 1494

<sessionState> element, 1427, 1497, 1500–1502

set block, 204, 1330

Set button, 1474

set directive, 676

set keyword, 204

set method, 195, 196, 198, 202, 676

Set() method, 749

Set Primary Key option, 842

set scope, 198, 199

set_prefix, 202, 676

set_PetName() method, 584

set_SocialSecurityNumber() method, 203

set_XXX() method, 202

SetBinding() method, 1241, 1327

SetBindings() method, 1241

SetCurrentPay() method, 197

SetDriverName() method, 174

SetF1CommandBinding() method, 1203

SetID() method, 197

SetInterestRateObj() method, 185

SetLength() method, Stream class, 793

SetMathHandler() method, 436

SetName() method, 196, 197

setter method, 194

Setter objects, 1312, 1313

<Setter> elements, 1317

Setters collection, 1312, 1313

Setters property, 1312

settings, changing for bindings, 1053–1054

setup.exe program, 50

SetupInformation property, AppDomain class, 639

SetValue() method, 1135, 1328, 1330

shadowing, members, 245–247

shallow copy, 349, 350, 351

Shape array, 332, 333

Shape class, 189, 191, 192, 242, 243, 244, 245, 324, 1247, 1253

Shape objects, 333, 1252, 1253

Shape property, 1262

Shape references, 245

Shape types, 330, 1271, 1272

ShapeData type, 1553, 1557

ShapeData.cs file, 1553

ShapeInfo variable, 157

ShapePickerDialog class, 1553–1555

shapes
 adding rectangles, ellipses, and lines to canvas, 1249–1252
 overview, 1247–1248

- paths, 1254–1257
- polylines and polygons, 1253–1254
- removing rectangles, ellipses, and lines from canvas, 1252–1253
- working with using Expression Blend brush and transformation editors, 1269–1271
- combining shapes, 1268
- converting shapes to paths, 1267–1268
- overview, 1266
- selecting shape to render from tool palette, 1266–1267
- Shapes application**, 242
- *.shapes files, 1559
- Shapes project**, 247
- Shapes types**, 1253
- ShapesLib.cs file**, 525
- shared assemblies**
 - .NET
 - consuming, 567–569
 - generating strong names at command line, 561–563
 - generating strong names using Visual Studio 2010, 563–564
 - installing strongly named assemblies to GAC, 565–566
 - overview, 558–559
 - strong names, 560–561
 - viewing .NET 4.0 GAC using Windows Explorer, 566
 - configuring, 533
 - reflecting on, 598–600
- SharedCarLibClient application**, 568, 569
- SharedCarLibClient directory**, 573
- SharedCarLibClient.exe file**, 569, 573, 574
- SharpDevelop**
 - authoring CIL code using, 665–666
 - building C# applications with, 50–53
- Shift property**, 1537
- Shift+Click operation**, 1220
- Shift-Click operation**, 1220
- ShoppingCart class**, 1502
- short circuit**, 121
- short data type**, 86, 87, 106, 107, 108
- short variables**, 106
- Show All Files button**, 546, 711, 970, 1287
- Show button**, 1389
- Show Errors check box**, 1383
- Show() method**, 1137, 1529, 1530, 1532, 1542
- Show Table Data option**, 842, 882
- ShowConnectionStatus() method**, 856
- ShowDialog() method**, 1137, 1183, 1530, 1542
- ShowEnvironmentDetails() method**, 80
- ShowInstructions() method**, 872, 873
- ShowInTaskbar property**, 1530, 1538
- ShowMessageBox property**, 1463
- ShowNumberControl.xaml**, 1331
- ShowSummary property**, 1463
- Sign the assembly check box**, 563
- Signing tab**, 563
- Silverlight plug-ins**, 1126
- Silverlight, WPF and**, 1126
- Simple application programming interface (API) for Extensible Markup Language (XML) (SAX)**, 993
- simple data adapters**, 914–915
- simple math services**, building, 1057–1058
- Simple Object Access Protocol (SOAP)**, 261, 1016, 1019, 1029
- Simple Styles.xaml file**, 1320, 1321, 1323
- SimpleArrays() method**, 137
- SimpleBoxUnboxOperation() method**, 363
- SimpleButton icon**, 1322
- SimpleCanvas.xaml file**, 1187
- SimpleClassExample project**, 167, 181
- SimpleCSharpApp project**, 73, 81
- SimpleCSharpApp.bat file**, 76
- SimpleDataSet application**, 889, 903
- SimpleDataSet project**, 891, 902
- SimpleDelegate application**, 402
- SimpleDelegate project**, 405
- SimpleDispose application**, 306
- SimpleDispose project**, 309
- SimpleDockPanel.xaml file**, 1193
- SimpleException class**, 273
- SimpleException project**, 263
- SimpleException.Car class**, 268

SimpleFileIO project, 792
 SimpleFinalize application, 303
 SimpleFinalize project, 305
 SimpleGC class, 289
 SimpleGC project, 302
 SimpleGrid.xaml file, 1191
 SimpleIndexer project, 440, 441
 SimpleLambdaExpressions project, 435
 SimpleMath class, 403, 404, 435, 711
 SimpleMultiThreadApp application, 745
 SimpleMultiThreadApp project, 747
 SimpleSerialize project, 807, 818
 SimpleStackPanel.xaml file, 1190
 SimpleStateExample project, 1473
 SimpleVSWinFormsApp application, 1518
 SimpleVSWinFormsApp project, 1533
 SimpleWinFormsApp application, 1513
 SimpleWinFormsApp project, 1518
 SimpleWrapPanel.xaml file, 1188
 SimpleXamlApp.csproj file, 1148, 1149
 SimpleXamlApp.exe assembly, 1149
 single constructor definition, 180
 single file Web pages, building

- adding data access logic, 1397–1401
- ASP.NET control declarations, 1403–1404
- ASP.NET directives, 1401–1403
- compilation cycle for single-file pages, 1405–1406
- designing UI, 1396–1397
- overview, 1395
- referencing AutoLotDAL.dll, 1396
- "script" block, 1403

- single logical parameter, 130
- single services, exposing using multiple bindings, 1052–1053
- single-file assemblies
- building and consuming, 536–549
 - building C# client application, 545–547
 - building Visual Basic client application, 547–549
- CIL (common intermediate language), 544
- cross-language inheritance, 549
- manifest, 541–544
- type metadata, 544–545
- vs. multi-file assemblies, 14
- single-file page model, 1395
- single-file pages, compilation cycle for, 1405–1406
- single-threaded apartment, 1522
- single-threaded process, 626
- *.sitemap file, 1445
- SiteMap icon, 1447
- SiteMapDataSource class, 1447
- SiteMapDataSource component, 1446, 1447
- SiteMapDataSource instance, 1446
- <siteMapNode> elements, 1446
- SiteMapPath control, 1439, 1445
- SiteMapPath type, establishing bread crumbs with, 1447
- SiteMapPath widget, 1447
- sitewide themes, applying, 1468
- Size property, 868
- Size type, 1548
- SizeF type, 1548
- sizeof keyword, 486
- SkewTransform type, 1262
- <SkewTransform> element, 1263
- *.skin files, 1466–1468
- SkinID property, 1432, 1469
- slash symbol, 44
- Sleep() method, System.Threading.Thread Class, 741
- slider bar, 1231
- *.sln file, 55
- SlowDown() method, 465
- slugbug.jpg file, 1448
- smart tag, 335
- SMEs (subject matter experts), 1078
- sn command-line utility, Mono, 1571, 1574
- Snap In Module menu, 621, 622
- sn.exe utility, 560, 561, 1571
- Snippets group, 63
- *.snk file, 563, 564, 664
- SOA (service-oriented architecture) tenets, 1021–1022

SOAP (Simple Object Access Protocol),
 261, 1016, 1019, 1029
 Soap/Binary serialization processes,
 customizing
 overview, 818–819
 using attributes, 823
 using *ISerializable* interface, 820–822
 SoapFormatter class, 807, 808
 SoapFormatter type, 809, 810, 813
 SocialSecurityNumber property, 203, 204,
 229, 256
 sockets, 1019
 software development kit (SDK), 997, 1015,
 1022, 1026, 1042, 1046, 1074, 1395,
 1410, 1423
 SolidBrush type, 1547
 SolidColorBrush type, 1258
 Solution Explorer Utility, Visual Studio
 2010, 56–58
 Solution Explorer window, 224, 225, 1520
 Solution menu option, 51
 Song objects, 313, 315
 Sort() methods, 143, 355, 358, 374
 sort types, custom, 358
 Sort<T>() method, 374
 SortByPetName property, 358
 SortedDictionary<TKey, TValue> class, 377
 SortedList class, 362
 SortedSet<T> class, 377, 383–385
 SortedSet<T> type, 376
 sorting enabling, 1453
 Source button, SharpDevelop, 52
 Source Code/Downloads area, Apress web
 site, 55
 source files, compiling multiple with
 csc.exe, 46–47
 Source property, 263, 1275, 1279, 1286,
 1289, 1358
 Source value, 1278
 space-sensitive, 1301
 spaghetti code, 4
 Span class, 1230
 Span element, 1227
 Span type, 1227
 specialname attribute, 675, 676
 specialname token, 689
 specifying base addresses, 1038–1040
 Speed property, 220, 221, 506
 SpeedRatio property, Timeline class, 1305
 SpeedUp() method, 168, 169
 spell checking logic, building window
 frame using nested panels, 1200
 SpellCheck.IsEnabled property, 1200
 Spelling Hints menu item, 1197
 SpellingError object, 1200
 Spin() method, 1358, 1359, 1364
 SpinControl objects
 designing, 1358
 renaming, 1357–1358
 SpinControl_Loaded method, 1359
 SpinControl.xaml file, 1357
 SpinImageStoryboard, 1360, 1361
 SpinningButtonAnimationApp
 application, 1306
 SpinningButtonAnimationApp project,
 1309
 Split() method, String system type, 98
 splitters, 1192
 SportsCar class, 13, 66, 67, 194, 414, 532,
 544
 SportsCar icon, 66
 SQL (Structured Query Language), 908,
 910, 912, 914, 915, 918, 919, 922,
 945, 1394
 SQL queries, 490
 SQL Server 2010 database, 1503
 SQL Server 7.0, 1503
 SQL Server database, 1502
 SQL Server Express, 53
 SQL Server Management Tool, 840
 SQL statement, 865
 SQL# tool, Mono, 1571, 1572
 SqlCommand class, 918
 SqlCommand objects, 882, 918, 937
 SqlCommand type, 858
 SqlCommandBuilder class, using to
 configure data adapters, 918–919
 SqlConnection class, 828
 SqlConnection object, 321, 863
 sqlConnectionString attribute, 1502

SqlConnectionStringBuilder () method, 857
SqlDataAdapter class, 913, 914, 918, 922
SqlDataAdapter object, 919
SqlDataAdapter parameter, 917
SqlDataAdapter variable, 917
SqlDataReader class, 828, 957
SqlDataSource class, 1450, 1451, 1454
SqlDataSource component, 1450, 1451, 1452
SqlDataSource type, 1451
SqlParameter class, 918
SqlParameter objects, 918, 937
SqlParameter type, 869
SqlProfileProvider type, 1504
SqlTransaction data provider, 878
SqlTransaction object, 879, 882
SqlTransaction type, 879
 square brackets, 620
Square class, 342, 525
Square type, 455, 456, 457, 458, 459
SquareIntPtr() method, 482
SquareNumber() method, 403
 st (store) prefix, 679
 stack, 154
Stack class, 362
Stack<T> class, 377, 380–381, 656
stackalloc keyword, 485
stackalloc pointer-centric keyword, 479
 stack-allocated integer, 366
 stack-based data, 366
StackOverflowException class, 272
StackPanel class, 1138, 1160, 1216, 1222, 1225, 1228
StackPanel control, 1341
StackPanel layout manager, 1332
StackPanel node, 1217
StackPanel objects, 1371
StackPanel panels, 1190–1191
 <**StackPanel**> elements, 1225
 <**StackPanel**> tag, 1132
 <**StackPanel**> type, 1174, 1176, 1181, 1198, 1239, 1253, 1293
stackTemplatePanel, 1345
StackTrace documents, 269
StackTrace property, 81, 263, 267, 268–269
Standard area, **Toolbox**, 1439
StarButton control, 1341, 1367–1368, 1371
 starg opcode, 679
 Start Debugging menu selection, **Debug** menu, 284
 Start icon, 1094
Start() method, 629, 635, 742, 745
StartAddress member, **ProcessThread** type, 633
StartAndKillProcess() method, 635, 637
StartNew() method, 766
StartPosition property, 1530, 1538
StartTime member, **ProcessThread** type, 633
StartTime property, System.Diagnostics.Process class, 629
StartType property, 1065
Startup event, 1128, 1129, 1130, 1136, 1137, 1139, 1140, 1145
Startup Object dropdown list box, Visual Studio 2010, 74
StartupEventArgs class, 1137, 1140
StartupEventHandler delegate, 1137
StartupUri property, 1129, 1153
StartupUrl property, 1147
 state data, maintaining, 1484–1486
 state management techniques. *See* ASP.NET state management techniques
state of exceptions, configuring
 Data property, 270–272
 HelpLink property, 269–270
 overview, 267
 StackTrace property, 268–269
 TargetSite property, 268
State property, 855, 856, 1041
StateBag type, 1478
stateConnectionString attribute, 1501
 stateless protocols, 1380
 stateless wire protocol, 1473
States tab, 1367
 [**STAThread**] attribute, 1136, 1522
 static assemblies, 688

static attribute, 674
 static class, defining extension methods, 461
 static constructor, 186, 187, 216
 static data, 182, 184
 static keyword
 classes, 187–188
 constructors, 185–187
 field data, 182–185
 methods, 181–182
 static members, 176, 181, 182, 187, 738
 static methods, 182, 404
 static read-only fields, constant field data, 216
 statically invoking extension methods, 464
 statically typed, 703
 StaticData project, 182, 188
 StaticMethods application, 182
 StatusBar, building window frame using
 nested panels, 1198
 StatusBar widget, 322
 StatusCode property, 1421
 StatusDescription property, 1421
 stfld opcode, 685
 Sticky Notes API, 1228
 sticky notes, Documents tab, 1232–1234
 stloc opcode, 679
 stloc.0 opcode, 293, 657
 stobj opcode, 679
 Stop() method, 313
 storage, for enum type, 145–146
 store (st) prefix, 679
 Stored Procedure Name dropdown box, 981
 stored procedures, invoking using
 generated codes, 943
 Stored Procedures node, 843
 storing session data
 in ASP.NET session state servers, 1500–1501
 in dedicated databases, 1502
 <Storyboard> element, 1310, 1362
 storyboards
 authoring animation in XAML, 1310
 programmatically starting, 1363–1364
 Storyboard.TargetName value, 1312
 Storyboard.TargetProperty value, 1312
 stream wrappers, 793
 Stream-derived type, 1175
 StreamingContext type, 821
 streamlined syntax, 210
 StreamReader class, 776
 StreamReader type, 789
 StreamReaders class
 directly creating types, 797–798
 overview, 794
 reading from text files, 796–797
 writing to text files, 795–796
 streams, I/O manipulation, 792
 StreamWriter class, 776
 StreamWriter object, 789
 StreamWriter type, 795
 StreamWriterReaderApp project, 798
 StreamWriters class
 directly creating types, 797–798
 overview, 794
 reading from text files, 796–797
 writing to text files, 795–796
 Stretch property, Shape class, 1249, 1358
 string argument, 132, 1084
 string array, 78, 98, 496, 769
 String class, 104, 223, 256
 string concatenation technique, 23, 99
 string data
 basic manipulation, 98–99
 concatenation, 99–100
 escape characters, 100–101
 overview, 97
 parsing values from, 94
 strings and equality, 102
 strings are immutable, 102–104
 System.Text.StringBuilder type, 104–105
 verbatim strings, 101–102
 string field, 66
 string keyword, 68, 93
 string literals, documenting, 586
 String Member variable, emitting, 695–696
 string objects, 86, 102, 103, 104, 394, 498, 513, 1099

string parameter, 229, 589
 string types, 75, 103, 104, 133, 394, 865,
 1099, 1105
 string values, 441–442, 1095, 1100
 string variables, 98, 99, 129, 255, 768, 1095,
 1339
 string[] args array, 75
 string[] type, 1098
 StringAnimationUsingKeyFrames class,
 1304, 1312
 <StringAnimationUsingKeyFrames>
 element, 1312
 StringAnimation.xaml file, 1311
 stringArray variable, 138
 StringBuilder object, 105
 StringCollection type, 363
 String.Concat() method, 99, 100
 StringDictionary type, 363
 string.Format() method, 85, 86
 StringFormat type, 1548
 stringified format, 589
 StringIndexer project, 442
 String.Length property, 120
 StringReaders class, 776, 798–799
 StringReaderWriterApp project, 799
 strings array, 76
 StringsAreImmutable() method, 103
 StringTarget() method, 416
 StringWriters class, 798–799
 stroke, 1223
 Stroke property, 1249, 1273, 1365
 Stroke value, 1273
 StrokeCollection object, 1223
 StrokeDashArray property, Shape class,
 1249
 StrokeEndLineCap property, Shape class,
 1249
 Strokes property, 1223
 StrokeThickness property, 1249, 1262, 1368
 StrokeThickness value, 1273
 [Strong Name Key] file extension, 560
 strong names
 generating at command line, 561–563
 generating using Visual Studio 2010,
 563–564

installing strongly named assemblies to
 GAC, 565–566
 overview, 560–561
 strongly typed
 database code, isolating into class
 libraries
 adapters for, 936–937
 deleting data with generated codes,
 942–943
 inserting data with generated codes,
 941–942
 invoking stored procedure using
 generated codes, 943
 overview, 938
 selecting data with generated codes,
 940–941
 viewing generated codes, 939–940
 DataRows, 935
 DataSets, 932–934
 DataTables, 934
 exceptions, 273
 object model, 943
 StronglyTypedDataSetConsoleClient
 application, 940
 StronglyTypedDataSetConsoleClient
 project, 943
 struct keyword, 20, 151
 StructuralObject.SetValue() method,
 971
 structure types
 Common Type System (CTS), 20
 creating variables, 152–153
 overview, 151
 structure variable, 154
 structured exception handling
 .NET, 260–262
 application-level exceptions
 (System.ApplicationException),
 273–276
 configuring state of
 Data property, 270–272
 HelpLink property, 269–270
 overview, 267
 StackTrace property, 268–269
 TargetSite property, 268

corrupted state exceptions (CSE), 285
 example of, 263–267
 multiple exceptions
 finally blocks, 282
 general catch statements, 279–280
 inner exceptions, 281
 overview, 277–278
 rethrowing, 280
 overview, 259
 system-level exceptions
 (*System.SystemException*), 272
 throws, identifying, 282–283
 unhandled exceptions, result of, 283
 Visual Studio debugger, 284–285
Structured Query Language (SQL), 908,
 910, 912, 914, 915, 918, 919, 922,
 945, 1394
structures
 defining in CIL, 670–671
 generic, specifying type parameters for,
 372–374
stsfld opcode, 679
stub code, 424, 1205
Style class, 1312
style inheritance, 1312
Style object, 1313, 1317
Style property, 1313, 1314, 1316, 1317, 1355
Style resource, 1316
style sheets, 1465
styles, WPF
 animated, 1318
 applying, 1313–1314
 assigning programmatically, 1319–1320
 defining
 with multiple triggers, 1317
 overview, 1313–1314
 with triggers, 1317
 generating with Expression Blend,
 1320–1324
 incorporating control templates into
 styles, 1354–1355
 overriding settings, 1314
 overview, 1312
 subclassed existing, 1315
 unnamed, 1316
sub opcode, 678, 680
subclassing existing WPF styles, 1315
subdirectories, creating with *DirectoryInfo*
 type, 781–782
subject matter experts (SMEs), 1078
submit button, 1390, 1391, 1461
subset data type, 116
subset variable, 497, 498, 502
.subsystem directive, 668
Subtract() method, 394, 404, 470
Suggestions property, 1200
Sum() method, 516
Sum<>() method, 509
summaries, creating, 1462–1463
summary pane, 1462
Summary window, 223
Sun Microsystems, 1562
SuppressContent property, 1421
SuppressFinalize() method, *System.GC*
 class, 298
Surround With group, 63
Surround With menu, 64
SuSe Linux, 1580
Suspend() method, 742
***.svc files**, 1074
SvcConfigEditor.exe, altering
 configuration files using, 1059–
 1061
svctutil.exe file, generating proxy code
 using, 1046–1047
Swap() method, 385, 394, 483
Swap Panes button, 1170
Swap<T>() method, 386, 387, 388, 394
SwapStrings() method, 129
Switch activity, 1107–1108
switch construct, 390
Switch editor, 1108
switch keyword, 122
switch opcode, 678
switch statement, 119, 121–123, 872
Switch<T> activity, WF 4.0, 1089, 1107
SyncDelegateReview program, 730
SyncDelegateReview project, 731
synchronization
 thread synchronization, 729

using [Synchronization] attribute, 757–758
 using C# lock keyword, 753–754
 using System.Threading.Interlocked type, 756–757
 using System.Threading.Monitor type, 755–756
 [Synchronization] attribute, 649, 729, 757–758
 synchronous blocking manner, 1084
 synchronous call, 734
 synchronous manner, 730
 synchronously method, 398
 syntactic constructs, C#, 8
 syntax, 666
 syntax folding, 49
 system data types
 class hierarchy, 90–92
 enum type
 declaring variables, 146–147
 discovering name/value pairs of, 148–150
 overview, 144
 System.Enum type, 147
 underlying storage for, 145–146
 and new operator, 89–90
 nullable types
 ?? operator, 164–165
 overview, 162
 working with, 163–164
 numerical data types, 92
 overview, 86
 parsing values from string data, 94
 reference types
 passing by reference, 160
 passing by value, 158–160
 structure type, 151–153
 System.Boolean, 93
 System.Char, 93–94
 System.DateTime, 95
 System.Enum type, 147
 System.Numerics, 95–97
 System.Text.StringBuilder, 104–105
 System.TimeSpan, 95
 value types
 containing reference types, 157–158
 overview, 154
 vs. references types, 155–156, 161–162
 variable declaration, 88–89
 System.Messaging namespace, 1031
 System namespace, 23, 29, 73, 86, 95, 149, 223, 314, 517, 732
 system types, class hierarchy of, 91
 System.ValueType class, 161
 System.Web.UI.TemplateControl class, 1416
 System.Activator class, 601–602
 System.Activities namespace, 1083
 System.Activities.Activity object, 1082
 System.Activities.dll assembly, 1088, 1112
 System.Activities.Statements namespace, 1088
 System.AppDomain class, 638–639
 System.AppDomain type, 692
 System.ApplicationException
 (application-level exceptions), 273–276
 System.ApplicationException class, 276
 System.Array class, 142–144, 148, 355, 361, 500, 501, 507, 758
 System.Array method, 144
 System.Array namespace, 494
 System.Array object, 513
 System.Array type, 344, 496
 System.AsyncCallback argument, 732
 System.Attribute class, 604, 609, 610
 System.Boolean class, 674
 System.Boolean data type, 23, 162
 System.Boolean parameters, 399
 System.Boolean structure, 89
 System.Boolean system type, 86, 113
 System.Boolean type, 93, 1164
 SystemBrushes type, 1547
 System.Byte class, 673
 System.Byte data type, 22
 System.Byte system type, 86, 109, 147
 System.Char class, 673
 System.Char data type, 23
 System.Char system type, 87, 93–94

System.Collections class, 363, 507
System.Collections namespace, 270, 271, 344, 357, 358, 361, 363, 368, 507
System.Collections.ArrayList variable, 365, 368
System.Collections.Generic namespace
 collection initialization syntax, 378
 List<T> class, 379–380
 overview, 376–377
 Queue<T> class, 382–383
 SortedSet<T> class, 383–385
 Stack<T> class, 380–381
System.Collections.Hashtable class, 255
System.Collections.IEnumerator interface, 344
System.Collections.Specialized class, 363
SystemColors type, 1547
System.ComponentModel.CancelEventArgs class, 1141
System.ComponentModel.Component class, 1525
System.Configuration namespace, 577, 578, 839, 849, 923
System.Configuration.AppSettingsReader type, 578
System.Configuration.dll assembly, 839, 849, 871, 923
System.Console class
 basic input and output with, 82–83
 formatting numerical data, 84–86
 formatting output, 83
 overview, 81
System.Console namespace, 30
System.Console type, 45
System.Console.WriteLine() method, 657
System.ContextBoundObject base class, 649
System.Convert class, 112
System.Core.dll assembly, 377, 495, 498, 517, 709
System.Data namespace, types
 IDataReader and **IDataRecord** interfaces, 836
 IDbCommand interface, 834
 IDbConnection interface, 833
IDbDataAdapter and **IDataAdapter** interfaces, 835
IDbDataParameter and **IDataParameter** interfaces, 834–835
IDbTransaction interface, 834
 overview, 832
System.Data .NET namespace, 29
System.Data.Common class, 838
System.Data.Common namespace, 827, 831, 847, 848, 849, 851, 916
System.Data.Common .NET namespace, 29
System.Data.Common.DataTableMapping class, 916
System.Data.Common.DbProviderFactory class, 848
System.Data.DataSetExtensions .NET namespace, 29
System.Data.DataSetExtensions.dll assembly, 495, 945, 946, 1105
System.Data.DataTable object, 866, 1107
System.Data.dll assembly, 494, 826, 829
System.Data.EntityClient namespace, 957, 978
System.Data.EntityClient .NET namespace, 29
System.Data.Entity.dll assembly, 955, 956, 984, 986, 1105, 1242
System.Data.Objects namespace, 958, 986
System.Data.Objects.ObjectSet<T> class, 959
System.Data.Odbc namespace, 829, 830
System.Data.OleDb data provider, 850
System.Data.OleDb namespace, 829, 830
System.Data.OleDb types, 851
System.Data.OracleClient.dll library, 830–831, 1415
System.Data.SqlClient namespace, 831
System.Data.SqlClient class, 838
System.Data.SqlClient namespace, 829, 830, 853, 914, 917, 922
System.Data.SqlClient .NET namespace, 29
System.Data.SqlClient type, 863

System.Data.SqlClientCe namespace, 830
System.Data.SqlClient.dll assembly, 494, 831
System.Data.SqlClientCe namespace, 829
System.Data.SqlClient.dll assembly, 829
System.Data.SqlTypes namespace, 831
System.DateTime type, 95
System.Decimal data type, 23
System.Decimal system type, 87
System.Delegate class, 91, 398, 401, 402, 729
System.Diagnostics namespace, members of, 627
System.Diagnostics.Process class, 628
System.Diagnostics.Process.ExitCode property, 76
SystemDirectory property,
 System.Environment class, 81
System.dll assembly, 363, 376, 377, 379
System.Double class, 673
System.Double data type, 23
System.Double system type, 87, 92
System.Drawing namespace, 31, 1546, 1547, 1553
System.Drawing .NET namespace, 29
System.Drawing.* assembly, 1128
System.Drawing.Bitmap class, 32
System.Drawing.Color variable, 1555
System.Drawing.dll assembly, 32, 533, 1117, 1118, 1511, 1513, 1545, 1546
System.Drawing.Drawing2D namespace, 1546, 1550
System.Drawing.Graphics class, 1548
System.Drawing.Imaging namespace, 1546
System.Drawing.Printing namespace, 272, 1546
System.Drawing.Text namespace, 1546
System.Dynamic namespace, 709
System.EnterpriseServices namespace, 878, 1015, 1016, 1022
System.Enum class, 21, 147, 148, 671
System.Enum.Format() method, 148
System.Environment class, 79–81, 1098, 1163
System.EventArgs argument, 1517
System.EventArgs class, 424, 1403, 1517–1518
System.EventArgs parameter, 1517
System.EventArgs type, 1517
System.EventHandler class, 1402, 1517–1518
System.EventHandler delegate, 1141, 1398, 1403, 1424, 1516
System.Exception catch block, 286
System.Exception class, 91, 261–262, 265, 270, 272, 273, 274, 278, 279
System.Exception object, 266, 267, 269, 1426
System.Exception.Message property, 269, 275
System.Exception.StackTrace property, 268
System.Exception.TargetSite property, 268
System.Func<T> delegate, 315, 316
System.Func<T> delegate, 763
System.Func<T1, TResult> delegate parameter, 519
System.GC class, 289
System.GC type, 298–302
System.Guid class, 95, 889
System.IAsyncResult interface, 732–733
System.IComparable interface, 354
SystemIcons type, 1547
System.IdentityModel.dll assembly, 1023
System.Int16 class, 673
System.Int16 data type, 22
System.Int16 system type, 86
System.Int32 class, 366, 369, 673
System.Int32 data type, 22, 28
System.Int32 system type, 86, 92, 107, 113, 145, 155
System.Int32 variable, 680
System.Int32.ToString() method, 686
System.Int64 class, 673
System.Int64 data type, 22
System.Int64 system type, 87
System.IntPtr type, 674
System.IO namespace, 27, 272, 281, 775–776, 902, 1206, 1226
System.IO .NET namespace, 29

System.IO, System.Data namespace, 30
 System.IO.Compression .NET namespace, 29
 System.IO.FileStream class, 307
 System.IO.Pipes namespace, 1019
 System.IO.Ports .NET namespace, 29
 System.Lazy<T> class, 289, 316
 system-level exceptions
 (System.SystemException), 272
 System.Linq namespace, 495, 771
 System.Linq .NET namespace, 29
 System.Linq.Enumerable class, 492, 493,
 500, 501, 509, 518
 System.Linq.Enumerable type, 521
 System.MarshalByRefObject class, 1525
 System.Messaging namespace, 1015, 1022
 System.MulticastDelegate class, 398, 400,
 401, 729
 System.MulticastDelegate delegate, 21
 System.Net class, 768
 System.Net namespace, 768
 System.Net.PeerToPeer namespace, 1019
 System.Net.Sockets namespace, 1019
 System.NotImplementedException, 336
 System.Nullable<T> structure type, 163
 System.Numerics type, 95–97
 System.Numerics.dll assembly, 96
 System.Object argument, 424, 732, 1517
 System.Object class
 overriding system.Object.Equals(),
 254–255
 overriding
 System.Object.GetHashCode(),
 255–256
 overriding system.Object.ToString(),
 254
 overview, 250–253
 static members of, 257–258
 static members of System.Object class,
 257–258
 testing modified person class, 256
 System.Object collections, 10
 System.Object data type, 23
 System.Object parameter, 747, 758, 759,
 1517, 1534, 1549

System.Object reference, 602
 System.Object system type, 91
 System.Object types, 368, 602, 1292, 1479,
 1485, 1489, 1494
 System.Object variables, 364, 366, 680, 722
 system.Object.Equals() method, 254–255
 System.Object.Finalize() method, 161,
 289, 303–304, 306, 309
 System.Object.GetHashCode() method,
 255–256
 System.Object.GetType() method, 140,
 588–589
 System.Objects array, 361
 System.Objects class, 363, 366, 367, 508
 system.Object.ToString() method, 254
 System.OperatingSystem, System.String,
 323
 System.OverflowException exception, 109
 SystemPens type, 1547
 System.Predicate<T> delegate, 430
 System.Predicate<T> type, 430
 System.Random member variable, 182
 System.Reflection namespace, 68, 494,
 587, 590, 595, 599, 600, 601, 621,
 691
 System.Reflection .NET namespace, 29
 System.Reflection object model, 595
 System.Reflection, System.Xml
 namespace, 1346
 System.Reflection.Assembly class, 554
 System.Reflection.Emit namespace, 654,
 688, 689–690, 691
 System.Reflection.Emit .NET namespace,
 29
 System.Reflection.Emit.ILGenerator, 690–
 691
 System.Reflection.Emit.OpCodes class,
 691
 System.Reflection.MethodBase object, 268
 System.Reflection.MethodInfo objects,
 401, 590
 System.Reflection.TypeAttributes enum,
 695
 System.Runtime.ExceptionServices
 namespace, 285, 286, 287

System.Runtime.InteropServices
 namespace, 718
System.Runtime.InteropServices .NET
 namespace, 29
System.Runtime.InteropServices.Marshal
 type, 303
System.Runtime.Remoting namespace,
 1016, 1022
System.Runtime.Remoting.Contexts
 namespace., 757
System.Runtime.Remoting.Contexts.Context object, 728
System.Runtime.Remoting.Messaging
 namespace, 738
System.Runtime.Serialization namespace,
 818, 823, 1023, 1027
System.Runtime.Serialization.dll
 assembly, 1022, 1023, 1027
System.Runtime.Serialization.Formatters.
 Binary and System.IO namespace,
 1558
System.Runtime.Serialization.Formatters.
 Binary class, 529
System.Runtime.Serialization.Formatters.
 Binary namespace, 902
System.SByte class, 673
System.SByte data type, 22
System.SByte system type, 86
System.Security .NET namespace, 30
System.Serializable attribute, 276
System.ServiceModel namespace, 1020,
 1023, 1027, 1029, 1032, 1036
System.ServiceModel .NET namespace, 29
<system.serviceModel> element, 1037,
 1038, 1042
System.ServiceModel.Activities.dll
 assembly, 1090
System.ServiceModel.ClientBase<T> class,
 1046
System.ServiceModel.Configuration
 namespace, 1023
System.ServiceModel.Description
 namespace, 1023
System.ServiceModel.dll assembly, 1022,
 1023, 1032, 1036, 1037, 1047, 1062

System.ServiceModel.MsmqIntegration
 namespace, 1023
System.ServiceModel.Security namespace,
 1023
System.Single class, 673
System.Single data type, 23
System.Single system type, 87
System.String class, 73, 91, 104, 497, 674
System.String data type, 23, 28, 1479, 1504
System.String instance, 102
System.String system type, 87, 93, 97, 98,
 102, 113, 1175
System.String variable, 680
System.String.Format() method, 686
System.Structure class, 154
system-supplied collection, 118
System.SystemException (system-level
 exceptions), 272
System.SystemException class, 273
System.Text namespace, 104
System.Text.RegularExpressions
 namespace, 1460
System.Text.StringBuilder class, 73
System.Text.StringBuilder type, 104–105
System.Threading class, 758, 762, 768
System.Threading namespace, 739–740,
 745, 747, 749, 753, 756, 760, 761,
 765
System.Threading .NET namespace, 30
System.Threading.Interlocked type, 756–
 757
System.Threading.Monitor class, 755, 756
System.Threading.Monitor type, 755–756
System.Threading.Tasks class, 761, 762
System.Threading.Tasks namespace, 762,
 765, 768, 771, 774
System.Threading.Tasks .NET namespace,
 30
System.Threading.Tasks.Parallel class, 763
System.Threading.Thread class
 Name property, 743
 obtaining statistics about current
 thread, 742
 overview, 741
 Priority property, 744

System.Threading.ThreadPriority
enumeration, 744
System.Threading.Thread.txt, 1577
System.Threading.Timer class, 758
System.TimeSpan type, 95
System.Transactions namespace, 878
System.Type class, 91, 147, 587, 595, 1158
System.Type parameter, 590, 623
System.Type.GetType() method, 589
System.UInt16 class, 673
System.UInt16 data type, 23
System.UInt16 system type, 86
System.UInt32 class, 673
System.UInt32 data type, 23
System.UInt32 system type, 86
System.UInt64 class, 673
System.UInt64 data type, 23
System.UInt64 system type, 87
System.UIntPtr type, 674
System.Uri class, 1027, 1031, 1038, 1043
System.Uri object, 1288
System.ValueType class, 91, 92, 154, 161,
 670, 671
System.Void class, 95, 674
System.Web namespace, 33, 1481
System.Web .NET namespace, 29
<system.web> element, 1504
<system.web> root element, 1468
System.Web.Caching.Cache class, 1489
System.Web.Caching.Cache object, 1488
System.Web.dll library, 1404, 1416
System.Web.HttpApplication class, 1481,
 1482
System.Web.HttpCookie class, 1498
System.Web.RegularExpressions
 namespace, 1460
System.Web.Services namespace, 1016,
 1022
System.Web.UI.Control class, 1423, 1430,
 1432, 1478
System.Web.UI.HtmlControls class, 1440–
 1441
System.Web.UI.LiteralControl, 1435
System.Web.UI.Page class, 1402, 1405,
 1409, 1410, 1411, 1416, 1423, 1476
System.Web.UI.Page type, 1482, 1489
System.Web.UI.Page.Request property,
 1417
System.Web.UI.StateBag type, 1478, 1479
System.Web.UI.WebControls namespace,
 1404, 1429, 1430, 1440, 1441
System.Web.UI.WebControls.BaseValidator
 class, 1458
System.Web.UI.WebControls.WebControl
 class, 1430, 1465
System.Windows namespace, 29, 33, 1127,
 1128, 1137, 1156, 1280, 1342
System.Windows .NET namespace, 29
System.Windows.Annotations namespace,
 1232
System.Windows.Application class, 1128,
 1136
System.Windows.Controls namespace,
 1127, 1138, 1157, 1180, 1183, 1185,
 1430
System.Windows.Controls .NET
 namespace, 29
System.Windows.Controls.Button type,
 1150
System.Windows.Controls.ContentControl
 class, 1131–1132
System.Windows.Controls.Control class,
 1132
System.Windows.Data namespace, 1127,
 1157, 1240
System.Windows.DependencyObject
 class, 1135, 1330
System.Windows.Documents namespace,
 1127, 1183, 1227
System.Windows.Documents.Block class,
 1227
System.Windows.Documents.Inline class,
 1227
System.Windows.Forms namespace, 33,
 45, 322, 571, 746, 1008, 1430, 1512
System.Windows.Forms .NET namespace,
 29
System.Windows.Forms.* assembly, 1128
System.Windows.Forms.ColorDialog type,
 1556

System.Windows.Forms.ContainerControl
 class, 1526
System.Windows.Forms.Control class, 322,
 1515, 1526
System.Windows.Forms.DataVisualization
 .Charting namespace, 1511
System.Windows.Forms.DataVisualization
 .dll, 1511
System.Windows.Forms.dll assembly, 45,
 46, 48, 533, 540, 542, 558, 599, 662,
 746
System.Windows.Forms.Form class, 1513,
 1526, 1543
System.Windows.Forms.MessageBox
 class, 45, 585
System.Windows.Forms.MessageBox.Show()
 method, 662
System.Windows.Forms.MouseEventHandler
 delegate, 1534
System.Windows.Forms.ScrollableControl
 class, 1526
System.Windows.FrameworkElement,
 1133
System.Windows.Ink namespace, 1128,
 1157, 1183, 1226
System.Windows.Input namespace, 1280
System.Windows.Input.KeyEventHandler
 delegate, 1143
System.Windows.Input.MouseEventArgs
 class, 1142
System.Windows.Input.MouseEventHandler
 delegate, 1142
System.Windows.Markup namespace,
 1128, 1151, 1157, 1173, 1235, 1346
System.Windows.Media namespace, 1128,
 1157, 1252, 1280, 1343
System.Windows.Media.Animation
 namespace, 1304, 1364
System.Windows.Media.Animation.Timeline
 class, 1305
System.Windows.Media.Brush, 1257
System.Windows.Media.ColorConverter
 class, 1260
System.Windows.Media.Drawing class,
 1246, 1271
System.Windows.Media.Geometry class,
 1254
System.Windows.Media.Imaging
 namespace, 1279, 1280, 1288
System.Windows.Media.Stretch
 enumeration, 1249
System.Windows.Media.Transform class,
 1262
System.Windows.Media.Visual class, 1134,
 1135, 1246, 1277
System.Windows.Navigation namespace,
 1128, 1157
System.Windows.RoutedEventArgs
 parameter, 1337
System.Windows.Shapes namespace,
 1128, 1246, 1247, 1248, 1253, 1256,
 1270
System.Windows.Shapes .NET namespace,
 29
System.Windows.Style class, 1312
System.Windows.Threading.DispatcherObject,
 1135
System.Windows.UIElement, 1134
System.Windows.Window class, 1130,
 1146, 1175
System.Workflow.Activities .NET
 namespace, 30
System.Workflow.Runtime .NET
 namespace, 30
System.Xaml.dll assembly, 1127, 1135
System.Xml DOM model, 995
System.Xml namespace, 993
System.Xml namespaces, 494
System.Xml .NET namespace, 30
System.Xml.dll assembly, 494, 993, 995,
 996, 1011
System.Xml.Linq class, 995, 1000
System.Xml.Linq namespaces
 LINQ to XML axis methods, 1000–1001
 overview, 997–999
 XName (and XNamespace) class, 1001–
 1002
System.Xml.Linq .NET namespace, 29
System.Xml.Linq, **System.Xml.Schema**
 namespace, 997

System.Xml.Linq.dll assembly, 495, 997, 998, 1011
 System.Xml.Serialization namespace, 815
 System.Xml.XPath namespace, 997

T
 t variable, 703
 Tab key, 63, 423, 424
 tab order, configuring, 1540
 Tab Order Wizard, 1540–1541
 TabControl control, 1213–1215, 1227
 TabIndex property, 1133, 1438, 1527, 1540
 TabIndex value, 1540
 tabInk object, 1222
 TabItem control, 1214, 1216, 1228
 Table class, 1230
 Table element, 1227
 Table property, 891, 893
 table relationships
 in AutoLot database, visually creating, 846–847
 building, 924
 Table type, 1227
 TableAdapter class, 931
 TableMappings property, 835, 916
 TableName member, 897
 TableName property, 915
 Tables collection, 898, 934, 943
 tables, navigating between related, 925–927
 Tables node, 841, 842
 Tables property, 887, 932
 TabOrder property, 1540
 TabStop property, 1527, 1540
 tag prefix, 1159
 Tag property, 1225
 Target member, 401
 Target property, 404
 TargetProperty property, 1310
 *.targets files, 1148, 1149, 1150, 1153
 TargetSite property, 263, 267, 268, 269
 TargetType attribute, 1313, 1314–1315, 1351

TargetType property, 1095, 1098, 1316
 TargetUrl image, 1448
 Task class, 765–766, 768
 Task Parallel Library (TPL), 727, 729, 736, 762, 763, 764, 765, 768, 771, 772
 task parallelism, 768–771
 TaskFactory object, 766
 TCP (Transmission Control Protocol), 1017, 1020, 1022, 1025, 1028, 1030, 1031, 1032, 1050, 1052
 TCP-based bindings, 1030, 1049–1050
 TCP/IP (Transmission Control Protocol/Internet Protocol) address value, 1501
 Teenager class, 181, 182
 tempdb database, 1502
 Template property, 1133, 1344, 1348, 1350
 TemplateControl class, 1416
 templates, 1071–1073
 Service Website, 1025
 Visual Studio 2010, 1023–1025
 Visual Studio Windows Forms, 1518–1524
 templating services, 1132
 temporary cookie, 1498
 TerminateWorkflow activity, 1091, 1097, 1098
 Test Client application, WCF, 1058
 TestApp application, 45
 TestApp class, 47
 TestApp file, 43, 44, 45
 TestApp.exe application, 46, 48
 TestApp.exe assembly, 43, 48
 TestApp.exe file, 44, 45
 TestApp.rsp file, 47
 TestApp.rsp response file, 48
 TesterUtilClass class, 462
 testing
 ADO.NET database transactions, 882–883
 modified person class, 256
 services, 1075–1076
 TestWindow.xaml, 1296
 Text attribute, 1082
 Text edit box, 1081

text files
 reading to, 796–797
 writing to, 795–796

Text property, 1085, 1094, 1241, 1373, 1420, 1422, 1429, 1436, 1441, 1456

Text value, 1429

TextBlock controls, 1198, 1227, 1354, 1371

TextBox class, 907, 908, 910, 925, 1007, 1008, 1009, 1173, 1474

TextBox control, 768, 1198, 1206, 1227, 1431, 1439, 1455, 1487, 1495, 1505

TextBox objects, 1317

TextBox scope, 1429

TextBox style, 1317

TextBox type, 1174, 1175, 1177, 1467, 1536

TextBoxes control, 1262

TextBoxes widget, 1441

TextBoxLineDrawingVisual, 1344

TextChanged event, 1431

TextureBrush type, 1547

Theme property, 1417

themes
 *.skin files, 1466–1468
 applying at page level, 1469
 applying sitewide, 1468
 assigning programmatically, 1469–1471
 overview, 1465
 SkinID property, 1469

themes, ASP.NET. *See* ASP.NET themes

theMessage variable, 691

Then area, 1107

TheString property, 676

Thickness objects, 1305

third-party data providers, obtaining, 831

This application has succeeded message, 77

this keyword
 chaining constructor calls using, 176–178
 and constructor flow, 178–180
 overview, 174–175

this operator, 492

this reference, 682

this[] syntax, 440

Thread class, 728, 740, 741, 743, 762

Thread Local Storage (TLS), 627

Thread objects, 398, 742, 743, 745, 746, 751, 760, 761

thread scheduler, 728, 744

thread set of process, 631–634

thread synchronization, 729

Thread type, 742, 744

Thread.CurrentContext property, 651, 728

Thread.CurrentThread property, 728, 731, 742

Thread.GetDomain() method, 697, 728

threading primitives, 729

ThreadPool class, 740, 760

ThreadPoolApp project, 761

ThreadPool.QueueUserWorkItem() method., 760

ThreadPriority enumeration, 740, 741

ThreadPriority property, 744

ThreadPriority.Highest value, 744

ThreadPriority.Normal value, 744

Threads property,
 System.Diagnostics.Process class, 629, 632

Thread.Sleep() method, 730, 731, 735, 748, 753

ThreadStart delegate, 740, 744, 745–746, 747, 750

Thread.Start() method, 744, 750

ThreadState enumeration, 740, 741

ThreadState member, ProcessThread type, 633

ThreadState property, 741

ThreadStats Console Application, 742

ThreadStats project, 744

thread-volatile operations, 729

ThreeDCircle class, 245, 246, 247, 324, 328

three-letter abbreviation (TLA), 25

Throw activity, WF 4.0, 1092

throw keyword, 261, 265, 280

ThrowException() method, 691

ThrowIfCancellationRequested() method, 767

throwing general exceptions, 265–266

throws, identifying, 282–283

thumb, 1259

tilde symbol (~), 303
 time line editor, 1360
 time slice, 627
 Timeline area, 1211
 Timeline Base class, 1305
 Timeline window, 1270
 Timeout attribute, 1497
 Timeout property, 1496, 1497
 Timeout value, 1497
 timer callbacks, programming with, 758–759
 Timer class, 739, 740, 758
 Timer constructor, 759
 Timer object, 759
 Timer types, 740
 TimerApp Console Application, 758
 TimerApp project, 760
 TimerCallback delegate, 740, 758, 759
 TimeSpan object, 1308, 1309
 TimeSpan structure, 95
 TimeUtilClass class, 187
 Title attribute, 1146
 Title property, 1338
 Title property, System.Console class, 82
 <title> tags, 1384
 TLA (three-letter abbreviation), 25
 TLS (Thread Local Storage), 627
 To edit box, 1107
 To property, 1305, 1307, 1310
 ToArray() method, 380, 513
 ToArray<>() method, 509
 ToArray<>() method, 513
 ToArray<T>() method, 502, 503, 977
 ToDictionary<K,V>() method, 977
 ToDictionary<TSource,TKey>() method, 502
 toggle button, 1265
 <ToggleButton> element, 1264
 token, 753
 token class, 393
 token set, 654
 token value, 199
 ToList<>() method, 509
 ToList<T>() method, 502, 503, 977
 ToLower() method, String system type, 98

tool support, 1082
 ToolBar
 building window frame using nested panels, 1197–1198
 Ink API tab, WPF, 1217–1219
 toolbar buttons, 1195, 1196
 ToolBar class, 1197
 ToolBar control, 1198, 1217, 1228
 ToolBar element, 1198
 ToolBar objects, 1198
 ToolBar type, 1198
 <ToolBar> element, 1264
 <ToolBarTray> element, 1198
 Toolbox, Visual Studio 2010, 1080, 1093, 1180, 1438, 1522
 Tools area, 1212, 1215
 Tools editor, 1211, 1212
 Tools menu functionality, implementing, 1555–1556
 Tools menu system, 1552
 tools, Visual Studio 2010, 1384–1386
 Tools window, 1212, 1213, 1222
 ToolsSpellingHints_Click() method, 1197, 1200
 ToolStripMenuItem method, 1516
 ToolStripMenuItem object, 1516
 ToolTip property, FrameworkElement type, 1134
 ToolTip property, WebControl Base Class, 1438
 Top property, 1527
 ToString() method, 91, 148, 252, 253, 255, 263, 351, 379, 390, 476
 TotalProcessorTime member, ProcessThread type, 633
 ToUpper() method, 98, 103, 704, 705
 TPL (Task Parallel Library), 727, 729, 736, 762, 763, 764, 765, 768, 771, 772
 Trace attribute, 1402, 1411
 Trace property, 1411, 1417
 <trace> element, 1427
 TraceContext object, 1417
 Trace.Write() method, 1411
 tracing ASP.NET pages, 1410–1411
 tracing support, 1411

TraditionalDelegateSyntax() method, 430
TransactedReceiveScope activity, WF 4.0, 1090
 transaction activities, WF 4.0, 1091–1092
Transaction object, 828, 834
Transaction property, 882
 transactional literature, 878
 transactions, 877
TransactionScope activity, WF 4.0, 1092
Transform class, 1262
Transform editor, 1360
Transform member, 1254
Transform objects, 1254, 1262
Transform pane, 1270
 transformation editors, 1269–1271
TransformGroup type, 1262
TranslateTransform type, 1262
Transmission Control Protocol (TCP), 1017, 1020, 1022, 1025, 1028, 1030, 1031, 1032, 1050, 1052
Transmission Control Protocol/Internet Protocol (TCP/IP) address value, 1501
TreesAndTemplatesApp project, 1348
TreeView control, 1439, 1444, 1445–1447
TreeView widget, 322
TreeViews control, 1531
Triangle class, 327
Trigger objects, 1317
<Trigger.EnterActions> element, 1318
<Trigger.ExitActions> scope, 1318
Triggers
 defining WPF styles with multiple, 1317
 overview, 1317
 incorporating visual cues in WPF control templates using, 1351–1352
Triggers collection, 1317
Triggers editor, 1363
Triggers, Style class, 1313
Trim()method, String system type, 98
TrokeStartLineCap property, Shape class, 1249
True argument, 311
True blue value, 717
True operator, 445
True value, 347, 1140
TrueString property, 93
Truncate member, FileMode enumeration, 787
Try block, 267, 277, 280, 756
Try keyword, 109, 249, 261
Try scope, 304
TryCatch activity, WF 4.0, 1092
Try/catch block, 64, 266, 705, 706, 1176
Try/catch construct, 250
Try/catch logic, 283, 330, 365, 1113
Try/catch scope, 282
Try/final logic, 308
Try/finally block, 308
Try/finally logic, 309
TryFindResource() method, 1296, 1319
Tunneling events, 1338, 1339
TurboBoost() method, 539, 540, 544, 549, 602, 603
TurnOnRadio() method, 604
*.txt files, 1109, 1114, 1204
TxtAttempts control, 1371
TxtColor control, 1538
TxtFavCar textbox, 1474
TxtInstructions control, 1371
TxtInstructions property, 1373
TxtMake control, 1538
TxtMakeToView class, 908
TxtNewSP textbox, 1487
TxtPrice control, 1538
TxtRequiredField text box, 1459
TxtScore control, 1371
TxtUserMessage class, 1387
TypDefName token, 583
Type attribute, 1461, 1504, 1505, 1508
Type boundary, 532
Type class, 588, 1063
Type constructors, defining in CIL, 675
Type converters, XAML, 1160–1161
Type definition (TypeDef), 582
Type fidelity among formatters, 810–811
Type indexer, 366
Type members

- Common Type System (CTS), 22
 - defining in CIL, 674–677
- type metadata, 544–545, 581–586
 - documenting referenced assemblies, 585
 - documenting string literals, 586
 - documenting the defining assembly, 585
- TypeRef, 585
 - viewing
 - for Car type, 583–584
 - for EngineState enumeration, 582–583
 - exploring assemblies using ildasm.exe, 34
- Type Name edit area, 1095
- Type object, 588, 601
- type parameters
 - constraining, 392
 - constraining type parameters
 - examples using where keyword, 393–394
 - lack of operator constraints, 394–395
 - inference of, 387–388
 - overview, 371
 - specifying
 - for generic classes / structures, 372–374
 - for generic interfaces, 374–375
 - for generic members, 374
- type reference (TypeRef), 582
- type safety, 367–371, 373, 403
- type system, 6
- TypeAttributes enumeration, 695
- TypeBuilder class, 689, 696, 697
- TypeBuilder member, 689
- TypeBuilder.DefineConstructor() method, 696
 - TypeBuilder.DefineField() method, 696
- TypeConversions project, 106, 112
- typed variable, 702
- TypeDef #n token, 582
- TypeDef (type definition), 582
- TypeDef block, 585
- TypedTableBaseExtensions class, 946
- TypeDumper.DumpTypeToFile() method, 1577
- Type.GetCustomAttributes() method, 615
- Type.GetFields() method, 591
- Type.GetMethod() method, 602
- Type.GetMethods() method, 590
- Type.GetType() method, 592, 593, 594
- Type.Missing value, 717
- Type.Missing values, 717
- typeof() method, 386, 589
- typeof operator, 147, 578, 1158
- TypeRef, 585
- TypeRef #n token, 582
- TypeRef (type reference), 582
- TypeRef block, 585
- types
 - directly creating, 797–798
 - pinning with fixed keywords, 485–486
- Types array, 493
- type-safe container, 367
- typing variables, implicitly, 112

U

- U command, 872
- UAC (User Access Control) settings, 565
- UDTs (user-defined types), 20
- Ufo class, 550, 551
- ufo.cs file, 550
- ufo.netmodule file, 550, 551
- UI (web User Interface), 1474
- UI markup, 1147
- UIElement class, 1117, 1134, 1142, 1143, 1248
- UIElement objects, 1252, 1253, 1256
- UIElement property, 1255
- UIElement type, 1134
- UIElements, 1255, 1256, 1272
- uint data type, 86
- UIPropertyMetadata constructor, 1335
- UIPropertyMetadata object, 1335
- unary operator overloading, 448–449
- unbox opcode, 678
- unboxing operations, 364, 365

Unchanged value, 895
 Unchecked event, 1220
 unchecked keyword, 73, 108, 111
 undefined symbols error, 74
 underflow condition, 109
 unhandled exceptions, result, 283
 UnhandledException event, AppDomain class, 640
 Uniform Resource Identifier (URI), 768, 1032, 1034, 1047, 1050, 1071, 1394
 Uniform Resource Locator (URL), 261, 269, 1044, 1055, 1067, 1380, 1381, 1384, 1391, 1418
 UninstallSqlState.sql file, 1502
 Union() method, 515
 Union<>() method, 509
 Unique property, DataColumn class, 891
 uniquely named, 1072
 Unload event, 1424
 Unload() method, 639
 unloading AppDomains, programmatically, 646–648
 UnLock() method, HttpApplicationState type, 1484
 Unlock() method, HttpApplicationState type, 1487
 unmanaged code, 10
 unmanaged resources, 289, 298, 303, 305, 311
 unnamed styles, WPF, 1316
 unreachable object, removing, 291
 UnRegisterWithCarEvent() method, 410
 unsafe keyword, 481–482, 654
 unsafe swap function, 483
 UnsafeCode project, 486
 UPDATE command, 914
 Update() method, 835, 914, 918
 Update request, 861
 Update Service Reference menu option, 1056
 Update statement, 862, 1450
 UpdateCarInventory() method, 1491
 UpdateCarPetName() method, 876
 UpdateCommand property, 914, 918, 949
 UpdateInventory() method, 919, 921
 updating
 code file, 1409–1410
 records, 975
 upward cast, 106
 urgency level, 298
 URI (Uniform Resource Identifier), 768, 1032, 1034, 1047, 1050, 1071, 1394
 Uri array, 1039
 Uri class, 1063
 Uri objects, 1291
 UriKind value, 1291
 URL (Uniform Resource Locator), 261, 269, 1044, 1055, 1067, 1380, 1381, 1384, 1391, 1418
 url attribute, 1446
 url value, 1446
 UseGenericList() method, 372
 User Access Control (UAC) settings, 565
 User Control library, 1300
 user interface (UI)
 of LINQ to XML App, building, 1007
 rigging up to Helper class, 1009–1011
 User Interface (UI) element, 1385
 user profiles, defining within Web.config, 1504–1505
 User Strings token, 586
 UserControl class, 1144, 1366
 UserControl types, 1331
 <UserControl> element, 1156
 <UserControl> scope, 1356
 UserControl1.xaml file, 1300
 UserControls
 building custom with Blend
 animation, defining, 1359–1362
 initial C# code, 1359
 overview, 1356
 programmatically starting
 Storyboard, 1363–1364
 renaming initial, 1357–1358
 SpinControl, 1358
 extracting from drawing geometry, 1365–1366
 UserControl class, 1292
 UserControls control, 1442
 user-defined collection, 118

user-defined types (UDTs), 20
 userFavoriteCar variable, 1473, 1474, 1475
 UserHostAddress property, 1418
 UserHostName property, 1418
 user-interface (UI), designing, 1396–1397
 UserName property, System.Environment class, 81
 UserName type, 1094
 UserShoppingCart class, 1494, 1495
 UserShoppingCart type, 1495, 1496
 ushort data type, 86
 using block, 309
 using directive, 271
 using keyword, and disposable objects, 308–309
 using scope, 309, 1038
 using statement, 1409
 UsingNamespace() method, 691
 utility classes, 181, 187

V

v4.0 prefix, 566
 v4.0_major.minor.build.revision_publicKeyTokenValue directory, 567
 Validate attribute, 1418
 ValidateCurrentNumber, 1335
 ValidateInput() method, 1418
 ValidateValueCallback delegate, 1330, 1335
 ValidateValueCallback delegate, 1329, 1335
 Validation area, 1439
 validation controls
 CompareValidator widget, 1461–1462
 creating summaries, 1462–1463
 defining groups, 1463–1465
 overview, 1457–1458
 RangeValidator widget, 1460–1461
 RegularExpressionValidator widget, 1460
 RequiredFieldValidator widget, 1459–1460
 ValidationExpression property, 1460
 ValidationGroup property, 1464

ValidationGroups.aspx project, 1463
 ValidationSummary control, 1458, 1463
 ValidationSummary type, 1462
 ValidationSummary widget, 1462
 ValidatorCtrls project, 1459
 ValidatorCtrls website, 1465
 value attribute, 671
 value, passing reference types by, 158–160
 Value property, 163, 164, 271, 315, 868, 1107, 1237, 1389
 value token, 199
 value types
 containing reference types, 157–158
 overview, 154
 vs. reference types, 155–156, 161–162
 ValueAndReferenceTypes project, 155, 158
 ValueChanged event, 1236
 Values property, 1099
 ValueType class, 91, 154, 251
 ValueTypeAssignment() method, 156
 var data type, 113, 116
 var keyword, 73, 112, 113, 114, 115, 116, 118, 139, 490, 500
 var token, 113
 var-defined data point, 115
 Variable Type drop down list, 1098
 Variable Type dropdown list box, 1106
 variables
 assignment of, 1106
 data type, 90
 declaration of, 88–89, 680–681
 declaring with fully qualified name, 31
 for enum type, 146–147
 implicitly typing, 112
 local, 88, 127, 290, 429–430
 mapping parameters to in CIL, 681
 object, 196
 output, 127
 reference, 290
 structure, 154
 for structure type, 152–153
 web-based application, 1124
 workflow
 defining, 1106–1107
 workflow wide, defining, 1095–1096

XAML, declarations, 1159
 Variables aspect, 1095
 Variables button, 1095, 1098, 1106
 Variant data types, 115, 717, 718, 722
 VB (Visual Basic) literal syntax, 996–997
 VB code, 1097
 VB statements, 1094
 VB6 Component Object Model (COM)
 developers, 261
 vbc.exe compiler, 24
 vbc.exe file, 16
 vbnc compiler, Mono, 1569
 VBScript language, 1389
 VbSnapIn library, 620
 VbSnapIn.dll assembly, 618, 623
 VbSnapIn.dll library, 621
 vector graphics, generating using
 expression design, 1275–1276
 [VehicleDescription] attribute, 610, 612
 VehicleDescriptionAttribute attribute, 609,
 610
 VehicleDescriptionAttribute class, 615
 VehicleDescriptionAttributeReader
 application, 614
 Venn diagramming operations, 1268
 Venn diagramming tool, LINQ as, 515–516
 .ver directives, 542, 666
 .ver token, 542, 562
 verbatim strings, 101–102
 VerifyDuplicates() method, 471, 472, 473
 version numbers, setting, 919
 Version type, 693
 <version> element, 48
 Vertical split button, 1170
 Vertical value, 1189
 VerticalAlignment property,
 FrameworkElement type, 1133
 VerticalContentAlignment property,
 Control Type, 1133
 VeryComplexQueryExpression class, 521
 VeryDynamicClass, 706
 VES (Virtual Execution System), 37
 VideoDrawing object, 1258
 VideoDrawing type, 1272
 View Class Diagram button, 64, 225, 932
 View Code menu option, 1081, 1104, 1554
 View Code option, 621, 933, 1513, 1520
 View Detail link, 285
 View In Browser menu option, 1387, 1388,
 1399, 1465
 View Inventory menu item, 1452
 View Inventory node, 1446
 View menu, 56, 58, 60, 65, 223, 568, 608,
 939, 1169, 1450
 View Source, 1477
 view state
 adding custom data, 1478–1479
 demonstrating, 1477–1478
 overview, 1476
 Viewport3DVisual class, 1277
 Viewport3DVisual object, 1258
 ViewState property, 1478, 1485
 ViewStateApp project, 1477
 virtual, 22
 virtual directories, IIS, 1381
 virtual execution stack, 656
 Virtual Execution System (VES), 37
 virtual keyword, 125, 236–238, 243
 virtual members
 overriding using Visual Studio 2010,
 238–239
 sealing, 239
 virtual methods, 236, 243, 493
 Visibility property, UIElement type, 1134
 visibility trait, 22
 Visible property, 1432, 1433, 1527, 1529
 visual base class and derived child classes,
 1277
 Visual Basic (VB) literal syntax, 996–997
 Visual Basic 6.0, programming language
 comparison, 4
 Visual Basic, building client application,
 547–549
 Visual Basic compiler, 16, 1565, 1569
 Visual Basic Snap-In, 620
 Visual C# 2010 Express and Visual C++
 2010 Express, 53
 Visual C# 2010 Express, building C#
 applications with, 53–54
 Visual class, 1134, 1258, 1277, 1283

Visual Class Designer, Visual Studio 2010, 64–67
 visual designer surface, 1519–1520
 visual layer, rendering graphical data using DrawingVisual class, 1278–1279
 overview, 1277
 rendering to custom layout manager, 1280–1282
 responding to hit test operations, 1282–1284
 visual base class and derived child classes, 1277
 Visual object, 1258
 visual state groups, 1366
 Visual State Manager (VSM), .NET 4.0, 1356, 1366
 Visual Studio 2010
 AssemblyInfo.cs file, 613
 class diagrams, revising, 224–225
 Class View utility, 58–59
 code expansions, 63–64
 configuration files and, 556–558
 configuring brushes using, 1258–1260
 default namespace of, 531
 generating proxy code using, 1047–1048
 generating strong names using, 563–564
 HTML designer tools, 1384–1386
 implementing interfaces using, 335–336
 integrated .NET Framework 4.0 documentation, 67–69
 New Project dialog box, 56
 Object Browser utility, 60
 overriding virtual members using, 238–239
 overview, 54
 project templates, 1023–1025
 refactoring code, 60–63
 Solution Explorer Utility
 overview, 56
 referencing external assemblies, 57
 viewing Project Properties, 58
 unique features of, 55
 Visual Class Designer, 64–67
 WPF applications, building using

Button Click event, implementing, 1175–1176
 Closed event, implementing, 1177
 designer tools, 1169–1172
 GUI, designing, 1173–1174
 Loaded event, implementing, 1174
 overview, 1167
 project templates, 1168
 testing, 1177–1178
 WPF control templates, building
 custom
 {TemplateBinding} markup extension, 1352–1353
 ContentPresenter class, 1354
 incorporating into styles, 1354–1355
 incorporating visual cues using triggers, 1351–1352
 overview, 1348
 as resources, 1349–1351
 WPF controls, 1181–1182
 Visual Studio debugger, 284–285
 Visual Studio Windows Forms project template
 initial Form, 1520–1521
 overview, 1518
 Program class, 1521–1522
 visual designer surface, 1519–1520
 visually building menu systems, 1522–1524
 visual trees, 1252, 1278, 1341–1348
 Visual type, 1135, 1277
 Visual Web Developer 2010 Express, 53
 VisualBasicCarClient project, 549
 VisualBasicCarClient.exe file, 553
 VisualBrush class, 1258
 VisualBrush type, 1258
 VisualChildrenCount property, 1281
 VisualCollection container, 1282
 VisualCollection variable, 1280, 1281
 VisualStateGroup class, 1367
 VisualStateManager class, 1367, 1370
 VisualTreeHelper class, 1252, 1343
 VisualTreeHelper.HitTest() method, 1252, 1253, 1283
 void return value, 75, 76, 77

void value, 127, 171
 Vs2010Example application, 56
 VSM (Visual State Manager), .NET 4.0, 1356, 1366

W

W3C (World Wide Web Consortium), 995, 1019
 WaitCallback delegate, 760
 WaitForPendingFinalizers() method, System.GC class, 298
 WaitHandle class, 735
 WaitHandle.WaitOne() method, 735
 WaitOne() method, 735, 748
 WaitReason member, ProcessThread type, 633
 WAS (Windows Activation Service), 1026
 WCF. *See* Windows Communication Foundation
 WCF (core assemblies of Windows Communication Foundation), 1022
 WcfMathService.MyCalc class, 1054
 WcfTestClient.exe, 1024, 1058–1059, 1075
 web application, 1412
 Web Application model, 1413
 web application shutdown, handling, 1488
 Web Application Templates, Visual Studio, 1412
 Web applications, 1412–1413
 Web applications and servers
 ASP.NET development web server, 1382
 IIS virtual directories, 1381
 overview, 1380
 web controls
 categories of, 1438
 data centric, 1439
 security, 1440
 standard, 1439
 web controls, ASP.NET. *See* ASP.NET web controls
 Web Form, 1408, 1473, 1477, 1485, 1489, 1498

Web Form controls, 1416, 1429
 Web Form icon, Solution Explorer, 1408
 web method, 1018
 Web pages
 building single file
 adding data access logic, 1397–1401
 ASP.NET control declarations, 1403–1404
 ASP.NET directives, 1401–1403
 compilation cycle for single-file pages, 1405–1406
 designing UI, 1396–1397
 overview, 1395
 referencing AutoLotDAL.dll, 1396
 "script" block, 1403
 building using code files, 1406–1411
 Web Parts, 1393
 Web servers, posting back to, 1390–1391
 Web Service Definition Language (WSDL), 1019, 1021, 1034, 1044, 1055, 1072, 1073
 web service specifications (WS-*), 1020
 Web Services Addressing (WS-Addressing), 1029
 Web Services Basic (WS-Basic), 1029
 Web Services Enhancements (WSE), 1019
 Web Services Federation (WS-Federation), 1029
 Web Services Interoperability Organization (WS-I), 1019, 1029
 Web Services Reliability (WS-Reliability), 1028
 Web Services SecureConversation (WS-SecureConversation), 1030
 Web Services Security (WS-Security), 1028, 1030
 Web Services Transactions (WS-Transactions), 1028
 Web Services Trust (WS-Trust), 1030
 Web Site dialog box, 1017
 Web site directory structure
 App_Code folder, 1415
 overview, 1413
 referencing assemblies, 1414–1415
 Web sites applications, 1412–1413

web User Interface (UI), 1474
 Web-Centric service project templates, 1071–1073
 WebClient class, 768
 Web.config files, 1075, 1427–1428, 1504–1505
 WebControl class, 1404, 1430, 1437, 1438
 WebControl types, 1432
 webdev.webserver.exe utility, Microsoft .NET, 1571
 [WebMethod] attribute, 605, 606, 1016, 1018
`<%@WebService%>` directive, 1018
 website administration utility, ASP.NET, 1428
 Website option, 1409
 Web.sitemap file, 1445, 1446
 Welcome dialog box, 1207
 where clauses, 393, 394
 where keyword, constraining type parameters using, 393–394
 Where() method, 517, 519, 520
 where operator, 497, 509, 511, 517, 518
 where T : class constraint, 392
 where T : NameOfBaseClass constraint, 393
 where T : NameOfInterface constraint, 393
 where T : new() constraint, 392
 where T : struct constraint, 392
 WhereArrayIterator<T> class, 499
 While activity, WF 4.0, 1089
 while keyword, 682
 while loop, 117, 119
 widening operation, 106
 Width attribute, 1146
 Width property, 1133, 1145, 1152, 1187, 1193, 1219, 1304, 1326, 1438, 1527
 Width value, 1188, 1189, 1193
 wildcard character (*), 47
 wildcard token, 562
`<%windir%>\Assembly` directory, 1578
 Window and control adornments, WPF, 1180
 Window class
 overview, 1130
 System.Windows.Controls.ContentControl, 1131–1132
 System.Windows.Controls.Control, 1132
 System.Windows.DependencyObject, 1135
 System.Windows.FrameworkElement, 1133
 System.Windows.Media.Visual, 1134–1135
 System.Windows.Threading.Dispatcher Object, 1135
 System.Windows.UIElement, 1134
 Window construction, 1138
 Window designer, WPF, 1170
 window, dirty, 1549
 Window menu, 1303
 Window objects, 1130, 1135, 1137, 1138, 1155, 1173
 Window type, 1121, 1130, 1135, 1137, 1146, 1173, 1175, 1177, 1196, 1204
`<Window>` element, 1155, 1156, 1158, 1159, 1160, 1173, 1175, 1185, 1205, 1232
 WindowCollection type, 1129
`<Window.CommandBindings>` scope, 1205
 Window-derived class, 1137, 1146
 Window-derived object, 1138
 WindowHeight property, System.Console class, 82
 WindowLeft property, System.Console class, 82
`<Window.Resources>` scope, 1294
 windows
 closing, 1141–1142
 mapping data to C# code, 1150–1151
 naturally dirty, 1551
 strongly typed, 1137–1138
 Windows Activation Service (WAS), 1026
 Windows Application Programming Interface (API), 260, 285, 286, 729
 Windows Communication Foundation (WCF)

addresses, bindings, and contracts
 (ABCs)
 addresses, 1031–1032
 bindings, 1028–1031
 contracts, 1027

building client applications
 configuring TCP-based binding, 1049–1050
 generating proxy code using svccutil.exe, 1046–1047
 generating proxy code using Visual Studio 2010, 1047–1048

building services
 [OperationContract] attributes, 1035
 [ServiceContract] attributes, 1034
 overview, 1032
 service types as operational contracts, 1035–1036

composition of applications, 1025–1027

core assemblies of, 1022

data in one process, 625

designing data contracts
 examining Web.config files, 1075
 implementing service contracts, 1073–1074
 overview, 1070
 role of *.svc files, 1074
 testing services, 1075–1076
 using Web-Centric service project templates, 1071–1073

distributed computing APIs
 .NET remoting, 1016
 COM+/Enterprise Services, 1015
 Distributed Component Object Model (DCOM), 1014–1015
 Microsoft Message Queuing (MSMQ), 1015–1016
 named pipes, sockets, and P2P, 1019
 overview, 1013
 XML web services, 1016–1019

features, 1020

hosting services
 <system.serviceModel> element, 1042

coding against ServiceHost type, 1038
 enabling metadata exchange, 1043–1045
 establishing ABCs within App.config files, 1037
 ServiceHost type, 1040–1041
 specifying base addresses, 1038–1040

hosting services within Windows services
 creating Windows service installer, 1064–1065
 enabling MEX, 1064
 installing Windows service, 1066–1067
 overview, 1061
 specifying ABCs in code, 1062–1063

invoking services asynchronously from clients, 1067–1069

overview, 1013

service-oriented architecture (SOA)
 tenets, 1021–1022

simplifying configuration settings with WCF 4.0
 changing settings for bindings, 1053–1054
 default endpoints in, 1051–1052
 default MEX behavior configuration, 1054–1055
 exposing single services using multiple bindings, 1052–1053
 overview, 1050
 refreshing client proxy and selecting bindings, 1056–1057

using Service Library project templates
 altering configuration files using SvcConfigEditor.exe, 1059–1061
 building simple math services, 1057–1058
 testing with WcfTestClient.exe, 1058–1059

Visual Studio project templates, 1023–1025

Windows control, 1292

- Windows Explorer, viewing .NET 4.0 GAC using, 566
- Windows file header, 534–535
- Windows Forms applications
 - completing, 937
 - executing under Linux, 1580
 - extendable, 621–624
- Windows Forms Client program, building, 1578–1580
- Windows Forms database designer tools
 - `app.config` files, 932
 - completing Windows Forms applications, 937
 - `DataGridView` control, 927–932
 - strongly typed data adapters, 936–937
 - strongly typed `DataRow`s, 935
 - strongly typed `DataSet`s, 932–934
 - strongly typed `DataTable`s, 934
- Windows Forms Graphics object, 1279
- Windows Forms GUI toolkit, 903, 904, 906, 907, 913, 918, 920, 921, 927, 931
- Windows Forms GUIs
 - binding `DataTable` objects to `DataGridView` type, 912–913
 - deleting rows from `DataTable`s, 907–908
 - hydrating `DataTable`s from generic `List<T>`, 904–906
 - selecting rows based on filter criteria, 908–911
 - updating rows within `DataTable`s, 911
 - data binding entities to, 986–989
- Windows Forms message box, 540
- Windows Forms, programming with
 - building applications
 - overview, 1513
 - populating controls collection, 1515–1517
 - `System.EventArgs` and `System.EventHandler`, 1517–1518
 - building complete applications
 - adding infrastructure to `MainWindow` type, 1555
- capturing and rendering graphical output, 1557
- implementing serialization logic, 1558–1560
- implementing Tools menu functionality, 1555–1556
- main menu system, 1552–1553
- overview, 1551
- `ShapeData` type, 1553
- `ShapePickerDialog` type, 1553–1555
- designing dialog boxes
 - configuring tab order, 1540
 - `DialogResult` property, 1539
 - displaying dialog boxes, 1542–1543
 - overview, 1538
 - setting form's default input button, 1541
 - Tab Order Wizard, 1540–1541
 - understanding form inheritance, 1543–1545
- Form type
 - `Control` class, 1526–1529
 - `Form` class, 1529–1530
 - life cycle, 1531–1533
 - overview, 1525
- mouse and keyboard activity
 - determining which button was clicked, 1535–1536
 - determining which key was pressed, 1536–1537
 - overview, 1534
- namespaces, 1512–1513
- overview, 1511
- rendering graphical data using GDI+
 - `Graphics` type, 1548–1549
 - invalidating form's client area, 1551
 - obtaining `Graphics` object with `Paint` event, 1549–1550
 - overview, 1545–1546
 - `System.Drawing` namespace, 1547
- Visual Studio Windows Forms project template
 - initial Form, 1520–1521
 - overview, 1518
 - `Program` class, 1521–1522

- visual designer surface, 1519–1520
- visually building menu systems, 1522–1524
- Windows Forms properties, 1392
- Windows header information, 534
- Windows help file, 269
- Windows Management Instrumentation (WMI), 1043
- Windows menu, 1363
- Windows network identity, 1507
- Windows Open dialog box, 621
- Windows Presentation Foundation (WPF), 1285–1324, 1325–1375
 - animation
 - Animation class types, 1304–1305
 - authoring in C# code, 1306–1307
 - authoring in XAML, 1309–1312
 - looping, 1308–1309
 - overview, 1303
 - pacing of, controlling, 1307–1308
 - To property, 1305
 - By property, 1305
 - From property, 1305
 - reversing, 1308–1309
 - Timeline Base class, 1305
 - control templates
 - building custom with Visual Studio 2010, 1348–1355
 - default, 1341–1348
 - default, programmatically inspecting, 1344–1348
 - dependency properties
 - building custom, 1331–1336
 - CLR property wrappers, 1330
 - examining existing, 1327–1330
 - overview, 1325
 - Jackpot Deluxe WPF application
 - .NET 4.0 visual states, 1366–1370
 - extracting UserControl from drawing geometry, 1365–1366
 - finalizing, 1371–1375
 - overview, 1364
 - logical trees
 - overview, 1341
 - programmatically inspecting, 1342–1343
- resource system
 - binary resources, 1285–1291
 - object (logical) resources, 1292–1303
- routed events
 - overview, 1337
 - routed bubbling events, 1338–1339
 - routed tunneling events, 1339–1341
- styles
 - animated, 1318
 - assigning programmatically, 1319–1320
 - automatically applying with TargetType, 1314–1315
 - defining and applying, 1313–1314
 - defining with multiple triggers, 1317
 - defining with triggers, 1317
 - generating with Expression Blend, 1320–1324
 - overriding settings, 1314
 - overview, 1312
 - subclassing existing, 1315
 - unnamed, 1316
- UserControls, building custom with Blend
 - animation, defining, 1359–1362
 - initial C# code, 1359
 - overview, 1356
 - programmatically starting storyboard, 1363–1364
 - renaming initial, 1357–1358
 - SpinControl, 1358
- visual trees
 - overview, 1341–1342
 - programmatically inspecting, 1343–1344
- Windows Presentation Foundation (WPF)
 - applications
 - assemblies
 - Application class, 1128–1130
 - overview, 1126–1127
 - Window class, 1130–1135
 - building using code-behind files

- MainWindow class, adding code file for, 1165
- MyApp class, adding code file for, 1166
- processing files with msbuild.exe, 1166–1167
- building using only XAML
 - application object, defining, 1147
 - MainWindow class, defining, 1146–1147
 - overview, 1144–1145
 - processing files with msbuild.exe, 1148–1150
- building using Visual Studio 2010
 - Button Click event, implementing, 1175–1176
 - Closed event, implementing, 1177
 - designer tools, 1169–1172
 - GUI, designing, 1173–1174
 - Loaded event, implementing, 1174
 - overview, 1167
 - project templates, 1168
 - testing, 1177–1178
- building without XAML
 - application level data, interacting with, 1139–1140
 - closing window, 1141–1142
 - keyboard events, intercepting, 1143–1144
 - mouse events, intercepting, 1142–1143
 - overview, 1135–1136
 - strongly typed window, 1137–1138
 - user interface, 1138–1139
- flavors of
 - desktop applications, 1121–1123
 - navigation-based applications, 1124
 - WPF/Silverlight relationship, 1126
 - XBAP applications, 1124–1125
- motivation behind
 - optimized rendering model, 1120
 - overview, 1117
 - separation of concerns, 1119
 - simplifying UI programming, 1120–1121
- unifying APIs, 1118–1119
- syntax of
 - attached properties, 1162
 - class and member variable declarations, controlling, 1159
 - kaxaml, 1154–1156
 - kaxamlXAML XML namespaces and XAML, 1156–1159
 - markup extensions, 1163–1165
 - property-element syntax, 1161
 - XAML elements, XAML attributes and type converters, 1160–1161
- transforming markup into .NET assembly
 - BAML, 1151–1152
 - mapping application data to C# code, 1153
 - mapping window data to C# code, 1150–1151
 - overview, 1150
 - XAML-to-assembly process, 1153–1154
- Windows Presentation Foundation (WPF)
 - controls
 - commands
 - connecting to arbitrary actions, 1203–1204
 - connecting to Command property, 1202–1203
 - intrinsic control command objects, 1201
 - Open command, 1204–1206
 - overview, 1200
 - Save command, 1204–1206
 - core, 1179–1181
 - data-binding model
 - Data Binding tab, 1236
 - DataContext property, 1239
 - DataGrid tab, 1242–1244
 - establishing data bindings, 1236–1238, 1241–1242
 - IValueConverter interface, data conversion using, 1240–1241
 - overview, 1235
 - dialog boxes, 1183

- document controls, 1183
- Documents API
 - block elements, 1227
 - document layout managers, 1228
 - inline elements, 1227
- Documents tab, building
 - annotations, enabling, 1232–1234
 - loading FlowDocument, 1234–1235
 - overview, 1228
 - populating FlowDocument, 1230–1232
 - saving FlowDocument, 1234–1235
 - sticky notes, enabling, 1232–1234
- Expression Blend, building user interface with
 - key aspects of, 1207–1213
 - TabControl control, 1213–1215
- Ink API tab, building
 - ComboBox control, 1224–1226
 - InkCanvas control, 1222–1227
 - overview, 1216
 - RadioButton control, 1220–1222
 - ToolBar, 1217–1219
- ink controls, 1182–1183
 - overview, 1179
- panels
 - enabling scrolling for, 1194–1195
 - nested, building window frame using, 1195–1200
 - overview, 1184–1185
 - positioning content within, 1186–1194
- using Visual Studio 2010, 1181–1182
- Windows Presentation Foundation (WPF)
 - graphics rendering services
 - applying graphical transformations, 1262–1266
- brushes
 - configuring in code, 1260–1261
 - configuring using Visual Studio 2010, 1258–1260
- generating complex vector graphics
 - using expression design, 1275–1276
- options, 1246–1247
- overview, 1245
- pens, 1261–1262
- rendering graphical data using
 - drawings and geometries
 - building DrawingBrush using geometries, 1272–1273
 - containing drawing types in DrawingImage, 1274–1275
 - overview, 1271
 - painting with DrawingBrush, 1273–1274
- rendering graphical data using visual layer
 - DrawingVisual class, 1278–1279
 - rendering to custom layout manager, 1280–1282
 - responding to hit test operations, 1282–1284
 - visual base class and derived child classes, 1277
- shapes
 - adding rectangles, ellipses, and lines to canvas, 1249–1252
 - overview, 1247–1248
 - paths, 1254–1257
 - polylines and polygons, 1253–1254
 - removing rectangles, ellipses, and lines from canvas, 1252–1253
 - working with using Expression Blend, 1266–1271
- Windows property, 1129, 1130
- Windows services
 - creating installer, 1064–1065
 - hosting services within
 - creating Windows service installer, 1064–1065
 - enabling MEX, 1064
 - installing Windows service, 1066–1067
 - overview, 1061
 - specifying ABCs in code, 1062–1063
 - installing, 1066–1067
 - Windows Start button, 1572
 - Windows Task Manager utility, 625
 - Windows thread scheduler, 728

Windows Workflow Foundation 4.0 (WF)
 activities
 collection, 1092–1093
 control flow, 1089
 error handling, 1092–1093
 flowchart, 1089–1090
 messaging, 1090–1091
 overview, 1088
 primitives, 1091
 runtime, 1091
 transaction, 1091–1092
 business process, defining, 1078
 overview, 1077
 runtime engine
 WorkflowApplication class, hosting
 workflows using, 1086–1088
 WorkflowInvoker class, hosting
 workflows using, 1083–1086
 workflows
 consuming libraries, 1112–1114
 flowchart, 1093–1103
 isolating into dedicated libraries,
 1103–1111
 simple, 1079–1083
 WindowsBase.dll assembly, 1127, 1135,
 1157, 1168
 WindowsFormsDataBinding application,
 904
 WindowsFormsDataBinding project, 904,
 913
 <Windows.Resources> scope, 1297
 WindowsStartupLocation attribute, 1146
 WindowState property, 1530
 WindowTop property, System.Console
 class, 82
 window-wide resources, defining, 1292–
 1294
 WindowWidth property, System.Console
 class, 82
 WinFormsClientApp.cs, 1578
 WinFormsClientApp.rsp, 1579
 Winnebago class, 611
 WithCancellation() method, 771
 WithCancellation()method, 773
 Wizard control, 1439, 1441, 1455

wizards, 4
 Workflow Activity Library project, 1083
 Workflow Console Application project,
 1083
 workflow designer, defining arguments
 using, 1084–1086
 Workflow Foundation (WF), 1024
 Workflow node, 1103
 Workflow Service Application project
 template, WCF, 1083
 Workflow1.xaml file, 1081, 1084
 WorkflowApplication class, hosting
 workflows using, 1086–1088
 workflow-enabled applications, 30
 WorkflowInvoker class, hosting workflows
 using
 defining arguments using workflow
 designer, 1084–1086
 overview, 1083
 passing arguments to workflow, 1084
 WorkflowInvoker.Invoke() method, 1084,
 1113
 WorkflowLibraryClient project, 1112, 1114
 WorkflowRuntime class, 1086
 workflows
 consuming libraries, 1112–1114
 flowchart
 activities, connecting in, 1094
 FlowDecision activity, 1096–1098
 ForEachT activity, 1099–1100
 InvokeMethod activity, 1094–1095
 overview, 1093
 TerminateWorkflow activity, 1097
 variables, workflow wide, 1095–1096
 hosting using WorkflowApplication
 class, 1086–1088
 hosting using WorkflowInvoker class
 defining arguments using workflow
 designer, 1084–1086
 overview, 1083
 passing arguments to workflows,
 1084
 isolating into dedicated libraries
 arguments, defining, 1105–1106
 assemblies, importing, 1105

Assign activity, 1107
 Code activity, 1109–1111
 defining project, 1103–1104
 If activity, 1107–1108
 namespaces, importing, 1105
 Switch activity, 1107–1108
 variables, defining, 1106–1107
 simple, 1079–1083
WorkflowServiceHost class, 1088
WorkWithArrayList() method, 367
 World Wide Web (WWW) environment, 1473
 World Wide Web Consortium (W3C), 995, 1019
WPF. *See Windows Presentation Foundation*
 WPF Fundamentals node, 1336
 WPF triggers, 1366
 WPF User Control Library project, 1300
WpfAppAllCode namespace, 1137
WpfAppAllCode project, 1135, 1144
WpfAppAllXaml application, 1167
WpfAppAllXaml project, 1154
WpfAppCodeFiles folder, 1165
WpfAppCodeFiles project, 1167
WpfControlsAndAPIs application, 1207
WpfControlsAndAPIs project, 1244
WPFRoutedEventArgs project, 1337, 1341
WpfStyles application, 1313
WpfStyles project, 1320
 WrapPanel panel control, WPF, 1186
 WrapPanel panels, 1188, 1190
Write() method, 82, 793, 795, 800, 1421, 1422
WriteAllBytes() method, 791
WriteAllLines() method, 791
WriteAllText() method, 791
WriteByte() member, 793
WriteFile() method, 1421
WriteLine activity, 1080, 1081, 1084, 1085, 1093, 1094, 1097, 1098, 1099, 1100
WriteLine() member, 795
WriteLine() method, 75, 82, 83, 181, 704
WriteXml() method, 889, 901
WriteXmlSchema() method, 901
 writing, to text files, 795–796
WS-* (web service specifications), 1020
WS-* specifications, 1019
WS-Addressing (Web Services Addressing), 1029
WS-Basic (Web Services Basic), 1029
WSDL (Web Service Definition Language), 1019, 1021, 1034, 1044, 1055, 1072, 1073
 wsdl link, 1055
 wsdl utility, Mono, 1571
 wsdl.exe file, 1018
 wsdl.exe utility, Microsoft .NET, 1571
WSDualHttpBinding class, 1029, 1030, 1031
WSDualHttpBinding option, 1029
<wsDualHttpBinding> element, 1029
WSE (Web Services Enhancements), 1019
WS-Federation (Web Services Federation), 1029
WSFederationHttpBinding class, 1029, 1031
WSFederationHttpBinding option, 1029
WSFederationHttpBinding protocol, 1030
<wsFederationHttpBinding> element, 1029
WSHttpBinding class, 1029, 1063, 1070
WSHttpBinding option, 1029
WSHttpBinding protocol, 1029, 1058
<wsHttpBinding> element, 1029
WS-I (Web Services Interoperability Organization), 1019, 1029
WS-Reliability (Web Services Reliability), 1028
WS-SecureConversation (Web Services SecureConversation), 1030
WS-Security (Web Services Security), 1028, 1030
WS-Transactions (Web Services Transactions), 1028
WS-Trust (Web Services Trust), 1030
 WWW (World Wide Web) environment, 1473
 WYSIWYG (fixeddocuments), 1120

X

x: Array keyword, 1163
 x: ClassModifier keyword, 1158
 X icon, 1142
 x: Key keyword, 1158
 x: Name keyword, 1158
 x; prefix, 1157
 X property, 211, 378, 1535
 X string format character, 84
 x: tag prefix, 1146
 X value, 212
 X1 property, 1250
 X2 property, 1250
XAML
 .NET 4.0 visual states, 1369–1370
 authoring animation in
 discrete key frames, 1311–1312
 event triggers, 1310–1311
 overview, 1309
 storyboards, 1310
 exporting design document to, 1275–
 1276
 for simple workflows, 1081–1083
 transforming markup into .NET
 assembly, 1153–1154
WPF applications, building using
 application object, defining, 1147
 MainWindow class, defining, 1146–
 1147
 overview, 1144–1145
 processing files with msbuild.exe,
 1148–1150
WPF applications, building without
 application level data, interacting
 with, 1139–1140
 closing window, 1141–1142
 keyboard events, intercepting, 1143–
 1144
 mouse events, intercepting, 1142–
 1143
 overview, 1135–1136
 strongly typed window, 1137–1138
 user interface, 1138–1139
WPF, syntax of

attached properties, 1162
 class and member variable
 declarations, controlling, 1159
 kaxaml tool, 1154–1156
 markup extensions, 1163–1165
 overview, 1154
 property-element syntax, 1161
 type converters, 1160–1161
 XAML, 1156–1159
 XAML attributes, 1160–1161
 XAML elements, 1160–1161
 XAML XML namespaces, 1156–1159
**XAML (Extensible Application Markup
 Language)**, 993
**XAML (x:Name Extensible Application
 Markup Language) token**, 1146
XAML attribute, 1160
XAML browser application (XBAP), 1124
**XAML browser applications (XBAP
 applications)**, 1124–1125
XAML dialect, 1079
XAML editor, 1239, 1309, 1321, 1357
.xaml file, 1298
*.xaml files, 1082, 1103, 1145, 1146, 1147,
 1149, 1150, 1151, 1152, 1153
XAML files, external, 1082
XAML markup, 1152
XAML pane, 1155
XAML scope, 1316
XAML scrubber option, 1154
XAML string, 1347
XAML tab, 1369
XamlAnimations folder, 1309
XamlAnimations subdirectory, 1312
*.xaml.cs, 1165
XamlReader class, 1235
XamlReader type, 1173
XamlReader.Load() method, 1175
XamlSpecificStuff, 1157, 1158
XamlWriter class, 1235
XamlWriter type, 1173
x:Array keyword, 1158
x:Array markup extension, 1164
XAttribute class, 995, 998
XBAP (XAML browser application), 1124

- XBAP applications (XAML browser applications), 1124–1125
- XButton1 property, 1143
- XButton1 value, 1536
- XButton2 property, 1143
- XButton2 value, 1536
- XCData class, 998
- x:Class attribute, 1104, 1150, 1156, 1159, 1357
- x:Class keyword, 1158
- x:Class value, 1104
- x:ClassModifier attribute, 1159
- x:Code attribute, 1159
- x:Code keyword, 1158
- <x:Code> element, 1147
- XComment class, 998
- XContainer class, 1000, 1001
- x-coordinate, 1535
- Xcopy deployment, 553
- XDeclaration class, 998, 1003
- XDocument class, 998, 1000, 1002, 1003, 1006, 1008, 1011
- XDocument objects
 - generating documents from arrays and containers, 1004–1005
 - loading and parsing XML content, 1006
 - overview, 1002
- XDocuments class, 1004
- XElement class, 995, 996, 999, 1000, 1003, 1004, 1006, 1011
- XElement objects
 - generating documents from arrays and containers, 1004–1005
 - loading and parsing XML content, 1006
 - overview, 1002
- XElements class, 1004, 1005
- x:FieldModifier attribute, 1159
- XHTML (Extensible Hypertext Markup Language), 1383, 1392
- x:Key attribute, 1293, 1315
- x:Key value, 1293, 1316
- XML (Extensible Markup Language), 995, 996, 997, 998, 999, 1000, 1001, 1002, 1003, 1004
- XML (Extensible Markup Language) schema editor, 902
- XML APIs
 - vs. DOM models, 995–996
 - overview, 993–994
 - Visual Basic (VB) literal syntax, 996–997
- XML content, loading and parsing, 1006
- XML data, 815–816
- XML documents
 - building UI of LINQ to XML App, 1007
 - defining LINQ to XML Helper class, 1008–1009
 - importing Inventory.xml files, 1007–1008
 - overview, 1006
 - rigging up UI to Helper class, 1009–1011
- XML Editor option, 968
- XML markup, 1119
- XML namespace (xmlns) attribute, 1383
- XML namespaces, XAML, 1156–1159
- XML Paper Specification (XPS), 1120, 1183, 1227
- XML, serializing DataTable/DataSet objects as, 901–902
- XML web services, 1016–1019
- [XmlAttribute] attribute, 815
- XML-based grammar, 1088
- XmlDocument class, 995
- XmlElement class, 995
- [XmlElement] attribute, 815
- [XmlAttribute] attribute, 815
- xmlns (XML namespace) attribute, 1383
- [XmlNsDefinition] attribute, 1157
- XmlReader class, 993
- [XmlRoot] attribute, 815
- XmlSerializer type, serializing objects using, 814–816
- [XmlText] attribute, 815
- [XmlType] attribute, 815
- XmlWriter class, 993
- x:Name attribute, 1150, 1156, 1159, 1275, 1276, 1293, 1357
- XName class, 1001–1002

x:Name Extensible Application Markup Language (XAML) token, 1146
x:Name keyword, 1158
XName object, 1001
x:Name property, 1181
XNamespace class, 999, 1001–1002
XNode class, 999, 1000
x:Null keyword, 1158, 1163
xor opcode, 678
XPath (Extensible Markup Language Path Language), 993
XProcessingInstruction class, 999
XPS (XML Paper Specification), 1120, 1183, 1227
XQuery (Extensible Markup Language Query), 993
XSD (Extensible Markup Language Schema Definition) editor, 902
*.xsd file, 901, 902
xsd utility, Mono, 1571
xsd.exe utility, Microsoft .NET, 1571
XSLT (Extensible Stylesheet Language Family Transformations), 993
XSP server, 1566
xsp2 utility, Mono, 1571
x:Static keyword, 1158, 1163
x:Static markup extension, 1163
XStreamingElement class, 999

x>Type keyword, 1158, 1163
x>Type markup extension, 1164
x>TypeArguments keyword, 1158

■ Y

Y property, 211, 378, 1535
Y value, 212
Y1 property, 1250
Y2 property, 1250
y-coordinate, 1535
YesOrNo variable, 1095, 1097
yield keyword, building iterator methods with, 346
yield return statement, 346
yield return syntax, 346, 349
YourCars.dll assembly, 532
YourXaml.xaml file, 1174, 1175, 1176
Yugo value, 515
yugosOnlyView variable, 912

■ Z

zero second mark, 1360
zero-code, 1452
zooming, 49

